

**ADDENDUM TO THE TENDER
ESKOM HOLDINGS SOC LTD
INVITATION TO TENDER (ITT)
FOR**

Metsimaholo and North dam pumping system at Matimba Power Station for 06 months

Tender number	E2856GXLPMAT
Issue date	30 April 2026
Closing date and time	22 May 2026 at 10h00
Extended closing date and time	08 June 2026 @10:00am
Tender validity period	90 days from the closing date and time

Amended Price list

Table 1: Cost breakdown of the Metsimaholo Pumping System:

Item	UoM	QTY	Unit Price	Total
Self-Priming Centrifugal Pump	ea	3		
Floating Platform (POTON)	ea	3		
45Kw/2P/380V/IP55 Electric Motor or similar	ea	3		
Electrical Accessories	ea	1		
Supply,Install,earth and terminate Cabling	m	80		
Cable trenching/routing and sleeving	sum	1		
Electrical Control Panel for 2xDuty Pump and 1 Standby Pump including all ancillaries	ea	1		
DN250 Flanged HDPE Pipes including all ancillaries, flanges, bends etc	m	960		
DN250 Isolating Valves	ea	10		
DN250 Isolating Gate Valves	ea	25		
25mm Dragline Hose Pipe, 30m LG, Interval of 12m including clamps	m	500		
VYRSA 36 Sprinkler with 4.4mm Nozzle	m	500		

1.2m High Galvanized Sprinkler Stand	ea	184		
Saddle with 50mm outlet (Interval of 12m)	ea	500		
25mm stainless steel ball valve with handle	ea	500		
M20×165 bolts, Nuts and washers	sum	1		
Installation of pumps, floating platforms and all ancillaries	Sum	1		
Installation of electrical motors, panels and all electrical reticulation	Sum	1		
Installation of HDPE piping and all associated valves Mestimaholo Dam	Sum	1		
Installation of sprinkler system (Sprinklers, sprinkler stand, Dragline hose and all ancillaries)	Sum	1		
Sub-total				


Table 2: Cost breakdown of the North Dam Pumping System:

Item	UoM	QTY	Unit Price	Total
Floating Pump	m	1		
HDPE Pipe DN150	ea	24		
Controller	ea	1		
Electrical Panel	ea	1		
Auto Shut Valve	ea	1		
Isolation Valves	ea	2		
Cable routing, Cabling and all terminations	m	226		
Bush Clear	lot	1		
Installation of pumps including all ancillaries, piping and associated works for north dam.	sum	1		
Sub- Total				

Project Preliminaries and generals				
Item	UoM	QTY	Unit Price	Total
Project Management	Sum	1		
Designs	Sum	1		
Project Engineering & Commissioning	Sum	1		
SHEQ Officer	Sum	1		
Transportation and Crane Hire	Sum	1		
Consumables and Hired Equipment	Sum	1		
Food & Accommodation	Months	6		
Staff Transportation	Sum	6		
PPE	Sum	1		
Medicals and clearance	Sum	1		
Safety File	Sum	1		
Site Establishment	Once-off	1		
Site De Establishment	Once-off	1		
Sub- Total				
ESTIMATED PROJECT VALE				

Use the above template and submit Activity Schedule in the same format as shown above. The Activity Schedule need to address all design cost, manufacturing cost, installation cost, housekeeping cost and/or any cost that bares reference to this contract as per the works information and is the sole responsibility of the Contractor. This will be used as final cost estimation, and no values will be altered after placement of contract

Yours faithfully



Dumisani Makamu

Procurement Manager (Acting)

Date: 2026/05/27