### **Bridge & Marine**

### **Discipline's involvement**









### **Discipline's involvement**

- Piling and Pile Caps
- Superstructure
  - Precast Elements
  - Insitu Deck





### **Design criteria**

### Design ship characteristics

•	Deadweight tonnage (DWT)	50 000
•	Displacement (t)	66 000
•	Length overall (m)	250
•	Beam (m)	32
•	Draft (m)	13

### Alternative ships

Two bunker barges each 75m in length





### **Design criteria and assumptions**

- Vessel Loading
  - Mooring

Bow, stern and breasting, 3 per end at 20m centres,  $\pm$  10m behind cope

Six spring line moorings at 20m centres along cope

Berthing

Eight fenders at 20m intervals along cope over  $\pm$  140m

Set forward of the cope to prevent pile damage





### **Design criteria and assumptions**


- Live Loading
  - Vehicular loads 10kPa over entire area
  - Crane outrigger load of 80t on 1m x 1m area
- Geometric requirements
  - Link to existing Berth 209
  - Link to possible future chemical berths
  - Have minimum effect on shoreline





### Possible structures considered

- Gravity Structures
  - Dolphin structure with caissons
  - Anchored sheetpile wall
  - Block or counterfort wall structure
- Piled Structure
  - Due to poor soil conditions the only viable solution







### **Piling load transfer considerations**


- End bearing piles bedrock too deep at 70 80m
- Friction piles mostly sand, friction not very high
- Combination of the above most suitable


#### Piles used

- Tubular steel driven piles with sacrificial casings
- Full load to be carried by reinforced concrete inside casing
- 73 dia. 700 and 5 dia. 800 piles
- Some piles raking to carry lateral loads
- Installation by vibration followed by top driving

#### **TRANSNET**

















#### **TRANSNET**




### **Bridge & Marine**

### **Deck Structure**

- Precast Elements
  - Beams
  - Slab panels
  - Fender panels
- Insitu reinforced concrete
  - Pile caps
  - Beam connections
  - Deck
  - Upstand walls
  - Foam monitor towers


















# **\***















































### **Problems encountered and solutions**


- Contractor's Problems
  - Pile testing
  - Cracks in precast slab units
  - Placing of precast beams during construction
  - Access to place beams after last pile in position
  - Swells caused by passing vessels especially tugs
  - Cracks in walkway slab
- Design Problems
  - Cracks in some cantilever portions of the main deck
  - Cracks in upstand walls





### **Pile testing**


- CAPWAP (Case Pile Wave Analysis Program) method of analysis
  - Safety Factor for working Load
  - Estimated settlement at 1 and 1.5 times design load
- Results
  - FOS of 1.82 compared to 2.00
  - Predicted settlements within prescribed 15 and 18mm respectively
  - 58% of load carried in end bearing






































#### **Lessons learnt**

- Do not specify beam weight on construction drawings
- Ensure that prestressing sleeves can fit between the reinforcing
- Have sufficient construction joints in smaller elements i.e. bund walls
- Get Contractor to cast adjoining concrete elements at the same time

