

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



CLUSTER 2 (STELLENBOSCH AND VAN DER STEL STATION) BILL OF QUANTITIES (BOQ)

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



REFURBISHMENT FOR STELLENBOSCH STATION (BUILDINGS, ELECTRICAL AND PLATFORM RESURFACING)					
ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>PART A- BUILDINGS (TICKET OFFICE, TICKET VERIFICATION ,STAFF MESS ROOMS ,SHELTERS AND PUBLIC ABULUTIONS)</u>				
	<u>BILL NO.1</u>				
	-				
	<u>PRELIMINARIES AND GENERAL COSTS</u>				
	-				
1.1	The Contractor shall allow for all Preliminary Items as set out below in the tender price	Item	1.00		
	-				
	<u>BUILDING AGREEMENT AND PRELIMINARIES</u>				
	-				
	The JBCC Principal Building Agreement (Minor works agreement Edition 5.2 - May 2018) prepared by the Joint Building Contracts Committee shall be the applicable building agreement, amended as hereinafter described				
	-				
	<u>The JBCC Principal Building Agreement contract data form an integral part of this agreement</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	The JBCC General Preliminaries (May 2018) published by the Joint Building Contracts Committee for use with the JBCC Minor Works Agreement (Edition 5.2 – May 2018) shall be deemed to be incorporated in this project specific preliminaries, amended as hereinafter described				
	The contractor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause				
	<u>PREAMBLES FOR TRADES</u>				
	-				
	The General Preambles for Trades 2017 published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in this Project Specific Preliminaries				
	Supplementary preambles and/or specifications are incorporated in this Project Specific Preliminaries to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles				
	-				
	The contractors' prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model preambles and any supplementary preambles				
	BILL OF QUANTITIES				
	Please note that the Bill of Quantities is measured in accordance with the standard system of measuring building works				
	-				
	SECTION A: MINOR WORKS AGREEMENT				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	All standard clauses of the minor works agreement are applicable with the exception of the following				
	Clause 1.0 - Definitions and interpretation				
	Contract sum				
	The contract sum to include, unless otherwise stated, for all materials, fabrication, conveyance and delivery, unloading, storing, unpacking, hoisting, labour, setting, fitting and fixing in position, cutting and waste (except where to be measured in accordance with the standard system of measurement), patterns, models and templates, plant, temporary works, returning of packaging, duties, taxes (other than Value Added Tax), imposts, establishment charges, overheads, profit and all other obligations arising out of this agreement. Value Added Tax (VAT) is to be separately stated in the contract data				
	The contract sum shall include for all construction equipment, temporary works, services and other items and shall include for the supply, maintenance, operating cost and subsequent removal and making good as necessary				
	Value Added Tax				
	Provision is made in the contract data for inclusion in the contract sum of Value Added Tax (VAT)				
	GENERAL NOTES				
	Contractor is required to visit the site and inspect items before bidding for the tender.				
	View site : Stellenbosch Station				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Before submitting, the Contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings.				
	WORK AND MATERIALS				
	Old material to become property of the contractor				
	Old materials from alterations, except where described to be re-used or handed over, become the property of the contractor who must allow credit for same in the Final Summary				
	All rubble and debris from the pulling down are to be				
	carted away without delay and the site is to be left clean				
	and tidy.				
	-				
	<u>OCCUPATIONAL HEALTH AND SAFETY</u>				
	-				
1.2	Presentation, agreement and implementation of the health and safety plan including notifications to local health and safety authorities, open health and safety file inclusive of Act 85 of 1993 Occupational Health and Safety, Act 16 of 2002 Railway Safety Act and Covid 19 requirements as per the Department of labour.				
	Designated health and safety personnel, committee, etc as required and Health and Safety file				
	<u>Carried to summary</u>				R -
	<u>BILL NO. 2</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>ALTERATIONS, DEMOLITIONS, ETC</u>				
	REMOVAL OF EXISTING WORK				
	<u>Taking down and removing, ceilings, partitions, etc.</u>				
2.1	Gypsum plasterboard ceilings including cornices, timber brandering, etc	m ²	38.00	R	-
	<u>Hacking up/off and removing tile floor and including removing mortar bed or backing and preparing concrete surfaces for new screed, tile finisher</u>				
2.2	Floor Tiles	m ²	24.00	R	-
2.3	Wall Tiles	m ²	40.00	R	-
	<u>Take out and removing doors, etc. including thresholds, sills, etc. and building up openings in brick walls including making good cement plaster on both sides (making good paintwork).</u>				
2.4	Timber single door exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	17.00	R	-
	<u>Take up and remove floor covering carpeting.</u>				
2.5	Carpet tile floor covering including preparing screed for floor covering	m ²	24.00	R	-
	<u>Take out and removing piping, sanitary fittings, etc, including cutting off as necessary, disconnecting</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>pipng from fittings and making good floor and wall finishes.</u>				
2.6	WC pan with cistern	No	10.00	R	-
2.7	Wash hand basin	No	6.00	R	-
	<u>Taking out and removing doors, windows, etc. from brickwork to be demolished</u>				
2.8	Glazed aluminium window frame and glazing not exceeding 2,5m ²	No	22.00	R	-
	<u>Taking out and removing joinery fittings etc</u>				
2.9	Timber floor cupboard 1500 x 600 x 900mm high	No	1.00	R	-
	<u>Taking out/off and removing sundry metalwork</u>				
2.10	Steel double leaf security gate exceeding 2,5m ² and not exceeding 5,0m ²	No	1.00	R	-
	<u>Plaster exposed water pipe</u>				
2.11	Plaster exposed High density polyethylene water pipes in the wall including making good plaster to receive new wall paint	m ²	15.00	R	-
	<u>Earth filling supplied by the contractor compacted to 95% Mod AASHTO density.</u>				
2.12	Backfill to holes and including compaction testing	m ³	10.00	R	-

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>BUILDING UP OPENINGS</u>				
	<u>Breaking out for and forming plain openings through brick walls including necessary precast concrete lintels and making good plaster on side and face brick on the other and into reveals and with concrete thresholds with steel trowelled finish (making good paintwork elsewhere</u>				
2.13	Double brick walls	m ²	13.00		R -
	<u>Carried to summary</u>				R -
	<u>BILL NO. 3</u>				
	-				
	<u>CARPENTRY AND JOINERY</u>				
	-				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	-				
	<u>Joinery</u>				
	-				
	Descriptions of frames shall be deemed to include frames, transomes, mullions, rails, etc				
	Descriptions of hardwood joinery shall be deemed to include pelleting of bolt holes				
	-				
	<u>Fixing</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete				
	-				
	<u>Wrought Meranti doors hung to timber frames</u>				
3.1	40mm Single leaf Door 900 x 2100mm. high with rebated meeting styles	No	16.00		R -
3.2	40mm Double leaf door 1600 x 3000mm high, with rebated meeting styles	No	1.00		R -
	<u>General</u>				
	-				
	The following cupboard fittings have been measured as complete units i.e., the components of the units have not been separately measured. The descriptions, therefore, of such units shall be deemed to include all components, assembling, housing, notching, glueing, blocking, planting on and screwing with countersunk screws, edge strips, decorative plastic finish, glass, ironmongery, metalwork, paint or varnish finishes, etc				
	-				
	<u>Carried to Summary</u>				R -
	-				
	<u>BILL NO. 4</u>				
	-				
	<u>IRONMONGERY</u>				
	<u>LOCKS, HANDLES, INDICATORS ETC</u>				
4.1	2 lever lock set SABS approved	No	16.00		R -
4.2	3 lever lock set SABS approved	No	1.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



4.3	Mortice lock Indicator	No	7.00	R	-
	<u>HINGES, BOLTS, ETC</u>				
	"Halstead" or similar approved:				
4.4	100x70mm Brass butt hinges with concealed washers	No	34.00	R	-
	<u>DOOR SIGNAGE</u>				
	-				
	<u>Door mounted signs fixed to brickwork or concrete, as per Prasa Blueprint Specification.</u>				
4.5	300 x 300 Male Sign	No	2.00	R	-
4.6	300 x 300 Female Sign	No	2.00	R	-
4.7	300 x 300 Paraplegic Toilet sign	No	1.00	R	-
	<u>Carried to Summary</u>			R	-
	<u>BILL NO. 5</u>				
	-				
	<u>METALWORK</u>				
	-				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	-				
	Descriptions of bolts, anchors, etc				
	-				
	Descriptions of bolts shall be deemed to include nuts and washers				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete				
	<u>GALVNISED STEEL SCREEN AND GATES</u>				
	<u>Burglar gates</u>				
5.1	Service and install new Grade 304 Stainless steel security deadlock with deadcase plated fixed in a frame with master key and push and pull handles	No	1.00		R -
5.2	Welded security gate for opening 900 x 1800mm high overall, 25mm square hollow tubing hinge to a frame surround fixed to brickwork including Grade 304 Stainless steel security deadlock with deadcase plated fixed in a frame with master key and push and pull handles	No	1.00		R -
	<u>Canteen</u>				
	<u>Tubular metal table and metal Seating</u>				
5.3	6-Seater canteen table 1800 x 1307 x 770mm high fixed to floor	No	2.00		R -
	<u>GALVANISED STEEL MESH STONEGUARD</u>				
	Security wire mesh screens to frames as per PRASA CRES specification				
5.4	Welded security grille screen for opening 600 x 600mm high overall, with 25 x 25 x 3mm thick metal surround frame	No	1.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>Steel Bins</u>				
5.5	Steel litter bin size 400mm Ø x 750mm high / 72-litre capacity with steel ashtray, galvanised with a polyurethane pain	No	3.00		R -
	<u>Carried to Summary</u>				R -
	<u>BILL NO. 6</u>				
	-				
	<u>TILING</u>				
	-				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	-				
	<u>Descriptions:</u>				
	-				
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding.				
	-				
	Ceramic, porcelain, marble and granite tiles are to be fixed and grouted with suitable adhesives and grouts from the "Tal Professional" or similar approved range of products as recommended by the manufacturer of the tiles				
	<u>Preparatory work to existing painted plastered surfaces</u>				
	Preparation of all existing painted plastered surfaces is to include for removing all loose and flaking material by wire brushing, thoroughly washing down and allowing to dry completely and applying one coat masonry bonding agent				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>PORCELAIN TILES</u>				
	600 x 600 x 25mm Porcelain tiles, fixed with adhesive to screed and flush pointing with and including tinted grout:				
	-				
6.1	On floors-	m ²	45.00	R	-
6.2	On skirting -	m	28.00	R	-
	<u>SUNDRIES</u>				
	<u>M-Trim Aluminium</u>				
6.3	ESA100.80 Straight edge trim	m	15.00	R	-
6.4	EQS 100.84 Square stainless steel corner edge trim	m	23.00	R	-
	<u>Carried to Summary</u>			R	-
	<u>BILL NO. 7</u>				
	-				
	<u>CEILINGS AND PARTITIONING</u>				
	-				
	6.4mm "Rhino" gypsum plasterboard with 32mm wrought softwood				
	<u>Ceilings</u>				
7.1	Ceilings including 38 x 50mm sawn softwood brander at 400mm centres	m ²	30.00	R	-

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>Rhino gypsum plasterboard cornices</u>				
7.2	75mm Coved cornices	m	22.00	R	-
	<u>Carried to Summary</u>			R	-
	<u>BILL NO. 8</u>				
	-				
	<u>PAINTWORK</u>				
	<u>PAINTWORK, ETC PREVIOUSLY PAINTED WORK</u>				
	<u>ON EXTERNAL FLOATED PLASTER SURFACES</u>				
	-				
	<u>PREPARATORY WORK TO EXISTING WORK</u>				
	-				
	Note: All surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed, and cracks shall be opened, filled with suitable filler and finished smooth				
	-				
	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats plascon wall and/ or similar and equally approved all as per PRASA colour specification</u>				
8.1	External wall	m ²	1096.00	R	-
	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats Plascon Low sheen wall and/ or similar and equally approved all as per PRASA colour specification</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



8.2	Internal walls-	m ²	368.00	R	-
	ON PLASTERBOARD SURFACES				
	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats Plascon Low sheen wall and/ or similar and equally approved all as per PRASA colour specification</u>				
8.3	Ceilings, cornice and Partitions-	m ²	333.00	R	-
	ON WOOD SURFACES				
	<u>Prepare surfaces and paint one coat 'Dulux 'Supergrip primer and one coat 'Dulux' Trade universal undercoat and two coats Dulux trade Pearl glo and/ or similar and equally approved all as per PRASA colour specification</u>				
8.4	On doors-	m ²	45.00	R	-
8.5	On Timber Door frames, etc-	m ²	28.00	R	-
	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats Plascon Low sheen wall and/ or similar and equally approved all as per PRASA colour specification</u>				
	-				
8.6	Bargeboards-	m	405.00	R	-
	<u>Prepare surfaces and paint one coat 'Dulux ' primer for wood and one coat 'Dulux' Trade universal undercoat and two coats Dulux Trade Gloss enamel and/ or similar and equally approved all as per PRASA colour specification</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



8.7	Open slatted timber seating-	m	50.00		R	-
	<u>Prepare surfaces and paint one coat of ultra woodcare varnish and/ or similar and equally approved all as per PRASA colour specification</u>					
8.8	Heritage window, doors, frames etc.	m ²	30.00		R	-
	<u>Carried to Summary</u>				R	-
	-					
	-					
	<u>BILL NO.9</u>					
	<u>GLAZING</u>					
	<u>Glazing to steel with putty</u>					
	<u>Carefully take out remove glass and clean steel window frames to receive new glass</u>					
9.1	Clear float glass 4mm thick small panes exceeding 0.5m2 but not 1m2	m ²	10.00		R	-
	<u>Carried to Summary</u>				R	-
	<u>BILL NO.10</u>					
	-					
	<u>PLUMBING AND DRAINAGE</u>					
	<u>Stainless steel</u>					
	-					

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



10.1	Sink and drainer 900 x 530mm wide with one bowl	No	1.00		R	-
	<u>Heavy Duty Urinal</u>					
	-					
10.2	Wall mounted urinal with back inlet with flushing mechanism	No	5.00		R	-
	<u>Taps and Flush Valves</u>					
	-					
10.3	Concealed vandal resistant push-button urinal flush valve with sleeve	No	2.00		R	-
10.4	15mm chrome plated deck mounted sink mixer with overarm swivel outlet and adjustable flanges (Code: NA-970), manufactured in accordance with SANS 226:2004 Type 1 (BS 5412).	No	1.00		R	-
10.5	Basins self-closing push button pillar Tap, cold water supply only, chrome finish, code 08212 with flow time of 15 sec or equal approved.	No	6.00		R	-
10.6	Concealed vandal resistant push-button toilet flush valve	No	6.00		R	-
	<u>High density polyethylene class 16 pipes</u>					
	-					
10.7	25mm pipes with all other required connections laid in including wall trenching and plaster and make good	m	110.00		R	-
10.8	Testing water supply system	Item	1.00		R	-
	<u>WC,S</u>					

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



10.9	Whyte House vandal resistant WC pan and duct cistern (code 7109DP), complete with lid, fitments and duct flush pipe. Push button mechanism elsewhere specified. Should be used with any back inlet pan	No	10.00		R -
	<u>Sanitary Fittings & Accessories</u>				
10.10	Automatic Soap/ Sanitiser Dispenser fixed to the walls	No	8.00		R -
	<u>Carried to Summary</u>				R -
	<u>PART B-TAR PLATFORM RE-SURFACING, FENCING & ELECTRICAL KIOSK BUILDING</u>				
	<u>BILL NO. 11</u>				
	<u>EXTERNAL WORKS</u>				
	Excavation				
11.1	Remove existing Platform Tar and Excavation to reduce levels under platform areas	m ³	10.00		R -
	Earth filling supplied by the contractor under roads, parking areas, paving				
11.2	Sub-base layer G5 type material stabilized with 3% cement to obtain a C4 material compacted to 95% Modified AASHTO density	m ³	10.00		R -
	Compaction of surfaces				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



11.3	Compaction of ground surface under roads and parking areas including, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m ²	10.00		R -
	Tests				
11.4	Modified AASHTO Density" test to 93%	No	6.00		R -
	ASPHALT				
	Tar Surfacing (Platform)				
11.5	Tar road Platform resurfacing and making good	m ²	10.00		R -
	Road marking paint on Tar surfacing with non - reflective paint complete as per existing road marking signs layout				
11.6	100mm wide solid yellow line	m	400.00		R -
	ELECTRICAL KIOSK				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



11.7	Manufacture, Build and install a new electrical kiosk with clay brick walls, steel reinforced concrete flat top. Dimensions to be used in construction of kiosk: • Concrete slab width 145mm x length 2300mm x breadth 1500mm. • Brick part length 2000mm x breadth 1200mm. • Steel doors 5mm thick. • 740mm width x 1530mm length. • Structure height 1800mm. Doors to be manufactured of 5mm thick mild steel plate with heavy duty hinges and a locking mechanism. Doors to have a 5mm thick mild steel box to cover lock and handle. Doors and frames to be galvanized. Brick structure to be painted with 3 layers of etch primer and two layers of Prasa blue.	Item	1.00		R	-
	FENCING					
	<u>Palisade fence</u>					
	Should consist of three horizontal cross members or rails which can be punched with a profiled slot which allows the vertical pales to be slid through the cross member. They can be bolted or welded to the horizontal cross members					
	The standard opening between palisades (pales) should be 100mm, with the standard distance between palisade (pales) canters					
	No claim for excavation, Backfilling and compacting will be entertained, Shall deemed to be included on the tendered rates.					
	<u>NEW FENCING</u>					
	-					

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>"Hot Dipped galvanised Palisade Fence" or similar and approved fencing:</u>				
	-				
	Galvanised vandal proof Palisade Fencing 2100mm high comprising of 76x76x2mm square hollow section posts x 2700mm set 600mm deep in 300x300 concrete bases at 3000mm centres, with 40x40mm top and bottom beam frame bolted to post, 25x25mm vertical members spaced at 100mm centres with Tiger spikes welded to top beam.				
	-				
11.8	2100mm Galvanised steel fencing including posts complete, installed as per manufacturer's instructions	m	150.00		R -
	-				
	<u>Carried to Summary</u>				R -
	<u>Part - C Electrical supply and Electrical equipment to platforms, Building and shelters etc.</u>				
	<u>BILL NO.12</u>				
	-				
	<u>ELECTRICAL WORK</u>				
	-				
	<u>OCCUPATIONAL HEALTH AND SAFETY</u>				
	-				
	The contractor shall comply with all the requirements set out in the Construction Regulations, issued under The Occupational Health & Safety Act no 85 of 1993.				
	<u>All rubble shall be taken away from site on a daily basis.</u>				
	<u>Schedule of Quantities</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Unless otherwise stated the description of each item shall be deemed to include manufacturing, conveying, and delivering, unloading, storing, unpacking, hoisting, setting, fitting and fixing in position, cutting, waste, patterns, plant, temporary works, establishment charges, profit and other obligations arising out of the conditions of contract				
	Supply, install test commission and hand over in good working conditions complete the electrical system as per BOQ, specifications, IEE wiring regulations. All the material to be supplied to bear SABS mark or SABS mark of compliance.				
	-				
12.1	10mm ² SWA cable	m	50.00		R -
12.2	Trenching and Backfilling	m	100.00		R -
12.3	16mm ² SWA cable	m	60.00		R -
12.4	Supply and install 13W 2D LED Round Bulkhead light fittings for shelters. Bolt light fittings onto brick wall. Chasing into wall to hide cables.	Item	20.00		R -
12.5	Inside anti-vandal cages for shelters - Following these dimensions – Length= 340, Width= 340 and height= 220 and they must be deep galvanized.	Item	20.00		R -
12.6	LED Flood lights for station building outside	Item	3.00		R -
12.7	Re-wire shop on platform	Item	1.00		R -
12.8	Platform Light fittings LED 4000Lm minimum	Item	7.00		R -
12.9	Contactor	Item	2.00		R -
12.10	Photocell	Item	2.00		R -
12.11	Twin & Earth 2,5mm ²	m	100.00		R -
12.12	Hydroboil 10l	Item	1.00		R -
12.13	Pole Circuit breaker inspection covers	Item	3.00		R -
12.14	5 foot LED tubes	Item	60.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	HVAC Systems				
12.15	Supply, install and commission new 24000 BTU split unit, inverter technology air conditioner completely with all accessories (drain pipe, amorflex, copper pipe, refrigerant, cable, communication wire, brackets, circuit breaker, isolator, etc)	No	2.00		R -
	Carried to Total				R -
	<u>BILL NO.13</u>				
	<u>SIGNAGES</u>				
	<u>Digitally printed Prohibition Signs</u>				
13.1	800mm x 300mm ea Digitally printed Prohibition Signs Digitally Printed Graphics (Refer to Code sign LL of Prasa Signages Blue print)	No	2.00		
	<u>End of Platform Sign - New Pole Required</u>				
13.2	300mm x 300mm 800mm x 300mm End of Platform Sign - on existing with Digitally Printed Graphics Mounted to New Pole at the End of the Platform (Refer to Code sign NN of Prasa Signages Blue print)	No	4.00		
	<u>Carried to Total-</u>				
	SUB TOTAL				R -
	10 % Contingency				R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	SUB TOTAL				R	-
	15% VAT				R	-
	TOTAL				R	-

REFURBISHMENT FOR VAN DEL STEL (BUILDINGS, ELECTRICAL AND PLATFORM RESURFACING)					
	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>PART A- BUILDINGS (TICKET OFFICE, TICKET VERIFICATION, STAFF MESS ROOMS, SHELTERS AND PUBLIC ABULUTIONS)</u>				
	<u>BILL NO.1</u>				
	-				
	<u>PRELIMINARIES AND GENERAL COSTS</u>				
	-				
1.1	The Contractor shall allow for all Preliminary Items as set out below in the tender price	Item	1.00		R -
	-				
	<u>BUILDING AGREEMENT AND PRELIMINARIES</u>				
	-				
	The JBCC Principal Building Agreement (Minor works agreement Edition 5.2 - May 2018) prepared by the Joint Building Contracts Committee shall be the applicable building agreement, amended as hereinafter described				
	-				
	<u>The JBCC Principal Building Agreement contract data form an integral part of this agreement</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	The JBCC General Preliminaries (May 2018) published by the Joint Building Contracts Committee for use with the JBCC Minor Works Agreement (Edition 5.2 – May 2018) shall be deemed to be incorporated in this project specific preliminaries, amended as hereinafter described				
	The contractor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause				
	<u>PREAMBLES FOR TRADES</u>				
	-				
	The General Preambles for Trades 2017 published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in this Project Specific Preliminaries				
	Supplementary preambles and/or specifications are incorporated in this Project Specific Preliminaries to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles				
	-				
	The contractors' prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model preambles and any supplementary preambles				
	<u>BILL OF QUANTITIES</u>				
	Please note that the Bill of Quantities is measured in accordance with the standard system of measuring building works				
	-				
	<u>SECTION A : MINOR WORKS AGREEMENT</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	All standard clauses of the minor works agreement are applicable with the exception of the following				
	Clause 1.0 - Definitions and interpretation				
	Contract sum				
	The contract sum to include, unless otherwise stated, for all materials, fabrication, conveyance and delivery, unloading, storing, unpacking, hoisting, labour, setting, fitting and fixing in position, cutting and waste (except where to be measured in accordance with the standard system of measurement), patterns, models and templates, plant, temporary works, returning of packaging, duties, taxes (other than Value Added Tax), imposts, establishment charges, overheads, profit and all other obligations arising out of this agreement. Value Added Tax (VAT) is to be separately stated in the contract data				
	The contract sum shall include for all construction equipment, temporary works, services and other items and shall include for the supply, maintenance, operating cost and subsequent removal and making good as necessary				
	Value Added Tax				
	Provision is made in the contract data for inclusion in the contract sum of Value Added Tax (VAT)				
	GENERAL NOTES				
	Contractor is required to visit the site and inspect items before bidding for the tender.				
	View site : Van Der Stel				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Before submitting, the Contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings.				
	<u>WORK AND MATERIALS</u>				
	Old material to become property of the contractor				
	Old materials from alterations, except where described to be re-used or handed over, become the property of the contractor who must allow credit for same in the Final Summary				
	All rubble and debris from the pulling down are to be				
	carted away without delay and the site is to be left clean				
	and tidy.				
	-				
	<u>OCCUPATIONAL HEALTH AND SAFETY</u>				
	-				
1.2	Presentation, agreement and implementation of the health and safety plan including notifications to local health and safety authorities, open health and safety file inclusive of Act 85 of 1993 Occupational Health and Safety, Act 16 of 2002 Railway Safety Act and Covid 19 requirements as per the Department of labour.				
	Designated health and safety personnel, committee, etc as required and Health and Safety file				
	<u>Carried to summary</u>				R -
	<u>BILL NO. 2</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>ALTERATIONS, DEMOLITIONS, ETC</u>				
	REMOVAL OF EXISTING WORK				
	<u>Taking down and removing, ceilings, partitions, etc.</u>				
2.1	Gypsum plasterboard ceilings including cornices, timber brandering, etc	m ²	40.00		R -
	<u>Breaking out for and forming plain openings through brick walls including necessary precast concrete lintels and making good plaster on side and face brick on the other and into reveals and with concrete thresholds with steel trowelled finish (making good paintwork elsewhere</u>				
2.2	Opening 2000 x 2300mm high through half brick wall and make good	No	1.00		R -
	<u>Take out and removing doors, etc. including thresholds, sills, etc. and building up openings in brick walls including making good cement plaster on both sides (making good paintwork).</u>				
2.3	Timber double door exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	1.00		R -
	<u>Take out and removing piping, sanitary fittings, etc, including cutting off as necessary, disconnecting piping from fittings and making good floor and wall finishes.</u>				
2.4	WC pan with cistern	No	1.00		R -
2.5	Urinal	No	1.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



2.6	Wash hand basin	No	1.00		R -
	<u>Taking out and removing doors, windows, etc. from brickwork to be demolished</u>				
2.7	Glazed aluminium window frame and glazing not exceeding 2,5m ²	No	4.00		R -
	<u>Taking out/off and removing sundry metalwork</u>				
2.8	Steel double leaf security gate exceeding 2,5m ² and not exceeding 5,0m ²	No	1.00		R -
	<u>Taking out and removing joinery fittings etc</u>				
2.9	Timber sink cupboard 2000x600x900mm high including disconnecting waste pipe (new trap and connecting to new waste pipe elsewhere)	No	1.00		R -
	<u>Carried to summary</u>				R -
	<u>BILL NO. 3</u>				
	-				
	<u>CARPENTRY AND JOINERY</u>				
	-				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	-				
	<u>Joinery</u>				
	-				
	Descriptions of frames shall be deemed to include frames, transomes, mullions, rails, etc				
	Descriptions of hardwood joinery shall be deemed to include pelleting of bolt holes				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	-				
	<u>Fixing</u>				
	-				
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete				
	-				
	<u>Wrought Meranti doors hung to timber frames</u>				
3.1	40mm Single leaf Door 900 x 2100mm. high with rebated meeting styles	No	2.00		R -
3.2	40mm Double leaf door 1500 x 2100mm high, with rebated meeting styles	No	1.00		R -
	<u>Solid flush door on both sides hung to steel frames</u>				
3.3	40mm Door 810mm x 1900mm. high	No	11.00		R -
	<u>General</u>				
	-				
	The following cupboard fittings have been measured as complete units i.e. the components of the units have not been separately measured. The descriptions, therefore, of such units shall be deemed to include all components, assembling, housing, notching, glueing, blocking, planting on and screwing with countersunk screws, edge strips, decorative plastic finish, glass, ironmongery, metalwork, paint or varnish finishes, etc				
	<u>Kitchen cupboards etc with approved hinges, handles</u>				
3.4	Sink cupboard size 2000 x 600 x 900mm high with sides, bottom, divisions, shelf, back and 3 single hinged doors, with a Granite Top cut size to fit stainless steel sink (sink & Taps elsewhere)	No	1.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	-				
	<u>Carried to Summary</u>			R	-
	-				
	<u>BILL NO. 4</u>				
	-				
	<u>IRONMONGERY</u>				
	<u>LOCKS, HANDLES, INDICATORS ETC</u>				
4.1	2 lever lock set SABS approved	No	4.00	R	-
4.2	3 lever lock set SABS approved	No	6.00	R	-
4.3	Mortice lock Indicator	No	3.00	R	-
	<u>HINGES, BOLTS, ETC</u>				
	"Halstead" or similar approved:				
4.4	100x70mm Brass butt hinges with concealed washers	No	24.00	R	-
	<u>DOOR SIGNAGE</u>				
	-				
	<u>Door mounted signs fixed to brickwork or concrete</u>				
4.5	300 x 300 Male Sign	No	2.00	R	-
4.6	300 x 300 Female Sign	No	2.00	R	-
	<u>Carried to Summary</u>			R	-
	<u>BILL NO. 5</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>METALWORK</u>				
	-				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	-				
	Descriptions of bolts, anchors, etc				
	-				
	Descriptions of bolts shall be deemed to include nuts and washers				
	-				
	Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete				
	<u>GALVNISED STEEL SCREEN AND GATES</u>				
	<u>Burglar gates</u>				
5.1	Welded security gate for opening 1800 x 2200mm high overall, 25mm square hollow tubing hinge to a frame surround fixed to brickwork including Grade 304 Stainless steel security deadlock with deadcase plated fixed in a frame with master key and push and pull handles or equal approved.	No	3.00		R -
5.2	Welded security gate for opening 900 x 1800mm high overall, 25mm square hollow tubing hinge to a frame surround fixed to brickwork including Grade 304 Stainless steel security deadlock with deadcase plated fixed in a frame with master key and push and pull handles or equal approved.	No	1.00		R -
	<u>KROST Metal Shelving</u>				
	-				
5.3	914 x 381 1875mm High pre-painted and bolted metal shelving consisting of six shelves all three units bolted together fixed to the wall.	No	1.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>Steel locker</u>				
5.4	2 Tier two Door 1800 x300x450mm steel locker fixed to wall	No	2.00		R -
	<u>GALVANISED STEEL MESH STONEGUARD</u>				
	<u>Security wire mesh screens to frames as per PRASA CRES specification</u>				
5.5	Welded security grille screen for opening 600 x 600mm high overall, with 25 x 25 x 3mm thick metal surround frame	No	3.00		R -
	<u>PRESSED STEEL DOOR FRAMES</u>				
	<u>1,2mm. Rebated frame suitable one brick wall</u>				
5.6	Frame for door size 900 x 2032mm. high	No	1.00		R -
	<u>Steel Benches</u>				
5.7	4m Single Seat with straight leg wit Galvanised and polyurethane painted platform bench, set into concrete bed or similar approved.	No	3.00		R -
	<u>Steel Bins</u>				
5.8	Steel litter bin size 400mm Ø x 750mm high / 72-litre capacity with steel ash tray, galvanised with a polyurethane pain	No	2.00		R -
	<u>Carried to Summary</u>				R -
	<u>BILL NO. 6</u>				
	-				
	<u>CEILINGS AND PARTITIONING</u>				
	-				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	6.4mm "Rhino" gypsum plasterboard with 32mm wrought softwood				
	<u>Ceilings</u>				
6.1	Ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m ²	40.00		R -
	<u>Rhino gypsum plasterboard cornices</u>				
6.2	75mm Coved cornices	m	3.00		R -
	<u>Carried to Summary</u>				R -
	<u>BILL NO. 7</u>				
	-				
	<u>PAINTWORK</u>				
	<u>PAINTWORK, ETC PREVIOUSLY PAINTED WORK</u>				
	<u>ON EXTERNAL FLOATED PLASTER SURFACES</u>				
	-				
	<u>PREPARATORY WORK TO EXISTING WORK</u>				
	-				
	Note: All surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed, and cracks shall be opened, filled with suitable filler and finished smooth				
	-				
	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats plascon wall and/ or similar and equally approved all as per PRASA colour specification</u>				
7.1	External wall	m ²	75.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats Plascon Low sheen wall and/ or similar and equally approved all as per PRASA colour specification</u>				
7.2	Internal walls-	m ²	83.00	R	-
	ON PLASTERBOARD SURFACES				
	<u>Prepare surfaces and paint one coat plascon professional plaster primer and finish with two coats Plascon Low sheen wall and/ or similar and equally approved all as per PRASA colour specification</u>				
7.3	Ceilings, cornice and Partitions-	m ²	40.00	R	-
	ON WOOD SURFACES				
	<u>Prepare surfaces and paint one coat 'Dulux 'Supergrip primer and one coat 'Dulux' Trade universal undercoat and two coats Dulux trade Pearl glo and/ or similar and equally approved all as per PRASA colour specification</u>				
7.4	On doors-	m ²	30.00	R	-
7.5	On Door frames, etc-	m ²	4.00	R	-
	<u>Prepare surfaces and paint one coat 'Dulux ' primer for wood and one coat 'Dulux' Trade universal undercoat and two coats Dulux Trade Gloss enamel and/ or similar and equally approved all as per PRASA colour specification</u>				
	-				
7.6	Open slatted timber seating-	m	12.00	R	-
	Carried to Summary			R	-

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>BILL NO.8</u>				
	<u>GLAZING</u>				
	<u>Glazing to steel with putty</u>				
	<u>Carefully take out remove glass and clean steel window frames to receive new glass</u>				
8.1	Clear float glass 4mm thick small panes exceeding 0.5m2 but not 1m2	m ²	2.00		R -
	<u>4mm Silvered float glass copper backed mirrors with polished edges fixed with chromium plate dome headed mirror screws</u>				
8.2	Mirror size 300 x 450mm high	No	1.00		R -
8.3	Mirror size 450 x 600mm high	No	1.00		R -
	<u>Carried to Summary</u>				R -
	<u>BILL NO.9</u>				
	-				
	<u>PLUMBING AND DRAINAGE</u>				
	<u>Stainless steel</u>				
	-				
9.1	Sink and drainer 900 x 530mm wide with one bow	No	1.00		R -
	-				
	<u>Taps and Flush Valves</u>				
	-				
9.2	Concealed vandal resistant push-button urinal flush valve with sleeve or equal approved	No	1.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



9.3	15mm chrome plated deck mounted sink mixer with overarm swivel outlet and adjustable flanges (Code: NA-970), manufactured in accordance with SANS 226:2004 Type 1 (BS 5412) or equal approved.	No	1.00		R -
9.4	Basins self-closing push button pillar Tap, cold water supply only, chrome finish, code 08212 with flow time of 15 sec or equal approved.	No	2.00		R -
9.5	Concealed vandal resistant push-button toilet flush valve or equal approved	No	4.00		R -
	<u>WC,S</u>				
9.6	Whyte House vandal resistant WC pan and duct cistern (code 7109DP), complete with lid, fitments and duct flush pipe. Push button mechanism elsewhere specified. Should be used with any back inlet pan or equal approved	No	3.00		R -
9.7	Vandal resistant basin	No	1.00		R -
	<u>PVC gutters and rainwater pipes</u>				
	<u>Rainwater Disposal</u>				
9.8	80mm UPvc Downpipes fixed to brickwork	m	25.00		R -
9.9	Extra over for swan-neck	No	4.00		R -
9.10	Extra Over outlet	No	4.00		R -
9.11	Extra over for stopped ends	No	4.00		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	<u>Aluminium gutters</u>				
	-				
	<u>Standard Aluminium Chromadek or equally approved gutters finish to both sides fixed with brackets at suitable centres to fascia's</u>				
	-				
9.12	125 x 85mm gutters with beaded front edge fixed fascia board or equal approved	m	55.00		R -
	<u>Carried to Summary</u>				R -
	<u>PART B-TAR PLATFORM RE-SURFACING, FENCING</u>				
	<u>BILL NO. 10</u>				
	<u>EXTERNAL WORKS</u>				
	<u>ASPHALT</u>				
	<u>Tar Surfacing (Platform)</u>				
10.1	Tar road Platform patching and making good	m ²	5.00		R -
	<u>Road marking paint on Tar surfacing with non - reflective paint complete as per existing road marking signs layout</u>				
10.2	100mm wide solid yellow line	m	320.00		R -
	<u>External Anti-Bandit Door</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



10.3	Level G3 bullet resistant Anti-bandit door, complete with 100 x 50 x 3mm gauge MS frame and 25 x 25 x 3mm MS anlg rebates, overall size 930 x 2095mm high in "American Walnut" Formica cladding finish with peep hole, supplied with 5-lever CISA mortise dead lock with an additional heavy duty magnetic lock and striker including key switch and surface mounted casing, 6 Amp power supply, push buttons and interlock system, heavy duty aluminium continuous hinge, aluminium slam bar with heavy duty door closer (Dorma TS91) and D-style pull handles	No	1.00		R	-
	<u>FENCING</u>					
	<u>Palisade fence</u>					
	Should consist of three horizontal cross members or rails which can be punched with a profiled slot which allows the vertical pales to be slid through the cross member. They can be bolted or welded to the horizontal cross members					
	The standard opening between palisades (pales) should be 100mm, with the standard distance between palisade (pales) canters					
	No claim for excavation, Backfilling and compacting will be entertained ,Shall deemed to be included on the tendered rates.					
	<u>NEW FENCING</u>					
	-					
	<u>"Hot Dipped galvanised Palisade Fence" or similar and approved fencing:</u>					
	-					

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Galvanised vandal proof Palisade Fencing 2100mm high comprising of 76x76x2mm square hollow section posts x 2700mm set 600mm deep in 300x300 concrete bases at 3000mm centres, with 40x40mm top and bottom beam frame bolted to post, 25x25mm vertical members spaced at 100mm centres with Tiger spikes welded to top beam.				
	-				
10.4	2100mm Galvanised steel fencing including posts complete, installed as per manufacturer's instructions	m	150.00		R -
	<u>Carried to Summary</u>				R -
	Part - C Electrical supply and Electrical equipment to platforms, Building and shelters etc.				
	<u>BILL NO.11</u>				
	-				
	<u>ELECTRICAL WORK</u>				
	-				
	OCCUPATIONAL HEALTH AND SAFETY				
	-				
	The contractor shall comply with all the requirements set out in the Construction Regulations, issued under The Occupational Health & Safety Act no 85 of 1993.				
	All rubble shall be taken away from site on a daily basis.				
	<u>Schedule of Quantities</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



	Unless otherwise stated the description of each item shall be deemed to include manufacturing, conveying, and delivering, unloading, storing, unpacking, hoisting, setting, fitting and fixing in position, cutting, waste, patterns, plant, temporary works, establishment charges, profit and other obligations arising out of the conditions of contract				
	Supply, install test commission and hand over in good working conditions complete the electrical system as per BOQ, Specifications, IEE wiring regulations. All the material to be supplied to bear SABS mark or SABS mark of compliance.				
	-				
11.1	Supply and install 16mm ² 4 cores, SWA cable.	m	100		R -
11.2	Supply and install twin & earth 2,5mm ² cable.	m	150		R -
11.3	Supply and install 10mm ² 4 core SWA cable.	m	10		R -
11.4	Trenching for 300mm wide, trench 600mm deep.	m	100		R -
11.5	Lay concrete over cable.	m ³	2		R -
11.6	Supply and install 13W 2D LED Round Bulkhead light fittings, bolt light fittings into the brick wall and chase into the wall to hide the cable.	Ea	20		R -
11.7	Platform Light - Supply and install 150W LED Street Lights, Die cast aluminum housing, integrated LED chips and driver in module, low-Flicker and rated IP66. The light emitted to be cool white.	Ea	9		R -
11.8	Footbridge Light - Supply and install 60W LED Street Lights, Die cast aluminum housing, integrated LED chips and driver in module, low-Flicker and rated IP66. The light emitted to be cool white.	Ea	15		R -
11.9	Supply and install 3m high light poles 2mm thick wall minimum. Base plate to be welded onto pole. Base plate ~ 100mm x 100mm x 5mm thick with 4 holes 10mm diameter. Deep galvanized and secured with high tensile steel bolts and nuts to footbridge handrail. Securing bolts to be locked.	Ea	5		R -

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



11.10	Supply and install galvanized 25mm conduit to be welded onto the handrail of the footbridge.	m	150		R	-
11.11	Supply and install contactor.	Ea	2		R	-
11.12	Supply and install photocell.	Ea	2		R	-
11.13	Supply and install hydroboil 10L.	Ea	1		R	-
11.14	Supply and install 5 ft doubles tubes LED fittings, IP65 retrofit flourescent.	Ea	5		R	-
	<u>HVAC Systems</u>					
11.15	Supply, install and commission new 24000 BTU split unit, inverter technology air conditioner completely with all accessories (drain pipe, amorflex, copper pipe, refrigerant, cable, communication wire, brackets, circuit breaker, isolator, etc)	No	1.00		R	-
	Carried to Total				R	-
	<u>BILL NO.12</u>					
	<u>SIGNAGES</u>					
	<u>Wall Mounted Station Name</u>					
12.1	500mm x 3500mm Wall Mounted Station name (VAN DER STEL STATION) Illuminated Text with ACM Cladded steel structure with routed out graphics (Refer to Code sign D of prasa Signages Blue print)	No	1.00			
	<u>Double Sided Platform Station Name</u>					
12.2	2100mm x 3000mm Double sided platform station name (VAN DER STEL STATION) with ACM Cladded steel structure with vinyl graphic overlay suspended with two support 2.1m high poles (Refer to Code sign N of Prasa Signages Blue print)	No	2.00			
	<u>Double Sided Projecting Directional Sign</u>					

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



12.3	1000mm x 1500mm Double Sided Projecting Directional Sign with ACM Cladded steel structure with vinyl graphic overlay (Refer to Code sign V of Prasa Signages Blue print)	No	1.00		
	<u>Wall Mounted Information Sign</u>				
12.4	500mm x 500mm Wall Mounted Information Sign with ACM Cladded steel structure with vinyl graphic overlay (Refer to Code sign DD of Prasa Signages Blue print)	No	5.00		
	<u>Side Mounted Double Sided Informational Sign</u>				
12.5	500mm x 500mm Side Mounted Double Sided Informational Sign with ACM Cladded steel structure with vinyl graphic overlay (Refer to Code sign EE of Prasa Signages Blue print)	No	2.00		
	<u>Ticket Sales Decals - ABS and Vinyl</u>				
12.6	100mm x 530mm Ticket Sales Decals - ABS and Vinyl with Digitally printed Graphics with ABS backing (Refer to Code sign KK of Prasa Signages Blue print)	No	2.00		
	<u>Pole Mounted Double Sided Platform Number</u>				
12.7	500mm x 500mm Pole Mounted Double Sided Platform Number (1) with ACM Cladded steel structure with vinyl graphic overlay (Refer to Code sign HH of Prasa Signages Blue print)	No	1.00		
	<u>Digitally printed Prohibition Signs</u>				
12.8	800mm x 300mm ea Digitally printed Prohibition Signs Digitally Printed Graphics (Refer to Code sign LL of Prasa Signages Blue print)	No	2.00		
	<u>End of Platform Sign - New Pole Required</u>				

BID DESCRIPTION: APPOINTMENT OF AN 3GB OR HIGHER BUILDING CONTRACTORS FOR THE REFURBISHMENT AND MINOR WORKS AT CLUSTER 1 (MULDERSVLEI, DUTOIT) AND CLUSTER 2 (STELLENBOSCH, AND VAN DER STEL) STATIONS FOR A PERIOD OF 6 MONTHS FROM THE DATE OF SITE HANDOVER IN THE WESTERN CAPE REGION



12.9	300mm x 300mm 800mm x 300mm End of Platform Sign - New Pole Required with Digitally Printed Graphics Mounted to New Pole at the End of the Platform (Refer to Code sign NN of Prasa Signages Blue print)	No	2.00		
	<u>Carried to Total-</u>				
	SUB TOTAL				R -
	10% Contingency				R -
	SUB TOTAL				R -
	15% VAT				R -
	TOTAL				R -

NB: STATIONS WILL BE EVALUATED AND AWARDED PER CLUSTER, PLAESSE TICK THE CLUSTER YOU TENDERED FOR IN THE TABLE BELOW

STATIONS/ CLUSTERS	Tick	CIDB GRADING
Cluster 1: Muldersvlei and Du Toit		3GB OR HIGHER
Cluster 2: Stellenbosch and Van Del Stel		3GB OR HIGHER