

**ESKOM GENERATION****2024****SUPPLY, OPERATE AND  
MAINTAIN MOBILE COAL  
SCREENS FOR A PERIOD OF 36  
MONTHS AT CAMDEN POWER  
STATION: BILLS OF QUANTITIES.  
REV 01****CONTRACT NUMBER :****CONTRACTOR :****CONTRACT AMOUNT :  
(EXL. VAT)****CONTRACT AMOUNT :  
(INCL. VAT)**

# **Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station REV 01**

## **TABLE OF CONTENTS**

### **Contract Data**

NOTES TO TENDERERS

### **Bill of Quantities**

Bill No. 1      PRELIMINARIES

Bill No. 2      CONVEYOR 18 BILLS OF QUANTITIES

Bill No. 3      CONVEYOR E1 BILLS OF QUANTITIES

FINAL SUMMARY

# Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station REV 01

## NOTES TO TENDERERS

### NOTES TO TENDERERS

#### 1. BILLS OF QUANTITIES

This document comprises Notes to Tenderers and Bills of Quantities and is hereafter referred to as "the Bills of Quantities".

The Tenderers are to note that this is a Contract with a Bills of Quantities.

#### 2.1 CONTRACT DOCUMENTS

The contract documents will consist of:

2.1.1 The NEC3 Engineering and Construction Contract 2013 together with all amendments.

2.1.2 These Bills of Quantities, including all annexures and supplementary documentation referred to therein.

2.1.3 Documents to be provided by the Contractor in terms of the requirements of these Bills of Quantities.

2.1.4 Construction Regulations 2014

2.1.5 Occupational Health and Safety Act of 1993

#### 3 DRAWINGS

There are no drawings for this contract.

#### 4 VALUE ADDED TAX

Tenderers should compute their rates from the net costs (excluding Value Added Tax). Value Added Tax at the current rate of 15% is to be added to the net sub-total on the final summary page by means of a single sum calculation to establish the tender price.

#### 5 SCOPE OF WORK

As a guide only, the work comprises as follows:-

---

Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station

---

#### 6 ADDRESS WHERE DOCUMENTS CAN BE OBTAINED

Tender documents will be made available Electronically on an online portal to be provided by Eskom

#### 7 POSSESSION OF SITE

The date of which possession of the Site shall be given to the Contractor shall be within 7 **working days** of the acceptance of this tender.

#### 8 CONSTRUCTION PERIOD - DATES FOR PRACTICAL COMPLETION

The intended date for practical completion and penalty for each calendar day for non-completion shall be:

**Practical Completion: 36 Month** from the date of Site Handover

Tenderers are to note that the Contract will be delivered as a whole and NOT to be phased.

#### 9 COMMON LAW OR BY-LAW REQUIREMENTS

No liability for not specifically mentioning any normal contractual, Common Law or By-Law requirements will be accepted by the Employer, or Contracts Manager.

#### 10 AREA OF WORKS

The Tenderer shall ascertain by personal viewing of the site any restrictions to the area that may be occupied by the contractor including any restrictions imposed by any buildings, etc. and any limitations or restrictions that may be imposed by Eskom Engineers.

Access to the site shall be logically planned and enclosed to ensure minimum disruption to existing user operations.

The contractor is deemed to have allowed for all necessary temporary fencing, screening, hoardings, etc.

Space for the storage of Materials must be arranged with the Contracts Manager

The Contractor shall make all necessary provisions in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained as admitted. Tenderers will be held responsible for any misunderstanding of incorrect information, however obtained, except information which may have been given in writing over the signature of the Contracts Manager.

#### **11 MANAGEMENT OF WORKS**

The Contractor shall, to the satisfaction of the Contracts Manager, provide, in addition to the Contractor's Site Representative, the services of an experienced and competent Construction Manager.

The names and CV's of the Contractor's proposed Management Team shall be submitted to the Contracts Manager prior to commencement on site and, after the Contracts Manager's agreement on the composition and competence thereof has been obtained, no changes shall be made nor shall any member of the said team be removed from the project while remaining in the employ of the Contractor without the Contracts Manager's prior written approval.

The Contractor shall make necessary provisions in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.

#### **13 SITE CLEANLINESS**

The Contractor shall clear away all dirt, rubbish and superfluous material as they accumulate and leave the whole of the site clean and tidy on completion to the satisfaction of the Contracts Manager. The Contractor is advised that the adjacent site is functional at all times and that the incumbents should not be unduly inconvenienced.

#### **14 ORDERING OF MATERIALS**

No claims will be entertained due to non-availability of materials or labour. The Tenderer is therefore required to investigate and ensure that the specific materials and components required for the works will be available at the relevant estimated construction times, at the time of tendering.

#### **15 PROGRAMME**

The Contractor will be required to submit an outline programme of work to completion of the contract with the issue of the Form of Offer and Acceptance.

#### **16 CONTRACT PRICE ADJUSTMENT**

The Contract Sum shall be subject to CPAP.

#### **17. PRICED BILLS OF QUANTITIES:**

Tenderers must submit to the Contracts Manager a copy of the Bills of Quantities fully priced and extended, with his tender. After the Bills have been checked, and when called upon, each page of the Bills of Quantities shall be initialed and the Index page and the Final Summary page signed in full by the Tenderer.

#### **18. PAYMENT OF PRELIMINARIES:**

Tenderers are to note that the Payment of Preliminaries & Generals shall be on the NEC3 Contract [Prorated to the Value of Work Executed]

#### **19. ADJUSTMENT OF PRELIMINARIES:**

Tenderers are to note that the Adjustment of Preliminaries & Generals shall be on NEC3 Contract [Fixed - 10%, Value - 15% and Time - 75%]

#### **20 DIFFERENCE AND DISCREPANCIES:**

Should there be any difference or discrepancy between the prices or particulars contained in the official Tender Form and those contained in any covering letter from the Tenderer, the prices contained in the official Tender Form shall prevail.

Every Tenderer shall be deemed to have waived, renounced and abandoned any conditions printed or written upon any stationery used by him for the purpose of or in connection with the submission of his Tender, which are in conflict with the Conditions of Tender or Special and General Conditions of Contract.

Tenderers are warned that any material divergence from the official conditions or specifications may render their Tenders liable to disqualification.

The Tenderers are to note that if there are any arithmetical errors in the Tenderers' form of tender in calculation of the Tender Sum, the Contracts Manager will correct the calculation accordingly.

## **21 COMMUNICATION WITH MEMBERS OF THE CLIENT COMPANY OR PROFESSIONAL TEAM**

A Tenderer shall not in any way communicate with a member of the Client Company or Professional Team or with any officer on a question affecting any contract or the supply of goods or for any work, undertaking or service which is the subject of a Tender during the period between the closing date for receipt of Tenders and the dispatch of the written notification of the Employer's decision on the award of the contract; provided that a Tenderer shall not hereby be precluded from obtaining from the Employer or his authorised representative information as to the date upon which the award of the contract is likely to be made or, after the decision upon the award has been made by the Contracts Manager to which the Employer had delegated its powers, information as to the nature of the decision or such information as was publicly disclosed at the opening of Tenders.

## **22 IMPORT PERMITS:**

Tenderers must apply direct for any import permit and/or currency required, however the Contracts Manager will furnish successful Tenderers with a supporting statement if required.

## **23 BILLS OF QUANTITIES:**

No alteration, erasure, omission or addition is to be made to the text and conditions of these Bills of Quantities and should any such alteration, amendment, note or addition be made, the same will not be recognised, but the reading of the Bills of Quantities as prepared by the Contracts Manager will be adhered to.

It should be understood that the system of measurement herein adopted is the only system of measurement which will be recognised in connection with this contract. Before the signing of the contract, the Contracts Manager will be entitled to call for adjustments of individual rates and rectify discrepancies, as he considers necessary without alterations to the Tender amount.

## **24 TRAFFIC AUTHORITIES AND REGULATIONS (N/A)**

The Contractor shall comply with all requirements of the Authorities in connection with traffic control, gaining access to the site, prevention or disruption of the flow of traffic, transporting of materials and equipment to and from the site and he shall make all necessary arrangements, pay all deposits, fees and charges in connection therewith.

## **25 PROTECTION OF PERSONS AND PROPERTY**

The Contractor shall adopt all safety measures in compliance with all statutes, regulations, etc., and shall take all measures to protect all property and to secure the safety and freedom from injury of all persons.

The Contractor shall in addition take all necessary steps to prevent nuisance from dust and the like and shall use every endeavor to minimize noise emanating from the Contract Works. The Contractor is referred to the various forms that require his attention prior to commencing work on site - All forms duly completed and signed must be forwarded to the Contracts Manager.

Tenderers are to note that the building will remain occupied for the duration of the Works except for the sections of the Works under construction in terms of the requirements of the Sectional Completion.

## **26 EXISTING AND ADJOINING PROPERTIES, PAVINGS ETC.**

The Contractor shall execute the whole of the Contract Works with the minimum of disturbance to the existing and adjoining premises and occupants thereof. He shall keep the Site dust free and clean, and shall keep pavements, surrounding roads etc., free of builder's rubble and clean to the entire satisfaction of the Contracts Manager and the Authorities.

The Contractor shall leave such buildings, structures, fences, paving, roadways, Kerbs, gardens, municipal pavements, streets, etc., in the same condition at completion as they were at the commencement of the Contract. Before commencing work, the Contractor shall arrange with the owners of the existing and adjoining buildings and/or the Authorities for an inspection to be made jointly with themselves, the Contractor and the Contracts Manager in order to make written notes of any defects, etc. which may later be claimed to have been caused by the operations under this Contract. Should defects be disclosed, the Contractor shall submit same in writing to the Contracts Manager before commencing the Contract, failing which it shall be understood that no such defects existed and the Contractor shall be liable for all claims in this connection.

## **27 PROCEDURE OF WORKS**

The Contractor shall be solely responsible for ensuring that the procedure of works is kept to and no deviations will be entertained.

Should this, however not be possible then the Contractor shall timeously notify the Contracts Manager

The Contractor shall make any and all necessary allowances in his pricing for the disruption and costs that will be required to comply with any such restrictions.

## **SPECIAL CLAUSES**

### **28 TRADE NAMES, ETC.**

All materials, fittings, finishes, etc. specified under a "Trade Name", catalogue number or reference shall be either exactly as described or of equal quality, specification and weight to those described.

The Contracts Manager's written approval must be obtained for any departure from the specification before the submission of tenders, failing which specified materials, fittings, finishings, etc. shall be deemed to have been allowed for in the tenders.

Where articles other than what the manufacturer specified are used, an adjustment of the prices will be made and Variation Orders issued to cover these adjustments.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

All references in these Bills of Quantities to Specifications of the Bureau of Standards shall be deemed to be reference to the latest issues of such Specifications, and any subsequent amendments thereto. All articles, materials or items described as to conform to the SABS Specifications must bear the SABS mark.

### **29 CONTRACTOR'S RESPONSIBILITY**

The Contracts Manager and the other Professional Consultants shall not be responsible for any act or omission on the part of the Contractor, which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

### **30 SITE INSTRUCTIONS AND RECORDS**

The Contractor shall supply and have available at the site of the works at all times, the following site books:-

#### **a) Site Instruction Book**

Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Contracts Manager or other Employer's Agents to whom the Contracts Manager has delegated Authority in the book.

Only site instructions issued in such a book shall be recognised.

#### **b) Daily Record Book**

The Contractor shall record in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Contracts Manager and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Contracts Manager for his counter signature on a daily basis. Copies of these records shall be for the Contracts Manager, Employer and Contractor.

### **31 LOCATION OF TEMPORARY BUILDING AND TEMPORARY SERVICES**

The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hard standing and services, etc. required for his own and Sub-Contractor's use during the construction and maintenance period.

There is no guarantee given or implied that Site Conditions will be such that the Contractor will be able to erect such offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain permission and pay all cost in connection therewith.

By the submission of a tender, any Tenderer will, if awarded the contract to which this tender document relates, be deemed to be the mandatory as envisaged by Section 37 (2) of the Act. As a mandatory the successful Tenderer will be deemed to be the "Contractor" and an Employer in his/her/their own right with duties as prescribed in the Act and accordingly will be deemed to have agreed to be solely responsible for ensuring that in connection with the service to which this tender document relates, all work will be performed and machinery and plant used in accordance with the Act. Should the Contractor, for whatever reason be unable to perform as required by the Act, the Contractor undertakes to inform the Employer accordingly.

#### **The Contractor (mandatory) will be required to:-**

1 Provide the Employer with a Health and Safety programme and plan specifically related to the Works and ensure that the programme and plan are implemented and maintained, with the programme being subject to audit, at least once a month, by the Contracts Manager;

2 Exercise discretion and appoint a Full-time Safety Officer (in writing) to assist in the control of all safety related aspects, and to give input into the health and safety plan;

3 Appoint (in writing) a full time competent Supervisor (as defined in the Regulation in terms of the Act) to supervise the project;

4 Provide the Employer and any Sub-Contractors that may be engaged by the Contractor and/or Nominated Sub-Contractors with a programme of construction for the Works as well as a method statement with the necessary details and procedures for execution;

5 Provide the Employer both before commencing and during construction work with a copy of a risk assessment performed by a competent person who has been appointed in writing by the Contractor, and the risk assessment must form part of the health and safety plan;

6 Ensure that every employee or person (including visitors) who enters the site of the Works undergoes health and safety induction training pertaining to hazards identified on the site of the Works and upon such training having been successfully completed, the Contractor must issue written confirmation by a competent person to the trained employees or persons who shall be further instructed to carry such confirmation with them at all times whilst on the site of the Works;

7 Issue, on loan, the necessary personal protective equipment to visitors to the site of the Works; and

8 Be in good standing with the Compensation Commissioner at all times during the duration of the Contract.

9 The Contractor is to sign a Non-Disclosure Agreement prior to collecting or receiving any proprietary information from Eskom, drawings, documentation, reports and photographs

The Contractor will be deemed to have satisfied himself with his obligations in terms of the Act and to have allowed for all costs arising from compliance with the Act as no claim for extra costs arising from compliance with, and obligations in terms of the Act will be entertained.

### **32 CONTRACTORS TO VISIT SITE PRIOR TO SUBMISSION OF TENDER**

The contractors are urged to visit the site that has been identified to get an overview of the nature of works and the location of the building prior to pricing this document.

### **33 PRICING OF THESE GENERAL NOTES**

The Contractor must allow in his pricing for any additional costs arising from these "General Notes" as no later claims for additional costs will be considered.

### **34 TAX COMPLIANCE**

Failure to provide mandatory information required in this Bid will result in the submissions being deemed null and void and shall be considered non-responsive. An Electronic Tax Compliance Status (TCS) System will be used to verify the bidder's tax compliance status so bidders must request a unique security personal identification number (PIN) from SARS which must be submitted with the bid

**No alternative tender offers will be considered.**

**These Bills are not to be used for the purpose of ordering materials.**

**All Bill rates are to include for material, labour, plant, wastage, transport and profit.**

**Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station REV 01**

<b>PRELIMINARIES AND GENERAL</b>			
<b>BILL NO 1</b>	<b><u>PREAMBLE</u></b>		
	For Pricing of the Preliminaries and General Items, see the South African Bureau of Standards Standardised Specification for Civil Engineering Construction (SANS 1200AA - General (Small Works) as a guideline.		
	For Pricing of the Preliminaries and General Items, see the South African Bureau of Standards Standardised Specification for Civil Engineering Construction (SANS 1200AA - General (Small Works) as a guideline.		
	<b><u>PRICING OF THIS PRELIMINARIES</u></b>		
	Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the tenders omission to price any item will be entertained		
<b>Schedule Description</b>		<b>Unit</b>	<b>Amount</b>
	<b>ESTABLISHMENT OF FACILITIES ON SITE</b>		
<b>1</b>	<b>FIXED CHARGES</b>		
1.1	Contractual requirement ( Contractor to supply Breakdown)	sum	R
1.2	<b>Establishment of facilities on site</b>		
1.2.1	Transportation to site	sum	R
1.2.2	Offices for engineer & staff and signs	sum	R
1.2.3	Quality	sum	R
1.2.4	SAPS Vetting and /or Finger Print Check	sum	R
1.41	Other fixed-charge obligations: security.	sum	R
1.5	<b>Contractor's obligations in respect of the Occupational Health and Safety Act</b>		
1.5.1	Health and Safety Requirements	sum	R
1.3.2	PPE	sum	R
1.3.3	Medicals and Induction	sum	R
1.3.4	De- establishment	sum	R
	<b>TOTAL COST FIXED CHARGES (A)</b>		<b>R</b>
<b>2</b>	<b>TIME RELATED CHARGES</b>		
	<b>FACILITIES FOR CONTRACTOR</b>		
2.1	Operate & maintain facilities for the duration of the contract	sum	R
2.2	Offices for engineer & staff	sum	R
2.3	<b>Facilities for the Contractor for the duration of construction</b>		
2.5	Offices & storage sheds	sum	R
2.6	Workshops	sum	R
2.7	Ablution & latrine facilities	sum	R
2.8	Accommodation	sum	R
2.9	Transport	sum	R
2.1	Plant	sum	R
2.11	Other time-related obligations: security and other	sum	R
	<b>TOTAL COST TIME RELATED ITEMS (B)</b>		<b>R</b>
	<b>TOTAL COST A+B TRANSFERRED TO FINAL SUMMARY PAGE</b>		<b>R</b>

**CAMDEN POWER STATION  
BOQ SUMMARY - COAL BUNKERS STEEL STAIRCASE**

<b>Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station REV 01</b>					
Item	Description	Unit	Qty	Rate	Amount
	<p><b><u>BILL NO. 2: CONVEYOR 18</u></b></p> <p><b><u>PREAMBLES</u></b></p> <p>For Preambles refer to SANS Documents which is obtainable on request for the full descriptions of materials and work to be done in this Bill.</p> <p><b><u>SUPPLEMENTARY PREAMBLES</u></b></p> <p><b><u>Rate approvals:</u></b></p> <p>The tenderer is advised that any rate that is required for work must include the following breakdown:</p> <p>Material, labour, plant, wastage, transport and profit.</p> <p>All rates tendered on and / or pricing in these bills of quantities to be in the South African Rands Currency (ZAR)</p> <p>All individual amounts in these bills of quantities exclude Value Added Tax (VAT) VAT is to be calculated as a lump sum and added to the total of all values in the Final Summary under the item provided for VAT</p> <p><b><u>LABOUR INTENSIVE ITEMS</u></b></p> <p>The contractors must work in a labour intensive manner, . The Contractor must take this method of construction into consideration when programmes the work.</p> <p>The contractor shall comply with all requirements of the "Code of Good Practice for Employment and Conditions of Work for Special Public Works Programmes" issued in terms of the "Basic Conditions of Employment Act, 1997 (Act No. 75 of 1997)" and the related "Ministerial Determination", for the employment of locally employed temporary workers on a labour-intensive infrastructure project under the Expanded Public Works Programme (EPWP)</p> <p><b><u>PRICING OF THIS BILLS OF QUANTITIES</u></b></p> <p>Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the tenderes omission to price any item will be entertained</p> <p><b><u>TECHNICAL DOCUMENT</u></b></p> <p>The Contractor is referred to entire Technical Document 229-T2519 for the details of the Scope. The Contractor is to study the details of this document prior to pricing this Bills of Quantities</p> <p><b><u>APPOINTMENT OF TENDERER</u></b></p> <p>It is the intention of Eskom to appointment two contractors for this contract</p> <p><b><u>APPLICABLE STANDARD OF MEASUREMENT</u></b></p> <p>The applicable method of measurement is the Standard System of Measuring Building Work (seventh edition) for projects within South Africa and the Standard Method of Measuring Building Work for Africa 2015 (first edition) for projects elsewhere in Africa. The content of both of these documents are identical</p>				

**CAMDEN POWER STATION  
BOQ SUMMARY - COAL BUNKERS STEEL STAIRCASE**

<b><u>APPOINTMENT OF TENDERER</u></b>					
It is the intention of Eskom to appointment two contractors for this contract					
<b><u>SPECIAL NOTE</u></b>					
6 Diesel Mobile coal screens with a minimum capacity of 500T/h are required to feed coal to reclaim conveyors E1 and 18.					
4 screens will be utilised during normal operation (2 per conveyor), whilst 2 screens are on standby.					
Two contractors to supply 3 screens each are required to obtain the total of 6 screen, the scope of work for the 2 contractors will be the same.					
2.1	<b><u>SCREENING OF COAL WORKS</u></b>				
2.1.1	Coal Screening Machine: with mass meter,feed capacity of +800-1000 Ton/hour,feed size of 150X150 mm,feed height of 3635mm,hopper capacity of 8 cubic meters,belt conveyor feeder of 1200 x 3500 mm,triple deck vibration screen of 1520 x 6100mm,93 kw or more and diesel powered,the coal size output to be 40mm,sreens outputs to be 800-1000 tons per hour for each conveyor combined tonnages to be 1600-2000 tons per hour,the screens will be feeding one conveyor belt (Rate's be all inclusive)				
2.1.2	200 000 tons per month for 36 Months	ton	7 200 000	R	R
<b>TOTAL - TRANSFERRED TO FINAL SUMMARY</b>					R

**CAMDEN POWER STATION  
BOQ SUMMARY - COAL BUNKERS STEEL STAIRCASE**

**Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station REV 01**

Item	Description	Unit	Qty	Rate	Amount
	<p><b><u>BILL NO. 3: CONVEYOR E1</u></b></p> <p><b><u>PREAMBLES</u></b></p> <p>For Preambles refer to SANS Documents which is obtainable on request for the full descriptions of materials and work to be done in this Bill.</p> <p><b><u>SUPPLEMENTARY PREAMBLES</u></b></p> <p><b><u>Rate approvals:</u></b></p> <p>The tenderer is advised that any rate that is required for work must include the following breakdown:</p> <p>Material, labour, plant, wastage, transport and profit.</p> <p>All rates tendered on and / or pricing in these bills of quantities to be in the South African Rands Currency (ZAR)</p> <p>All individual amounts in these bills of quantities exclude Value Added Tax (VAT) VAT is to be calculated as a lump sum and added to the total of all values in the Final Summary under the item provided for VAT</p> <p><b><u>LABOUR INTENSIVE ITEMS</u></b></p> <p>The contractors must work in a labour intensive manner, . The Contractor must take this method of construction into consideration when programmes the work.</p> <p>The contractor shall comply with all requirements of the "Code of Good Practice for Employment and Conditions of Work for Special Public Works Programmes" issued in terms of the "Basic Conditions of Employment Act, 1997 (Act No. 75 of 1997)" and the related "Ministerial Determination", for the employment of locally employed temporary workers on a labour-intensive infrastructure project under the Expanded Public Works Programme (EPWP)</p> <p><b><u>PRICING OF THIS BILLS OF QUANTITIES</u></b></p> <p>Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the tenderes omission to price any item will be entertained</p> <p><b><u>TECHNICAL DOCUMENT</u></b></p> <p>The Contractor is referred to entire Technical Document 229-T2519 for the details of the Scope. The Contractor is to study the details of this document prior to pricing this Bills of Quantities</p> <p><b><u>APPLICABLE STANDARD OF MEASUREMENT</u></b></p> <p>The applicable method of measurement is the Standard System of Measuring Building Work (seventh edition) for projects within South Africa and the Standard Method of Measuring Building Work for Africa 2015 (first edition) for projects elsewhere in Africa. The content of both of these documents are identical</p> <p><b><u>APPOINTMENT OF TENDERER</u></b></p> <p>It is the intention of Eskom to appointment two contractors for this work</p>				

**CAMDEN POWER STATION  
BOQ SUMMARY - COAL BUNKERS STEEL STAIRCASE**

	<p><b><u>SPECIAL NOTE</u></b></p> <p>6 Diesel Mobile coal screens with a minimum capacity of 500T/h are required to feed coal to reclaim conveyors E1 and 18.</p> <p>4 screens will be utilised during normal operation (2 per conveyor), whilst 2 screens are on standby.</p> <p>Two contractors to supply 3 screens each are required to obtain the total of 6 screen, the scope of work for the 2 contractors will be the same.</p> <p><b><u>2.1 SCREENING OF COAL WORKS</u></b></p> <p>Coal Screening Machine: with mass meter,feed capacity of +800-1000 Ton/hour,feed size of 150X150 mm,feed height of 3635mm,hopper capacity of 8 cubic meters,belt conveyor feeder of 1200 x 3500 mm,triple deck vibration screen of 1520 x 6100mm,93 kw or more and diesel powered,the coal size output to be 40mm,sreens outputs to be 800-1000 tons per hour for each conveyor combined tonnages to be 1600-2000 tons per hour,the screens will be feeding one conveyor belt (Rate's be all inclusive)</p>				
2.1.2	200 000 tons per month for 36 Months	ton	7 200 000	R	R
<b>TOTAL - TRANSFERRED TO FINAL SUMMARY</b>					<b>R</b>

**Supply, Operate and Maintain Mobile Coal Screens at Camden Power Station REV 01****FINAL SUMMARY**

SECTION	DESCRIPTION	AMOUNT
1	PRELIMINARIES AND GENERAL	R
2	CONVEYOR 18	R
3	CONVEYOR E1	R
<b>SUB TOTAL</b>		R
<b>VAT @15%</b>		R
<b>TOTAL BID PRICE (INCL. VAT) - TRANSFERRED TO FORM OF OFFER AND ACCEPTANCE</b>		R