



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

CONTRACT NO: RLM/RWST/OMM/0102/2024/25

**RE-ADVERT: APPOINTMENT OF A CONTRACTOR FOR THE CONSTRUCTION OF THE BOSPOORT BULK
PIPELINE**

JULY 2025

**VOLUME 2: PARTICULAR SPECIFICATIONS, HEALTH AND SAFETY SPECIFICATIONS,
ENVIRONMENTAL MANAGEMENT PLAN**

NAME OF BIDDER:

Prepared by:

**RUSTENBURG WATER SERVICES TRUST
1A KOCK STREET
RUSTENBURG
0300**

BID CLOSES: 30 July 2025 at 10:00



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

CONTENTS LIST

RLM/RWST/OMM/0102/2024/25 - RE-ADVERT: APPOINTMENT OF A CONTRACTOR FOR THE CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

Employer

Witness 1

Witness 2

Contractor

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

| Contents | | | |
|---|--|-----------------|--------|
| Number | Heading | Volume | Colour |
| The Tender | | | |
| Part T1: Tendering procedures | | Volume 1 | |
| T1.1 | Tender Notice and Invitation to Tender | | White |
| T1.2 | Tender Data | | Pink |
| T1.3 | Standard Conditions of Tender | | Pink |
| Part T2: Returnable documents | | Volume 1 | |
| T2.1 | List of Returnable Documents | | Yellow |
| T2.2 | Returnable Schedules | | Yellow |
| T2.3 | Technical Schedules | Volume 1 | Yellow |
| The Contract | | | |
| Part C1: Agreement and Contract Data | | Volume 1 | |
| C1.1 | Form of Offer and Acceptance | | Yellow |
| C1.2 | Contract Data | | Yellow |
| C1.3 | Form of Guarantee | | Yellow |
| C1.4 | Occupational Health and Safety Agreement | | Yellow |
| Part C2: Pricing data | | Volume 1 | |
| C2.1 | Pricing Instructions | | Yellow |
| C2.2 | Bills of Quantities | | Yellow |
| C2.2 | Summary of Schedules | | Yellow |
| Part C3: Scope of Work | | Volume 1 | |
| C3 | Scope of Work | | Blue |
| C3.1 | Description of Works | | Blue |
| C3.2 | Engineering | | Blue |
| C3.3 | Procurement | | Blue |

Employer

Witness 1

Witness 2

Contractor


Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

| | | | |
|----------------------------------|---|-----------------|-------|
| C3.4 | Construction (Specifications) | | Blue |
| C3.4.1 | General Clauses and Requirements | | Blue |
| C3.4.2 | Standard Specifications | | Blue |
| C3.4.3 | Particular Specifications | Volume 2 | Blue |
| C3.4.4 | Variations and Additions to Standard and Particular Specifications | Volume 1 | Blue |
| C3.5 | Management | | Blue |
| C3.5.1 | Management of the Works | | Blue |
| C3.5.2 | Reference to the Scope of Works in Terms of the Occupational Health and Safety Act and Regulations: Health and Safety Specification | Volume 2 | Blue |
| C3.5.3 | Environmental Management Plan | Volume 2 | Blue |
| Part C4: Site information | | Volume 2 | |
| C4.2 | Conditions assessment of existing Bospoort pipeline | | Green |
| C4.1 | Geotechnical information | | Green |
| Book of Drawings | | Volume 3 | |



Employer



Witness 1



Witness 2



Contractor



Witness 1



Witness 2



C3.4.4 PARTICULAR SPECIFICATIONS FOR CIVIL WORKS

INDEX

| Item | Description | Page No |
|-------|--|------------|
| PLK: | MANUFACTURE AND SUPPLY OF VALVES | C3.4.4-2 |
| PLN: | MANUFACTURE, SUPPLY AND TESTING OF STEEL PIPES | C3.4.4-16 |
| PLQ: | CORROSION PROTECTION OF STEEL PIPES AND FITTINGS | C3.4.4-28 |
| PLS: | CEMENT MORTAR LINING OF PIPELINES | C3.4.4-70 |
| PLT: | FLOW METERS (GENERAL) | C3.4.4-86 |
| PLTP: | MANUFACTURE, SUPPLY AND TESTING OF THERMOPLASTIC PIPES | C3.4.4-95 |
| PLU: | PIPE BORING..... | C3.4.4-104 |
| AC | MITIGATION AND CATHODIC PROTECTION SPECIFICATION..... | C3.4.4.113 |

Tender
Part C3: Construction

C3.4.4-1

C3.4.4
Particular Specifications for Civil Works

ContractorWitness 1Witness 2EmployerWitness 1Witness 2



PLK: MANUFACTURE AND SUPPLY OF VALVES

INDEX

| Item | Description | Page No |
|--------------|--------------------------------------|------------------|
| PLK 1 | SCOPE | C3.4.4-3 |
| PLK 2 | STANDARDS | C3.4.4-3 |
| PLK 3 | MATERIALS | C3.4.4-3 |
| PLK 4 | TESTING AND INSPECTION | C3.4.4-14 |
| PLK 5 | MEASUREMENT AND PAYMENT | C3.4.4-15 |

Tender
Part C3: Construction

C3.4.4-2

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLK 1 SCOPE

This section of the Specification includes the manufacture, testing and supply of valves for the conveyance of raw or potable water at ambient temperatures in pipes under pressure.

PLK 2 STANDARDS

The most recent issues of the following standard specifications will apply for the purposes of this Specification.

| | | |
|-------------|---|---|
| SANS 144 | : | Cast-iron single door non-return valves |
| SANS 191 | : | Cast steel gate valves |
| SANS 192 | : | Cast steel single door non-return valves |
| SANS 664 | : | Cast iron gate valves for waterworks |
| SANS 665 | : | Cast iron gate valves for general purposes |
| BS 5155 | : | Cast iron and carbon steel Butterfly valves |
| ISO 2441 | : | Pipeline flanges for general use - shapes and dimensions of pressure tight surfaces |
| SANS 1123 | : | Steel pipe flanges |
| SIS 05 5900 | : | Pictorial surface preparation standard for painting steel surfaces |

PLK 3 MATERIALS

PLK 3.1 Sluice Valves

- PLK 3.1.1 The valve body, bonnet, thrust dome, gate and glands shall be of cast iron or cast steel as specified and depending on the required test pressures.
- PLK 3.1.2 The stuffing box shall be of ample depth to afford sufficient space for long period packing and the design shall be such as to allow the gland to be easily and conveniently repacked under pressure.
- PLK 3.1.3 Body and gate sealing rings shall be of bronze, gunmetal or stainless steel. RSV gate shall be nitrile rubber covered and fully encapsulated. The rubber shall not be removed from the guides of the gate.
- PLK 3.1.3 Spindles shall be of high grade stainless steel.
- PLK 3.1.4 An isolating valve must be able to check the specified water pressure from both sides.

Tender
Part C3: Construction

C3.4.4-3

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLK 3.2 Butterfly Valves

- PLK 3.2.1 Valve bodies and discs shall be of high-grade cast-iron or cast steel as specified and depending on the required test pressures.
- PLK 3.2.2 The disc shaft or stub-shafts shall be of stainless steel located in self-lubricating bearings.
- PLK 3.2.3 Sealing rings, seal retaining rings, body seatings and associated screws shall be of stainless steel.
- PLK 3.2.4 A butterfly valve must be able to check the specified water pressure from both sides.

PLK 3.3 Reflux Valves

- PLK 3.3.1 Valve bodies shall be of cast iron or cast steel depending on the specification or test pressures.
- PLK 3.3.2 Valve doors shall be of cast iron or cast steel.
- PLK 3.3.3 The valve body and doors or disc shall be fitted with replaceable stainless steel body and door seat rings.

PLK 3.4 Air Valves

PLK 3.4.1 Function

Air valves are required to perform any combination of the following functions:

- Uninterrupted high volume air discharge through a large orifice during pipe filling.
- Uninterrupted high volume air intake through a large orifice during pipe emptying.
- Discharge of pressurised air through a small orifice during normal operation.
- Surge alleviation mechanism during rapid air discharge or rejoining of separated water columns.

PLK 3.4.2 Closing mechanism, construction and design

- PLK 3.4.2.1 The air release and vacuum break valve shall be of a compact single chamber design with solid cylindrical High Density Polyethylene control floats. Floats of spherical design shall not be accepted. Any hollow float design will not be acceptable due to implosion and distortion making sealing difficult or impossible.

Tender
Part C3: Construction

C3.4.4-4

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLK 3.4.2.2 The ends of the cylinder shall be of fusion bonded epoxy powder coated mild steel, secured by means of stainless steel tie rods.

PLK 3.4.2.3 Floats shall be housed in a tubular stainless steel or corrosion protected body, secured by means of stainless steel fasteners.

PLK 3.4.2.4 The seats, spindles, guides, etc shall be of a suitable non-corroding metal with sufficient clearance and shall be designed to prevent abrasion of the ball or float when subjected to frequent operation.

PLK 3.4.2.5 The seats of the orifices shall not have sharp edges and shall be designed so as not to damage the ball or float when subjected to pressure.

PLK 3.4.2.6 The valve shall have an integral surge alleviation mechanism which shall operate automatically to limit transient pressure rise or shock induced by closure due to high velocity air discharge or the subsequent rejoining of separated water columns.

The limitation of pressure rise must be achieved by deceleration of approaching water prior to valve closure.

Relief mechanisms that act subsequent to valve closure cannot react in the low millisecond time span required and are therefore unacceptable.

The performance capability of an integral surge alleviation mechanism shall be substantiated through third party testing, conducted by a recognized authority.

PLK 3.4.2.7 Large orifice sealing shall be effected by the flat force of the control float seating against a nitrile rubber 'O' Ring housed in a dovetail groove circumferentially surrounding the large orifice.

Sealing in any other form shall not be accepted due to the vulcanizing of the float or the wedging of the float in the large orifice.

PLK 3.4.2.8 Discharge of pressurized air shall be controlled by the seating and unseating of a small orifice on a natural rubber seal affixed to the control float.

Valves with slotted air release apertures shall not be considered.


PLK 3.4.2.9 The intake/discharge orifice area shall be equal to the nominal size of the valve i.e. a 200 mm valve shall have a 200 mm intake/discharge orifice.

Valves up to and including 200mm NB shall incorporate an over pressure safety feature that will fail without an explosive effect, such as is normally the case when highly compressed air


Tender
Part C3: Construction

C3.4.4-5


C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2



is released suddenly. This feature shall consist of easily replaceable components such as gaskets, seals or the like.

PLK 3.4.2.10 The valve construction shall be proportioned with regard to material strength characteristics, so that deformation, leaking or damage of any kind does not occur by submission to 2 times the designed working pressure.

PLK 3.4.3 Testing

PLK 3.4.3.1 Manufacturers' published performance data must be substantiated by third party testing from a recognized test authority.

PLK 3.4.3.2 A high pressure strength and leak test whereby the valve is filled with water and pressurized to 2 times the rated working pressure which shall be held for a period of 2 minutes. Any leaking, weeping and sweating shall be a reason for rejection. These tests must be on total, completed units including floats.

PLK 3.4.3.3 Any imported valves shall be retested locally in all areas of specification.

PLK 3.4.4 Isolating valves for air valves

PLK 3.4.4.1 Each air valve shall be provided with a suitable double flanged resilient seal gate valve to isolate the air valve from the main.

PLK 3.4.4.2 The isolating valves shall be capable of operating in a horizontal position and shall be provided with a handwheel for operation and gearing is not required.

PLK 3.4.4.3 Each isolating valve shall be provided with a handwheel fitted to the spindle in an approved manner and shall have directional indication so cast into a recess on the upper surface of the rim that the top of the letter, arrows and rim are at the same level.

PLK 3.4.5 Drains

PLK 3.4.5.1 All air valves be provided with drain cocks so that the body of the valve can be drained when isolated from the pipeline. Cast steel gate valves shall be provided for this purpose.

PLK 3.4.6 Pressure gauge fitting

PLK 3.4.6.1 A 12-mm cast steel full bore gate valve shall be fitted to the spool piece between the isolating valve and the air valve flanges for attaching a pressure gauge.

Tender
Part C3: Construction

C3.4.4-6

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLK 3.5 Ring needle valves

- PLK 3.5.1 The valve body shall be of spheroidal graphite iron or cast-steel with supporting feet. The body seat shall be of stainless steel and shall be replaceable or may be deposit welded on a removable body section.
- PLK 3.5.2 For ring needle valves the piston (plunger) shall be of cast stainless steel with replaceable resilient seal to obtain drop tightness, held in place by a retaining ring of stainless steel and corrosion resistant screws.
- PLK 3.5.3 For spherical ball valves, the eccentrically supported ball plug shall be of cast stainless steel or spheroidal graphite iron with replaceable resilient seal to obtain drop-tightness, held in place by a retaining ring of stainless steel and corrosion resistant screws. The valve body shall include an access door to permit adjustment or replacement of the valve seal without dismantling the valve.

PLK 3.6 Manufacture

PLK 3.6.1 General

- PLK 3.6.1.1 The design pressure of the valves shall not be less than the pressure specified subject to a minimum of 1 000 kPa.
- PLK 3.6.1.2 All valves shall be double-flanged with bolt holes drilled off-centre all in accordance with the requirements of SANS 1123 or as otherwise specified.
- PLK 3.6.1.3 The Tenderer shall give as a function of the downstream pressure the maximum acceptable discharge of water through the valves without risks of vibration and cavitation. The Tenderer shall also submit the head-loss characteristics of the valves.
- PLK 3.6.1.4 The design pressure will be hand stamped on the top edge of the flanges of valves in kPa.
- PLK 3.6.1.5 If specified, valves shall be supplied with by-passes to be bolted on to the body of the valve and not to the adjoining pipework.
- PLK 3.6.1.6 Valves shall be fitted with position indicators if specified. Fully closed, fully open and intermediate positions shall be indicated in corrosive proof and robust design indicators.
- PLK 3.6.1.7 Arrows shall be cast on all handwheels together with the wording "OPEN" or "CLOSE". The closing direction shall be clockwise unless otherwise specified.

Tender
Part C3: Construction

C3.4.4-7

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

In the case of cap top valves, an aluminium disc of at least 100 mm diameter and with the same wording and arrows shall be slipped over the spindle and retained by the cap.

PLK 3.6.1.8 All valves shall be supplied complete including bolts, nuts, washers and gaskets in accordance with the class of valve. Bolts shall be of sufficient length to allow not more than three screw threads to protrude outside units after complete tightening of the assembly. Gaskets for flanged joints shall be of compressed asbestos fibre to BS 2815 Grade A and full faced with a minimum thickness of 3 mm for pressures up to and including 1 600 kPa cloth-inserted rubber may be used.

PLK 3.6.1.9 Where isolating valves are required to be equipped with extended off-set spindles, the spindles shall be equipped with sufficient universal joints to ensure satisfactory valve operation. All spindle extensions shall be secured to permanent structures with galvanised clamps to the Engineer's approval. The rate for such valve items shall include for any required clamps, extensions joint, etc.

Handwheels on such extended spindles shall be mounted on plain-ended spindle or handwheel pedestal as specified or indicated on the construction drawings.

Isolating valve operation:

| | |
|---|------|
| Cap top | CT |
| Handwheel | HW |
| Electric actuator | EA |
| Pneumatic actuator | PA |
| Handwheel spindle extension | HSE |
| Plain ended spindle extension | PESE |
| Platform-mounted handwheel pedestal | PMP |
| Handwheel pedestal on wall support bracket | HPWB |
| Stub handwheel pedestal on wall support bracket | SHWB |
| Grid-mounted handwheel pedestal | GMP |

PLK 3.6.1.10 The following information shall accompany the tender:

- Description
- Flange Drilling
- Maximum working pressure
- Maximum unbalanced pressure
- Test pressure
- Manufacturers number
- Material of components

Tender
Part C3: Construction

C3.4.4-8

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



- Gearing
- Accessories

PLK 3.6.2 Sluice Valves

- PLK 3.6.2.1 Double-flanged, wedge-gate, internal (non-rising) spindle sluice valves of the waterworks pattern are required to comply fully with SANS 191 or SANS 664 where applicable.
- PLK 3.6.2.2 Only full-way valves will be accepted (i.e. the gate must be clear of the waterway in the fully open position).
- PLK 3.6.2.3 The maximum force required to turn the handwheel at the maximum torque shall not be greater than 100 N per hand at the handwheel run (Total effort = 200 N) when operating at an unbalanced pressure equal to the rated working pressure of the valve. This may be achieved with the aid of gearing of a suitable ratio.

Where gears are used replaceable shear pins shall be provided to prevent damage to the valve if excessive pressure is used.

PLK 3.6.3 Butterfly Valves

- PLK 3.6.3.1 Horizontal spindle type butterfly valves complete with gearing, handwheels and flanged at both ends with separate bolting for joining to the adjacent pipework is required.
- PLK 3.6.3.2 All butterfly valves shall be double eccentric / offset type.
- PLK 3.6.3.3 Wafer valves or valves fitted with studs for attachment to the adjacent flanges are not permitted.
- PLK 3.6.3.4 Valves shall be drop-tight when closed and metal to metal sealing is not acceptable.
- PLK 3.6.3.5 All resilient seals shall be removable and readily replaceable on Site with the valve in position.
- PLK 3.6.3.6 Resilient seals shall be retained by corrosion resistant securing elements to prevent corroding in position (e.g. bolts, set screws, etc.)
- PLK 3.6.3.7 The valve-water seal shall be of the following types:
- a resilient seal fixed to the edge of the disc by corrosion resistant securing elements sealing on a stainless steel or bronze insert fixed in the body.
 - a resilient seal fixed to the body of the valve by corrosion resistant securing elements sealing on a stainless steel or bronze insert fixed in the edge of the discs.

Tender
Part C3: Construction

C3.4.4-9

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLK 3.6.4 Reflux Valves

PLK 3.6.4.1 Reflux valves shall be double-flanged, SANS 1551.

PLK 3.6.4.2 Valve bodies and seals shall be free of pockets that will allow dirt accumulation and prevent the doors from closing fully.

PLK 3.6.4.3 Stops or an approved resilient material shall be fitted into the body to prevent the doors from fluttering under full flow conditions.

PLK 3.6.4.4 Valves shall be designed to allow for rapid but non-slamming closing characteristics.

PLK 3.6.5 Air Valves

PLK 3.6.5.1 Air valves shall be supplied with double-flanged, wedgegate internal (non-rising) spindle sluice valves for isolation, which unless otherwise specified shall conform in all respects to this specification.

PLK 3.6.6 Ring needle valves

PLK 3.6.6.1 Ring needle valves used as auto closing valves shall fulfil the following functions:

- Electrical operation (isolating and control) suitable for opening and closing against the specified pressure and for continuous operation in any intermediate position.
- Automatic as well as manual mode control.
- Automatic reflux action for quick closure by means of drop-weight and hydraulic dash pot in case of power failure or motor protective tripping.
- Adjustable closing time and adjustable closing characteristic.

PLK 3.6.6.2 The totally enclosed flanged-on gearbox shall include the following:

- Either an electro-mechanical unit comprising:
 - a totally enclosed brushless electromagnetic gear clutch for quick closing;
 - a totally enclosed directly mounted electric valve actuator with integral electric controls and auxiliary handwheel for manual operation;
- or an electro-hydraulic unit comprising:
 - an oil hydraulic lift cylinder for opening the valve;

Tender
Part C3: Construction

C3.4.4-10

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



- a totally enclosed directly mounted electronic driven oil pump and oil reservoir. The oil pump and reservoir may be individually mounted on each valve or a centralised system may be employed to feed more than one valve and/or pumpline;
- a solenoid operated hydraulic control valve which shall be de-energised to initiate closure of the valve.

PLK 3.6.6.3 Either of the above actuators shall also be provided with:

- limit switches for signalling the “open”, “closed” and intermediate “10%” positions and further control functions as required;
- a directly mounted oil hydraulic dashpot with the necessary control valves for adjusting closing time and operating characteristic;
- means to operate the valve manually;
- valve shaft (stub shafts) of high tensile stainless steel located in bushes of zinc-free bronze;
- a drop weight lever arm of steel with adjustable cast iron drop weight. The lever arm shall be keyed or splined to the shaft.

PLK 3.6.6.4 The overhang shaft carrying the drop weight lever arm shall be supported at its bearing housing from the foundation block.

PLK 3.6.6.5 Travel of the drop weight shall be restrained for reasons of safety at either end of the lever arm.

PLK 3.6.6.6 The control valves shall be arranged for selection of either manual-electric or automatic-electric operation controlled from the pump control console. Push buttons “open”, “close” and “stop” for piloting these valves, when throttling is required, shall be incorporated in each pump control console, as well as indicator lamps showing “closed” (green) “intermediate” (amber) “open” (red) positions. In addition, a selector switch “manual/automatic” shall be incorporated, the automatic position being in conjunction with pump starting. A further “test” selector switch shall be mounted inside the panel to permit manual-electric testing of the equipment without running the pumpset.

PLK 3.6.6.7 In the “automatic” mode the valve shall open automatically from the fully closed to fully open position when the pumpset is started, likewise closing automatically, when the pumpset is to be shut down. In the “manual” mode the valve shall open automatically to at least the “10% open” intermediate position, whereafter manual selection of the valve position shall be enabled.

- Each valve shall be interlocked with the pump starter. When the pump is to be stopped, the valve shall close slowly to prevent water hammer either by means of the electric actuator or by releasing hydraulic pressure in the lift cylinder by means of control valves before the pumpset is tripped and stopped by interlocked relays.

Tender
Part C3: Construction

C3.4.4-11

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



- Similarly, the valve shall be arranged so that the pump can be started only when the valve is fully closed. The valve shall open only when the starting operation is completed and the motor is up to speed.

PLK 3.6.6.8 The control valves shall have automatic reflux action features to close by drop-weight, controlled by an oil hydraulic dashpot, in the event of power failure or motor protective tripping. The drop-weight shall be released by a solenoid operated clutch or a valve which is constantly energised during pumping operations. Closing time and characteristics shall be adjustable to minimise water hammer.

PLK 3.6.6.9 It shall be possible to energise the “manual” mode only when:

- the associated pump is running.
- the valve is at least 10% open as indicated by the “intermediate” lamp.
- the valve is in the “test” mode

Selection of the “manual” mode shall not affect the automatic reflux action.

When the opening of the valve has been set manually, the valve shall maintain this position in the absence of any further action.

PLK 3.6.6.10 “Test” mode: With both isolating valves closed and electrically interlocked, a test facility shall be provided to enable the maintenance personnel to manually operate the valve without the pumpset running by selection from inside the pump control console.

PLK 3.6.6.11 Valves shall be designed to operate free of cavitation in intermediate positions.

PLK 3.6.7 Electric Actuators

PLK 3.6.7.1 When specified, in the Project Specification the valves shall be fitted with electric, motor-driven flood-proof IP 68 actuators of robust design, capable of closing the valves under all unbalanced pressures.

PLK 3.6.7.2 The Tenderer shall state the maximum torque required to operate the valve in his Tender. In determining this maximum torque an allowance shall be made for any deterioration that could be expected to occur in the bearings during the life of the valve. The actuator shall be capable of transmitting twice this maximum torque without any of its components suffering permanent damage. This shall be proven to the Engineer's satisfaction by workshop tests.

Tender
Part C3: Construction

C3.4.4-12

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



- PLK 3.6.7.3 The actuators shall be capable of restraining the valve in any position under all possible conditions of operation, and shall not, in any circumstances, be capable of becoming self-motorised as a result of the dynamic torque loading on the disc or plunger.
- PLK 3.6.7.4 All gearing shall be manufactured in accordance with BS 436 Class C and shall be machine cut. All components requiring lubrication shall be adequately lubricated and totally enclosed flood-proof casing fabricated in cast iron and/or die cast aluminium to suit the service weather proof casing whether the valve is to be installed in the open or under cover. Actuators shall also be fitted with mechanical stops to prevent excessive turning and shall be provided with replaceable shear pins.
- PLK 3.6.7.5 Handwheels shall be fitted to all actuators. The direction of rotation to close the valve shall be clockwise when viewed from above the end of the input shaft and from the position of operation. In addition, they shall be clearly and indelibly marked with an arrow showing the direction of closing and the words "Close" and "Toe".
- PLK 3.6.7.6 Whether the valve is actuator driven or manually operated, the maximum force required to turn the handwheel at the maximum torque defined above shall not be greater than 100 N per hand at the handwheel rim. (Total effort = 200 N.) For large valves the minimum of complete revolutions of the handwheel to move the valve gate from fully open to fully closed shall not be less than 100.
- PLK 3.6.7.7 All electric actuators shall be provided with reversing contactors: local and remote control shall be provided; a device making the local control non-operative shall also be provided on the relevant remote control panel.
- PLK 3.6.7.8 After factory tests, the actuators shall be removed from the valve and delivered to Site in separate boxes to safeguard against damage.

PLK 3.6.8 Protection

All materials and workmanship to comply with relevant SANS Specifications.


PLK 3.6.8.1 Internal Protection

Internal surfaces of valve bodies and discs shall be grit blasted to a Sa 2½ of SIS 05 50 00 finish. Successive coats of an approved non-toxic epoxy resin paint suitable for spray application (Copon EP 2300 or similar) shall then be applied to give a final dry film thickness of 250 µm. Drying times between successive layers shall be strictly in accordance with the requirements of the paint manufacturer.


Tender
Part C3: Construction

C3.4.4-13


C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2



As an alternative to the protection as specified above, the Contractor may be required to use either a solventless epoxy paint system or a fusion bonded epoxy powder coating as specified in the Project Specification.

PLK 3.6.8.2 External Protection

External surfaces of valve bodies shall be wire brushed to a A 3 of SIS 05 59 00 standard and painted with one layer zinc chromate primer (dried film thickness 50 µm). This will be followed by two alkyd-based undercoats (each coat 25 µm thick) and one alkyd-based enamel finishing coat (dried film thickness 25 µm). Final colour will be as specified by the Engineer.

Machined flanges will be painted with a protective coating of shellac or similar.

PLK 3.7 Tolerances

Tolerances as specified in the appropriate SANS or BS standards shall apply to this Contract.

PLK 4 TESTING AND INSPECTION

PLK 4.1 Testing by Manufacturer

The Manufacturer shall carry out all tests to ensure that valve materials conform to the requirements of the relevant SABS or BS Specification. These tests will not necessarily be attended by the Engineer but records must be kept and all test results shall be made available to the Engineer.

PLK 4.2 Testing by Independent Body

The Engineer may appoint an independent recognised body to conduct control tests. Samples required for such tests will be provided by the Manufacturer free of charge and sampling will be done by this body in accordance with the relevant SANS or BS Specification.

The cost of such control tests will be borne by the Employer.

PLK 4.3 Inspection

PLK 4.3.1 Visual, operational and dimensional inspection of valves as well as inspection of protective coatings will be carried out by the Engineer and/or the Manufacturer in the Manufacturers workshops prior to the despatch of valves to site.

Tender
Part C3: Construction

C3.4.4-14

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLK 4.3.2 Inspection by the Engineer shall in no way relieve the Manufacturer of any of his obligations to design, manufacture and supply valves strictly in accordance with the Specification.

PLK 4.4 Hydrostatic Testing

PLK 4.4.1 All hydrostatic tests will be witnessed by the Engineer and the Manufacturer will give at least one week prior notification to the Engineer of the proposed dates for such tests.

PLK 4.4.2 Valve bodies will be close end tested to at least 1,5 times the working pressure. Test pressures will be maintained for at least 5 minutes and valve bodies will be water tight in all respects at the test pressure.

PLK 4.4.3 Assembled valves will be open-end tested to 1,5 x working pressure for materials strength and soundness. Valves will be drop tight from both directions over the complete range of pressures from 0 to 1,5 x working pressure.

PLK 4.4.4 Each valve will be supplied with a test certificate certifying that it complies in all respects with the requirements of this Specification.

PLK 5 MEASUREMENT AND PAYMENT

PLK 5.1 General

Tendered prices shall include for the following unless otherwise specified in the Project Specification.

- Protective coatings as specified.
- Couplings and/or jointing material for each type of valve.
- Packing and temporary protection against damage during transport and delivery.
- Temporary storage and maintenance if required.
- Delivery and storage of material on site or in a store as specified.
- Testing and inspections at Manufacturer's works.

PLK 5.2 Valves will be measured per unit of each type

Tender
Part C3: Construction

C3.4.4-15

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



PLN: MANUFACTURE, SUPPLY AND TESTING OF STEEL PIPES

INDEX

| Item | Description | Page No |
|--------|--|-----------|
| PLN 1 | SCOPE | C3.4.4-17 |
| PLN 2 | STANDARDS | C3.4.4-17 |
| PLN 3 | PROCESS OF MANUFACTURE FOR PIPES | C3.4.4-18 |
| PLN 4 | DIMENSIONAL REQUIREMENTS | C3.4.4-19 |
| PLN 5 | TESTING AND INSPECTION AT MANUFACTURER'S WORKS AND AT SITE | C3.4.4-19 |
| PLN 6 | FLANGES | C3.4.4-23 |
| PLN 7 | FLEXIBLE COUPLINGS AND FLANGE ADAPTORS | C3.4.4-25 |
| PLN 8 | BOLTS, THREADED RODS, STUDS, NUTS AND WASHERS | C3.4.4-25 |
| PLN 9 | THERMIT WELDING PADS | C3.4.4-26 |
| PLN 10 | MARKING OF PIPES..... | C3.4.4-26 |
| PLN 11 | UV PROTECTION OF COATINGS..... | C3.4.4-26 |
| PLN 12 | HANDLING, DELIVERY AND STORING OF PIPES AND SPECIALS | C3.4.4-26 |

Tender
Part C3: Construction

C3.4.4-16

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLN 1 SCOPE

This specification covers the manufacture and supply of bare, electric welded low carbon steel pipes and steel pipe special items for the conveyance of water at ambient temperatures and at medium pressures.

PLN 2 STANDARDS

Pipes and specials shall be manufactured, tested and inspected in accordance with the latest issues of the following standard specifications unless amended in subsequent clauses in this specification.

- a) Welded pipes larger than 150mm:

SANS 719: Steel Grades A, B and C

SABS 1431: Steel Grades 300 WA, 350 WA

API 5L: Steel Grades, X42, X46, X52, X56 and X60

EN 10025-2: Steel Grade S355JR + AR (where specified for specials)

- b) Welded specials and fittings smaller than or equal to 150mm:

SANS 62 (Heavy Class) up to 50 bar design pressure

- c) Seamless Pipes:

ASTM A106 – Schedule 40(40 bar) or 80(80 bar) as determined by the design pressure.

- d) Seamless specials and fittings:

ANSI B16.5 & B16.9 – Schedule as determined by the design pressure

- e) Qualifications of Welders

All manual or semi-automatic welds and repair welds shall only be undertaken by welders qualified under the tests laid down in accordance with API 1104.

- f) Non-destructive Tests and Adjudication

- Radiographic inspection: API 1104
- Ultrasonic inspection: API 5L

Tender
Part C3: Construction

C3.4.4-17

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

g) In this Specification reference is made to the latest issues of the following specifications:

SANS 719
API 5L
API 1104
ASME Section V
BS 2971
BS 2633

PLN 3 PROCESS OF MANUFACTURE FOR PIPES

PLN 3.1 Welding process

Pipes shall be manufactured by an approved semi-automatic submerged-arc welding process or shall be electric resistance welded. Where semi-automatic submerged-arc welding is employed, at least one pass shall be made on the inside and at least one pass on the outside. The number of longitudinal weld seams shall not exceed:

- a) one seam for pipes up to 1 000mm nominal diameter
- b) two seams for pipes larger than 1 000mm and up to 2 000mm nominal diameter

Circumferential welds by semi-automatic submerged-arc welding method for factory double jointed pipes shall have at least one pass on the inside and at least one pass on the outside.

PLN 3.2 Welds

SANS 719, BS 2971 and BS 2633 shall generally apply.

For fusion welded pipes and specials, the internal weld bead shall not protrude more than 1,0 mm into the bore of the pipe or special.

For electric resistance welded pipes, the height of upset metal and flash on the inner surface shall not exceed 2,0mm.

For pipes to be joined by butt welding, the internal weld bead shall be ground flush with the pipe body for a length of 200mm from ends to be joined.

For pipes to be coupled by flexible couplings, external weld reinforcement or upset metal and flash shall be ground flush with the pipe body for a length of 200mm from the end to be coupled.

Tender
Part C3: Construction

C3.4.4-18

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLN 4 DIMENSIONAL REQUIREMENTS

PLN 4.1 Pipes

All dimensions shall be in accordance with SANS 719 clause 5.1 (or other relevant clause numbers in later versions) except for the following amendment to clause 5.1.3:

The wall thickness of pipe shall, subject to a tolerance of +10% or -0%, be one of the relevant values given in columns 3 to 6 of table 2, unless otherwise specified by the purchaser.

PLN 4.2 Specials

The tolerances on specials will be in accordance with BS 534, Section 4.

Unless shown otherwise, branch and manifold sections of Tees to have a common centre line and of scour tees to have a common invert line.

All dimensions on layout drawings or item details are outer face to outer face, i.e. overall.

Position dimensions for puddle flanges and restraining flange refers to centre of flanges.

PLN 5 TESTING AND INSPECTION AT MANUFACTURER'S WORKS AND AT SITE

PLN 5.1 General

Factory and site testing and inspections (quality assurance), supervision of tests and reviewing of test records shall be carried out by the Contractor.

Unless otherwise specified in the contract documents, the Contractor shall appoint an independent inspectorate ("Inspectorate") and shall be responsible for the Inspectorate's and all associated costs. The name of the Inspectorate to be submitted for the Employer /Engineer's approval. The Inspectorate will be responsible for the monitoring, witnessing and reviewing of the quality assurance plans, testing, inspections and records on behalf of the Employer / Engineer. The service provided by the Inspectorate shall not replace the duties and responsibilities of the Contractor in terms of the Contract.

All tests and inspections at the factory and on site shall be at the expense of the Contractor who shall provide all necessary testing facilities, labour, instruments, equipment and samples that will be required by the Contractor and the Inspectorate, to verify that the material complies with the Specifications. The testing facilities, instruments and equipment shall comply with the requirements of the Inspectorate.

Tender
Part C3: Construction

C3.4.4-19

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The Inspectorate shall be afforded every facility and opportunity during the manufacturing and testing to enable the inspection to be carried out effectively.

All test samples shall be selected by the appointed Inspectorate and all instruments used for testing purposes shall be approved by the Inspectorate and if in the opinion of the Inspectorate any instrument should require calibration, such instruments shall be calibrated at the expense of the Contractor by the SABS or such other body as may be approved by the Inspectorate.

No mechanical working or straining of pipes and specials shall be allowed after testing and inspection.

PLN 5.2 Visual Inspection

All finished pipes and specials shall be visually examined and shall be free of injurious defects as defined in API 5L Section 10.2.7. In addition, welds on specials shall be inspected by the application of a penetrant-dye on the inside of the welds and no trace of the dye should appear on the outside of the pipe after completion of the test.

PLN 5.3 Non-destructive Inspection

PLN 5.3.1 Ultrasonic Inspection

The Engineers approval of a detailed method statement is required for the use of this test method prior to the start of production. When this method is used 100% of all longitudinal or spiral welds on straight pipes shall be checked with an approved ultrasonic method capable of continuous and uninterrupted inspection of the weld seam in accordance with API 5L, Annexure E5. The equipment shall be checked with an applicable reference standard at least twice every production shift.

PLN 5.3.2 Radiographic Inspection to API 1104

Radiographic testing of welds are regarded as industry norm and shall be used unless approved otherwise by the Engineer. Test records are required to be saved in digital format. It is a requirement that 100% of longitudinal, circumferential, spiral welds and scalp welds shall be subject to radiographic inspection in accordance with API 1104, Section 9.3.

Radiographic inspection of pipes shall be as follows:

- a) Longitudinal Welded Pipe

Tender
Part C3: Construction

C3.4.4-20

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Submerged-arc fusion welded pipe, if inspected full length by ultrasonic methods, shall also be inspected by radiographic methods for a distance of 200 mm from each end of each length of pipe. Electric resistance welded pipes shall, however, only be inspected full length by ultra-sonic methods.

b) Spiral Welded Pipe

Submerged-arc fusion welded pipe, if also inspected full length by ultrasonic methods, shall also be inspected by radiographic methods for a distance of 100 mm from each end of each length of pipe and of the complete "H" at all skelp end welds including 150 mm of the spiral welds in both directions away from the intersection points with the skelp end welds.

c) Circumferential Butt Welds

100 percent of the length of circumferential butt welds shall be examined radiographic methods unless consistently acceptable results are obtained. Then the number of welds to be tested may be reduced by the Engineer.

d) Specials

100 percent of the length of all manual or semi-automatic welds in specials shall be examined radiographically (where possible) and all other welds by liquid penetrant testing unless consistently acceptable results are obtained. Then the number of welds to be tested may be reduced by the Engineer.

Where specials cannot be hydrostatically tested, all welds shall be liquid penetrate tested as per ASME Section V.

e) Repairs

For straight pipes 100 percent of the total length of all repairs shall be examined radiographically unless repairs are done prior to ultrasonic inspection and such repairs pass ultrasonic inspection. Then no radiographic inspection of same is required.

For pipe specials, 100% of all repairs shall be examined radiographically (where possible) and all other weld by liquid penetrant testing.

f) Pipes for rail, road and river crossings shall be examined radiographically 100 percent of the total length of all welds.

Tender
Part C3: Construction

C3.4.4-21

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLN 5.3.3 Liquid Penetrant Testing

All fillet welds and other welds where requested by the Engineer, shall be liquid penetrant tested in accordance with sub-clause 7.2.1 of SANS 1200 L, clause 9.5 API 1104, ISO 10893-4 and ASTM E165.

PLN 5.3.4 Magnetic Particle Testing

Where requested by the Engineer, magnetic particle testing shall be done in accordance with ASME Boiler and Pressure Vessel Code, Section V, Article 7.

PLN 5.4 Hydrostatic Testing

Each individual straight pipe shall be subjected to a hydrostatic test in accordance with the methods described in API 5L. Test pressures shall be such as to produce tensile fibre stresses in the pipe wall of 90% of the minimum specified yield strength of the steel or shall be 9 MPa whichever is the lesser. Leaks or sweats shall be considered injurious defects.

Should it not be possible to hydrostatically test straight piping and/or specials, the liquid penetrant test as per ASME Section V shall be done on all welds over and above the non-destructive tests specified above. This shall only be applicable with the prior written approval of the Engineer.

PLN 5.5 Repair of Injurious Defects

Injurious defects found by non-destructive testing of welds, visual examination, hydrostatic testing or determined by any other means to exceed the limitations in API 5L Section 10, shall be repaired in accordance with API 5L Annexure D but subject always to the requirements of this specification.

PLN 5.6 Destructive Testing

PLN 5.6.1 Type of tests

The following destructive tests shall be performed in accordance with SANS 719 clause 6.2 on the first pipe and thereafter on one pipe of every 500 subsequent pipes.

- a) Transverse Tensile Test
- b) Root Bent Test (Electric Fusion Welds)
- c) Flattening Test (Electric Resistance Welds)

Tender
Part C3: Construction

C3.4.4-22

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLN 5.6.2 Sampling for Destructive Tests

The following samples shall be selected for destructive testing:

a) **First Sample**

A section long enough to provide all the test specimens and material shall be cut from the selected pipe.

b) **Second Sample**

If the test specimens and material from the first selected pipe fail to pass any of the tests, a section long enough to provide the appropriate specimens for the tests failed by the first sample shall be cut from two further pipes.

c) **Third Sample**

If the test specimen from the second sample fails to pass the test(s) a similar section shall be cut from each of a further ten pipes.

d) **Compliance**

The piping shall be considered as complying with the specification if after testing of the first or the second or the third sample no defect is found.

PLN 6 FLANGES

- a) Flanges shall be designed and manufactured to BS EN 1092 Part 1 for steel flanges and Part 2 for cast iron flanges, unless otherwise specified on the drawings. Flanges not covered by BS EN 1092 shall be manufactured according to NWS 1676 Revision 0 dated May 1981. Unless otherwise indicated on the drawings or specified in the Bill of Quantities, flanges shall be of forged Grade 300WA steel or ASTM A105.
- b) Sealing faces shall be machined flat to a tool-mark of 0.8 mm to 1.25 mm pitch spiral or concentric serrations and back of flanges to be either machined or spot-faced around holes with sufficient clearance to ensure proper seating of bolt heads and nuts. All bolt holes shall be drilled perpendicular to the flange face. Bolt holes shall be positioned off-centre and symmetrically off-set from the vertical centre lines of the flange and flanges shall be installed truly square to the axis of the pipe. The Contractor shall check the compatibility of drilling of all flanges to be connected together.
- c) Flange thicknesses and bolt sizes shall conform to the appropriate table of BS EN 1092 or NWS 1676 Revision 0 dated May 1981 for flanges not covered by BS EN 1092. The

Tender
Part C3: Construction

C3.4.4-23

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Contractor shall satisfy himself that the flanges in his supply shall match the flanges supplied by others or at interfaces between Subcontractors, if any.

- d) The Contractor shall ensure that the drilling patterns of pipe specials to be installed on both sides of valves and flow meters will match that of the appropriate supplied valve and flow meter.
- e) All flanges designed for pressure ratings up to and including 1600 kPa, shall be flat faced with full face gaskets. Flanges designed for pressure rating exceeding 1600 kPa shall be raised face flanges supplied with ring gaskets. Flanges with pressure ratings of 6400 kPa and higher and flange sizes of 2500 mm diameter and larger, irrespective of pressure rating, shall incorporate an "O" ring groove. Details of the "O" ring groove shall be furnished by the Contractor for consideration by the Engineer.
- f) All gaskets supplied under this Contract shall be of tanged graphite full face for flat joint faces and aramid and glass fibre with nitrile rubber binder to BS 7531 ring face for raised faces. Gaskets shall be suitable for the specified pressures with a minimum thickness of 3 mm and purpose made to the dimensions of the matching flanges. Joints in gaskets shall be kept to the minimum. Where not avoidable, joints shall be a tight fitting dovetail design.
- g) Corrosion protection for the area not clamped shall be similar in all respects to that applied externally to the pipework/valve/pump.
- h) All mill scale on flanges shall be removed by abrasive blasting before flanges are fitted and welded to pipes and fittings.
- i) All flanges shall be supplied complete with bolts, nuts, washers and gaskets. Rubber joint rings shall comply with SANS 4633.
- j) Puddle flanges shall not be drilled.
- k) Some flexible couplings to be restrained by means of a restraining flange. Unless specified on the Drawings, the diameter, number and length of the long restraining bolts as well as any possible pipe wall thickening shall be designed by the Contractor with the assistance with the manufacturer. The effect of cyclic loading and fatigue must also be taken into consideration. The seal retaining flange on the flexible coupling may be factory machine scalloped to accommodate the long bolts. All the necessary nuts, washers, etc. for the restraining bolts must be provided by the Contractor.

Restraining flanges need not have all the bolt holes specified in the applicable flange drilling table. Only those required for the long restraining bolts need to be provided. These holes must comply with the applicable flange drilling table and be spaced equally on the flange PCD and symmetrically around the flange centre lines.

Restraining bolts to be positioned so as to not interfere with any stubs specified for an item.

- l) Blank (Blind) flanges for pipes equal to or greater than 400 dia to be provided with two suitable lifting handles with coating similar to the blank flange.

Tender
Part C3: Construction

C3.4.4-24

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLN 7 FLEXIBLE COUPLINGS AND FLANGE ADAPTORS

Flexible couplings and flange adaptors shall be the Viking Johnson or Klamflex type or similar approved by the Engineer. Straub, Arpol or similar clamp on couplings are not acceptable.

Manufacturer of straight and stepped couplings (SR-C & ST-C) as well as flange adaptors (FA) to be approved by the Engineer. Couplings must be able to withstand hydrostatic test pressures of 1.5 times the specified design pressures and coupling flanges must be designed to withstand all stresses due to tightening of the bolts.

Rubber rings shall generally comply with SABS 974 Class F.

Flexible couplings shall be supplied complete with all necessary bolts, nuts and rubber jointing rings.

Coupling installation gaps to comply with supplier's specification.

Applicable to all flange adaptors:

- Studs may not be welded onto flange.
- Flange to be drilled and tapped for threaded studs where applicable.
- Drilling to suit connecting flange.

PLN 8 BOLTS, THREADED RODS, STUDS, NUTS AND WASHERS

The following specification is applicable:

- (a) The threads of all bolts, nuts and studs shall be in accordance with SANS 1700-7-3, 1700-7-5, 1700-14-3, 1700-14-4 (in part);
- (b) No brass bolt or stud shall have a diameter of less than 6mm;
- (c) Two washers shall be installed underneath each bolt and nut;
- (d) Each bolt shall protrude by at least three threads but not more than five threads through the nut with all washers in position and all bolts at a flange must be of equal length;
- (e) The Contractor shall supply to the Employer any special tool required for any nut, bolt, screw or other fastener used in a position which is not accessible using conventional tools. This also applies where the size or shape of the fastener is not conventional.
- (f) Bolts, threaded rods, studs, nuts and washers shall be hot dipped galvanised to SANS 763 or ISO 1461 and shall be coated with molybdenum disulphide lubricant after installation.
- (g) Bolts, shall comply with SANS 1700 Grade 8.8.
- (h) Stainless steel threads shall be treated with nickel base anti-seize corrosion protection compound.

Tender
Part C3: Construction

C3.4.4-25

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLN 9 THERMIT WELDING PADS

Where pipes and specials are to be jointed by means of flexible couplings and will be subjected to cathodic protection, the manufacturer shall weld steel plates not less than 50 x 75 x 10 mm thick 250 mm from each end of all pipes during the pipe manufacturing process (i.e. before lining and coating) to provide adequate area for thermit welding pad bonding cables to the piping to make it electrically continuous and enable a cathodic protection system to be applied without damage to the coating.

PLN 10 MARKING OF PIPES

All pipes and specials shall be clearly hand stamped alongside a longitudinal or spiral weld on one end of the pipe with the following.

- a) Grade and thickness of steel
- b) Serial number of the pipe or specials
- c) Outside diameter
- d) Factory hydraulic test pressure in kPa

PLN 11 UV PROTECTION OF COATINGS

All pipes with MDPE, 3LPE or Bituguard coatings shall be painted with a white polypropylene overcoat [to be approved by the Engineer] for protection against UV. The overcoat to be maintained by applying additional layers until the pipe is backfilled.

PLN 12 HANDLING, DELIVERY AND STORING OF PIPES AND SPECIALS

The contractor shall ensure that pipes and specials including coating and lining are not damaged.

Coated pipes and fittings shall be handled with the use of padded slings of width sufficient to prevent damage to the coating. Chain slings, hooks, wire ropes, rope slings without canvas covers, composition belt slings with protruding rivets and any other equipment with a possibility to damage the coating shall not be used. Slings shall be suitably rated for the loads to be handled and in good condition. Deteriorated slings shall not be used.

All pipes are to be handled with the aid of a "spreader" lifting beam. The dragging or skidding of pipes and specials in contact with the ground shall not be permitted.

Pipes shall be stacked with a minimum clearance of 100 mm between adjacent pipe walls and a minimum of 200mm clear of the ground. Pipes shall be stored on sand bags with sufficient supports to prevent permanent longitudinal deflections. Sandbags are required at least at one

Tender
Part C3: Construction

C3.4.4-26

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



third of a single pipe length from each pipe end. The sand bags shall be at least 500 mm wide for pipes with Bituguard coating.

Pipes shall also be stacked in a manner that limits loading on lower layers of pipes. Any pipe showing permanent ovality as a result of surcharge loading will be rejected.

All pipe deliveries shall be accompanied by delivery notes which will be checked by the Engineer on-site. The Engineer reserves the right to not accept and reject pipe deliveries where there are discrepancies.

Tender
Part C3: Construction

C3.4.4-27

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ: CORROSION PROTECTION OF STEEL PIPES AND FITTINGS

INDEX

| Item | Description | Page No |
|--------|---|-----------|
| PLQ 1 | SCOPE | C3.4.4-28 |
| PLQ 2 | CORROSION PROTECTION SYSTEMS | C3.4.4-28 |
| PLQ 3 | SURFACE PREPARATION..... | C3.4.4-34 |
| PLQ 4 | HOT-DIP GALVANIZING..... | C3.4.4-36 |
| PLQ 5 | EPOXY PAINTS..... | C3.4.4-36 |
| PLQ 6 | UV-RESISTANT MULTI-PURPOSE EPOXY PAINT | C3.4.4-39 |
| PLQ 7 | RE-COATABLE POLYURETHANE | C3.4.4-39 |
| PLQ 8 | FUSION BONDED, MEDIUM DENSITY, POLYETHYLENE COATINGS (FBMDPE)..... | C3.4.4-39 |
| PLQ 9 | POLYMER MODIFIED BITUMEN (BITUGUARD) | C3.4.4-40 |
| PLQ 10 | THREE LAYER POLYETHYLENE COATING (3LPE)..... | C3.4.4-49 |
| PLQ 11 | RIGID POLYURETHANE COATING (RPU)..... | C3.4.4-52 |
| PLQ 12 | PETROLATUM TAPE WRAPPING SYSTEM..... | C3.4.4-60 |
| PLQ 13 | JOINT COATING SYSTEMS..... | C3.4.4-61 |
| PLQ 14 | CUT BACK AT PIPE ENDS | C3.4.4-66 |
| PLQ 15 | UV PROTECTION..... | C3.4.4-66 |
| PLQ 16 | ADDITIONAL EXTERNAL PROTECTION FOR PIPES CAST INTO CHAMBER WALLS | C3.4.4-66 |
| PLQ 17 | JOINT BETWEEN EPOXY LINING AND CEMENT MORTAR LINING..... | C3.4.4-67 |
| PLQ 18 | MEASUREMENT AND PAYMENT..... | C3.4.4-67 |

Tender
Part C3: Construction

C3.4.4-28

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 1 SCOPE

This specification covers various corrosion protection systems for cast iron, steel and stainless steel pipes and fittings for the conveyance of water at ambient temperatures.

PLQ 2 CORROSION PROTECTION SYSTEMS

PLQ 2.1 Standards and codes

The following standards and codes form part of this specification. Unless otherwise specified herein, the latest edition shall apply.

ASTM–American Society for Testing and Materials

| | |
|------------|--|
| ASTM D2240 | Standard test method for rubber property (Durometer Hardness) |
| ASTM D4541 | Standard test method for pull-off strength of coatings using portable adhesion testers |
| ASTM G14 | Standard test method for impact resistance of pipeline coatings (falling weight test) |
| ASTM D4285 | Standard test method for indicating oil or water in compressed air |
| ASTM G62 | Standard test methods for holiday detection in pipeline coatings |

BS EN–British Standard European Norm

| | |
|-------------|--|
| BS EN 10289 | Steel tubes and fittings for onshore and offshore pipelines. External liquid applied epoxy and epoxy-modified coatings |
| BS EN 10290 | Steel tubes and fittings for onshore and offshore pipelines - External liquid applied polyurethane and polyurethane-modified coatings |
| BS EN 12068 | Cathodic protection - External organic coatings for the corrosion protection of buried or immersed steel pipelines used in conjunction with cathodic protection - Tapes and shrinkable materials |
| BS EN 13000 | Steel tubes and fittings for onshore and offshore pipelines. Bitumen hot applied materials for external coating |

ISO–International Organization for Standardization

| | |
|----------|--|
| ISO 1514 | Paints and varnishes – Standard panels for testing |
| ISO 2808 | Paints and varnishes – Determination of film thickness |
| ISO 4624 | Paints and varnishes – Pull off test for adhesion |

Tender
Part C3: Construction

C3.4.4-29

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| | |
|-------------------|--|
| ISO 8501-1 | Preparation of steel substrates before application of paints and related products - Visual assessment of surface cleanliness - Part 1: Rust grades and preparation grades of uncoated steel substrates and of steel substrates after overall removal of previous coatings |
| ISO 8502 | Preparation of steel substrates before application of paints and related products - Tests for the assessment of surface cleanliness |
| ISO 8503 | Preparation of steel substrates before application of paints and related products - Surface roughness characteristics of blast-cleaned steel substrates Part 1: Specifications and definitions for ISO surface profile comparators for the assessment of abrasive blast-cleaned surfaces. Part 2: Method of grading of surface profile of abrasive blast-cleaned steel-comparator procedure. Part 4: Method for the calibration of ISO surface profile comparators and for the determination of surface profile - stylus instrument procedure. Part 5: Replica tape method for the determination of surface profile. |
| ISO 8504-2 | Preparation of steel substrates before application of paints and related products - Surface preparation methods - part 2: Abrasive blast cleaning |
| ISO 11124-1 | Preparation of steel substrates before application of paints and related products - Specifications for metallic blast cleaning abrasives - Part 1: General introduction and classification Part 2: Chilled iron grit Part 3: High-carbon cast-steel shot and grit Part 4: Low-carbon cast-steel shot |
| ISO 12944-4: 2017 | Paints and varnishes — Corrosion protection of steel structures by protective paint systems - part 4: Types of surface and surface preparation |
| ISO 12944-5: 2018 | Paints and varnishes — Corrosion protection of steel structures by protective paint systems - part 5: Protective paint systems |

NACE - National Association of Corrosion Engineers

| | |
|-------------|--|
| NACE RP0274 | High-Voltage electrical inspection of pipeline coatings prior to installation |
| NACE RP0287 | Field measurement of surface profile of abrasive blast cleaned steel surfaces using a replica tape |

Tender
Part C3: Construction

C3.4.4-30

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| | |
|-------------|--|
| NACE SP0394 | Application, performance, and quality control of. plant-applied, fusion-bonded epoxy external pipe |
|-------------|--|

SSPC–Steel Structures Painting Council

| | |
|------------|---|
| SSPC PA 2 | Measurement of dry coating thickness with magnetic gauges (Steel Structures Painting Manual, Ch 5 - Paint Application Specs.) |
| SSPC SP1 | Solvent cleaning |
| SSPC SP11 | Power tool cleaning to bare metal |
| SSPC SP 15 | Commercial Power Tool Cleaning. |
| SSPC SP 16 | Brush-Off Blast Cleaning of Coated and Uncoated Galvanized Steel, Stainless Steels, and Non-Ferrous Metals |

South African Bureau of Standards

| | |
|----------------|---|
| SANS 241 | Specifications for drinking water |
| SANS 1160:2011 | Drinking water system components - Health effects |
| SANS 1217 | Internal and external organic coating protection for buried steel pipelines |

PLQ 2.2 Standard corrosion protection systems

The following corrosion protection systems shall apply unless otherwise specified in the project specific specifications/employer's requirements or in the bill of quantities or on the drawings.

PLQ 2.2.1 Buried steel pipework

All specials, fittings and couplings shall be lined and coated with epoxy paint. After installation the specials, fittings and couplings shall be protected with a tape wrapping system in accordance with ISO 21809-3:2016/A1:2020. The following alternative systems are applicable:

- Type 10 – hot applied bituminous tapes, minimum 5mm thickness (e.g. Densotherm HD).
- Type 11A – Petrolatum tapes, with mastic filler and external bondbreaker (e.g. Denso Petrolatum).
- Type 12A – Polymeric tapes, with pressure sensitive adhesive, minimum thickness 300µm (e.g. Denso MDP 032).
- Type 12A – Polymeric tapes, with polymer modified bitumen mastic adhesive, minimum thickness 1000µm (e.g. Denso Ultraflex or CPT).
- Type 13A – Reinforced viscoelastic tape with integral or applied polymeric outerwrap, minimum thickness 1300µm (e.g. Stopaq Wrappingband CZH)

Tender
Part C3: Construction

C3.4.4-31

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The type, combination and application of the tape wrapping system shall be as detailed in the project specific specifications/employer's requirements or in the bill of quantities or on the drawings.

Standard pipe lengths shall be lined with epoxy paint and coated with fusion bonded medium density polyethylene (FBMDPE), Polymer Modified Bitumen, 3LPE or Rigid Polyurethane as specified below in this specification, unless otherwise specified in the project specific specifications/employer's requirements or in the bill of quantities or on the drawings.

Where the application of epoxy lining and the testing thereof is not feasible for a specific pipe or special or fitting of small diameter, the Contractor shall notify the Engineer and request the approval of the Engineer for hot-dipped galvanized lining and coating of the particular pipe or special or fitting as specified below in this specification.

PLQ 2.2.2 Pipework inside chambers

a) New pipework:

Fittings, specials and couplings shall be coated and lined with epoxy paint.

Where the application of epoxy lining and the testing thereof is not feasible for a specific pipe or special or fitting of small diameter, the Contractor shall notify the Engineer and request the approval of the Engineer for hot-dipped galvanized lining and coating of the particular pipe or special or fitting as specified below in this specification.

The outside end of the fitting cast into the wall as well as flanges and couplings outside the chamber shall be protected with a Denso Clingwrap protection system.

After installation and where specified in project specific specifications/employer's requirements or in the bill of quantities or on the drawings, the pipe shall be painted with re-coatable polyurethane to the Employer's colour coding specification. All systems to comply with ISO 12944-4 and 12944-5 (Table C.4 System C4.07).

b) Deteriorated aged external coatings shall be repaired as follows:

i) General

The area to be repaired shall be demarcated to the extremity of sound coating which shall retain a firm edge during surface preparation. If the apparently sound coating does not display a firm edge during surface preparation, the repair shall be extended until a firm edge is obtained.

Tender
Part C3: Construction

C3.4.4-32

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The sound coating adjacent to the repair area shall be feathered and roughened using abrasive paper only for a distance of 50mm from the edge of the exposed steel.

Surface preparation shall be undertaken by means of one of the following techniques:

- Abrasive blast cleaning of steel surface to Sa 2 ½ of ISO 8501-1 using portable vacuum recovery blasting equipment.
- Mechanical cleaning of steel surface using Bristle Blaster™, abrasive flapper disc or power sander to SSPC SP15. Grinding discs may not be used.

The prepared steel surface shall be free of moisture, dust & debris prior to application of the repair coating.

Dust and debris shall not exceed 0,2% when tested in accordance with SANS 8502-3:2008.

Total soluble salts shall be in accordance with the requirements of the specific coating supplier when tested in accordance with SANS 8502-6 (Bresle Patch).

The feathered edge of the sound epoxy shall be activated using MEK or the solvent compatible with the repair coating.

ii) Aged epoxy coated pipework

The repair material shall be aluminium flake pigmented surface tolerant epoxy mastic (e.g. Carbomastic 15) or similar approved by the Engineer plus re-coatable polyurethane to the Employer's colour coding specification.

The repair coating shall be applied in multiple coats to match the dry film thickness of the original coating. (minimum 300 micron).

The painted area shall be tested for pinholes and thickness.

iii) Aged bitumen coated pipework

The repair material shall be Polymer Modified Bitumen heat applied wrapping (Densotherm HD) or similar approved by the Engineer.

PLQ 2.2.3 Pipework exposed to sunlight

- a) Pipe diameter up to 150mm

Tender
Part C3: Construction

C3.4.4-33

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Pipework shall be hot-dipped galvanized.

Pipe surface shall be prepared for coating application as per ISO 12944-4.

Atmospheric exposure (Inland) ISO 12944-5: 2018 Table D.1 System G3.02:

Galvanised pipes shall be coated in the factory with epoxy primer (80 micron).

Erection damage must be repaired with “single pack zinc rich epoxy primer” followed by a full coat of silver polyurethane acrylic (50 micron)

Atmospheric Exposure (Coastal) ISO 12944-5:2018 Table D.1 System G5.05:

Galvanised pipes shall be coated in the factory with epoxy primer (80 micron) plus epoxy intermediate (125 micron per coat).

Erection damage must be repaired with “single pack zinc rich epoxy primer” and epoxy intermediate, followed by a full coat of silver polyurethane acrylic (50 micron)

After installation the pipe shall be painted with re-coatable silver polyurethane acrylic (50 micron) as per ISO 12944-5

- b) Pipe diameter larger than 150mm

Pipework shall be lined with epoxy paint.

Atmospheric exposure (Inland) ISO 12944-5: 2018 Table C.3 System C3.06:

Pipes shall be coated in the factory with two component inorganic zinc silicate primer (75 micron) plus one coat of silver polyurethane acrylic (50 micron).

A second coat of silver polyurethane acrylic (50 micron) must be applied on site. The inorganic zinc silicate must be repaired with “single pack zinc rich epoxy primer”.

Atmospheric Exposure (Coastal) ISO 12944-5:2018 Table C.5 System C5.08:

Pipes shall be coated in the factory with two component inorganic zinc silicate primer (75 micron) plus two coats of epoxy intermediate (125 micron per coat).

Erection damage must be repaired with “single pack zinc rich epoxy primer” and epoxy intermediate, followed by a full coat of silver polyurethane acrylic (50 micron)

PLQ 2.2.4 Exposed pipework inside buildings


- a) Pipe diameter up to 150mm

Pipework shall be hot-dipped galvanized.


Tender
Part C3: Construction

C3.4.4-34


C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2

Pipe surface shall be prepared for re-coatable polyurethane site application.

After installation the pipe shall be painted with re-coatable polyurethane to the Employers colour coding specification. All systems to comply with ISO 12944-4 and 12944-5:2018 (Table D.1 System G2.01)

- b) Pipe with diameter larger than 150mm

Pipes, fittings and couplings shall be lined and coated with epoxy paints.

After installation the pipework external shall be painted with re-coatable polyurethane to the Employers colour coding specification. All systems to comply with ISO 12944-4 and 12944-5:2018 (Table C.2 System C2.05).

PLQ 2.2.5 Pipework inside water retaining structures

All pipework (including stainless steel) inside water retaining structures and cast into the walls or floor of water retaining structures shall be lined and coated with epoxy paint.

All stainless steel shall be grade 316L.

PLQ 3 SURFACE PREPARATION

Contractors must submit information on the cleaning methods to be used to comply with the specified requirements.

PLQ 3.1 Surface preparation of steel surfaces

All projections, sharp edges, layers that have formed and tool marks must be removed from the surface so that the surface is smooth, and it must be abrasive blast cleaned in accordance with section 5.3 of SANS 10064:2011 so that it meets the following requirements:

- (a) A grade of cleanliness of Sa 3 of ISO 8501-1 for immersion/buried conditions or Sa 2 ½ of ISO 8501-1 for atmospheric exposure.
- (b) A surface profile between 60 micron and 85 micron when tested in accordance with SANS 5772.
- (c) Dust and debris shall not exceed 0,2% when tested in accordance with SANS 8502-3:2008.
- (d) The profile produced shall be angular and shall be in accordance with the requirements of the material product data sheet when tested in accordance with SANS 5772 (profile gauge) or SANS 8503-5 (replica tape)

Tender
Part C3: Construction

C3.4.4-35

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- (e) Water soluble salts shall not exceed 100mg/m² when tested in accordance with the Weber Reilly Method or conductivity measurement. Lower values may be required for immersion applications.
- (f) Any laminations revealed by blast cleaning shall be ground out and re-blast cleaned to meet the requirements above.

PLQ 3.2 Surface preparation of galvanized surfaces

Surfaces to be coated shall not be passivated.

Galvanized steel surfaces shall be degreased prior to coating, using either a water soluble solvent degreaser in accordance with SANS 1344 and the manufacturer's instructions, or a mild acid-detergent degreasing solution to be approved by the Engineer.

Large areas shall be prepared by sweep-blasting with non-metallic abrasive in accordance with SSPC SP16. Cracking, flaking or any form of de-lamination of the zinc coating due to excessive blast-cleaning shall not be permitted. Removal of zinc by blast-cleaning shall not exceed 10 µm.

Surfaces that cannot be sweep-blasted shall be abraded manually or mechanically with abrasive paper grade 220 or by using non-metallic abrasive pads.

Finally, all dust and debris shall be removed by vacuum-cleaning.

Epoxy primer for galvanised surfaces shall be applied immediately after surface preparation to a minimum dry thickness of 50 µm.

PLQ 3.3 Surface preparation of stainless steel surfaces

Oil and grease contamination shall be removed by:

- Steam-cleaning
- An emulsifiable or aqueous detergent, or
- An alkaline cleaning solution.

Stainless steel surfaces shall be blast-cleaned with stainless steel grit or non-metallic abrasive. The use of steel shot and steel or cast iron grit is strictly prohibited.

The grade of cleanliness shall be in accordance with SSPC SP16.

Surface profile shall be in the range of 30 to 50 µm.

Tender
Part C3: Construction

C3.4.4-36

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Where blasting is impractical, the surface shall be roughened manually with abrasive paper grade 220, disc grinders or flapper wheel abrasive pads. In all instances, clean, uncontaminated equipment must be used.

Dust and debris shall be removed by vacuum-cleaning.

PLQ 4 HOT-DIP GALVANIZING

The following specification is applicable:

- (a) Where galvanising is specified or a requirement of the design, such galvanising shall be performed by the hot-dip process to SANS EN 10240 in part and SANS ISO 1461;
- (b) For all parts, other than wires, the equivalent zinc coating thickness shall not be less than 455 g of zinc per square metre of surface;
- (c) The galvanising must be clean, smooth, of uniform thickness, unblemished and free from defects;
- (d) All drilling, welding, cutting, sawing, punching, filing and bending shall be complete and the metal shall be cleaned of any machining blemishes, millscale, rust and lubricants, before galvanising;
- (e) Galvanised areas must be kept free of lubricants. Surfaces which are in contact with oil shall not be galvanised or cadmium plated;
- (f) Electrolytic deposition of zinc is not acceptable.
- (g) Unless otherwise specified, steel pipes up to 150 mm dia shall be hot-dipped galvanized. Hot-dip galvanizing to be in accordance with SANS 121 ISO 1461 except that minimum thickness shall be 55 micron. Cut ends and small damaged areas shall be repaired by the application of a zinc-rich epoxy (single pack) to SANS 121 ISO 1461 (ZINC GALV 1 – Dulux or POLY GALV – Plascon).
- (h) Only heavy duty galvanising shall be accepted and all items to be provided with a SANS approval certificate.

PLQ 5 EPOXY PAINTS

PLQ 5.1 General

Epoxy paint shall comply with SANS 1217 or ISO 12944-4 and ISO 12944-5. Surface preparation shall be abrasive blast cleaning to Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals for internal linings/immersion conditions, or Sa 2½ of ISO 8501-1 or SSPC SP16 for non-ferrous metals for atmospheric exposure.

The following will be applicable where epoxy paint is specified:

Tender
Part C3: Construction

C3.4.4-37

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- Lining of pipes with nominal diameter equal or larger than 600 mm and standard pipe lengths of 9,144 m, 12,192 m, 18,3 m and 19.2 m:

Solvent free epoxy SANS 241 certified (Pipecoat SFX or similar product approved by Engineer), with a minimum dry film thickness of 500 micron and a maximum dry film thickness of 800 micron. (Equivalent to ISO 12944-5:2018, Table C.6 System I.06)

- Lining and coating of all other pipes, specials and fittings, except where multi-purpose epoxy coating is specified:

Solvent borne epoxy (Carboguard 891 or similar product approved by Engineer) with a minimum dry film thickness of 500 micron and a maximum dry film thickness of 800 micron. (Equivalent to ISO 12944-5:2018, Table C.6 System I.06)

Epoxy paint and the repair kit for the repair of epoxy shall be from the same manufacturer.

Edges with epoxy paint shall have a radius of 3 mm or 50 % of the pipe wall thickness (smaller of two).

Where another type of coating is specified, epoxy paint lining shall continue around pipe edge for each of the following:

- *Flanged end*

Onto both flange faces, extending for 50 mm (min) onto pipe outer wall beyond flange.

- *Ends suitable for straight or stepped couplings or flange adapters*

Onto pipe outer wall for 250 mm (min) from pipe end.

- *Ends suitable for flange adapters, incorporating a restraining flange*

Onto pipe outer wall from pipe end, up to and including both faces of the restraining flange as well as 50 mm (min) beyond the restraining flange.

The following specification shall be applicable to pipes, specials and fittings to be welded on site:

- In the factory:

Abrasive blast cleaning of complete steel surface to Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals. Apply epoxy paint to 100mm from pipe end.

Tender
Part C3: Construction

C3.4.4-38

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- On site:

Abrasive blast cleaning of steel surface to Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals and 50 mm of painted surface to a surface profile of 60 – 85 microns.

Apply epoxy repair kit from the same manufacturer as the factory applied epoxy to a minimum dry film thickness of 500 micron. The type of epoxy repair kit shall be subject to the approval of the Engineer.

At completion of the laying of pipes, after the epoxy lining of welded joints, repair of lining defects and cleaning of pipes and before filling of the pipe with water, the Contractor shall be responsible for the holiday (pinhole) testing of the epoxy lining of the complete pipeline. The Contractor shall implement measures to prevent entrance by persons, animals, water or any other foreign matter into the sections where holiday testing was successfully completed.

Holiday testing shall be undertaken in accordance with ASTM D5162 Test method B: High Voltage Spark Testing.

PLQ 5.2 Repair/rehabilitation of aged internal epoxy linings on site

The following deviations from paragraph PLQ 5.1 shall be applicable to the repair/rehabilitation of aged internal epoxy linings of steel pipes, specials and fittings on site:

The repair material shall be a surface tolerant reinforced epoxy with minimum 90% volume solids. A certain level of solvent is preferred in order to enhance the wettability, flow and adhesion characteristics of the material. The following materials are approved for this application:

- Carboguard 891GF Glass Flake System from Stoncor
- Ceramic Epoxy from Spec Coats
- Zip E from Corrocoat

Glass flake pigmented epoxy coatings from other manufacturers may be considered subject to approval by the Engineer.


Alternative products (e.g. Pipecoat SFX or Carboguard 550) may be considered for special cases of large scale repair work under controlled climatic conditions and with special measures for quality assurance in place and subject to approval by the Engineer. These alternative products shall be subjected to site application trials.

The area to be repaired shall be demarcated to the extremity of the sound epoxy coating which shall retain a firm edge during surface preparation. If the apparently sound epoxy does not display a firm edge during surface preparation, the repair shall be extended until a firm edge is obtained.


Tender
Part C3: Construction

C3.4.4-39


C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2

The sound epoxy adjacent to the repair area shall be feathered and roughened using abrasive paper only for a distance of 50mm from the edge of the exposed steel.

Surface preparation shall be undertaken by means of one of the following techniques:

- Abrasive blast cleaning of steel surface to Sa 2½ of ISO 8501-1 using portable vacuum recovery blasting equipment.
- Mechanical cleaning of steel surface using Bristle Blaster™, abrasive flapper disc or power sander to SSPC SP15. Grinding discs shall **not** be used.

The prepared steel surface shall be free of moisture, dust & debris prior to application of the repair coating.

Dust and debris shall not exceed 0,2% when tested in accordance with SANS 8502-3:2008.

Total soluble salts shall be in accordance with the requirements of the specific coating supplier when tested in accordance with SANS 8502-6 (Bresle Patch).

The feathered edge of the sound epoxy shall be activated using MEK (Carboline Surface Prep 1 or similar approved by the Engineer) or the solvent compatible with the repair coating.

The epoxy repair coating shall be applied by brush ensuring the paint is worked into the surface of both the exposed steel and the feathered edge of the sound epoxy, overlapping 50mm onto the sound coating.

The repair coating shall be applied in a single coat to a minimum dry film thickness of 600 micron.

The painted area shall be tested for pinholes and thickness.

PLQ 6 UV-RESISTANT MULTI-PURPOSE EPOXY PAINT

Multi-purpose Epoxy shall be surface tolerant, self-priming aluminium pigmented epoxy mastic.

PLQ 7 RE-COATABLE POLYURETHANE

The area to be over-coated shall be abraded with abrasive paper grade 220 to a uniform matt finish.

The surface shall be vacuum-cleaned to remove dust and debris.

Over-coat with a 40 µm minimum layer of re-coatable polyurethane in accordance with the Employer's colour code.

Tender
Part C3: Construction

C3.4.4-40

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 8 FUSION BONDED, MEDIUM DENSITY, POLYETHYLENE COATINGS (FBMDPE)

A uniform FBMDPE coating must be obtained by dipping the already prepared and heated pipe into a fluidified bed of FBMDPE powder which then fuses directly on to the heated surface.

The pipe coating shall be Sintakote II complying with all aspects of AS 1193, AS 4131 and AS 4321 of the latest revisions.

All coating materials shall be supplied complete with an original ISO 17050-1 Certificates of Conformity (COC) for the materials, clearly indicating compliance with all mechanical, physical and chemical properties of the coating, as defined in AS 4321, AS 1193 and AS 4131.

The supplier shall ensure that testing takes place as per AS 4321 Appendix A, as defined in Table A1 for the pipeline coating at the mill. In addition to this, a detailed third party report indicating compliance as per the 5 Yearly Type Testing and the annual testing as per Table A1 shall be submitted to the Engineer before production commences.

The minimum Dry Film Thickness (DFT) shall be 2.3mm minimum or as per Table 1 of AS 4321 for the different pipeline diameters as agreed by the Engineer.

The pipeline frequency of testing during production shall be as per AS 4321 Table 2.

The surface profile shall be angular and at least 60 μ -75 μ and the dust and debris level shall never exceed Class 2 ISO 8502-3 during production, the latter shall be confirmed during production on every 5th pipe and records shall form part of the hand-over pack issued to the Engineer. The cutback distance of the coating shall be 75mm from the pipe end.

PLQ 9 POLYMER MODIFIED BITUMEN (BITUGUARD)

This specification relates to factory applied pipe coating operations based on hot applied polymer modified bitumen. It is also applicable to modification, refurbishment and repairs on pipes coated with standard (oxidised or blown) bitumen fiberglass coatings.

PLQ 9.1 Applicable Standards

This part of the Specification makes reference to the standards listed below. Unless otherwise specified the latest editions of these documents, including all addenda and revisions, shall apply.

British Standards

| | |
|---------|--|
| BS 410 | Specification for test sieves. |
| BS 1796 | Methods using test sieves of woven wire cloth and perforated metal |

Tender
Part C3: Construction

C3.4.4-41

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| | |
|--------------------------|--|
| | plate. |
| BS 2000 | Methods of test for petroleum and its products. |
| BS 3900 | Methods of test for paints: Part A 6 (replaced by EN 535) – Determination of flow time of paints. Part B 2 (replaced by ISO/DR 1515) – Determination of volatile matter and non-volatile matter. |
| BS 4147 | Bitumen-based hot-applied coating materials for protecting iron and steel, including suitable primers where required. |
| BS 7079 | (Replaced by ISO 8501-8504) – Preparation of steel substrates before application of paints and related products. |
| BS EN 10300 | Steel tubes and fittings for onshore and offshore pipelines – Bituminous hot applied materials for external coating. |
| Swedish Standard | |
| SIS OS 5900 | Pictorial surface preparation standards for painting steel surfaces. |
| American Standard | |
| ASTM D 113-86 | Ductility of bituminous materials. |
| ANSII AWWA C203-91 | Coal-tar Protective Coatings and linings for steel water pipelines – enamel and tape-hot applied. |

PLQ 9.2 Materials

PLQ 9.2.1 Primer

The primer shall be of synthetic composition, designed to be used with a specific polymer modified bitumen. The drying rate of the primer shall be suited to the application conditions. The primer shall be supplied in new sealed steel drums.

The primer shall have the characteristics shown in the table below. In addition, when stored in original sealed containers at ambient temperature, the primer shall retain the properties as set out in the table for not less than 6 months from the date of delivery.

CHARACTERISTICS OF PRIMER

| CHARACTERISTIC | REQUIREMENTS | METHOD OF TEST |
|--|---------------|---|
| Viscosity at 23°C | 35-60 seconds | Flow cup No 4 |
| Volatile matter (max. % loss by mass) | 75 | BS3900: Part A6 = EN 535 BS3900: Part B2 = ISO/DR 1515 (105°C for 3 hours) |

Tender
Part C3: Construction

C3.4.4-42

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 9.2.2 Polymer Modified Bitumen

a) Composition

The polymer modified bitumen shall consist of a uniform mixture of the following:

- A formulated blend of polymer modified bitumen, as specified in (c) and (d) below.
- A proportion of approved filler (limestone or asbestos shall not be used).
- Characteristics of the filler shall be as specified in (b) below.

b) Filler Grading

Method of test to BS 1796 modified to use the metric sieves specified in BS 410.

Passing 90 microns – not less than 93%.

Passing 250 microns – not less than 99%.

c) Characteristics of the Polymer Modified Bitumen

The material shall conform to the requirements given in the table below when tested in accordance with the methods specified.

d) Performance Tests of the Polymer Modified Bitumen System

The polymer modified bitumen shall be of thermoplastic rubber/bitumen modification.

The polymer modified bitumen containing mineral filler shall pass the performance test specified in the following table:

CHARACTERISTICS AND PERFORMANCE TEST: PMB

| PROPERTIES | METHOD | UNIT | REQUIREMENTS |
|------------------------|------------|-------------------|--------------|
| Softening Point | ASTM D36 | °C | 115-130 |
| Penetration @ 25°C | ASTM D5 | 1/10 mm | 15-30 |
| Density @ 25°C | BS 4147 | g/cm ³ | 1.1-1.4 |
| Viscosity @ 170°C | Brookfield | Cp | 7000-12000 |
| Viscosity @ 190°C | Brookfield | Cp | 3000-6000 |
| Filler Content | BS 4147 | % | 20-30 |
| Impact @ -10°C | BS 4147 | mm ² | Max. 6500 |
| Peel Initial / Delayed | BS 4147 | mm | Max: |
| Sag @ 25°C | BS 4147 | mm | 3,0/3,0 |
| Sag @ 40°C | BS 4147 | mm | 3,0/3,0 |
| Sag @ 50°C | BS 4147 | mm | 3,0/3,0 |
| Sag @ 60°C | BS 4147 | mm | 3,0/3,0 |
| Sag @ 80°C | BS 4147 | mm | Max. 1.5 |
| Aging Test @ 190°C | Phoenix | hours | Min. 72 |
| Bend | BS 4147 | mm | Min. 15 |

Tender
Part C3: Construction

C3.4.4-43

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Notes:

The test plates shall be cleaned by abrasive blasting to grade Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals and with a profile of 50 – 75 microns (SANS Method 772). They shall be coated with primer at a rate of 100g per m².

- For the impact test a plate 12.7 mm thick shall be used and a single impact made in each quarter of the plate. The average of the four areas disbonded shall not exceed the permitted value shown in the table.
- The peel test at 25°C is equivalent to / replaces the preliminary adhesion test in the original Specification.

PLQ 9.2.3 Outerwrap

- The outerwrap consists of a combination of polyester and glass fibres to ensure the required strength and elasticity. This is combined with a glass fabric of uniform quality and amount to control the best application and the required amount of bleed through, in order for the outerwrap to provide maximum protection.
- The outerwrap shall be impregnated with the polymer modified bitumen compatible material to fulfil the characteristics shown in the table below.
- The characteristics of the outerwrap shall comply with the requirements of the table below and shall be determined in accordance with the test procedure.

CHARACTERISTICS OF OUTERWRAP SATURANT

| CHARACTERISTIC | REQUIREMENT | METHOD OF TEST |
|--------------------|--------------------------|----------------|
| Softening Point | Min 100°C | BS 2000 |
| Penetration @ 25°C | 60-85 1/10 mm | BS 2000 |
| Saturant | Polymer Modified Bitumen | |

PHYSICAL CHARACTERISTICS OF OUTERWRAP

| CHARACTERISTIC | TYPE A | TYPE B | METHOD OF TEST |
|-------------------------------|-----------|-----------|----------------|
| Minimum Thickness (mm) | 0.6 | 0.6 | AWWA C203-91 |
| Weight (g) per m ² | 500 – 700 | 500 – 700 | AWWA C203-91 |
| Tensile strength (N/50 mm) | | | |
| Longitudinal | > 800 | > 400 | AWWA C203-91 |
| Transverse | > 800 | > 200 | AWWA C203-91 |

Tender
Part C3: Construction

C3.4.4-44

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 9.3 Application

PLQ 9.3.1 Care of Wrapping Materials

All wrapping materials consigned to the coating yard or factory shall be properly stored to prevent damage or deterioration.

PLQ 9.3.2 Care of Pipe

Throughout the wrapping process pipe and coating materials shall be kept clean and away from all foreign matter.

PLQ 9.3.3 Marking

Any pipe manufacturer's identifying marks shall be removed before the start of the wrapping process and shall be permanently marked on the side of each pipe at both ends with a weatherproof paint. Metallic dye stamping shall only be permitted using approved stamps and only on the pipe bevel.

PLQ 9.3.4 Blast Cleaning

In preparation for the application of primer all grease or heavy soil shall be removed without spreading over the surface with a volatile solvent, e.g. xylene (or approved equivalent) and thereafter the external surface of the pipes shall be cleaned by abrasive blasting to Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals and surface profile amplitude 75 µm. Refer to 37.15 for detailed description of surface preparation process.

PLQ 9.3.5 Priming

- a) Following blast cleaning and within 2 hours, the pipe exterior shall be coated with the primer applied at a controlled rate to the manufacturer's recommendations. Pipes shall be coated within 24 hours of being primed.
- b) The primer shall be applied to a dry, clean and dust free pipe and thereafter the primed pipe shall be kept free from moisture, dust or any other contaminant. The primed pipe shall be uniform and free from runs, drips, flooded or bare areas. Particular care shall be taken to ensure complete coverage of weld areas.
- c) The primer should be applied at a pipe temperature of 10°C (or above) or 3°C above the dew point. If the pipe temperature is lower than this level or if moisture is present on the pipe, heating of the pipe may be required.
- d) Deteriorated or contaminated primer shall not be applied to the pipe. Primer that has deteriorated or become contaminated after its application shall be removed to the

Tender
Part C3: Construction

C3.4.4-45

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

satisfaction of the Employer or his representative, at the Contractor's expense. The cleaned area shall then be re-primed.

PLQ 9.3.6 External Coating and Wrapping Application

- a) The pipe, after priming and when the primer is no longer tacky, shall be passed through coating facilities of a type approved by the Engineer. The machine shall coat the pipe weld (longitudinal or spiral) with a 50 mm wide strip of extruded polymer modified bitumen and thereafter the entire pipe with an extruded coating of polymer modified bitumen and shall simultaneously apply the outerwrap.
- b) All primed surfaces shall be clean and dust free immediately prior to coating.
- c) The coating (including the outerwrap) shall have a minimum average thickness as specified in SANS ISO 2808 (5.5 mm minimum average and 5 mm minimum at any point) The coating shall be reinforced by a spirally-wound layer of outerwrap pulled into the polymer modified bitumen with an overlap of 20 mm, such that the outerwrap is wetted by the polymer modified bitumen. Particular attention shall be paid to the location of the reinforcement and thickness of the wrapping over the weld. The average thickness shall be determined in the following manner: At least four thickness measurements at approximately the pipe quarter points per lineal metre of pipe length shall be taken. At least 25% of the measurements shall be taken at the weld bead. The average thickness shall be the arithmetic average of all measurements.
- d) The completed coating shall be well bonded to the pipe metal; uniform, smooth and free from Holidays, laminations, voids or other defects.
- e) The wrapping shall be carefully trimmed off 100 mm from the ends of each pipe and bevelled throughout its thickness over a minimum length of ± 5 mm, unless otherwise specified by the Employer or his representative.
- f) Solar protection paint shall be applied to the coated pipe while the coating is still warm. It shall be white in colour, water resistant, continuous and shall cover the wrapping sufficiently to form an effective barrier to solar radiation. The solar protection shall be terminated approximately 100 mm from each end of the wrapping (i.e. 200 mm from each end of the pipe).

PLQ 9.4 Inspection and Testing


The Contractor shall be responsible for and shall bear the cost of a system of inspection and repair of the wrapped pipe approved by the Engineer. The system shall meet all relevant requirements in this Section and in addition the following requirements:

- a) Monitoring of grit size and the finish of blast cleaned pipe.
- b) Viscosity measurement and control of film thickness of external primer at least once for every batch of primer, in addition to visual checks of the applied prime coating.


Tender
Part C3: Construction

C3.4.4-46

C3.4.4
Particular Specifications for Civil Works



Contractor



Witness 1




Witness 2



Employer



Witness 1



Witness 2

- c) Adequate temperature control of the polymer modified bitumen at the application head. In order to ensure that the polymer modified bitumen applied to the pipe has the characteristics specified, samples of the polymer modified bitumen shall then be taken from the application head and subjected to the following test and frequency of testing shown in the table below.
- d) Visual checks on the outer wrap and the appearance of the final wrap.
- e) Holiday detection of 100% of the surface area of every wrapped pipe with approved equipment operating at a minimum 15 kV, maximum 25 kV with regular calibration of the equipment to the satisfaction of Quality Assurance.
- f) Test of bond strength and thickness of the wrapping including removal of samples of the wrapping for inspection.
- g) Adequate and proper repair of any defects to ensure compliance with this Section. A need to repair more than 1 defect per m² of pipe coating shall be sufficient grounds to reject the pipe and cause the Contractor to adjust his process to reduce the number of defects to an acceptable level.

Any necessary repairs of tested pipes shall be carried out by the Contractor at no additional cost to the Employer.

One pipe from every day's production shall be held back for examination on the following day. This examination shall include bond testing, thickness testing and examination for laminations, voids or any other defects.

If, in the opinion of the Engineer, there are a significant number of defects on the test pipe, then a back check procedure will be invoked. This will involve checking the ten pipes immediately preceding and the ten pipes immediately following the faulty test pipe (the pipe numbers shall be available from the final inspection). These twenty pipes shall be subjected to an examination similar to that carried out on the test pipe. Should the number of defects detected be, in the opinion of the Engineer, significant, then the entire production for that week shall be quarantined and jointly investigated by the Contractor and the Engineer.

Should tests in any production batch show a defect rate of more than 10%, the Engineer may reject the whole batch. In such cases the Contractor shall conduct an investigation to establish the cause of the defects.

'IN PLANT TESTING'

| TEST | FREQUENCY OF TESTING |
|-------------------------------|----------------------------|
| 1. Softening Point | Twice per working shift |
| 2. Penetration at 25°C | Twice per working shift |
| 3. Bond test for coated pipes | One pipe per working shift |

Tender
Part C3: Construction

C3.4.4-47


C3.4.4
Particular Specifications for Civil Works



Contractor




Witness 1



Witness 2



Employer



Witness 1



Witness 2

These tests should be conducted at the coating Plant by the Contractor and monitored by the Authority (AIA), who would be trained in the procedures by the coating material supplier.

At least once during the Contract or when the method of surface preparation is changed, a sample wrapped pipe shall be tested for resistance to cathodic disbonding.

When tested, the wrapping shall not be disbonded from the pre-damaged area by more than a 5 mm radius after exposure for 28 days at the specified potential, i.e. -1500 mV (BS 3900:F1 1).

The inspection activities shall be coordinated with the Contractor's operations so as to delay or interfere with the operations as little as possible. The Contractor's methods shall, nevertheless, always permit inspection to be made and allow adequate repair of imperfections.

Prior to dispatch from his Plant, the Contractor shall ensure that the wrapped pipe is correctly marked on the internal painted surface of the pipe at each end with approved paint, with sufficient information to enable subsequent identification of the pipe to be made. Documentation shall be supplied to the Engineer to enable the history of the processing of each pipe to be traced.

PLQ 9.5 Methods of Testing

PLQ 9.5.1 Testing of Wrap Characteristics

a) General

The procedures given below are reference methods of test, which shall be used to establish conformity to the Specification in cases of dispute. Other similar methods, however, may be used by manufacturers for routine quality control purposes with the approval of the Engineer.

b) Thickness

The thickness shall be determined by means of a suitable instrument fitted with a micrometre dial gauge, a cylindrical brass block 57 mm in diameter and giving a nominal loading of 3.45kN/m² and a surface plate.

The thickness shall be measured by interposing the outer wrap between the cylinder and the surface plate. Measurements shall be made by marking 75 mm square across the effective width of the mat and making a measurement within each square. No single reading across the width of the mat shall be less than the specified minimum thickness.


c) Weight per m²

The weight per square metre shall be determined by cutting representative samples from the effective width of the outer wrap. The samples shall be of such a size, that the weight per square metre may be determined to an accuracy of $\pm 2\%$.


Tender
Part C3: Construction

C3.4.4-48


C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2

d) Tensile Strength

The tensile strength shall be measured with approved equipment. The size of the samples cut from the roll shall be 520 mm long and shall have the required width.

When mounted in the equipment, the distance between the jaws shall be 320 mm. The constant rate of separation of the jaws shall be in the range of 100 mm to 610 mm/minute and the tensile strength at breaking point shall be determined. For reference purposes the rate of separation of the jaws shall be 200 mm/minute. At least four samples shall be tested and an average figure obtained. The test may be carried out on narrower samples if required, provided that at least two of the reinforcing strands are included in the specimen. Sealing of the ends is recommended.

The value for tensile strength obtained from a narrower sample shall be extrapolated to 150 mm width.

PLQ 9.5.2 Bond Test for Coated Pipes

- a) Measure the temperature of the coating with a surface thermometer.
- b) If the temperature of the coating is not between 10°C and 25°C, cool or warm the pipe in the test area to bring the temperature within this range.
- c) Using a knife, heated if necessary, make two parallel cuts, through the coating down to the pipe surface. The cuts shall be 100 mm long and 30 mm apart.
- d) With a stiff flat blade, loosen the coating the full width between the two cuts and lift the wrap upward in a direction at right angles to the pipe surface.
- e) The bond shall be considered satisfactory if the coating does not peel cleanly from the primer or the pipe surface but is removed with difficulty.
- f) This bond test should be carried out at the start of each shift or change in production and thereafter at a frequency approved by the Engineer.

PLQ 9.6 Handling

At all times the pipe, unwrapped as well as wrapped, shall be handled with the aid of slings, lifting yokes and protected hooks to the approval of the Engineer.

At all times the coated pipe shall be handled and stacked in such a manner as to prevent damage to the coating. Particular care shall be taken immediately after coating to avoid damage while the enamel is above ambient temperature. No stacking or loading shall be undertaken until the coating has cooled sufficiently to avoid marking.

The coated pipe shall be stored at all times clear of the ground and in such a way that either water or mud cannot accumulate on the inside or outside of the pipe. Storage shall be effected by the

Tender
Part C3: Construction

C3.4.4-49

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

use of wooden bearers, suitably covered, or mounds of gravel-free sand, covered with polyethylene sheets.

The pipe shall only be stacked to a height such that no flattening of the wrapping occurs.

The pipes shall be separated from each other with approved polyethylene covered pads.

PLQ 9.7 Repairs

Although the polymer modified bitumen has excellent self-healing properties, damage caused by transportation or laying of the coated pipe may occur. This shall be quickly repaired using torch-on membrane.

Damage shall be repaired by removing the existing coating to at least 10 mm beyond the area of damage. The repair area shall then be cleaned of all deleterious matter to 100 mm beyond the proposed repair area. Exposed metal shall be re-primed in accordance with this Section. The repair patch, which shall lap at least 50 mm onto sound coating, shall be applied by gently heating with a gas torch and applying it to the pipe in a manner, which prevents the entrapment of air bubbles. All air bubbles shall be removed using a wooden roller or by other means and the perimeter of the repair patch shall be neatly finished off. The patched area shall then be Holiday tested in accordance with the Specification.

PLQ 10 THREE LAYER POLYETHYLENE COATING (3LPE)

The 3LPE coating shall comply with ISO 21809-1. The Canadian Specification CSA Z245.20/Z245.21 is not applicable.

The materials supplied as part of the 3LPE coating, including the Fusion Bonded Epoxy (FBE), Copolymer adhesive and Polyethylene (PE) outer coating shall be supplied with ISO 10474 or EN 10204 Inspection Certificates 2.1 and 2.2, giving the results of the testing of coated pipes, as supplied on the contract/purchase order and signed by an authorised representative of the Engineer.

An Inspection and Testing Plan (ITP) providing an overview of the sequence of inspections and tests, including appropriate resources and procedures and a Quality Control Procedure (QCP) shall be submitted for the approval of the Engineer's representative prior to coating production commencing.

Subsequent to the approval of the documentation detailed above, a Procedure Qualification Trial (PQT) shall take place and shall be witnessed by the Engineer's representative as well as subsequent inspection/testing of its properties, to confirm that the Application Procedure

Tender
Part C3: Construction

C3.4.4-50

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Specification (APS) is adequate to produce a coating with the specified properties. All to be carried out prior to the start of production.

The 3LPE shall be Type B coating, as per ISO 21809-1 Table 1.

The minimum thickness of the 3LPE coating shall be as follows:

| | |
|----------|---|
| FBE | 0.30 mm |
| Adhesive | 0.20 mm |
| HDPE | 2.00 mm for nominal pipe diameter up to and including 250 mm |
| | 2.50 mm for nominal pipe diameter larger than 250 mm but less than 600 mm |
| | 3.0 mm for nominal pipe diameter 600 mm and larger |

The 3LPE shall have minimum total thickness as above, and on heavier wall pipes it shall comply with class B3, as per ISO 21809-1 Table 2.

Polyethylene layer cut back shall be provided at pipe ends as follows:

Pipe ends shall be supplied as bare steel, free of all coating, for a distance of 100 mm (+25mm/-0mm tolerance) from the pipe end. In addition, each pipe end shall be left without polyethylene / adhesive coating so that a 20 mm (+10mm/-0mm tolerance) FBE toe protrudes on the steel beyond the cutback polyethylene coating layer.

The ends of the coating shall be bevelled at 30° to 45°.

The applicator shall use epoxy material that is in accordance with Table 3, Class B, as per ISO 21809-1 and shall test the materials/ensure compliance as detailed above in accordance with ISO 10474 or EN 10204.

The applicator shall use adhesive material that is in accordance with Table 4, Class B, as per ISO 21809-1 and shall test the materials/ensure compliance as detailed above in accordance with ISO 10474 or EN 10204.

The applicator shall use PE/PP material that is in accordance with Table 5, Class B, as per ISO 21809-1 and shall test the materials/ensure compliance as detailed above in accordance with ISO 10474 or EN 10204.

The applicator shall provide batch certificates supplied by the manufacturer of each material and shall contain the information given in Table 6 ISO 21809-1. The batch certificate shall state test methods and acceptance criteria. The applicator shall identify the materials and shall confirm that

Tender
Part C3: Construction

C3.4.4-51

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

the certificates comply and relate to the specified materials, as well as the requirements stipulated in Clauses 8.3.2 and 8.3.3 ISO 21809-1.

Prior to the start of coating production and any specified PQT, the applicator shall prepare an APS as per Clause 9.2 ISO 21809-1.

The APS, including any Engineer approved written revisions, shall be approved by the Engineer prior to the start of production and any specified PQT and there shall comply with the requirements of Table 7, Class B coating system.

The APS shall be verified by a PQT in accordance with ISO 21809-1 Annexure L. The applicator shall prepare an ITP and a daily log to record quality control data in accordance with Annexure L of ISO 21809-1.

Prior to the commencement of the surface preparation for the coating operations, a visual inspection shall be performed on the bare steel pipes in order to verify that there are no steel or weld defects (welding slag, spatter or raised/sharp edges) or contamination with oil, grease, soil, dirt and similar contaminants.

In the event that steel defects are detected they shall be rectified using a file, light grinding or any other suitable tool as stipulated in API 1104 Clause 13.10. This intervention shall not reduce the pipe wall thickness below the tolerances specified in the relevant Specifications. In case the steel defect is of the nature that simple correction of this defect cannot be performed, the pipe affected by this defect shall be quarantined until the appropriate measures are taken.

In case oil, grease, or any other residues (e.g. adhesive materials or similar contaminants) are present, then they shall be removed using a high pressure water based detergent cleaner, and/or a suitable "solvent" as per the requirements of SSPC-SP-1 Specification. In the event of other "adherent" contaminant being present, then power tool brushes or any other appropriate method may be utilised in order to remove the contaminant from the pipe surface prior to grit blasting.

The blast cleaning abrasives shall be, at all times, kept dry, clean and free from contamination. The blast cleaning shall be performed when the following conditions are satisfied:

- The steel surface temperature is at least 3°C above the ambient dew point, which shall be checked using a calibrated hygrometer or other method approved by the Engineer.
- The steel surface shall have no traces of moisture;
- The steel surface is protected from bad weather conditions such as rain or strong winds which can bring contaminants such as soil, sand, dirt, salt or any other such similar contaminant.

Tender
Part C3: Construction

C3.4.4-52

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

In the case that the steel surface temperature is less than 3°C above the ambient dew point or traces of moisture are detected on the steel surface, the steel surface shall be heated using induction heating until the steel surface temperature is within the range of 50°C to 60°C. This temperature shall be maintained until all of the moisture has been removed from the steel surface.

Abrasive blast cleaning shall be in strict compliance with ISO 21809-1 Clause 10.1.2 with the exception that the profile shall be measured using ISO 8503-4 (Stylus method), replica tape is not permitted.

As per ISO 8502-3, the cleanliness of the steel surface shall be measured using the ISO Form: "Preparation of Steel Substrates before Application of Paint and Related Products – Test for the Assessment of Surface Cleanliness – Part 3: Pressure Sensitive Tape Method." As prescribed, a strip of clear tension tape shall be placed, tacky side down, onto the blasted steel surface of the pipe after cleaning. The tape shall then be removed from the surface and placed on a piece of white glossy paper where it will be compared to the cleanliness levels provided in the ISO 8502-3 specification procedure. This shall not exceed a "Debris" and "Dust" level of Class/Level 2 at any given time and shall be recorded during pipe production on at least every 5th pipe to confirm compliance and records shall be kept for the client, which may be inspected at any given time.

The salt level on the bare steel pipe surface shall be measured according to ISO 8502-2 and shall be a maximum of 20 mg NaCl/m². The basic procedure of the test shall be to dampen circular piece of test paper of known area with a specified volume of laboratory water containing less than 0.1µg/cm² of salt. The test paper shall then be applied to the pipe for a period of 2 minutes, after which the test paper will be removed from the pipe and its resistivity measured. The salt content on the pipe will then be determined through the calibrated Salt Contamination Meter which uses the negative correlation between resistivity and salt content, along with empirically measured historical data to provide a reading.

If excessive salt contamination is established (≥ 20 mg NaCl/m²) during production testing, then the applicator shall ensure that a "Pre-Wash" system shall be employed prior to coating in order to remove the salt without causing "flash rusting" or any other "surface contamination". The "pre-wash" shall be performed and shall form an integral part of the production Pre-Qualification Testing (PQT) before acceptance of the "Pre-Wash" procedure.

The maximum time elapsed after completion of the abrasive blasting operation, pre-wash (if applicable) and the application of the P primer shall be 120 minutes if RH < 85% and 60 minutes if RH > 85%. At no time shall the steel surface temperature be allowed to drop below the dew point before application of the P Primer. Should either of these conditions apply, the surface preparation shall be re-inspected and/or the surface preparation repeated as required.

The application of the 3LPE coating shall be in accordance with the approved APS in accordance with Clauses 10.2.2.3 and 4 of ISO 21809-1.

Tender
Part C3: Construction

C3.4.4-53

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Inspection and testing shall be carried out in accordance with the approved APS and ITP and shall meet the minimum requirements as stipulated in ISO 21809-1 Tables 8 and 9.

Coating repairs shall be addressed in accordance with an Engineer's approved APS and PQT as per Clause 12 ISO 21809-1.

Pipeline marking shall be as per the Employer's requirements, but shall as a minimum include all aspects detailed in Clause 13 of ISO 21809-1.

PLQ 11 RIGID POLYURETHANE COATING (RPU)

PLQ 11.1 Introduction

This part of the Specification defines the minimum technical requirements for liquid applied coating for factory coated pipe and specials. The coating system shall comprise a homogenic layer of 100% solids rigid polyurethane mechanically bonded to the metal substrate.

Where specified it shall be used for the external coating of pipes. The pipeline will be buried and will be protected against external corrosion by the external coating and cathodic protection systems. The external coating (primary corrosion protection system) shall be suitable for the operating conditions applying to the specific pipeline.

PLQ 11.2 Standards

Unless otherwise specified herein, the latest edition of the following Standards should be read in conjunction with this Specification:

American Society for Testing and Materials

| | |
|-------------|--|
| ASTM D16 | Standard Test Method for Paint, related coatings, materials and applications. |
| ASTM D 543 | Standard Test Method for Evaluating the resistance of plastics to chemical reagents. |
| ASTM D 570 | Standard Test Method for Water absorption of plastics. |
| ASTM D 2240 | Standard Test Method for Rubber Property (Durometer Hardness) |
| ASTM D 4060 | Standard Test Method for Abrasion resistance of organic coatings by the Taber abraser. |
| ASTM D 4541 | Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers |
| ASTM G14 | Standard test method for impact resistance of pipeline coatings (Falling Weight Test) |
| ASTM D 4285 | Method for indicating Oil or Water in Compressed Air |

Tender
Part C3: Construction

C3.4.4-54

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

British Standard and European Norm

BS EN 10290 Steel tubes and fittings for onshore and offshore pipelines - External liquid applied polyurethane and polyurethane-modified coatings.

ISO – International Organisation for Standardization

ISO 1514 Paints and varnishes - Standard panels for testing
 ISO 2808 Paints and varnishes - Determination of film thickness
 ISO 4624 Paints and varnishes - Pull off test for adhesion
 ISO 8501-1 Preparation of Steel Substrates Before Application of Paints and Related Products - Visual Assessment of Surface Cleanliness - Part 1: Rust Grades and Preparation Grades of Uncoated Steel Substrates and of Steel Substrates after Overall Removal of Previous Coatings
 ISO 8502 Preparation of steel substrates before application of paints and related products - Tests for the assessment of surface cleanliness
 ISO 8503 Preparation of Steel Substrates Before Application of Paints and Related Products - Surface Roughness Characteristics of Blast-Cleaned Steel Substrates
 Part 1: Specifications and definitions for ISO surface profile comparators for the assessment of abrasive blast-cleaned surfaces.
 Part 2: Method of grading of surface profile of abrasive blast-cleaned steel comparator procedure.
 Part 4: Method for the calibration of ISO surface profile comparators and for the determination of surface profile - Stylus instrument procedure.
 Part 5: Replica tape method for the determination of surface profile.
 ISO 8504-2 Preparation of Steel Substrates Before Application of Paints and Related Products - Surface Preparation Methods - Part 2: Abrasive Blast Cleaning
 ISO 11124-1 Preparation of Steel Substrates Before Application of Paints and Related Products - Specifications for Metallic Blast Cleaning Abrasives -
 Part 1: General introduction and classification
 Part 2: Chilled iron grit
 Part 3: High-carbon cast-steel shot and grit
 Part 4: Low-carbon cast-steel shot

NACE – International

NACE RP0274 High-Voltage Electrical Inspection of Pipeline Coatings Prior to Installation
 NACE RP0287 Field Measurement of Surface Profile of Abrasive Blast Cleaned Steel

Tender
 Part C3: Construction

C3.4.4-55

C3.4.4
 Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

NACE RP0394 Surfaces Using a Replica Tape
Application, Performance, and Quality Control of Plant-applied, Fusion-Bonded Epoxy External Pipe Coating

SSPC – Society for Protective Coatings

SSPC SP11 Power Tool Cleaning to Bare Metal
SSPC PA 2 Measurement of Dry Coating Thickness with Magnetic Gauges (Steel Structures Painting Manual, Ch 5 - Paint Application Specs.)
SSPC SP 10 Near-White Metal Blast Cleaning NACE No.2-2000 (Steel Structures Painting Manual, Ch 2 - Surface Preparation Specs.)

PLQ 11.3 Materials

The required coating shall be a two-component liquid applied rigid polyurethane subject to the approval of the Engineer.

The two components shall have different colours allowing the verification of the correct mixing, and checking of the uniformity of the colour of the mixed product.

The coating is considered cured when it has attained the hardness recommended by the product manufacturer.

PLQ 11.3.1 Handling of Materials

Materials shall be handled and stored in accordance with the material manufacturer's recommendations, which shall be available for review by the Engineer at the Contractor's premises. Materials shall be stored in an air-conditioned, temperature controlled environment until required for use.

Coating materials shall be segregated by type and batch during storage and handling. Materials from damaged containers shall be rejected, unless otherwise agreed with the Engineers representative in the factory or on Site.

Materials shall be used in the order in which they are delivered and before their expiry date for use.

PLQ 11.3.2 Documentation from the Materials Manufacturer

The commercial rigid polyurethane coating system offered shall be qualified by the Contractor and will be subject to the Engineer's approval prior to application. Testing should be conducted on each applicable coating and shall meet the acceptance criteria of the table below. The

Tender
Part C3: Construction

C3.4.4-56

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

qualification shall be based on tests carried out by an independent recognized certifying body and the relevant documents shall be submitted to the Engineer.

Full traceability of each batch of coating material shall be maintained. As a minimum, the following data shall be compiled and shall be available for immediate review by all parties:

- Name of manufacturer;
- Complete material identification: Trade name, chemical name and type of product details;
- Batch number;
- Date of manufacture;
- Place of manufacture;
- Shelf life / expiry date (if appropriate);
- Health and safety, and environmental instructions;
- Hazard warnings;
- Storage instructions;
- Quantity; and
- Manufacturing standard.

Any material not labelled with the above information shall not be used.

PLQ 11.3.3 Rigid Polyurethane Properties

The coating material properties and characteristics with respect to the 100% solids rigid polyurethane coating shall comply with the requirements of a Type V coating type in terms of the ASTM D16 Standard. The coating material shall be a homogenic solvent free layer with a chemical three-dimensional covalent cross-linked structure. The layer shall be made up from a liquid two pack coating system with Part A being poly-isocyanate rich and Part B consisting of polyols or amines that ensures relatively short curing times. Aliphatic polyurethanes shall be used above ground and aromatic polyurethanes shall be used below ground.

The performance properties of the coating shall comply with the requirements stated in the following table. The Contractor shall submit a full and comprehensive product datasheet to confirm material compliance with the Specification.

COATING MATERIAL PERFORMANCE PROPERTIES

| PROPERTIES | TEST REFERENCE | ACCEPTANCE CRITERIA |
|-------------------------------|--------------------------|------------------------------|
| Minimum application thickness | BS EN 10290 (Annexure A) | 1800 µm (Dry Film Thickness) |
| Adhesion to steel | ASTM D 4541 Method E | > 15 MPa |

Tender
Part C3: Construction

C3.4.4-57

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| PROPERTIES | TEST REFERENCE | ACCEPTANCE CRITERIA |
|---|--------------------------|--------------------------------------|
| Adhesion to factory coating | ASTM D 4541 Method | > 10 MPa |
| Hardness | ASTM D 2240 (Shore D) | As specified by coating manufacturer |
| Flexibility | BS EN 10290 (Annexure K) | Pass |
| Tensile strength | ASTM D 638 | >15 MPa at 3mm thickness |
| Resistance to cathodic disbondment | BS EN 10290 (Annexure E) | r < 8mm (28 days) |
| Dielectric strength | ASTM D 149 | Minimum 15 V/μm |
| Specific Electrical Insulation Resistance | BS EN 10290 (Annexure F) | 10 ⁶ ohm.m ² |
| Impact resistance | BS EN 10290 | > 5J/mm at 23°C >3J/mm at 5°C |
| Indentation resistance | BS EN 10290 (Annexure H) | <0.2mm at 23°C |

PLQ 11.4 Application

PLQ 11.4.1 Surface Preparation

Refer to Clause PLQ 3 for the general steel surface preparation requirements. The steel surface shall be grit blasted to Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals with an anchor profile of minimum 75 μm. The hardness of the abrasive material must be Rockwell C 54 or greater. The abrasive material shall be dry, clean, and free from contamination. Salt contamination tests shall be regularly performed on abrasive to verify that total salt level in the soluble contaminants is less than 25ppm. Extensive grinding shall not be performed without Engineer approval. The anchor pattern shall be restored on all ground surfaces.

The quality control plan (QCP) hold point at the completion of the surface preparation shall be subject to the signing off by the Approved Inspection Authority (AIA) prior to the application of the coating material for all pipes, specials and joint repairs.

PLQ 11.4.2 Coating Application

The application of the coating shall only proceed once the cleanliness of the steel substrate has been approved and the substrate temperature is more than 3°C above the dew point temperature. The work area shall be kept dry as the material reacts with humidity and moisture.

When required the surface shall be heated using an induction heating coil, radiant heaters or hot air to a temperature as recommended by the coating material manufacturer and in accordance with this Specification. The temperature shall not exceed 85°C and the use of propane torches or gas burners for pre-heating and post-heating is expressly prohibited. Infrared heaters may be

Tender
Part C3: Construction

C3.4.4-58

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

used for post-heating. The temperature of the bare steel shall be monitored using temperature-indicating crayons. The amount of crayon used shall be the minimum amount required for accurate measurement. Crayon markings shall be removed with a wire brush.

The individual liquid components of the rigid polyurethane coating shall be agitated thoroughly before use to disperse pigments and assure homogeneity. No thinning shall be done and the components shall not be mixed together.

The material shall be applied using a plural component, adjusted to the specified mix ratio on a heated airless spray unit with metering pumps. The width of the spray jet, the set up distance from the substrate surface and the overlap, the pipe rotation speed and the rate of application shall be predetermined for the final required dry film thickness applied in the workshop.

The wet film thickness shall be measured in accordance with ISO 2808. Particular attention shall be paid to the recommended dry film thickness which shall be measured in accordance with SSPC PA 2. No spot measurement may be less than 85% of the specified average thickness. Tools and equipment shall be cleaned using only such solvents as are recommended by the product manufacturer. Particular care shall be taken in the handling of the coated items before the coating has reached the minimum value of hardness recommended by the manufacturer. All pipes and other components shall be high spark holiday tested in accordance with NACE RP0274 at the test voltage recommended by the coating manufacturer.

For factory-coated pipe, bends and specials the cut back shall be 150 ± 20 mm. The edge of the cut-back shall be feathered at $30 - 45^\circ$.

PLQ 11.5 Inspection and Testing

The Contractor shall demonstrate that the proposed coating material and procedures will meet the requirements of this Specification when applied to pipes and pipe specials. The Contractor shall provide the documentation proof that the final selected coating material complies with the requirements listed in Table 37/15.

The Contractor shall test the finished coating during production to demonstrate continued compliance with this Specification. Details of all inspections and testing shall be fully documented in accordance with the approved quality control plan mentioned in Clause 37.4.2.

All stages of the surface preparation, coating and testing shall be subject to 100% inspection by the Contractor. The Engineer shall be informed at least two weeks prior to the start of surface preparation to allow scheduling of inspection personnel in the factory as well as on Site.

Tender
Part C3: Construction

C3.4.4-59

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 11.6 Testing of Production Pipes

The Contractor shall execute the following tests and provide written documentation proof of the test results within the agreed time frames:

PLQ 11.6.1 Visual Inspection (every pipe)

The coating shall be smooth, glossy, and free from pin holes, excessive orange peel effect, bubbling or excessive runs or sags.

PLQ 11.6.2 Dry Film Thickness (every pipe)

DFT shall be inspected in accordance with SANS ISO 2808, with a minimum average thickness of 1.8mm and a minimum of 1.6mm at any point.

PLQ 11.6.3 Electrical Insulation Defects (Holiday) Inspection (every pipe)

The coating shall be free from electrical insulation defects when tested with a high voltage holiday detector set at 15 kV.

PLQ 11.6.4 Hardness Shore 'D' (every pipe)

The Shore 'D' hardness shall comply with the minimum set by the manufacturer in pre-qualification.

PLQ 11.6.5 Adhesion (1 test per shift)

The pull-off adhesion at 23°C shall be greater than 15 MPa.

PLQ 11.6.6 Cathodic Disbondment (1 test per 50 pipes and commencement of new batch or new production run))

The disbondment shall be less than 8mm radius. BS EN 10290 Annexure E 48hr.

PLQ 11.6.7 Composition (1 test per 50 pipes or new batch or new production run)

The Thermo Gravimetric Analysis (TGA) scan shall be checked against the manufacturer's qualification scan.

Tender
Part C3: Construction

C3.4.4-60

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 11.7 Coating Repairs

Since polyurethane systems are chemically cured, very thorough abrasion of damaged or defective coating is required to ensure an adequate physical bond.

PLQ 11.7.1 Repairs before Full Cure in the Factory [Within Sixteen (16) Hours at 23°C of Application of Last Coat]

The area to be over-coated shall be abraded with abrasive paper grade 220 to a uniform matt finish.

The abraded surface shall be vacuum-cleaned or be blown clean with uncontaminated dry compressed air to remove dust and debris.

Brush grade polyurethane shall be applied in as many coats as are required to achieve the specified thickness free of electrical insulation defects.

PLQ 11.7.2 Repairs after Full Cure [After Sixteen (16) Hours at 23°C of Application of Last Coat]

The area to be over-coated shall be abraded with abrasive paper grade 220 to a uniform matt finish.

The abraded surface shall be vacuum-cleaned or be blown clean with uncontaminated dry compressed air to remove dust and debris.

The coating manufacturer's adhesive primer or activating solvent shall be applied only to the abraded surface.

After the designated curing time, brush grade polyurethane shall be applied in as many coats as are required to achieve the specified thickness free of electrical insulation defects.

Repairs shall be carried out with repair grade materials from the supplier of the factory applied coating, unless otherwise approved by the Engineer.

The repair material shall be as recommended by the supplier of the factory applied coating. The supplier shall confirm material compatibility and surface preparation requirements. Prior to any repair work, the supplier shall demonstrate the use of the material to the Contractor and Engineer on site.

The repaired area shall comply with the quality control requirements as set out in paragraph PLQ 11.6.

Tender
Part C3: Construction

C3.4.4-61

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Based on the above the Contractor shall prepare a detailed method statement on the repair of the coating for the approval of the Engineer.

PLQ 12 PETROLATUM TAPE WRAPPING SYSTEM

PLQ 12.1 General

An EN 12068 Class A Petrolatum System shall be used for the wrapping of buried flange and flexible joints and where specified in the Specifications, Bill of Quantities or Drawings. The Denso Clingwrap protection system or similar products approved by the Engineer will also be acceptable.

PLQ 12.2 Surface preparation

Bare pipes and fitting to be prepared to a recommended standard of St2 as specified by the Swedish Standard SIS 05590:

St2: Hand Tool Cleaning

Removal of all rust scale, mill scale, loose rust and loose paint to the degree specified by hand wire brushing, hand sanding, hand scraping, hand chipping or other hand impact tools or by a combination of these methods. The substrate should have a faint metallic sheen and also be free of oil, grease, dust, soil, salts and other contaminants.

Chamfer any raised edges or steps in the existing coating.

PLQ 12.3 Primer application

Surface to be primed with Priming Solution (e.g. S105 Paste)

Primer is applied to the steel surface with a brush or paint roller. The primer to be thoroughly mixed prior to application.

The primer to cover the entire steel surface, including the nuts and bolts and overlap onto the mill applied primary coating system by a minimum of 200mm.

The primer must not be diluted. Primer cans should remain covered when not in use to avoid solvent evaporation and contamination.

Tender
Part C3: Construction

C3.4.4-62

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLQ 12.4 Profiling mastic application

Apply Profiling Mastic to both sides of the fitting to form a generous fillet from the coupling onto the pipe barrel. The Profiling Mastic is also used to cover the bolt heads and nuts to form a regular profile onto which the Petrolatum Tape can be applied.

PLQ 12.5 Petrolatum tape application

Apply one layer of the Petrolatum Tape to the body of the pipe or fitting, ensuring that there is no air entrapped beneath the tape. The Petrolatum must be applied spirally, with a 55% overlap and at least 100 mm onto the factory coating and the barrel of the pipe.

PLQ 12.6 Clingwrap outerwrap tape application

Spirally apply Clingwrap Outerwrap Tape to cover the entire Petrolatum Tape system. Start at one end, wrapping with a 55% overlap, proceed to the other end and ensure the Clingwrap Outerwrap extends 100mm beyond each end of the repair.

PLQ 13 JOINT COATING SYSTEMS

PLQ 13.1 FBMDPE, three layer polyethylene (3LPE) and Rigid Polyurethane coating


The unprotected area at welded joints shall be protected against corrosion as follows:

- The cutback of the coating shall be 100mm from the pipe ends.
- Chamfer any raised edges or steps in the existing coating.
- The factory applied polyethylene pipe surface to which the cold tape wrapping is to be applied shall be abraded with 40 grit abrasive paper or sweep blasted for a minimum of 50 mm onto the mainline coating to obtain a surface profile with an R_z value between 40 and 70 μm
- Abrasive blast clean the steel surface Sa 3 of ISO 8501-1 or SSPC SP16 for non-ferrous metals. The surface profile shall be checked in accordance with ISO 8503-1, ISO 8503-4 and ISO 8503-5 with an average R_z larger than 75 μm . All types of abrasive that are used in the preparation of the field joints and small repairs shall comply with ISO 11124-2 to 4.
- The surface to be coated shall at the time of application be dry and free of dust and any contamination detrimental to the adhesion of the coating to the steel substrate. The Contractor shall prepare a detailed method statement on how the field joint area will be kept dry and clean during the application operation. It shall also include the trench space requirements for the application equipment.
- All dust, detritus and salts shall be removed from the metal substrate. The level of salts shall be measured in accordance with the requirements of ISO 8502-9 and shall be $\leq 30 \text{ mg/m}^2$


Tender
Part C3: Construction

C3.4.4-63

C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2

- The application of the coating shall only proceed once the cleanliness of the steel substrate has been approved and the substrate temperature is more than 3°C above the dew point temperature.
- The temperature of the substrate shall be within the application temperature range specified by the coating manufacturer. When required the surface shall be heated using an induction heating coil, radiant heaters or hot air to a temperature as recommended by the coating material manufacturer and in accordance with this Specification. The temperature shall not exceed 85°C and the use of propane torches or gas burners for pre-heating and post-heating is expressly prohibited. Infrared heaters may be used for post-heating. The temperature of the bare steel shall be monitored using temperature-indicating crayons. The amount of crayon used shall be the minimum amount required for accurate measurement. Crayon markings shall be removed with a wire brush.
- Applicable to 3 LPE only: Apply Denso Protal 7200 liquid epoxy to the blast cleaned surface and adjacent prepared factory FBE coating to a minimum dry film thickness of 400 micron.
- The entire joint surface to be wrapped shall be primed with Denso Butyl Primer P16HT.

Allow approximately 30 minutes drying time or until the primer is tacky to the touch.

- Apply 100mm or 150mm wide 3 ply PE/Butyl rubber self-amalgamating inner-wrap compliant with DVGW EN12068 Class C 50°C (DENSO S43HT on similar product approved by the Engineer).

The tape shall be applied to ensure that a minimum 55% overlap.

- Apply 100mm or 150mm wide 2 ply PE/Butyl rubber outer-wrap compliant with DVGW EN 12068 Class C 50°C (DENSO R23 on similar product approved by the Engineer).

The tape shall be applied to ensure that a minimum 55% overlap shall be achieved.

The tape shall be applied to a minimum width of 50mm beyond the applied inner tape-wrapped area onto the primed shop applied coating.

Ensure that the tape is in full contact with the underlying surface with no wrinkles, fish-mouths or bubbles.

- Holiday detection shall be carried out in accordance with NACE RP0188.

The quality control plan (QCP) hold point at the completion of the surface preparation shall be subject to the signing off by the Approved Inspection Authority (AIA) prior to the application of the coating material for joint repairs

Tender
Part C3: Construction

C3.4.4-64

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Damaged areas on coatings shall be repaired in accordance with the specifications and guidelines of the coating manufacturer. Hand or power cleaning can be used for small repair areas such as pinholes and areas inaccessible for blast cleaning. 80 Grit or coarser sandpaper can be used to suitably roughen and abrade the area to be prepared. The area shall be sanded to the substrate taking care not to polish the substrate.

Only Engineer approved DVGW Certified and or other Engineer approved certification materials may be used. All materials shall comply with the requirements of EN 12068 Class C HT50°C UV for either tapes and heat shrinkable sleeves (HSS), unless otherwise approved by the Engineer. An ISO 17050-1 Certificate of Conformity from the supplier (point of origin) stipulating compliance with all chemical, physical and mechanical properties of the applied product, as per ISO 10474 or EN 10204 Inspection Certificates 3.1.B and 3.1 shall be submitted to the Engineer i.e. the DVGW Type Test Report and in-house batch testing for the batch(s) to be supplied.

Pipeline field joint repairs (FJR) may not commence without an Engineer approved Inspection and Testing Plan (ITP) document providing an overview of the sequence of inspections and tests, including appropriate resources and procedures and Quality Control Procedure (QCP).

Subsequent to the approval of the documentation detailed above, a Procedure Qualification Trial (PQT) shall be carried out, to be witnessed by the Engineer's representative. The PQT shall include the application of the FJR and subsequent inspection/testing of its properties, to confirm that the Application Procedure Specification (APS) is adequate to produce a FJR system with the specified properties and shall be carried out prior to the start of production.

Alternatively for RPU mainline coatings, the same RPU material can be applied, once the Engineer has approved the APS, QCP and ITP. An ISO 17050-1 Certificate of Conformity from the RPU supplier (point of origin) stipulating compliance with all chemical, physical and mechanical properties of the applied product, as per ISO 10474 or EN 10204 Inspection Certificates 2.1 and 2.2 shall be submitted to the Engineer i.e. the EN 10290 Type Test Report and in-house batch testing for the batch(s) to be supplied as per EN 10290.

PLQ 13.2 FBMDPE, 3LPE and RPU coating (Stopaq viscoelastic wrappingband application)

As an alternative to PLQ 13.1, the unprotected area at welded joints shall be protected against corrosion as follows:

- The cutback of the coating shall be 100 mm from the pipe ends.
- Chamfer any raised edges or steps in the existing coating.
- Abrasive blast clean to Sa 2,5
- Degrease using isopropanol alcohol and a cloth.
- Apply first Stopaq Wrappingband CZH [minimum thickness of 1,5 mm] such that there is a

Tender
Part C3: Construction

C3.4.4-65


C3.4.4
Particular Specifications for Civil Works




Contractor




Witness 1




Witness 2



Employer




Witness 1




Witness 2

minimum of 50mm overlap over the weld and a minimum of 50mm overlap over the coating.

- Where the end of the Wrappingband meets the beginning, peel back the first 100mm of the release foil such that the end can be applied over the beginning with a 100mm overlap.



- Remove the remainder of the release foil and then apply the second Wrappingband in the same manner and remove release foil.



- After removing the release foil, rub the Stopaq by hand to release any trapped air and spark test with 15kV.
- Position the High Impact Shield (HIS) at the 10 o'clock position and wrap around the pipe such that a 100mm overlap results at the joint.
- The HIS shall extend 50mm either side of the Stopaq coating overlap.
- Centre and apply the closure strip on the seam of the HIS. Heat the closure strip and tap on it until attachment is complete. Do not use a siliconized roller.
- Apply heat working from one side to the other against the wind. Apply full heat (100%) to the area there is no Stopaq beneath the HIS.
- Apply 75% heat to area where Stopaq is present beneath the HIS.

Tender
 Part C3: Construction

C3.4.4-66

C3.4.4
 Particular Specifications for Civil Works

Contractor


Witness 1

Witness 2

Employer

Witness 1

Witness 2



- Immediate backfill after application if possible.
- Holiday detection shall be carried out in accordance with NACE SP0188.
- Damaged areas on coatings shall be repaired in accordance with the specifications and guidelines of the coating manufacturer.

PLQ 13.3 Polymer Modified Bitumen (Bituguard) Coating

The unprotected area at welded joints shall be protected against corrosion as follows:

- Where applicable, remove the whitewash for a distance of 150mm from the edge of the factory applied coating. Ensure the end of the factory coating is firmly adhered. Cut back any areas of loose or damaged coating to 10mm beyond the area of damage. Ensure the edge of the factory applied coating is bevelled at 30° or less.
- Chamfer any raised edges or steps in the factory coating.
- Surface preparation shall be abrasive blast cleaning to Sa 2,5 of ISO 8501-1. The white wash on the factory coating to be removed for a distance of 100 mm from the end of the coating.
- The steel surface and 100 mm of the factory coating on both sides of the joint to be coated with Bitumen Primer (Denso Primer D or similar product approved by the Engineer).
- Using hot air or gas torches, apply custom sized Hot Applied EN 10268 Class B HT50°C Bitumen rolls of membrane to achieve the same minimum thickness as the factory applied coating with a minimum thickness of 5 mm. Densotherm HD heat applied bitumen wrapping is also acceptable. The applied membrane shall overlap onto itself or the factory coating by a minimum of 50 or 100mm respectively.
- Ensure a liquid bead of coating is maintained in contact with the steel at all times to prevent air entrapment. The perimeter of the field joint shall be neatly finished off and blended into the factory coating.
- The finished joint shall be free of air bubbles, and shall exhibit the same bond to steel as the factory coated pipe.

Joint preparation shall be subject to witness and hold inspection by the Engineer prior to


Tender
Part C3: Construction

C3.4.4-67


C3.4.4
Particular Specifications for Civil Works



Contractor



Witness 1



Witness 2



Employer



Witness 1



Witness 2

application of the primer and coating. The finished joint shall be holiday tested at 15kV and any holidays repaired.

PLQ 14 CUT BACK AT PIPE ENDS

Only if it is expected that the pipes will be exposed to corrosive conditions for long periods before it is installed, the unprotected grit blasted bare steel surface at the ends of pipes, specials and fittings to be welded on site shall be painted with a temporary paint product in the factory, to prevent corrosion of the pipe end before the permanent joint corrosion protection is applied on Site. Alternatively, the uncoated steel surface could be temporarily protected by a pressure sensitive tape. The temporary paint and remains of the tape (after being removed by hand) shall be completely removed by abrasive blast cleaning as part of the surface preparation process. For each project the Contractor shall consult with the Engineer whether the temporary paint on the pipe ends is required.

PLQ 15 UV PROTECTION

All pipes with FBMDPE, 3LPE or Bituguard coatings shall be painted with a white PVA or acrylic (to be approved by the Engineer) for protection against UV. The overcoat to be maintained by applying additional layers until the pipe is backfilled.

PLQ 16 ADDITIONAL EXTERNAL PROTECTION FOR PIPES CAST INTO CHAMBER WALLS

After the concrete has cured for 7 days, wire brush or scabble the exterior and interior surfaces of the wall to remove laitance. Dry brush to remove all loose powder.

Mix ABE Super Laykold and water (1:1 ratio) and apply as a primer to the concrete and the pipe surfaces. After 1 hour apply a thick coat of ABE Super Laykold to the concrete and the pipe and immediately embed 250mm wide ABE non-woven polyester membrane "SBP" into the Super Laykold. After 3 hours apply another coat of Super Laykold.

Similar products approved by the Engineer can also be used.

This additional protection is required on the inside and outside of chamber walls.

There must be no contact between the steel pipe and the chamber reinforcement.

PLQ 17 JOINT BETWEEN EPOXY LINING AND CEMENT MORTAR LINING

The joint between epoxy lining and cement mortar lining shall be protected as follows:

- Unprotected steel surface to be abrasive blast cleaned to Sa3.

Tender
Part C3: Construction

C3.4.4-68

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- Epoxy lining to be light abrasive blast cleaned to a surface profile of 60 – 85 micron over a distance of 50 mm minimum.
- Pro-Struct 617NS mortar filler to be applied into the joint between the epoxy and the cement mortar and finished to a smooth surface at a 45-degree angle to the pipe surface.
- Epoxy paint (approved by the Engineer) to be applied on the blast cleaned steel surface, the Pro-Struct 617NS mortar filler and on the cement mortar lining for a minimum distance of 50mm, with a minimum dry film thickness of 500 micron.

PLQ 18 MEASUREMENT AND PAYMENT

If corrosion protection and painting is not measured separately in the Bill of Quantities, the price for corrosion protection and painting shall be deemed to be included in the price for the pipes, fittings and specials.

Tender
Part C3: Construction

C3.4.4-69

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS: CEMENT MORTAR LINING OF PIPELINES

INDEX

| Item | Description | Page No |
|--------|---|-----------|
| PLS 1 | SCOPE | C3.4.4-71 |
| PLS 2 | MATERIALS | C3.4.4-71 |
| PLS 3 | CEMENT-MORTAR FOR LINING | C3.4.4-73 |
| PLS 4 | ACCESS OPENINGS AND ACCESS POINTS FOR IN SITU APPLIED LININGS | C3.4.4-75 |
| PLS 5 | CLEANING PIPE SURFACES | C3.4.4-75 |
| PLS 6 | APPLICATION OF MORTAR LINING | C3.4.4-77 |
| PLS 7 | THICKNESS AND SURFACE FINISH OF LINING | C3.4.4-81 |
| PLS 8 | CURING | C3.4.4-82 |
| PLS 9 | INSPECTION OF LINING | C3.4.4-83 |
| PLS 10 | DEFECTS..... | C3.4.4-83 |
| PLS 11 | SAMPLES AND TESTS..... | C3.4.4-84 |
| PLS 12 | BACKFILLING OF EXCAVATIONS | C3.4.4-84 |
| PLS 13 | DISPOSAL OF UNDESIRABLE MATERIAL | C3.4.4-84 |

Tender
Part C3: Construction

C3.4.4-70

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS 1 SCOPE

This specification covers the cement-mortar lining of steel pipelines.

PLS 2 MATERIALS

PLS 2.1 Cement

- a) Cement shall comply with the latest requirements of SABS ENV 197-1 Type CEM 2A.
- b) Pozzolan material shall not be used in addition to or to replace a portion of the cement.
- c) Cement used for the trial mortar mix to be specified in the tender and all cement used for this contract shall be produced from the same factory unless otherwise permitted by the Engineer in writing. The name of the factory shall be stated by the tenderer.
- d) Cement shall be from the same order of delivery. All cement in storage for longer than eight (8) weeks and all cement in unsealed pockets shall be removed from storage and be discarded.
- e) Cement shall be delivered to the site in a dry condition undamaged by exposure to the weather and shall be stored on the site in approved weather and damp-proof conditions. The floor shall be at least 300 mm above ground-level and covered with a waterproof membrane.
- f) All cement spilled from broken pockets on working surfaces or storage floors shall not be used on the work. It shall be swept up each day and removed from the work together with all broken pockets of cement.

PLS 2.2 Sand

- a) Sand for cement mortar shall be river sand, natural pit sand, crusher sand or a blend of the sands provided it is clean and the grains are inert, hard, durable and uncoated. The supplier and type of sand and its typical grading envelope shall be stated by the tenderer.
- b) Sand shall be well graded and a sieve analysis of a representative sample carried out in accordance with SABS method 829 shall show that it complies with the following grading requirements:

| Sieve size (mm) | Percentage passing by mass |
|--------------------|----------------------------|
| 1,180 | 100 |
| 0,075 | 0 to 10 |

- c) Sand shall be free from injurious amounts of dust, clay lumps, shale, soft or flaky particles, mica, loam, oil, alkali, and other deleterious substances. The maximum percentage by mass of deleterious substances shall not exceed the following limits:

Tender
Part C3: Construction

C3.4.4-71

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| Deleterious substances | Percentage by mass |
|---------------------------------------|--------------------|
| Shale | 1 |
| Clay lumps | 1 |
| Mica and other deleterious substances | 2 |
| Sum of all deleterious substances | 3 |

- d) The water demand of the sand is defined as the quantity of water in litres required to make one cubic metre of a mortar which having a sand to cement ratio by mass of 1,0 has a consistence of 8,5 mm DB penetration when tested in accordance with BS 4551 : 1980. The water demand of the sand shall not exceed 340 l/m³.
- e) The water demand of the sand shall be determined from at least three trial cement-mortar mixes each of a different water content and shall be stated by the tenderer.
- f) Sand tested for organic impurities in accordance with SABS Method 832 shall yield a test solution not darker in colour than the reference solution.
- g) The chlorine content of the sand determined by SABS Method 830 shall not be greater than 0,01 per cent (mass/mass).
- h) The Contractor shall submit samples of the sand to the Engineer for his approval before use. Prior to commencing the work the Contractor shall submit a report in detail from an approved testing laboratory showing that the sand complies with the specification.
- i) The testing laboratories of the SABS, CSIR, CCI, or other laboratories subject to the prior approval in writing of the Engineer, will be accepted as approved laboratories in which tests or designs required by the specification may be carried out.
- j) Sand shall be stored on site on an impermeable surface, protected from the weather, and washed sand shall be allowed to drain freely for at least 24 hours before use. The Engineer may require the Contractor to test the sand daily (or more frequently if necessary) for moisture content, impurities and grading before use.

PLS 2.3 Water

Water for mortar shall be clean and free from injurious amounts of dissolved mineral salts, organic matter or other substances which may impair the strength or durability of the mortar and shall generally conform to the recommendations in the appendix to BS 3148.

PLS 2.4 Admixture

- a) Admixture is any other material apart from cement, sand and water that is added to the cement-mortar or painted onto the bare steel surface prior to cement-mortar application.
- b) No admixture shall be used that has a deleterious effect on the electrochemical passivation of the steel surface by the cement-mortar or on the water flowing in the pipe after the lining has been placed. In addition chloride based admixture or admixture that amperes the durability, fatigue strength or ability of the mortar to resist impact loadings shall not be used.

Tender
Part C3: Construction

C3.4.4-72

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- c) Prior written approval of the Engineer shall be obtained for the use of any admixture and the Contractor shall submit test data to substantiate the admixture performance.

PLS 2.5 Welded Steel Fabric

Welded steel fabric shall conform to SABS 1024, except that wire diameter and mesh sizes shall conform to this Specification.

PLS 3 CEMENT-MORTAR FOR LINING

PLS 3.1 Composition

Cement-mortar for steel pipe lining shall be composed of cement, sand, water, and if required, admixture, that are well mixed and of proper consistency to obtain a dense, homogeneous lining of the required thickness that will adhere firmly to the pipe surface.

PLS 3.2 Proportions

- a) The mortar mix shall be designed to produce mortar which will attain the specified compressive and flexural strengths and which will in addition have high density and impermeability.
- b) Cement-mortar shall have a maximum water to cement ratio by mass of 0,36:1 and a maximum sand to cement ratio by mass of 1,5:1 (for drag trowel and hand application) and 2:1 (for centrifugal span lining).
- c) The workability of the mortar shall be the consistence measured by the dropping ball penetration test carried out in accordance with BS 4551:1980.
- d) The proportions of cement, sand and water shall be based upon laboratory tests made with the cement, sand and water to be used on the work. These proportions together with the design workability shall be stated by the tenderer.
- e) The exact proportions of the constituents shall be determined by the characteristics of the sand used, the condition of the cleaned pipe surface, the thickness of the lining, the size of pipe and the lining equipment used.
- f) Two mortar mixes shall be designed: one suitable for machine application and one suitable for hand application where machine application is impracticable. Guide workability levels for designing these mixes are a 9 mm penetration and a 6 mm penetration respectively.
- g) The Contractor shall timeously submit a report of the proposed cementmortar mix designs to the Engineer for his approval before the work begins. This report, from an approved testing laboratory, shall show that the mixes comply with the specification and shall give for each design mix for at least three different water contents, one of which corresponds to the design workability level stated in the tender, the consistence obtained when using the materials proposed for the work.

Tender
Part C3: Construction

C3.4.4-73

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS 3.3 Strength

- a) The mortar compressive and flexural strength shall be determined from 160 mm by 40 mm prisms stored, demoulded, cured and tested in accordance with the "ISO" SABS method 866. High frequency (200 Hz) vibration shall be used to compact the mortar when moulding in order to expel all the air entrained when mixing. A minimum period of 2 minutes shall be used.
- b) The minimum 7-day compressive and flexural mortar strengths below which not more than 5 per cent of results may fall are 30 MPa and 5,5 MPa respectively. The corresponding 28-day mortar strengths are 42 MPa and 6,5 MPa respectively.
- c) At least 6 representative mortar prisms shall be made for each day of machine lining applicable. Three of these prisms shall be tested at 7-day's age and 3 at 28-day's age. The 6 prisms shall be made from one batch of mortar sampled whenever possible from the hopper of the lining machine.

PLS 3.4 Batching, Mixing and Workability

- a) All mortar shall be batched and mixed in mechanical mixers of good condition under the supervision of a competent and experienced person.
- b) All materials shall be batched by mass and the combined error in weighing the materials shall not exceed 2 per cent. Equipment performance shall be checked when required by the Engineer and the Contractor shall provide apparatus as required for this testing.
- c) All weighing and measuring equipment shall be checked daily, and if necessary adjusted, before cement-mortar mixing commences.
- d) The quantity of water used in each batch of mortar shall be carefully adjusted to maintain the cement to water ratio required for the approved mix.
- e) Allowance must be made for the moisture content of the sand which shall be determined either by weighing and drying or by the speedy moisture meter. Allowance shall also be made for moisture collecting on the interior of pipe surface, the method of transporting the mortar from the mixer to the lining machine and the trowelling system used.
- f) Mixing shall be continued for not less than 90 seconds after all the materials including water are in the mixer. All mortar shall be thoroughly mixed and the whole of each batch shall be uniform, free of lumps and free from segregation. The minimum time of 90 seconds may be increased at the discretion of the Engineer.
- g) Adequacy of mixing shall be judged visually and if in the Engineer's opinion mixing is unsatisfactory, the mixer shall be replaced by a machine which will produce acceptable mixing.
- h) Any batch not complying with the specification shall be removed from site or disposed of as directed by the Engineer or Inspector.

Tender
Part C3: Construction

C3.4.4-74

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- i) The workability of the freshly mixed mortar shall be determined periodically from a sample taken immediately prior to being transported to the lining machine, or where practicable from a sample taken at the lining machine itself.
- j) There shall be no retempering of the mix after discharge from the mixer. Only fresh mortar shall be used, mortar in a mixed state for longer than 1 hour shall be discarded.

PLS 3.5 Once the optimum workability for the day's run is determined the consistence shall not vary by more than 1 mm DB penetration.

PLS 4 ACCESS OPENINGS AND ACCESS POINTS FOR IN SITU APPLIED LININGS

PLS 4.1 The Contractor shall provide access openings in the pipeline for inspection, cleaning and lining work by cutting out a suitable section of piping. On completion of the lining operation, the Contractor shall replace the relined cut out section by means of electric arc welding carried out in accordance with the requirements of Section PLN of the Particular Specification.

The average spacing and dimension of the access openings required shall be stated by the tenderer.

PLS 4.2 Welding can be inspected by means of ultrasonic or radiographically testing. This inspection will be carried out in accordance with BS 3923 and API 1104 by an inspection authority appointed by the Engineer. All defects not complying with API 1104 shall be ground out and repaired to the approval of the Engineer. The costs of all repairs and consequential inspection shall be borne by the Contractor.

PLS 4.3 The actual position of each opening shall be sited so that it does not interfere with anchor blocks, valve chambers, scour piping, etc., and so that it does not cause an obstruction to traffic, access to properties, structures etc. The position of each access opening to be approved by the Engineer. Access openings shall not interfere with pipe joints, expansion joints, etc.

PLS 4.4 An access point is an opening to the pipe interior such as an access manhole or large diameter air valve saddle. It may be used for inspection, cleaning, cement-mortar lining or curing as required by the Contractor in which case it becomes his responsibility to control all access at the point until the blank flange and/or air valve is refitted and bolted up by the Contractor prior to filling the pipe with water.

PLS 4.5 The Contractor is responsible to prevent animals, reptiles, etc. from entering the pipe.

PLS 5 CLEANING PIPE SURFACES

PLS 5.1 The Contractor shall clean the steel surface to be cement-mortar lined so as to provide a clean, firm and sound surface free from contaminants such as loose rust, loose mill scale, weld slag,

Tender
Part C3: Construction

C3.4.4-75

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

loose corrosion products, dust, soil, grit, oil, grease, accumulations of water and water soluble salts, which can adversely affect the adhesive bond of the freshly applied mortar and the electrochemical passivating mechanism of the cement-mortar.

- PLS 5.2** Mechanical cleaning by hand or machine methods or both shall be used. Details of the method and equipment to be used for cleaning shall be submitted with the tender. Solvent emulsions shall be used to remove oil or grease followed by thorough rinsing with clean water. Compressed air tools or equipment used inside the pipe, shall be fitted with an adequate oil removal filter and moisture drain trap which shall be inspected and cleaned regularly.
- PLS 5.3** The interior surface of the installed pipeline shall be cleaned to a degree of cleanliness equivalent to preparation grade St 2 of SABS Method 767 (thorough scraping and wire brushing).
- PLS 5.4** At the start of the contract after cleaning but before any lining is carried out a standard of cleanliness for the pipe surface which is assessed for freedom from dust and debris using transparent cellophane tape in accordance with SABS Method 769 is to be agreed upon between the Engineer and the Contractor and will be strictly adhered to for the duration of the contract.
- PLS 5.5** Cleaning of the pipeline surfaces shall be completed not less than one day or more than two days in advance of the lining operation and no lining shall be carried out unless the cleaned surface has been inspected and approved by the Engineer.
- PLS 5.6** Immediately prior to the machine application of lining, excessive condensation and pools of water, rust dust, sand, mud, loose mortar, rebound debris and other foreign materials that have accumulated since the cleaned pipe section was inspected and approved shall be removed by suitable methods that are to be agreed upon before the lining is applied.
- PLS 5.7** The Contractor shall provide 60 watt halogen or 20 watt fluorescent lamps to illuminate the cleaned pipe and provide suitable movable lamps to illuminate the surfaces when the Engineer carries out testing and inspection.
- PLS 5.8** The Contractor shall provide his workmen and the Engineers representative with protective clothing and appliances such as dust respirators, goggles, face shields and masks to prevent bodily harm while carrying out the cleaning operation.
- PLS 5.9** Cleaning water, rust and debris removed from the pipeline shall be collected, loaded and transported at a maximum of 3 day intervals but should the local accumulation become excessive it shall be removed at shorter intervals as determined by the Engineer.

Dirty cleaning water shall not be disposed of in a manner that will cause soil erosion in the working area. The rate for cleaning shall include for collecting, loading, transporting and disposal of the cleaning water, rust and debris at permanent disposal sites.

Tender
Part C3: Construction

C3.4.4-76

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS 6 APPLICATION OF MORTAR LINING

PLS 6.1 Machine Application of Mortar Lining

- a) For shop applied linings pipes shall be adequately supported.
- b) The lining shall be applied in one layer by use of a machine with an applicator head which will centrifugally or otherwise place mortar against the surface of the pipe without injurious rebound and with sufficient velocity or pressure to cause the mortar to be densely packed and to adhere in place. Details of the machine to be used shall be submitted in the tender. The use of compressed air in direct contact with the cement-mortar will not be permitted in the process of mixing or application. The rate of travel of the machine and the rate of discharge of mortar against the wall of the pipe shall be entirely mechanically controlled so as to produce a smooth lining of uniform thickness through the interior of the pipeline. The lining machine shall be provided with attachments for mechanically trowelling the mortar. Both the application and trowelling of the mortar shall take place at the rear of the machine so that the freshly placed and trowelled mortar will not again be disturbed or touched until after it has set. The trowel attachment shall be such that the pressure applied to the lining will be uniform, producing a smooth surface without shoulders or undulations, and producing a lining of uniform thickness.
- c) The Contractor shall only be permitted to place a double layer (or skin) on approval of the Engineer. A double layer (skin) shall be placed within 24 hours after the first layer has been placed. A minimum layer thickness of 5 mm is required. The total cost for a double layer will be for the account of the Contractor.

PLS 6.2 Centrifugal spun lining of pipes

The coating, if applicable, shall be suitably protected against mechanical damage during the handling and spinning operations. Before being placed in the spinning machine, the pipe shall be suitably braced with external stiffening rings, which shall not be removed until the appropriate one of the following periods has elapsed from the time of placing of the lining:

- a) 72 hours when water curing is used.
- b) 36 hours when steam curing is used.

End gauge rings shall be securely attached to the pipe ends to control the lining thickness, to act as a stop end to prevent mortar leakage and to stiffen and hold the pipe ends round.

Each pipe shall be rotated in a spinning machine with its axis horizontal during and for a suitable period after the placing of the lining. The speed of rotation shall be such as to produce a uniform distribution of the cement mortar over the interior surfaces of the pipe. Sufficient mortar to line completely one pipe to the appropriate nominal thickness shall be mixed in one batch, and it shall

Tender
Part C3: Construction

C3.4.4-77

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

be of such consistency as to minimise segregation during spinning. The mortar shall be placed in the pipe immediately after mixing and before initial set has taken place, and in a manner providing uniform longitudinal distribution of the batch from end to end of the pipe. As soon as the mortar lining has achieved a uniform thickness over the whole interior surface of the pipe, the speed of rotation shall be increased to a speed that will compact the mortar and is not less than a peripheral speed of 17 metres per second. The required speed shall be maintained for such a period as will give the maximum density of mortar and smoothness of surface, and sufficient bonding to permit removal of the pipe from the machine without injury to the lining. All water and laitance expelled during spinning shall be removed in such a manner that the surface of the lining is smooth, level and true.

After the lapse of a suitable period after spinning (as determined by experiment), the spun lining shall be given a steel trowelled or smoothing bar finish. A second trowelling may be necessary to remove all laitance and produce a smooth and hard finished surface.

For spigot and socket joints, the concrete lining shall be ended as shown on Figure 1 at the end of this specification.

PLS 6.3 Pipe Ends for Shop Applied Linings

For flanged pipes and specials and pipes intended for jointing by couplings, concrete lining shall be ended flush with pipe ends with a 6mm bullnosing of edges by means of a nosing tool.

For pipes to be butt welded, the lining shall terminate 50 mm from the internal end of each pipe and the end of the lining shall be bevelled to form an undercut angle of approximately 85 degrees between the clear end of pipe barrel and the lining end. The unlined surface of 50 mm wide from each end may be protected by strips of pressure sensitive plastic tape, firmly pressed into the surface to exclude all air, moisture and to give temporary protection between the works and butt welding on the site.

For spigot a socket joint with a fillet weld, the cement mortar shall end as shown on figure 1 attached.

PLS 6.4 Hand Application of Mortar Lining

- a) In addition to the repair of but welded joints, hand applied mortar shall be allowed only where machine application is impracticable. Bends less than 22,5° shall be lined by machine unless stated by contractor in the tender to the contrary. The Engineer may order the correction of defective lining to be carried out by hand application of mortar lining.
- b) Any voids related to flexible couplings will be filled by hand with mortar and finished flush with inside wall of pipe prior to application of mortar lining.

Tender
Part C3: Construction

C3.4.4-78

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- c) Areas to be hand lined shall be cleaned and all dust removed with a soft wire hand brush.
- d) Cement slurry shall be applied to the cleaned pipe and existing cement lining as a bond coat in a layer no more than 2 mm thick after wetting the existing lining.
- e) Cement slurry consist of cement, water and admixture. A suitable admixture is a styrene-butadiene copolymer latex (SBR) manufactured for use with Portland Cement as a bonding agent (Nitobond or Duralatex or a similar product approved by the Engineer). The proportion of cement, water and admixture shall be in accordance with the manufacturer's specifications and submitted to the Engineer.

A typical proportion is a SBR/Water mix of 1:1 and add cement to form a slurry consistency.

- f) The cement-mortar shall be applied before the slurry is dry. Admixture shall be used in the cement mortar and the proportion shall be in accordance with the manufacturer's specifications and submitted to the Engineer. A typical proportion is a SBR/Water mix of 1:3 added to the cement/sand mix.
- g) Hand applied mortar shall be finished with steel trowels and the quality, thickness, uniformity and surface finish shall be substantially equivalent to the machine applied mortar lining.

Care shall be taken to maintain full lining thickness at the intersection of branch and pipeline barrels.

- h) All hand finishing work in a section of pipeline, including hand patching of defective lining, shall be completed within 24 hours after completion of the machine application of mortar lining to that section. If necessary application of mortar lining by machine shall be delayed or stopped to assure compliance with this provision.
- i) The cost of hand application of mortar lining and all hand finishing work shall be included in the rate for lining.
- j) Hand applied linings of specials (bends, tees, reducers, etc.) of nominal diameter 600 mm and larger to be handled or transported after application of the lining and windows at access openings for all pipe diameters shall be reinforced by tack-welding 100 mm x 50 mm x 2,5 mm diameter steel mesh to the inside of the pipe in such a way that it is not in contact with the pipe except where welded. The minimum cover over the mesh shall be 10 mm.

PLS 6.5 Spigot and Socket Joints for steel pipes

Refer to Figure 1 at the end of this specification

At spigot and socket pipe ends the internal protection shall be done in accordance with the following:

Tender
Part C3: Construction

C3.4.4-79

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- Prior to the joining of the pipes the vertical surfaces of the cement-mortar lining and the steel surfaces of both pipes shall be coated with a slurry. Mix a bonding agent (Supercrete from Samson or a similar product approved by the Engineer) with water (2:1 ratio) to form the slurry. The surface of the cement-mortar must be wet when it is coated with the slurry. Mix the slurry with an expansive cementitious grout (Standard Bedding grout from Samson or a similar product approved by the Engineer). While the slurry is still wet the grout shall be trowelled to the vertical surface of the cement-mortar lining in the socket.
- Alternatively mix Multibond SBR 1070 with water (1:3 ratio) to form a slurry. Mix cement with sieved plaster sand (1:1 ratio). Add the Multibond/water slurry to the cement/sand mix (1:3 ratio) to form a mortar. Apply the Multibond/water slurry to the steel surfaces and wet vertical surfaces of the factory cement mortar lining and wait till it is tacky and then apply the mortar to the vertical surface of the cement-mortar lining in the socket.
- Push the spigot into the socket and tack weld. The excess grout which has been squeezed out of the joint shall then be removed from the pipe and the joint shall be smoothed with scraper or a sponge on a rope where man access into the pipe is not feasible. Complete the welding before any movement at the joint is allowed and while the grout is still wet.
- The joint shall be welded at low amps and with thin rods to reduce the temperature of the steel at the grout.

All mix ratios above are per volume.

The Contractor shall keep the joint covered with wet hessian on the outside until it is covered with soil to ensure proper curing of the mortar.

The Contractor shall conduct tests to determine the optimum jointing procedure and to proof that the above methods are producing satisfactory results (to the satisfaction of the Engineer) before installation of the pipes commences. If the pipeline is not accessible for visual internal inspection of the joints, the Contractor shall conduct CCTV inspections of the joints immediately after the completion of the first ten joints and a regular basis thereafter to proof the quality of the joint repairs.

PLS 6.6 Moving of pipes

Lined pipes shall not be moved for a period of 7 days and not be transported for a period of 14 days after completion of the lining. Covers on both pipe ends are required during transport and storing at the factory and on site. The manufacturer of the pipes shall ensure that covers remain intact and on the pipe ends at the factory and during transport and off-loading on site.

Tender
Part C3: Construction

C3.4.4-80

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS 7 THICKNESS AND SURFACE FINISH OF LINING

PLS 7.1 The minimum mean thickness of the lining shall be 12 mm per measurement station. The range of mean thickness shall be between 12 and 15 mm. A lining with a thickness of less than 7 mm at any point is unacceptable. The thickness of lining on specials shall generally comply with the above provided that the minimum cover of mortar over reinforcement shall not be less than 10 mm. The maximum unbiased standard deviation of thickness shall be 3 mm. The thickness statistics shall be calculated for each measurement station and for all stations in a pipe section between access openings.

PLS 7.2 The finished surface shall be uniformly smooth with no trace of sand or gritty particles. After trowelling the finished surface shall be examined by the Engineer or his representative for quality, and the Contractor shall provide adequate interior lighting for this purpose. The Contractor shall request all inspections in writing once the Contractor has executed his own quality control inspections and must give the Engineer at least 48 hours' notice of his inspection requirements. Adequate time must be allowed for the Engineer to carry out the inspections. Ridges or uneven build-up caused by irregularity in the travel rate of the machine shall be a cause for rejection of a lining. A "pock mark" or "orange peel" effect shall also be a cause for the rejection of a lining. In all cases the Engineer's decision on quality will be final.

PLS 7.3 The lining shall be well finished with a smooth surface free from excessive laitance and surface irregularities. Projections exceeding a height of 1,5mm shall be removed by trowelling before the cement-mortar has set, or by grinding after the lining has cured.

The thickness of the laitance, if any, shall not exceed 10% of the thickness of the lining, or 1,25mm, whichever is less.

PLS 7.4 The lining surface finish will be measured using a 305mm long straight edge and a 1,6 mm feeler gauge. At each measurement station the gaps between the lining and a straight edge laid parallel to the pipe axis at opposite ends of the pipe diameter, shall be checked to see if they are greater than 1,6mm. Any one or more gaps bigger than 1,6 mm will result in a failure being recorded for that straight edge location.

PLS 7.5 The ends of only one pipe diameter at each measurement station shall be checked for surface finish and this diameter shall change in a clockwise rotation of 45 degrees to the adjacent diameter at the next measurement station. The surface finish pass rate for a pipe section is the number of straight edge locations measured less the number of failures, expressed as a percentage of the measured locations.

The lining surface finish shall be free from excessive number of defects and shall have a minimum pass rate of 50 percent.

Tender
Part C3: Construction

C3.4.4-81

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS 8 CURING

PLS 8.1 Curing operations shall begin immediately following completion of machine mortar lining of a section of pipeline or the hand mortar lining of an access point, bend, branch, taper, special or access opening. The section of lined pipe shall be sealed off with airtight covers or removable bulkheads over all openings and the lining shall be maintained in a moist condition by the addition of water until in- situ lined pipes are filled with water or for at least 42 days for shop applied linings or up to the date the pipes are delivered to site if it is done between 14 days and 42 days after cement mortar lining. The construction contractor shall be responsible to maintain the cement mortar in a moist condition up to at least 42 days after manufacturing, should the pipes be on site before the expiring of the 42 day period. The method of curing is subject to the approval of the Engineer.

PLS 8.2 The Contractor shall inspect each section that is undergoing curing daily to ensure it has adequate curing moisture and that all seals are in place. If necessary water shall be added to maintain a moist lining and any seal found damaged shall be replaced.

PLS 8.3 The exterior surfaces of pipe exposed to sunlight shall be covered with a minimum of three layers of hessian which shall be sprinkled with water and kept damp in the daytime during the period of lining, finishing and curing so as to prevent cracking of the lining due to temperature effects.

PLS 8.4 During curing period steps shall be taken when necessary to prevent the temperature of the steel shell falling below 2°C.

PLS 8.5 Steam Curing of Shop Applied Linings

The Contractor has to prove that the pipe coating will not be damaged during steam curing.

Immediately after application of the cement-mortar lining, the ends of the pipe shall be completely sealed. After the lined pipe has been standing for not less than 2 hours, steam shall be so injected into it as to raise the temperature at a rate not exceeding 28°C per hour until the temperature of the lining is within the range 55-70°C. Steaming shall continue for a further 6 hours, the temperature of the lining being maintained within the range specified. Steaming shall be discontinued and the pipes shall remain sealed for a further 2 days from the time that the temperature of the pipe has fallen to ambient. During this period precautions shall be taken to prevent the temperature of the steel falling below 2°C.

During the curing cycle, excluding the 2 day holding period, the temperature of at least one pipe out of that day's production, shall be recorded by a suitable automatic recording instrument. If the temperature record reveals that the requirements set out above have not been achieved, then the pipes shall be subjected to the full curing period of at least 7 days.

Tender
Part C3: Construction

C3.4.4-82

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLS 8.6 The manufacturer must ensure that the type and quality of the pipe end covers is adequate to ensure it remains intact during storing, transporting and handling.

PLS 9 INSPECTION OF LINING

PLS 9.1 As soon as the lining has hardened to the stage that it will not be damaged by workmen or their means of transport in the pipe, the lined surfaces shall be inspected for surface finish, thickness and other defects and the defective area shall be marked for repair. The Contractor shall provide facilities for lighting and inspection.

PLS 9.2 The Contractor shall make available a suitable trolley for the sole use of the Engineer and/or his representatives.

PLS 9.3 In each pipe section that has been lined and trowelled in a day's run, measurement stations will be marked out at 10 m spacing. The lining at each measurement station will be checked for thickness at 8 points on the pipe circumference, 45 degrees apart starting at the crown of the pipe. The lining thickness at all edges (branches, tees, etc.) will be checked.

PLS 9.4 The lining thickness will be determined with a hand held eddy current thickness gauge supplied by the Contractor that has been calibrated against known thicknesses of mortar taken from the same day's batch of mortar. The thickness gauge will also be used to locate and mark areas of lining between measurement stations that are too thin or too thick.

PLS 9.5 The cured lining of each pipe and special applied in a shop shall be inspected visually for defects before the pipe leave the factory.

PLS 9.6 The inspections and measurements shall be done by the Contractor, to the approval of the Engineer.

PLS 10 DEFECTS

PLS 10.1 Defects in cement-mortar lining which may include but are not limited to sand pockets or porous spots, voids, blisters, excessively cracked areas, excessively debonded areas, areas of lining thinner or thicker than specified, areas of unsatisfactory surface finish and mortar that does not meet the strength requirements shall be repaired by the Contractor notwithstanding that the lined area may previously have been inspected and passed by the Engineer. This may involve the removal of large sections of lining, re-cleaning of the pipe surface and re-lining of the pipe, the costs of which shall be borne by the Contractor.

PLS 10.2 Small defective areas shall be repaired by manual removal of the defective lining and by hand application of mortar lining within 24 hours after lining application. All defective concrete shall be

Tender
Part C3: Construction

C3.4.4-83

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

removed and the surrounding area of concrete chipped back to a position where the concrete is firmly bonded to the steel. In removing the defective lining, the mortar shall be cut back to a square shoulder and no chamfered joints will be permitted. Defective areas encompassing the full circumference of the pipe shall be replaced by machine application.

PLS 10.3 Cracks bigger than 1,0 mm shall be repaired by brushing and wiping of cement slurry into the cracks.

PLS 10.4 Defective lining rejected at the time of lining shall be removed before the initial set of the mortar. The removal and disposal of material shall be at the Contractor's expenses.

PLS 10.5 Defective lining removed from the pipeline, waste cement-mortar from trial mixes, cleaning of pump hoses and equipment, and any other debris from the lining operations, shall be collected and temporarily deposited in a suitable heap or container and shall not litter the site. It shall be transported off site twice a week and disposed of.

PLS 11 SAMPLES AND TESTS

The cost of supplying samples and making any test shall be borne by the Contractor unless prior arrangement for payment is agreed to in writing by the Engineer. The Contractor is to allow for these costs in his price.

PLS 12 BACKFILLING OF EXCAVATIONS

Backfilling of the excavations may only be carried out after the welding and repair of coating have been approved by the Engineer.

PLS 13 DISPOSAL OF UNDESIRABLE MATERIAL

All material and debris removed from the pipeline shall be loaded, transported and disposed of at approved dumping sites. The removal and disposal of all such material shall be included in the rates for cleaning.

Tender
Part C3: Construction

C3.4.4-84

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1


Witness 2

Employer

Witness 1

Witness 2

FIGURE 1
 SPIGOT & SOCKET PIPE END



Tender
 Part C3: Construction

C3.4.4-85

C3.4.4
 Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLT: FLOW METERS (GENERAL)

INDEX

| Item | Description | Page No |
|--------|--|-----------|
| PLT 1 | SCOPE | C3.4.4-87 |
| PLT 2 | IN-LINE ULTRASONIC FLOW METERS | C3.4.4-87 |
| PLT 3 | CLAMP-ON ULTRASONIC FLOW METERS..... | C3.4.4-88 |
| PLT 4 | FLANGED MECHANICAL TURBINE METERS..... | C3.4.4-89 |
| PLT 5 | ELECTROMAGNETIC FLOW METERS | C3.4.4-90 |
| PLT 6 | DIGITAL INDICATOR/INTEGRATOR | C3.4.4-91 |
| PLT 7 | INSTRUMENT PANELS | C3.4.4-92 |
| PLT 8 | SURGE PROTECTION | C3.4.4-93 |
| PLT 9 | SIGNAL CABLE | C3.4.4-93 |
| PLT 10 | EARTHING..... | C3.4.4-93 |
| PLT 11 | EQUIPOTENTIAL BAR | C3.4.4-94 |
| PLT 12 | LABELS | C3.4.4-94 |
| PLT 13 | GENERAL REQUIREMENTS..... | C3.4.4-94 |
| PLT 14 | COMMISSIONING | C3.4.4-94 |

Tender
Part C3: Construction

C3.4.4-86

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLT 1 SCOPE

This section of the Specification deals with the supply, delivery, installation and commissioning of:

- a) in line ultrasonic flow meters;
- b) clamp on ultrasonic flow meters
- c) flanged mechanical turbine meters
- d) electromagnetic flow meters.

PLT 2 IN-LINE ULTRASONIC FLOW METERS

PLT 2.1 General Requirements

An in-line ultrasonic flow meter will consist of:

- a) Two machined, stainless steel, weld-on sockets with inserted perspex windows, which are held by two plastic flanges secured with stainless steel bolts and spring washers.

The tenderer shall be responsible for the welding of the sockets on to the pipeline, as well as making good all corrosion protection according to applicable specifications.

- b) Two 1 MHz sensing units, connected via co-axial cables of 50 ohms, with a minimum length of 12 m, to the transmitter.

The sensing units are to be removable under full pressure, while the pipeline is operating.

Both sensing units shall be electrically isolated from the pipeline.

- c) A transmitter that shall have two output circuits:
 - i. One circuit for the 4-20 mA output signal to drive an indicator, and if later required a recorder, with maximum load capacity of 1 000 ohm.
 - ii. The second circuit to drive a 24 V integrator, with a 2% zero flow cut off.

All power requirements other than 230 V will have to be provided for by the successful Tenderer.

The transmitter shall have facilities to adjust for the various pipe diameter and flow rates.

Tender
Part C3: Construction

C3.4.4-87

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLT 3 CLAMP-ON ULTRASONIC FLOW METERS

PLT 3.1 General Requirements

Single channel flow meters operated in transit time or time-of-flight mode shall be provided unless otherwise specified. The flow meter provided shall be capable of measuring the instantaneous flow in a pipeline and give the accumulated flow. The installation shall comprise at least two (2) sensing units (transducers) that are connected via co-axial cables and connected to a signal conversion unit. The signal unit shall be locally programmable and shall be supplied complete with programmer unit. The signal converter shall further more have a LCD display for instantaneous flow and totalize flow and shall have a 4-20 mA and pulsed output for remote indications. The signal converter unit will be mounted in an outdoor type cubicle, which will be supplied and installed under the electrical portion of the Contract.

Welding of transducers onto the pipe will not be allowed.

The IP rating for the housing of the transducers shall be *submersible*.

The mountings on the transducers shall be manufactured by stainless steel.

The location of the flow meter installation shall be indicated on the relevant drawings, together with the following general information:

- Pipe outer diameter
- Pipe material
- Pipe wall thickness
- Internal lining
- Average thickness of internal lining
- Fluid to be measured
- Distance between transducers and signal converter
- The operating temperature for all equipment shall be minimum -10°C and maximum 55°C.

PLT 3.2 Flow Accuracy

The flow accuracy (velocity) shall be $\pm 1\%$ of reading for pipe diameter greater than 150mm and flow velocities greater than 0.3 m/s. For pipe diameters smaller than 150mm, the flow accuracy shall be $\pm 3\%$.

The overall rangeability or turn-down ratio shall be at least 400:1.

The repeatability for clamp-on transducers shall be 0.2 to 0.5% of full scale reading.

Tender
Part C3: Construction

C3.4.4-88

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLT 3.3 Calibration

The Contractor shall allow for the calibration of the flow meter one month after installation by Technology Services International of Eskom enterprises. A certificate of calibration shall be submitted to the Engineer, acceptance of which signifies final completion of the installation.

PLT 3.4 Guarantee Period

The ultrasonic flow meter shall be guaranteed for a period of at least **24 Months** from date of **successful commissioning**.

PLT 4 FLANGED MECHANICAL TURBINE METERS

PLT 4.1 Equipment Preferred

All mechanical turbine meters shall be type Sensus or similar and approved.

PLT 4.2 Accuracy

All mechanical meters supplied in terms of this Contract shall perform to an accuracy of better than $\pm 2\%$ error over the meters operating range i.e. between Q_t (transitional flow) and Q_n (continuous flow). The performance characteristics of the meters offered shall be equal to or better than the values tabled below:

| Size (DN) (mm) | Q_{min} (m ³ /h) | Q_t (m ³ /h) | Q_n (m ³ /h) | Q_{max} (m ³ /h) |
|-------------------|----------------------------------|------------------------------|------------------------------|----------------------------------|
| 40 | 0.3 | 0.8 | 40 | 60 |
| 50 | 0.3 | 0.8 | 50 | 90 |
| 80 | 0.5 | 0.8 | 120 | 200 |
| 100 | 0.8 | 1.8 | 230 | 300 |
| 150 | 1.8 | 4 | 450 | 600 |
| 200 | 4 | 6 | 800 | 1200 |
| 250 | 6 | 11 | 1250 | 1600 |
| 300 | 12 | 15 | 1400 | 2000 |
| 400 | 25 | 50 | 2000 | 3000 |
| 500 | 45 | 60 | 3000 | 4500 |
| 600 | 100 | 180 | 3300 | 6500 |
| 800 | 210 | 320 | 6000 | 12000 |

Tender
Part C3: Construction

C3.4.4-89

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLT 4.3 General Requirements

Meters must be fitted with dry dial registers, which comprise 6 digit cyclometer-type totalizers, registering in kiloliters (kl) or m³. These registers must be sealed to prevent ingress of dirt or moisture. The registers, which are to be fitted as standard, must be able to provide one high frequency opto-type pulse output function and two low frequency reed-type pulse output functions. All flow meters shall be provided complete with frequency converter unit and opto coupler. The frequency converter unit will be mounted in an outdoor type cubicle, which will be supplied and installed under the electrical portion of the Contract.

No consideration will be given to meter types, which necessitate the use of special tools or fitment of any form of gland in the process of connecting pulser units, or, meters which require a register-change to switch from one volume unit per pulse to another. Dismantling of registers for this purpose will not be acceptable. Tenderers are to provide full details of these aspects with their tenders.

Cover bolts must be of stainless steel material to facilitate easy removal of mechanisms. Meter bodies must be coated with a high quality sintered epoxy powder coating, both internally and externally, to provide maximum protection against corrosion.

Although most of the meters will be installed horizontally, it must be possible to install the meters vertically (with flow in the upward direction) or in an inclined position (with flow in the upward direction), should site conditions make this necessary.

Tenderers must provide full details of the minimum lengths of straight pipe required upstream and downstream for each size of meter offered, to ensure that the accuracy of the meters remain within the stated limits, under normal operating conditions. Preference will be given to meter types requiring a minimum of straight pipe upstream and downstream, as installation space and lay lengths are at a premium.

The performance of the meters offered shall not be affected by outside magnetic influences.

Details of head loss across the meters offered shall be provided by the Tenderer.

PLT 5 ELECTROMAGNETIC FLOW METERS

PLT 5.1 General Requirements

All electromagnetic flow meters supplied under this contract shall be for high measuring accuracy i.e. $\pm 0.5\%$ of reading plus 0.05% of full scale. The repeatability or reproducibility of measurement

Tender
Part C3: Construction

C3.4.4-90

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

shall be $\pm 0.1\%$ of full scale. The meter shall have a long term zero stability of $\pm 0.2\%$ and linear variation shall be less than 0.2% .

Electrodes shall be manufactured from a high quality metal and shall be removable for cleaning purposes. Removal of electrodes with the line under pressure is preferred.

The minimum downstream and upstream unrestricted straight pipe run required for the specified measurement accuracy shall be stated by the Tenderer.

Although most of the meters will be installed horizontally, it must be possible to install the meters vertically (with flow in the upward direction) or in an inclined position (with flow in the upward direction), should site conditions make this necessary.

The flow meter shall be equipped with a separate mountable signal converter unit complete with sufficient length of signal cable. The signal converter shall be locally programmable and shall be supplied complete with programmer unit. The signal converter shall further more have a LCD display for instantaneous flow and totalized flow and shall have a 4-20 mA and pulsed output for remote indications. The signal converter unit will be mounted in an outdoor type cubicle supplied under the electrical scope of the Contract.

Electromagnetic meters and converters shall be suitable for outdoor installation and shall be adequately protection against lightning.

PLT 6 DIGITAL INDICATOR/INTEGRATOR

The display shall be a 6-digit, 0.56" (14.2mm) High Red L E D, giving a maximum display of 999999. The decimal point shall be selectable.

A flashing display shall be given during totaliser overflow.

The indicator/integrator shall be powered by 230 V AC at 50 Hz.

The indicator/integrator shall be constructed in such a way that it can be calibrated to the required flow and also by means of a selector button, display the accumulated quantity of water released.

The front bezel shall meet NEMA 4/IP65 requirements

The manufacturer of the indicator/integrator shall comply with ISO 9001 and proof of this to be submitted with the tender documents.

The indicator/integrator shall have a lock-out facility to limit operator entry to the programmable settings and totaliser.

Tender
Part C3: Construction

C3.4.4-91

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The totaliser shall have a programmable time base with a scale factor of 0.001 to 100.0 and a low-end cut-out.

The remote indicator/integrator if required is to be fitted into an IP 66 enclosure in such a way that the flow reading is clearly visible with space available for the labelling and surge protection as specified.

PLT 7 INSTRUMENT PANELS

All panels will comply with the minimum requirements for an IP 65 rating.

All cable entries will be fitted with the appropriate cable gland. All cable glands will comply with IP 68.

Each enclosure is to be fitted with an M10 brass bolt and two nuts that will act as an earth bar. All surge protection in the enclosure to be grounded onto this bolt.

a) Local indicator/integrator

An instrument panel is required to house the flow meter power supply unit if required, indicator/integrator and surge protection and shall comply with the following:

1. At least 500 mm high, 400 mm wide and 200 mm deep.
2. Constructed from polycarbonate.
3. The door shall be removable and have concealed hinges and captive, stainless steel hinge pins.
4. Be fitted with a plain painted metal chassis of at least 2.5 mm thick.
5. Be fitted with a polyester internal door for mounting of the totaliser.
6. The external door shall be fitted with a window that allows sight of the totaliser.
7. The external door shall have an extruded polyurethane seal fitted to a groove.
8. Only two closure points that are situated outside the sealed area. At least one of the closure points shall be lockable with a cylindrical barrel type lock and two keys shall be supplied for this lock.
9. Shall be wall mountable with 4 stainless steel brackets giving a space of at least 10 mm between the enclosure and the wall.

b) Remote indicator/integrator (if required)

An instrument panel is required to house the remote indicator/integrator and surge protection and shall comply with the following:

Tender
Part C3: Construction

C3.4.4-92

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

1. Constructed from polycarbonate.
2. The door shall be removable and have concealed hinges and captive, stainless steel hinge pins.
3. Fitted with a polyester internal door or stand-offs for mounting of the totaliser.
4. The external door shall be fitted with a window that allows sight of the totaliser.
5. The external door shall have an extruded polyurethane seal fitted to a groove.
6. Only two closure points which are situated outside the sealed area. At least one of the closure points shall be lockable with a cylindrical barrel type lock and two keys shall be supplied for this lock.
7. Shall be wall mountable with 4 stainless steel brackets giving a space of at least 10 mm between the enclosure and the wall.

PLT 8 SURGE PROTECTION

Single phase 230 V AC medium protection units that are certified to withstand surges of up to 75kA.

Two wire, 230 V AC fine protection units that are certified to withstand surges of up to 40kA.

Two wire, 24 V AC fine protection units that are certified to withstand surges of up to 40kA.

Two explosion proof, pipeline spark gaps rated to withstand surges of up to 100kA, complete with pipeline mounting brackets and a fly lead of at least 300mm.

All surge protection units must be grounded to a common earth point in the panel that houses the ultra sonic flow meter. If a nut and bolt arrangement is used it shall be at least an M10 and shall be made of brass. Care has to be taken to ensure that the nut and bolt do not negate the IP 65 rating of the enclosure.

PLT 9 SIGNAL CABLE

All signal cable to be 1,5 mm², 4 core, twisted pair, braided screened cable.

PLT 10 EARTHING

The successful Tenderer is to supply 70 mm², stranded copper cable as well as lugs that will fit the cable and an M10 bolt to connect between the equipotential bar and earth mat.

The successful Tenderer is to supply 16 mm², green PVC insulated, stranded copper cable to connect between the common earth at the instrument panel and the equipotential bar.

Tender
Part C3: Construction

C3.4.4-93

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLT 11 EQUIPOTENTIAL BAR

An equipotential bar with cover must be suitably mounted within each flow meter chamber. Modular terminals should be provided to accommodate 3 connections of up to 16 mm², 3 connections of 16 - 95 mm² and 3 for flat connections up to 30 mm wide.

PLT 12 LABELS

Two types of labels are required. One for the site and installation name, the other giving details of the flow meter characteristics.

Labels to be manufactured from plastic engraved stock with white lettering on a black base.

Lettering to be 10 or 6 mm high x 5 and 3 mm wide and labels to be at least 105 mm X 30 mm.

All labels to be fitted with at least two strips of 12 mm wide double sided tape that run for the total length of the label.

PLT 13 GENERAL REQUIREMENTS

All screws, brackets, cable saddles, nuts, bolts, washers etc. used in the installation of the equipment shall be from stainless steel.

Before delivery to site all equipment and all parts supplied under this contract will be checked and certified at the supplier's workshop to ensure that they are in working condition by a delegated representative of the client.

PLT 14 COMMISSIONING

The equipment as supplied under this Contract shall be commissioned after **one fault free month** of operation.

If during this month the equipment or any part thereof should fail the successful Tenderer shall repair the equipment at his own expense and once again leave the equipment to operate for one fault free month before commissioning. All costs incurred shall be for the successful Tenderer's account. This cycle to continue until one fault free month has been attained.

Tender
Part C3: Construction

C3.4.4-94

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLTP: MANUFACTURE, SUPPLY AND TESTING OF THERMOPLASTIC PIPES

INDEX

| Item | Description | Page No |
|-------------|---|----------------|
| PLTP 1 | SCOPE | C3.4.4-96 |
| PLTP 2 | STANDARDS | C3.4.4-96 |
| PLTP 3 | CERTIFICATION, DOCUMENTATION AND QUALIFICATIONS | C3.4.4-100 |
| PLTP 4 | MATERIALS | C3.4.4-101 |
| PLTP 5 | WELDING | C3.4.4-102 |
| PLTP 6 | TESTING | C3.4.4-102 |
| PLTP 7 | HANDLING AND INSTALLATION | C3.4.4-104 |

Tender
Part C3: Construction

C3.4.4-95

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLTP 1 SCOPE

This Specification covers the manufacturing, supply, installation and testing of thermoplastic pipes and fittings.

PLTP 2 STANDARDS

The latest revisions of the following Standards shall be applicable.

| COMMONLY USED STANDARDS FOR PLASTIC PIPING SYSTEMS | |
|--|--|
| SANS 15874-1 | Plastics piping systems for hot and cold water installations - Polypropylene (PP) Part 1: General |
| SANS 15874-2 | Plastics piping systems for hot and cold water installations - Polypropylene (PP) Part 2: Pipes |
| SANS 15874-3 | Plastics piping systems for hot and cold water installations - Polypropylene (PP) Part 3: Fittings |
| SANS 15874-5 | Plastics piping systems for hot and cold water installations - Polypropylene (PP) Part 5: Fitness for purpose of the system |
| SANS 15875-1 | Plastics piping systems for hot and cold water installations - Crosslinked polyethylene (PE-X) Part 1: General |
| SANS 15875-2 | Plastics piping systems for hot and cold water installations - Crosslinked polyethylene (PE-X) Part 2: Pipes |
| SANS 15875-3 | Plastics piping systems for hot and cold water installations - Crosslinked polyethylene (PE-X) Part 3: Fittings |
| SANS 15875-5 | Plastics piping systems for hot and cold water installations - Crosslinked polyethylene (PE-X) Part 5: Fitness for purpose of the system |
| SANS 1601 | Structured wall pipes and fittings of unplasticized poly(vinyl chloride) (PVC-U) for buried drainage and sewerage systems |
| SANS 16422 | Pipes and joints made of oriented unplasticized poly(vinyl chloride) (PVC-O) for the conveyance of water under pressure - Specifications |
| SANS 2001-DP1 | Construction works Part DP1: Earthworks for buried pipelines and prefabricated culverts |
| SANS 2001-DP4 | Construction works Part DP4: Sewers |
| SANS 21138-1 | Plastics piping systems for non-pressure underground drainage and sewerage - Structured-wall piping systems of unplasticized poly(vinyl chloride) (PVC-U), polypropylene criteria for pipes, fittings and system polyethylene (PE) Part 1: Material specifications and performance(PP) |

Tender
Part C3: Construction

C3.4.4-96

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| COMMONLY USED STANDARDS FOR PLASTIC PIPING SYSTEMS | |
|--|---|
| SANS 21138-2 | Plastics piping systems for non-pressure underground drainage and sewerage - Structured-wall piping systems of unplasticized poly(vinyl chloride) (PVC-U), polypropylene (PP) and polyethylene (PE) Part 2: Pipes and fittings with smooth external surface, Type A |
| SANS 21138-3 | Plastics piping systems for non-pressure underground drainage and sewerage - Structured-wall piping systems of unplasticized poly(vinyl chloride) (PVC-U), polypropylene (PP) and polyethylene (PE) Part 3: Pipes and fittings with non-smooth external surface, Type B |
| SANS 21307 | Plastics pipes and fittings – butt fusion jointing procedures for polyethylene (PE) pipes and fittings |
| SANS 22391-1 | Plastics piping systems for hot and cold water installations - Polyethylene of raised temperature resistance (PE-RT) Part 1: General |
| SANS 22391-2 | Plastics piping systems for hot and cold water installations - Polyethylene of raised temperature resistance (PE-RT) Part 2: Pipes |
| SANS 22391-3 | Plastics piping systems for hot and cold water installations - Polyethylene of raised temperature resistance (PE-RT) Part 3: Fittings |
| SANS 370 | Steel mesh reinforced polyethelene (PE) pipes for water supply |
| SANS 4427-1 | Plastics piping systems - Polyethylene (PE) pipes and fittings for water supply - Part 1: General |
| SANS 4427-2 | Plastics piping systems - Polyethylene (PE) pipes and fittings for water supply - Part 2: Pipes |
| SANS 4427-3 | Plastics piping systems - Polyethylene (PE) pipes and fittings for water supply - Part 3: Fittings |
| SANS 4427-5 | Plastics piping systems - Polyethylene (PE) pipes and fittings for water supply - Part 5: Fitness for purpose of the system |
| SANS 4437-1 | Plastics piping systems for the supply of gaseous fuels - Polyethylene (PE) Part 1: General |
| SANS 4437-2 | Plastics piping systems for the supply of gaseous fuels - Polyethylene (PE) Part 2: Pipes |
| SANS 4437-3 | Plastics piping systems for the supply of gaseous fuels - Polyethylene (PE) Part 3: Fittings |
| SANS 4437-5 | Plastics piping systems for the supply of gaseous fuels - Polyethylene (PE) Part 5: Fitness for purpose of the system |
| SANS 674 | Steel-reinforced spirally wound PE drainage and sewer pipes |
| SANS 791 | Unplasticized poly(vinyl chloride) (PVC-U) sewer and drain pipes and pipe fittings |
| SANS 8772 | Plastics piping systems for non-pressure underground drainage and sewerage - Polyethelene (PE) |

Tender
Part C3: Construction

C3.4.4-97

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| COMMONLY USED STANDARDS FOR PLASTIC PIPING SYSTEMS | |
|--|--|
| SANS 8773 | Plastics piping systems for non-pressure underground drainage and sewerage - Polypropylene (PP) |
| SANS 966-1 | Components of pressure pipe systems Part 1: Unplasticized poly(vinyl chloride) (PVC-U) pressure pipe systems |
| SANS 966-2 | Components of pressure pipe systems Part 2: Modified poly(vinyl chloride)(PVC-M) pressure pipe systems |
| SANS 967 | Unplasticized poly(vinyl chloride) (PVC-U) soil, waste and vent pipes and pipe fittings |
| EN 13476-1 (Parts 1, 2 and 3) and ISO 9969 | PE structured wall sewer pipes |

| STANDARDS RELEVANT TO THE MATERIAL AND RAW MATERIAL QUALITY FOR THERMOPLASTIC PLASTIC PIPING SYSTEMS | |
|---|---|
| SANS 1133 | Plastics - Determination of the melt mass-flow rate (MFR) and the melt volume-flow rate (MVR) of thermoplastics |
| SANS 2505 | Thermoplastics pipes - Longitudinal reversion - Test method and parameters |
| SANS 2507-1 | Thermoplastics pipes and fittings - Vicat softening temperature Part 1: General test method |
| SANS 3127 | Thermoplastics pipes - Determination of resistance to external blows - Round-the-clock method |
| SANS 9227 | Corrosion tests in artificial atmospheres - Salt spray tests |
| SANS 9852 | Unplasticized poly(vinyl chloride) (PVC-U) pipes - Dichloromethane resistance at specified temperature (DCMT) - Test method |

| STANDARDS FOR THE INSTALLATION PROCEDURES AND WELDING APPLICATIONS OF PLASTIC PIPING SYSTEMS | |
|---|---|
| SANS 10089-3 | The petroleum industry Part 3: The installation, modification, and decommissioning of underground storage tanks, pumps/dispensers and pipework at service stations and consumer installations |
| SANS 10252-1 | Water supply and drainage for buildings Part 1: Water supply installations for buildings |
| SANS 10252-2 | Water supply and drainage for buildings Part 2: Drainage installations for buildings |
| SANS 10254 | The installation, maintenance, replacement and repair of fixed electric storage water heating systems |
| SANS 10268-1 | Welding of thermoplastics - Welding processes Part 1: Heated-tool welding |

Tender
Part C3: Construction

C3.4.4-98

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| STANDARDS FOR THE INSTALLATION PROCEDURES AND WELDING APPLICATIONS OF PLASTIC PIPING SYSTEMS | |
|---|--|
| SANS 10268-2 | Welding of thermoplastics - Welding processes Part 2: Electrofusion welding |
| SANS 10268-3 | Welding of thermoplastics - Welding processes Part 3: Hot-gas welding |
| SANS 10268-4 | Welding of thermoplastics - Welding processes Part 4: Hot-gas extrusion welding |
| SANS 10268-5 | Welding of thermoplastics - Welding processes Part 5: Solvent welding |
| SANS 10268-6 | Welding of thermoplastics - Welding processes Part 6: Ultrasonic welding, staking and insertion |
| SANS 10268-10 | Welding of thermoplastics - Welding processes Part 10: Weld defects |
| SANS 10269 | Welding of thermoplastics - Testing and approval of welders |
| SANS 10270 | Welding of thermoplastics - Approval of welding procedures and welds |
| SANS 1655 | Welding of thermoplastics - Welding rods, fillers and solvents |
| SANS 1671-1 | Welding of thermoplastics - Machines and equipment Part 1: Heated-tool welding |
| SANS 1671-2 | Welding of thermoplastics: Machines and equipment Part 2: Electrofusion welding |
| SANS 1671-3 | Welding of thermoplastics - Machines and equipment Part 3: Hot-gas welding |
| SANS 1671-4 | Welding of thermoplastics - Machines and equipment Part 4: Hot-gas extrusion welding |
| SANS 1671-6 | Welding of thermoplastics - Machines and equipment Part 6: Ultrasonic welding, staking and insertion |
| SANS 6269 | Welding of thermoplastics - Test methods for welded joints |

| STANDARDS USED TO DETERMINE THE STRENGTH AND DIMENSIONAL REQUIREMENTS AND TOLERANCES FOR PLASTIC PIPING SYSTEMS | |
|--|--|
| SANS 130-1 | Thermoplastics pipes, fittings and assemblies for the conveyance of fluids - Determination of the resistance to internal pressure Part 1: General method |
| SANS 9080 | Plastics piping and ducting systems - Determination of the longterm hydrostatic strength of thermoplastics materials in pipe form by extrapolation |
| SANS 11922-1 | Thermoplastics pipes for the conveyance of fluids - Dimensions and tolerances Part 1: Metric series |

| ADDITIONAL INTERNATIONAL STANDARDS FOR TESTING OF PLASTIC PIPING SYSTEMS | |
|---|--|
| ISO 6259-1 | Thermoplastics pipes - Determination of tensile properties - Part 1: General test method |

Tender
Part C3: Construction

C3.4.4-99

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

| ADDITIONAL INTERNATIONAL STANDARDS FOR TESTING OF PLASTIC PIPING SYSTEMS | |
|--|---|
| ISO 6259-2 | Thermoplastics pipes - Determination of tensile properties - Part 2: Pipes made of unplasticized poly(vinyl chloride) (PVC-U), chlorinated poly(vinyl chloride) (PVC-C) and high-impact poly(vinyl chloride) (PVC-HI) |
| ISO 11357-6 | Plastics - Differential scanning calorimetry (DSC) - Part 6: Determination of oxidation induction time (isothermal OIT) and oxidation induction temperature (dynamic OIT) |
| ISO 13761 | Plastics pipes and fittings - Pressure reduction factors for polyethylene pipeline systems for use at temperatures above 20 °C |
| ISO 18553 | Method for the assessment of the degree of pigment or carbon black dispersion in polyolefin pipes, fittings and compounds |
| ISO 18553 Amd 1 2007 | Method for the assessment of the degree of pigment or carbon black dispersion in polyolefin pipes, fittings and compounds (AMENDMENT 1) |
| ISO 21307 | Plastics pipes and fittings - Butt fusion jointing procedures for polyethylene (PE) pipes and fittings used in the construction of gas and water distribution systems |

PLTP 3 CERTIFICATION, DOCUMENTATION AND QUALIFICATIONS

All plastic pipes and fittings have to comply with the relevant SANS Specification and shall be certified accordingly by authorities accredited by SANAS (South African National Accreditation System), for example SABS and SATAS.

Pipe manufacturers have to be members of SAPPMA (South Africa Plastic Pipe Manufacturers Association).

The Contractor shall submit the following documentation of the manufacturers to the Engineer before commencement of the manufacturing of pipes and fittings:

- Proof of current SANS Standard certification for product.
- SANAS accreditation of the certification authority (e.g. SABS or SATAS).
- SAPPMA certificate in order to ensure adherence to the SAPPMA/IFPA code of conduct and quality assurance standards.
- ISO 9001:2015 quality control accreditation.

All pipes shall be marked with the date and time of production, relevant SANS Standard, mark of certification authority (e.g. SABS or SATAS), SAPPMA mark of quality reassurance, pipe diameter and pressure / strength class.

Tender
Part C3: Construction

C3.4.4-100

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The following work must be performed by IFPA (Installation Fabrication Plastics Pipe Association) members:

- All fabricated fittings and specials manufactured from HDPE pipe or PVC pipe.
- All on site welding/gluing and fabrication work on Site.

IFPA members are bound by a code of conduct calling for full compliance to policies and local standards. IFPA members are able to prove full traceability to all its employees performing IFPA related tasks.

The Contractor shall provide the necessary training to its employees to ensure IFPA standards are maintained. The Contractor shall submit its IFPA member certificate to the Engineer before commencement of manufacturing and construction.

PLTP 4 MATERIALS

PLTP 4.1 General

The following documentation shall be submitted by the Contractor to the Engineer before manufacturing:

- Certificate of Analysis (raw material)
- Quality Certificates (SABS, SATAS, etc.)
- Quality Control Plan

Inspection Documents shall comply with BS EN 10204 and shall be submitted by the Contractor to the Engineer. Unless otherwise specified in the Specifications or by the Engineer, Inspection Documents Type 3.1 are required.

Delivery of material shall only commence upon completion of the minimum required Batch Released Tests (BRT).

Quality systems shall be in accordance with SANS ISO 9001:2015 including Product Quality Plans for all products.

PLTP 4.2 PVC-O Pipes

PVC-O pipes shall be Class 500 with material properties as specified in paragraphs 4.1 and 4.2 of Technical Specification prCEN/TS 15223:2007(E) published by the European Committee for Standardization (CEN).

Tender
Part C3: Construction

C3.4.4-101

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLTP 4.3 High Density Polyethylene (HDPE) Pipes

Only unprocessed PE 100 polymer compliant to SANS ISO 4427-1 shall be used. This requirement shall be validated by the manufacturer.

PLTP 5 WELDING

Refer to PLTP 2 for the relevant welding standards.

The Contractor shall be responsible for the following:

- Compiling of Preliminary Welding Procedure Specification, recording of qualification welds and conducting of 3rd party testing;
- Compiling of Welding Procedure Specification and Qualification Report with required testing;
- Compiling of Final Welding Procedure Specification;
- On-site 3rd party inspections;
- Compiling of Welding Quality Packs with inspection reports, COC's, COA's, Certificates, etc.

Employees responsible for electro-fusion or butt welding of HDPE pipes shall have (as a minimum) a certificate of competence at NQF Level 2 (in accordance to SANS 10268).

Welders shall be trained and qualified for a specific pipe diameter and class and for a specific welding process (e.g. butt, electro-fusion, socket fusion, hot gas extrusion) by Plastics SA. On successful completion of training the welder shall be tested and certified in accordance with SANS / ISO 10269 – Testing and approval of welders.

The IFPA stamp is required at all welds.

Calibration Certificates are required for welding equipment and welding machines shall be able to produce accurate welding reports.

PLTP 6 TESTING

PLTP 6.1 Hydrostatic pressure testing of spigot / socket joints

At least three spigot / socket joints per batch of uPVC pipes shall be subjected to the one hour test as described in Section 5.8 of SANS 966 Part 1 at a laboratory approved by the Engineer. The Engineer shall be provided the opportunity to witness these tests. Should any of the tests fail, the associated uPVC pipe batch will be rejected.

Tender
Part C3: Construction

C3.4.4-102

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLTP 6.2 Testing of HDPE butt-weld connections

Quality control testing during butt-welding of HDPE pipes will be required. In addition, the welder shall be separately qualified for all pipe sizes to be welded. The quality control testing for qualifying the welder shall be as follows:

- a) Observe the joining process to confirm that the proper butt-welding procedure is being followed.
- b) Visually inspect the joint and compare it to a sample or picture of an acceptable joint.
- c) Allow the joint to cool for at least one hour.
- d) A 300 mm wide ring section of the HDPE pipe shall be cut with the butt-weld joint centered as illustrated in Figure 1. Cut four strips lengthwise through the joint area, 90 degrees apart for visual examination and bend testing. The width of the test bend is proportional to the pipe wall thickness. If the pipe wall thickness is less than 25.4 mm, a 25.4 mm wide strip is recommended. If the pipe wall thickness is greater than 25.4 mm, the width of the test strip shall be equal to the pipe wall thickness.
- e) Visually inspect the strap samples for voids, discontinuities, lack of bonding, misalignment, bead size, etc.
- f) The bend testing consists of the following steps:
 - Allow each test strip to cool to a temperature ranging between 18°C and 27°C.
 - Each test strip shall then be clamped in a vice 25.4 mm under the weld bead as illustrated in Figure 2.
 - A steel extension pipe of appropriate diameter and length shall then be slipped over the free end of the specimen to 25.4 mm above the weld bead.
 - The bend test shall be performed by bending the test specimen 180 degrees (minimum 90 degrees) in the direction that places the concave interior surface/root of the pipe wall/weld in tension as illustrated in Figure 2. No failures in the butt-weld area are permitted with all four test strips.
- g) If flaws are observed or develop during bending, try to determine the cause, recheck the procedure, and make another joint.
- h) The welder is disqualified if the second joint is also unacceptable.
- i) Butt-weld of HDPE pipes to be installed shall not commence until a trial fission has passed the bend test.

Tender
Part C3: Construction

C3.4.4-103

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2




Figure 1: Bend strap test detail




Figure 2: Bend strap test detail (side view)

PLTP 7 HANDLING AND INSTALLATION

PLTP 7.1 General

Handling and installation shall comply with guidelines provided in the Technical Manual of SAPPMA (latest edition).

Tender
Part C3: Construction

C3.4.4-104

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLTP 7.2 Ultra Violet (UV) protection

PVC pipes shall be stored under 80% black HDPE UV stabilised shade netting (blocking 80% UV).

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLU: PIPE BORING

INDEX

| Item | Description | Page No |
|-------------|-------------------------------|----------------|
| PLU1 | SCOPE | C3.4.4-107 |
| PLU2 | INTERPRETATIONS | C3.4.4-107 |
| PLU3 | MATERIALS | C3.4.4-107 |
| PLU4 | PLANT | C3.4.4-108 |
| PLU5 | DESIGN | C3.4.4-108 |
| PLU6 | SAFETY | C3.4.4-108 |
| PLU7 | SURVEYING | C3.4.4-109 |
| PLU8 | BLASTING | C3.4.4-109 |
| PLU9 | CONSTRUCTION | C3.4.4-110 |
| PLU10 | TOLERANCES | C3.4.4-112 |
| PLU11 | MEASUREMENT AND PAYMENT | C3.4.4-112 |

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLU PIPE BORING

PLU1 SCOPE

This section covers the insertion by boring of underground pipes without disturbing the surface. The information regarding pipe jacking contained in this section is not limited to the jacking of circular precast concrete pipe sections but also applies in general to the jacking of rectangular, square and arched precast-concrete sections.

The Contractor shall make use of an approved specialist pipe jacking firm.

PLU2 INTERPRETATIONS

For the purposes of this section, the following words and expressions shall have the meanings hereby assigned to them except where inconsistent with the context.

(a) Pilot hole

A hole with a maximum diameter of 50 mm, drilled to ensure that a subsequently bored, larger hole, will be properly aligned.

(b) Pipe boring

The work involved in boring a horizontal hole and inserting a pipe therein. Also referred to as “directional drilling”.

(c) Pipe boring pits

Excavations at either end of the boring operation from and between which boring and pipe installation are carried out.

(d) Reception pit

An excavated shaft located at the end of a bored section of a pipeline.

PLU3 MATERIALS

(a) Pipes – Pipe Boring

Pipes for pipe boring shall be HDPE Class SDR17 PN10.

(b) Other precast-concrete sections

Any precast-concrete sections, other than pipes, to be bored shall comply with the requirements specified in the SABS 1200 or Section 3.4.2 of this document.

Tender
Part C3: Construction

C3.4.4-107

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLU4 PLANT

(a) General

The Contractor shall, provide and use suitable equipment for boring the hole and for jointing and inserting the pipes.

(b) Lighting

The Contractor shall provide adequate lighting for the execution of the Works.

(c) Ventilation

Sufficient ventilation shall be provided to remove dust and to ensure safe working conditions.

PLU5 DESIGN

The Contractor shall furnish detailed design calculations, specifications and working drawings to explain his methods of installation and of providing temporary support for the road, rail track, or other service or structure and any modifications to structures required before pipe boring commences.

The design shall be carried out by a professional engineer with adequate experience in this field. Calculations, specifications and drawings shall be signed by the engineer responsible for their preparation.

PLU6 SAFETY

(a) General

The Contractor shall at all times observe adequate safety precautions on the Site as specified in Section 3.4.3 of this document. Permission to proceed with the Works shall not in any way detract from the obligations and liabilities of the Contractor in regard to such safety or to the adequacy of the boring structures and methods of working.

(b) Safety of existing works

The pipeline shall be bored through under the relevant road, railway or other service or structure without disrupting the traffic and without disturbing the alignment or levels of the road surface, the tracks, or other relevant service or structure to an extent that may impair the safety of traffic or of the service or structure.

Before commencing work in the vicinity of any structure, the Contractor shall make a detailed examination of the structure, record its condition, and submit a copy of such record to the Engineer.

Tender
Part C3: Construction

C3.4.4-108

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLU7 SURVEYING

(a) General

The Contractor shall take measurements before and after each boring operation and shall record any change in line or level (or both) of any road, rail track or other service or structure being traversed. A copy of the records shall be submitted to the Engineer on the same day.

(b) Working under roadways

Before commencing work under a roadway, the Contractor shall measure levels on the road surface directly above the boring line and for a distance of at least 5 m on each side of the boring line. These levels shall be measured at 500 mm intervals and 300 mm from the edges of the surfacing. In order to facilitate control of the measuring of levels, the exact position of each spot height shall be discreetly marked on the road surface before the levels are measured.

After completion of the Works, the Contractor shall remeasure the levels in the same manner as before, and he shall submit to the Engineer the final records of levels taken before and after boring. The submission of such records shall be a prerequisite for any consideration by the Engineer of the acceptability or otherwise of the Works or the issue of any certificate of completion.

If, within the Defects Liability Period, the road shows any sign of settlement in the vicinity of the bored pipe, the road authority may remeasure the levels on the Site.

The Contractor shall be held responsible for the rectification, to the satisfaction of the road authority and the Engineer, of any deformation that occurs in the road surface as a result of the boring operation during the said period of one year.

(c) Checking the alignment of the pipeline

The Contractor shall check the line and the level of the pipeline at least once during the installation of each pipe length and shall take such corrective action as may be necessary. A copy of the results of all checks and a statement of any corrective measures taken shall be available for inspection on the Site, and a copy shall be given to the Engineer on the same day.

PLU8 BLASTING

No blasting will be allowed for pipe boring.

Tender
Part C3: Construction

C3.4.4-109

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLU9 CONSTRUCTION

(a) General

Boring, excavation and other specialized work shall be undertaken only by persons fully conversant with the work.

Boring operations shall commence at the lower level of the pipeline. Should Site conditions necessitate or permit boring to be carried out from the higher level of the pipeline, the Engineer's written approval shall be obtained before the work commences.

The Contractor shall not commence any work until the Engineer has specified, in writing, that the Contractor may proceed.

(b) Excavation

Subject to the provisions of PLU8 above, the appropriate requirements of PSD and PSDB shall apply. The materials excavated shall be classified as follows for payment purposes:

(i) Hard material:

For pipe boring operations, the material penetrated will be classified as hard when the Contractor can prove that the work cannot be efficiently carried out by using normal boring equipment and some other method, such as rock drilling, has to be used.

(ii) Soft material:

All material not classified as hard material.

Notwithstanding the above classification, all material in previously constructed fills, embankments and pavement layers and through which boring is carried out, shall be classified as soft material.

The decision of the Engineer as to the classification of the material shall be final and binding, and any objection as to the classification shall be made before some method other than boring is used.

Special reference shall be made to clause 16 of section 001 regarding the classification of excavated material in restricted areas.

(c) Pipe boring pits

The Contractor shall be responsible for excavating the pits in the positions indicated on the construction drawings at each end of the section of pipeline or sleeve that is to be bored. These pits shall be of dimensions at least equal to the minimum dimensions needed for the Contractor's equipment and for safe and efficient working. The approximate dimensions of

**Tender
Part C3: Construction**

C3.4.4-110

**C3.4.4
Particular Specifications for Civil Works**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

the pits that the Contractor intends to excavate shall be agreed upon with the Engineer before work commences. The excavated material shall be stockpiled for later backfilling. The sides of the pits shall be adequately supported by timbers or by other approved means. Where a pit adjoins a railway line or a heavily used road, the sides of the pit shall be shored during the entire operation to prevent any movement caused by vibration arising from rail or road traffic from occurring.

The Contractor shall ensure that the pits are dewatered at all times.

(d) Pipe boring

After the pipe boring pits have been completed, and on the written instructions of the Engineer, a pilot hole shall be drilled using suitable equipment. After the pilot hole has been inspected and approved, it shall be enlarged by boring to the diameter required for the installation of the specified pipe.

(e) Grouting and sealing

Before the boring operation, the Contractor shall determine, in an approved manner, the average cross-section of the completed excavation ahead of the pipeline and shall submit his calculations to the Engineer on the same day.

These cross-sections, together with the external pipe diameter, shall be used for calculating the approximate volume of grout that will be needed after the entire boring operation has been completed and will assist in determining whether all voids have been grouted.

All holes in the pipeline shall be sealed with an approved epoxy sealant after the grouting has been completed.

The grouting of the pipes installed by means of pipe boring shall be carried out only on the written instructions of the Engineer and in a manner approved by the Engineer.

(f) Backfilling

The pipe boring pits shall be backfilled, only when so instructed by the Engineer, using excavated or imported material compacted to at least the density of the undisturbed surrounding material.

When the installed pipe is part of a pipeline, the boring pits will form part of the pipeline trench and as such shall be backfilled in the manner specified in sections SABS 1200D and DB as applicable. Payment for such backfilling will be made under the applicable sections.

Surplus excavated materials shall be disposed of as specified in the Project Specifications or as determined by the Engineer on Site.

Tender
Part C3: Construction

C3.4.4-111

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PLU10 TOLERANCES

Subject to any requirements of the Section 3.4.2 imposed on account of the gradient(s) of the pipeline or in view of the purpose for which it is required, the pipes shall be positioned within the tolerances given below.

Should the difference between the actual and the specified position or alignment of the finished pipeline exceed the value of the said tolerance to an extent as to involve additional costs in respect of locating, installing, supporting or maintaining any service of which the bored pipe forms part or that has been designed to be laid through the bored structure, the Contractor shall bear such additional costs, provided that the details of the work to be done to relocate, install, or support the said service have been provided and the order for the work to be done (by the Contractor or by others) has been given by the Engineer within 30 working days of the completion of the boring operation.

Permissible tolerance limits shall be as follows:

- (i) In plan ± 100 mm
- (ii) Vertical ± 100 mm

Adjustment to line or level or both shall be gradual, and the manufacturer's permissible angular deflection of the pipes shall not be exceeded at any point.

PLU11 MEASUREMENT AND PAYMENT

PLU11.1 Establishment on Site sum

The tendered lump sums shall include full compensation for the establishment on Site and the subsequent removal of all special equipment and plant for pipe boring, including maintaining the safety of existing structures, services, roads, railways, etc, for bracing, lighting, watching, dewatering and surveying, and for maintaining all temporary works until the work is completed.

This work will be paid for as a lump sum, 80% of which becomes payable when all equipment is on the Site and boring has commenced, and the remaining 20% will become payable after the work has been completed, the equipment removed and the Site reinstated to a condition acceptable to the Engineer.

PLU11.2 Access to and from pipe boring pits sum

The tendered lump sum shall include full compensation for the provision and maintenance of access roads to the reception pits, the negotiations with land owners where applicable, the erection and maintenance of temporary gates, fences and road signs where applicable, and for the removal

Tender
Part C3: Construction

C3.4.4-112

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

and reinstatement of the access roads and temporary works on completion of the boring operations to the satisfaction of the Engineer and landowners concerned. The work will be paid for in two instalments as specified in pay item PLU10.1.

PLU11.3 Excavating in soft material cubic metre (m³)

The tendered lump sums shall include full compensation for all work necessary for excavating the pits to suit the Contractor's equipment, for excavating by hand where applicable, for shoring the sides of the excavation, and for stockpiling the excavated material at predetermined sites. The work shall be carried out as specified in the appropriate clauses of SABS 1200D and DB (see also PLU9 of this section).

PLU11.4 Extra over item PLU10.3 for excavating hard material cubic metre (m³)

The unit of measurement shall be the cubic metre of material measured in the original position before excavation and classified as hard in terms of sub-clause PLU9(b). The dimensions of the excavation shall be agreed on as specified in sub-clause PLU9(b) of this section.

The tendered rate shall include full compensation for all extra work and effort required for excavating in hard material.

PLU11.5 Backfilling the pipe boring pits with

The unit of measurement for shall be the cubic metre of suitable excavated or imported material used for backfilling the pipe boring pits to the extent determined by the Engineer.

The tendered rates shall include full compensation for loading approved material previously excavated or alternatively for loading the material from approved borrow pits, for transporting it to where required and for off-loading, and placing the material.

The tendered rate shall also include full compensation for compacting the material in 150 mm thick layers to a density of at least that of the surrounding undisturbed material.

Material shall be imported only on the instructions of the Engineer.

| | | |
|-----|--------------------|-------------------------------|
| (a) | Excavated material | cubic metre (m ³) |
| (b) | Imported material | cubic metre (m ³) |

PLU11.6 Supply of pipes to be bored (description, type and diameter stated) metre (m)

Tender
Part C3: Construction

C3.4.4-113

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The unit of measurement shall be the metre of completed bored pipeline measured between the ends of the completed pipeline continuously through intermediate boring stations and shall include intermediate boring pipes.

The tendered rate shall include full compensation for the supply, delivery and storing the pipes.

PLU11.7 Boring of holes through:

The unit of measurement shall be the metre length of hole bored and approved.

The tendered rates shall include full compensation for all labour, equipment (other than equipment provided under PLU10.1), materials and appurtenant work necessary to bore the hole including the pilot hole in the positions indicated and as specified and for removing any bored material to spoil sites found by the Contractor. Should spoil sites be provided by the Employer, overhaul will be payable where material is transported outside the free-haul boundaries.

- | | |
|------------------------------|-----------|
| (a) Soft material | |
| (1) Diameter of hole stated | metre (m) |
| (2) Etc. for other diameters | metre (m) |
| (b) Hard material | |
| (1) Diameter of hole stated | metre (m) |
| (2) Etc. for other diameters | metre (m) |

PLU11.8 Inserting pipes – Pipe Boring

The unit of measurement shall be the metre of each size and type of pipe jointed and inserted.

The tendered rates shall include full compensation for jointing and inserting the pipes in the bored hole.

- | | |
|------------------------------|-----------|
| (a) State diameter of pipe | metre (m) |
| (b) Etc. for other diameters | metre (m) |

PLU11.9 The grouting of voids for pipe boring

The unit of measurement shall be the metre of each size of pipe grouted on the instructions of the Engineer.

The tendered rates shall include full compensation for all plant, material and labour necessary for carrying out the work in a manner approved by the Engineer.

Tender
Part C3: Construction

C3.4.4-114

C3.4.4
Particular Specifications for Civil Works

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- | | | |
|-----|--------------------------|-----------|
| (a) | State diameter of pipe | metre (m) |
| (b) | Etc. for other diameters | metre (m) |

| | | |
|----------|--|-------------------|
| PLU11.10 | Timbering and shoring left temporarily in the thrust and reception pits and pipe boring pits | square metre (m²) |
|----------|--|-------------------|

The tendered rate PLU10.3 shall include full compensation for the removal of the supply, fixing, timbering and shoring by the pipe-boring contractor.

END OF SECTION

| | | | | | |
|------------|-----------|-----------|----------|-----------|-----------|
| | | | | | |
| Contractor | Witness 1 | Witness 2 | Employer | Witness 1 | Witness 2 |

Isinyithi Cathodic Protection

Company Reg # : 2002/002423/07
VAT# : 4570234502

P O Box 2905, Wilkoppen, 2068
13 Robin Drive, Fourways 2191
T: 011 465-1807
E: pipeline@isinyithi.co.za



SPECIFICATION

CLIENT : Phatwe Consulting Engineers / Rustenburg Water Services Trust

PROJECT : New Bospoort Pipeline

SCOPE : AC Mitigation and Cathodic Protection Specification

DATE : March 2021

REF : 6940/161259[1]

Report by: 
N C Webb

Internal Review: 
V Sealy-Fisher



Reports are submitted to clients on a confidential basis;

No reference to the work or test results in any manner will be discussed or made public without written authorisation from the client;

All work is considered proprietary property of the client and is maintained by Isinyithi as such.

Disclaimer: Responsibility rests with the reader to verify the latest revision of the report.

DOCUMENT SIGN OFF




Job Title **Bospoort Pipeline**

Document title **AC Mitigation and Cathodic Protection Specification**

Project Number **6940**

Document Reference **161259[1]**





| Organisation | Name | | Date |
|---|----------|---|-------------|
| Isinyithi Cathodic Protection (Pty) Ltd | N C Webb |  | 10 Mar 2021 |
| | | | |
| | | | |

Job Title Bospoort Pipeline

Document title AC Mitigation and Cathodic Protection Specification

Project Number 6940

Document Reference 161259[1]

| Revision | Date | Revision Description | For review/comment | |
|----------|----------|----------------------|--|---|
| 0 | Aug 2020 | | Prepared By | Checked by |
| | | Name | Neil Webb | V Sealy-Fisher |
| | | Signature |  |  |
| Revision | Date | Revision Description | Comments incorporated | |
| 1 | Mar 2021 | | Prepared By | Checked by |
| | | Name | Neil Webb | V Sealy-Fisher |
| | | Signature |  |  |

| | | |
|-----------|--|-----------|
| 1 | SCOPE | 7 |
| 2 | DEFINITIONS, ABBREVIATIONS AND REFERENCES | 8 |
| 2.1 | Definitions | 8 |
| 2.2 | Abbreviations and Material Symbols | 8 |
| 2.3 | References | 9 |
| 3 | DESIGN AND GENERAL REQUIREMENTS | 10 |
| 3.1 | Design | 10 |
| 3.2 | Electrical Continuity | 10 |
| 3.3 | Cathodic Protection Test Stations | 11 |
| 3.4 | Impressed Current Cathodic Protection | 13 |
| 3.5 | AC Interference Mitigation (Increased Voltage Mitigation) | 27 |
| 3.6 | Cabling | 32 |
| 4 | MATERIALS AND PLANT MANUFACTURING | 36 |
| 4.1 | General | 36 |
| 4.2 | Compatibility of Materials | 36 |
| 5 | INSTALLATION AND OPERATING REQUIREMENTS | 38 |
| 5.1 | Electrical continuity | 38 |
| 5.2 | Insulating Flanges (IF) | 38 |
| 5.3 | Test Stations | 38 |
| 5.4 | AC Interference Mitigation Systems | 39 |
| 5.5 | Permanent ICCP Installation | 39 |
| 5.6 | Records | 39 |
| 6 | TESTING/COMMISSIONING | 41 |
| 7 | STANDARDS | 43 |
| 8 | GUIDELINES FOR SAFE WORKING PROCEDURES | 45 |
| 9 | OPERATING AND MAINTENANCE MANUALS | 55 |
| 10 | MEASUREMENT AND PAYMENT | 56 |
| 10.1 | Surveys by the Nominated Subcontractor (CP Specialist) Unit: PS | 56 |
| 10.2 | Supply of cable Unit: m | 56 |
| 10.3 | Installation of cables Unit: No. | 56 |
| 10.4 | Supply and installation of CP & ACM equipment Unit: No | 57 |
| 10.5 | Trenching for cables Unit: m | 57 |
| 10.6 | Supply and installation of backfill for anodes Unit: m ³ | 57 |
| 10.7 | Coating integrity testing during construction. Unit: sum | 57 |
| 11 | ANNEXURE 1 : PERFORMANCE SPECIFICATION / DATA SHEET: CATHODIC PROTECTION CABLES | 58 |



LIST OF TABLES

Table 3.1: Table of chemical composition of coke breeze 14

Table 3.2: Table of Destructive tests required on two anodes per batch..... 15

Table 3.3 : Zinc ribbon specification27

Table 3.4 : Performance Specification for DC Decoupling Device for Gradient Control Wire (Ribbon) and
Lumped Grounding Mat29

Table 3.5 : Performance Specification for VLD for Equipotential Mats or Steel Reinforcing of a Concrete
Structure31

Table 3.6 : Cable specification (unless specified otherwise on the drawings)32

1 SCOPE

This specification deals with system component design, the manufacture, shop assembly and testing, supply, installation, site testing, site commissioning, all operating and maintenance during the Defects Notification Period of the temporary and permanent Cathodic Protection (CP) systems and alternating current interference mitigation (ACIM) system on the pipeline constructed under this Contract.

The work required shall be done as per the system specifications and requirements set out below under the direction of a specialist AC Mitigation and Cathodic Protection Representative of the Engineer (CP Eng Rep). Due to the nature of the investigations and system component designs required in this specification, the final testing and design validation regarding the system design work will be monitored by the CP Eng Rep. This will be done progressively during the construction of the pipeline.

This specification shall be interpreted as follows:

- a) For Employer's Design it shall be regarded as a Specification.
- b) For Contractor's Design of system components it shall be regarded as an Employer's Requirement.

2 DEFINITIONS, ABBREVIATIONS AND REFERENCES

2.1 Definitions

For the purpose of this document:

- a. **“Manufacture”** includes, as applicable, the purchase of materials or goods, manufacture, fabrication and assembly, any specified corrosion protection measures and any off-site inspection or testing of materials or parts.
- b. **“Installation”** includes, as applicable, all handling and transport from storage, if necessary, all erection and setting to work.
- c. **“Performance Specification”** means the Employer’s Requirement.

2.2 Abbreviations and Material Symbols

For the purpose of this Document, the following shall have the meaning given:

| | | |
|----------|---|--|
| A | : | Ampere (unit for electrical current) |
| AC | : | Alternating current |
| ACIM | : | AC interference mitigation |
| ASTM | : | American Society for Testing and Materials |
| BS EH | : | British European |
| CD | : | Capacitive discharge |
| CDT | : | Current Drainage Test |
| CP | : | Cathodic protection |
| CSE | : | copper/copper sulphate reference electrodes |
| CSV | : | Comma separated values |
| DC | : | Direct current |
| DCVG | : | Direct Current Voltage Gradient |
| DFT | : | Dry film thickness |
| DGPS | : | Differential global positioning system |
| GPRS | : | General Packet Radio Services |
| HDG | : | Hot-dip galvanised |
| HVAC | : | High voltage AC transmission lines |
| Hz | : | Hertz (unit of frequency) |
| ICCP | : | Impressed Current Cathodic Protection |
| ISO | : | International Organisation for Standardization |
| MMO | : | Mixed metal oxide anode |
| MOV | : | Metal Oxide Varistor |
| NACE | : | NACE International. |
| Ω | : | Ohm |
| PVC | : | Polyvinyl chloride |
| r.m.s. | : | root mean square |

| | | |
|--------|---|--|
| SACP | : | Sacrificial anode cathodic protection |
| SANS | : | South African National Standards |
| SRE | | Stationary (permanent) reference electrode |
| SPD | : | Surge Protection Device |
| SS-DCD | : | Solid state DC decoupling device |
| USB | : | Universal Serial Bus |
| V | : | Volt |
| VLD | : | Voltage Limiting Device |
| XLPE | : | Cross-linked polyethylene |
| Zn | : | zinc |

2.3 References

When reference is made to a Code of Practice, Specification or Standard, the reference shall be taken to mean the latest edition or replacement at time of tender of the Code, Specification or Standard; including addenda, supplements, modifications and revisions thereto. Where a previous version is intentionally used, it will be indicated as such. Where reference is made to a Code, Specification or Standard that has subsequently been withdrawn and not replaced, the intended content will remain relevant unless confirmed otherwise in writing by the Engineer.

3 DESIGN AND GENERAL REQUIREMENTS

3.1 Design

3.1.1 General

The materials used, the component design and the cathodic protection provided shall comply with the relevant system requirements set out below.

3.1.2 Drawings

The Contractor shall be responsible for submitting relevant component design, construction and installation Drawings to the Engineer for approval, within 3 months of the award of the Contract. The Drawings shall include dimensions and material details of plant offered for approval.

The Contractor shall also be responsible for "as-built" drawings of all CP Stations, AC mitigation stations and all hardware and Plant installed as part of this Contract.

3.2 Electrical Continuity

The pipeline must be electrically continuous within defined sections. Where electrical continuity is required as detailed in the drawings and bill of quantities, all flanged components shall be made electrically continuous by means of a continuity bond. Continuity bonding around valve chambers where bolted flanges, dismantling flanges or couplings are found will be achieved either by external buried cables or internal cables mounted on the valve chamber walls, as designated in the bill of quantities.

3.2.1 Continuity bonding around the outside of chambers

Bonding cables will be attached to the pipe(s) each side of the valve chamber wall. Excavation around the chamber will be in accordance with the relevant specifications.

Two off double insulated single core 35 mm² copper cables laid in parallel shall be thermit welded separately directly to the pipe overt.

Continuity bonding shall include excavation, cable connections, making good of coating and lining systems to original coating system, test and back filling. All cables shall be clearly identified by means of permanently marked plastic ferrules with black lettering on a yellow background. Ferrules shall be the slip-on type and matched to the size of the cable.

3.2.2 Continuity bonding around the inside of valve chambers

One off 16 mm² double insulated single core copper cable shall be welded to the pipe overt where the pipe protrudes through the chamber wall on the upstream and downstream sides. The cables coming from the upstream and downstream sides must be installed against the chamber walls using 15mm galvanised conduit and connected via a link panel for selective continuity. Continuity bonding shall include cable connections, making good of coating and lining systems to original coating system, conduit, saddles, terminations and link panel. All cables shall be clearly identified by means of permanently marked plastic ferrules with black lettering on a yellow background. Ferrules shall be the slip-on type and matched to the size of the cable.

3.2.3 Continuity bonding of buried couplings

Buried flanges shall be made continuous by means of 2 off 25 x 5mm steel flat-bars welded across the flanges prior to encapsulation.

Buried VJ couplings shall be made continuous by 2 x 35mm², single core, double insulated, black cable welded across the flange and on the barrel of the flange (including 6 x welds and coating make good).

3.3 Cathodic Protection Test Stations

Cathodic Protection and AC Interference Mitigation monitoring test facilities (recording, bonding and current measurement) shall be located inside purposely provided bunkers located as indicated in the installation schedule.

The enclosure shall be manufactured from 30 MPa concrete and shall be a minimum of 150 mm thick and shall be reinforced with hot-dip galvanised (HDG) mild steel (minimum 8 mm diameter).

The vandal resistant enclosure shall be manufactured from 5 mm (min) thick 3Cr12 plate which shall be reinforced as required. Corrosion protection of enclosures shall be multi-purpose epoxy plus re-coatable polyurethane.

A common-key vandal resistant (stainless) steel locking mechanism shall be utilised to lock the 3Cr12 enclosure. Details of the locking mechanism shall be submitted to the Engineer for approval before manufacturing or construction of the enclosure.

The internal enclosure shall be at least 800 mm x 420 mm x 450 mm (H x D x W) and accommodate the 75mm uPVC (Class 12) duct for a portable reference electrode.

The enclosure shall be installed with a concrete foundation, base and 1.2m x 100 mm thick concrete surround with reinforced 100 mm x 100 mm x 6 mm HDG mild steel mesh. The reinforcing mesh shall be connected to a cable that is to terminate within the enclosure, should an equipotential plane be required for AC interference mitigation.

Inside the lockable enclosure, the 75mm uPVC (Class 12) tube shall extend above a 2.5mm thick stainless steel Grade 304L gland plate, to permit the portable reference electrode to be installed directly into the soil (via the uPVC duct) with no outside interference.

The Contractor shall submit details and drawing for an appropriate terminal board/link panel of polycarbonate, or GRP, to be mounted in the bunker with associated ducts penetrating through the floor of the bunker for cables.

3.3.1 Recorder-Type Test Point Facilities (Type B)

Type B bunker connection panels require connections for the following:

- Pipe power cable
- Pipe monitor cable
- VLD from gradient control mat
- AC Coupon with 10 ohm 50W resistor
- DC Coupon with 10A slow blow fuse
- Stationary reference electrode
- SSDCD from zinc ribbon (if required)

3.3.2 Bonding Type Test Point Facilities (Type C)

Type C bunker connection panels require connections for the following:

- Pipe power cable
- Pipe monitor cable
- Foreign pipe power cable
- Foreign pipe monitor cable
- VLD from gradient control mat
- AC Coupon with 10 ohm 50W resistor
- DC Coupon with 10A slow blow fuse
- Stationary reference electrode
- SSDCD from zinc ribbon (if required)

3.4 Impressed Current Cathodic Protection

3.4.1 Introduction

It is proposed that shallow horizontal groundbeds be used for the Bospoort Pipeline.

The groundbeds will contain tubular MMO anodes or similar rating silicon iron anodes, encased in galvanised steel canisters, with each canister spliced alternatively to the positive ring main cable. The anode canisters will be 2 m in length, 200 mm diameter, while the spacer canisters will be 1 m long, 200 mm diameter.

Watering systems will be provided so as to enable the groundbed resistance to be more constant and to prevent the groundbeds from drying out.

3.4.2 Dimensions and general description

The actual length of the groundbed is presented in the CP design report. However, each groundbed has the following common features:

- Anodes in canisters
- Coke breeze backfill
- Positive ring main cable
- Splices of the anode tail to the ring main shall be encapsulated in epoxy splicing kits
- Watering system
- Cable warning tape

The watering system will be installed during the groundbed construction in order to ensure an even groundbed resistance over time.

Cable warning tape (yellow on black) will be installed at a depth of 600 mm below surface along the entire length of the groundbed.

3.4.3 Watering System

The watering system will consist of a ribbed and slotted, double walled PVC drainex pipe, 110 mm in diameter. The pipe is covered by one layer of flow net and then by one layer of bidim A2. The pipe lengths are usually 6m in lengths. They need to be coupled together with couplings and the end of the pipe must be closed with a suitable end cap. The drainex pipe will be fed using a 50mm PN 12 HDPE pipe from the closest valve chamber using a suitable ball valve and pressure reducing valve. The pipe will be laid in a dedicated trench from the designated valve chamber to the start of the groundbed.

3.4.4 Coke Breeze

Sasol Corr-Carb pitch coke shall be used or a similar product approved by the CP Eng Rep. The chemical composition is as follows:.

Table 3.1: Table of chemical composition of coke breeze

| Element/Compound | Specification | Test Method |
|----------------------------|------------------------------------|--|
| Fixed Carbon | 99.5% min | By calculation – 100% minus (%ash + VCM) |
| Sulphur | 0.25% max | ASTM D 4239 |
| Ash & volatiles | 0.50% max | Ash – ASTM D 4422 Volatiles – BS 1016: Part 4 |
| Moisture | 0.15% max | ASTM D 3173 |
| Bulk density | 1000 kg/m ³ max | ASTM D 527 |
| Resistivity | 55 Ωm max | Alusuisse C-109 |

The particle size distribution (calculated as per ASTM D 293) shall be a maximum of 100% < 1.0 mm and a min of 5% < 0.5 mm.

The coke breeze will be used to surround the anode in the canister and in addition, the canistered anodes will be located within a coke breeze surround measuring 300 mm by 300 mm.

3.4.5 Anode Canisters

Anodes will be located inside spirally welded galvanised steel canisters, having dimensions of 200mm diameter and 2 000 mm long and will have been pre-packed at the manufacturer's (or supplier's, or installation contractor's) premises. The anodes will be centrally located within the canister, and the annular space between the anode and the canister will be filled with coke breeze.

The ends of the canisters will be sealed and the anode cable will protrude through the side with protective glands.

3.4.6 Anodes

Mixed metal oxide (MMO) or equivalent anodes will be used for the impressed current CP system.

Anodes will be manufactured from tubular titanium metal to ASTM B 338, either Grade 1 or 2, and will be coated with iridium and tantalum oxides. The anode dimensions will be 500 mm x 19 mm diameter x 0.9 mm wall thickness with a minimum capacity of 50 A.y.

The anode to cable connection will be made in the centre of the anode, using a crimped or welded insert over the copper cable to give a resistance of less than 0.001 Ω and a minimum breaking strength of 1200 kg. Heat shrink is used to seal the ends of the wedge and the copper cable.

The ends of the anode will be sealed with a rubber end cap and the annular space between the tubular anode and the copper cable will be filled with a cast resin.

In addition to the certification provided by the manufacturer, two anodes from the batch will be subjected to the following range of destructive tests at an independent laboratory approved by the CP Eng Rep:

Table 3.2: Table of Destructive tests required on two anodes per batch.

| Test | Minimum requirements/Test Method |
|---------------------------------------|--|
| Test solution | 10% by volume sulphuric acid |
| Test temperature | Less than 50 °C for duration of test |
| Test Current Density | 20 kA/m ² min |
| Test Duration | Minimum 35 days at the specified current density |
| Coating adhesion test | ASTM B 571 |
| X-Ray/NDT | The tubular anode shall be X-Ray'ed in order to ensure that bubbles are not contained within the epoxy sealant |
| Metallurgical and SEM analysis | Anodes will be sectioned and the MMO coating verified |

3.4.7 Cabling

The anode tails will be 10 mm² PVC/HMWPE/PVDF.

3.4.8 Cable Warning Tape

Cable warning tape will be inserted above the groundbed, at a depth of 600 mm below surface.

3.4.9 Transformer Rectifier Units

3.4.9.1 Scope

This specification is for the supply and delivery of Transformer Rectifier Units (TRU) for the CP system of the Bospoort Pipeline. TRUs will be standard construction in order to minimise spares requirements and facilitate maintenance.

All documentation related to the supply of CP and ACM equipment shall comply with the requirements of the main contract.

3.4.9.2 General Specification for TRU Cabinet construction

a. General Comments

The TRU's are to be installed in concrete structures (Rocla) in a rural area but with industrial atmospheric pollution. Cold dry conditions occur in winter. All components must be treated so as to provide satisfactory service under the corrosive conditions of the sites.

The general details of the sites are as follows:

| | | |
|----------------------|---|------------------------------------|
| Altitude | : | 1200 m above sea level |
| Ambient Temperature | : | -10° to 40° C |
| Relative Humidity | : | 10% to 80% |
| Lightning conditions | : | 8.1 flashes/km ² /annum |

The TRU's may be used in environments where metallic dust, soot and grit may be present.

All structure bolts, washers and nuts shall be Grade AISI 304 stainless steel. Bolts with spring washers are preferred and "Nylock" nuts are permissible where devices being secured remain at ambient temperature.

The TRU's will be installed within concrete enclosures, so no TRU cabinet is required and the TRU components shall be mounted on a free-standing frame capable of being located inside the concrete enclosure. The frame shall be made from mild steel that has been hot dip galvanized and must be bolted onto the concrete floor.

All components shall be mounted on one frame, and access to all components, especially in regard to replacement of diodes shall be possible without excessive dismantling.

Suitable lifting lugs (capable of carrying the total mass of the frame and all its components) shall be incorporated onto the frame/cabinet to allow safe handling and installation on site.

TRU's will be powered by single phase 230V AC power.

b. Powder coating for chassis plates

Apply by means of electrostatic spray to ensure a final DFT of 120 micron per coat. Epoxy, epoxy polyester or polyester powder baked at 190 °C for 15 minutes. Ethylene vinyl acetate thermoplastic powder coating baked at 220 – 250 degrees Celsius for full curing.

| | | |
|------------------|---|------------------------------|
| Exterior colours | : | as specified by the Engineer |
|------------------|---|------------------------------|

| | | |
|------------------|---|------------------------------|
| Interior colours | : | as specified by the Engineer |
|------------------|---|------------------------------|

c. Electronic PC Boards (PCB)

All electronic printed circuit boards shall be coated with a proprietary conformal military spec. coating designed to prevent corrosion to the exposed component leads. All PCB's shall have a primary solder mask and legend.

d. General Specification for electrical wiring

All current carrying conductors shall be insulated to withstand a minimum voltage of 1000V. All wiring shall comply with the provisions of the Wiring Code of Practice; SANS 10142 (latest edition).

Wherever possible flexible, multi-strand cable is to be used.

Joints or splices in any wiring will not be permitted. No more than two conductors shall be connected to any one terminal.

All conductors shall be numbered at both ends with reference to the Schematic Wiring Diagram supplied with the unit.

All conductors excluding busbars shall be routed in trunking or harnessed using polyethylene spiral wrapping.

Thyristor gate leads (if fitted) shall be screened or twisted pair.

All current-carrying conductors shall be multi-stranded, flexible and sized to adequately carry the design current without a rise in temperature.

All conductors shall be terminated at each end with suitably-sized, pre-insulated lugs or pre-insulated ferrules. No trimming of conductor strands will be permitted. All ferrules and lugs shall be crimped with appropriately sized crimping equipment.

Where elevated temperatures are expected beyond the operating range of PVC insulated conductors then the conductors in the heat affected area must be insulated with materials capable of withstanding the elevated temperature environment.

Dimple crimping of lugs and ferrules is not permissible, only hexagonal crimping dies may be utilized when crimping and must be adequately sized and include the cable size marking in the die.

Cable markers must be colour coded as well as have their number embossed indelibly on the marker.
i.e.

| | |
|----|--------|
| 0- | Black |
| 1- | Brown |
| 2- | Red |
| 3- | Orange |
| 4- | Yellow |
| 5- | Green |
| 6- | Blue |
| 7- | Violet |
| 8- | Grey |
| 9- | White |

Cable markers must be appropriately sized to suit the insulation size of the cable.

Cable markers shall read from cable to lug on all conductors.

All AC supply conductors shall be colour coded according to the incoming phase and retain the colour nominated throughout the cabinet.

AC carrying conductors must be routed separately from DC carrying conductors.

Grounding cables connected to Surge diversion devices must be kept as short as possible and may not be routed with either AC or DC carrying conductors.

e. *Terminals*

All terminals shall be completely accessible after completion of wiring.

All terminations made to buss bars shall be provided with spring washers.

All supply power terminations shall be enclosed and be highlighted with a warning label.

Transformer and inductor or smoothing Capacitor terminations shall be covered with a transparent cover prohibiting accidental contact.

Output terminals shall be fully insulated from any metal of the housing or chassis.

All terminals shall be clearly marked and sized according to the current the terminal will carry.

f. General specification for colour coding and labelling of conductors, equipment and components

| | |
|--------------------------------|-------------------------------|
| Positive electrical conductors | Red |
| Negative electrical conductors | Black |
| Earth cables | Green with yellow stripe |
| AC Supply cables | |
| Phase 1 | Red or Brown |
| Phase 2 | Yellow or White |
| Phase 3 | Blue |
| Neutral | Black |
| Reference Electrode cable | Yellow |
| Electrical warning signs | Black on yellow background |
| Monitor cable | Blue |
| Transformer Secondary cables | Grey |
| Component Labels | Black on a white back ground. |

All labels shall be engraved sandwich type Gravoply labels. All labels to be mounted with screws or blind rivets only. Silk screen labels or Aluminum anodized labels shall not be utilized.

3.4.9.3 Electrical Construction

a. General

The TRU is to comprise a step-down, double wound transformer with earth screen, coarse tapplings and a controlled rectifier bridge to produce a DC output.

The maximum output voltage is to be 50 Volts DC and the output current will be 20 Amps.

A fused isolator shall be provided such that the TRU can be manually disconnected from the load.

The output of the unit will be automatically controlled in one of four control modes as follows:

- Constant output current.
- Constant output voltage.
- Constant Structure to Electrolyte potential.
- Iterative "Instant off" structure to electrolyte potential.

The rectifier bridge will consist of Silicon diodes rated at twice the rated current and a peak inverse voltage of 1600 Volts. The diodes shall be mounted on convection cooled heat sinks. The output of the Unit shall be smoothed and contain a ripple of less than 5%.

b. Automatically Controlled TRU

The main rectifier bridge shall be connected for full wave rectification. The heat sink shall have a thermal switch to automatically interrupt operation of the TRU should the temperature of the heat sink exceed 80°C and restore operation when the temperature of the heat sink falls to below 80°C. The primary circuitry of the main transformer will be protected via a D curve 5 kA circuit breaker adequately rated so as to avoid nuisance tripping. The circuit breaker must dis-engage all phases of the TRU when tripping and must be capable of isolating the supply from the unit.

The secondary circuit of the main transformer will be protected via thermal fuses incorporated into each phase between the output of the transformer and the rectifier bridge. The AC fuses must be adequately rated to allow for maximum output current and voltage to be maintained for 1 hour without rupturing. With a 20% increase in output current one of the AC fuses must rupture within twenty minutes of the increase in output current.

The rectifier is to be protected with thermal fuses incorporated into the positive and negative legs. The fuses are to be adequately rated to allow for maximum rated current to be maintained for one hour without rupturing. With a 20% increase in output current one of the DC fuses must rupture within twenty minutes.

All thermal fuses are to be of the mechanical indicating type whereby an irreparable form of mechanical indication occurs when a fuse is ruptured.

c. Transformer

All Transformers shall be double wound to BS171 complete with inter-winding screen. The inter-winding screen must be routed out of the transformer and earthed as close to the transformer mounting as possible.

The transformer is to be vacuum impregnated with a suitable insulating varnish and baked subsequent to vacuum impregnation.

Regulation of auxiliary windings shall not be greater than 3 % and on the main step down winding 10%.

The transformer must have suitable windings on the secondary of the transformer to facilitate coarse selection of the voltage. The windings must be so wound to provide coarse adjustment of 33%, 66% and 100% of the step down voltage.

d. *Earthing /Grounding*

All metal components shall be connected to the common earth and to the AC supply earth.

All electrical circuits shall be floating with respect to earth.

All earth connections within the enclosure must be as short as possible and rated at possible fault current.

Earth buss bar mounting studs must be adequately sized to accommodate collective fault current.

A separate earthing system will be provided for the TRU consisting of copper earth rods and bare copper earthing cable which will have a resistance below 10 Ω .

e. *Auxiliary Power Socket Outlet*

A 15A power socket adequately inspected according to the Occupation Health and Safety Act & Regulations, Act 85 of 1993 as amended, will be provided in the distribution board cabinet located on the inside of the concrete enclosure (Rocla).

f. *Output Control*

The adjustment and control of the output shall be achieved through a magnetic amplifier located in the primary side of the transformer, a fully controlled thyristor bridge or a switch mode integrated unit.

g. *Magnetic Amplifier (optional)*

The magnetic amplifier shall be of the air-cooled type.

The magnetic amplifier shall enable the DC output current of the rectifier to be varied between 7.5% and 100% of the full load current, when connected in series with the primary winding of the rectifier transformer.

The current rating of the magnetic amplifier shall be not less than that of the primary winding of the rectifier transformer.

Alteration of the current output will be by means of a variable DC supply to change the control current to the magnetic amplifier.

The control current must not exceed 1 A.

The magnetic amplifier shall be mounted on the same frame as the rectifier set.

h. Output Control Modes Of Operation

Selection of the control mode as well as adjustment of the limits and control set points must be user programmable and the control equipment must be capable of both local as well as remote selection. Remote selection of the control mode is to be accomplished via the RS 232 port utilizing modbus protocol.

Irrespective of control mode, the TRU control equipment must be capable of output voltage, output current and potential pre-set limits. When the control equipment is changed from one control mode to another control mode, all user programmable parameters must be automatically restored to minimum values to prevent an instantaneous application of output voltage or output current to the load.

The Automatic control equipment must be capable of controlling the application of power to the load in either a pre-programmable incremental percentage of maximum output stepped manner, or in a linear incremental manner, in addition to the aforementioned control modes, the selection must be user programmable.

The input impedance of the reference electrode input to the control equipment must be no less than 500 MΩ and must not adversely load the reference electrode thereby distorting the potential measurement.

Precise control is required and local adjustment of set points and control modes must be via sealed tactile push buttons and not through the use of adjustable potentiometers as these deteriorate with time especially in corrosive atmospheres.

i. Constant Output Current

Irrespective of load circuit resistance the output current of the TRU shall be maintained constant.

j. Constant Output Voltage

Irrespective of load circuit resistance the output voltage of the TRU shall be maintained constant.

k. Potential Control

The output of the TRU must be automatically varied to maintain the potential between a permanently installed reference electrode and the structure, constant.

l. Meters and Monitors

The TRU will include high quality meters to indicate the following:

- Output Voltage
- Output current
- Reference Potential
- No DC output current- hour totalizer.

The input impedance of the reference potential digital volt meter must exceed 500 MΩ and must not adversely load the reference electrode or the control circuitry. The accuracy of the reference potential meter must be less than $\pm 20\text{mV}$.

All meters must be either LCD or analogue display types and the display must be legible in direct sunlight and from a distance of 2 metres.

Captive (banana) sockets must be incorporated below the meters mentioned above and must be continuously connected to the measurement points mentioned above. The captive sockets connected to the output current measurement point must be labelled with the shunt rating e.g. $50\text{mV} = 25\text{ A}$.

m. Surge Protection

- **Mains Surge Protection**

Surge protection devices must be installed in the incoming mains circuit immediately electrically down stream of the isolating mains circuit breaker. The Surge protection devices must be rated at a discharge current of 40 kA and the maximum permitted operating voltage to be 25% above the RMS value of the applied voltage. The response time of the over voltage device is to be less than 25 ns. Where three phase units are implemented, then the surge protection devices must be connected between each phase and earth. Single phase units to have the surge protection device connected between live and earth.

- **Output Circuit Surge Protection**

Output Voltage $\leq 50\text{ V DC}$

Surge protection devices must be installed after the DC fuses situated in the positive and negative legs of the TRU. The Surge protection devices must be rated at a discharge current of 40 kA and the maximum permitted operating voltage to be 25% above the RMS value of the maximum output voltage. The response time of the over voltage device is to be less than 25 ns. Two 40 kA surge protection devices must be installed in parallel between the positive leg and earth and the negative leg and earth.

n. Component Layout

Transformers and inductances to be mounted to the bottom of the cabinet/frame and shall not interfere with any gland plate that may be installed. The Rectifier and any other heat sinks are to be mounted in the upper reaches of the cabinet/frame. Trunking and any other heat sensitive devices must be kept well away from the heat bearing heat sinks.

AC and DC current carrying conductors must be routed in separate ducts and or looms and may not be mixed in the same loom or duct.

All components must be accessible from the front and must be mounted such that they are easily removed for repairs and in situ repair work.

All components must be labelled and cross referenced to the laminated schematic drawing mounted in the cabinet.

o. Inspection and Testing

All material, test and compliance certificates must be incorporated into the O & M Manual.

The following tests must be carried out at the manufacturer's works, after successful completion of the tests a certificate will be issued by the manufacturer and signed by the Engineer or his nominated representative. All testing and damaged components resulting from the testing will be at the manufacturer's expense and carried out at the manufacturer's premises. Adequate adjustable load resistances, adjustable power supplies and testing equipment will be made available to the Engineer by the manufacturer to verify specified operational characteristics of the TRU under test.

p. Pre Power-Up Testing

The various earth points, cabinet body, chassis plates and all exposed metal surfaces shall be measured for continuity to the main earth terminal.

The cabinet and AC inputs, the DC outputs shall withstand a 1 kV insulation test. The insulation testing shall be conducted with all circuit breaker and fuses in their normal operating position without power or load connected.

q. Power On Testing

The TRU shall operate for a period of 5 hours continuously at maximum current and at full rated voltage with all doors closed or until the temperature of the Rectifier heat sink is stable for a period of one hour. Where the temperature continues to rise after a period of 7 hours the equipment will be rejected. The ambient, cabinet compartment internal temperature, heat sink temperature and transformer winding temperatures must be recorded during the heat run and plotted upon conclusion of the heat run. K type thermocouples shall be used for the continuous recording of the all the various

temperatures. Immediately after the heat run the aforementioned insulation check will be carried out without the power or load applied. A maximum heat sink temperature of 80 °C is permissible at the highest vertical point of the heat sink.

Control mode testing shall be carried out after the conclusion of the heat run.

r. Constant Current Tests

The manufacturer will demonstrate the TRU's ability to control the output current to within 5 % of the pre-determined set point. The load resistance is to be manually adjusted to ensure that the output current remains constant irrespective of the Load resistance. Four specific current set points are to be set 25%, 50% 75% and 100% of maximum rated output current. Voltage at the given pre-determined set points will be recorded and noted in the O & M Manual.

s. Constant Voltage Tests

The manufacturer will demonstrate the TRU's ability to control the output voltage within 5% of the pre-determined set point. The load resistance is to be adjusted to ensure that the output voltage remains constant irrespective of the Load resistance. Four specific voltage set points are to be set 25%, 50% 75% and 100% of maximum rated output voltage. Current at the given pre-determined set points will be recorded and noted in the O & M Manual.

t. Constant Potential Tests

The manufacturer will demonstrate the TRU's ability to control the electrolyte to structure potential within 40 mV of the pre-determined set point. Current limit and voltage limit features are to be tested and verified whilst carrying out potential mode testing. Dynamic feedback is required to demonstrate the control mode. That is, a simulated CP system must be used to demonstrate the control mode. In the potential mode verification a variable power supply may not be used to simulate the Reference Electrode.

u. DC Overload Testing

A DC overload test is to be carried out upon conclusion of the Control mode demonstration.

The AC fuses must be adequately rated to allow for maximum output current and voltage to be maintained for 1 hour without rupturing.

With a 20% increase in output current one of the AC fuses must rupture within twenty minutes of the increase in output current. The DC fuses must be removed and replaced with link bars during the AC fuse test to verify rupturing capacity of the AC fuses.

The DC fuses are to be adequately rated to allow for maximum rated current to be maintained for one hour without rupturing. With a 20% increase in output current one of the DC fuses must rupture within twenty minutes. The AC fuses must be removed and replaced with link bars during the DC fuse test to verify rupturing capacity of the DC fuses.

Output voltage, Output current, Mains input voltage, Mains input current and time taken for fuse to rupture must be recorded in the O&M Manual.

During the DC overload test no component, cable or terminal shall display any signs of overload damage.

The Engineer may at his discretion call for other pertinent coating, mechanical or electrical tests to be done in order to prove compliance with the specification.

3.4.9.4 Documentation

The TRU shall be supplied with the following documentation

- A removable clear laminated schematic diagram and the laminated schematic diagram shall be located inside the TRU enclosure.
- TRU operation and maintenance manual (O & M) complete with schematic, parts list, fault finding flow chart, operating instructions, original certificates and recommended spare.
- Three copies of the O & M shall be supplied to the Engineer prior to commencement of the manufacturing of the equipment.

3.4.9.5 Guarantee

The equipment shall carry an unconditional guarantee with the exception of damage resulting from vandalism, mechanical damage, external fire, flooding and use outside of operating parameters. Guarantee period in accordance with the conditions of contract.

3.4.9.6 Information to be Provided by the Tenderer

The following information must be provided by the tenderer, prior to the start of manufacture of the units:

a. Transformer

- Type and make
- Type of HV winding
- Type of LV winding
- Rating of primary and secondary winding

b. *Rectifier*

- Type and make
- Ripple frequency

3.5 AC Interference Mitigation (Increased Voltage Mitigation)

3.5.1 Gradient Control Wires

Gradient control wires or mitigation wires are typically installed parallel to the pipe as a grounding or earthing mechanism. These wires are also referred to as ribbons. The gradient control wires are generally installed for the following two main reasons: (i) to provide an earthing point which earths induced pipeline currents and reduces the overall pipeline voltage, (ii) to reduce the coating stress voltages and touch voltages in their vicinity by changing the potential of the soil around the pipeline (ground potential rise or GPR).

In the case of one ribbon placed parallel to the pipe, it would generally be placed on the side closest to the overhead powerlines and at the invert level of the pipe. The second ribbon would be placed on the opposite side of the pipe. The ribbon should have a minimum separation distance to the pipeline of 200 mm. These ribbons are connected to the pipe by means of a cable through a DC decoupling device.

If the zinc wires are to be installed in discrete sections, it would generally be limited to 400 m in length with the connection to the pipe made in the middle of such a section. In such a case the ends of consecutive sections must be more than 1 m from one another.

Gradient control wires shall be zinc ribbon. The composition of the zinc shall be as per ASTM B418 95 – Type II, and suitable independent compositional testing (once per batch) shall be carried out by an accredited laboratory, in addition to the quality control information presented by the supplier of the zinc wire.

The zinc wire linear weight is linked to its geometry and shall at least adhere to the requirements as specified in Table.3.3.

Table 3.3 : Zinc ribbon specification

| Aspect | 0.983 kg/m Ribbon | 1.785 kg/m Ribbon |
|---------------------------------|-------------------|-------------------|
| Zinc weight | 0.893 kg/m | 1.785 kg/m |
| Cross section (D1 x D2) | 12.7 mm x 14.3 mm | 22.2 mm x 15.8 mm |
| Radii (R1 x R2) | 2 mm x 5 mm | 2 mm x 5 mm |
| Steel Core Wire diameter | ≥ 3.3 mm | ≥ 3.4 mm |
| Potential | -1.1 VCSE | -1.1 VCSE |

If required, jointing of the zinc ribbon shall be made by exposing the steel core wire and jointing this with a hex crimped ferrule with silver solder. The exposed wire jointed part is then encapsulated with zinc (10 mm minimum cover) by casting this around the joint.

The gradient wire shall be covered with Bedding material used for backfilling the pipe.

3.5.2 Lumped or Nodal Grounding Mat

Lumped grounding or earthing is often required as an additional mitigation measure or as a measure on its own. The gradient control wires are installed for the following two main reasons: (i) to provide an earthing point which earths induced pipeline currents and reduces the overall pipeline voltage, (ii) to reduce the coating stress voltages and touch voltages in their vicinity by changing the potential of the soil around the pipeline (ground potential rise or GPR).

Lumped grounding (earthing) shall be by means of a mat constructed from zinc ribbon. The mat is to be made up by affixing the zinc ribbon at right angles to form a square followed by further zinc ribbon inside this square to form blocks. The dimensions of the square and the spacing of the internal wires shall be in accordance with the specifications and the drawings. At each wire cross point the steel wire core is to be exposed and the steel wire is to be spot welded to one-another. The exposed wire jointed part is then then encapsulated with zinc (10 mm minimum cover) by casting this around the joint.

The grounding mat shall be zinc ribbon. The composition of the zinc shall be as per ASTM B418 -95 – Type II, and suitable independent compositional testing shall be carried out by an accredited laboratory, in addition to the quality control information presented by the supplier of the zinc wire.

The zinc wire geometry shall at least adhere to the following:

Cross section (D1 x D2) : 12.7 mm x 14.3 mm

Radii (R1 x R2) : 2 mm x 5 mm

Zinc weight : 0.89 kg/m

Steel Core Wire diameter : 3.3 mm

Potential : -1.1 VCSE

Such a grounding mat would generally be placed on the side closest to the overhead powerlines and not more than 900mm below finished ground level. The zinc mat would be connected to the pipe by means of two cables directly to the pipe or through a DC decoupling device as specified in the schedule of quantities.

3.5.3 DC Decoupler for Zinc Ribbon and Lumped Zinc Grounding Mat

The grounding (earthing) system that is achieved by zinc material shall not be connected to the pipeline either directly or through a solid-state DC decoupling device (SS-DCD) as defined in the schedule of rates and quantities. Such a device shall be housed in a pre-cast concrete bunker. The device shall be certified by a suitably accredited test laboratory to meet the specifications given in Table 3.4.

Table 3.4 : Performance Specification for DC Decoupling Device for Gradient Control Wire (Ribbon) and Lumped Grounding Mat

| Specification /Test | Level /Requirement | Comment |
|---|--|---|
| Class 1 impulse current rating | 10 kA., 10/350 μ sec | to SANS 61643-1 requirement |
| Front of wave spark-over voltage | ≤ 500 V, 1.2/50 μ sec | to SANS 61643-1 requirement |
| Rated AC short circuit | 3.7 kA r.m.s., 1 sec, 50 Hz | to SANS 61643-1 requirement |
| Rated AC load current | 45 A r.m.s., 50 Hz, max temp incr. 40° C | at maximum DC blocking voltage, to SANS 61643-1 requirement |
| AC impedance at 50 Hz | ≤ 0.04 Ohm | at rated load current |
| DC blocking voltage | -3V/+1V(+/-10%) | Progressive characteristic. |
| DC. leakage (blocked) | ≤ 1 mA | at AC load thermal limit |
| DC current withstand | 10 A for 15 mins | without overheating, test in both directions |
| Housing dielectric withstand voltage | 5.8 kV | to SANS 61643-1 requirement |
| Environmental, enclosure | IP55 | adjust upwards for more extreme environments |
| Ambient temperature range | -15° C to 60° C | |
| Air clearance and creepage distances | 10 mm and 15 mm min respectively | to SANS 61643-1 requirement |
| Protection against direct contact | no direct contact | Using IEC60529 test finger |
| Basic insulation level required | 2 500 VAC | |

Additional requirements for the DC decoupling device are:

- The decoupling device shall comprise a suitably rated diode stack capable of blocking direct current in both directions at the specified voltages.
- The device shall exhibit a progressive, smooth transition from blocking to conduction to and vice versa without commutating.
- A bypass capacitor (network) shall be connected in parallel with the diode stack to conduct 50Hz AC up to the blocking voltage of the diode stack.
- The capacitor (network) shall be protected by a suitably rated surge protection device (SPD) for high voltage and lightning-induced transients. The SPD shall be decoupled from the capacitor and diode network with the appropriate inductance, in accordance with SANS 61312-3. This inductance shall remain effective (i.e. not saturated) during simultaneous transient and maximum DC current conditions.
- The decoupling device shall preferably be of open frame construction to permit maintenance and replacement of component parts. The frame shall be sized to fit on a standard 800 mm x 600 mm chassis plate.
- The decoupling device shall be provided with two M10 terminals at each installation point for the connection of 35 mm² single core cables.
- The housing for the components shall be supplied with a danger warning sign for High Voltage at an obvious place on the unit.

The SS-DCD shall be supplied with wiring diagrams and general arrangement Drawings. All relevant and necessary dimensions together with block wire diagrams shall be supplied prior to manufacture, supply and installation for approval by the Engineer. Details of the enclosure and layout shall also be provided

3.5.4 Equipotential Apron (Mats) / Plane

Gradient control wires or mitigation Equipotential aprons or mats are required at all locations of the exposed pipeline appurtenances (i.e. valve chambers, bunkers and test posts, structures in contact with the pipe, structures housing components that are connected to the pipe) on the pipeline sections where specified.

Equipotential aprons shall be implemented with steel weld mesh mats or rebar grids.

Steel weld mesh installation at chambers or bunkers (or structures) shall be as follows:

The concrete apron is usually placed on the finished ground level around the structure (or buried at a depth as shown on the drawings). The apron shall only be placed on firm undisturbed ground or a compacted prepared base. The dimension of the concrete apron shall be at least 1.2 m from any part of the structure.

A 200 mm x 200 mm reinforcing steel weld mesh of 6 mm diameter steel wire (not galvanized) mesh ref number 193 extending 1.2 m beyond the external wall of the chamber. All overlaps shall be 200 mm minimum joined by welding at least every 400 mm to form an electrically continuous system.

For circular chambers the weld mesh shall be two overlapping panels with a circular cut-out to achieve a 1.2 m distance from side of the chamber – the mesh may be cut square if preferred on condition that the minimum distance of 1.2 m is achieved.

The weld mesh is centrally located in an 85 mm thick Class 15/19 MPa concrete slab.

The mesh panels are connected to the pipeline with two cables through a voltage limiting device and the cables be kept as short as possible (≤ 1.5 m). Refer to section 3.5.5

Continuity in a reinforced steel concrete structure relies on the interconnection of the re-bar (reinforcing). The reinforcing is then equipped with at least two (2) connector plates (5 mm thick steel with a 12 mm hole for cable connection) which is welded to the mesh / re-bar protruding through the wall at suitable positions. The connector plates are connected to the pipeline with a cable through a voltage limiting device and the cables kept as short as possible (≤ 1.2 m).

For air valves using pre-cast concrete rings as walls, the steel reinforcing is generally inaccessible and only the reinforcing in the concrete floor is connected to the pipeline.

3.5.5 Voltage Limiting Device for Equipotential Plane

The equipotential planes for pipelines equipped with a Cathodic Protection system shall not be connected to the pipeline directly, but only through a suitable decoupling device. Such a device shall be housed in a valve chamber or a dedicated enclosed AC mitigation station as appropriate. The device shall be certified by a suitably accredited test laboratory to meet the specifications given in Table 3.5.

Table 3.5 : Performance Specification for Voltage Limiting Device (VLD) for Equipotential Mats or Steel Reinforcing of a Concrete Structure

| Specification / Test | Level / Requirement | Comment |
|---|----------------------------------|--|
| Nominal impulse discharge current rating | 10 kA., 8/20 μ sec wave form | to SANS 61643-1 requirement |
| Voltage protection level | ≤ 400 V | to SANS 61643-1 requirement |
| Response time | ≤ 25 nsec | |
| Short circuit withstand | 3.7 kA r.m.s., 1 sec, 50 Hz | to SANS 61643-1 requirement |
| Housing dielectric withstand voltage | 5.8 kV | to SANS 61643-1 requirement |
| Maximum continuous AC operating voltage | 75 Vr.m.s. (+/-10%) | |
| Maximum continuous DC operating voltage | 100 V (+/-10%) | |
| Operating state / Fault indication | Green / Red | Mechanical switch |
| Environmental enclosure | IP55 | Adjust upwards for more extreme environments |
| Ambient Temperature | -15° C to 60° C | |
| Air clearance and creepage distances | 10 mm, 40 mm respectively | to SANS 61643-1 requirement |
| Protection against direct contact | IP4X | Using IEC 60529 test finger |

The housing for the components shall be supplied with a danger warning sign for High Voltage at an obvious place on the unit.

3.6 Cabling

All connections of cathodic protection and AC interference mitigation materials and plant to the pipeline and equipotential apron / mat / structure reinforcing, are to be made with single core multi-strand copper cables. All cables are to be insulated as specified and rated for voltages up to 600 V / 1 000 V. The stranding shall be in accordance with SANS 1507.

Table 3.6 : Cable specification (unless specified otherwise on the drawings)

| Purpose | Size (mm ²) | Insulation | Colour |
|---|--|-------------------------------------|---------------|
| Pipe to VLD in chamber/bunker | 25 | PVC/PVC | Black |
| Pipe to DC decoupler in chamber/ bunker | 35 | PVC/PVC | Black |
| Pipe to a link coupling for monitoring in chamber/bunker | 16 | PVC/PVC | Black |
| Pipe to chamber/bunker in ground for monitoring or coupons | 16 | PVC/PVC | Black |
| Pipe to chamber/bunker in ground for VLD | 25 | PVC/PVC | Black |
| Pipe to chamber/bunker in ground for DC decoupler | 35 | PVC/PVC | Black |
| AC Coupon to link coupling in chamber/ bunker | Two Core 6 | PVC | Blue |
| Grounding wire (ribbon) | 35 | PVC/PVC | Yellow /Green |
| Grounding to mat/apron/chamber mesh | 25 | PVC/PVC | Yellow /Green |
| Continuity bonding in chamber | 16 | PVC/PVC | Black |
| Cross bonding and continuity bonding in soil around a structure | 2x 35 | PVC/PVC | Black |
| Continuity bonding in soil around a flange | 2x 5mm thick steel flat welded to flange | Encapsulate with bituminous product | N/A |

The cable to zinc connections shall comprise of suitably sized hex crimped ferrules between the cable and the steel core of the zinc ribbon. The ferrule shall be silver soldered after crimping. The whole joint and an overlapping section past the jointed area shall be encapsulated with an approved self-vulcanizing butyl rubber tape and heat shrink mastic lined tube with a 2.5 mm after recovery thickness.

Splicing of cables underground shall be avoided. However, should splicing be required, a suitable compression fitting and press tool shall be used or alternatively a line tap if an additional cable is to join the main cable. The connections are to be waterproof epoxy filled splicing kits. The cable insulation is to be roughened with 160 grit sand paper before the epoxy is poured into the mould. The epoxy is to completely cover the exposed cable and jointing material and shall fill the mould completely. Sufficient time must be allowed for the epoxy to set (as per manufacturer's instructions) before the joint is buried. The epoxy splicing kit may not be used if the expiry date has passed.

Lug connections shall be made with heavy duty copper with electroplated tin connector lugs of appropriate size. A heat shrink sleeve shall be provided to seal off the break in insulation and the lug and this sleeve is to protrude sufficiently past this point to make a waterproof seal.

Cable markings shall be one of the following types:

- Snap-on plastic marker of suitable size with engraved black lettering on yellow background.
- Stainless steel strip tape with information punched in (minimum letter height 4.5mm) with metal fixing ties.

3.6.1 Cable Connections to Pipe

3.6.1.1 General

A suitable method to secure cables to pipes is required to allow for continuity bonding, cross bonding, pipe to test post connections, CP, ACIM component connections to be made.

The connection of a cable to the steel pipe is preferably made at any thicker part available at the jointing locality – such a thicker part be a pad specifically provided for this purpose, the socket of an insert type connection, a flange, or any other suitable thicker material part.

Cable connection on thin walled pipes (less than 8 mm thick) or pipes lined with epoxy or polyurethane requiring any form of heat must be made with the pipes full of water unless the pipe has been supplied with thermit welding pads. Any such welding must be preceded with by a trial on a spare pipe and the lining subjected to a holiday detection test (spark test) before and after the attachment.

A detailed application and quality control procedure for any proposed cable connection to pipe is required after successful trials have been made and a proposed cable connection method is established.

Thermit welding is the preferred method should it comply with the requirements. Stud welding or thermit welding with solder pads are the alternative preferred method of cable attachment on thin wall pipes (i.e. wall thickness less than 8 mm).

3.6.1.2 Thermit Welding

As far as possible, cables are to be connected to the pipe barrel at a field joint prior to field joint repair and coating make good or at a flange.

The area where thermit welding is to take place shall be thoroughly cleaned to provide an area approximately 75mm x 75mm. All traces of petroleum mastic, concrete, pipeline coating, primer material or any other matter must be removed and the surface is to be brushed with a steel wire brush. Prior to making the weld the area must be roughened using a coarse file or flapper disc, and preheated with a portable gas torch.

The end of the insulated cable must be made bare for at least 25mm. A retaining cap in the bottom of the mould is placed and the weld powder is poured into the mould. The weld is covered with the starting powder. The cable is then placed on the pipe and the mould squarely over the cable, pressing it down firmly. The lid

is closed, the starting powder is ignited with a flint gun which allows the weld to solidify. The mould is removed and the residue is cleaned out in preparation for the next weld.

After the above procedure has been carried out, the weld shall be tested by tapping the weld with a 2kg hammer. Should any movement occur the cable shall be re-welded and re-tested.

3.6.1.3 Stud Welding

Remove section of pipe coating using a portable sanding device. Remove all traces of dirt and degrease.

The weld gun must be manually loaded with an appropriately designed stud and pressed onto the pipe surface in such a way that the supporting feet touch the surface of the pipe. The welding process is initiated by actuating the start button. Against the force of the pressure spring, the gun coil lifts the lifting mechanism with the welding stud off the surface of the pipe by the set gap distance. The power thyristor of the welding unit is triggered. The gun coil is switched off-circuit so that the stud is accelerated back onto the pipe surface by means of the pre-tensed pressure spring. As soon as the ignition tip of the stud touches the surface of the pipe, the welding circuit is closed. The high capacitor discharge current of the welding unit has the effect that the ignition tip of the stud partially evaporates. In so doing, the ignition gap between the surface of the pipe and the stud is ionised and welding arc is ignited.

As a result of the heat charge of the welding arc, the fore-part of the stud and an area of the pipe surface of approximately the same size melt so that a pool of molten mass forms on the areas to be welded. When the stud makes contact with the surface of the pipe, the arc goes out. Before the molten mass hardens the stud is pressed by the force of the spring. The remaining energy of the capacitor battery is discharged in a short circuit. The weld gun can then be removed from the welding stud immediately afterwards.

Connect the lugged cable to pipe using stud welder.

3.6.1.4 Pin Brazing

The technique used shall ensure that metallurgical contact is achieved between the cable and the pipe. Details of the equipment to be used must be submitted to the Engineer before being applied.

The minimum area of coating shall be removed. After connecting the cable the entire exposed area shall be encapsulated in epoxy. The procedure for this is as follows:

- Clean the remaining coating to at least 50mm beyond the final repair limits.
- Construct a dam from a suitable material around the coating repair area.

Apply 2 component (squish pack) over the repair area, ensuring a minimum 1mm cover over the cable connection (Epoxy 151 UW or similar product approved by the Engineer). A minimum overlap of 50mm shall be made over the existing coating.

3.6.1.5 *Making Good of the Coating System*

All coating repairs at cable connections shall be made in accordance with the repair procedures relevant to the coating system applied to the pipe.

If cables are attached to the barrel of the pipe, these attachments should be made at field joints to minimise the number of repairs required. If the pipe is epoxy lined, then repairs will also be required to the internal lining.

Any attachments to the barrel of the pipe which are buried, will require repair using circumferential wrapping. Patch repairs may not be used in buried applications.

Cable connections to epoxy or [polyurethane] coated fittings in valve chambers shall be encapsulated with epoxy or a heat applied bituminous patch.

4 MATERIALS AND PLANT MANUFACTURING

4.1 General

All materials shall possess qualities adequate for the purpose for which they are to be used. All materials and properties claimed for these materials shall, unless specified otherwise in this document, comply with the requirements of the latest edition of the appropriate South African or other internationally recognised standard specification at the time of Tender.

For each type of Plant, the manufacturer and or supplier shall indicate the materials used for each of the proposed sub-assemblies.

The Plant shall be manufactured using new prime quality materials taking into account the latest technical innovations. Recycled and/or reconstituted materials will only be considered if they are fully justified and approved by the Engineer prior to manufacture and/or supply.

The Engineer retains the right to request and obtain full references of suppliers and materials and Plant supplied as well as all original copies of all the material's Certificates of Conformity regarding raw materials used to manufacture products.

4.2 Compatibility of Materials

The responsibility for selecting materials, which are compatible with the liquids or surroundings with which the Plant comes into contact, to prevent corrosion and/or abrasion rests with the Contractor. The materials used shall be at least equal to those specified in this Specification.

4.2.1 Electrical Cables

All cables supplied and installed shall conform to the requirements of Annexure 1

Cable designations, sizes and insulation requirements are listed in the Bill of Quantities

4.2.2 Stationary Reference Electrodes (SRE)

All stationary reference electrodes (SRE's) shall be designed for permanent burial. All SRE's shall be of the Zinc/Zinc Sulphate (Zn) type and calibrated to a calomel reference electrode with a tolerance <10mV. Certification and approval shall be furnished prior to delivery of any SRE.

4.2.3 Insulating Flange Kit

An insulating flange consists of an insulating gasket, bolt sleeves and washers, appropriately sized steel bolts and nuts and washers and a voltage limiting spark gap for protection of the insulating materials.

The insulating gasket between flanges to be in accordance with Table 4.1 based on pipe diameter and pressure rating. The I.D. of the pipe and gasket shall in all instances be equal.

Table 4.1 : Insulating Gaskets

| No | Field Test Pressure (MPa) | Nominal Pipe Diameter (mm) | Insulating Gasket Material |
|----|---------------------------|----------------------------|--|
| 1. | Lower or equal to 4.6 | All diameters | 3mm aramid fibre/nitrile rubber (Novus 34 or equivalent approved by the Engineer) full face gasket in one piece. |

Insulating sleeves shall be a minimum 1mm thick glass fibre reinforced epoxy resin sleeve for each bolt. Total length of sleeves is to be 2-3mm less than the length between inside faces of steel washers. The insulating sleeves shall fit completely inside the insulating washers.

Insulating washers shall be 6mm thick LHM G11 silicon glass with O.D. the same as that of machined steel washer, 2 off for each stud bolt. The I.D. to be a sliding fit over the insulating sleeve.

Steel washers shall be machined with diameter and thickness as indicated in Table 4.2

Table 4.2 :Machined Washers

| Stud bolt Diameter (d) | Machined Washer Thickness |
|------------------------------------|---------------------------|
| $d \leq 36\text{mm}$ | 6mm |
| $36\text{mm} < d \leq 42\text{mm}$ | 8mm |
| $d > 42\text{mm}$ | 10mm |

Stud bolts and studs shall be grade 8.8 and nuts grade 8 to SANS 1700. Stud bolt diameters shall be selected to the next smaller size for installation in standard drilled flanges. Stud bodies shall be machined down to the next standard smaller size and suitable smaller nut to be used.

Special stepped stud bolts shall be used for blind tapped holes opposite spindles in valve bodies.

Explosion-proof Spark Gap Type ExFS™ L300 shall be installed across the flange faces complete with hot-dip galvanised mild steel mounting brackets to suit the flange bolt, as supplied by Dehn or similar approved by the Engineer. The width of the holding bracket of the explosion-proof spark gap shall be the same as the steel and insulation washers and the bottom end be rounded off to fit into the spot faced area of the valve and/or steel flange.

The outer rims of the flanges must be wrapped circumferentially with a white plastic backed polymer modified bituminous tape, or similar approved, 1,5 to 2,0mm thick with a minimum 25mm overlap. In case of surface irregularities, i.e. raised face flanges, etc., an approved mastic material shall be used to provide a smooth contour for subsequent tape application. A 25mm wide plastic backed electrical tape (SANS 122-1975) coloured red shall be applied in the centre on the horizontal surface. A metal tag shall be attached via a 1mm stainless steel locking wire through a 2mm hole drilled in the tag and in the most overt insulating flange bolt. The following is to be stamped on the metal tag: **"OPERATING INSULATING FLANGE"**

5 INSTALLATION AND OPERATING REQUIREMENTS

5.1 Electrical continuity

The steel pipeline will be electrically continuous in defined sections between in-line valves. Where required, in-line valves will be bonded either internally within chambers through a link panel or externally with buried cables, as detailed in the installation schedule. All buried flanged joints will be bonded prior to encapsulation.

5.2 Insulating Flanges (IF)

In order to effect isolation from the earth conductors of electrical actuators, IF kits will be installed each side of each actuated in-line valve and in accordance with the CP and AC mitigation design.

Insulation at pump stations is installed on the first suitable flange inside the pump station precinct as designated on the drawings.

Insulating flanges are required both sides of electromagnetic flowmeters.

After installation, all insulating joints must be inspected and tested to ensure their compliance with the Specifications and Drawings. The proposed test method and sequence shall be agreed with the Engineer in order to ensure the efficiency and compliance regarding electrical isolation. The inspection shall be witnessed by the Engineer and tested by the Contractor.

5.3 Test Stations

All cables shall be terminated using tinned copper bootlace ferrules or blade/pin lugs. All cables shall be labelled.

All cables will be interconnected through appropriate link panels as shown on the Drawings.

Pipe cables shall be connected directly to the pipe and brought into the test station bunker.

Type B test points shall be installed as indicated in the CP Design document and as directed in the installation schedule.

Stationary reference electrodes and coupons shall be installed at pipe mid-line at Type B locations on the opposite side of the valve chamber to the sacrificial anodes as designated in the installation schedule.

Type C test points are required at all foreign pipeline crossings, and/or parallel sections and/or convergence and/or divergence from the foreign pipelines as indicated on the Drawings or by the Engineer.

Test stations in ACIM areas will incorporate the requisite SSDCD's as detailed in the Installation Schedule.

5.4 AC Interference Mitigation Systems

Installation of AC Interference Mitigation systems shall take place concurrently with pipe laying.

Temporary connections from the zinc ribbon to the pipe may be made prior to installation of bunkers at valve chambers if necessitated by high AC potentials.

Permanent connection of the zinc ribbon will be made directly to the pipe by thermit welding at the nearest field joint

5.5 Permanent ICCP Installation

Groundbed location shall be as indicated on the Drawings or instructed by the Engineer.

The groundbed shall be excavated to 3m depth.

The coke column shall be installed to 150mm depth and the coke shall be thoroughly tamped down prior to the installation of the anodes. Once the anodes and the ring main have been installed, the balance of the coke column shall be installed and tamped down before backfilling.

The feed and return cables from the groundbed shall be routed to the TRU and terminated directly on the TRU.

5.6 Records

The following complete records shall be kept on site for inspection by the Engineer and handed over at the end of the Contract. The location of each excavation, anode excavation and/or anode, test point, AC mitigation enclosure, cross bond to any foreign service pipeline and/or any cable or bond shall be marked and numbered with the allocated tag number before any photo is taken.

5.6.1 Permanent anode ground-beds (ICCP)

- a. Individual anode DGPS position and depth of installed anode and photographed;
- b. Anode header cable route (all bends) DGPS position and cable depth (no joints).

5.6.2 Test Points and DC Cable Connections to the Pipeline

- c. Pipeline depth and DGPS position;
- d. Photograph of exposed pipeline (before coating removal - if applicable);
- e. Photograph of pipeline with coating removed and/or pipeline cleaned;
- f. Photograph of welded cable connections (before priming and re-coating);
- g. Photograph of re-coated area
- h. Description and photograph of bedding/padding material;
- i. Description and photograph of test point foundation;
- j. Photograph of test point installation and surround;
- k. Photograph of test point terminations and connections;

- l. Coupons;
- m. SRE;
- n. Bunker installation including Concrete Test Results;
- o. Details of keys and locks; and
- p. Drawings, data sheets, etc.

5.6.3 AC Mitigation Test Points and AC Mitigation Cable Connections

- a. DGPS position of zinc ribbon at start point, end point including all bends and description and photograph of zinc ribbon bedding/padding material;
- b. Nodal installation details
- c. DGPS position and photograph of all zinc ribbon joints;
- d. Record and description of all equi-potential earth grids/mats including records of the installation, progressive compaction and reinstatement;
- e. Description and photograph of AC mitigation enclosure foundation;
- f. Description and photograph of AC mitigation enclosure installation and surround; and
- g. Photographs of AC mitigation terminations and connections.
- h. Drawings, data sheets, etc

5.6.4 Bonding to Other Pipelines

- a. Pipeline depth and DGPS position at crossing and/or bond location;
- b. Pipeline exposed (before coating removal) and photographed;
- c. Pipeline coating removed;
- d. Welded cable connections (before priming and re-coating) and photographed;
- e. Re-coated area (full circumferential wrap with 50% overlap) and photographed;
- f. Bedding/padding material and photographed;
- g. Test point foundation;
- h. Test point installation and surround; and
- i. Test point terminations and connections.

6 TESTING/COMMISSIONING

All CP and AC interference mitigation plant and material shall be energised and/or tested at the manufacture or Contractors facility prior to site release.

6.1.1 Factory Acceptance Testing

Factory Acceptance Testing (FAT) shall take place at the manufacturer's facility. The FAT shall demonstrate conformance with this specification and shall take place prior to dispatch.

6.1.2 Testing of Insulating Joints (IF Kits)

Insulating joints are to be housed in a well-drained and ventilated chamber / area with inspection access.

Insulating joints shall not leak at field test pressure.

After installation, the insulating joints must be inspected to ensure their compliance with the specifications and drawings and tested for satisfactory electrical insulation. The inspection shall be witnessed by the Engineer.

A radio high frequency tester should be used to test the insulation of the joint. The test shall be performed on each side of the flange as well as on each bolt-nut set individually.

Re-testing must be carried out upon replacing any faulty component.

6.1.3 Testing of Solid-state DC Decouplers

The solid-state DC decoupler (SS-DCD) shall be tested at the Contractor's expense at the Works or at an independent third-party inspectorate's laboratory/works in the presence of the Engineer. A sample of the SS-DCD to be supplied shall be made available for testing purposes. All of the SS-DCD device components shall pass the tests prescribed below and as per the equipment/component type test data sheets. One complete item shall be fully tested to destruction. The Contractor will issue a Test Certificate upon completion of the tests which shall be signed by the Engineer.

The SS-DCD device shall be tested at 125% of the fault current rating and for at least 10 cycles of a standard 50 Hz cycle. The pre-set DC blocking voltage shall be tested and confirmed. At least 125% of the steady state AC shall be passed through the unit for a minimum 15 minute period. No item and/or component of the SS-DCD shall fail. Failure of a single item/ component shall imply complete failure of the SS-DCD device.

The Engineer may also call for other pertinent tests in order to prove compliance.

6.1.4 Current Drainage Testing (CDT)

The pipeline itself must be electrically continuous and all other civil structures and extraneous earths shall be electrically isolated from the pipeline at pump stations, off-takes, chambers, scour valves, air valves, isolating

valves, non-return valves, etc. by means of insulating flange kits, etc. The pipeline shall not be bonded to Foreign Service pipelines unless designed accordingly and subsequent to interference testing.

Refer to specification PSL 4.4 in section C3.4.3 in the Scope of Works for pipeline coating and cathodic protection acceptance testing.

6.1.5 Energising, Commissioning and Hand-Over

The Contractor shall provide a suitably qualified technician and/or technicians to jointly energise and commission the CP system.

This shall include for:

- Energising and commissioning all SS-DCD;
- Commissioning - Corrosion Coupons;
- Commissioning - IR free potentials;
- Commission – interference testing (AC/DC);
- Commissioning - Data logging (CP TP and AC mitigation sites);
- Electrical Completion Certificate; and
- Mechanical Completion Certificate.

The Contractor shall provide the required equipment, vehicles and personnel to effectively carry out the required services.

6.1.6 CP and AC Interference Monitoring

The pipeline potentials (DC and AC) shall be monitored by the Contractor from the time the first pipe section is backfilled until the permanent CP system is commissioned and is handed over. Baseline potential DC and AC readings are required from the pipe sections prior to connecting any CP and ACIM components to the pipe.

Pipe monitoring shall comprise bi-weekly pipe recordings at all monitoring points. DC potentials shall be measured using spot measurements. AC potential and coupon current shall be recorded over a period of 40hours. DC & AC monitoring shall alternate at fortnightly intervals. This information is to be correlated to determine the effective operation of the CP and ACIM systems. The Contractor shall submit bi-weekly reports of the monitoring and recordings to the Engineer for evaluation.

7 STANDARDS

The following Standards and Codes of Practice with all relevant amendments and attachments shall be utilised as part of the Works where details and/or information is not specifically covered within this Specification. Any conflicts and/or contradictions shall be brought to the attention of the Engineer in writing who shall review the conflicts and/or contradictions and submit written clarification in this regard.

In addition, Standards and Codes of Practice listed in the performance specifications included in the Annexures will also apply.

Standards Australia

AS/NZS 4853 Electrical Hazards on Metallic Pipelines.

International Organisation for Standardization

ISO 14555 Welding - Arc stud welding of metallic materials.

International Standards and Procedures

| | |
|-------------|--|
| ASTM B – 8 | Concentric-Lay Stranded Copper. Conductors |
| ASTM B418 | Cast and Wrought Galvanic Zinc Anodes Used For Cathodic Protection |
| DIN 50925 | Corrosion of metals; proof of effectiveness of cathodic corrosion protection of underground installations |
| NACE TM0102 | Measurement of protective coating electrical conductance for underground pipeline |
| NACE TM0109 | Techniques for aboveground evaluation of the coating condition of underground metallic pipelines |
| NACE SP0207 | Performing close-interval DC pipe-to-electrolyte potential surveys on buried or submerged metallic pipelines |
| NACE SP0502 | Pipeline external corrosion direct assessment methodology |
| NACE SP0286 | Standard Practice: Electrical isolation of cathodically protected pipelines |
| NACE SP0177 | Standard Practice: Mitigation measures of alternating current and lightning effects on metallic structures and corrosion control systems |

South African National Bureau of Standards

| | |
|---------------------|--|
| SANS 121 (ISO 1461) | Hot dip galvanised coatings on fabricated iron and steel articles. |
| SANS 122 | Pressure-sensitive adhesive tapes for electrical purposes (Metric units) |

| | |
|-------------------------------|---|
| SANS 1411 | Materials of insulated electric cables & flexible cords |
| SANS 1411 Parts 1 to 7 | Materials of insulated electric cables and flexible cords |
| SANS 1507 Parts 1 to 6 | Electric cables with extruded solid dielectric insulation for fixed installations (300/500 V to 1,900/3,300 V). |
| SANS 1700 SET | Fasteners |
| SANS 10064 | Preparation of steel surfaces for coating. |
| SANS 10140 | Parts 1 to 3: Identification - Colour Marking. |
| SANS 10142 Part 1 | The wiring of premises Part 1: Low-voltage installations |
| SANS 10129 | Plastic tape wrapping of steel pipelines. |
| SANS 13509 | Cathodic protection measurement techniques |
| SANS 15589 -1 | Cathodic protection of pipeline transportation systems: Part 1: On-land Systems |
| SANS 50162 | Stray Currents |
| SANS 53509 (EN 13509) | Cathodic protection measurement techniques |
| SANS 50162 (EN 50162) | Protection against corrosion by stray current from direct current systems |
| SANS 60479-1 (IEC TS 60479-1) | Effects of current on human beings and livestock |

Other Standards and Guidelines

Eskom 240-66418968 Guideline on the electrical co-ordination of pipelines and powerlines

8 GUIDELINES FOR SAFE WORKING PROCEDURES

The following guidelines for safe working procedures at pipeline construction close to high voltage overhead powerlines are applicable:

Attention!

This is not a comprehensive safety procedure. This Procedure provides some of the general safe practices and is not a comprehensive manual. The intention of this procedure is to raise the awareness of potential dangers to the pipeline construction team caused by nearby electrical circuits and to define some minimum safety requirements. The Contractor remains fully responsible for safe working procedure in terms of the Contract.

8.1.1 Introduction

When construction activities occur within electrical power line servitudes, there are a number of issues that need to be considered that are influenced by the relative localities of the pipeline and overhead power line or power cable.

Unsuspected voltage can be present on a pipeline (and pipes ready for constructing a pipeline) through Conductive, Inductive as well as Capacitive coupling between a pipe or pipeline and the nearby electrical circuits.

During a power line fault or lightning strike, very high voltages can be induced in the pipeline, which can damage the cathodic protection systems, rupture the coating, and present a significant safety hazard for any person close to or in contact with the pipeline and its appurtenances. During normal operation the induced pipeline voltages are lower, but could still present a safety hazard and can result in accelerated corrosion of the pipeline.

Any raised electrical potentials found on a pipeline should be reported to a competent person so that the cause is understood and that appropriate mitigation measures can be implemented. This section should not be viewed as a restriction to use better methods and it should be understood that a generalized account does not make provision for unpredictable or un-expected circumstances.

Additional Abbreviations for this Section:

| | |
|-------|---|
| ESA | Electrical Supply Authority |
| HVDC | High Voltage Direct Current |
| LVAC | Low Voltage Alternating Current : <1 kV |
| MVAC | Medium Voltage Alternating Current : 1 kV to 33 kV carried on Distribution Lines (Dx) |
| HVAC | High Voltage Alternating Current : 44 kV to 132 kV carried on Distribution Lines (Dx) |
| EHVAC | Extra High Voltage Alternating Current : >132 kV carried on Transmission Lines (Tx) |

Note: Direct connection (including arcing danger) is relevant for all overhead powerlines regardless of the system normal voltage it is known for (it therefore includes low voltage system as well).

8.1.2 Normative Documents

The latest edition at time of project commencement of all the normative documents shall be regarded as forming part of this document and shall have equal standing. In case of a conflict this document shall take precedence.

The Contractor is to obtain its own copy of these publication(s) and shall have a copy available at the construction site.

NACE standard SP0177 titled “Mitigation of Alternating Current and Lightning Effect on Metallic Structures and Corrosion Structures”

Attention is drawn to section 5.3: “Construction”.

The minimum protective measures for AC influence are provided in the NACE SP0177 standard, and this should be followed on the site of Works.

This document is available from the National Association of Corrosion Engineers (NACE) International and can be purchased online from their web site (www.nace.org).

Eskom guideline titled “Guideline on the Electrical Co-ordination of Pipeline and Power Lines” with unique reference number 240-66418968

A copy of this document can be downloaded from the Corrosion Institute of Southern Africa website (www.corrosioninstitute.org.za under the TAB Core Knowledge – Publications).

The normative and informative documents listed in this Eskom guideline form part of the suite of documentation that shall be applied to the construction activities where applicable.

8.1.3 Electrical Safety Officer

An Electrical Safety Officer (ESO) shall be appointed for the site of Works prior to any work commencing close to or within an electrical powerline servitude.

The ESO shall have sufficient training to understand basic electricity as well as specialist training on steel pipe construction close to electrical powerlines.

The ESO shall have the following minimum qualifications as per Eskom Guideline on the Electrical Co-ordination of Pipeline and Power Lines:

Completed the Eskom’s Operating Regulations for High Voltage Systems (ORHVS) responsible person training course

Be authorised by an ORHVS authorised person (GMR2.1) to work without constant supervision in a power line servitude

Completed the South African Electrolytic Corrosion Committee (SAECC) Electrical Safety Officer training course

Experience in the supervision and management of temporary mitigation measures during pipeline construction

The ESO must be furnished with the authority and equipment required to implement and maintain safe working conditions. The ESO shall have the required measurement instruments and equipment to measure AC and DC potentials with respect to adjacent ground and remote earth.

The ESO shall keep a record of any non-compliance and advise the construction manager (site agent) and the project safety officer.

8.1.4 General Safety Requirements

- a. All construction personnel and visiting persons entering the site of Works shall be made aware of and able to recognize the potential shock hazards and be trained in appropriate safety measures. The awareness shall be for electrostatic (capacitive), electromagnetic (inductive) and conductive coupling (resistive) conditions.
- b. All overhead electrical power lines should be regarded as being “live” (ie connected to a power supply causing a carrying potential (voltage) which is dangerous.
- c. The Contractor shall determine and have available on site the local representative name and contact details of the electrical supply utility(s). The Contractor shall have local liaison with the electrical utility to know when planned switching, outages, load changes or any changes that may affect the pipeline induced or capacitive voltages. Work involving contact with the pipe and pipe sections shall be stopped during scheduled switching and re-closing of the electrical power system.
- d. Qualified personnel shall measure and record the pipeline voltage to earth to verify that conditions are safe to work (ie $V_{ac} < 15 \text{ V rms.}$), on all sections and on each day prior to the commencement of any construction or other activity involving contact with the pipeline.
- e. For pipeline voltage measurements, a voltmeter of suitable range and impedance shall be used. Low resistance earth connections shall be used to avoid induction or capacitive pickup on test leads and related items that could result in erroneous readings on a high impedance instrument.
- f. Test leads shall be attached to the instrument first and then to the pipeline. After measurement, the leads shall be removed from the pipeline first and from the instrument last.

Each time a voltage measurement is made, the following minimum data shall be recorded:

- location,
 - time,
 - date, and
 - pipe-to-earth voltage.
- g. An adequate record keeping systems shall be developed and kept up to date by the Contractor. This record keeping shall include all daily recorded measurements and readings in an orderly manner.

8.1.5 Arrangements Regarding Work Within and Near to a Powerline Servitude

Note: This section is relevant when working near to or within all overhead powerlines and underground cables with a system normal voltage >1 kV (ie all MVAC, HVAC, and EHVAC as well as any DC overhead powerlines).

- a. No work may commence within a powerline servitude unless the Electrical Supply Authority (ESA) (Eskom or other institution) has issued a letter of consent and the Contractor has submitted a letter of acceptance to the conditions of the ESA. The application, letter of consent and acceptance letter from the Contractor must be available on site at the site offices at all times.
- b. If permission has been granted, the Contractor must give at least 7 working days prior notice of the commencement of work.
- c. The Electrical Supply Authority (ESA) (Eskom or other institution) shall at all times have unobstructed access to and egress from its servitude areas.
- d. The construction of temporary (or permanent) metallic fences can be extremely hazardous and is prohibited without written approval from the relevant ESA.
- e. The use of explosives of any type within 500m of a powerline or cable servitude is not permitted without the written consent from the relevant ESA.
- f. Changes in ground level may not infringe the statutory ground to conductor clearances or the statutory visibility clearances.
- g. The Contractor is to report any damage to the ESA property, private property or public facilities to the relevant authority. Repair measures are to be agreed upon and a signed off completion inspection release is required from the relevant authority for each case.
- h. No excavations are permitted within the following distances of any above ground powerline structure (includes tower structure, guy wires, anchors and any other attachment):
 - MVAC & HVAC : 6m
 - EHVAC : 20m.
- i. No above ground buildings or temporary structures are allowed within the servitude areas and the following additional distances from the centre line of a MVAC & HVAC (ie up to 132 kV) powerline applies:
 - all voltages < 22 kV and 22 kV : 9 m
 - From >22 kV to 88 kV : 11 m
 - From >88 kV to 132 kV : 18 m

- j. No above ground buildings or temporary structures are allowed within the servitude areas and the following additional distances from the centre line of an EHVAC (ie >132kV) powerline applies:
- From 220 kV to 275 kV (delta) : 18 m
 - From 220 kV to 275 kV (horizontal) : 23.5 m
 - From 132 kV to 400 kV (self-supporting) : 23.5 m
 - From 132 kV to 400 kV (stayed) : 27.5 m
 - From >400 kV to 765 kV : 40 m
- k. The ESO must be in contact with the electrical utility to know of planned switching, outages, and load changes that may affect pipeline voltage. Work involving contact with the pipeline shall be stopped during scheduled switching of the electric power system.
- l. When the AC mitigation measures agreed upon by the Eskom and the Employer have been installed, an Eskom representative must be requested to inspect all the components of this installation and to perform necessary measurements according to the inspections required.

Final approval of the CP and AC mitigation installation is subject to the outcome of this inspection by Eskom.

8.1.6 General Safe Working Procedures Within and Near to a Powerline Structure

- a. No person, equipment or machinery shall enter the HVAC, EHVAC or HVDC servitude without the approval of the ESO. All affected areas shall be suitably demarcated and access restricted to those personnel who have been advised of the hazards and requirements when working underneath or adjacent to HVAC, EHVAC or HVDC power lines.
- b. All personnel shall be made aware of and be able to recognize the potential shock hazards and be trained in the approved safety procedures.
- c. Pipeline construction personnel shall avoid contact with HVAC, EHVAC or HVDC structures and supports. No mechanical equipment shall come closer than 5 m from any power line tower.
- d. Direct connections to the power line tower structures or buried counterpoise earthing system are not permitted under any circumstances. The earthing systems of the power line and the pipeline must be kept separate.
- e. Temporary construction sheds, trailers, living quarters, pipe sections, storage areas or vehicle fuelling facilities are not permitted in the HVAC, EHVAC or HVDC servitude.
- f. Vehicles such as mobile cranes with extendable members that can potentially exceed the minimum vertical clearance height shall be identified and the operators issued with specific instructions with regard to the maximum permissible extension, prior to doing any work in the HV/EHV servitude.
- g. If for any unforeseen reason, the life-threatening situation occurs where a construction vehicle comes into contact with a live HV/EHV conductor or a flash-over occurs, the operator(s) shall remain inside the vehicle and attempt to get it out of the contact situation using ONLY the vehicle's own power. On NO account shall the operator(s) leave the vehicle and on NO account shall any person approach the vehicle, until the contact situation has been reversed, or until the ESO has received confirmation from the electricity utility that the power line has been de-energized. Arcing may temporarily stop due to the action of the protection, however this in itself shall NOT be taken as an indication that the line is safe, since the line may automatically attempt to re-energize. Effective assistance in this

situation entails ensuring that all persons present maintain a safe distance from the vehicle (>10 m) and alarming the electricity utility's operational centre.

- h. Any foreign metal structures exposed during trenching inside or alongside HVAC, EHVAC or HVDC servitudes shall be treated as a live electrical conductor, until measurement proves otherwise.
- i. The pipeline shall not be bonded to any foreign structures without an assessment by a qualified engineer and written permission from the owner.
- j. The use, storage, disposal, treatment or generation of any hazardous substances shall not be permitted in the power line servitude.

8.1.7 Direct Connection (Conductive Coupling)

Note: This section is relevant for all overhead powerlines regardless of the system normal voltage it is known for (it therefore includes low voltage system as well).

- a. When a power system with a grounded neutral has unbalanced conditions (eg during a power transmission tower fault) current may flow to the earth. Substantial currents in earth may result from phase-to-phase-to-ground or phase-to-ground faults. The following conditions may result from such faults:
 - A metallic structure (eg a steel pipe) in the earth may form part of the current path
 - A metallic structure (eg a steel pipe) in the earth that is coated with a dielectric material (ie insulated from the ground) may develop a significant AC potential across such coating.

Such an unbalance situation on medium and high voltage systems (ie >1kV) usually seen as a short and the power supplier's equipment should automatically cut the power supply to that faulted system. Faults on low voltage power systems (ie 1kV and lower) might go undetected for extended periods of time [SANS10280-1Sec 11.1]. Although the raised soil potential is concentrated within the immediate vicinity of the short, the hazardous electrical potential can be transported over long lengths in the metallic structure (eg pipe). Touching the metallic structure during the duration of the short can cause fatal electrical shock.

- b. All persons on site of Works shall avoid contact with MVAC, HVAC, EHVAC or HVDC powerline structures and its supports. No mechanical equipment shall come closer than 5m from any powerline structure and associated element.
- c. Upon entering or crossing a LVAC, MVAC, HVAC, EHVAC or HVDC powerline servitude, appropriate warning signage shall be erected. Such warning sign shall have the electrical hazard sign with the wording warning against overhead powerlines, viz:



- d. A minimum of four (4) signs are to be erected – two facing the approaching direction (one on each side of the pipe route) and the other two the opposite direction (one on each side of the pipe route). The signage shall have reflective markings yellow with black lettering and symbol on steel plate. The overall signage size shall at least be 600mm wide. The signage shall be erected at a suitable height on treated wooden poles (100mm minimum diameter) planted in the ground. The signage shall be maintained in good condition throughout the Contract period and removed upon completion of the project.
- e. The minimum vertical clearance between construction equipment and bare overhead conductors shall be in accordance with SANS 10280. The actual height of the conductors at their lowest point shall be measured by means of optical measuring equipment and during a hot day to ensure that this minimum clearance is achieved. The following are minimum clearances for the nominal rms Voltages:
- Up to 44kV : 3.0m
 - Over 44kV up to 66kV : 3.2m
 - Over 66kV up to 88kV : 3.4m
 - Over 88kV up to 132kV : 3.8m
 - Over 132kV up to 220kV : 4.5m
 - Over 220kV up to 275kV : 4.9m
 - Over 275kV up to 400kV : 5.6m
 - Up to 533kV DC : 6.1m
 - Over 400kV up to 765kV : 8.5m
 - Over 765kV : to be obtained by Contractor from the power utility.
- f. The above clearances are from Regulation 15 of the Electrical Machinery Regulations 1998 of the OHS Act.
- g. Vertical clearance is the open air distance between the top most part of a construction equipment or vehicle and the electrical wire conductor.
- h. All work on a pipeline is to be stopped when lightning (electrical storm activity) is imminent or present at the site of Works. Any heavy weather with threatening lightning is sufficient cause to stop the works. Any heavy weather with threatening lightning or actual lightning along any remote part of an electrically continuous pipe shall result in immediate stopping of all works on the pipeline. In this case an electrically continuous pipe includes both sides of the pipe that is joined by means of an isolated joint as such a joint is not necessarily sufficient to block the voltages generated from lightning strikes.

8.1.8 Capacitive Coupling

Capacitive coupling is typically a hazard during construction with respect to electrical shock or arcing when the structure (eg a pipe section) is on isolated supports (eg wooden chocks) prior to being installed into the ground. Although generally not dangerous, it may cause involuntary movements when electrical discharge happens through a person which can cause secondary harm or damages. Monitoring of voltages on pipes stored in this manner within 1km of an overhead electrical servitude is advised. Appropriate grounding of these sections are recommended.

On pipelines paralleling AC powerlines and for pipe routes crossing powerlines, temporary electrical grounds shall be installed and maintained up to backfilling at 300m intervals, commencing from 1km from the powerline coming close to the pipeline or when the AC potentials rise as the pipe approaches the vicinity of the powerline. Sufficient temporary grounds are to remain until adequate permanent grounding connections are made. Temporary ground can be done with adequately sized cables (35mm² insulated stranded copper wire) and a simple driven ground rod. Grounding to any existing semi-conductor may not be done unless authorized by the ESO.

In all servitude areas of HVAC and EHVAC and HVDC power lines, machinery and vehicles with rubber tyres should be equipped with a heavy duty steel chain fixed to the chassis with a length to allow 1m of chain to freely drag along the ground to discharge any electrostatic build-up.

8.1.9 Inductive Coupling

- a. Inductive coupling from overhead high voltage powerlines can result in dangerous AC voltages and current flow in the adjacent metallic structure (eg the pipe). Induced voltages may increase during power fault conditions. Pipeline voltage measurements are required on installed pipelines from 2 km of the overhead powerline or if the project specifications require it. These measurements are to be taken with a voltmeter of suitable range and impedance. A low resistance ground shall be established by means of a metal rod driven into the ground. Low resistance connections shall be used to avoid induction or capacitance pickup on test leads and related items that would result in erroneous readings on a high impedance instrument. Voltages more than 15 Vac are considered dangerous and work on pipelines must be stopped if this condition occurs. If AC voltages more than 5 V are measured, mitigation measures should be planned for implementation should an AC voltage of 15V be reached.
- b. A suitable recording instrument should be installed to measure AC voltages over a period of 7 days to determine peaks, anomalies and cyclic events if any meaningful presence of AC induced voltages are measured. The frequency of a repeat of the 7 day measurement should be determined in consultation with the powerline representative.
- c. At every section of pipeline that experiences a voltage >15 Vac, electrical shock warning signage shall be erected. Such warning sign would have the electrical hazard sign with the wording “Danger – Electric Shock Risk”, viz:



- d. Two signs per every 500m of pipeline are to be erected adjacent to the pipeline – the signs are to be affixed back-to-back on one pole facing opposite directions. The signage shall have reflective markings yellow with black lettering and symbol on steel plate. The overall signage size shall at least be 600mm wide. The signage shall be erected at a suitable height on treated wooden poles (100mm

minimum diameter) planted in the ground. The signage shall be maintained in good condition throughout the Contract period and removed upon completion of the project.

- e. Pipelines exhibiting voltages greater than 15 Vac rms shall be earthed by means of temporary earth rods of at least 1,8m in length and connected to the pipeline by means a green insulated stranded copper conductor with a cross sectional area of at least 35mm². Prior to connecting the earth rod to the pipeline, the earth resistance of the earth rod shall be measured and if the earthing resistance is higher than 10Ω additional rods shall be installed in a crow's-foot configuration with a spacing of 2m.

Pipelines parallel to AC power systems shall be earthed opposite the midpoint of each span, maximising the distance to the nearest HVAC or EHVAC structure.

The temporary connections to the pipeline shall be made with earthing clamps that apply firm pressure at the contact point with a mechanically sound connection, and with the coating at the contact point removed down to the bare metal.

Temporary ground rods shall be installed at intervals of 300m or less (the evaluation and optimum solution is to be determined for each site),

Temporary earths shall be left in place until immediately prior to backfilling. Sufficient temporary earths shall be maintained on each section until adequate permanent grounding connections have been made.

- f. When the pipeline voltage remains above 15 Vac rms in spite of the temporary earth rods, temporary earth mats that extend a minimum of 1 m outside the work area shall be used. The connection between the pipeline earthing clamp and the temporary earth mat shall be made with 25 mm² or larger stranded copper cable. There shall be no contact between persons over the earth mat and those not over the mat, including the handing over of tools or materials.
- g. To prevent the risk of personal injury or arc burns, the connection and disconnection of temporary earths shall be carried out in the following order:

For connection:

- the earthing clamp is connected to the pipeline,
- the earthing cable is connected to the earth rod,
- the earthing cable is connected to the earthing clamp.

For disconnection:

- the earthing cable is disconnected from the earthing clamp,
- the earthing cable is disconnected from the earth rod,
- the earthing clamp is removed from the pipeline.

- h. The above measures shall be provided when any activity takes place where contact with the pipe is required, eg for welding pipes together, cutting of pipe, surface preparations and coating operations, coating applications at field joints, coating repairs, bolting fittings onto flanged ends of the pipe, etc.
- i. When cutting pipe, adequate bonding across the location of the cut shall be ensured irrespective of the AC voltage measured between the pipeline and earth. The AC potential on the pipe shall be measured and additional earthing installed if this voltage exceeds 15 V AC rms before the cutting commences.
- j. For lowering pipe into the trench that is to be connected to the installed pipeline, the coated pipe section shall be handled with non-conductive slings. All contact with the bare part of the pipe shall be avoided until the pipe is connected with the grounded pipe.
- k. Bonding cables should be provided to bridge any gap between two pipe sections (eg where a valve is to be installed).
- l. Work over insulating joints, flanges or couplings may only proceed after the AC voltage status has been measured. A temporary bond across the flange or the use of a properly sized temporary earth mat shall be used to protect personnel while they work on the pipe.
- m. Where coating is to be applied at field joints or for any other reason (such as repairs), precautions shall be taken to ensure that equipment contacting the bare pipe is adequately bonded and earthed.

9 OPERATING AND MAINTENANCE MANUALS

The following data and documentation as minimum shall be submitted in a Data Pack or as part of the Operating and Maintenance Manuals.

- a. Data Pack (electronically and 3x paper copies):
- b. As-built drawings
- c. Workshop drawings
- d. FAT and SAT documentation
- e. Coordinates of all AC Mitigation & CP components to sub-meter accuracy. DGPS raw data files of TRU, TP, ACM, groundbed and cable routes
- f. Signed off installation sheets
- g. Method statements
- h. Specification and data sheets, certificates and details of all temporary and permanent CP materials used
- i. All information required in terms of the Specification including all photographs, DGPS raw data files, etc
- j. Operation and Maintenance Manuals for all electrical and mechanical components

Operating and Maintenance Manual to contain as a minimum:

- Operating and maintenance instructions for electrical and mechanical components; and
- Operating and maintenance instructions for remote monitoring.

10 MEASUREMENT AND PAYMENT

The CP and AC Interference Mitigation systems shall be deemed to be fully inclusive of all sundry items, such as cable joints, ferrules, lugs, heat shrink, labels, etc., All equipment required to install these sundry items shall also deem to be included in the installation costs such as hydraulic crimping tools, heat guns, grinders, etc. The tendered rates or sums shall cover the cost of anything not specially mentioned, but which an experienced Contractor can reasonably foresee as being required to enable the apparatus and equipment to be installed and/or function safely and correctly as specified. No claims whatsoever for extras will be allowed on the grounds that a necessary piece of plant or part thereof is not specifically mentioned in the Bill of Quantities.

Tender rates or sums shall include for secure packaging to ensure that plant items are not damaged prior to installation and cover costs of delivery, storage, etc.

10.1 Surveys by the Nominated Subcontractor (CP Specialist)

Unit: PS

A CIPS/DCVG coating integrity survey will be undertaken by the Nominated Subcontractor (CP specialist) once the pipeline is installed for the Taking Over Certificate (TOC) and at the end of the Defects Notification Period (DNP) for the Final Certificate (for Fidic Conditions of Contract). For General Conditions of Contract TOC will mean Certificate of Completion, DNP will mean Defects Liability Period and Final Certificate will mean Final Approval Certificate.

A Current Demand Test (CDT) will be conducted by the Nominated Subcontractor (CP specialist) once the pipeline is installed for the TOC.

DC interference current assessment and interference survey of foreign services will be conducted by the Nominated Subcontractor (CP specialist).

Provisional sums are included, and a provision is made against this item for a percentage allowance for overheads, charges and profit on the net cost of the items.

10.2 Supply of cable

Unit: m.

The rate tendered shall include for full compensation of all costs incurred in the manufacture, procurement, supply and delivery to site of all materials and equipment required for installation of cable inside the trench.

Payment will only be effected after full compliance of the items with the Specification has been certified by the Engineer.

10.3 Installation of cables

Unit: No.

The rate tendered shall include for full compensation of all costs incurred for the complete installation of cables. The rate shall further include all terminations, cable ties, cable labels, thermit welding, coating make good, cable warning tape and galvanised conduit where required

Payment will only be effected after full compliance of the items with the Specification has been certified by the Engineer.

10.4 Supply and installation of CP & ACM equipment

Unit: No

The rate tendered shall include for full compensation of all costs incurred in the manufacture, procurement, supply and delivery to site of all materials and equipment required and the complete installation of the plant as detailed in the BOQ.

Payment will only be effected after full compliance of the items with the Specification has been certified by the Engineer.

10.5 Trenching for cables

Unit: m

The rate tendered shall include for full compensation of all costs incurred for excavating the trench. The rate shall include all materials and equipment required for excavating and backfilling the trench.

The rate shall further include for suitable bedding and backfill material around the cables.

Payment will only be effected after full compliance of the items with the Specification has been certified by the Engineer.

10.6 Supply and installation of backfill for anodes

Unit: m³

The rate tendered shall include for full compensation of all costs incurred in the supply and installation of the anode backfill. The rate shall include all materials and equipment required for placing the backfill.

Payment will only be effected after full compliance of the items with the Specification has been certified by the Engineer.

10.7 Coating integrity testing.

The rate tendered shall include for full compensation of all costs incurred in the provision and execution of DCVG and CDT surveys and tests undertaken by the contractor during construction.

No compensation will be made for works required to investigate and/or repair defects identified during these tests. Repeat surveys or tests to prove compliance will not be compensated.

Payment will only be effected after full compliance of the items with the Specification has been certified by the Engineer.

10.7.1 Construction DCVG testing

Unit: sum

10.7.2 Current Drainage Testing during construction

Unit: sum

11 ANNEXURE 1 : PERFORMANCE SPECIFICATION / DATA SHEET: CATHODIC PROTECTION CABLES

Performance Specification / Data Sheet : Cathodic Protection Cables

Referenced Standards:

| | |
|------------------|---|
| ASTM D3222 | Standard Specification for Unmodified Poly(Vinylidene Fluoride) (PVDF) Molding Extrusion and Coating Materials |
| SANS 1507-1 to 6 | Electric cables with extruded solid dielectric insulation for fixed installations (300/500 V to 1 900/3 300 V) Part 1 to Part 6 |
| SANS 1411-1 to 7 | Materials of insulated electric cables and flexible cords Part 1 to Part 7 |
| ISO 9001:2000 | Quality Control and Assurance Specification |

Design and Operating Details :

| | | | | |
|-----------------------------------|--|---|-----|-------|
| Design Life: | Min | 25 years and/or as required by the Design Specification | | |
| Ambient Temperature: | Min | -6°C | Max | +48°C |
| Burial Temperature | Min | 06°C | Max | +15°C |
| Installed Conditions: | Buried soil/electrolyte environment appropriate for service conditions | | | |
| | Anode Cable Insulation to be suitable for installed conditions - low pH, Acidic, Oxygen or Halogen Gas evolution | | | |
| | Cables to be fully UV Stabilised for RSA Conditions | | | |
| Quality Control and Accreditation | ISO 9001:2000 Certified Accreditation / SANS 1507 / SANS 1411 Certified and Accredited Supplier | | | |

Dimensions and Description:

| | | |
|---|----------------------------------|---|
| 1 | Length (Min) | Minimum - As Specified (Maximum 5% Tolerance on supplied length) |
| 2 | Length (Max) | Maximum - As Specified (Maximum 5% Tolerance on supplied length) |
| 3 | Cross Section (mm ²) | As Specified with SANS 1507/SANS1411 Maximum Allowable Tolerance on supplied cable. |
| 4 | Voltage Drop (V) | Maximum Value as determine over length and specified cross sectional area as agreed by client and in accordance with SANS10142 |
| 5 | Operating Temperature | Maximum Value as determine over length and specified cross sectional area as agreed by client and in accordance with SANS 1411/1507 |

Anode Cabling Details

| Insulation Layer | Colour | Insulation | Rating |
|---|--|------------|---|
| Inner: | As Specified | XLPE | SANS 1507/1411 and suitably rated for service conditions - Original Manufacturers Certificate of Conformity |
| Middle / Outer (Double Insulated Cables): | As Specified | PVC | SANS 1507/1411 and suitably rated for service conditions - Original Manufacturers Certificate of Conformity |
| Inner – ICCP Anode | As Specified | PVDF | ASTM D3222 and suitably rated for service conditions - Original Manufacturers Certificate of Conformity |
| Steel Wire Armoured Cables (SWA): | As Specified | Outer PVC | SANS 1507/1411 and suitably rated for service conditions - Original Manufacturers Certificate of Conformity |
| Labelling: | Ferrule Type (Black on yellow) suitably rated for service conditions - (Nominally every 10m for buried cables) | | |

| | | | |
|---|---|--------------------------|--|
| | Numbering/labelling in accordance with relevant block or relevant wiring diagram | | |
| Inspection, Testing and Documentation | | | |
| Test Item | Rating | | Minimum Compliance |
| Cable Insulation Test (660V/1000V) | Max | 1KV | Original Test Certificate from cable manufacturer and testing as per relevant SANS1507 requirement |
| Cable Resistance Test (660V/1000V) | SANS | As applicable | Original Test Certificate from cable manufacturer and testing as per relevant SANS1507 requirement |
| Cable Conductor (Material and Capacity) | SANS | As applicable | Original Test Certificate from cable manufacturer and testing as per relevant SANS1507 requirement |
| Documentation | | Details and Requirements | |
| ISO 9001:2000 Certification: | Certified Copy of Valid Certificate | | |
| Cable Suppliers Original Test Reports: | SANS 1411 / ASTM D3222 Original Test Certificate from cable manufacturer. Certified Copy of Valid Certificate | | |
| | SANS 1507/SANS 1411 Manufacturing Accreditation Certificate. Certified Copy of Valid Certificate | | |
| | Material COC, Waybills, Delivery Notes, Delivery Documentation, etc., | | |



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

C3.5B EMPLOYER'S OCCUPATIONAL HEALTH AND SAFETY SPECIFICATION

**RLM/RWST/OMM/0102/2024/25 - RE-ADVERT:
APPOINTMENT OF A CONTRACTOR FOR THE
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Developed by Pieter Herbst

Tender
Part C3: Scope of Work

C3.5-1

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

Employer's Occupational Health and Safety Specification

INDEX

| Section | Description | Page No |
|---------|---|---------|
| 1. | DEFINITIONS | C3.5-25 |
| 2. | INTRODUCTION | C3.5-28 |
| 3. | SCOPE OF THESE SPECIFICATIONS | C3.5-28 |
| 4. | LEGAL REQUIREMENTS AND REFERENCE DOCUMENTS | C3.5-29 |
| 5. | LETTER OF GOOD STANDING | C3.5-29 |
| 6. | NOTIFICATION OF CONSTRUCTION | C3.5-29 |
| 7. | REVIEW OF SHE PERFORMANCE | C3.5-29 |
| 8. | STOP WORK NOTICE | C3.5-32 |
| 9. | SITE MANAGEMENT, SUPERVISION, APPOINTMENTS AND RESPONSIBILITIES | C3.5-33 |
| 10. | COMPETENCE AND TRAINING | C3.5-38 |
| 11. | COST OF HEALTH AND SAFETY | C3.5-39 |
| 12. | HEALTH AND SAFETY REPRESENTATIVES AND SAFETY COMMITTEES | C3.5-39 |
| 13. | SHE MANAGEMENT PLANS | C3.5-40 |
| 14. | EMERGENCY MANAGEMENT | C3.5-46 |
| 15. | MEDICAL EVALUATION OF WORKERS | C3.5-48 |
| 16. | TEMPORARY ELECTRICAL INSTALLATION | C3.5-48 |
| 17. | STACKING & STORAGE | C3.5-48 |
| 18. | PERSONAL PROTECTIVE CLOTHING AND EQUIPMENT | C3.5-48 |
| 19. | HEALTH AND SAFETY SIGNAGE | C3.5-49 |
| 20. | PLANT, MACHINERY AND EQUIPMENT | C3.5-49 |
| 21. | CONSTRUCTION EMPLOYEES' FACILITIES | C3.5-50 |
| 22. | SITE HOUSEKEEPING | C3.5-50 |
| 23. | HANDLING AND STORAGE OF HAZARDOUS AND FLAMMABLE CHEMICAL SUBSTANCES | C3.5-51 |
| 24. | INTOXICATION | C3.5-51 |
| 25. | MINIMUM ADMINISTRATIVE REQUIREMENTS | C3.5-52 |

Tender
Part C3: Scope of Work

C3.5-24

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

1. DEFINITIONS

- a) **“Construction Regulations”** means the Occupational Health and Safety Act's, No 85 of 1993, Construction Regulations 2014 that has come into effect on August 7, 2014;
- b) **“agent”** means a competent person who acts as a representative for a client;
- c) **“angle of repose”** means the steepest angle of a surface at which a mass of loose or fragmented material will remain stationary in a pile on the surface, rather than sliding or crumbling away;
- d) **“bulk mixing plant”** means machinery, appliances or other similar devices that are assembled in such a manner so as to be able to mix materials in bulk for the purposes of using the mixed product for construction work;
- e) **“client”** means any person for whom construction work is being performed;
- f) **“competent person”** means a person who -
- has in respect of the work or task to be performed the required knowledge, training and experience and, where applicable, qualifications, specific to that work or task: Provided that where appropriate qualifications and training are registered in terms of the provisions of the National Qualification Framework Act, 2000 (Act No.67 of 2000), those qualifications and that training must be regarded as the required qualifications and training; and
 - is familiar with the Act and with the applicable regulations made under the Act;
- g) **“construction manager”** means a competent person responsible for the management of the physical construction processes and the coordination, administration and management of resources on a construction site;
- h) **“construction site”** means a work place where construction work is being performed;
- i) **“construction supervisor”** means a competent person responsible for supervising construction activities on a construction site;
- j) **“construction vehicle”** means a vehicle used as a means of conveyance for transporting persons or material, or persons and material, on and off the construction site for the purposes of performing construction work;
- k) **“construction work”** means any work in connection with -
- the construction, erection, alteration, renovation, repair, demolition or dismantling of or addition to a building or any similar structure; or
 - the construction, erection, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runway, sewer or water reticulation system; or the moving of earth, clearing of land, the making of excavation, piling, or any similar civil engineering structure or type of work;
- l) **“construction work permit”** means a document issued in terms of regulation 3;
- m) **“contractor”** means an employer who performs construction work;

Tender
Part C3: Scope of Work

C3.5-25

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

- n) **“demolition work”** means a method to dismantle, wreck, break, pull down or knock down of a structure or part thereof by way of manual labour, machinery, or the use of explosives;
- o) **“design”** in relation to any structure, includes drawings, calculations, design details and specifications;
- p) **“designer”** means -
- a competent person who -
 - prepares a design;
 - checks and approves a design;
 - arranges for a person at work under his or her control to prepare a design, including an employee of that person where he or she is the employer; or
 - designs temporary work, including its components;
 - an architect or engineer contributing to, or having overall responsibility for a design;
 - a building services engineer designing details for fixed plant;
 - a surveyor specifying articles or drawing up specifications;
 - a contractor carrying out design work as part of a design and building project; or
 - an interior designer, shop-fitter or landscape architect;
- q) **“excavation work”** means the making of any man-made cavity, trench, pit or depression formed by cutting, digging or scooping;
- r) **“explosive actuated fastening device”** means a tool that is activated by an explosive charge and that is used for driving bolts, nails and similar objects for the purpose of providing fixing;
- s) **“fall arrest equipment”** means equipment used to arrest a person in a fall, including personal equipment, a body harness, lanyards, deceleration devices, lifelines or similar equipment;
- t) **“fall prevention equipment”** means equipment used to prevent persons from falling from a fall risk position, including personal equipment, a body harness, lanyards, lifelines or physical equipment such as guardrails, screens, barricades, anchorages or similar equipment;
- u) **“fall protection plan”** means a documented plan, which includes and provides for -
- all risks relating to working from a fall risk position, considering the nature of work undertaken;
 - the procedures and methods to be applied in order to eliminate the risk of falling; and
 - a rescue plan and procedures;
- v) **“fall risk”** means any potential exposure to falling either from, off or into;
- w) **“health and safety file”** means a file, or other record containing the information in writing required by these Regulations;
- x) **“health and safety plan”** means a site, activity or project specific documented plan in accordance with Rustenburg Water Services Trust health and safety specification;
- y) **“health and safety specification”** means a site, activity or project specific document prepared by Rustenburg Water Services Trust pertaining to all health and safety requirements related to construction work;

Tender
Part C3: Scope of Work

C3.5-26

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

- z) **“material hoist”** means a hoist used to lower or raise material and equipment, excluding passengers;
- aa) **“medical certificate of fitness”** means a certificate contemplated in regulation 7(8);
- bb) **“mobile plant”** means any machinery, appliance or other similar device that is able to move independently, and is used for the purpose of performing construction work on a construction site;
- cc) **“National Building Regulations”** means the National Building Regulations made under the National Building Regulations and Building Standards Act, 1977 (Act No. 103 of 1977), and promulgated by Government Notice No. R. 2378 of 30 July 1990, as amended by Government Notices No's R. 432 of 8 March 1991, R. 919 of 30 July 1999 and R. 547 of 30 May 2008;
- dd) **“person day”** means one normal working shift of carrying out construction work by a person on a construction site;
- ee) **“principal contractor”** means an employer appointed by the client to perform construction work;
- ff) **“Professional Engineer or Professional Certificated Engineer”** means a person holding registration as either a Professional Engineer or Professional Certificated Engineer in terms of the Engineering Profession Act, 2000 (Act No. 46 of 2000);
- gg) **“Professional Technologist”** means a person holding registration as a Professional Engineering Technologist in terms of the Engineering Profession Act, 2000;
- hh) **“provincial director”** means the provincial director as defined in regulation 1 of the General Administrative Regulations, 2003;
- ii) **“scaffold”** means a temporary elevated platform and supporting structure used for providing access to and supporting workmen or materials or both;
- jj) **“shoring”** means a system used to support the sides of an excavation and which is intended to prevent the cave-in or the collapse of the sides of an excavation;
- kk) **“structure”** means -
- any building, steel or reinforced concrete structure (not being a building), railway line or siding, bridge, waterworks, reservoir, pipe or pipeline, cable, sewer, sewage works, fixed vessels, road, drainage works, earthworks, dam, wall, mast, tower, tower crane, bulk mixing plant, pylon, surface and underground tanks, earth retaining structure or any structure designed to preserve or alter any natural feature, and any other similar structure;
 - any falsework, scaffold or other structure designed or used to provide support or means of access during construction work; or
 - any fixed plant in respect of construction work which includes installation, commissioning, decommissioning or dismantling and where any construction work involves a risk of a person falling;
- ll) **“suspended platform”** means a working platform suspended from supports by means of one or more separate ropes from each support;
- mm) **“temporary works”** means any falsework, formwork, support work, scaffold, shoring or other temporary structure designed to provide support or means of access during construction work;

Tender
Part C3: Scope of Work

C3.5-27

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- nn) **“the Act”** means the Occupational Health and Safety Act, 1993 (Act No. 85 of 1993);
oo) **“tunneling”** means the construction of any tunnel beneath the natural surface of the earth for a purpose other than the searching for or winning of a mineral.

2. INTRODUCTION

The objective of this specification is to ensure that Principal contractor and contractors achieve an acceptable level of safety performance.

This document forms an integral part of the contract and Principal contractor and contractor shall make it part of their contract with their sub-contractors and suppliers.

Compliance to this document does not absolve Principal contractor and contractors to comply with the minimum legal requirements and Principal contractor and contractors remains responsible for the Health and safety of their employees, in terms of the Occupational Health and Safety Act 85 of 1993 and the Construction Regulations 2014 and any other requirements.

3. SCOPE OF THESE SPECIFICATIONS

These specifications are applicable to the specific scope of work the BOSPOORT AT RUSTENBURG, NORTH – WEST construction project, including management, planning, engineering, design and construction of projects.

The content of this specification has the objective to assist principal contractor and contractors entering into contracts with Rustenburg Water Services Trust that they comply with the Occupational Health and Safety (OH&S) Act, No. 85 of 1993.

Compliance with this document does not absolve the Principal contractor and contractors from complying with minimum legal requirements and each employer remains responsible for the health and safety of his employees and those of his Mandataries.

Principal contractor and other Contractors should therefore insist that this specification form part of any contract that he may have with other Contractors and/or Suppliers.

**Tender
Part C3: Scope of Work**

C3.5-28

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

4. LEGAL REQUIREMENTS AND REFERENCE DOCUMENTS

All employers onsite have a moral and legal duty to ensure that their workplace is safe from hazards to the health and safety of their workers and shall as a minimum comply with the requirements of the Occupational Health and Safety Act 85 of 1993, its regulations and all associated standards as per section 44 of the Act and any other legislation and industry accepted standards pertaining to their scope of work.

An updated copy of the Act and Construction Regulations 2014 must be kept on site.

5. LETTER OF GOOD STANDING

Principal contractor and contractors shall be in good standing with the Compensation Commissioner or approved organisation as required by the Compensation of Occupational Injuries and Diseases Act 130 of 1993 and the Construction Regulation 4(g) prior to commencement of work.

6. NOTIFICATION OF CONSTRUCTION

The appointed principal contractor has the responsibility to notify the Department of labour of the intended construction before commencement of construction.

7. REVIEW OF SHE PERFORMANCE

7.1. Risk Assessment

Construction Regulation 2014 section 5.1.a. Rustenburg Water Services Trust shall prepare a baseline risk assessment for an intended construction work project;

Construction Regulation 2014 section 9.1 Principal contractor and contractors performing construction work shall before the commencement of any construction work and during construction work, cause a risk assessment to be performed by a competent person appointed in writing and the risk assessment shall form part of the health and safety plan to be applied on the site and shall include at least-

The identification of the risks and hazards to which persons may be exposed to, including ergonomic hazards;

The analysis and evaluation of the risks and hazards identified;

Tender
Part C3: Scope of Work

C3.5-29

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

A documented plan of safe work procedures to mitigate, reduce or control the risks and hazards that have been identified;

A monitoring plan; and

A review plan;

To ensure safety of employees and compliance to legislation, Principal contractor and contractors will be required to conduct three types of risk assessments and all employees must be trained in the risk assessments via an induction program and records of such must be kept for auditing purposes.

a) Baseline Risk Assessment

Before the commencement of construction work contractors must, taking into consideration the baseline risk assessment and these health and safety specification of develop a site specific Risk Assessment for all operations that have contracted for.

b) Issue Based Risk Assessment

An issue based risk assessment must be completed for any work that falls out of their original area of responsibility, or if changes in conditions arise or the need arises due to incidents that occurred during the construction phase.

c) Continuous Risk Assessment

In order to maintain a safe and incident free project, continuous risk assessments must be done and for example;

- Daily supervisors task specific risk assessment
- Arranged health and Safety audits that take place at least once a month
- Daily site/tool/equipment/plant/facilities inspection
- Toolbox talks/Safety talks on a weekly basis
- General awareness programs, and
- Planned job observations.

**Tender
Part C3: Scope of Work**

C3.5-30

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

d) Daily supervisors task specific risk assessment

It is required of Principal contractor and contractors supervisors to do a daily task specific risk assessment before any task commences in their area of responsibility during the daily task planning discussion. Participation and input of the team of workers is of critical importance.

This is to establish what activities are planned, what hazards and risks are attached to these activities and what pre-cautionary measures should be taken.

This risk assessment must be recorded and the responsible supervisor and his team must sign this document as proof that they are aware of the hazards and risks of the planned task and that appropriate precautionary action have been discussed and taken. Such proof must be kept in the safety file.

This risk assessment is compulsory before a task commences and work will be stopped if it has not been completed. Appropriate disciplinary action will be taken against the responsible Construction manager/supervisor of Principal contractor or contractor if this risk assessment has not been completed.

e) Inspections

Principal contractor and contractors must inspect site/tool/equipment/plant/facilities on a daily/weekly/monthly basis as established in their baseline and issue based risk assessment for their scope of work to ensure that it is safe for use, create no hazard and poses no risk to persons and property.

f) Audits

Monthly Audits

As per section 5 of the Construction Regulation 2014 Rustenburg Water Services Trust and/or its Agent will be conducting monthly audits at times agreed with the Principal contractor and the same will be done by Principal contractor on their appointed contractors.

The scope of the audits will focus on legal compliance and requirements of these specification and the Principal contractor and contractors' scope of work and area of responsibility and accountability on this specific contract to ensure their Health and safety plan and file has been implemented, adhered to and maintained.

Rustenburg Water Services Trust, its agent or the principal contractor reserves the right to conduct unannounced ad hoc audits and inspections as it deems necessary in the interest of health and safety onsite.

**Tender
Part C3: Scope of Work**

C3.5-31

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

A representative of Principal contractor and contractors and where applicable a relevant Health and Safety Representative must accompany the auditor on all Audits.

Contractors have to audit their sub-contractors as per above and keep records of these audits in their health & safety files, available on request.

g) Reports

Detailed reports of the findings of audits and inspections shall be reported in writing within 7 days to Principal contractor site management and contractors. Results must be discussed at project management and health and safety meetings. Copies of audit reports shall be kept by Principal contractor and contractors in their health and safety file.

Non-conformance close-out reports

Non-conformances reported via audit or inspection reports as above must be closed out and a report sent to the auditor and Principal contractor management within the time prescribed by the auditor, inspector or any authorised person.

8. STOP WORK NOTICE

Rustenburg Water Services Trust reserve the right through his agent, Principal contractor, safety officer or any person authorised thereto, to stop any operations onsite including that of contractors' teams and persons, if the supervisors daily task specific risk assessment has not been completed or should it be found that any operations are unsafe and in non-compliance with legislation, their health and safety plan and this specification.

The stop work order will only be lifted after the construction manager/construction supervisor of the offending contractor has rectified the unsafe condition and have discussed the non-conformance with its workers in the form of a toolbox talk/relevant training and after proof has been provided of compliance to the person who issued this notice. A copy of the stop work notice will sent to Rustenburg Water Services Trust CEO and its agent.

!!!!NOTE!!!!

Any expenses incurred by Rustenburg Water Services Trust due to any non-conformance by the Principal contractor and/or contractor will be for the account of the offending party.

**Tender
Part C3: Scope of Work**

C3.5-32

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Except for the work stoppage, in addition the Rustenburg Water Services Trust may impose a financial penalty, terminate their contract, withholding payment until compliant or any appropriate action decided upon by Rustenburg Water Services Trust CEO and its agent.

9. SITE MANAGEMENT, SUPERVISION, APPOINTMENTS AND RESPONSIBILITIES

a) Project participants and relationships

Rustenburg Water Services Trust is ultimately responsible for all aspects, i.e. (not limited to) finance, planning, health and safety, environmental protection, engineering construction and will appoint persons, companies who will carry out the work.

b) List of participants:

- i) Health and safety agent
- ii) Designers
- iii) Principal contractor
- iv) Contractors
- v) Sub-contractors

c) Appointments and responsibilities

Rustenburg Water Services Trust appointments

- i) Health and safety agent.
- ii) Designers and principal agent.
- iii) Principal contractor.

d) Rustenburg Water Services Trust responsibilities as client

Rustenburg Water Services Trust shall:-

- prepare a baseline risk assessment and a suitable site specific health and safety specification for the intended construction work based on the base line risk assessment;
- provide the designer with these health and safety specification and ensure that the prepared health and safety specification are taken into consideration during the design stage;
- ensure that the designer carries out all responsibilities required in Construction regulation 6;

**Tender
Part C3: Scope of Work**

C3.5-33

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- before appointing any principal contractor ensure that the principal contractor has the necessary competencies and resources to carry out the construction work safely;
- ensure that Principal contractor is registered and in good standing with the compensation fund or with a licensed compensation insurer;
- before any work commences on a site, have Principal contractor health and safety plan and file approved for implementation;
- take reasonable steps to ensure that Principal contractor health and safety plan are implemented and maintained through monthly health and safety audits and document verification;
- where changes are brought about to the design or construction work, make sufficient health and safety information and appropriate resources available to execute the work safely; and
- take reasonable steps to ensure co-operation between all contractors appointed to enable each of those contractors to comply with these Regulations;
- where Rustenburg Water Services Trust requires additional work to be performed because of a design change or an error in construction due to the actions of Rustenburg Water Services Trust ensure that sufficient safety information and appropriate additional resources are available Principal contractor to execute the required work safely.
- Where a fatality or permanent disabling injury occurs on a construction site, Rustenburg Water Services Trust must ensure that a report as contemplated in section 24 of the Act, in accordance with regulations 8 and 9 of the General Administrative Regulations, 2013 is forwarded to the provincial director. This report shall include the measures that the contractor intends to implement to prevent a re-occurrence of such incident and to provide a safe work environment.

e) Rustenburg Water Services Trust appointed agent

i) Agent's responsibilities

The agent shall:-

- act as Rustenburg Water Services Trust representative and the duties that are imposed by Construction regulation 2014 upon Rustenburg Water Services Trust apply as far as reasonably practicable to the agent.
- manage the health and safety on a construction project for Rustenburg Water Services Trust;

**Tender
Part C3: Scope of Work**

C3.5-34

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

f) Rustenburg Water Services Trust appointed Designer

i) Designer of a structure responsibilities

The designer shall

- ensure that the applicable safety standards incorporated into these Regulations under section 44 of the Act are complied with in the design and take into consideration the health and safety specification of Rustenburg Water Services Trust;
- before the contract is put out to tender, make available in a report to Rustenburg Water Services Trust:-
 - all relevant health and safety information about the design of the relevant structure that may affect the pricing of the construction work;
 - the geotechnical-science aspects, where appropriate; and
 - the loading that the structure is designed to withstand;
 - inform Rustenburg Water Services Trust in writing of any known or anticipated dangers or hazards relating to the construction work, and make available all relevant information required for the safe execution of the work upon being designed or when the design is subsequently altered;
 - refrain from including anything in the design of the work necessitating the use of dangerous procedures or materials hazardous to the health and safety of persons, which can be avoided by modifying the design or by substituting materials;
 - take into account the hazards relating to any subsequent maintenance of the relevant structure and must make provision in the design for that work to be performed to minimize the risk;
 - carry out the necessary inspections at appropriate stages to verify that the construction of the relevant work is carried out in accordance with his design;

g) Appointed Principal contractor

i) The appointed principal contractor shall make at least the following appoints

All appointments will be accompanied by proof of competence/CV

1) Contractor construction manager

A construction manager who is competent to identify the hazards and risks in the area of his responsibility and has the authority to take action to rectify any unsafe situation as required by section 8 of the OHSACT. The construction manager will be responsible to ensure that

**Tender
Part C3: Scope of Work**

C3.5-35

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

construction is done in a safe manner as per section 8.1 of the Construction regulation. A construction manager may only work on the site that he has been appointed for.

2) Assistant construction manager

Where applicable, an assistant to the construction manager who will assist the manager (CR 8.2) in the execution of his duties. An assistant construction manager may only work on the site that he has been appointed for.

3) Construction supervisor

A construction supervisor who is competent to identify the hazards and risks in the area of his responsibility and has the authority to take action to rectify any unsafe situation as required by section 8 of the OHSACT. The construction supervisor will be responsible to ensure that construction is done in a safe manner as per section 8.7 of the Construction regulation. A construction supervisor may only work on the site that he has been appointed for.

4) Assistant to construction supervisor

Where applicable, an assistant to the construction supervisor (CR 8.8) who will assist the manager in the execution of his duties. An assistant construction supervisor may only work on the site that he has been appointed for.

5) Health and safety officer

A safety officer (CR 8.5) with relevant competence (at least have confirmation of application from SACPCMP), to assist Principal contractor and contractors in the implementation and monitoring of the Health and Safety plan.

An organogram with the potential candidates to be appointed in these positions shall be made part of the Health and Safety Plan.

The person making the appointment is required to discuss the responsibilities and authorities with the appointee and it must be agreed upon with appointees and thereafter placed in the Health and safety file and kept on site for audit purposes.

**Tender
Part C3: Scope of Work**

C3.5-36

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

6) Responsibilities of Principal contractor

Principal contractor shall:-

- provide Rustenburg Water Services Trust a suitable, sufficiently documented site-specific health and safety plan, based on these specifications which must be approved by Rustenburg Water Services Trust agent before work commences and be reviewed and updated by Principal contractor as work progresses;
- develop and update a health and safety file which must include all documentation required in terms of the Act and its Regulations and these specifications; and
- on appointing any other contractor, in order to ensure compliance with the provisions of the Act-
 - provide contractors who are tendering to perform construction work for the, with the relevant sections of the health and safety specifications of Rustenburg Water Services Trust pertaining to the construction work which must be performed;
 - only appointed sub-contractors to perform construction work who has the necessary competencies, resources and have appointed a full-time competent construction supervisor (appointment must be in writing) to perform the construction work safely;
 - ensure prior to work commencing that every contractor is registered and in good standing with a registered compensation fund;
 - appoint each contractor in writing for the part of the project on the construction site;
 - approve each contractors health and safety plan and file before they are allowed to commence with work and approval must be done in writing by the Principal contractors health and safety agent/manage/advisor or officer and proof must be available in the principal contractors' health and safety file
 - take reasonable steps to ensure that each contractors health and safety plan is implemented and maintained through monthly health and safety audits and document verification and provide a copy of the health and safety audit to the within seven days after the audit;
 - where changes are brought about to the design or construction work, make sufficient health and safety information and appropriate resources available to execute the work safely; and
 - where Rustenburg Water Services Trust requires additional work to be performed because of a design change or an error in construction due its actions, Rustenburg Water Services Trust shall ensure that sufficient safety information

Tender
Part C3: Scope of Work

C3.5-37

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

and appropriate additional resources are available to execute the required work safely.

- take reasonable steps to ensure co-operation between all contractors to enable each of those contractors to comply with these Regulations.
- hand over a consolidated health and safety file to Rustenburg Water Services Trust upon completion of the construction work

Where a fatality or permanent disabling injury occurs on the construction site, Principal contractor must ensure that a report as contemplated in section 24 of the Act, in accordance with regulations 8 and 9 of the General Administrative Regulations, 2013 is forwarded to the provincial director. This report shall include the measures that the contractor intends to implement to prevent a re-occurrence of such incident and to provide a safe work environment. The incident must be reported to the client or his agent as soon as possible but within 24 hours.

10. COMPETENCE AND TRAINING

a) Induction

Principal contractor as Principal contractor shall ensure that all site personnel and visitors undergo project specific induction before starting work or entering the site. A record of attendance shall be kept in the health & safety file.

b) Awareness (Toolbox talks)

Principal contractor and contractors shall ensure that relevant toolbox talks which deals with the hazards, risks and safe work procedures specific to their activities take place at least once per week.

c) Competency

Definition

A competent person is a person who has in respect of the work or task to be performed the required knowledge, training and experience and, where applicable, qualifications, specific to that work or task: Provided that where appropriate qualifications and training are registered in terms of the provisions of the National Qualification

**Tender
Part C3: Scope of Work**

C3.5-38

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Framework Act, 2000 (Act No.67 of 2000), those qualifications and that training must be regarded as the required qualifications and training;

Principal contractor and contractors shall:-

- ensure that their employees appointed are competent and that all training required to do the work safely and without risk to health of their or other persons, has been successfully completed before work commences.
- ensure that all operators, drivers and users of construction vehicles, mobile plant and other equipment must be in possession of valid proof of training, valid licenses and/or certificates of the correct code where machinery, plant or equipment is utilised.
- proof of these licenses and/or certificates and/or proof of competence will be kept in the Contractors Health, Safety file.

11. COST OF HEALTH AND SAFETY

Rustenburg Water Services Trust shall ensure that potential principal contractors offering a tender for proposed work have made adequate provision for the cost of health and safety measures in terms of his/her documented Health and Safety Plan and measures based on these Health and Safety specifications during the period of the project.

The cost shall be duly quantified and clearly identified for such for example, medicals, PPE, training, special equipment etc.

The same rule on cost of health and safety applies to Principal contractor when contractors and its sub-contractors making a bid for work on this contract.

12. HEALTH AND SAFETY REPRESENTATIVES AND SAFETY COMMITTEES

If Principal contractor or contractors as employers has more than 20 employees on site, he/she shall ensure that Health and Safety Representative is appointed in writing and necessary training is provided. A proof of such training shall be kept on site.

Irrespective whether Principal contractor or contractors has more than 20 workers employed onsite, it is required that at least one Health and Safety Representative is appointed who shall form part and attend the Joint Health and Safety Committee meeting of the principal contractor, irrespective of the number of workers onsite.

**Tender
Part C3: Scope of Work**

C3.5-39

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

The joint Health and Safety Committee meeting may form part of the project progress meetings held by Principal contractor and contractors and minutes, agendas and attendance records of this meeting must be kept in Principal contractor and contractors' health and safety file.

13. SHE MANAGEMENT PLANS

a) Health and safety plan

Based on these specifications, a suitable documented health and safety plan will be submitted to Rustenburg Water Services Trust by Principal contractor. This plan will address the hazards identified and includes safe work procedures to mitigate, reduce or control those hazards identified.

The same requirement exists between the Principal contractor and contractors.

b) Public Safety, Edge protection and Barricading, Traffic accommodation and access control

Public safety

Principal contractor and contractors Health and Safety program must provide for public safety, safe traffic accommodation and safe work areas by pre-planning and setting out correct/appropriate hazard warning signs i.e. No Un-authorized Entry, Danger Construction Work in Progress, Excavation warnings, Hard Hat, Lifting Operations and Visitors to Report to Site Office, etc.; to ensure safety at all times and the responsible person is the Site supervisor (8.7).

Edge Protection and Barricading

The Principal Contractor must ensure that all exposed edges and openings are guarded and demarcated always until permanent protection has been erected.

The Principal Contractor has the following options when contemplating the protection of openings, slabs and edges:

A physical barrier at the edge of the opening/slab, which must be strong enough to carry the weight of a person in the process of falling (wire and barricade tape will not be deemed sufficient).

The Principal Contractor's fall protection plan must detail the following safety measures:

Tender
Part C3: Scope of Work

C3.5-40

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- finished floor slab edges;
- stairways;
- floor penetrations;
- lift shafts; and
- all other openings and areas from where a person may fall.

The Principal Contractors fall protection plans must include the strategies for management of edge protection and penetrations.

Barricading onsite must be of high quality to ensure that hazard and risk areas are safe to public, vehicles and workers.

!!!!!!Note: The use of barricade tape and wire is not allowed on this project!!!!!!

Traffic management

Traffic control must be dealt with through placement of correct traffic signs and delineators and having flagmen in the appropriate positions.

All roadwork must be planned to limit the interference with normal traffic and during peak traffic hours.

Access control

It is the responsibility of the Principal Contractor to ensure that the site is fenced and has an access gate that will prevent any unauthorised persons from entering the site.

Access to the site must also be refused to any persons who appear to be under the influence of alcohol, drugs or any other intoxicating substance.

Any person onsite who is found to be under the influence of alcohol, drugs or any other intoxicating substance will be removed from site.

c) Working at height

i. Fall protection plan

In accordance with the 2014 Construction regulations Principal contractor and contractors -

**Tender
Part C3: Scope of Work**

C3.5-41

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- designate a competent person to be responsible for the preparation of a fall protection plan;
- ensure that the fall protection plan is implemented, amended where and when necessary and maintained as required; and
- take steps to ensure continued adherence to the fall protection plan.
- A fall protection plan must include -
- a risk assessment of all work carried out from a fall risk position and the procedures and methods used to address all the risks identified per location;
- a processes for the evaluation of the employees' medical fitness necessary to work at a fall risk position and the records thereof;
- a programme for the training of employees working from a fall risk position and the records thereof;
- a procedure addressing the inspection, testing and maintenance of all fall protection equipment; and
- a rescue plan detailing the necessary procedure, personnel and suitable equipment required to affect a rescue of a person in the event of a fall incident to ensure that the rescue procedure is implemented immediately following the incident.

Principal contractor and contractors must ensure that -

- the appointed construction manager CR 8.1/construction supervisor Cr 8.7 is in possession of the most recently updated version of the fall protection plan.
- all unprotected openings in floors, edges, slabs, hatchways and stairways are adequately guarded, fenced or barricaded or that similar means are used to safeguard any person from falling through such openings;
- no person is required to work in a fall risk position, unless such work is performed safely;
- fall prevention and fall arrest equipment are -
- approved as suitable and of sufficient strength for the purpose for which they are being used, having regard to the work being carried out and the load, including any person, they are intended to bear; and
- securely attached to a structure or plant, and the structure or plant and the means of attachment thereto are suitable and of sufficient strength and stability for the purpose of safely supporting the equipment and any person who could fall; and
- fall arrest equipment is used only where it is not reasonably practicable to use fall prevention equipment.

**Tender
Part C3: Scope of Work**

C3.5-42

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

d) Temporary Works

Definition

“temporary works” means any falsework, formwork, support work, scaffold, shoring or other temporary structure designed to provide support or means of access during construction work;

Scaffolding, formwork and support work

It is the Principal contractor's responsibility to ensure that:

- scaffolding, form and support work is erected, used and maintained safely in accordance with Construction Regulation 12 and 16, SA National of Standards Code of Practice, SANS 10085 entitled, “The Design, Erection, Use and Inspection of Access Scaffolding.
- that erectors, inspectors and supervisors have received the relevant training required by the National Qualification Framework Act, 2000 (Act No.67 of 2000),
- persons erecting and inspecting scaffolding, form and support work should therefore be able to ensure that, at the time of handing over to the user, the scaffolding is adequate for its intended purpose.
- when using access scaffolding must ensure that such scaffolding, when in use, complies with the safety standards incorporated for this purpose into these Regulations under section 44 of the Act.
- training is provided to all persons who work on these platforms.
- appoint a designer in writing temporary works to design, inspect and approve the erected temporary works on site before use.
- all temporary works operations are carried out under the supervision of a competent person who has been appointed in writing for that purpose.
- all temporary works structures are adequately erected, supported, braced and maintained by a competent person so that they are capable of supporting all anticipated vertical and lateral loads that may be applied to them, and that no loads are imposed onto the structure that the structure is not designed to withstand;
- all temporary works structures are done with close reference to the structural design drawings, and where any uncertainty exists the structural designer should be consulted;
- detailed activity specific drawings pertaining to the design of temporary works structures are kept on the site and are available on request to an inspector, Rustenburg Water Services Trust, its agent and Principal contractor;
- all persons required to erect, move or dismantle temporary works structures are provided with adequate training and instruction to perform those operations safely;

Tender
Part C3: Scope of Work

C3.5-43

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- all equipment used in temporary works structure are carefully examined and checked for suitability by a competent person, before being used;
- all temporary works structures are inspected by a competent person immediately before, during and after the placement of concrete, after inclement weather or any other imposed load and at least on a daily basis until the temporary works structure has been removed and the results have been recorded in a register and made available on site;
- no person may cast concrete, until authorization in writing has been given by the competent appointed person;
- if, after erection, any temporary works structure is found to be damaged or weakened to such a degree that its integrity is affected, it is safely removed or reinforced immediately and adequate precautionary measures are taken in order to –
 - secure any deck panels against displacement; and
 - prevent any person from slipping on temporary works due to the application of release agents;
- as far as is reasonably practicable, the health of any person is not affected through the use of solvents or oils or any other similar substances;
- upon casting concrete, the temporary works structure is left in place until the concrete has acquired sufficient strength to safely support its own weight and any imposed load, and is not removed until authorization in writing has been given by the competent person contemplated in paragraph (a);
- the foundation conditions are suitable to withstand the loads caused by the temporary works structure and any imposed load in accordance with the temporary works design.
- provision is made for safe access by means of secured ladders or staircases for all work to be carried out above the foundation bearing level;
- a temporary works drawing or any other relevant document includes construction sequences and methods statements;
- the temporary works designer has been issued with the latest revision of any relevant structural design drawing;
- a temporary works design and drawing is used only for its intended purpose and for a specific portion of a construction site; and
- the temporary works drawings are approved by the temporary works designer before the erection of any temporary works.
- That no person use a temporary works design and drawing for any work other than the structure it was intended for.

**Tender
Part C3: Scope of Work**

C3.5-44

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

e) Environmental protection

Principal contractor and contractors has to perform their work in such a manner to prevent environmental pollution and damage of air, water, and land resources. It includes management of visual aesthetics, noise, solid waste, dust, radiant energy, and radioactive materials, as well as other pollutants and resources encountered or generated by Principal contractor and contractors.

f) Cranage and lifting operations

It is the Principal Contractor responsibility to ensure compliance with the section 22 of the 2014 construction regulation and section 18 of the 2015 Driven Machinery Regulations, which includes inspecting machinery regularly, appointing a competent person to inspect and ensure maintenance, issuing PPE and relevant clothing, and training those who use machinery.

The responsibility includes to ensure:

- The crane is designed and erected under the supervision of a competent person;
- Lifting equipment, i.e. slings, hooks, ropes and all other equipment is inspected and certified by a registered test facility;
- Tower cranes must be load tested on erection with a copy of the test certificate kept in the health & safety file;
- The tower crane, alterations and maintenance must be conducted by a competent person;
- That a relevant risk assessment and method statement are developed and applied;
- That the effects of wind forces on the crane are taken into consideration and that a wind speed device is fitted that provides the operator with an audible warning when the wind speed exceeds the design engineer's specification;
- That the bases for the tower cranes and tracks for rail-mounted tower cranes are firm, level and secured;
- That the tower crane operators are competent to carry out the work safely; and
- That the tower crane operators have a medical certificate of fitness to work in such an environment, issued by an occupational health practitioner in the form of Annexure 3.
- Intermediate safety inspections must be conducted at least every 6 months. Records of all maintenance and inspections must be kept in the health & safety file.
- Lifting plans must be developed by a competent person for lifting work and plans must be available onsite when lifting operations are in progress.

**Tender
Part C3: Scope of Work**

C3.5-45

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

g) Excavations CR 13

All requirements with regards to excavations are as set out in the Construction Regulations section 13 shall be complied with as a minimum and Principal contractor and contractors shall familiarise themselves with the content thereof and act accordingly.

Where excavations deeper than 1.5 meters are made, this will be preceded by an issue based risk assessment and method statement to be approved by the clients' agent, a competent person appointed by the principal contractors.

Principal contractor and contractors will appoint a competent person to supervise and inspect all excavation work. The findings and recommendations of such inspections will be documented daily and records thereof will be kept for auditing purposes.

Principal contractor and contractors shall ensure that provision is made for barricading, shoring, dewatering and inspection of excavations.

Inspections are to be done in the following instances:-

- Daily (prior to each shift);
- After unexpected fall of ground;
- After substantial damage to supports; and
- After rainfall.

Principal contractor and contractors shall erect warning signs next to an excavation within which persons are working or carrying out inspections or tests.

14. EMERGENCY MANAGEMENT

a) Fire precautions

It is essential for Principal contractor and contractors to properly investigate and plan its fire prevention and protection measures. Fire prevention and protection measures are intended respectively to prevent and restrict the devastating effects of fires, and are therefore critical components of Principal contractor and contractors health, safety and environmental (HSE) management efforts.

Principal contractor and contractors should focus on fire prevention and should ensure that the following measures are in place:

Tender
Part C3: Scope of Work

C3.5-46

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- a properly equipped and trained fire crew to assist in the suppression or containment of wildfires and to maintain fire mitigation measures.
- ensure that staffs are trained and capable of fighting fires.
- identify areas of high fire risk/hazards.
- identify activities in the project that could lead to the ignition of a fire and determine and then implement mitigatory measures.

b) First aid management

The following first aid arrangements must be put into place

Principal contractor and contractors shall have qualified first aiders (when more than 10 employees) and first aid equipment (if more than 5 employees) as required by the GENERAL SAFETY REGULATIONS 3 and ANNEXURE THERETO.

The first aid box shall be inspected by a competent appointed person on a monthly basis and records kept in their health and safety files.

c) Incident Management

i) Recording and investigation of Incidents

Principal contractor and contractors Health and Safety program must make provision for every incident to be investigated by a competent person who will be assisted by supervisors, workers, SHE representatives and other relevant persons.

Where an incident was caused by or occurred involving his staff or property, report all incidents where an employee is injured, has died or there has been damage to property to the client, principal contractor immediately, but at least within 24 hours after the incident and as per Section 24 of the Act & General Administrative Regulation 8 by means of "annexure A" to the inspectorate.

- forward a full investigation report within seven days of the incident to the inspectorate, Rustenburg Water Services Trust and Principal contractor.
- provide Rustenburg Water Services Trust and Principal contractor and with a monthly "incident/near-miss" statistics report

**Tender
Part C3: Scope of Work**

C3.5-47

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

15. MEDICAL EVALUATION OF WORKERS

Principal contractor and contractors must ensure that all his or her employees have a valid medical certificate of fitness specific to the construction work they are to perform issued by an occupational health practitioner in the form of Annexure 3.

16. TEMPORARY ELECTRICAL INSTALLATION

Principal contractor will ensure that the control of all temporary electrical installations at the site is designated to a competent registered person.

Records of the certificate of electrical compliance and weekly inspections of temporary installations must be available in the safety file.

17. STACKING & STORAGE

Principal contractor and contractors Health and Safety program shall make provision that:

- adequate storage areas are provided and is under the supervision of an appointed stacking and storage supervisor,
- storage areas must be kept neat and under control,
- good housekeeping principals are implemented and maintained in storage areas

18. PERSONAL PROTECTIVE CLOTHING AND EQUIPMENT

It is important to note that PPE is the least desirable option to prevent injuries or damage and therefore Principal contractor and contractors must take such steps as may be reasonably practicable to eliminate or mitigate any hazard or potential hazard to the safety or health of employees, before resorting to personal protective equipment;

You shall ensure that your employees are provided with adequate personal protective equipment (PPE) for the work they perform in accordance with the HIRA outcomes and in accordance with the requirements of General Safety Regulation 2(1) of the OHS Act.

It is also the responsibility of Principal contractor and contractors to:

Tender
Part C3: Scope of Work

C3.5-48

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- Inform workers of the potential risks involved in their work
- Provide them with PPE free of charge
- Provide continuous training, exercise control and enforce the wearing of PPE where necessary.
- Instruct employees in the proper use, maintenance and limitations of the safety equipment.
- Ensure that PPE is used as required

A document with all of the above information and the signature of the relevant workers will be kept in the site safety file.

19. HEALTH AND SAFETY SIGNAGE

Principal contractor and contractors Health and Safety program must provide for the relevant signs are placed correctly conspicuous areas in accordance with the risk assessment for example;

- No Unauthorized Entry
- Danger Workman Above
- Hard Hat Area
- First aid facilities
- No Smoking
- Scaffolding Safe for Use or Unsafe For Use

20. PLANT, MACHINERY AND EQUIPMENT

a) Principal Contractor And Contractors Equipment

Plant is operated, maintained and managed under the supervision of a competent appointed person.

Only appointed drivers/operators who have a valid operator's competence certificates, driver's licences and certificate of medical fitness are allowed to operate sites.


All plant and equipment are required to be in good, safe working condition, maintained and serviced in accordance with manufacturer's specifications before it will be allowed to work onsite.

Daily inspection plant, machinery, equipment are required before start of shift and records must be kept in health and safety file.


Tender
Part C3: Scope of Work

C3.5-49


C3.5
Employer's OHS Specification




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

b) Hired Plant and Machinery

Principal contractor and contractors shall:

- ensure that any hired plant and machinery used on site is safe for use. The necessary requirements as stipulated by the OHS Act 85/1993 and Construction Regulations 2014 shall apply.
- ensure that operators hired with machinery are competent and that certificates, proof of medicals, completed daily inspections and copies of ID documents are kept by the operator and in the site health & safety file.

All relevant Sub Contractors must ensure the same.

21. CONSTRUCTION EMPLOYEES' FACILITIES

Where applicable and reasonably practical Principal contractor and contractors shall:

- provide potable water is available onsite,
- shall ensure that at least one sanitary facility appropriately marked for each sex and for every 30 workers or part thereof,
- Covered eating areas

The above facilities must be kept in a clean, hygiene, safe condition and in a good state.

22. SITE HOUSEKEEPING

Principal contractor and contractors must ensure that:

- housekeeping is continuously implemented and maintained;
- materials and equipment is properly stored;
- scrap, waste and debris is removed regularly;
- materials placed for use are placed safely and not allowed to accumulate or cause obstruction to the free-flow of pedestrians and vehicular traffic;
- waste and debris not to be removed by throwing from heights but by chute or crane;
- where practicable, construction sites are fenced off to prevent entry of unauthorized persons;
- an unimpeded work space is maintained for every employee;
- every workplace is kept clean, orderly and free of tools and the likes that are not required for the work being done;

**Tender
Part C3: Scope of Work**

C3.5-50

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- as far as is practicable, every floor, walkway, stair, passage and gangway is kept in good state of repair, skid-free and free of obstruction, waste and materials;
- openings in floors, hatchways, stairways and open sides of floors or buildings are barricaded, fences, boarded over or provided with protection to prevent persons from falling.

23. HANDLING AND STORAGE OF HAZARDOUS AND FLAMMABLE CHEMICAL SUBSTANCES

Principal contractor and contractors shall:

- ensure that the use, transport, storage and disposal of HCS are carried out as prescribed in the HCS Regulations as well as applicable environmental legislation, SANS standards and recommendations in the Hazardous Materials Survey.
- ensure that all there is a register kept for all hazardous chemicals used in their operations on site and that they all have Material Safety Data Sheets (MSDS).
- provide suitable and adequate protective equipment when working in an area where hazardous chemicals and materials are being used;
- ensure that its employees have familiarised themselves with the hazardous material data sheets applicable
- ensure that users are aware of the hazards and precautions that need to be taken when using the chemicals and a competent Hazardous Chemical Substance coordinator must be appointed.
- that First Aiders are aware of the MSDS"s and how to treat HCS incidents appropriately. Copies of the MSDS"s must be kept in the first aid box and in the store.
- that containers are clearly labeled "flammable substances" must be stored separately, away from other materials, and in a well-ventilated area (appropriate cross ventilation).

Commented [WK1]: shouldn't this read "principal contractor and contractors shall ensure" and then remove it from the beginning of each bullet cause the last two bullets of the list don't read easily

24. INTOXICATION

No intoxicating substance of any form shall be allowed on site.

Any person who appears to be under the influence of drugs or any conditions which may render, or be likely to render him incapable of taking care of himself or the persons under his charge or suspected of being intoxicated shall not be allowed on the site.

Any person required to take medication shall notify the relevant responsible person thereof, as well as the potential side effects of the medication.

Tender
Part C3: Scope of Work

C3.5-51

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Any person suffering from any illness/condition that may have a negative effect on his/her/anyone other person's health or safety performance must report this to his/her superior.

Principal contractor and contractors shall ensure that no person under his control shall bring any intoxicating substance onto site.

Principal contractor and contractors is expected to subject any person suspected of being under the influence of intoxicating substance to testing for substance abuse and any such person refusing to undergo such a test will be removed from site or denied access to the site.

25. MINIMUM ADMINISTRATIVE REQUIREMENTS

Principal contractor and its contractors shall use the applicable health and safety information in this specification to develop and submit a suitable and sufficient health and safety plan and safety file for the scope of their work.

It is required that the document has a table of content and that each section is separated with dividers.

The work performed by Principal contractor and contractors is subject to South African legislation as well as these specifications as they relate to their scope of work on this project.

Rustenburg Water Services Trust will evaluate, discuss and negotiated the health and safety plan and file with the principal contractor and after final approval issue an acceptance letter to the principal contractor.

The above is applicable between Principal contractor as principal contractor and its contractors and between the contractor and its sub-contractors.

A copy of letter of approval must be presented to the construction manager/supervisor before commencement of work and kept in the health and safety file.

If Principal contractor as principal contractor or any contractor onsite is found in noncompliance with the above rule of approval, the Principal contractor or contractor will be issued with a work stoppage notice and not be allowed to work onsite until they are in full compliance

Disciplinary action will be taken against the relevant construction manager or construction supervisor who have allowed this noncompliance.

**Tender
Part C3: Scope of Work**

C3.5-52

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

!!!!!!Note!!!!!!

Example of content of a health and safety file (the following list serves as an example only and it is the principal contractor, contractors and sub-contractors responsibility to ensure that they have covered all aspects and requirements of legislation and governing bodies pertaining to their activities)

- 1) Scope of work
- 2) Company emergency numbers
- 3) Workers and contractors management
 - a) List of workers
 - b) Copies of workers medicals
 - c) Copies of ID documents
 - d) List of contractors
- 4) Daily/Weekly/Monthly inspections of all tools, equipment, and plant used onsite
- 5) Non-conformance management
 - a) Workers non-conformance reports
 - b) Client non-conformance reports
 - c) Non-conformance close-out report
- 6) Monthly safety statistics
- 7) PPE Management
 - a) PPE issuing form
 - b) PPE inspection
 - c) PPE Policy
- 8) Safety training records
 - a) Induction training material
 - b) Induction training
 - c) Toolbox talks
 - d) Emergency procedures
 - e) Small tool training
 - f) Risk training
 - g) Safe work procedures training
 - h) Working at height training
 - i) First aid training
 - j) Fire training
 - k) Plant operators training
 - l) Scaffold and formwork erector training
 - m) Legal liability training for supervisors

**Tender
Part C3: Scope of Work**

C3.5-53

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- n) SHE rep training
- o) Incident investigator training
- p) PPE training
- q) Policies training
- 9) Records of monthly safety meeting
 - a) Agendas
 - b) Minutes of meeting
 - c) Attendance registers
- 10) Monthly Safety management/safety file audit result
- 11) Site safety inspection reports
- 12) Health and safety policy
- 13) Company and SHE organogram
- 14) Proof of good standing with compensation commissioner
- 15) Site risk assessment
 - a) Baseline
 - b) Issue based
 - c) Daily site supervisors task specific risk assessment
 - d) Risk methodology
 - e) List of 4 highest risks
- 16) Site Safety specification
- 17) Safety management plans
 - a) Health and Safety plan
 - b) Fall protection plan
 - c) Environmental plan
- 18) Scaffold and formwork design drawings
- 19) Copy of Mandatory appointments
- 20) Copy of appointment by Client
- 21) Copy of contractors appointment by
- 22) All Health and Safety appointments as per your scope of work
- 23) Method statements of your activities
- 24) Incident management
 - a) Incident management procedures
 - b) Site incident report list
 - c) Annex A
 - d) WCL 2
 - e) Incident investigation report
- 25) Hasardous chemicals management

**Tender
Part C3: Scope of Work**

C3.5-54

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- a) List of Hazardous and flammable chemicals used onsite
- b) MSDS
- c) Hazardous chemicals handling procedures
- 26) Occupational health and safety act
- 27) Construction regulations 2014
- 28) SANS 10085

2) Covid 19 preparedness

ADDITIONS TO HEALTH AND SAFETY SPECIFICATIONS TO INCLUDE COVID 19

Table of content:

1. Introduction
2. References
3. Workers transport
4. Security/access control/control of visitors onsite
5. Pre-construction evaluation, screening and training
6. Facilities, resources and action required by principal contractor where applicable contractor onsite
7. Required documentation development and updates
8. Procedures at start at end of shift
9. Managing and controlling flammable hazardous chemicals
10. Contractor management
11. Compliance monitoring and discipline
12. Additional recourses and recourse management

Tender
Part C3: Scope of Work

C3.5-55

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

1. Introduction

COVID 19 Novel Corona virus has changed the world we live in and how we will live in it in future. Due to this it has become necessary to take special precautions to prevent further spread of this disease.

This document is an addendum to the original project health and safety specifications to assist the principal contractor and contractors to protect their workers

2. References

The Department of Employment and Labour has appealed to employers to use the prescriptions of the Occupational Health and Safety (OHS) Act of 1993 in governing workplaces in relation to Coronavirus Disease 2019 COVID19.

The OHS Act read with the Hazardous Biological Agents Regulations requires the employer to provide and maintain as far as is reasonably practicable a working environment that is safe and without risks to the health of employees.

Section 8(2)(b) requires steps such as may be reasonably practicable to eliminate or mitigate any hazard or potential hazard before resorting to personal protective equipment (PPE). However, in the case of COVID19, a combination of controls is required, although the main principle is to follow the hierarchy of controls.

However, before the implementation of control measures, current risk assessments need to be reviewed and updated, considering the new hazards posed by exposure to COVID-19 in the workplace. This is in accordance with Section 8 (2) (d) of the OHS Act".

3. Workers transport

- a. Where possible the contractors must arrange transport of their employees in line with the travel rules of not more than 70% occupancy and social distancing
- b. Where not possible to avoid the use of public transport provide employees with information on the virus and precautions to take during public transport travel:
 - i. Frequent sanitising
 - ii. Maintain social distancing (at least 2 m)
 - iii. Always wear a mask
 - iv. Cough and sneezing safe practice

**Tender
Part C3: Scope of Work**

C3.5-56

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- v. When being coughed or sneezed on, turn face away and do not touch face before hands have been sanitised
- vi. Do not travel if experiencing symptoms of infection

4. Security/access control/control of visitors onsite

- a. The principal contractor must enforce strict access control and no person may enter the site except those who have undergone induction training and who is listed on the employee list.
- b. The only exceptions are persons who have pre-arranged official appointment which has been approved by the project construction manager. This person may not enter the site before he is received and escorted by a person designated by the construction manager

5. Pre-construction evaluation, screening and training

Principal contractor and contractors pre-construction requirements:

It is critical that the principal contractor conduct the following preparatory actions before going to site. These actions must be documented and each employee must sign that he/she has undergone this screening and training and understands

a. Evaluation:

- i. Employees medical evaluation, ensuring annual medical is valid
- ii. Screening:
 - 1. Fever screening
 - 2. Health questionnaire (signs and symptoms)
 - 3. Questionnaire of travel during shut down and exposure
 - 4. Employee practical understanding of:
 - a. the risks of the virus
 - b. how do you get contaminated
 - c. how do you get infected
 - d. signs and symptoms
 - e. prevention

b. Training program

Develop risk-based training and awareness program, policies and procedure for COVID 19 and communicate it with management and employees which include the following:

**Tender
Part C3: Scope of Work**

C3.5-57

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- i. What is COVID 19
- ii. How are you infected
- iii. Explanation of symptoms and signs
- iv. Explain the risk of underlying conditions, i.e.:
 1. [People 65 years and older](#)
 2. People with chronic lung disease or moderate to severe asthma
 3. People who have serious heart conditions
 4. People who are immunocompromised
 5. People with diabetes
 6. People with chronic kidney disease undergoing dialysis
 7. People with liver disease
- v. Self-monitoring and reporting of symptoms, possible exposure or infection to company
- vi. How to self-isolate
- vii. How to prevent infection:
 1. Correct methods of washing and sanitising
 - a. Hands
 - b. Personal hygiene
 - c. Site facilities
 2. Social distancing
 3. Not touching face
 4. The correct way to cough or sneeze
 5. Correct use, limitations of and disposal of PPE
- viii. What to do if you are not feeling well and are presenting with the symptoms include:
 1. Employees
 - a. Who to contact at your company?
 - b. Relevant company contact numbers
 - c. Do not go to work
 2. Principal contractor and contractors

**Tender
Part C3: Scope of Work**

C3.5-58

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- a. Responsibilities and procedures followed by company management when employee presents with symptoms, or confirmed to be infected
- b. Procedures and care of persons who are in isolation or being treated at hospital or COVID 19 facility
- c. Company and employee return to work after recovery procedures

ix. Updated company COVID 19:

- 1. SHE plan,
- 2. policies,
- 3. PPE
- 4. Method statements
- 5. Stay at home policy and sick leave
- 6. Employee assistance/care program

x. Include COVID awareness in every day DSTI

6. Facilities, resources and action required by principal contractor where applicable contractor onsite

- a. Appointment and training of security personnel and adequate personnel to conduct procedures of screening, isolating, conducting questionnaire and further actions required if person presents positive COVID 19 symptoms
- b. Provide these employees with appropriate PPE for their tasks
- c. Procedure for sanitising, screening and recording results
- d. Prevention of employees having to come into close-proximity (Queuing or bundling together.)
- e. Evaluation of daily screening, reporting to management and if required update procedure and training
- f. Adequate and appropriate risk-based:
 - i. PPE
 - ii. Sanitising/hand washing facilities at entrance, eating areas, offices, kitchens, toilets
 - iii. Awareness signage and posters
- g. Procedures for sanitising site, offices, toilets, eating areas, meeting rooms
- h. Procedures and rules to minimise exposure:

Tender
Part C3: Scope of Work

C3.5-59

C3.5
Employer's OHS Specification

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- i. Meetings
 - ii. Induction, Toolbox talk, DSTI
 - iii. Duration and numbers of delegates allowed at meetings
 - iv. Sanitising of areas, offices, boardrooms and furniture
- i. Provide an isolation area/tent/room where person can be interviewed and remain until instructions have been received from the COVID 19 control centre on next step to be taken

CORONA 24 Hour HOTLINE 0800029999

7. Required documentation development and updates

The contractor must develop new and update existing plans, policies and procedures to include COVID 19

- a. The plan and policy
- b. Company COVID 19 plans, policies, procedures and programs to include:
 - i. Prevention, exposure, infection
 - ii. Social distancing during entering and exiting site, meetings, training
 - iii. Creating different areas for and staggering start of work and lunch-times, training sessions and effective planning of required staff compliments
 - iv. Cooperation with local police, clinic, emergency services and notifying them of the project and developing beneficial relationships
 - v. Engaging with CLO and communities and establish a trust relationship by providing relevant information and possible assistance where possible
 - vi. Emergencies (mass infections)
 - vii. Post-infection return to work guideline, which include:
minimum medical and practical criteria for return to work, medical evaluation by occupational health practitioner
 - viii. Employee emotional care and assistance during and post infection
 - ix. Management and disposal of contaminated PPE and equipment
 - x. Procedure and planning to maximise social distancing
 - xi. Managing PPE and other personal waste
- c. Updated risk assessment to include COVID 19 hazards and risks

**Tender
Part C3: Scope of Work**

C3.5-60

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

8. Procedures at start at end of shift

- a. Include conducting and recording information of:
 - i. Sanitisation
 - 1. At start of shift all persons must sanitise with soap and water or sanitiser that contains at least 60% alcohol
 - 2. Site facilities, offices, boardrooms, toilets, eating areas, surfaces
 - ii. Fever screening and procedure when person has fever
 - 1. Re-do fever screen and if high fever
 - a. Isolate and questionnaire
 - b. Procedure if evidence points at infection
 - c. Contact call centre and follow instructions
 - d. Also follow company procedure for reporting to management, client and authorities

9. Managing and controlling flammable hazardous chemicals

- a. The type of sanitiser used for CIVID 19 must have a minimum of 60% alcohol and it is important that adequate stock is held onsite
- b. Due to its high alcohol content it poses a fire risk as well as a possible risk of being used by workers for intoxicating purposes which can lead to poisoning
- c. It is therefore particularly important to include these risks into account when the risk assessments is updated
- d. The principal contractor and contractors must ensure that they provide a flammable liquid storage facility, considering the quantities they will be storing onsite which conforms with local government fire regulations and GSR 4
- e. The storage area must be lockable and issuing and stock levels must be controlled by an appointed competent hazardous chemical substance controller
- f. Records of stock levels, issuing and usage must be updated daily and any discrepancies must be reported to management and investigated
- g. Appropriate and adequate signage must be posted
- h. Adequate Alcohol resistant foam or Carbon dioxide (CO₂) must be appropriately positioned
- i. Inspections of the flammable hazardous chemicals store must be conducted at least monthly.

**Tender
Part C3: Scope of Work**

C3.5-61

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

10. Contractor management

It is the responsibility of the principal contractor's responsibility to ensure that all contractor comply with the requirements of the addition to the original project health and safety specifications

11. Compliance monitoring and discipline

- a. Monitoring of compliance is critical to the prevention program and there may be no tolerance of non-compliance
- b. Strict appropriate disciplinary action must be instituted against persons and or employers found in breach of the requirements
- c. The client will be responsible compliance through audits and inspections and evaluation of principal contractors reports
- d. The principal contractor must monitor compliance through inspections and COVID 19 specific audit of:
 - i. Available equipment
 - ii. Sanitiser/washing facilities
 - iii. Sanitising of site facilities
 - iv. Employee screening
 - v. Access control
 - vi. Availability of isolation facilities
 - vii. Separation and procedures followed when employees present with symptoms
 - viii. Continues awareness training
 - ix. Recordkeeping
- e. Any suspected or confirmed infection or noncompliance with the COVID 19 requirements must be reported to the client health and safety agent with immediate effect

12. Additional recourses and recourse management

- a. It is a fact that finance and budgets most projects that are currently running have already been allocated and approved and therefore funds should be available from the client to pay contractors
- b. It is therefore critical that principal contractor ensure that their payment certificates and related documents are correct and is submitted before deadline dates with their invoices. Many delays in payment from clients are due to incorrect or insufficient documentation that has been submitted late.

**Tender
Part C3: Scope of Work**

C3.5-62

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



**CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

- c. It is important to understand that the COVID 19 virus has affected all parties and cooperation will increase the probability of completing the project successful
- d. It is critical that the client and principal contractor re-negotiate and discuss the project deadlines and budget and agree on solutions to the benefit of all
- e. Clients must not delay payment to principal contractors and principal contractors must do the same with their contractors. Delaying payments will have a snowball effect all the way down to the workers who have in some case already not received salaries or has only received partial payment
- f. Businesses must do their utmost to protect the workers who are the most crucial asset of construction
- g. Although SMME are businesses in their own right, many of these companies were already struggling financially before lockdown started and the principal contractor could use the assistance of the project CLO to ensure that workers are being paid and if not report it to the principal contractor.
- h. All the above requirement and information must be filtered down to the contractors onsite

**Tender
Part C3: Scope of Work**

C3.5-63

**C3.5
Employer's OHS Specification**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Risk Hazard Matrix

Probability: 1) Unlikely - 5) Rare - 6) Possible - 8) Likely - 10) Almost certain Occurrence

Consequences: 1) minor or no injury/damage - 2) serious injury/damage - 3) Fatality, major injury/damage - 6) multiple fatalities, major injuries/damage

Rating: less than 7 - Low risk. >< 7 and 15 - Moderate risk. >< 16 and 29 - High risk. > than 29 - Extreme High risk


| Multiply the score of the consequence with the score of the probability to get the risk rating | | Probability | | | | |
|--|---|-------------|------|-----------------------------|--|--|
| | | Unlikely | Rare | Possible to occur over time | Likely to occur under routine conditions | Will almost certain occur under current conditions |
| Consequences | | 1 | 5 | 6 | 8 | 10 |
| Multiple fatalities, major injuries/damage | 6 | 6 | 30 | 36 | 48 | 60 |
| Fatality, major injury/damage | 3 | 3 | 15 | 18 | 24 | 30 |
| Serious injury/damage | 2 | 2 | 10 | 12 | 16 | 20 |
| Minor or no injury/damage | 1 | 1 | 5 | 6 | 8 | 10 |

Extreme High Risk

High Risk

Moderate Risk

Low Risk

| Baseline Risk assessment | | | | | | | |
|--|--|--|--|------------|----------|--------|--------------------|
| Site: BOSPOORT AT RUSTENBURG, NORTH – WEST | | 14/07/2020 | Assessor: P Herbst  | | | | |
| Description/Area/ Activities/Task | Hazards | Damage to property, injury to person | Recommendations to reduce or control | Likelihood | Severity | Rating | Rating, L, M, H |
| Stages 1 to 4 | | | | | | | |
| 1) Pre-construction | | | | | | | |
| Design | Designer not taking 2014 Construction regulation into account during stages 2,3 and 4 Designs does not include safety aspects for safety during constructability, operability and maintainability Designs does not conform to the Design Specification as per the Engineering Scope of Work, checked and signed of by all relevant designers and engineer. Designs does not make provision for anchor points for working at height hook-up Design has made inadequate provision for lightning protection | Serious injury/Multiple fatalities. Property damage Financial loss Environmental impact Prosecution Damage to companies image | Designers are legally required to conform with all legislation and specifically the requirements of section 6 of the 2014 construction regulations. | 6 | 6 | 36 | EH |
| Surveys | All relevant surveys not completed Recommendations of surveys not adhered to in planning and designs for example: Traffic congestion Exposure to harmful chemicals Contaminated land Etc; | Serious injury/Multiple fatalities. Property damage. Financial loss Environmental impact Prosecution Damage to companies image Harm to health of workers | Emalahleni local municipality must have relevant surveys done including, geotech, ground water, environmental impact, traffic, existing services. Information in the reports must be used by designers in their designs and information that could affect health and safety in constructability, maintainability and operability must be reported to the client | 6 | 6 | 36 | EH |

| | | | | | | | |
|---|--|---|--|---|---|----|---|
| Ground/soil conditions | Saturated soil Unstable soil Contaminated soil Low water table No Geotech survey completed | Serious injury/Fatalities. Property damage. Tank movement Financial loss Environmental impact Prosecution Damage to companies image | Survey to be done to determine soil conditions and location of underground services Where any uncertainty pertaining to the stability of the soil still exists, the decision from a professional engineer or a professional technologist competent in excavations shall be decisive and such a decision shall be noted in writing and signed by both the excavation supervisor and the professional engineer or technologist. | 6 | 3 | 18 | H |
| Work permits, licences, way-leaves and authorisations | Legal noncompliance Unknown services | Serious injury/Fatalities. Property damage Financial loss Environmental impact Prosecution Damage to companies image | Emalahleni local municipality and the principal contractor needs to ensure that all relevant work permits, licences, way-leaves and authorisations are in place before work commences | 6 | 3 | 18 | H |
| Procurement and cost management | Inadequate funds to complete project safe, expected quality and on time Delays in appointment of contractor, designers and specialists Insufficient technical and safety information in tender document Delay in start date will cause pressure on contractor to make deadline Appointment of contractor based on cost and not on competence and health and safety performance | Serious injury/Fatalities. Property damage Financial loss Environmental impact Prosecution Damage to companies image | Emalahleni local municipality project cost management must ensure that the project budget includes all costs including health and safety and procurement must ensure that the principal contractor has provided adequate funds to ensure that the project can completed safe, on time and to the quality expected by the client | 6 | 3 | 18 | H |
| Time constraints | Client has not allowed for adequate time to complete project to standard and on time | Serious injury/Fatalities. Property damage Financial loss Environmental impact Prosecution Damage to companies image | It is important to ensure that time for the construction is realistic and takes all possible aspects that can cause delays into account | 6 | 3 | 18 | H |

Stages 5 and 6

2) Site establishment, preparation of laydown area and construction site

| | | | | | | | |
|---|--|--|---|---|---|----|---|
| Fencing of laydown area | Access to laydown area accessible by unauthorised persons Laydown area too small for volume of construction material | Muscular skeletal injury. Back injuries Cuts, bruises and fractures Injury to employees Damage to property | Planning of material deliveries to prevent this situation Prior arrangement and planning with principal contractor construction manager | 6 | 2 | 12 | M |
| Preparing laydown area, office, stores and ablution | Levelling surface Lifting/sling of containers in position on bases with a crane | Cuts, bruises and fractures Injury to employees Damage to property | Pre-planning of site lay-out and activities Ensure that crane and lifting operations are planned equipment certified, operators competent, risk assessment completed and work permit is in place Certified electrician and plumber to connect services and COC issued | 6 | 1 | 6 | L |
| Employees facilities | No shaded eating area Inadequate toilet facilities for both sexes and inadequate signage posted. Toilets not serviced on regular basis. No or inadequate potable water | Contamination of food through exposure to site dust, rain and elements. In-hygienic condition which could also lead to disease. | Suitable shaded eating area which protects the employees from the elements must be provided. Principal contractor must ensure that there are adequate male and female toilets available onsite as per construction regulation 2014. Facilities for both sexes must have signs showing male and female. Facilities to be kept clean and hygienic and toilet paper provided. | 6 | 2 | 12 | M |

3)Material delivery, loading, offloading, manual and mechanical handling of materials, plant, equipment

| | | | | | | | |
|--|---|--|--|---|---|----|---|
| Delivery, loading and off-loading of construction material | <p>Vehicles entering / leaving site</p> <p>Small manoeuvre space</p> <p>Inadequate warning systems in place when reversing and offloading</p> <p>Collision with equipment</p> <p>Spillages from materials</p> <p>Workers/machine/plant in same working area</p> <p>Lifting & lowering operations</p> <p>Failure of lifting equipment</p> | <p>Traffic disruption, injuries to people, damage to vehicles & property</p> <p>Environmental damage, Waste generation</p> <p>Possible fatality</p> <p>Damage to material</p> <p>Crushing of persons and materials</p> <p>Damage to toppling crane</p> | <p>Deliveries to be co-ordinated with principal contractors site management</p> <p>Planning of storage areas</p> <p>Vehicles to have reverse hooters / spotter to control reversing</p> <p>Drivers inducted on entering, speed limits displayed</p> <p>Induction training and safety talks, warning lights and acoustic warnings fitted to plant</p> <p>Check test certificate and examination certificate</p> <p>Check certificates for lifting equipment (chains, slings, shackles, etc)</p> <p>Ensure lifting gear is rated to carry load (SWL)</p> <p>Ensure materials being lifted are properly packaged and slung</p> <p>Be aware that there should be a minimum clearance of 600mm between any slewing parts of a crane and any fixed installation to prevent being trapped</p> <p>Access to the work area during lifting operations is to be restricted to those involved with and competent in the work in hand.</p> <p>Only competent banksmen to be used</p> <p>The crane driver and the banksmen are to ensure that the signals given are clearly understood</p> <p>Supervisor to plan procedures</p> <p>Good housekeeping practices should be implemented</p> | 6 | 2 | 15 | M |
| Manual and mechanical handling | <p>Employees not instructed on lifting and manual handling SWP</p> <p>Employees not obeying safety rules</p> <p>Improper lifting techniques.</p> <p>worker falling/tripping.</p> <p>Fall of material being carried</p> <p>Incorrect equipment/plant used for lifting</p> <p>Struck by falling load</p> <p>No risk assessment and permit available</p> | <p>Cuts, bruises and fractures</p> <p>Injury to employees</p> <p>Damage to property</p> | <p>Personnel should be aware of safe manual handling techniques</p> <p>Personnel to wear Personal Protective Equipment when carrying items, e.g.: safety footwear and gloves</p> <p>Ensure good housekeeping against tripping/fall hazards</p> <p>Worker to get assistance if load too heavy-</p> <p>Team lift where necessary</p> <p>Utilise mechanical lifting and carrying aids where possible</p> <p>Personnel to ensure item being carried, moved is properly bonded or will not be liable to break apart whilst being manually handled</p> <p>assessment and work permit required</p> | 6 | 1 | 6 | L |

| | | | | | | | |
|----------------------|---|---|---|---|---|----|---|
| Stacking and storage | Materials and equipment being stacked incorrect No storage and stacking plan Collapses of stacked material Not adequate storage space in designated laydown area | Injury to people Damage to plant, vehicles and equipment Damage to property Obstruction of emergency escape routes | Supervisors and employees to adhere to the safe stacking principles. Inspection registers to be completed as required. Stacking only in the designated areas Stacking and storage plan required from principal contractor Planning of material deliveries to prevent this situation | 6 | 2 | 12 | M |
|----------------------|---|---|---|---|---|----|---|

| | | | | | | | |
|-------------------------------------|---|--|---|---|---|----|---|
| Delivery of building material | Small manoeuvre space | Damage to property | Planning of storage areas | 6 | 2 | 12 | M |
| | Workers/machine/plant in same working area | Possible Fatality, fractures, cuts & bruises | Induction training and safety talks, warning lights and acoustic warnings fitted to plant | 6 | 3 | 18 | H |
| Loading and off-loading of vehicles | Lifting & lowering Operations Failure of equipment Failure of lifting equipment Fall onto and from hazards | Falling material Crushing by materials Hand injuries to the slingers Toppling crane Fatality | Check test certificate and examination certificate Check inspection have been carried out Check certificates for lifting equipment (chains, slings, shackles, etc) Ensure lifting gear is rated to carry load (SWL) Ensure materials being lifted are properly packaged and slung Be aware that there should be a minimum clearance of 600mm between any slewing parts of a crane and any fixed installation to prevent being trapped Access to the work area during lifting operations is to be restricted to those involved with and trained in the work in hand. Do not allow members of the public to gain access to the area Only trained banksmen to be used The crane driver and the banksmen are to ensure that the signals given are clearly understood | 6 | 2 | 12 | M |
| Loading and offloading of vehicles | Loading and offloading of trucks & other materials Lifting & lowering Operations Failure of lifting equipment Untrained employees Dropping load onto fingers, legs or feet. | Injury too hands, legs and feet Possible fatal injury Damage to material falling off truck Damage to vehicle or third party vehicles Back injury | All employees to be inducted regarding the use of PPE and its maintenance Supervisor to plan procedures Good housekeeping practices should be implemented Truck driver to be responsible for his load | 6 | 3 | 18 | H |

| | | | | | | | |
|--|--|--|--|---|---|----|----|
| Manual Handling of materials | Employees not instructed on SWP Improper lifting techniques. Operative falling/ tripping. Contamination from the substance being carried Fall of material being carried | Muscular skeletal injuries. Damage to property. Back injuries | Personnel should be aware of safe manual handling techniques Personnel to wear Personal Protective Equipment when carrying items, e.g.: safety footwear and gloves Ensure good housekeeping against tripping/fall hazards Operative to get assistance if load too heavy- team lift if necessary Utilise mechanical lifting and carrying aids where possible Personnel to ensure access equipment, ladders will take weight of operative and load being carried Personnel to ensure item being carried is properly bonded or will not be liable to break apart whilst being manually handled | 6 | 2 | 12 | M |
| 3) Legal compliance | | | | | | | |
| Compliance with national, international, provincial, local legislation and laws, industry and Emalahleni local municipality and any other applicable standards, rules, regulations, licence and requirements | Emalahleni local municipality, appointed designers, consultants, specialists, principle agent, construction health and safety agent, safety manager and officers, principal contractor and employees in non-compliance with these requirements Non-compliance not reported and recorded No action taken to rectify non-compliance Non-compliance not closed out | Multiple injuries, fatalities, damage to property, environmental damage, catastrophic result Financial loss/claims Prosecution Damage to public image | All project participants must adhere to at least the following, but not limited to: •Applicable National Legislation, international, provincial, local legislation and laws Regulations (laws, decrees...) Ensure that the latest version of the requirements are used | 6 | 6 | 36 | EH |

3) Site establishment

| | | | | | | | |
|--|---|--|---|---|---|----|---|
| Working onsite without hoarding | Public exposure to construction activities, excavation, noise, dust | Vehicle collides with person resulting in fatality Injuries to persons Damage to property | Worksite emergency response plan Trained first aiders on site Proper hoarding of construction area Traffic control for vehicular movement Person controlling traffic wearing reflector jackets, use a flag and visible signage Use of experienced contractor with competent supervisor Signage to include "No unauthorized entry" and "Warning – Construction Site" | 6 | 3 | 18 | H |
| Installation of Hoarding. | Unsafe use of PPE. Obstacles on ground may cause tripping and falling Material may dislodge causing employee to fall Untrained employees working with portable electrical equipment Unsafe electrical tools Unsafe extension cords Incompetent workers Hoarding not stable and secure | Loss time injuries Severe injuries Property damage Loss in production Fatalities Electrocution | All employees to be trained on safe use of PPE. Good housekeeping All equipment and tools to be checked daily Provide safe access at all times Lift all cables off ground where possible All workers to be trained for the task at hand Only competent workers to use electrical tools Ensure that Hoarding posts are secure in the ground | 6 | 3 | 18 | H |
| | The erector not following the specific position as indicated by the Engineers Drawing. When digging for fence poles, services can be damaged. When fence Y-Standards get knocked it can damage services. | Loss time injuries Severe injuries Property damage Loss in production. | All employees to be trained on safe use of PPE. Good housekeeping All equipment and tools to be checked daily Provide safe access at all times All workers to be trained for the task at hand Only competent workers to use electrical tools | 6 | 2 | 12 | M |
| Uncontrolled access of job-seekers, criminal elements. | Rioting and violence. | Injury to employees, fatalities, damage to property and loss of production. | Develop site specific emergency contingency plan. Contact local police unit to ensure fast re-action. Place plan in conspicuous place. Ensure that supervisors and workers know the emergency drill. | 6 | 3 | 18 | H |
| Employees accommodation onsite | Accommodation not to standard, workers sleeping on ground, poor ventilation, or adequate for number of employees | Employees can get ill, personal belongings can be damaged. | Accommodation to be planned in advance by principal contractor and standard in line with legislation must be applied. Accommodation must have adequate ventilation, beds that is off the floor and no over-crowding. | 6 | 1 | 6 | L |

| | | | | | | | |
|--|---|--|---|---|---|----|---|
| Employees facilities | No shaded eating area | Contamination of food through exposure to site dust, rain and elements. | Suitable shaded eating area which protects the employees from the elements must be provided. | 6 | 2 | 12 | M |
| | Cooking facilities not to standard and no washing facility. | Living area contaminated by food scraps causing infestation of mice, rats and other insects which could lead to disease. | The cooking area must be protected from the elements, have adequate waste disposal bins, and not create a fire risk. | 6 | 2 | 12 | M |
| | Inadequate potable water. | Employees can suffer from dehydration or even stomach disease due to the use of unsafe water. | Adequate potable water must be provided onsite. | 1 | 2 | 2 | L |
| | No or inadequate showers available. | In-hygienic condition which could also lead to disease. | Showers should be adequately enclosed and have running water. | 6 | 1 | 6 | L |
| | Inadequate toilet facilities for both sexes and inadequate signage posted. Toilets not serviced on regular basis. | In-hygienic condition which could also lead to disease. | Adequate serviced toilets must be available onsite as per construction regulation 2014. | 1 | 1 | 1 | L |
| 4) Exposure to climate, weather and natural hazards | | | | | | | |
| Conducting construction activities in nature | Safety and Health Risk from the Environment | Snake bite Bee Stings Dog Bites | Qualified first aider required for site who can treat snakebite Snake bite kit to be on hand Check area before working Find out nearest hospital and get emergency telephone numbers | 5 | 2 | 10 | M |

| | | | | | | | |
|--|--|--|--|---|---|----|---|
| Conducting construction work in adverse weather conditions | Exposure to sun, extreme heat, cold, wind, rain, lightning | Dehydration Heat exhaustion Skin cancer Hypothermia, colds, flu Loss of productivity Fatality | Each employee performing manual labour in high temperatures exceeding 30 degrees must be declared medically fit for specific work before work conditions Have workers acclimatised before starting work Induct employees to take at least 600 millilitres of water every hour and on how to avoid heatstroke provide affected employees with prompt first-aid treatment in the event of heatstroke Provide sun protective clothing and cream Provide waterproof clothing of a type that will effectively protect the wearer against harm Schedule work in such a way that it would not warrant the use off PPE (Waterproof Clothing) | 6 | 3 | 18 | H |
| Exposure to dehydration / heat exhaustion | Employees being exposed to elements Unfavourable work conditions Excessive exposure to high temperatures | Danger to employees fainting at work, possibly while at height Heatstroke | Each employee performing manual labour in high temperatures exceeding 30 degrees must be declared medically fit before work commences and thereafter yearly by a registered medical practitioner or a registered nurse and be issued with a fitness certificate Have workers acclimatised before starting work Induct employees to take at least 600 millilitres of water every hour and on how to avoid heatstroke Provide affected employees with prompt first-aid treatment in the event of heatstroke | 5 | 2 | 10 | M |

5) Installation and fitment of electrical system, fittings and equipment

| | | | | | | | |
|--|--|--|---|---|---|----|---|
| Installation of and working with high and low tension cables and equipment | Exposure to electricity by persons with lack of knowledge on safe work procedure | Shock Burns Fire Death Damage to property | All electrical wires must be sealed All electrical connections must be correct and properly sealed Do not touch electrical wires Wear the correct personal protective equipment, even if switched off, when working with electricity Keep water away from electrical wires Switch off electricity when working with electricity or near electricity especially if water is used Prevent tools and other equipment from touching electrical wires Use insulated tools and equipment Electrician to certify that electricity is switched off Lock out/Tag out system to be used to prevent accidental activation of electricity All electricity must be switched off when working near electricity with water | 6 | 3 | 18 | H |
| | Working at height | Fatality, major fractures, cuts and bruises | Job specific training, Induction training and safety talks and planning and supervision | 6 | 3 | 18 | H |
| | Working with grinder, abrasives and cutting flame | Fire, inhalation of dust, eye injuries and burns | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 1 | 6 | L |
| | Lack of knowledge on safe work procedure | Shock Burns Fire Fatality Property damage | Only trained, competent workers may work on electrical system. Certified supervisor must be onsite at all times | 6 | 3 | 18 | H |
| Installation of systems, distribution boards and equipment | Exposed wires Unauthorized people gaining access to DB board Faulty switches Overloading of wiring Not following lock-out procedures Incompetent electrical installer | Electrocution Fire Property damage Serious injuries/fatality. | Distribution boards to be properly earthed Earth leakage relays should always be functional. All openings on DB box to be blocked to prevent rodents Lock out procedures to be in place. C.O.C must be available. | 6 | 3 | 18 | H |

| | | | | | | | |
|---|---|---|--|---|---|----|---|
| Chasing into concrete using a grinder. | Exposure to dust, noise, particles and vibration Contact with existing services. Fall from height. Use of incorrect blade. | Cuts Inhalation of dust. Hearing loss if prolonged exposure to noise. Eye injury. Fractures | Correct PPE use. Correct training received. Use eye protection. Checking plan and conducting services surveys | 6 | 2 | 12 | M |
| Install cable (surface) | Use of impact drill Noise. Striking or being struck by falling objects. Flying particles including dust. Use of hand/power tools. Contact with existing services. | Hearing loss if prolonged exposure to noise. . Cuts. Eye injuries Cuts abrasions. | Correct PPE. use. Correct training received. Checking plan and conducting services surveys Inspect equipment before shift Maintain equipment to manufacturers standard.. | 6 | 2 | 12 | M |
| 6) Cranes, lifting, slinging and lifting equipment | | | | | | | |
| Lifting and Rigging. | Lifting equipment not maintained & inspected frequently can cause injury or damage to property. Operator, rigger and banksman not competent or experienced. | Serious Injury/ fatal. Property damage. Loss of income. | Adhere to lifting and rigging procedures. Only competent employees to operate lifting equipment. Only certified lifting equipment to be used. All lifting equipment to be fitted with SWL identifying tags. | 6 | 3 | 18 | H |
| Crainage | Incompetent crane operator Defective crane Hitting person/property whilst maneuvering crane into position Outrigger hitting person/property during extension and lowering Improper hooking offload resulting in dropping part or entire load Use of damaged slings/chains Incorrect slings used for load Crane tipping over Load test not done. No lifting plan | Loss time injuries Serious injuries Fatalities Property damage | Operator certificate of competency to be kept on file Crane to comply with all requirements as per the construction regulation, driven machinery regulation Banks man to be appointed Only certified chains/slides to be used Correct PPE. to be used Operator to do pre use checklists daily Lifting plan must be developedfor each job | 6 | 3 | 18 | H |

7) Working with tools, electric tools, small plant and equipment

| | | | | | | | |
|-----------------------------|--|---|---|---|---|----|---|
| Working with electric tools | Tools not correct for job. Tools not serviced. Broken tools not removed from service. Workers not trained to use tools correctly. | Electric shock Burns. Damaged equipment. Cuts, bruises, fractures | Electric tools and installations to be in good condition Inspect electric tools before use Do not use electric tools in wet/damp conditions Use personal protective equipment such as insulated gloves Electrical installations register to be maintained, inspected by competent person Put on all necessary PPE No unauthorised work Get lock out permit Report to site office Switch off appropriate circuit breaker DB Use a lock out board - place key in pocket Ensure good housekeeping is maintained | 6 | 2 | 12 | M |
| Working with hand tools | Exposure to defective equipment Incorrect usage of equipment Untrained staff using hand tools | Serious injury. Lost time injury. Personnel injury. Property damage. | Ensure: Tool is correct for job Tool is in good order and suitably sharp Personnel must be competent/instructed in tool usage and tool safely Lighting is sufficient Access is safe, working platform is secure, leading edge is guarded Operative is wearing all necessary PPE | 6 | 2 | 12 | M |

8) Excavation, trenching, bulk earthworks, backfill, reinstatement and relevant equipment

| | | | | | | | |
|--|--|--|---|---|---|----|---|
| Excavation, trenching, bulk earthworks | Cave-in of trench/excavation | Damage to excavator and possible fatality, injury to persons | Plan and supervise excavations, use of excavation form, Shoring, benching or any other safety measures required by the when ground formation or depth requires, Removal of workers from trench/ excavation at risk is increased due to close working of compactors, change in ground conditions, rain or water seepage | 6 | 3 | 18 | H |
| | Persons/vehicles falling into trench/ excavation | Fractures, cuts, bruises and injury to persons | Protect vehicles from falling into excavations - provide barriers, signage, etc as necessary | 6 | 2 | 12 | M |
| | Possibility of hitting existing cables/pipes | Electric explosion, electrocution, fire, lost time through lack of water or electricity and replacement cost | Correct planning and use of excavation planning form, appointment of competent supervisor | 6 | 2 | 12 | M |
| | Toxic fumes Collapse of adjacent structures Dust Not conforming to the Construction regulations Uncontrolled access Hoarding not erected with sufficient height and safety distance | Suffocation Serious injury/Fatal. Lost time injury. Personnel injury. Property damage. | Survey to be done to determine soil conditions and location of underground services Excavations should be sloped to prevent collapse. If more than 2 meters deep, excavations must be shored, be provided with safe access in case of emergency Record the full details and results of inspections to be kept on site The competent person is to inspect the excavation on site: Daily, Prior to each shift and After rain , after an unexpected fall of ground and after any damage to supports, bracing or shoring Where any uncertainty pertaining to the stability of the soil still exists, the decision from a professional engineer or a professional technologist competent in excavations shall be decisive | 6 | 3 | 18 | H |

| | | | | | | | |
|------------------------|--|--|--|---|---|----|---|
| Compacting and Filling | Contact with tipping materials Contact with moving plant Vehicles/personnel falling into excavations Contact with underground services Hearing Loss Use untrained employees | Serious injury/Fatal. Lost time injury. Personnel injury. Property damage. | Flagmen to control vehicles movement Only trained personnel use plant Personal Protective Equipment to be worn Personnel to stand clear as materials are being tipped Use stop blocks and signs to warn vehicles of excavations, where applicable Stand clear of plant whilst materials are being compacted Establish position of underground services and protect services from damage | 6 | 3 | 18 | H |
| Ground/soil conditions | Saturated soil Unstable soil Contaminated soil Collapse of trench/ excavation walls/trapping Falling into excavation Collapse of adjacent structures | Serious injury/Fatal. Lost time injury. Personnel injury. Property damage. Suffocation Cuts Bruises Fractures | Survey to be done to determine soil conditions and location of underground services Beware of undermining of other structures (e.g.: buildings, scaffolds) Safety shoes, visible vests, dust masks, hard hats and gloves to be used Where any uncertainty pertaining to the stability of the soil still exists, the decision from a professional engineer or a professional technologist competent in excavations shall be decisive and such a decision shall be noted in writing and signed by both the excavation supervisor and the professional engineer or technologist, as the case may be. | 6 | 3 | 18 | H |
| Underground Services | No surveys done to establish existing services. No way-leaves available Striking of buried services | Injury to employees Disruption of services to community. Fines and claims for damage | Make all necessary enquiries to establish what services are in the area. Consult drawings and advice from service provider (e.g.: Municipality or ESKOM) when planning work. Assume all service to be live (Unless confirmation is received to confirm that services are isolated or otherwise made safe). Do not work near live services without authorisation from site management. Comply with the requirements of the safe system of work for underground services. Where available, locate services with a locator Hand dig around services | 6 | 2 | 12 | M |

| | | | | | | | |
|---------------------------------|--|--|---|---|---|----|---|
| Bulk earthworks | Large plant not able to stop in time. Operator not seeing other employees Unsafe act or condition not being rectified in time. Employees crossing the haulage roads. | Loss time injury Property damages Serious injury/fatalities. | Supervisor to make sure bulk earthworks area is out of bounds to unauthorized persons All employees to be inducted Correct PPE. to be used and all workers to be clearly visible Pre use inspections to be done daily Operator certificates must be on site | 6 | 3 | 18 | H |
| 9) Building of structure | | | | | | | |
| Bricklaying | Working with tools, bricks and mortar | Foot, hand and body injuries | Provision of proper PPE, Induction training and safety talks and planning | 6 | 1 | 6 | L |
| | Working at height on scaffold and trestles | fatality, major fractures, cuts and bruises | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 3 | 18 | H |
| | Working at unprotected edges | fatality, major fractures, cuts and bruises | Planning, barricade, training and toolbox talks | 6 | 3 | 18 | H |
| Plastering | Faulty hand tools Faulty spirit level Rubble and material. (tripping and falling) Working at heights (different level falls) | Poor quality work Lost time injury. Serious injury/fatal. | Good quality tools Tools in good condition Clean area Training on correct use of tools Fall protection plan to be in place | 6 | 3 | 18 | H |
| Finishing. | Hand tools used incorrectly Exposure to hazardous materials, Dust, paint and other materials. Poor Housekeeping Trip hazards hazards. Working in elevated position. | Loss time injuries Severe injuries Loss in production. | Correct PPE.use. Correct training received. Use eye protection. | 6 | 2 | 12 | M |
| Partition installation | Unsafe use of PPE. Obstacles on ground may cause tripping and falling Material may dislodge causing employee to fall down Untrained employees working with portable electrical equipment Unsafe electrical tools Unsafe extension cords (electrocution) Unsafe ladders Incompetent workers | Loss time injuries Severe injuries Property damage Loss in production Fatalities Electrocution | All employees to be trained on safe use of PPE. Good housekeeping All equipment and tools to be checked daily Provide safe access at all times Lift all cables off ground where possible All workers to be trained for the task at hand Only competent workers to use electrical tools Provide a valid fall protection plan | 6 | 3 | 18 | H |

| | | | | | | | |
|---|--|--|---|---|---|----|---|
| Paving | Truck colliding with workers/vehicles/plant while delivery of material Lack of supervision Unstable foundations or pallets can cause collapsing of brick stack Struck by falling loads Incorrect use of PPE. Scattered and protruding objects Exposure to noise and dust Loss time injuries Fatalities Hazardous chemicals (petrol) Faulty hand tools Incorrect level and positioning of paving | Severe injuries Property damage Loss in production | Truck driver to be trained and competent All workers to be trained and inducted Correct use of PPE. (dust masks) Level area and all load bearing equipment in satisfactory condition Supervisor to safely space workers from each other MSDS, use gloves when refueling Always use correct lifting techniques | 6 | 2 | 12 | M |
| | Repetitive bending. Exposure to noise and dust | Impact injuries Ergonomic injuries Cuts Injury to knees Hearing and eye damage | Impervious gloves to be worn/ barrier cream to be used Kneelers or similar to be available Personal protective equipment to be worn – for example if saw used to cut pavers | 6 | 2 | 12 | M |
| Glazing | Cutting and working with glass and aluminium | Major cuts and amputations | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 2 | 12 | M |
| Fitting and fixing door and window frames | Faulty equipment and tools Working with electric power tools Unprotected openings and doorways Loss time injury | Serious injuries Property damage | All tools and equipment to be according to SABS standards and weekly tools inspections to be done Only trained and competent employees to work with power | 6 | 2 | 12 | M |
| Plumbing | Working with open flame | Fire and burn wounds, property damage | Fire prevention training, safety talks, adequate fire equipment | 6 | 2 | 12 | M |
| | Working at height | Fatality, major fractures, cuts and bruises | Induction training and safety talks and planning and supervision, Provision of proper PPE | 6 | 3 | 18 | H |
| | Improper use of tools Use of untrained employees Use of open flames Struck by materials falling | Injury to person Fire Burns Exposure to lead fumes | Ensure standard safety procedures are followed at all times Only use trained and competent personnel Ensure there is a safe working area at all times Ensure materials are stored neatly Ensure there is safe access and egress at all times Ensure all personnel wear suitable and sufficient personal | 6 | 2 | 12 | M |

| | | | | | | | |
|-----------------------------|--|---|---|---|---|----|---|
| Tiling | Carrying tiles | Back injuries | Induction training and safety talks and planning | 6 | 2 | 12 | M |
| | Exposure to tile chippings, dust | Exposure to dust, eye injuries | Provision of proper PPE, Induction training and safety talks and planning | 6 | 1 | 6 | L |
| | Working with grinder | Fire, inhalation of dust, eye injuries | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 1 | 6 | L |
| Painting | Working at height and exposure to paint | Fatality, major fractures, cuts and bruises, allergy to | Induction training and safety talks and planning and supervision, Provision of proper PPE | 6 | 3 | 18 | H |
| Placing of pre-stress slabs | Placement of heavy concrete slabs | Fatality, major fractures, cuts and bruises | Planning, barricade, training and supervision | 6 | 3 | 18 | H |
| Installation of ceilings | Working on unsafe scaffolding and ladders Objects falling on workers below Incorrect use of PPE. Incorrect use of equipment and tools Unsafe use of tools and equipment. | Severe injuries to employees Loss time injuries Property damage | Supervisors to make sure ladders and scaffolding is up to standard at all times All workers to be trained in correct use of PPE. and safe use of hand tools Good housekeeping | 6 | 2 | 12 | M |

10) Steelwork

| | | | | | | | |
|------------------------------------|--|--|---|---|---|----|---|
| Steelwork | Carrying heavy material | Back, hand and foot | Induction training and safety talks and planning | 6 | 1 | 6 | L |
| | Working with grinder, abrasives and cutting flame | Fire, inhalation of dust, eye injuries and burns | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 2 | 12 | M |
| | Exposure to welding arch and fumes | Long term respiratory disease | Good ventilation and Provision of proper PPE, Induction training and safety talks and planning | 6 | 2 | 12 | M |
| Steel Erection | Lack of knowledge on safe work procedure Incompetent erectors, crane operators, rigger Workers harness not secured or no lifeline. Work area not barricaded Lifting equipment not in good working condition. | Cuts, bruises and fractures Possible fatalities Damage to property | Adhere to all general precautions for working at height Barrier off / exclude area below work All lifting appliances to be examined and inspected Inspection register in place and up to date All personnel to be trained and competent and wear clipped on safety harnessed when working at height Ensure that lifting equipment (slings, chains, shackles) test certificates are current and on site Competent persons only to connect loads and direct plant | 6 | 3 | 18 | H |
| Installation of balustrade fencing | Transfer of material to assembly area Use of portable electric tools Use of welding machines Working on ladders or unsafe working platforms Fire | Severe injuries Loss time injuries Property damage | Workers to be trained on safe use of hand tools and safe lifting methods All ladders to be according to standard Fire extinguishers available on site Only trained workers to use with portable electric equipment | 6 | 2 | 12 | M |

11) Temporary work

| | | | | | | | |
|----------------|--|---|---|---|---|----|---|
| Temporary work | Working with tools, bricks and mortar | Foot, hand and body injuries | Provision of proper PPE, Induction training and safety talks and planning | 6 | 1 | 6 | L |
| | Working at height on scaffold and trestles | fatality, major fractures, cuts and bruises | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 3 | 18 | H |
| | Working at unprotected edges | fatality, major fractures, cuts and bruises | Planning, barricade, training and toolbox talks | 6 | 3 | 18 | H |
| Form Work | Untrained erectors. No temporary work design. No competent supervision Poor quality or inadequate material | Serious injury/Fatal. Lost time injury. Personnel injury. Property damage. | Formwork must be assembled by competent workers under supervision of an experienced supervisor. Formwork must be assembled in accordance with the design that was developed by a competent person. The formwork must be signed off by the designer before concrete pour. | 6 | 3 | 18 | H |
| Tower Scaffold | Scaffold not built to standard Lifting of heavy unit into ceiling Un-authorized access Overloading of scaffold Weather conditions Medical condition of worker | Injury to employees, possible fatal and damage to property. | Tower to be on firm level ground with wheels or feet properly supported. Height not to exceed 3 times the base dimension. i.e. 2x3m Erection by competent person Inspection before first use Weekly record of inspection required Guard rails and Toe boards as per normal scaffolds Beware when moving of overhead obstructions, such as power lines Never move in strong winds | 6 | 3 | 18 | H |
| Shuttering | Lack of planning. Incorrect equipment No pre use inspection of equipment Incorrect PPE. Designated areas and structures not in clean and orderly fashion | Serious injury. Loss time injuries. Property damage. | Equipment to be checked, identified and entered in a prior to use All employees to be trained Good housekeeping at all times Ensure proper/safe off loading | 6 | 2 | 12 | M |

12) Plant and equipment

| | | | | | | | |
|--------------------------------------|--|---|---|---|---|----|---|
| Plant or Vehicles Operation | Equipment failing Workers injured by passing traffic Road users and pedestrians at risk from operation of moving plant Noise | Hearing Loss Injury to employees Damage to property | Implement traffic protection measures Trained and competent operators must be used Check plant and vehicles on daily basis before use and record inspections. Maintain vehicles in safe condition Medical certificates of fitness required for construction plant Crossing of road by construction vehicles or machines must be limited to the practical minimum Plant and vehicles must be fitted with amber rotating beacons and reverse alarms/hooters Wear appropriate protective clothing/equipment, e.g.: goggles, gloves, ear defenders, etc as appropriate | 6 | 2 | 12 | M |
| Compactors | High noise levels | Hearing loss | Provision of proper PPE, Induction training and safety talks | 6 | 2 | 12 | M |
| | Heavy moving machine | Foot injury | | 6 | 1 | 6 | L |
| Operation of machinery and vehicles. | Employees not trained or licensed can cause incorrect operation of equipment resulting in collision. Poor visibility can cause collision. ` Checklist not properly visually done. | Lost time injury. Serious/fatality. Damage to property. | Formal training on the use of equipment. Correct type of license used by the operators. Medical certificates available. Proper checklist system to be implemented. Defects logged and repair prior to use. | 6 | 3 | 18 | H |
| Parking of machinery and vehicles. | Uneven surfaces can cause machinery/vehicle to run away. If park brake is not applied, machinery/vehicle can run away. If stop block is not put behind wheels machinery/vehicle can move. If machinery/vehicle is not locked it can cause the use of unauthorised person. | Serious injury/ fatality. Lost time injury. Property damage. | Draft safe work procedures for parking of machinery/ vehicles. Train employees on the procedures. All machinery/vehicles to be equipped & Cd with stop blocks. Ensure park brake in working condition at all time. | 6 | 3 | 18 | H |
| Use of generators | Chemical vapors. Noise. Fire Back injuries when lifting Electric shock | Lost time injury. Personnel injuries Noise induced hearing loss | Correct PPE. to be used Prevent spillages and leaks Fire extinguisher available Generator to be properly earthed and in good condition. | 6 | 2 | 12 | M |

| | | | | | | | |
|---|--|--|---|---|---|----|---|
| Grader | Employee being injured by standing on, under or too close to engine or tamping drum Grader engine failure Grader colliding into other plant or LDV Employees being run over by grader. | Severe injuries Lost time injuries Fatalities Property damage Environmental damage | All protective guards must be in place before start of engine. Operator should be competent and trained with competency certificate in file Grader must be well maintained inspected. Correct PPE must be used | 6 | 3 | 18 | H |
| Transporting and tipping of soil by using tipper trucks | Tipper colliding into other LDV Tipper overturning Material tipped onto employees Tipper reversing over employees Employees exposed to noise and dust Tipper tipping in incorrect area | Severe injuries Loss time injuries Damage to property Fatalities Loss in production. | Operator must be trained and competent Tipper to be used at safe angle Employees to stay clear of tipper when dropping of soil Tipper truck must be well maintained with records on file | 6 | 3 | 18 | H |
| Use of Pneumatic drill/Jackhammers | Damaged machine could cause injury and or damage Not using PPE while working with machine Incompetent employees working with machine can cause injury Employees exposed to dust and noise Unsafe use of power tools | Loss time injuries. Severe injuries. Property damage. | Machines need to be serviced and well maintained Pre use checklist to be done Competent and trained employees to use machine only Always use the correct PPE. (respirators, eye protection) Only trained and competent people to work with power tools | 6 | 2 | 12 | M |
| Operating the whacker. | Incompetent operator Hazardous chemicals (petrol) Employees exposed to dust, noise and vibration | Loss time injury Property damage | Use correct PPE. Operator needs to be competent and trained MSDS, use hand gloves when refueling | 6 | 2 | 12 | M |

| | | | | | | | |
|-----------------|---|--|--|---|---|----|---|
| Excavator. | Machine overturning. Materials or equipment falling from Machine. Workers being endangered by machine operation. Machine arcing with or coming into contact with overhead cables or underground services. | Loss time injuries Severe injuries Property damage Loss in production Fatalities Damage to existing services could cause financial claims | Operator to be trained and competent. The operator will be responsible for ensuring machine is not misused and that it is maintained accordingly. Excavator must not be operated within 6m of overhead power cables when the boom is fully extended, unless suitable precautions are taken. Before excavation ground survey will be made to locate any underground services and prevent damage or injury. | 6 | 3 | 18 | H |
| Dumper. | Machine overturning. Falling of dumper. Collision with other plant or pedestrians. | Loss time injuries Severe injuries Property damage Loss in production | Driver to be trained, certified and have a valid driver's license. No unauthorised persons will be permitted to use the dumper. No overloading the dumper. Dumper not to be within 1.5m of any excavation. When tipping the dumper must be on level ground and suitable measures must be taken to prevent "overturning". | 6 | 2 | 12 | M |
| TLB | Workers can fall under wheels. Struck by boom or bucket. Falling material on workers or equipment. Collision with other plant or pedestrians. | Loss time injuries Severe injuries Property damage Loss in production Fatalities | Driver to be trained, certified and have a valid driver's license. No unauthorised persons will be permitted to use the TLB. No overloading the TLB. TLB not to be within 1.5m of any excavation. No extra worker or persons in cab except operator. | 6 | 3 | 18 | H |
| Water Tanker. | Fall under wheels. Collision with other plant or pedestrians. Water Tanker overturn. | Loss time injuries Severe injuries Property damage Loss in production Fatalities | Driver to be trained, certified and have a valid driver's license. No unauthorised persons will be permitted to use the Water Tanker. No worker allowed on the back of moving Water Tanker. | 6 | 3 | 18 | H |
| Concrete Mixer. | Loose clothing can get caught in machine. Limbs trapped or severed. Inhalation of cement dust. Eye injuries. | Loss time injuries Severe injuries Property damage Loss in production. | Operator to be trained and competent in using a concrete mixer. Proper PPE. to be worn. Correctly moving and handling the chutes. Stay always a clear distance from concrete mixer. | 6 | 2 | 12 | M |

| | | | | | | | |
|--------------------------|--|---|---|---|---|----|---|
| 12 Ton flat drum roller. | Fall under drum. Collision with other plant or pedestrians. Workers can fall under drum. | Loss time injuries Severe injuries Loss in production. Fatality | Operator to be trained and competent in using a flat drum roller. Proper PPE. to be worn. Always aware of workers around the roller. | 6 | 3 | 18 | H |
| Pad foot roller. | Fall under drum. Collision with other plant or pedestrians. Workers can fall under drum. Not wear always a kidney belt for vibration it can cause carpal tunnel syndrome and kidney problems. | Loss time injuries Severe injuries Loss in production. Damage to property. Fatality | Operator to be trained and competent in using a pad foot roller. Proper PPE. to be worn. Always aware of workers around the roller. | 6 | 3 | 18 | H |

13) Hotwork

| | | | | | | | |
|--|--|---|---|---|---|----|---|
| Welding & Flame Cutting Equipment Inspection & Use | Sparks being created in a vapour zone Possible explosion Injury to employees Fire hazard Untrained persons Unsafe equipment Incorrect connection to welding machine Poor welding operation Exposure of others in work area to sparks Exposure of poisonous gases | Damage to property Injury to employees Electrocution Fire Burns, injury to employees Electrical shock Arc' eyes injury | Only trained employees may operate the machine Train employees and keep copy of training certificate Keep a copy of certificate Keep machine in good condition Keep register up to date and inspect equipment monthly Operator must be in visual contact with the welding equipment at all times Ensure welding machine is positioned away from access route and is visible to the operator at all times. Only approved welding cables may be used. Operator and supervisor must ensure only approved connections are used. Clamp ground or earth cable into position Use correct clamps; Connect only by means of approved clamps Do not weld ground or earth cable into position Secure work area and good ventilation Always clamp the earth cable into position Use a screen, or work In an area away from other employees Work in an area with good ventilation | 6 | 2 | 12 | M |
| Flame cutting. | Unsafe flame cutting equipment used. Employees not competent to perform flame cutting. Flame cutting equipment not maintained and inspected. | Fatality. A lost time injury. Property damage. | Flame cutting equipment to be fitted with flashback arrestors. Flame cutting equipment to be inspected daily and deviations rectified. Safe storage or pressure equipment after use. Only competent employees to perform flame cutting. Ensure the correct PPE. | 6 | 3 | 18 | H |
| Arc welding. | Employees not competent to perform arc welding. Faulty equipment. Chemical/ flammable material next to welding activities. Inspections not frequently performed on equipment. | Serious injury/fatal. Lost time injury. Property damage. Environmental. | Only competent employees perform arc welding. Frequently inspections. No welding to be done near flammable liquids. Ensure the correct PPE. | 6 | 3 | 18 | H |

| | | | | | | | |
|---|--|---|---|---|---|----|---|
| Oxy acetylene equipment | Using unsafe and faulty equipment Fire and smoke inhalation from burning steel Incompetent workers The use of gas equipment has a high potential for fire and or explosions Flammable liquids close to working area Unauthorised persons in work area. | Loss time injuries Severe injuries Explosions Fatalities Property damage | NEVER use oil or grease on any gas fittings Correct use of PPE. Fire equipment to be in close proximity Only trained and competent workers to use equipment Store in a safe way No unauthorized persons in work area. Make sure area of work is clear of unauthorized persons. | 6 | 3 | 18 | H |
| 14) Stacking, storage and housekeeping | | | | | | | |
| Stacking and storage | Storage and work areas not kept clean and safe | Damage to property, injuries | Job specific training, Induction training and safety talks and planning and supervision | 6 | 1 | 6 | L |
| Stacking of material. | Employees not trained on safe work procedures. The crane operator incompetent. The slings are not tested as prescribed. Equipment not inspected and maintained frequently. Lifting equipment not maintained & inspected frequently can cause injury or damage to property. | Serious injury/fatal. Lost time injury. Personnel injury. Property damage. | Adhere to lifting and rigging procedures. Only competent employees to use lifting equipment. Only certified lifting equipment to be used. All lifting equipment to be fitted with SWL identifying tags. Area where to be stacked is level area. Barricading to be done around stacking material. | 6 | 3 | 18 | H |
| Stacking of Structural Steel | Employees not trained. Not wearing the correct PPE. Steel is not placed on wood poles not direct on ground to prevent rust. | Serious injuries Lost time injury. Personnel injury. | Train employees on the procedures. Use correct PPE. | 6 | 2 | 12 | M |
| Housekeeping | Poor housekeeping on construction sites. Trips and falls Creating dust Fire hazards | Serious injury. Lost time injury. Personnel injury. Property damage. | Ensure the area below where any elevated work is being performed is free of any rubble, spikes, tools or equipment Ensure that all areas have been checked by competent persons on a daily basis Ensure that all site agents have certified their work area as safe by the end of each shift Good housekeeping principles. | 6 | 2 | 12 | M |

15) Handling and storage of hsardous chemicals

| | | | | | | | |
|---------------------------------------|--|--|---|---|---|----|---|
| Hazardous Substances, Use and Storage | Exposure to vapours Direct contact with substances Use untrained employees | Injuries to workers through use of hazardous substances, e.g.: injuries to eyes, skin, inhalation, etc Damage to environment | Use substances in accordance with data sheet, particularly reference protective clothing required (example: gloves, goggles, etc) Know what First Aid measures are Have welfare facilities available for washing of hands, etc Train employees in usage of substances | 6 | 2 | 12 | M |
| Use and storage of flammable liquids | Improper storage of flammable substances Possible fire Unmarked containers Employees smoking in vapour zones Untrained employees | Serious injury to employees Burns Property damage Explosions Fire | Flammable substances to be stored in an appropriate flammable store which is well ventilated and a reasonably fire resistant container, cage or room and kept locked with proper access control measures in place Material Safety Data Sheets to be in safety file No smoking, and no heat/ignition close to or at sources Employees to be made aware of dangers Signage to be brought on to indicate dangers | 6 | 2 | 12 | M |
| Diesel Storage | Theft of fuel Fire at storage area Spillage due to leak in tank Inhalation of hazardous vapors. | Property damage Serious injuries/fatal Lost time injury | Ensure that security guards is on duty and that there are sufficient lighting during the night Employees should be trained in firefighting and fire extinguishers available in all areas on site Fuel tank to be properly secured and well ventilated. Bund wall to be in place to contain all spillage. Display no smoking and open flame signage. Provide adequate fire equipment with signage. | 6 | 3 | 18 | H |
| Hazardous chemicals and storage | Inhaling Handling Untrained employees Insufficient ventilation | Severe injuries Loss time injuries. Fatal. | Use the SABS 0228 code of practice Correct PPE. to be used by employees Sufficient ventilation in storage areas | 6 | 3 | 18 | H |

16) Confined space

| | | | | | | | |
|-----------------|---|---|--|---|---|----|---|
| Confined Spaces | <p>Lack of oxygen</p> <p>Explosive gasses</p> <p>Not being able to communicate with each other</p> <p>Restricted movement</p> <p>Not using correct PPE.</p> <p>Ensure all sources of energy (steam, electricity, water) to confined space is isolated and locked out.</p> <p>Unlit area</p> | <p>Suffocation</p> <p>Serious injuries</p> <p>Fatalities</p> <p>Property damage</p> | <p>Ensure that correct PPE. is issued</p> <p>Trained competent person to ensure that locking out of energy sources has been completed. (water, compressed air)</p> <p>All employees to have completed induction training.</p> <p>All employees must have valid medical certificate</p> <p>Ensuring that communication is maintained at all times with "hole watch" tested using a dosimeter to ensure atmosphere is safe to work in.</p> <p>Install sufficient lighting.</p> | 6 | 3 | 18 | H |
|-----------------|---|---|--|---|---|----|---|

17) Working at heights

| | | | | | | | |
|------------------------------------|---|--|---|---|---|----|---|
| Working at Height Elevated Work | <p>Unsafe access(Ladders, scaffold) to work area</p> <p>Objects falling from above.</p> <p>Falling debris, tools and equipment.</p> <p>Incliment weather.</p> | <p>Serious injury/Fatal.</p> <p>Lost time injury.</p> <p>Personnel injury.</p> <p>Property damage.</p> | <p>All access equipment is properly constructed (inspections record must be maintained)</p> <p>Only trained personnel construct, dismantle or control the access equipment</p> <p>All access equipment must have full toe boards and guardrails - comply with SANS 10085 on erection/use and dismantling of scaffolding</p> <p>No access equipment may be loaded above the level of the guardrail</p> <p>No access equipment to be loaded above its safe working load Where work involves leaning out on an open leading edge, then all personnel are to be fitted with full body harness. The harness must be connected at all times</p> <p>All fall arrest equipment to be correctly maintained</p> <p>Ensure if ladders are being used for access, they are either footed or tied. Also the ladder must be set at the correct level of 1 in 4 or approximately 75</p> <p>PPE to be used: harnesses, hardhats, safety shoes, overalls.</p> <p>Ensure staff at height all has medical and psychological certificates. Harnesses to be inspected daily.</p> | 6 | 3 | 18 | H |
|------------------------------------|---|--|---|---|---|----|---|

| | | | | | | | |
|-------------------------------|---|---|--|---|---|----|---|
| Open edges | Un-authorised removal of edge protection and signage No edge barricading done. | Fatalities. Serious injury. Loss time injuries. Property damage. | Use barricades in such a manner to prevent any person from falling. Always ensure that barricading is done in a manner that is safe Barricading must be of high standard. Barricading must be able to prevent a person from falling from open edges. | 6 | 3 | 18 | H |
| Working at elevated positions | Slipping and falling, persons not fit to work at heights i.e. vertigo, epilepsy. Objects falling down from above. Working unsecured and falling down. Trying to carry material or tools up a ladder/ scaffolding while climbing up. Areas not barricaded. | Loss time injuries. Fatalities. Property damage. | Adequate secure ladders/platforms and scaffolding to be used All employees working at heights to have valid medical certificate Fall prevention systems to be | 6 | 3 | 18 | H |
| Edge Protection. | Solid Edge Protection not installed on all open edges of Buildings including Excavations 1.5 meters or deeper. No warning signs posted. | Fatalities Loss time injuries Severe injuries Property damage Loss in production. | Barricading must be strong enough to prevent a person from falling from height. Fall risk signs can be posted. Induction training must cover working in close proximity to open edges. Regular toolbox talks on the topic must be conducted. Daily task risk assessments must be conducted and recorded. | 6 | 3 | 18 | H |

18) Roofwork

| | | | | | | | |
|---------------------|--|--|---|---|---|----|---|
| Roof work | Working at height | fatality, major fractures, cuts and bruises | Provision of proper PPE, Induction training and safety talks and planning and supervision | 6 | 3 | 18 | H |
| | Carrying heavy material on roof | fatality, major fractures, cuts and bruises of worker and others | Induction training and safety talks and planning | 6 | 3 | 18 | H |
| Roof truss erection | Unsafe access to work area Incorrect PPE used Objects falling from heights and injuring workers below Workers falling down due to non-use of fall restraint systems Rainy or wet conditions Lifting and transporting roof trusses to assembly area Trusses not properly secured. Workers not medical fit. | Loss time injuries Serious injury/fatalities Property damage | Only trained workers to work on heights Ladders to be fastened at all times Safety harnesses must be used at all time while working on heights Correct PPE. to be used No work to commence in wet conditions Properly secure and brace trusses to prevent falling down. Erect 1 truss at a time | 6 | 3 | 18 | H |

| | | | | | | | |
|--------------------------------------|--|---|---|---|---|----|---|
| Roof sheeting and cladding | Un-authorized access to roof Working on sloped angle with roof sheeting. Bad weather conditions Dropping of roof sheeting Tools and equipment dropping down Unsafe use of portable electric tools Workers not tied to anchor point or lifeline Workers not wearing fall protection harnesses No fall protection plan | Loss time injuries Severe injuries Property damage Loss in production Fatalities | Supervisors to ensure that there is safe access to roof area, by providing safe access ladders or scaffolding All employees to use safety harnesses while working on roof with life lines running parallel with roof No work to be done in bad or wet weather conditions Sheeting to be placed from one side to the other to prevent open spaces All employees to be trained in working at height and inducted Correct use of PPE. | 6 | 3 | 18 | H |
| 19) Concrete work | | | | | | | |
| Foundations (excavating and pouring) | Inclement weather, rain can cause collapsing of excavation. Open excavations Underground services The truck is not road worthy. | Loss time injuries Severe injuries Property damage Loss in production Fatalities | Make sure ground is from a stable formation before workers get into excavation. Always barricade off the open excavations Approved engineer's drawings to identify all underground services Stockpiling of soil to be a safe distance away from excavation edge Formal training on the use of equipment. Licensing of operators. Medical certificates available. Checklist system to be completed before work commences. | 6 | 3 | 18 | H |
| Steel Fixing | Injuries to hands, fingers, limbs, feet due to handling of steel Tripping , falling ,slipping on steel Steel falling from above can injure workers. Eye injuries due to flying fragments of wires. Workers falling from elevated heights | Back injuries caused by manual handling Eye injuries from tie wire Trips / falls Falling from height | PPE must include safety boots and goggles Manual handling training may be required Use only trained personnel Cap starter bars to prevent injuries where feasible Use of safety equipment e.g. safety gloves safety shoes hard hats and eye protection No unauthorised persons allowed in area Steel area to be barricaded off. Ensure that workers have proper safety | 6 | 2 | 12 | M |

| | | | | | | | |
|---|--|--|--|---|---|----|---|
| Use of explosive actuated fastening devices | Pointing tools carelessly in any direction Employees not trained in the use of explosive powered tools Machines not cleaned or oiled Miss fires Unsafe disposal of empty cartridges | Serious injury. Lost time injuries Property damage | Competent workers to be trained Daily checklists to be done Correct PPE. must be used at all times | 6 | 2 | 12 | M |
| 22) Fire protection | | | | | | | |
| Fire fighting and prevention | Fire can occur Fire alarm not functional, therefore people not hearing the sound of alarm Non availability of fire equipment Untrained personnel using wrong type of equipment or extinguishers to distinguish fire | Property damage Serious injuries Fatality | Fire escape routes to be determined and clearly marked Formal training on the emergency evacuation plan and to be reviewed. Monthly checklist of all fire equipment Formal training on basic firefighting | 6 | 3 | 18 | H |

23) Demolition

| | | | | | | | |
|------------------------|---|---|---|---|---|----|---|
| Demolition work | Demolishing the wrong structure Substandard/dangerous equipment Exposure to dust, noise & vibration Not wearing correct PPE. Rubble overloading floors Hidden services (electrical, water) Possible collapsing of structures | Damage to equipment plant Serious injuries/fatality. Property damage Lost time injuries. | Correct drawings and permits need to be obtained Adjacent property, building or part of building to be demolished will be surveyed and a report, in writing, prepared as to the findings. All equipment and tools in good working order Only trained workers to perform work of this nature Rubble to be removed on a regular basis All services to be disconnected. Demarcate demolition area and display warning signage. Temporary supports to be installed according to engineer's drawings. | 6 | 3 | 18 | H |
| Breaking concrete slab | Employees exposed to dust and noise Unsafe use of power tools (jack hammer). Workers not using the applicable PPE. | Loss time injuries Serious injuries Property damage | Always use the correct PPE. (respirators, eye protection) Only trained and competent people to work with power tools | 6 | 2 | 12 | M |

24) Transport and traffic management


| | | | | | | | |
|-----------------------------------|--|---|--|---|---|----|---|
| Transporting people. | Road worthy vehicle to be used. Vehicle used for transporting people not properly equipped with necessary safety requirements. Workers not seated. | Injuries to workers Lost time due to injury. Property damage. | Ensure that where people are transported together with material and tools that vehicle is equipped as per road safety act requirements. Ensure employees are properly seated. LDV's used for transporting people must comply with standard regulations. No standing is allowed. | 6 | 2 | 12 | M |
| Exit/Entry into the Public Roads. | Heavy vehicles entering high traffic areas No construction traffic signs posted No flagman | Motor vehicle collusion. Fatalities Loss time injuries Severe injuries Property damage Loss in production. | Driver to be trained, certified and have a valid driver's license permitted to use a vehicle. Traffic management plan must be developed. Flagman must be posted and correct signs posted. | 6 | 3 | 18 | H |


25) Health and Ergonomics


| | | | | | | | |
|---|-----------------------|---|--|---|---|----|---|
| Construction work creating Dust | Exposure to dust | Breathing in dust can cause long term health problems. Eye damage. Property damage. | Wear respiratory protection Dampen down and minimise dust where possible Make use of environmentally friendly methods to minimize dust kick-up, use bale straw and spread over area to prevent wind kick-up | 6 | 2 | 12 | M |
| Construction equipment creating excessive noise | Exposure to Noise | Noise can damage hearing permanently | Wear hearing protection Have machinery tested to establish the exposure to noise levels so that proper protection can be issued Induct employees on hearing loss before they are exposed to high levels of noise | 6 | 2 | 12 | M |
| Construction equipment creating vibration | Exposure to Vibration | Ergonomic injury to employees | Medical surveillance. Restricting exposure times Employees exposed to vibration must receive induction on using their PPE | 6 | 2 | 12 | M |

26) Effect on public

| | | | | | | | |
|--|---|---|---|---|---|----|---|
| Working in built up or residential areas | Adjacent Land Use Boundary and access control/public liability exposure. Increased foot traffic across or next to site Children playing on site Members of public entering site | Members of public getting injured. Loss of property Civil claims against contractor | Proper segregation of construction works from other land users Signage indicating dangers of entering site The construction site must be suitably and sufficiently fenced off Provide a controlled access point to prevent the unauthorised entry of persons | 6 | 2 | 12 | M |
|--|---|---|---|---|---|----|---|

| | A | B | C | D | E | F | G | H | I |
|----|---|--|--|--|--|--|---|-----------------------|---|
| 1 | BASELINE RISK ASSESSMENT | | | | | | | | |
| 2 | Site: BOSPOORT AT RUSTENBURG, NORTH – WEST | | | Risk Assessment Team: Pieter Herbst (Pr. CHSA/057/2017) | | | | | |
| 3 | Date: 13 July 2020 | | | | | | | | |
| 4 | EXPOSURE AND INFECTION WITH CORONA VIRUS | | | | | | | | |
| 5 | Frequency 2 < 15% chance of exposure - 3 ><15 and 50% chance of exposure 4 ><50 and 75% chance of exposure 5 >75% chance of exposure | Probability of injury /loss /damage Unlikely = 1 Possible = 2 Almost certain = 3 Certain to happen = 4 Has happened before = 5 | Severity of inj/damage Minor/no inj/damage = 2 Serious inj/damage = 3 fatality/major damage = 4 multiple fatalities/damage = 5 catastrophic = 6 | Rating Up to 13 = Low risk. ><14 and 36 = Moderate risk. 36> = High risk | | |  | | |
| 6 | Description of Area/Activities/Task | Hazards | Risk , Unwanted Event & Consequences | Frequency of exposure to hazard | Probability of injury loss / damage | Severity of injury/ loss/damage | Score | Rating L, M, H | Recommended controls |
| 7 | Infection with Corona virus | Exposure to Corona virus through: | Infected employees could die, become very ill, infect many other persons including public. Loss of production. Delay in project. Financial loss. Total disaster. | 4 | 3 | 6 | 72 | H | Company must develop an infection prevention, infection management and after care contingency plan which must include; a. Training of staff b. Precautionary measures c. Workers reporting system d. What procedures will be followed by company when a person reports possible infection e. Procedures when person has been confirmed as infected(support) Re-entry of persons who have recovered f. training of site management and workers in these procedures g. Provision of appropriate PPE Provision of washing facilities and sanitiser. |
| 8 | | Working in close proximity to other workers | | | | | | | |
| 9 | | Travel to work in taxi, bus and train | | | | | | | |
| 10 | | Physical contact with infected person | | | | | | | |
| 11 | | Contact with contaminated tools, equipment, surfaces | | | | | | | |
| 12 | | Infected person coughing or sneezing onto those in close proximity | | | | | | | |
| 13 | | Not being issued or wearing appropriate PPE | | | | | | | |
| 14 | | Not having adequate washing facilities with appropriate sanitiser available | | | | | | | |
| 15 | | Management not developing a contingency plan and communicating it with employees | | | | | | | |
| 16 | | Workers not adequately informed about the threat and protection methods | | | | | | | |
| 17 | | Mass gatherings and meetings | | | | | | | |
| 18 | | Workers not adequately washing hands | | | | | | | |
| 19 | Travel history not declared by persons accessing the site | | | | | | | | |

| | | | | | | | | | |
|----|--|--|---|--|-----------------------------------|--|---|-----------------------|---|
| | A | B | C | D | E | F | G | H | I |
| 1 | <u>BASELINE RISK ASSESSMENT</u> | | | | | | | | |
| 2 | Site: BOSPOORT AT RUSTENBURG, NORTH – WEST | | | Risk Assessment Team: Pieter Herbst (Pr. CHSA/057/2017) | | | | | |
| 3 | Date: 13 July 2020 | | | | | | | | |
| 4 | EXPOSURE AND INFECTION WITH CORONA VIRUS | | | | | | | | |
| 5 | Frequency 2 < 15% chance of exposure - 3 ><15 and 50% chance of exposure 4 ><50 and 75% chance of exposure 5 > 75% chance of exposure | Probability of injury /loss /damage Unlikely = 1 Possible = 2 Almost certain = 3 Certain to happen = 4 Has happened before = 5 | Severity of inj/damage Minor/no inj/damage = 2 Serious inj/damage = 3 fatality/major damage = 4 multiple fatalities/damage = 5 catastrophic = 6 | Rating Up to 13 = Low risk. ><14 and 36 = Moderate risk. 36> = High risk | | |  | | |
| 6 | Description of Area/Activities/Task | Hazards | Risk , Unwanted Event & Consequences | exposure to hazard | Frequency of loss / damage | Severity of injury/ loss/damage | Score | Rating L, M, H | Recommended controls |
| 20 | Communication and awareness | Potentially infected / exposed employees not identified and monitored due to a lack of awareness communication and hygiene measures | Inadequate communication channels will not reinforce health and hygiene measures in the workplaces such as hand hygiene, respiratory etiquette, and staying home when ill in order to limit transmission. It may also help with compliance with public / community health advice. | 4 | 3 | 5 | 60 | H | Provide awareness posters / signage and include access to handwashing facilities and place hand sanitizing dispensers in prominent locations throughout the workplace. |
| 21 | | | | | | | | | |
| 22 | Medical management | Occupational health practitioner services not available i.e. rural areas | Although screening may not identify all individuals infected with COVID-19 in the workplace, occupational health and safety professionals may be able to quickly and safely identify and isolate symptomatic individuals in the workplace. | 4 | 3 | 5 | 60 | H | Plan for rapid isolation of a symptomatic employee and identify an area where employees/clients can be isolated if they become ill at the workplace; Ensure that contact details of care professionals and relevant information is available and communicated health. |
| 23 | | Records of COVID 19 Exposure Medical Questionnaire not retained | Relevant information required for effective monitoring and identification purposes not available | | | | | | Questionnaires must be discussed with employees and records must be retained. |
| 24 | | Inadequate workplace cleaning and disinfection protocols | The frequency (i.e. one contact versus multiple contacts) and duration (i.e., transient contact versus prolonged contact) of exposure to high-touch surfaces and objects could potentially increase the risk of contamination. | | | | | | Enhance environmental cleaning procedures and protocols with a special attention to high-touch surfaces and object (e.g., phones, computers and toilet facilities) |

| | | | | | | | | | |
|----|--|--|---|--|--|--|---|-----------------------|--|
| | A | B | C | D | E | F | G | H | I |
| 1 | <u>BASELINE RISK ASSESSMENT</u> | | | | | | | | |
| 2 | Site: BOSPOORT AT RUSTENBURG, NORTH – WEST | | | Risk Assessment Team: Pieter Herbst (Pr. CHSA/057/2017) | | | | | |
| 3 | Date: 13 July 2020 | | | | | | | | |
| 4 | EXPOSURE AND INFECTION WITH CORONA VIRUS | | | | | | | | |
| 5 | Frequency 2 < 15% chance of exposure - 3 ><15 and 50% chance of exposure 4 ><50 and 75% chance of exposure 5 > 75% chance of exposure | Probability of injury /loss /damage Unlikely = 1 Possible = 2 Almost certain = 3 Certain to happen = 4 Has happened before = 5 | Severity of inj/damage Minor/no inj/damage = 2 Serious inj/damage = 3 fatality/major damage = 4 multiple fatalities/damage = 5 catastrophic = 6 | Rating Up to 13 = Low risk. ><14 and 36 = Moderate risk. 36> = High risk | | |  | | |
| 6 | Description of Area/Activities/Task | Hazards | Risk , Unwanted Event & Consequences | Frequency of exposure to hazard | Probability of injury / loss / damage | Severity of injury/ loss/damage | Score | Rating L, M, H | Recommended controls |
| 38 | Personal protective equipment (PPE) | PPE purchased not in accordance with standards and specifications | Increase of infection due to non-compliance. Lack of resources to purchase adequate stock of relevant PPE | 5 | 5 | 4 | 100 | H | Workers who are exposed to people who are ill with respiratory symptoms, such as coughing and sneezing, may use face masks and eye protection if the nature of their work warrants it. Gloves are only recommended when workers will be in direct contact with an ill person, or a contaminated object or environment. PPE must be used correctly; training on their use should be provided and records Shall be retained. |
| 39 | | Not selecting appropriate PPE in relation to the hazard route of transmission | | | | | | | |
| 40 | | Incorrect fitting of PPE | | | | | | | |
| 41 | | Inadequate information and training communication and / or material | | | | | | | |
| 42 | | Limitation of PPE not identified and / or communicated | | | | | | | |
| 43 | | Shortage of stock | | | | | | | |
| 44 | | PPE not safely disposed | | | | | | | |
| 45 | | Cross contamination due to incorrect storage of PPE | | | | | | | |



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

C3.5C EMPLOYER’S ENVIRONMENTAL MANAGEMENT PLAN

**RLM/RWST/OMM/0102/2024/25 - RE-ADVERT:
APPOINTMENT OF A CONTRACTOR FOR THE
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Tender
Part T1: Tendering Procedures

C3.5-1

C3.5
Employer’s EMP

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



ENVIRONMENTAL MANAGEMENT PROGRAMME (EMPr)

File Reference Number:

NWP/EIA/97/2018

Project Title:

The proposed construction of a 500mm diameter rising- and an 800mm diameter gravity potable water pipelines from the Bospoort WTW to tie into the existing pipeline to Rustenburg town, a reservoir and associated access roads currently under the jurisdiction of the Rustenburg Local Municipality, North West Province.

Prepared for:

Applicant:

Rustenburg Water Services Trust (Mr. Pet Maas)
701 Missionary Mpheni House
Corner Nelson Mandela & Beyers Naude Road
Rustenburg
0300

Cell: +27 (0)83 445 7287

Fax: +27 (0)86 645 8844

Email: pet.maas@tigros.co.za

Compiled by:

Ecoleges Environmental Consultants cc

Tel: +27 (0)83 644-7179

Fax: 086 697 9316

P.O. Box 9005, Nelspruit, 1200

P.O. Box 516, Machadodorp, 1170


Email: justin@ecoleges.co.za

Submission Date: 7 June 2019

Report Status: Final 00

DOCUMENT CONTROL

Table 1. Document Control.

| COMPILED BY | STATUS | REVISION | SIGNATURE | DISTRIBUTED ON |
|------------------|--------|----------|--|----------------|
| Hlengile Mtsweni | Draft | 00 | | 29 April 2019 |
| Justin Bowers | Final | 00 |  | 06 June 2019 |
| | | | | |

EXECUTIVE SUMMARY

The project proponent, Rustenburg Water Services Trust, has appointed Ecoleges Environmental Consultants as the Environmental Assessment Practitioner (EAP) to undertake an application for an Environmental Authorisation (EA) through a Basic Assessment (BA) process, as the proposed pipeline and reservoir construction trigger listed activities in terms of the EIA Regulations (2014) as amended (GG No. 40772, GN No. 326 & 327, 7 April 2017) in terms of Section 24 of the National Environmental Management Act (NEMA, Act 107 of 1998). The application was submitted on the 18th March 2019 to the North West Department of Rural, Environment and Agricultural Development (DREAD) as the designated Competent Authority.

Following the upgrading of the 12Mℓ/d Bospoort Water Treatment Works (WTW) to 24Mℓ/d, a new 500mm diameter rising main is required to convey potable water, from an existing pipeline from the WTW to the new reservoir. An 800mm diameter pipe will supply the water from the reservoir at approximately 300ℓ per second to augment the current Vaalkop supply system and provide much needed potable water to the communities in the area as well as Rustenburg Town.

This Environmental Management Programme (EMPr) is developed in compliance with section 24N of the NEMA, 1998, as amended and contains those requirements prescribed in the EIA Regulations, 2014, as amended, including section 23 and Appendix 4 of GN No. R. 326 of 7 April 2017.

The EMPr is to be read in conjunction with the BA Report (BAR) and Environmental Authorisation (EA) providing detail on the affected environment as well as the impact assessment for the anticipated environmental impacts.

Activities to be undertaken during the construction, operational and decommissioning phases include:

Construction Phase

- Site preparation;
 - Clearly delineate the construction footprint to avoid construction creep outside the approved development footprint;
 - Complete search and rescue for fauna/flora of conservation concern or protected status ahead of any construction activities;
- Establish access roads (access roads largely pre-existing);
- Transport plant and equipment to site;
- Establishment of laydown areas;
- Establishment of ancillary infrastructure;
- Construction and establishment of the pipeline/reservoir;
- Site rehabilitation; and
- Environmental management and monitoring throughout the construction process, inclusive of:

- Continuous monitoring and removal of alien or invasive plant species;
- Dust monitoring and management;
- Storm water monitoring and management;
- Erosion monitoring and remediation;
- Fire management;
- Vegetation and habitat management;
- Hazardous substance monitoring and management, including detecting any leakage or spillage; and
- Monitoring and management measures to protect hydrological features.

Operational Phase

- Maintenance, repairs of the pipeline/reservoir and associated infrastructure inclusive of:
 - Cleaning, maintaining the pipeline and reservoir permanent servitude, including associated infrastructure;
 - Removal of alien invasive vegetation; and
 - Maintain and repair fencing (where applicable).
- Environmental management and monitoring throughout the operational process, inclusive of:
 - Continuous monitoring and removal of alien or invasive plant species;
 - Storm water monitoring and management;
 - Erosion monitoring and remediation;
 - Fire management;
 - Vegetation and habitat management;
 - Monitoring and management measures to protect hydrological features; and
 - Scour chamber discharges and water quality monitoring;
- Waste management; and
- Health and safety implementations.

Decommissioning

Complete decommissioning can occur should it no longer be economically feasible to continue the pipeline & reservoir operation; activities will include:

- Apply for environmental authorisation;
- Site reparation;
- Disassembly and recycling of existing components; and
- Rehabilitation of the site.

The implementation of the EMPr within the project is not an optional additional or “add on” requirement. The EMPr is legally binding, integral to the contract and is as important as the engineering aspects of the contract. The EMPr is a working document to be used throughout the life of the project, until such time that closure is achieved.

TABLE OF CONTENTS

| | |
|--|-----|
| DOCUMENT CONTROL..... | 2 |
| EXECUTIVE SUMMARY | 3 |
| CHECKLIST..... | 7 |
| ABBREVIATIONS / ACRONYMS AND DEFINITIONS | 9 |
| SECTION 1: DETAILS & EXPERTISE OF THE EAP AND APPLICANT..... | 13 |
| SECTION 2: INTRODUCTION & BACKGROUND | 15 |
| SECTION 3: DESCRIPTION OF THE ACTIVITY | 15 |
| SECTION 4: LAYOUT MAP OF PROPOSED ACTIVITY | 30 |
| SECTION 5: ACTIVITIES, ASPECTS AND IMPACTS AND THEIR MANAGEMENT, MITIGATION & DESIRED OUTCOMES..... | 33 |
| SECTION 6: ENVIRONMENTAL AWARENESS PLAN..... | 101 |
| SECTION 7: RESPONSIBILITIES OF ROLE PLAYERS | 103 |
| SECTION 8. COMMUNICATION | 105 |
| SECTION 9: ENVIRONMENTAL EMERGENCY PLAN FOR THE CONTROL OF ENVIRONMENTAL INCIDENTS..... | 108 |

TABLE OF FIGURES

| | |
|--|----|
| Figure 1. Site layout map of the pipeline route and the reservoir. | 31 |
| Figure 2. Site sensitivity map of the pipeline route and the reservoir..... | 32 |
| Figure 3: A breakdown of the different types of impacts including the resources used to identify them. | 34 |









TABLE OF TABLES

| | |
|---|-----|
| Table 1. Document Control. | 2 |
| Table 2. Environmental Management Programme Checklist. | 7 |
| Table 3. List of terms for abbreviations used in this document..... | 9 |
| Table 4. Definitions of some terms used in this document. | 10 |
| Table 5. A detailed description of the activities (including Listed Activities as per the EIA Regulations, 2014 as amended) and resultant aspects of the project that are covered by the EMPr. | 16 |
| TABLE 6. COMPLIANCE MANAGEMENT..... | 37 |
| TABLE 7. CONSTRUCTION CAMP, LAYDOWN AREAS, STOCKPILES, STORES & EQUIPMENT..... | 42 |
| TABLE 8. WASTE MANAGEMENT (generation, handling, storage and disposal, including hazardous waste). | 50 |
| TABLE 9. FAUNA & FLORA MANAGEMENT..... | 62 |
| TABLE 10. WATER USE & MANAGEMENT (INCLUDING WATERCOURSES). | 68 |
| TABLE 11. AIR QUALITY MANAGEMENT..... | 74 |
| TABLE 12. SOIL MANAGEMENT..... | 77 |
| TABLE 13. SOCIAL-ECONOMIC MANAGEMENT (HEALTH, SAFETY & SECURITY & COMMUNICATION). | 83 |
| TABLE 14. CULTURAL, HERITAGE, ARCHAEOLOGICAL & PALEONTOLOGICAL MANAGEMENT..... | 89 |
| TABLE 15. INFRASTRUCTURAL & TRAFFIC MANAGEMENT (INCLUDING PARKING ON SITE). | 96 |
| TABLE 16. VISUAL ASPECT MANAGEMENT. | 100 |

CHECKLIST

An environmental management programme (EMPr) must comply with section 24N of the NEMA, 1998, as amended and contain those requirements prescribed in the EIA Regulations, 2014, as amended, including Regulation 23 and Appendix 4. Additional requirements relating to content of the EMPr specified in the any comments and responses received from I&AP's including the competent authority are also included as well as referencing relevant guideline documents. Table 2 indicates the requirements stipulated in the EIA Regulations which have dictated the layout and content of this EMPr.

Table 2. Environmental Management Programme Checklist.

| Content of Environmental Management Programme (EMPr) | Page/Section |
|---|---|
| 1. (1) An EMPr must comply with section 24N of the Act and include- |  |
| (a) details of | |
| (i) the EAP who prepared the EMPr; and | Page 12 |
| (ii) the expertise of that EAP to prepare an EMPr, including a curriculum vitae; | Page 13 |
| (b) a detailed description of the aspects of the activity that are covered by the EMPr as identified by the project description; | Section 3 Page 15-29 |
| (c) a map at an appropriate scale which superimposes the proposed activity, its associated structures, and infrastructure on the environmental sensitivities of the preferred site, indicating any areas that should be avoided, including buffers; | Section 4 Page 31 & 32 |
| (d) a description of the impact management outcomes, including management statements, identifying the impacts and risks that need to be avoided, managed and mitigated as identified through the environmental impact assessment process for all phases of the development including- | Section D Page 33-95 |
| (i) planning and design; |  |
| (ii) pre-construction activities; |  |
| (iii) construction activities; |  |
| (iv) rehabilitation of the environment after construction and where applicable post closure; and |  |
| (v) where relevant, operation activities; |  |
| (f) a description of proposed impact management actions, identifying the manner in which the impact management outcomes contemplated in paragraph (d) will be achieved, and must, where applicable, include actions to - | Section D Page 33-95 |
| (i) avoid, modify, remedy, control or stop any action, activity or process which causes pollution or environmental degradation; |  |
| (ii) comply with any prescribed environmental management standards or practices; |  |
| (iii) comply with any applicable provisions of the Act regarding closure, where | N/A |

| | |
|--|-------------------------------------|
| <i>applicable; and</i> | |
| <i>(iv) comply with any provisions of the Act regarding financial provisions for rehabilitation, where applicable;</i> | N/A |
| <i>(g) the method of monitoring the implementation of the impact management actions contemplated in paragraph (f);</i> | Section D Page 33-95 |
| <i>(h) the frequency of monitoring the implementation of the impact management actions contemplated in paragraph (f);</i> | Section D Page 33-95 |
| <i>(i) an indication of the persons who will be responsible for the implementation of the impact management actions;</i> | <input checked="" type="checkbox"/> |
| <i>(j) the time periods within which the impact management actions contemplated in paragraph (f) must be implemented;</i> | <input checked="" type="checkbox"/> |
| <i>(k) the mechanism for monitoring compliance with the impact management actions contemplated in paragraph (f);</i> | Section D Page 33-95 |
| <i>(l) a program for reporting on compliance, taking into account the requirements as prescribed by the Regulations;</i> | <input checked="" type="checkbox"/> |
| <i>(m) an environmental awareness plan describing the manner in which-</i> | Section 6 Page 59 |
| <i>(i) the applicant intends to inform his or her employees of any environmental risk which may result from their work; and</i> | Section 6 Page 59 |
| <i>(ii) risks must be dealt with to avoid pollution or the degradation of the environment; and</i> | Section 9 Page 66 |
| <i>(n) any specific information that may be required by the competent authority.</i> | <input checked="" type="checkbox"/> |
| <i>(2) Where a government notice gazetted by the Minister provides for a generic EMP, such generic EMP as indicated in such notice will apply.</i> | N/A |

ABBREVIATIONS / ACRONYMS AND DEFINITIONS

Table 3. List of terms for abbreviations used in this document.

| Abbreviation / Acronym | Term |
|------------------------|---|
| BA | Basic Assessment as per Regulation 19 of the EIA Regulations (2014), as amended. |
| BPDM | Bojanala Platinum District Municipality |
| CA | Competent Authority |
| CAR | Corrective Action Reports |
| CLO | Community Liaison Officer |
| CRE | Chief Resident Engineer |
| DEA | Department of Environmental Affairs (National) |
| DMR | Department of Mineral Resources |
| DREAD | Department of Rural, Environment and Agricultural Development (North West) |
| DWS | Department of Water & Sanitation |
| EA | Environmental Authorisation |
| EAPASA | Environmental Assessment Practitioners Association of South Africa |
| ECO | Environmental Control Officer |
| EIA | Environmental Impact Assessment as provided for in Section 24 of NEMA (Act 107 of 1998) and EIA Regulations (2014), as amended. |
| EIAr | Environmental Impact Assessment Report |
| ELU | Existing Lawful Use as per Part 3 of the National Water Act (Act 36 of 1998) |
| EM | Environmental Manager |
| EMPr | Environmental Management Programme |
| GA | General Authorisation as per Section 39 of the National Water Act (Act 36 of 1998) |
| HSO | Health & Safety Officer |
| I&APs | Interested and Affected Parties |
| IDP | Integrated Development Plan |
| IEA | Independent Environmental Auditor |
| LA | Listed Activity (EIA Regulations, 2014) |
| LN1 | Listing Notice 1: GN. No. R. 983, 4 December 2014, as amended in GN. No. R. 327, 7 April 2017. |
| LN2 | Listing Notice 2: GN R. 984, 4 December 2014, as amended in GN. No. R. 325, 7 April |

| | |
|---------|---|
| | 2017. |
| LN3 | Listing Notice 3: GN R. 985, 4 December 2014, as amended in GN. No. R. 324, 7 April 2017. |
| MPRDA | Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002) |
| NEMA | National Environmental Management Act, 1998 (Act No. 107 of 1998) |
| NHRA | National Heritage Resources Act, 1999 (Act No. 25 of 1999) |
| NWA | National Water Act, 1998 (Act No. 36 of 1998) |
| SACNASP | South African Council for Natural Scientific Professions |
| SAHRA | South African Heritage Resources Agency |
| SDF | Spatial Development Framework |
| SEO | Site Environmental Officer |
| SO | Social Officer |
| WUL | Water Use License |
| WTW | Water Treatment Works |
| WWTW | Wastewater Treatment Works |

Table 4. Definitions of some terms used in this document.

| Term | Source | Definition |
|---------------------------|------------------------|--|
| Aspect (environmental) | ISO 14001: 2015 | <p>Element of an organisation's activities or products or services that interacts or can interact with the environment.</p> <p>An environmental aspect can cause (an) environmental impact(s). A significant environmental aspect is one that has or can have one or more significant environmental impact(s).</p> |
| Corrective Action | ISO 14001: 2015 | Action to eliminate the cause of a non-conformity (or non-compliance in the case of an EMPr) and prevent recurrence. |
| Development | EIA Regulations (2014) | Means the building, erection, construction or establishment of a facility, structure or infrastructure, including associated earthworks or borrow pits, that is necessary for the undertaking of a listed or specified |

| | | |
|-----------------------|---|---|
| | | activity, but excludes any modification, alteration or expansion of such a facility, structure or infrastructure, including associated earthworks or borrow pits, and excluding the redevelopment of the same facility in the same location, with the same capacity and footprint. |
| Development footprint | EIA Regulations, 2014 as amended | Any evidence of physical alteration because of the undertaking of any activity. |
| Environment | ISO 14001:2015 | Surroundings in which an organisation operates, including air, water, land, natural resources, flora, fauna, humans and their relationships. |
| Environment | National Environmental Management Act (Act 107 of 1998) | The surroundings within which humans exist and that are made up of— (i) the land, water and atmosphere of the earth; (ii) micro-organisms, plant and animal life; (iii) any part or combination of (i) and (ii) and the interrelationships among and between them; and (iv) the physical, chemical, aesthetic and cultural properties and conditions of the foregoing that influence human health and well-being. |
| Environmental Impact | ISO 14001: 2015 | Change to the environment, whether adverse or beneficial, wholly or partially resulting an organisation's environmental aspects. |
| Maintenance | EIA Regulations (2014) | Means actions performed to keep a structure or system functioning or in service on the same location, capacity and footprint. |
| Performance | ISO 14001: 2015 | Measurable unit. Performance can relate either to quantitative or qualitative findings. |
| Significant impact | EIA Regulations (2014) | Means an impact that may have a notable effect on one or more aspects of the environment or may result in |

| | | |
|-------------------------|---|---|
| | | non-compliance with accepted environmental quality standards, thresholds or targets and is determined through rating the positive and negative effects of an impact on the environment based on criteria such as duration, magnitude, intensity and probability of occurrence. |
| Sustainable development | National Environmental Management Act (Act 107 of 1998) | The integration of social, economic and environmental factors into planning, implementation and decision-making so as to ensure that development serves present and future generations. |
| Watercourse | EIA Regulations, 2014 as amended | <p>(a) a river or spring;</p> <p>(b) a natural channel in which water flows regularly or intermittently;</p> <p>(c) a wetland, pan, lake or dam into which, or from which, water flows; and any collection of water which the Minister may, by notice in the Gazette, declare to be a watercourse as defined in the National Water Act, 1998 (Act No. 36 of 1998); and</p> <p>a reference to a watercourse includes, where relevant, its bed and banks.</p> |

SECTION 1: DETAILS & EXPERTISE OF THE EAP AND APPLICANT

Details of –

(i) The EAP who prepared the report; and applicant details

| | |
|--|------------------------------------|
| Environmental Assessment Practitioner | Ecoleges Environmental Consultants |
| Contact Person | Justin Aragon Bowers |
| Postal Address | PO Box 9005, Nelspruit, 1200 |
| Telephone | +27(0)83 644 7179 |
| E-mail | justin@ecoleges.co.za |

| | |
|------------------------------|---|
| Project Applicant | Rustenburg Water Services Trust |
| Trading Name (if any) | |
| Contact Person | Pet Maas |
| Physical Address | 701 Missionary Mpheni House Cnr Nelson Mandela & Beyers Naude Road Rustenburg 0300 |
| Postal Address | N/A |
| Postal Code | 0300 |
| Telephone | N/A |
| Cell | 083 445 7287 |
| Fax | 086 645-8844 |
| Email | pet.maas@tigros.co.za |

(i) *The expertise of the EAP to prepare the EMP, including a curriculum vitae;*

Abbreviated Curriculum Vitae of Justin Aragon Bowers

| | |
|--|---|
| Name | Justin Bowers |
| Date of birth / ID No. | 15 October 1972 7210155074089 |
| Nationality | South African |
| Marital Status | Married with four children |
| Current Address | P O Box 516, Machadodorp, 1170. ● Redwing Farm, erf. Kaalbooi 368JT, Waterval Boven District, 1195, Mpumalanga, South Africa ● Cell: 082 451-5608 ● e-mail: justin@ecoleges.co.za |
| Languages | English, Afrikaans and Basic Zulu |
| Driver's Licence | Code EB, A & C1 |
| Specialisations | Key Fields: Compliance monitoring, vegetation ecology, rehabilitation plans, environmental / ecological management plans, environmental auditing, Environmental Impact & Basic Assessment. |
| Qualifications & Courses Attended | <p>1998 – 2000 NATIONAL DIPLOMA: NATURE CONSERVATION, Technikon Pretoria</p> <p>2001 – 2002 BACCALAUREUS TECHNOLOGIAE: NATURE CONSERVATION, Technikon Pretoria</p> <p>2003 – 2007 MAGISTER TECHNOLOGIAE: NATURE CONSERVATION (CUM LAUDE), Tshwane University of Technology, Pretoria</p> <p>2008 Environmental Law elective (MBA Programme), Rhodes University, Grahamstown.</p> <p>2010 – Present Certificate in Aquaculture, Department of Genetics & Aquaculture, University of Stellenbosch</p> <p>2014 Implementing Environmental Management Systems, Centre for Environmental Management, North-West University, Potchefstroom.</p> <p>2017 Transition ISO 14001 course, Centre for Environmental Management, North-West University, Pretoria locale.</p> <p>2018 EMS: Lead Auditor, CEM, North-West University, Potchefstroom.</p> |
| Latest Publication | Sadie J. Ryan, Paul C. Cross, John Winnie, Craig Hay, Justin Bowers, Wayne M. Getz. 2012. The utility of normalized difference vegetation index for predicting African buffalo forage quality. <i>Journal of Wildlife Management</i> DOI: 10.1002/jwmg.407. |
| Professional affiliations | IAIA ^{sa} , GSSA, SACNASP. |

SECTION 2: INTRODUCTION & BACKGROUND

Following the upgrading of the 12Mℓ/d Bospoort Water Treatment Works to 24Mℓ/d, a new 500mm diameter rising main is required to convey potable water from the Treatment Works to the new reservoir. An 800mm diameter pipe will supply the water from the reservoir to Rustenburg town. Both these lines will be steel pipelines and will convey approximately 300ℓ per second between the Treatment Works and Rustenburg Municipality. The pipelines will augment the current Vaalkop supply system and provide much needed potable water to the communities in the area as well as Rustenburg Town.

SECTION 3: DESCRIPTION OF THE ACTIVITY

(b) a detailed description of the aspects of the activity that are covered by the EMP as identified by the project description.

Table 5 describes all the activities that will be undertaken during the lifespan of this project including the identified listed activities and other associated activities (that do not require environmental authorization in their own right), but are needed to achieve the desired objective, that is the upgrading of the Bospoort Water Treatment Works via:

Construction of a new 500mm diameter rising main to convey potable water from the Treatment Works to the new reservoir. An 800mm diameter pipe will supply the water from the reservoir to Rustenburg town.

Table 5. A detailed description of the activities (including Listed Activities as per the EIA Regulations, 2014 as amended) and resultant aspects of the project that are covered by the EMPr.

| Phase | Activity | Sub-activities | Aspects |
|--|--|--|--|
| Planning & Design (including pre-construction) | Compliance with legal requirements by acquiring authorisations, permits and/or licenses for activities/uses undertaken during construction and operation | Protected Species | Impacting protected species prior to obtaining the required licenses / permits. |
| | | Water Use (21a) | Taking water from a watercourse prior to obtaining the required licences / permits. |
| | | Water Use (21f) | Discharging waste or water containing waste into a water resource prior to obtaining the required licences / permits. |
| | The development of- (ii) infrastructure or structures with a physical footprint of 10 square metres or more; where such development occurs- (a) within a watercourse; (c) if no development setback has been adopted within 32 metres of a watercourse, measures from the edge of a watercourse; h. North West iv. Critical biodiversity areas as identified in systematic biodiversity plans adopted by the competent authority. | Water Use (21g) | Impacting the watercourse through disposal of waste prior to obtaining the required licences / permits. |
| | | Water Use (21c & i) | Impeding or diverting the flow of water & altering the bed, banks, course or characteristics of a watercourse |
| | | Access Roads (not exceed threshold & layout to have minimal impacts) | Poor alignment & extent of linear activities like roads, fences, pipelines or other cleared servitudes can increase runoff, cause erosion and sedimentation of aquatic habitats and result in regulatory non-compliance. |
| | | Servitudes & wayleaves | Commencement without authorisation / permit from relevant authorities. |
| | | Compliance monitoring | Commencement without appointment of an Environmental Control Officer (ECO) to monitor compliance with the EA & EMPr. |
| | | Municipal bylaws | Non-compliance with the municipal bylaws. |
| | | Protection of archaeological findings | Destruction of graves and other sites of archaeological value and need for relevant permits where necessary. |
| | Socio-economic considerations | Employment of local labour | Insufficient employment of local labour. |

| Phase | Activity | Sub-activities | Aspects |
|-------|----------|--|---|
| | | | Presence of construction workforce. |
| | | | Influx of job seekers. |
| | | | Loss of farm labour to construction work. |
| | | | Job seekers may begin enquiring prior to commencement of construction as awareness of the project grows. |
| | | Economic benefits from professionals | If the appointed professionals are unreasonably expensive, the funds to head the projects might be exhausted. |
| | | Expectations | Job seekers may begin enquiring prior to commencement of construction as awareness of the project grows. |
| | | Uncertainty | Community confusion, frustration & lack of information. |
| | | Construction and use of Temporary Access Roads | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Increase in vehicle movement in area. |
| | | Provision of sanitation systems | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Ground water contamination. |
| | | Demarcation, fencing and gates | Loss of vegetation and habitat. |
| | | | Impede faunal movement. |
| | | | Impeded human movement and disrupted daily activities. |
| | | Working near or on the watercourse | Decline in water availability of water resource. |
| | | Water Use, abstraction and Management | |

| Phase | Activity | Sub-activities | Aspects |
|--------------|---|--|--|
| Construction | <p>Site establishment (construction camp, sanitation, temporary accommodation)</p> <p><i>LN3: Listed Activity 12</i> <i>The clearance of an area of 300 square metres or more of indigenous vegetation except where such clearance of indigenous vegetation is required for maintenance purposes undertaken in accordance with a maintenance management plan.</i> <i>h. North West</i> <i>iv. Critical biodiversity areas as identified in systematic biodiversity plans adopted by the competent authority;</i> <i>vi. Areas within a watercourse or wetland, or within 100 metres from the edge of a watercourse or wetland</i></p> | Clear & grub (fence line, pipeline, reservoir footprint, access roads and associated infrastructure) | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Noise Generation. |
| | | Construction and use of Temporary Access Roads | Loss of Vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Increased level of noise generation. |
| | | | Increase in vehicle movement in area. |
| | | | Dust generation. |
| | | Sanitation | Ground water contamination. |
| | | Fencing & gates | Loss of vegetation and habitat. |
| | | | Impede faunal movement. |
| | | | Impeded human movement and disrupted daily activities. |
| | | Lighting | Visual intrusion in remote areas. |
| | Access control including fencing of perimeter | Construction and use of Temporary Access Roads | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Increased level of noise generation. |
| | | | Increase in vehicle movement in area. |

| Phase | Activity | Sub-activities | Aspects |
|-------|--|--|--|
| | | Fencing & gates | Dust generation. |
| | | | Loss of vegetation and habitat. |
| | | | Impede faunal movement |
| | | | Impeded human movement and disrupted daily activities. |
| | Contractor's employees (staff conduct, movement) | Water use and management | Water contamination. |
| | | | Misuse of available water. |
| | | Cooking of food | Harvesting & fire control. |
| | | Sanitation | Unpleasant odours. |
| | | | Mismanagement of sewerage. |
| | | Employment of local labour | Insufficient employment of local labour. |
| | | | Presence of construction workforce. |
| | | | Influx of job seekers. |
| | | | Loss of farm labour to construction work. |
| | Construction of permanent & temporary access roads | Vegetation Clearing & Soil Hardening | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased level of noise generation. |
| | | Impact on the existing road conditions | The development of potholes. |
| | | | Damage to vehicles. |
| | Transport on site & accommodation of traffic (parking areas) | Parking | Potential increase in vehicle accidents. |
| | | | Increase in vehicle movement in area. |
| | | | Impact on the existing road conditions. |
| | | | Increase human safety risk. |
| | | | Increase in the level of noise generation. |
| | | | Greenhouse gas emissions. |

| Phase | Activity | Sub-activities | Aspects |
|-------|---|--|---|
| | | Impact on the existing road conditions | The development of potholes. |
| | | | Damage to vehicles. |
| | | | Potential increase in vehicle accidents. |
| | Sourcing & management of water (for drinking, sanitation & construction activities) | Drinking, dust suppression & sanitation | Water contamination. |
| | | | Misuse of available water. |
| | Sourcing & management of building material | Excavation of suitable bedding and backfill material | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | Topsoil stripping and storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Soil contamination. |
| | | | Encroachment and establishment of alien vegetation. |
| | | Slopes and slope stabilisation | Dust generation. |
| | | | Increased potential for erosion. |
| | | | Water contamination. |
| | | | Decline in aesthetic quality of the environment. |
| | | | Increase human safety risk. |
| | Stockpiling and material laydown areas (spoil, mulch, building sand, topsoil, windrows, material & equipment) | Topsoil stripping storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Soil contamination. |
| | | | Encroachment and establishment of alien vegetation. |

| Phase | Activity | Sub-activities | Aspects |
|-------|--------------------------|---|--|
| | | Slopes and slope stabilisation | Reduced productivity of subsistence farmland. |
| | | | Dust generation. |
| | | | Increased potential for erosion. |
| | | | Water contamination. |
| | | | Decline in the aesthetic quality of the environment. |
| | | | Increase human safety risk. |
| | Earthworks & excavations | Trenching | Dust generation. |
| | | | Increased potential for erosion. |
| | | | Increase human safety risk. |
| | | | Entrapment of small fauna |
| | | Importing of suitable bedding and backfill material | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Reduced productivity of subsistence farmland. |
| | | | Increased potential for erosion. |
| | | Topsoil stripping and storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Soil contamination. |
| | | | Reduced productivity of subsistence farmland. |
| | | | Encroachment and establishment of alien vegetation. |
| | | Slopes and slope stabilisation | Dust generation. |
| | | | Increased potential for erosion. |
| | | | Water contamination. |
| | | | Decline in aesthetic quality of the environment. |

| Phase | Activity | Sub-activities | Aspects |
|-------|---|---|--|
| | | Crushing of material | Increase human safety risk. |
| | | | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | <p>Construction of a pipeline and reservoir</p> <p>LN1: Listed Activity 9 The development of infrastructure exceeding 1000 metres in length for the bulk transportation of water or storm water-</p> <p>(i) with an internal diameter of 0.36 metres or more; or (ii) with a peak throughput of 120 litres or more; excluding where – (a) such infrastructure is for the bulk transportation of water or storm water or storm water drainage inside a road reserve or railway line reserve; or (b) where such development will occur within an urban area.</p> <p>LN3: Listed Activity 2 The development of reservoirs,</p> | Spoil material generation and management | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Decline in the aesthetic quality of the environment. |
| | | Transportation and storage of the cement and associated materials | Increase in vehicle movement in area. |
| | | | Impact on the existing road conditions. |
| | | | Increase human safety risk. |
| | | | Increase in the level of noise generation. |
| | | | Greenhouse gas emissions. |
| | | Protection of archaeological findings | Destruction of graves and other sites of archaeological value. |

| Phase | Activity | Sub-activities | Aspects |
|-------|--|--|--|
| | excluding dams, with a capacity of more than 250 cubic metres. h. North West iii. Outside urban areas; (dd) Critical biodiversity areas as identified in systematic biodiversity plans adopted by the competent authority or in bioregional plans; | | |
| | Pipeline Watercourse Crossings | Effects from pipeline trenching | Increased potential for erosion. |
| | | Excavation stockpiles | Increased potential for water pollution |
| | | Mixing of soil horizons | Encroachment and establishment of alien vegetation. |
| | | Clearing of riparian zone | Loss of vegetation, habitat and soil fertility. |
| | Handling of waste & generation (solid waste including 'spoil', liquid waste, separation, storage and disposal) | Domestic and construction waste collection, storage, handling and disposal | Unpleasant odours. |
| | | | Increase in waste generation. |
| | | | Decline in the aesthetic quality of the environment. |
| | | Spoil material generation and management | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Decline in the aesthetic quality of the environment. |
| | Handling of hazardous substances (fuel/oil, cement, bitumen, sewage/grey water) & management (including storage) at sanitation sites, kitchens, batching sites, refuelling areas and on site. | Maintenance of sanitation systems | Unpleasant odours. |
| | | | Soil contamination. |
| | | | Water contamination. |
| | | | Mismanagement of sewerage. |
| | | Bund area for fuel storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |

| Phase | Activity | Sub-activities | Aspects |
|-------|---|---|---|
| | | Use of flammable material and other material stores | Soil contamination. |
| | | | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Soil contamination. |
| | | Refuelling of construction vehicles and plant | Soil contamination. |
| | | | Water contamination. |
| | | Handling, storage, disposal of hazardous waste | Unpleasant odours. |
| | | | Soil contamination. |
| | | | Water contamination |
| | | Transportation of hazardous waste | Potential spillages of hazardous waste. |
| | | | Increase human safety risk. |
| | | | Greenhouse gas emission. |
| | Plant management (parking, driving, repair and maintenance, and refuelling) | Refuelling of construction vehicles and plant | Soil contamination. |
| | | | Water contamination. |
| | | Bund area for fuel storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Soil contamination. |
| | | Operation and movement of construction vehicles and plant | Dust generation. |
| | | | Increase in level of noise generation. |
| | | | Soil contamination. |
| | | | Increase human safety risk. |
| | | | Vibration. |
| | | | Greenhouse gas emissions. |
| | Building work (concrete work) | Water use and management | Water contamination. |

| Phase | Activity | Sub-activities | Aspects |
|-------|-------------------------------|--|--|
| | | Spoil material generation and management | Misuse of available water. |
| | | | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Decline in the aesthetic quality of the environment. |
| | | Excavation of suitable bedding and backfill material | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | Disturbing natural areas | Slopes and slope stabilisation | Dust generation. |
| | | | Increased potential for erosion. |
| | | | Water contamination. |
| | | | Decline in aesthetic quality of the environment. |
| | | | Increase human safety risk. |
| | | Topsoil stripping and storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Soil contamination. |
| | | | Reduced productivity of subsistence farmland. |
| | | | Encroachment and establishment of alien vegetation. |
| | Site closure & rehabilitation | Removal of structures and infrastructures | Increase in waste generation. |
| | | Removal of inert waste and rubble | |
| | | Hazardous waste and pollution control | |

| Phase | Activity | Sub-activities | Aspects |
|-----------------------------------|--|---|---|
| | | Final shaping of disturbed areas | Increased potential for erosion. |
| | | Topsoil replacement and soil amelioration | |
| | | Ripping and scarifying | |
| | | Planting | Reduced productivity of subsistence farmland. |
| | | Grassing | |
| | | Maintenance | Encroachment and establishment of alien vegetation. |
| | | Management of alien vegetation | Loss of vegetation, habitat and soil fertility. |
| Operation (including maintenance) | Operation employment | Consultation with affected parties | Insufficient consultation. |
| | | Employment of local labour | Insufficient employment of local labour. |
| | | | Presence of construction workforce. |
| | | | Influx of job seekers. |
| | Pipeline & Reservoir Infrastructure | Maintenance and Repair | Increase in waste generation |
| | Operation of Scour Chamber | Discharging from Scour Outlets | Increased potential for erosion. |
| | | | Increased potential for water pollution |
| | Consumption (energy, water, and other resources) | Water use and management | Water contamination. |
| | | | Misuse of available water. |
| | | Cooking of food | Fire hazard. |
| | | | Illegal wood harvesting. |
| | Maintenance | Refuelling of construction vehicles and plant | Soil contamination. |
| | | | Water contamination. |
| | | Handling, storage & disposal of | Unpleasant odours. |

| Phase | Activity | Sub-activities | Aspects |
|--|--|-----------------------------------|---|
| Decommissioning (including rehabilitation) | | waste | Soil contamination. |
| | | | Water contamination. |
| | | Maintenance of sanitation systems | Unpleasant odours. |
| | | | Mismanagement of sewerage. |
| | Lighting to create visibility at night | Use of generators | Increase in level of noise generation. |
| | | | Soil contamination. |
| | | Security | Trespassing. |
| | Terrestrial and aquatic ecological management | Use of herbicides | Loss of vegetation, habitat and soil fertility. |
| | | | Soil contamination. |
| | | Harvesting of indigenous plants | Loss of local biodiversity |
| | | Overgrazing | Increased potential for erosion. |
| | | | Reduced productivity of subsistence farmland. |
| | Social & community changes | | Dust generation. |
| | | Security | Trespassing. |
| | | Fire Control | Loss of vegetation, habitat and soil fertility. |
| | | Employment of local labour | Insufficient employment of local labour. |
| | | | Presence of construction workforce. |
| | | | Influx of job seekers. |
| | | | Loss of farm labour to construction work. |
| | | Visual aspects | Visual Intrusiveness. |
| | Disposal of infrastructure, residual of all types of waste | Demolition activities | Dust generation. |
| | | | Increased level of noise generation. |
| | | | Vibration. |
| | | | Increase in waste generation. |

| Phase | Activity | Sub-activities | Aspects |
|-------|---|---|--|
| | | Removal of inert waste and rubble | Increase human safety risk. |
| | | | Decline in the aesthetic quality of the environment. |
| | | | Soil contamination. |
| | Human influence (staff conduct, movement) | Harvesting of indigenous plants | Loss of vegetation, habitat and soil fertility. |
| | | | Decline in the aesthetic quality of the environment. |
| | | Fires for heat & cooking | Fire hazard. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Illegal wood harvesting. |
| | | Littering | Decline in the aesthetic quality of the environment. |
| | | | Unpleasant odours. |
| | | | Increase in waste generation. |
| | | | Decline in the aesthetic quality of the environment. |
| | | Noise | Increase human safety risk. |
| | | | Increase in the level of noise generation. |
| | Roads and access routes | Topsoil stripping and storage | Dust generation. |
| | | | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | | Encroachment and establishment of alien vegetation. |
| | | Road decommissioning & rehabilitation | Dust generation. |
| | | | Increased level of noise generation. |
| | | | Soil contamination. |
| | Rehabilitation of affected footprint | Removal & transportation of structures and infrastructures; | Increase in vehicle movement in area. |
| | | | Impact on the existing road conditions. |
| | | | Increase human safety risk. |

| Phase | Activity | Sub-activities | Aspects |
|-------|----------|--|---|
| | | | Increase in the level of noise generation. |
| | | | Greenhouse gas emissions. |
| | | | Increased potential for erosion. |
| | | Maintenance & management of alien vegetation | Loss of vegetation, habitat and soil fertility. |
| | | | Increased potential for erosion. |
| | | Planting & grassing | Reduced productivity of subsistence farmland. |
| | | Topsoil replacement and soil improvement | Loss of vegetation, habitat and soil fertility. |
| | | Final Shaping of disturbed areas | Increased potential for erosion through lack of conformance to surrounding landscape. |

SECTION 4: LAYOUT MAP OF PROPOSED ACTIVITY

(c) a map at an appropriate scale which superimposes the proposed activity, its associated structures, and infrastructure on the environmental sensitivities of the preferred site, indicating any areas that any areas that should be avoided, including buffers.

“The Environmental Management Programme (EMPr) to be submitted as part of the EIAr must include the following:

ii. The final site layout map.

iv. An environmental sensitivity map indicating environmental sensitive areas and features identified during the EIA process.

v. A map combining the final layout map superimposed (overlain) on the environmental sensitivity map.”




Figure 1. Site layout map of the pipeline route and the reservoir.




Figure 2. Site sensitivity map of the pipeline route and the reservoir.

SECTION 5: ACTIVITIES, ASPECTS AND IMPACTS AND THEIR MANAGEMENT, MITIGATION & DESIRED OUTCOMES

1.(1)(d) a description of the impact management outcomes, including management statements, identifying the impacts and risks that need to be avoided, managed and mitigated as identified through the environmental impact assessment process for all phases of the development including-

- (i) planning and design;*
- (ii) pre-construction activities;*
- (iii) construction activities;*
- (iv) rehabilitation of the environment after construction and where applicable post closure; and*
- (v) where relevant, operation activities;*

1.(1)(f) a description of proposed impact management actions, identifying the manner in which the impact management outcomes contemplated in paragraph (d) will be achieved, and must, where applicable, include actions to -

- (i) avoid, modify, remedy, control or stop any action, activity or process which causes pollution or environmental degradation;*
- (ii) comply with any prescribed environmental management standards or practices;*
- (iii) comply with any applicable provisions of the Act regarding closure, where applicable; and*
- (iv) comply with any provisions of the Act regarding financial provisions for rehabilitation, where applicable;*

1.(1)(g) the method of monitoring the implementation of the impact management actions contemplated in paragraph (f);

(h) the frequency of monitoring the implementation of the impact management actions contemplated in paragraph (f);

(i) an indication of the persons who will be responsible for the implementation of the impact management actions;

(j) the time periods within which the impact management actions contemplated in paragraph (f) must be implemented;

(k) the mechanism for monitoring compliance with the impact management actions contemplated in paragraph (f);

(l) a program for reporting on compliance, taking into account the requirements as prescribed by the Regulations;

(m) an environmental awareness plan describing the manner in which-

(i) the applicant intends to inform his or her employees of any environmental risk which may result from their work; and

(ii) risks must be dealt with in order to avoid pollution or the degradation of the environment; and

(n) any specific information that may be required by the competent authority.

The impacts are considered within the scope of the project, including but not limited to the Listed Activities. The relevant impacts resulting from Listed Activities and associated activities, including environmental, socio-economic and cultural heritage, are informed by a predetermined list of potential environmental impacts, comments received from Interested and Affected Parties and the findings contained in specialist studies.




Figure 3: A breakdown of the different types of impacts including the resources used to identify them.

As stipulated in regulation 1(1)(d) of Appendix 4 of the EIA regulation (2104), as amended; the setting of desired impact management outcomes forms the principle objective of an EMPr. Outcomes are driven by impact management actions including measures and mitigations to avoid, modify, remedy, control or stop any action, activity or process which causes pollution or environmental degradation; to comply with any prescribed environmental management standards or practices, including legal requirements and in some cases, “best practices” that the Implementer aspires to fulfil (e.g. Equator Principles). The outcomes are achieved by implementing and achieving measurable Targets (both quantitative & qualitative). Management and mitigation measures are set to afford guidance and parameters to the implementer to achieve the set outcomes. The following section describes management programmes for the different environmental attributes pertaining to the Project. As part of the Management

Programmes, the section describes the potential environmental impacts which may result from the identified aspects / activities, the desired outcomes of mitigating these impacts as well as the targets used to measure the level of environmental compliance and performance.

The following legislation, guidelines, departmental policies, environmental management instruments and / or other decision-making instruments that have been developed or adopted by a competent authority in respect of activities associated with a development of this nature, were identified and considered in the preparation of this EMPr:

1. Bojanala Platinum District Municipality IDP (Final) 2017/18;
2. Conservation of Agricultural Resources Act, 1993 (No 43 of 1983) and the regulations dealing with declared weeds and invader plants;
3. Constitution of the Republic of South Africa Act, 1996 (No. 108 of 1996), including section 24;
4. DAFF (1970) Sub-Division of Agricultural Land Act, 1970 (No. 70 of 1970),
5. DEA (2011), National list of ecosystems that are threatened and in need of protection. GN 1002, GG 34809, 9 December 2011.
6. DEAT (2004) Environmental Management Plans, Integrated Environmental Management, Information Series 12, Department of Environmental Affairs and Tourism (DEAT), Pretoria.
7. DWA (2007), Guideline for Developments within a Flood line (Edition 1), Department of Water Affairs and Forestry, Pretoria, South Africa;
8. DWAS (2016), General Authorisation in GN No. 509 published in Government Gazette No. 40229 dated 26 August 2016;
9. DWAS (2016), General Authorisation in GN No. 538 published in Government Gazette No. 40243 dated 2 September 2016;
10. Environment Conservation Act, 1989 (No 73 of 1989), including Schedules 4 and 5 of the National Regulations regarding Noise Control made under Section 25 of the Environment Conservation Act, 1989 (Act 73 of 1989) in GN No. R 154 of Government Gazette No. 13717 dated 10 January 1992. (Note that this particular section of the Environment Conservation Act is not repealed by NEMA (107 of 1998)). Conservation of Agricultural Resources Act, 1983 (Act No. 43 of 1983);
11. Fertilizers, Farm Feeds, Agricultural Remedies and Stock Remedies Act (Act No. 36 of 1947);
12. Government Municipal Systems Act (Act 32 of 2000);
13. Hazardous Substances Act, 1973 (Act No. 15 of 1973);
14. Health Act, 2003 (Act No. 61 of 2003);
15. Local Government: Municipal Systems Act (Act 32 of 2000);
16. Lochner, P. 2005. Guideline for Environmental Management Plans. CSIR Report No ENV-S-C 2005-053 H. Republic of South Africa, Provincial Government of the Western Cape, Department of Environmental Affairs & Development Planning, Cape Town.
17. Minerals and Petroleum Resources Development Act, 2002 (No 28 of 2002);
18. National Environmental Management Act, 1998 (No 107 of 1998) including EIA Regulations, 2014 published in Government Notice No. R. 982, R. 983, R. 984 and R.

985 in Government Gazette No. 38282 dated 04 December 2014, as amended in Government Notice No. R. 324, R. 325, R. 327 and R. 328 in Government Gazette No. 40772 dated 07 April 2017;

19. National Environmental Management: Air Quality Act, 2003 (No 57 of 2003) including the list of activities which result in atmospheric emissions published in GN No. 248 of Government Gazette No. 33064 dated 31 March 2010;
20. National Environmental Management: Biodiversity Act, 2004 (No 10 of 2004);
21. National Environmental Management: Waste Act, 2009 (Act No. 59 of 2009) ("NEM: WA");
22. National Forest Act, 1998 (No 84 of 1998);
23. National Heritage Resources Act, 1999 (No 25 of 1999);
24. National Veld and Forest Fire Act, 1998 (No 101 of 1998);
25. National Water Act, 1998 (Act No. 36 of 1998), Sections 27, 28, 29 ,30 ,31 and 39 (Sections dealing with General Authorisations and Water Use Licenses).
26. North West Biodiversity Management Act (NWBMA -Act 4 of 2016), Provincial Gazette no. 7721, Provincial Notice 3, 3 January 2017, as amended (not in force at time of report).
27. Rustenburg Local Municipality Bylaws, especially fire brigade services by laws no. 2 of 2015.

The following management programme aims to set management actions to achieve stated desired outcomes for each environmental aspect, including quantifying the measurable targets. While the impacts and management & mitigations have been addressed under the various project development phases, they are not intended to be mutually exclusive, and impacts from one phase are likely to occur in subsequent phases; but in the interest of reducing redundancy they have not been repeated for each phase.

TABLE 6. COMPLIANCE MANAGEMENT.

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------------|---|---|--|--|---|--|--|
| 6.1 | All Phases with special emphasis on Planning & Design Phase (including Pre-Construction) | | | | | | |
| 6.1.1 | PROTECTED SPECIES | | | | | | |
| 6.1.1.1 | Impacts on protected plants. Appointed Ecologist identified <i>Sclerocarya birrea</i> (Marula) at Ch 1000. | Comply with the relevant sections of the National Forest Act (NFA) (Act 84 of 1984), the National Environmental Management: Biodiversity Act, 2004 (NEM:BA) (Act No. 10 of 2004) and North West Biodiversity Management Act (NWBMA, Act 4 of 2016), | Obtain and provide proof of issuance of necessary permits for any listed species under NFA, NEMBA and NWBMA (if relevant). | The applicant shall apply for and obtain the relevant licenses / permits from the appropriate authorities (DAFF, DEA, and Provincial Authority) prior to disturbing or destroying any protected species. | Applicant / Contractor to appoint botanist. | Prior to commencement of construction. | Compliance to be verified by SEO, ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------------|---|--|--|---|-------------------------|--|---|
| | | Provincial Gazette no. 7721, Provincial Notice 3, 3 January 2017, as amended (not in force at time of report). | | | | | |
| 6.1.2 | WATER USE AUTHORISATION FOR TREATED EFFLUENT | | | | | | |
| 6.1.2.1 | Contravention of section 21 (f) & (g) of the NWA. | The commencement of water uses that are authorised in terms of the NWA, 1998 (Act No. 36 of 1998). | Issuance of a Water Use License. | The applicant shall apply for a water use entitlement, i.e. a WUL for section 21 (f) & (g) water uses for the discharge and disposal of the effluent. | Applicant / EAP. | Prior to commencement of construction. | Compliance to be verified by ECO & IEA. |
| 6.1.3 | WATER USE AUTHORISATION FOR ABSTRACTION | | | | | | |
| 6.1.3.1 | Contravention of section 21 (a) of the NWA. | Utilisation of surface water within volume stipulated in the Water Use License. | Records demonstrating abstraction volumes in compliance with WUL limits. | Abstraction must not exceed the limits prescribed in the WUL, factoring in the amount abstracted by the Bospoort WTW. | Applicant / Contractor. | Applicant. | Compliance to be verified by ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------------|--|--|---|--|------------------|---|---|
| 6.1.4 | WATER USE AUTHORISATION FOR PIPELINE CROSSINGS | | | | | | |
| 6.1.4.1 | Contravention of section 21 (c) & (i) of the NWA. | The commencement of water uses that are authorised in terms of the NWA, 1998 (Act No. 36 of 1998). | Issuance of a Water Use License. | The applicant shall apply for a water use entitlement, i.e. a WUL for section 21 (c) & (i) water uses for impeding or diverting the flow of water & altering the bed, banks, course or characteristics of a watercourse | Applicant / EAP. | Prior to commencement of construction. | Compliance to be verified by ECO & IEA. |
| 6.1.5 | Compliance Monitoring | | | | | | |
| 6.1.5.1 | Commencement of construction prior to the appointment of an ECO. | Monitor compliance with the EMPr from the onset of construction and until the rehabilitated development is handed over to the Applicant for operation. | Proof of ECO appointment prior to commencement of construction. | A qualified, suitably experienced & accredited independent ECO must be appointed (registered with SACNASP & EAPASA (if applicable)) to monitor and report to the competent authority on compliance with the EA and EMPr, and where necessary oversee or facilitate the identification and permitting / licensing of protected species prior to clearing of any vegetation. | Applicant. | Prior to commencement of construction and until the rehabilitated development is handed over to the applicant for operation. The minimum frequency for ECO inspections is monthly, unless specified | To be verified by IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------------|--|---|--|---|----------------|---|--|
| | | | | | | otherwise in the Environmental Authorisation. | |
| 6.1.5.2 | Ignorance of duty of care and remediation of environmental damage in accordance with Section 28 of the National Environmental Management Act, 1998 | Ensure compliance with Section 28 of the National Environmental Management Act, 1998 (Act No. 107 of 1998), as amended. | Records demonstrating when the incident occurred and how it was remediated. | The applicant must be responsible for compliance with the provisions for duty of care and remediation of environmental damage in accordance with Section 28 of the National Environmental Management Act, 1998 (Act No. 107 of 1998), as amended. | Applicant | As and when the incident occurs. | Compliance to be verified by SEO, ECO & IEA |
| 6.1.6 | Municipal By-laws | | | | | | |
| 6.1.6.1 | Commencement of construction prior to submission and approval of building plans by the Rustenburg Local Municipality. | Local municipality approval of building plans. | Issuance of a certificate referred to in section 118(1) of the Local Government Systems Act (Act 32 of | The plans and specifications for any building, whether of a temporary or permanent nature, to be erected on the land must be submitted to the Rustenburg Local Municipality for approval in terms of the Local Government: Municipal | Applicant. | Prior to commencement of construction. | Compliance to be verified by SEO, ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|-------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | 2000). | Systems Act, 2000 (Act No. 32 of 2000). | | | |

TABLE 7. CONSTRUCTION CAMP, LAYDOWN AREAS, STOCKPILES, STORES & EQUIPMENT.

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|---|--|---|--|------------------------|--|------------|
| 7.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 7.1.1 | Land surface pollution. | Reduce risk of pollution or harm to sensitive environments from the inappropriate location of construction related sites within or within proximity to those sensitive environments. | Approved and effectively implemented layout plan indicating designated construction-related sites, servitude (temporary & permanent) and location of sensitive areas. | <p>A construction site layout plan must be developed by the contractor and approved by the SEO / ECO to ensure that all construction related sites are located outside sensitive environments, including no-go areas and buffer zones.</p> <p>Furthermore, those construction related sites or activities with the greater risk or potential for causing pollution or harm to the receiving environment, including but not necessarily limited to laydown areas, material stockpiles, toilets, waste skips and stores, must not be within close proximity to the aforesaid sensitive environments, i.e. these construction related sites</p> | Applicant / Contractor | Prior to commencement of construction. | ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|--|--|---|---|------------------------|---|------------|
| | | | | or activities must not, as far as is practical, be located on the watercourse-side of any construction camp or area demarcated for construction activities. | | | |
| 7.1.2 | Degradation of the environment outside of the development footprint. | Zero construction creep into and subsequent degradation of areas outside the preferred or approved development footprints. | Approved and effectively implemented (demarcated on site) layout plan indicating all environmental sensitivities, especially no-go areas. | <p>Permanent and temporary construction footprints must be designated, and sensitive terrestrial & aquatic habitats demarcated as no-go areas during construction, including required buffer zones.</p> <p>The project footprint must be clearly demarcated on the ground to ensure that no construction creep results toward any watercourses or defined sensitive areas.</p> <p>Placement of infrastructure and laydown & stockpile areas must be</p> | Applicant / Contractor | Prior to and ongoing enforcement during construction. | ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|---------------------------|---|--|---|------------------------|--------------------------|------------|
| | | | | done so as not to negatively affect surface water runoff in a way that leads to erosion and export of material to be deposited in any watercourses. | | | |
| 7.2 | Construction Phase | | | | | | |
| 7.2.1 | Land contamination. | To avoid and reduce anthropogenically induced environmental pollution. To ensure compliance with Rustenburg Municipality Bylaws. | Incident registers that indicate pollution events, from the operation of construction plant, equipment or other vehicles, over time. Compliance with section 24 of fire brigade services by laws no. 2 of 2015 published in terms of Section 12 and | Emergency breakdowns must be addressed with immediate and adequate pollution containment measures including but not limited to drip trays and spill kits. No washing of plant and equipment within the construction camp, and no repairs or servicing of construction plant, equipment or other vehicles, except for emergency breakdowns, are permitted within the preferred or approved development footprint, construction-related areas, no-go areas and on neighbouring properties. | Applicant / Contractor | Throughout construction. | ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|-------------------|------------------|---|--|----------------|-----------------------|------------|
| | | | 13 of the Local Government: Municipal System Act, 2000 (Act 32 of 2000) as amended. | <p>The contractor(s) and any sub-contractors, including their employees, are prohibited from entering the designated no-go areas for whatever reason and without the prior written consent of the SEO.</p> <p>Refuelling of vehicles and plant may only take place at a designated and permitted (from local Fire Chief) fuel storage tank or mobile fuel bowser, under the guidance of a Specific Operating Procedure (SOP) that limits spillage and addresses remedial actions in the event of a spillage.</p> <p>The contractor shall restrict the following activities to the construction camp:</p> <ul style="list-style-type: none"> - Bulk waste storage, | | | |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|-------------------|------------------|----------------------|---|----------------|-----------------------|------------|
| | | | | <ul style="list-style-type: none"> - Parking, - Storing hazardous materials, - Emergency vehicle & plant repair & maintenance as far as practicable, - Designated concrete mixing area - Material stockpiles, and - Lay down areas. <p>Use chemical toilets that contain the sewerage in a closed and removable 'tank', i.e. do not use open drums. Environmentally friendly toilets should also be considered e.g. E-loos. Toilets must track the construction front.</p> <p>Use drip trays for refuelling, emergency repair / maintenance work and all stationary construction plant and equipment that can leak, such as TLBs,</p> | | | |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|-------------------|---|---|---|-------------------------|---|---|
| | | | | compressors and generators. Washing of equipment including brushes shall not occur on site or in a watercourse but shall be restricted to the main construction camp where adequate containment measures are in place. | | | |
| 7.2.2 | Noise pollution. | To avoid nuisance noise to affected landowners & occupiers and reduce noise impacts to the environment and implement active monitoring in the event of noise-related complaints received. | Noise must fall within the parameters set by: 1.(SANS) Standard 10103:2008: The measurement and rating of environmental noise with respect to annoyance and | Noise generation must be managed, including the use of radios and other music playing appliances. Vehicles and plant must be in a good state of repair to limit noisy operations. | Applicant / Contractor. | Frequency of monitoring as stipulated in relevant regulation and standard, as amended from time to time following any noise-related complaints. | SEO or appointed specialist service provider. Verification to be done by ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|--|---|---|---|-------------------------|---|------------|
| | | | speech communication. 2.DEA Regulations No. R.154. Noise Control Regulations promulgated in terms of Section 25 of the Environment Conservation Act, 1989 (Act No. 73 of 1989). GG No. 13717, 10 January 1992. | | | | |
| 7.2.3 | Degradation of the environment outside of the development footprint. | To avoid impacts to the biodiversity integrity and ecological function of areas outside the | No impacts outside the development footprint. All contraventions to be recorded in | No residues of stockpiled material must be left on site, that can impede restoration of ecological function and remain a visual intrusion on the landscape. | Applicant / Contractor. | Update to incident register following each contravention. | ECO & IEA. |

| No. | Potential Impacts | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|-------------------|------------------------|----------------------|---|----------------|-----------------------|------------|
| | | development footprint. | incident register. | <p>Disturbed habitats resulting from construction-related activities must be rehabilitated immediately after the cessation of those activities on or near the disturbed habitats.</p> <p>The alignment of fences or roads and the placement of potential impediments, such as walls, laydown & material stockpile areas must not alter surface water runoff patterns (i.e. impede or increase surface water runoff) in a way that will cause ponding or erosion and sedimentation of a watercourse.</p> | | | |

TABLE 8. WASTE MANAGEMENT (generation, handling, storage and disposal, including hazardous waste).

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|---|---|---|--|-------------------------------|---|------------|
| 8.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 8.1.1 | Shortening the lifespan of the local waste disposal sites. | To minimise the generation of project-specific waste by implementing an effective waste management strategy based on the waste hierarchy. | Keep accurate records of waste volumes (litres, kg and / or m ³) generated by type. | <p>Establish and implement an Integrated Waste Management Strategy including avoidance, reduction, re-using, recycling and disposal, i.e. the production of hazardous waste can be avoided by providing drip trays, reduce waste by using the correct quantities, re-use concrete rubble as back fill or recycle steel off-cuts and dispose of non-hazardous solid waste at a registered municipal dump site.</p> <p>Induct all labourers on the waste management strategy and enforce it through regular (at least</p> | Applicant / Contractor (SEO). | Prior to commencement of construction with ongoing maintenance and updates to Strategy. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|---|----------------|-----------------------|------------|
| | | | | <p>weekly) toolbox talks.</p> <p>Keep accurate records of waste generated by type.</p> <p>All hazardous and solid waste must be removed to a licensed waste disposal site for the type of waste produced. No solid waste may be disposed of on site. The storage of solid waste on site, until such time as it may be disposed of, must be in a manner acceptable to the Local Authority and the Department of Water and Sanitation (DWS) or the Department of Environmental Affairs (DEA).</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|--|--|--|--|-------------------------------|--------------------------|------------|
| | | | | | | | |
| 8.2 | Construction Phase | | | | | | |
| 8.2.1 | Removal of inert waste and rubble. Loss of ecological function and agricultural potential. | Maintain ecological function and agricultural potential. | Zero concrete hard pan layers observed on the ground. All waste waybills & certificates of safe disposal and landfill licenses in register and on file. | In the event of concrete hard pan layers, break up all concrete hard pan layers and dispose of appropriately (at a registered landfill site) or re-use the concrete in legitimate construction works. | Applicant / Contractor (SEO). | For each disposal event. | ECO & IEA. |
| 8.2.2 | The high economic cost of disposing hazardous waste at authorised landfills, and potential contamination of land by illegal dumping. | The reduced generation of hazardous waste and the avoidance of environmental (land and water) contamination. | Indicators and trends in hazardous waste generation and management over time while considering amount of active construction to contextualise | The contractor shall contain contaminated water from washing brushes and other tools as well as the dirty water (possibly hazardous) in a conservancy tank until sufficient volume warrants disposal by a registered hazardous waste | Applicant / Contractor (SEO). | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|---|--|---|---|-------------------------------|--------------------------|------------|
| | | | efforts. All waste waybills & certificates of safe disposal and landfill licenses in register and on file. | management company. The contractor shall return used oil to the supplier or an oil recycling company. | | | |
| 8.2.3 | Solid and liquid waste can be harmful to fauna if swallowed / ingested or if the creature becomes entangled or impaled. | Healthy animals (wild and domesticated). | Zero incidence (in the incident register) of waste induced harm to wildlife or livestock. No litter observed in the development footprint and no-go areas. | Designate a temporary bulk waste storage area, ensure it is "predator-proof", and provide sufficient scavenger proof dust bins during construction. Provision must be made for the adequate storage of used and contaminated substances such as oil, lubricants and other petroleum products during the construction and operational phases of the | Applicant / Contractor (SEO). | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|---|---|--|--|-------------------------------|--------------------------|------------|
| | | | | <p>development. The substances must be stored in such a way that it would not pose threat to the environment.</p> <p>Do not litter and ensure sound housekeeping.</p> | | | |
| 8.2.4 | Improper handling, storage or disposal of waste can cause toxicity – the introduction of toxic or hazardous substances into a watercourse - spills can be washed into the watercourse by storm water run-off. | To ensure sound waste management practices that do not affect any aquatic environments. | Zero incidence (in the incidence register) of waste induced impacts on aquatic environments. | <p>Hard-surfaces and parking areas with storm water outlets should not channel litter, oil and fuel spills into a watercourse, causing water pollution.</p> <p>The contractor is prohibited from discharging untreated waste water, including domestic water from sanitation facilities, into a watercourse.</p> <p>The contractor shall store & contain hazardous</p> | Applicant / Contractor (SEO). | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|---|---|---|---|-------------------------------|--------------------------|------------|
| | | | | chemicals within a secure, safe and adequately bunded facility at the construction camp, to ensure spillages do not enter any aquatic environments. | | | |
| 8.2.5 | Construction activities will produce solid and liquid waste, which can contaminate the ground (litter, spillage) if improperly handled, stored or disposed. | To reduce contamination of the soil through improper management of waste. | Low incidence of waste induced ground contamination, with a trend indicating constant improvement over time (not just quantities but procedural improvements too). Suitable close-out documentation and reviews of SOPs & MS | Do not mix concrete on open ground. Mix in a wheel barrow, a mixing tray or on a concavely shaped and supported liner. In the event of a leak or spill onto the ground, immediately remove contaminated soil to the depth of penetration and temporarily store in a designated solid waste container until sufficient volume warrants disposal at a registered waste site. | Applicant / Contractor (SEO). | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|---|---|----------------|-----------------------|------------|
| | | | following significant contamination events. | <p>Alternatively, onsite treatment of contaminated soil should be considered to be facilitated by a registered hazardous waste management company.</p> <p>The burning, burying or illegal dumping of waste is prohibited.</p> <p>When handling hazardous materials, such as when refuelling vehicles or generators, the contractor shall implement appropriate precautionary measures, such as a ground cover or drip trays, to prevent spills from contaminating the ground.</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|---|----------------|-----------------------|------------|
| | | | | <p>The contractor shall prevent the run-off of slurry or cement contaminated water from concrete / plaster mixing sites.</p> <p>Adequate waste receptacles must be available, including those that track with the active work fronts, to ensure effective waste management.</p> <p>Remove ineffective danger tape / netting that has begun to litter the site or surrounding areas.</p> <p>Follow housekeeping rules to avoid littering (littering is</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|----------------------------|---|---|---|---|--------------------------|------------|
| | | | | likely to be more prevalent at designated eating / rest areas). | | | |
| 8.2.6 | The contamination of soil. | To reduce the amount of hazardous waste, specifically contaminated soil, that is generated during construction. | <p>Sound management & disposal of contents of drip trays and / or utilisation of alternative hydrocarbon absorbents in drip trays.</p> <p>Zero sand observed in drip trays and bunds.</p> <p>Zero spills or leaks observed under or near stationary construction plant and equipment.</p> | <p>Use drip trays for refuelling, emergency repair work and all stationary construction plant and equipment that can leak, such as TLBs, compressors and generators.</p> <p>Drip trays must be regularly emptied, or they can be filled with hydrophobic hydrocarbon absorbent material to avoid the content from overflowing during rainfall events.</p> | Applicant / Contractor (SEO & Plant Operators). | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|--|---|---|---|-------------------------|--------------------------|------------|
| 8.2.7 | The contamination of soil (and generation of waste) by undesirable practices. | To reduce the amount of hazardous waste, specifically contaminated soil, that is generated during construction. | Zero observations of spills covered with soil. | Do not cover spills with virgin soil. It merely increases the disposal cost for a greater volume of hazardous waste. Utilise as an alternative, hydrocarbon absorbents, for spillages. | Applicant / Contractor. | Throughout construction. | ECO & IEA. |
| 8.2.8 | Illegal dumping will result in the loss of certain land uses like agriculture and conservation and remove natural habitat. | Continued self-sustainability of the site's ecological and agricultural integrity. | Waybills and/or safe disposal certificates from the service provider. No evidence of illegal dumping of project-specific waste within the development footprint, no-go areas or neighbouring | The contractor shall dispose of general waste, that cannot be recycled, at a registered municipal landfill site. All waste to be removed to a suitable waste disposal facility by a registered service provider, where relevant. | Applicant / Operator. | Throughout operation, | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|--|--|--|--|-----------------------|---------------------------|------------|
| | | | properties. | | | | |
| 8.3 | Operational Phase | | | | | | |
| 8.3.1 | Solid waste can be blown away and into the landscape. | A pristine environment, devoid of wind-blown litter. | No litter or other open sources of project generated waste observed within the fenced premises. | The site will be kept tidy always. All waste shall be picked up daily. Maintain good housekeeping tendencies. | Applicant / Operator. | Throughout operation. | IEA. |
| 8.4 | Decommissioning Phase | | | | | | |
| 8.4.1 | The generation of potentially harmful waste that has the potential of contaminating the environment if not disposed at a licensed landfill or, if disposed at an appropriate landfill, reduces the capacity and lifespan of that site. | To minimize waste and ensure suitable disposal at the end of project life. | No evidence of residual structures relating to the project, unless specifically retained at landowner's request. | Properly dispose of all waste & residual structures. | Applicant. | At decommissioning phase. | IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|---|---|---|---|----------------|---------------------------|------------|
| 8.4.2 | Illegal dumping sites cannot retain the ecological functions and land use required to generate ecosystem goods and services and tangible economic benefits including income from conservation or farming. | To ensure that no illegal waste dumps are left in situ following decommissioning. | Restoration of the footprint to a functional ecological and agricultural state. | The illegal dumping or disposal of waste generated from the decommissioning of the pipeline & reservoir within the development footprint, no-go areas or on adjacent properties is strictly prohibited. | Applicant. | At decommissioning phase. | IEA. |

TABLE 9. FAUNA & FLORA MANAGEMENT.

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|--|--|---|--|-------------------------|---------------------------------|-----------------|
| 9.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 9.1.1 | The construction of new service tracks can destroy plants of conservation concern. | To reduce the impacts of roads on fauna & flora. | The successful relocation of plants of conservation concern into suitable habitats. | Prior to the construction of any new roads, a search & rescue must be conducted by a suitably qualified specialist for protected fauna & flora and that of conservation concern; which must then be transplanted outside the works area in a comparative habitat type. Ascertaining similar habitat types may require soil sampling and analysis over and above above-ground similarities. | Applicant / Contractor. | Prior to & during construction. | SEO, ECO & IEA. |
| 9.2 | Construction Phase | | | | | | |
| 9.2.1 | Increased risk of alien plant invasion to the detriment of the local ecology and agricultural potential. | To effectively control the invasion of any alien plants. | No new alien plant recruitment (directly or indirectly resulting from construction | Alien invasive vegetation recruitment must be controlled within and along the construction footprint and fence lines. Manual control measures are preferred, but where herbicides are used | Applicant / Contractor. | Throughout construction. | SEO, ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|--|--|----------------|-----------------------|------------|
| | | | activities) within the development footprint and neighbouring no-go areas or properties. | <p>they must be those endorsed & selective for the target species with the lowest environmental toxicity.</p> <p>Applicant shall collect and destroy all seeds of weed, invader and alien plant species occurring within disturbed and /or rehabilitated areas.</p> <p>Applicant shall immediately uproot, cut or debark weed, invader and alien plant species upon being identified.</p> <p>Areas disturbed during construction shall be monitored for the recruitment of weed, invader and alien</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|---|---|---|---|---|-----------------------|-----------------|
| | | | | <p>plant species and controlled immediately upon being found to occur.</p> <p>Recruitment of alien and invasive plants must be controlled to ensure they do not seed and propagate (both declared weeds and those that are outside of their natural distribution).</p> | | | |
| 9.2.2 | Construction activities (i.e. clearing and grading) have the potential to directly impact, that is damage / injure and destroy / kill, local fauna and flora. (The impacts are exacerbated when the species | To reduce in situ losses of protected and conservation important flora & fauna. | Spatially explicit "Search & Rescue" register indicating the nature & position of all translocated flora & fauna. | <p>A search and rescue must be undertaken of all footprints that will be temporarily or permanently affected during construction of the development footprint.</p> <p>All fauna and flora that are protected or of conservation importance must either be cordoned off and protected or translocated outside of the</p> | Applicant / Contractor. All search & rescue & translocation activities must be carried out by suitably qualified specialists. | Pre-Construction. | SEO, ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------|---|--|---|---|-------------------------|--------------------------------------|------------|
| | affected are classified as protected, sensitive, rare, or threatened and endangered). | | | <p>site establishment and pipeline and reservoir footprint, into habitats of a similar nature.</p> <p>Avoid direct contact with fauna, through clearing and grading as it can cause injury or death.</p> | | | |
| 9.2.3 | <p>Harvesting of:</p> <ul style="list-style-type: none"> - indigenous plants for muthi; - firewood; and - poaching of animals. | To ensure no harvesting of natural resources within and adjacent to the development footprint. | <p>Zero incidence of harvesting.</p> <p>All incidences recorded in the incident register including close-out actions.</p> <p>Compliance with the North West Biodiversity Management Act (NWBMA, Act 4 of 2016),</p> | <p>The harvesting or collection of any natural product(s) from the environment is strictly forbidden.</p> <p>Do not poach or hunt animals within development footprint, no-go areas and neighbouring properties.</p> <p>“Problem” animals must be handled with assistance from the provincial conservation authority.</p> | Applicant / Contractor. | Throughout construction & operation. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|------------|---|---|--|---|------------------------|---|------------|
| | | | Provincial Gazette no. 7721, Provincial Notice 3, 3 January 2017, as amended (not in force at time of report). | Except for search and rescue operations authorized by the ECO and the Provincial Conservation Authority, no mammal, bird, reptile, invertebrate or fish shall be intentionally caught, hunted or poached, within the development footprint and no-go areas. | | | |
| 9.4 | Decommissioning Phase | | | | | | |
| 9.4.1 | Impacts on biological functioning and productivity of vegetation. | To ensure restoration of ecological function following decommissioning. | No degraded areas within the decommissioned footprint. | Reinstate ecological function by recreating an open system by removing all project related fencing. | Applicant / Landowner. | At completion of decommissioning activities | IEA. |
| 9.4.2 | Alien Plant Invasion Risk. | To ensure no residual alien plants at cessation of operations. | Zero incidence of alien plants within the decommissioned footprint. | The rehabilitated servitudes shall be monitored following the completion of decommissioning of the pipeline and reservoir footprints for the recruitment | Applicant / Landowner. | At completion of decommissioning activities, within the growth season, as well as the following | IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|--|----------------|--|------------|
| | | | | and subsequent control of weed, invader and alien plant species. | | growth season following decommissioning. | |

TABLE 10. WATER USE & MANAGEMENT (INCLUDING WATERCOURSES).

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--|--|---|---|-------------------------------------|--|------------------|
| 10.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 10.1.1 | Decrease in water quality of watercourses. | To minimise the risk of impacts to water resources in and around the project footprint. | No high-risk activities located within close proximity to water resources. | Avoid placing high risk (pollution generating) activities within close proximity to a watercourse as they can cause water pollution. | Applicant / Contractor. | During site establishment & throughout construction. | SECO, ECO & IEA. |
| 10.1.2 | Uncontrolled and unsustainable abstraction from a watercourse or aquifer (borehole) and depletion of already constrained groundwater resource. | Utilisation of surface water within the allocation stipulated in the Water Use License for the Bospoort WTW. | Implementation of a register recording abstraction volumes. Provision of adequate storage of water allowing for abstraction rates within Water Use License conditions. | Abstraction volumes must comply to the conditions of the Water Use License. Adequate storage of water must be provided, to allow for suitable abstraction rates that will not exceed the rate stipulated in the WUL throughout the construction process. Water meters must be | Applicant / Contractor / Land owner | Prior to and monthly throughout construction. | SECO, ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--|--|--|---|-------------------------|--------------------------|------------------|
| | | | | installed on all abstraction pipelines/equipment to ensure that utilisation rates are measured and monitored and do not exceed the permissible limits. | | | |
| 10.2 | Construction Phase | | | | | | |
| 10.2.1 | Excessive abstraction from a watercourse or aquifer. | To reduce water usage for construction activities. | Evidence of dust control additives used to minimise water usage for dust suppression activities, including completed logbooks and no evidence of over wetting, i.e. erosion or pools of water (puddles). | An environmentally friendly water-soluble dust control additive / binder must be added as an additive to any water used for dust suppression. The additives generally assist with surface stabilization thereby significantly reducing water usage. | Applicant / Contractor. | Throughout construction. | SECO, ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|---|---|---|---|-------------------------|--------------------------|------------------|
| | | | | <p>All water bowsters must maintain logbooks in which quantities used for construction and dust suppression are recorded.</p> <p>Water bowsters implementing dust suppression, must determine optimal rates of application to ensure over-wetting does not occur.</p> | | | |
| 10.2.2 | Decrease in water quality of water resources. | To minimise the risk of water contamination and activities that impact negatively on water quality. | All high-risk activities to be located at least 35m away (specified buffer zone) from any water resource (surface or ground). | <p>Chemical toilets shall be in the shade, at least 35m from any watercourse.</p> <p>Re-fuelling with a mobile fuel bowser shall take place outside any watercourse.</p> | Applicant / Contractor. | Throughout construction. | SECO, ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|---|---|--|---|-----------------------|-----------------------|------------|
| 10.3 | Operational Phase | | | | | | |
| 10.3.1 | Impediments to surface water runoff. | To retain as far as possible surface water hydrology. | Limited signs of erosion along or resulting from the fence line. | Fence lines must be regularly cleared of accumulating debris (accumulating debris does not refer to living plants, otherwise the removal of plants will cause more erosion), to allow surface water to flow uninhibited across the development footprint. | Applicant / Operator. | Throughout operation. | IEA. |
| 10.3.2 | The excessive and / or wasteful use of water has the potential to reduce the ecological reserve required for sustaining the local ecosystem.' | To use water in a manner that is ecologically sustainable and not wasteful. | No drips, leaks or other evidence of wasteful water use. | Water leaks shall be repaired immediately upon being found. Water-saving showerheads shall be used, where relevant. Consider placing a cistern displacement device in the toilet | Applicant / Operator. | Throughout operation. | IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|---|---|---|--|-----------------------|-----------------------|------------|
| | | | | <p>cistern.</p> <p>Educate employees on the importance and practices of water efficiency.</p> <p>If practical, consider harvesting rainwater from drainpipes.</p> <p>Use an aerator and / or a water flow-reducing spout on the taps and shower heads.</p> | | | |
| 10.3.3 | Poor water quality can be a health risk or harmful to humans. | To ensure safe potable water for employees. | Compliance of potable water to SANS 241 standard. | Water used for potable (drinking) purposes must be tested to ensure compliance with the minimum standards. Should elements of the water not comply, the water must be treated to ensure no acute or | Applicant / Operator. | Quarterly. | IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | | chronic health risks. | | | |

TABLE 11. AIR QUALITY MANAGEMENT.

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|---|--|---|---|--|-------------------------|-------------------------------|--|
| 11.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| No pre-construction impacts associated with this phase. | | | | | | | |
| 11.2 | Construction Phase | | | | | | |
| 11.2.1 | Old and poorly maintained vehicles cause the most air pollution from cars, specifically GHG emissions that are released to the atmosphere, contributing to global warming and acid rain. | To reduce the level of car or other combustion-related pollutants entering the atmosphere (by keeping well-maintained plant and equipment). | Evidence of servicing at required intervals. No visible evidence of excessive emissions. | Construction plant and equipment shall be kept in a good state of repair to reduce combustion-related emissions. | Applicant / Contractor. | During construction. | Plant Manager, SEO, ECO & IEA. |
| 11.2.2 | Negative effects on floral photosynthetic functioning and potential increase in breathing ailments of site staff, surrounding landowners, communities and | To manage dust entrainment on access roads which may not exceed the thresholds stipulated in the National Dust Control | Full compliance with National Dust Regulations. Acceptable Dust fallout rate | Effective implementation of the National Dust Control Regulations. Excessive vehicle movement, and the transport and off-loading of dispersive materials shall be avoided during windy conditions, unless additional dust suppression | Applicant / Contractor. | During construction, monthly. | Following complaints and / or obvious signs of significant dust fallout. Monitoring of dust fallout to be undertaken |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|--|--|--|--|-------------------------|--|--|
| | fauna. | Regulations. | (mg/m ² /day): Residential area < 600 Non-residential area < 1200 Exceedance not more than twice in a year, not sequential months. | methods will ensure that the dust fallout does not exceed the acceptable limits. The contractor is to take into consideration predicted wind speeds from the local weather station when planning construction-related activities with a high risk of generating dust. Dust suppressant must be prioritised for any drilling activities. | | | by a professional service provider and compliance to be verified by ECO & IEA. |
| 11.2.3 | Safety risks and road accidents due to reduced visibility. | To reduce vehicular accidents due to poor dust-induced visibility. | Full compliance with National Dust Regulations. | Dust suppression must be carried out on access roads where high dust entrainment is evident. Dust generated by construction activities must be minimized by dust suppression techniques such as the use of water sprinklers. | Applicant / Contractor. | During construction. Dust fallout evaluation monthly and dust suppression as conditions dictate. | Following complaints and / or obvious signs of significant dust fallout affecting visibility of traffic. Monitoring of dust fallout to |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--------------------------|---|---|---|-------------------------|---|--|
| | | | | | | | be undertaken by a professional service provider and compliance to be verified by ECO & IEA. |
| 11.2.4 | Unpleasant odours. | To reduce unpleasant odours often associated with ablution facilities. | Records of regular servicing, and daily cleaning log. | Chemical toilets shall be kept hygienic and cleaned daily to avoid unpleasant odours. | Applicant / Contractor. | During construction. | SEO, HSO, ECO & IEA. |
| 11.3 | Operational Phase | | | | | | |
| 11.3.1 | Decrease in air quality. | To manage dust entrainment on access roads which may not exceed the thresholds stipulated in the National Dust Control Regulations. | Full compliance with National Dust Regulations. | Effective implementation of Dust Control Regulations. Dust suppression must be carried out on access roads to minimise operational dust emissions. | Applicant / Operator. | As required to minimise dust emissions. | IEA. |

TABLE 12. SOIL MANAGEMENT.

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|------------------------------------|---|---|---|-------------------------------|--|------------|
| 12.1 | Planning & Design Phase | | | | | | |
| 12.1.1 | Loss of valuable topsoil. | To minimise disturbance & contamination of topsoil. | Compliance with site layout plans. | Clearing, and the location of topsoil stockpiles and / or windrows, shall take place in pre-authorised and clearly defined areas only. | Applicant / Contractor. | Prior to and during construction. | ECO & IEA. |
| 12.2 | Construction Phase | | | | | | |
| 12.2.1 | Decline in soil organisms. | To maintain the biological integrity of disturbed soil. | The list of plant species, and their relative abundancies, chosen for rehabilitation reflects the natural plant communities that need to be rehabilitated.' | Re-seed disturbed areas after construction with grass seeds of the naturally occurring plant species to encourage soil invertebrate species richness. | Applicant / Contractor (SEO). | Following construction or construction induced disturbance. | ECO & IEA. |
| 12.2.2 | Loss of valuable topsoil. | To retain all disturbed and cleared topsoil. | Comparative quantification of cleared and reinstated topsoil | Any topsoil removed during the establishment of parking areas, temporary roads, or any other cleared areas, must be protected from vehicular and construction | Applicant / Contractor (SEO). | During initial clearing and prior to reinstatement of topsoil. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|--------------------------------------|---|--|---|-------------------------------|--------------------------|------------|
| | | | volumes. | impacts. Do not mix topsoil with cement and / or subsoil or let it be pulverised by trucks. | | | |
| 12.2.3 | Potential sterilisation of the soil. | To maintain soil viability. | Use of only selective, environmentally friendly herbicides. | Where possible, refrain from using non-selective herbicides to control vegetation, depending on the active ingredient, it can sterilise the soil. Application of herbicides may only be applied by or under the supervision of a Certified Pest Control Officer as stipulated by the Fertilizers, Farm Feeds, Agricultural Remedies and Stock Remedies Act (Act No. 36 of 1947). | Applicant / Contractor (SEO). | Every treatment episode. | ECO & IEA. |
| 12.2.4 | Soil contamination. | To reduce and avoid soil contamination. | No evidence of contaminating activities on unprotected ground, or in | Construction plant and equipment shall be kept in a good state of repair to reduce hydrocarbon leakages. | Applicant / Contractor (SEO). | During construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|--------------------------------------|--------------------------------|--|--|------------------------|-----------------------|------------|
| | | | the case of accidental spills, documented evidence of rapid remediation. | <p>Immediately remove contaminated soil to the depth of penetration and temporarily store in a designated solid (separate hazardous) waste container until sufficient volume warrants disposal at a registered (separate hazardous) waste dump site. Alternatively, onsite treatment of contaminated soil should be considered with and / or in consultation with a registered hazardous waste management company.</p> <p>Soil horizons must be stockpiled or windrowed separately during excavation to ensure they can be reinstated in reverse order and ensure restored soil structure.</p> | | | |
| 12.2.5 | Soil erosion, soil loss & associated | To reduce erosion induced soil | To record all areas prone | Areas disturbed and rehabilitated during construction shall be | Applicant / Contractor | During construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|----------------------------|---|---|---|----------------|-----------------------|------------|
| | degradation of ecosystems. | losses and consequential ecosystem degradation. | and affected by erosion and implement suitable pre-emptive and remedial measures. | <p>monitored for signs of erosion and if found to occur, immediately corrected ('source') and repaired ('symptom').</p> <p>Bulk shape the areas where material is introduced to mimic or blend in with the surrounding, natural topography. Do not fine shape or rake because an uneven surface will impede surface water run-off and facilitate infiltration.</p> <p>Correct any cause of erosion at the onset thereof by controlling / diverting storm water run-off, immediately repairing and stabilizing / rehabilitating impacted areas in the most appropriate manner.</p> <p>Ensure a quick and adequate cover with indigenous and local grass species.</p> | (SEO). | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | | <p>Ensure storm water run-off is adequately controlled on disturbed sites before rehabilitating them (ripping, replacing the topsoil and mulching/brush packing), i.e. cut-off berms.</p> <p>Grading of existing farm roads must not be promoted, but farm tracks must be utilised as far as possible.</p> <p>Sediment traps may be necessary to prevent erosion and soil movement if there are topsoil or subsoil stockpiles or windrows present during the wet season.</p> <p>The Contractor shall monitor the rehabilitated servitudes for the duration of the contract defects and liability period for signs of</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | | erosion. | | | |

TABLE 13. SOCIAL-ECONOMIC MANAGEMENT (HEALTH, SAFETY & SECURITY & COMMUNICATION).

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--|--|--|--|--|---|------------|
| 13.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 13.1.1 | Concerns about social disturbance and community safety (including loitering at construction site). | To reduce human induced impacts and nuisance factors. | No complaints from affected parties in the on-site complaints register. Where complaints are lodged effective and timeous close-out must be demonstrated. | Adequate accommodation and transport must be provided for all staff to reduce impact on the property owner and adjacent farms as well as relieving pressure off road networks. A complaints register must be maintained and be accessible on site, in which complaints linked directly to the project can be lodged, and addressed in a proactive manner. | Applicant / Contractor (via CLO and SO). | Prior to and during construction and operation. | ECO & IEA |
| 13.1.2 | Community confusion, frustration & lack of information. | To avoid creating false hope where job creation opportunities are concerned. | Development of an effective job seeker database. | Implementation of a community relations strategy until all activities on site cease and rehabilitation is completed. Develop a job seeker database or integrate with an existing service provider in the adjacent towns, to | Applicant / Contractor / Operator | Prior to and during construction and operation. | ECO & IEA |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--|---------------------------------------|--|---|------------------------------------|--|------------|
| | | | | ensure job seekers' details are captured. As positions become available, this database can be searched for suitable skills within the local populous before positions are outsourced. These measures will reduce the potential nuisance factor to the land owner, caused by job seekers reverting to visiting the proposed site of development. | | | |
| 13.2 | Construction & Operation Phase | | | | | | |
| 13.2.1 | Increase in crime including damage to property infrastructure and vandalism. | Reduce impacts associated with crime. | No perpetuating criminal activity. Improvements to security must be demonstrated following an incident. | Adequate security measures must be in place throughout construction & operation phases to discourage criminal elements from site. | Applicant / Contractor / Operator. | At commencement of construction, especially site establishment and during operation. | ECO & IEA. |
| 13.2.2 | Potential social pathologies (social | Reduce impacts associated with | No strike & community | Ensure effective communication and engagement with staff and | Applicant / Contractor / | At commencement | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|---|---|--|---|--|--|---|
| | unrest). | disgruntled staff. | actions by staff. Improvements to engagement with staff & community must be demonstrated following an incident. | surrounding community via inter alia the appointment of a suitably qualified CLO. Transparent communication through the right channels to communicate with the community as to when and how their contracts will come to an end. | Operator (CLO). | of construction, and during operation. | |
| 13.2.3 | Injury to site staff from construction, demolition and blasting activities. | To ensure effective Health & Safety implementation. | Appointment of a suitably qualified HSO and compliance monitoring against the OHSA (Act 85 of 1993). | Implement a safety plan, access protocols, grievance mechanism and compensation policy. All staff must undergo a site induction that outlines the socio-environmental constraints of the site. | Applicant / Contractor (HSO) / Operator. | Throughout Construction & Operation. | Health & Safety Audits biannually or otherwise stipulated in the OHS or construction regulations. |
| 13.2.4 | Injury to trespassers resulting in possible lawsuits. | To avoid inadvertent injuries to trespassers. | No recorded injuries to trespassers. | Increase security to protect trespassers from being electrocuted if and where electric fences are installed. Adequate signage must be placed | Applicant / Contractor. | Throughout construction | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|--|---|--|--|------------------------------------|--|------------|
| | | | | around the development warning uninformed people of the potential hazards and dangers associated with the project. | | | |
| 13.2.5 | Negative effects on the wellbeing of the local inhabitants and site staff as well as the potential outbreak of disease (including HIV/AIDS). | To avoid negative impacts on the health of the residents and occupiers. | Effective implementation of awareness training including measures to assess effectiveness of training. | AIDS / HIV awareness training must be undertaken to ensure that the labour force is well informed on the matter. Dangerous fumes, noise, dust and water impacts must be avoided that may affect both the labour force and surrounding landowners and users. | Applicant / Contractor / Operator | Ongoing | ECO & IEA. |
| 13.2.6 | Potential increase in pedestrian and livestock accidents. | To reduce impacts and injuries to pedestrian and livestock. | No injuries recorded in incident register. Close-out Reports must demonstrate improvements to avert a | An awareness must be fostered to drive carefully to avoid killing or injuring people or animals and damage to property. Open excavations must be secure and cordoned off to avoid accidental injury to humans and animals alike. | Applicant / Contractor / Operator. | Ongoing awareness and following cessation of use of borrow pits. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|---|--|--|---|----------------|--|------------|
| | | | recurrence. | <p>Any complaint from the public during the construction and operation of this project must be attended to by the person involved as soon as possible to the satisfaction of the parties concerned. A complaint register must be kept to address issues and complaints raised by concerned parties.</p> <p>A complaints register should be kept during construction and operational phase of this project to address issues and complaints raised by concerned parties.</p> | | | |
| 13.3 | Decommissioning Phase | | | | | | |
| 13.3.1 | Increased unemployment after construction & operation ends. | To minimize the negative social impacts at the end of each phase of the project. | Develop an effective implementation of an Exit Strategy. | <p>Develop and implement a holistic Exit Strategy that adequately and timeously communicates and buffers staff lay-offs.</p> <p>Clearly make the terms and conditions of employment known to</p> | Applicant. | Prior to commencement of construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|---|----------------|-----------------------|------------|
| | | | | all employees (temporary & permanent) including anticipated duration of each phase. | | | |

TABLE 14. CULTURAL, HERITAGE, ARCHAEOLOGICAL & PALEONTOLOGICAL MANAGEMENT.

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--|---|---|---|-------------------------|--------------------------|------------|
| 14.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 14.1.1 | Surveying and pegging of temporary footprints can disturb sites of historical significance, i.e. Graves. | To ensure initial survey & clearing activities do not disturb know heritage sites. | All graves and know heritage sites are secure (fenced or cordoned-off). | Ensure that none of the layout & designs of permanent footprints will disturb sites of historical significance, including graves. All formal and informal cemeteries and burials must be left in situ and not be disturbed. If this is not possible, a permit must be applied for in terms of Section 36 of the NHRA (Act 25 of 1999) and is subject to mandatory public consultation. | Applicant. | Prior to surveying. | ECO & IEA. |
| 14.1.2 | Lack of awareness of heritage resources. | To promote awareness about heritage resources and their presence within the development area. | Heritage content in site induction, toolbox and awareness talks. | Include an awareness of heritage resources in the environmental induction. Categories of heritage resources include, inter alia: • Evidence of archaeological sites or remains include remnants of stone-made structures, indigenous ceramics, bones, stone artefacts, ostrich eggshell | Applicant / Contractor. | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|---|--|--|--|-------------------------|--------------------------|------------|
| | | | | fragments, marine shell and charcoal / ash concentrations. • Archaeological or paleontological sites over 100 years old, • Sites of cultural significance associated with oral histories, • Significant cultural landscapes or views, or viewscapes, • Burial grounds, unmarked human burials, graves of victims of conflict, and/or graves older than 60 years, • Structures older than 60 years, • Fossils, etc. | | | |
| 14.2 | Construction Phase | | | | | | |
| 14.2.1 | Loss of archaeological & palaeontological valuable artefacts. | To ensure construction activities do not disturb known or incidental heritage sites. | No loss of archaeological valuable artefacts. All known "heritage" sites within the | All areas of heritage value must be demarcated and avoided. Incidental discoveries during clearing and grubbing, and archaeological artefacts unearthed during excavations must, be disclosed to site management with immediate | Applicant / Contractor. | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|---|---|---|---|-------------------------|--------------------------|------------|
| | | | development footprint is suitably cordoned off. | cessation of activities until their significance can be assessed by a qualified heritage specialist. | | | |
| 14.2.2 | Loss of cultural and heritage value to society. | To ensure correct procedures are followed following chance finds to preserve the heritage resource. | Adherence to protocols specified in management actions following a chance find. | <p>Contact a professional archaeologist, depending on the nature of the finds, as soon as possible to inspect the findings.</p> <p>In the event that fossils are uncovered during construction then the Fossil Chance Finds Procedure under the PIA report must be implemented.</p> <p>If there are any new heritage resources discovered during construction and operation phases of the proposed development, then construction must cease within the immediate vicinity and a buffer zone of 30 m must be established.</p> | Applicant / Contractor. | Throughout construction. | ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | | <p>A professional archaeologist or palaeontologist, depending on the nature of the finds, must be contracted as soon as possible to inspect the findings at the expense of the developer.</p> <p>If any evidence of archaeological sites or remains (e.g. remnants of stone-made structures, indigenous ceramics, bones, stone artefacts, ostrich eggshell fragments, charcoal and ash concentrations), fossils or other categories of heritage resources are found during the proposed development, SAHRA APM Unit (Natasha Higgitt/Phillip Hine 021 462 5402) must be alerted as per section 35(3) of the NHRA. If unmarked human burials are uncovered, the SAHRA Burial Grounds and Graves (BGG) Unit (Thingahangwi Tshivhase/Mimi</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|---|----------------|-----------------------|------------|
| | | | | <p>Seetelo 012 320 8490), must be alerted immediately as per section 36(6) of the NHRA. A professional archaeologist or palaeontologist, depending on the nature of the finds, must be contracted as soon as possible to inspect the findings. If the newly discovered heritage resources prove to be of archaeological or palaeontological significance, a Phase 2 rescue operation may be required subject to permits issued by SAHRA;</p> <p>If any unmarked human burials are uncovered and the archaeologist called in to inspect the finds and/or the police find them to be heritage graves, then mitigation may be necessary and the SAHRA Burial Grounds and Graves (BGG) Unit must be contacted for processes to follow</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | | <p>(Mimi Seetelo 012 320 8490).</p> <p>The contractors and workers should be notified that archaeological sites might be exposed during the construction work.</p> <p>Contractors and workers shall be advised of the penalties associated with the unlawful removal of cultural, historical, archaeological or palaeontological artefacts, as set out in the National Heritage Resources Act (Act No. 25 of 1999).</p> <p>Sites BP3 – 13 must be mitigated by a qualified archaeologist. All impacted sites must be mapped in detail and where archaeological deposit is present (such as the midden at BP9), this deposit must be sampled by means of archaeological excavations. A permit in terms of section 35 of</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--|--------------------------------------|------------------|----------------------|--|----------------|-----------------------|------------|
| | | | | the NHRA and Chapter II and IV of the NHRA Regulations must be applied for from SAHRA via SAHRIS for this purpose; | | | |
| 14.3 | Operational & Decommissioning Phases | | | | | | |
| Significant heritage impacts are mostly expected to occur during the construction phase. | | | | | | | |

TABLE 15. INFRASTRUCTURAL & TRAFFIC MANAGEMENT (INCLUDING PARKING ON SITE).

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-------------|--|---|--|---|-------------------------|-------------------------------|---|
| 15.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| 15.1.1 | No impacts expected during these phases. | | | | | | |
| 15.2 | Construction & Operation Phase | | | | | | |
| 15.2.1 | Dust entrainment from unsurfaced roads can result in unacceptably high dust fallout. | To manage dust entrainment on access roads which may not exceed the thresholds stipulated in the National Dust Control Regulations. | Full compliance with National Dust Regulations. Acceptable Dust fallout rate (mg/m ² /day): Residential area < 600 Non-residential area < 1200 Exceedance not more than twice in a year, not sequential months. | Dust suppression must be carried out on access roads where high dust entrainment is evident. To reduce water usage, a suitable soil binder must be used in dust suppression activities. Excessive water usage to control dust on dirt roads can cause erosion and lead to hazardous conditions for road users. | Applicant / Contractor. | During construction, monthly. | Following complaints and / or obvious visible signs of excessive dust fallout, monitoring of dust fallout must be undertaken by a professional service provider and compliance to be verified by ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--------|---|---|--|--|-------------------------|-----------------------|---|
| 15.2.2 | Parking and driving carelessly can increase collisions with mammals, birds, reptiles, amphibians and insects – collectively referred to as “roadkills”. | To avoid and minimise impacts from traffic on animals residing on and around the property. | Compliance to speed limits. No recorded project vehicle associated animal mortalities. | Drivers shall always adhere to the relevant speed limit(s) (on the existing road network) and restrict their movements to the existing and / or approved roadway or servitude. The speed limit on the property shall be 40 km/h and 30km/h within the development footprint. A register must be maintained of all animal mortalities recorded on the property and localised access roads. | Applicant / Contractor. | During construction. | Compliance to be verified by ECO & IEA. |
| 15.2.3 | Contamination from spills when refuelling, parking, driving, emergency repairing, operating plant or equipment to soil or nearby or within the watercourse. | To reduce contamination of soil from leaking plant and vehicles and upon occurrence is remediated promptly. | Spills are removed within 48 hours of event. Records of servicing by off-site workshop. Drip tray issued | Oil & fuel spills on roadways and parking areas must be removed to depth of penetration following their discovery and placed in a designated hazardous container for safe disposal. Drip trays must be placed under all plant that is parked overnight and extended periods not in | Applicant / Contractor. | During construction. | Compliance to be verified by ECO & IEA. |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|-----|------------------|------------------|--|---|----------------|-----------------------|------------|
| | | | to all plant and recorded in a register. | <p>operation.</p> <p>Drip trays can be filled with hydrophobic hydrocarbon absorbent material to avoid content being leached out during rainfall events.</p> <p>No servicing or washing of vehicles or plant may take place in parking bays, and all servicing must be done off-site, no service or wash-bays are to be constructed on site.</p> <p>Emergency breakdowns in the parking areas or along roads, must be addressed after adequate pollution containment measures have been implemented including but not limited to drip trays and spill kits.</p> <p>Refuelling of vehicles and plant</p> | | | |

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--|-----------------------|------------------|----------------------|---|----------------|-----------------------|------------|
| | | | | may only take place at a designated and permitted (from local Fire Chief) fuel storage tank or mobile fuel bowser, under the guidance of a Specific Operating Procedure (SOP) that limits spillage and addresses remedial actions in the event of a spillage. | | | |
| 15.3 | Decommissioning Phase | | | | | | |
| There are no significant impacts expected during this phase. | | | | | | | |

TABLE 16. VISUAL ASPECT MANAGEMENT.

| No. | Potential Impact | Desired Outcomes | Targets & Indicators | Management Actions & Mitigation Measures | Responsibility | Timeframe / Frequency | Monitoring |
|--|--|---|--|--|----------------|-----------------------------------|------------|
| 16.1 | Planning & Design Phase (including Pre-Construction) | | | | | | |
| There are no significant impacts expected during this phase, as footprint location has already mitigated the planning and design requirements. | | | | | | | |
| 16.2 | Construction & Operational Phase | | | | | | |
| 16.2.1 | Impact of construction on visual receptors, including road users and local homesteads. | To manage the facility in a way that minimised its visual impacts on the surrounding environment. | Demonstration of effects to minimise visual impacts. | Use visual screens to minimise the visual impact on the scenic resources of this region. Have minimal placements that can be visually intrusive to sensitive receptors. Utilise fencing options that do not create a significant visual barrier. | Applicant. | Throughout the project lifecycle. | ECO & IEA. |
| There are no significant impacts expected during the decommissioning phase. | | | | | | | |

SECTION 6: ENVIRONMENTAL AWARENESS PLAN

This section of the report is included in compliance with Section 24N(3)(c) of the NEMA and the EIA Regulations (2014) as amended.

The EMPr needs to include, inter alia:

An environmental awareness plan describing the manner in which-

- (i) The applicant intends to inform his or her employees of any environmental risk which may result from their work; and*
- (ii) Risks must be dealt with to avoid pollution or the degradation of the environment;*

Throughout the construction & operational phases environmental as well as health and safety awareness training should be provided to all employees to promote the effective implementation of the EMPr actions.

This section of the report focusses on the environmental awareness training. It provides a guideline as to the possible environmental risks that may be experienced as part of the project as well as way to avoid the risks and subsequent environmental degradation. The aim is to provide a guide to developing a comprehensive yet easily understandable awareness plan to present to employees of all education and skill levels which should be presented to the employees at least one week prior to commencement of construction. The following pointers are given for the environmental awareness training course:

- Environmental awareness training should be undertaken by the environmental and / or health and safety representative of the developer / contractor with the input of an EAP or ECO if required;
- Environmental awareness reminders should be undertaken at least bi-annually to ensure that employees and Contractors are kept aware of the risks and management thereof;
- It is recommended that awareness posters be developed and placed on site in highly visible areas to provide the required information when it needs to be referred to as well as reminding employees of their obligations regarding environmental protection;
- A slideshow can also be developed for initial awareness induction and for use as a reminder of the environmental risks and responsibilities at the site or induction of future Contractors; and
- Throughout the presentations (posters, meetings, slideshows, etc.), it is recommended that visual aids be used to explain the potential risks and management thereof as thoroughly as possible.

Should any new personnel be contracted or arrive on site during the construction period, they should attend the environmental awareness course. The environmental awareness training should be provided to all labourers, technical staff and any other Contractor appointed.

The awareness training forms part of this EMPr and should be implemented as part of the conditions of environmental management and risk prevention. Refer to the management

measures in Tables 6 through 16 above for proposed management and mitigation actions to be undertaken to prevent or minimise the risks described below. Attention should be focussed on the following areas of sensitivity during the construction phase:

- Removal of vegetation during site clearance;
- Animal habitat disturbance due to vegetation clearance;
- Soil erosion and pollution;
- Soil compaction;
- Health and safety;
- Degradation of roads; and
- Fire risks.

Other elements to be taken into consideration by the employees during both the construction and operational phases include:

- The presence of animals on site;
- Disturbances to neighbours due to noise and traffic;
- The positive impacts, of the greener technology being implemented, on the biophysical and socio-economic environments; and
- Awareness should be raised regarding the possible occurrence of sensitive plant and animal species and heritage features.

The awareness training for this project should aim to prevent, and where prevention is not possible, mitigate detrimental environmental impacts. It should promote awareness of environmental risks and management thereof. It should furthermore promote green thinking and provide information on alternative energy sources and energy consumption reduction.

SECTION 7: RESPONSIBILITIES OF ROLE PLAYERS

The approved EMPr shall be printed, completed and kept in an on-site file designated for all matters pertaining to environmental management. Co-operation is required between the applicant, contractor, and ECO to ensure that activities are managed in an amicable and responsible manner and in accordance with the philosophies of environmental legislation and principles of the EMPr.

This EMPr is predominantly compiled for the management of construction & operations associated with the development of a solar PV facility, once the Planning and Authorisation phases are complete. The tabulated management programmes assign responsibilities to one or more role player, the below descriptions identify responsibilities and accountabilities in the case of any uncertainty.

Applicant

The applicant remains ultimately accountable for ensuring that the development is implemented according to the requirements of the EMPr. Although the applicant delegates specific responsibilities to role players to perform functions on his / her behalf, the ultimate accountability cannot be delegated. The developer is responsible for ensuring that sufficient resources (time, financial, man-power, equipment, etc.) are available to the other role players (e.g. the contractor, SECO, etc) to efficiently perform their tasks in terms of the EMPr. The responsibility of restoring the environment in the event of any negligence, which leads to damage of the environment, also falls to the applicant.

The applicant must ensure that the EMPr is included in any documents (tender, appointment etc.) so that any contractor who is appointed is bound to the conditions of the EMPr. The applicant must appoint an independent Environmental Control Officer (ECO) prior to commencement of construction, to help identify pre-construction & construction criteria that need to be fulfilled timeously, to avoid non-compliance with the overarching authorisation conditions and / or legislation.

Contractor

The contractor, as the developer's agent on site, is bound to the EMPr conditions through his / her contract with the developer and is responsible for ensuring that she / he adheres to all the conditions of the EMPr. The contractor shall be responsible for the actions undertaken by all their employees including sub-contractors. The contractor must thoroughly familiarise him / herself with the EMPr requirements before coming onto site and must request clarification on any aspect of these documents, should they be unclear. The contractor must ensure that he / she has provided sufficient budget for complying with all EMPr conditions at the tender / appointment stage.

The contractor must comply with all instruction (whether verbal or written) given by the environmental manager, project manager or site engineer in terms of the EMPr.

Site Environmental Officer (SEO)

The Site Environmental Officer (SECO) shall be appointed by the contractor to implement the EMPr daily. The SEO shall ensure that all construction activities are carried out in accordance with the relevant conditions of the EMPr, Environmental Authorisation (EA), General Authorisation (GA) or Water Use License (WUL) (under the National Water Act), wayleaves, provincial ordinances & provincial bylaws.

Environmental Control Officer (ECO)

The Environmental Control Officer (ECO) is appointed by the applicant as an independent monitor of the implementation of the EMPr, EA & GA / WUL. He / she must form part of the project team and be involved in all aspects of the project planning that can influence environmental conditions on the site.

The ECO must attend relevant project meetings, conduct inspections to assess compliance with the EMPr, EA & GA / WUL and be responsible for providing feedback on potential environmental problems associated with the development. In addition, the ECO is responsible for:

- Liaising with relevant authorities;
- Liaising with contractors regarding environmental management; and
- Undertaking routine monitoring and appointing a competent person / institution to be responsible for any specialist monitoring (if required).

The ECO has the right to enter the site and undertake monitoring and auditing at any time, subject to compliance with health and safety requirements applicable to the site (wearing safety boots, head gear, mouth mask etc.).

Independent Environmental Auditor (IEA)

An IEA shall be appointed by the Applicant to undertake EMPr, EA & GA / WUL compliance audits at 6-monthly intervals during construction. The purpose of conducting a periodic compliance audit would be to systematically check and evaluate progress on EMPr, EA & GA / WUL implementation. The environmental audit will serve as a 'snapshot' of the environmental situation and progress at a given point in time. The purpose of the audit is to illustrate whether there has been any improvement or change over time.

The IEA will fulfil the auditing requirements by systematically auditing the Project's performance & compliance against the requirements of the EA, EMPr & GA / WUL in a process that is carefully planned, structured and organised. The audit process must, on a sampled basis, track past actions, activities, events, and procedures through using existing documentation, conducting interviews with managers and personnel, and observing practices on site.

Following construction, the IEA will undertake operational audits in accordance with the EIA Regulations (2014) as amended, which at the time of compilation of this report was every 5

years but may change with future amendments. Additional auditing requirements may be needed to fulfil the requirements of any Norms & Standards.

SECTION 8. COMMUNICATION

At least monthly construction site meetings should be held where feedback can be given, and any potential problems identified and remedied. If they cannot be remedied then construction in that area should be stopped, until a suitable remedy is identified.

Monitoring Compliance

Pre-construction, Construction and Post-construction:

The ECO will be responsible for monitoring and reporting on compliance of the activity from pre- to post-construction.

Inspections and resulting compliance reports shall be a systematic, independent and documented process for obtaining compliance evidence and evaluating it objectively to determine the extent to which the compliance criteria are fulfilled. The compliance criteria (or reference) against which the compliance evidence is compared shall include this EMP, the Environmental Authorisation & General Authorisations or a Water Use License (under the National Water Act).

The ECO must undertake monthly inspections of the site and submit monthly environmental compliance reports to the Department of Environmental Affairs (DEA) as the competent authority for this project, unless otherwise prescribed in the EA. The compliance reports must identify the actual and potential transgressions, describe the impacts, provide verifiable evidence (photographs, records or statements) and recommend corrective and preventive actions (including completion dates). The compliance reports must measure the applicant / contractor's level of compliance against the aforesaid criteria. Performance scoring / reporting is optional.

The SECO shall maintain an on-site diary to record environmental aspects (elements of the construction activities that can interact with the environment) and environmental impacts (any change to the environment, whether adverse or beneficial, wholly or partially resulting construction activities), daily.

The EMP is a legally binding document and should form part of the contract. Should there be failure to comply with the EMP the following steps are envisaged:

Step 1

The ECO meets with the contractor and points out the deviation from the EMP. The ECO and Contractor agree on a solution and this non-compliance is recorded by the ECO as well as the solution put forward to rectify it.

Step 2

Should there still be non-compliance or there is a more serious infringement of the EMPr the contractor is informed in writing with a deadline by which the problem must be rectified. Any extra costs that may be accrued must be borne by the contractor.

Step 3

If non-compliance persists, the Chief Resident Engineer (CRE) or Project Manager (PM) shall order the contractor to suspend construction in that specific area or the project as a whole until the activity at variance with the EMPr is corrected and or remedial actions taken. Any cost that occurs as a result of such action shall be for the account of the contractor.

Step 4

Where there is non-compliance with the EMPr and no evidence that the contractor intends complying even though the above 3 steps have been taken the applicant may terminate the contract due to non-compliance (breach of contract). Such measures do not replace any legal proceedings that may occur as a result of such non-compliance.

Environmental Awareness Plan

The applicant shall ensure that his project team, contractor and labourers are adequately trained with regard to the implementation of the EMPr, EA & GA / WUL throughout construction.

Time Periods and Failure to Comply with the EMPr

The time periods within which the measures prescribed in this EMPr must be implemented shall be applicable to the full duration of the activity that is being undertaken and mitigated. The time periods within which corrective and preventive actions need to be implemented shall be determined by the nature and severity of the finding. In the absence of a prescribed deadline or completion date, findings shall be corrected or prevented immediately upon being found to occur, if practical.

Pre-construction

Environmental Awareness Inductions shall be targeted at two distinct levels of employment: management (applicant, architect, engineer, contractor / site agent) and labourers (including the site foreman). The SEO shall be responsible for preparing and presenting inductions appropriate to the audience. Inductions shall be undertaken prior to the commencement of construction. Where possible the presentation will be conducted in the language of the employees.

The Environmental induction for management shall include mitigations that are relevant to or require management's involvement prior to implementation including, but not limited to, the following:

- Measures required during the Planning and Design, and Pre-construction phase, and
- Site establishment.

The Environmental induction for the contractor's labourers and foreman shall, as a minimum, include the following:

- A description of the actual and potential environmental impacts,
- Standard operating procedures for undertaking construction activities (i.e. mixing concrete, driving, etc.) that can have an environmental impact,
- Staff conduct including sanitation and movement,
- The integrated waste management strategy,
- The steps to be taken should any item of perceived environmental importance including archaeological artefacts be located or unearthed, and
- The environmental emergency plans.

Construction

The SEO and ECO shall undertake an informal training needs analysis throughout construction to identify appropriate environmental topics and the appropriate labourers to target. The analysis shall be informed by the findings contained in the site diary and compliance reports. Training shall be given during toolbox talks.

The SEO and ECO shall keep records of the environmental inductions and subsequent toolbox talks in an on-site file designated for all matters pertaining to environmental management.

Operation:

The operator & relevant authorities should be responsible for monitoring compliance with aspects of the activity that fall within their jurisdiction.

SECTION 9: ENVIRONMENTAL EMERGENCY PLAN FOR THE CONTROL OF ENVIRONMENTAL INCIDENTS

Definition of an 'Environmental Incident'

Section 30 (1) (a) of NEMA 'incident' means an unexpected, sudden and uncontrolled release of a hazardous substance, including from a major emission, fire or explosion, that causes, has caused or may cause significant harm to the environment, human life or property"

Procedure

The contractor shall ensure that emergencies are reported and controlled in accordance with the sequence of events prescribed for spillages in a watercourse, on land and fire, including:

- Action to be taken
- Removal and remediation measures to be implemented
- Internal and external communication plan
- Prescribed reporting procedure

The contractor shall ensure that their employees are adequately trained to react to environmental emergencies in accordance with this procedure.

The SECO shall complete the table of contact numbers, erect them in a conspicuous place within the construction camp and make its whereabouts known to all of the contractor's staff.

Equipment

The following equipment is required to successfully implement this procedure. It must be ensured that the equipment is supplied to or is readily available for all living quarters, site offices, kitchen areas, workshop areas, stores and on site.

1. A spill kit including absorbent fibres, mats and booms
2. A net
3. A whistle
4. Adequate lighting for night shifts
5. Spades
6. Sand bags
7. Designated hazardous waste drums
8. (Trained personnel with) protective clothing for extinguishing fires
9. Fire extinguishers
10. Fire beaters
11. Water carts/tankers with pumps and hoses
12. Water pumps and pipes (for fires started at the watercourse crossings)

Contact Numbers

| Organisation | Name | Telephone/cell Number |
|--|------|-----------------------|
| Project Personnel | | |
| Applicant | | |
| Engineer | | |
| Contractor | | |
| HSO | | |
| SEO | | |
| ECO | | |
| Interested and Affected Parties | | |
| Land Owner | | |
| Adjacent Land Owner | | |
| Adjacent Land Owner | | |
| Emergency Services | | |
| Spill Clean-up Service Provider | | |
| Fire Department | | |
| Chief Fire Officer (Fire Chief) | | |
| SA Police Services | | |
| Disaster Management Centre | | |
| Local Municipality | | |
| District Municipality | | |
| Irrigation Board | | |
| Water Catchment Management Agency | | |
| Water Treatment Works | | |
| DWS (Regional Head of Department / | | |

| | | |
|--|--|--|
| Chief Director) | | |
| DWS (Regional Director: Water sector Regulation & Use) | | |
| DEA (Provincial Head of Department) | | |
| DEA (Director: Environmental Impact Management) | | |
| DEA (Director General) | | |
| DEA (Director: Environmental Impact Evaluation) | | |

SPILLAGE IN A WATERCOURSE

| ACTION TO BE TAKEN | | |
|---------------------------|-----------------------|---|
| Personnel | Responsibility | Action |
| Employee | Reporting | The person responsible for, or who discovers, a hazardous substance spill must report the incident to their immediate Supervisor. |
| Supervisor | Reporting | Report the incident to the SEO, HSO and Resident Engineer. <ul style="list-style-type: none"> Note that the SEO will take control of all relevant actions once he/she arrives on the scene. |
| HSO | Reporting | Report the incident to an Inspector (designated under section 28 of the Occupational Health & Safety Act, 1993) within the prescribed period and manner. |
| Supervisor / SEO | Initial investigation | Determine the extent of the spill, i.e. its boundaries, by observing for the following: <ol style="list-style-type: none"> Any visual indication of pollution, Any odours or emissions detected, Any indication of the source of pollution, Any sign of damage to the natural system. <ul style="list-style-type: none"> The Supervisor / SEO should provide lighting if working at night. |
| Supervisor / SEO | Co-ordination | Sound an alarm/whistle. <ul style="list-style-type: none"> The designated response team consisting of area specific personnel and including the environmental leader, will congregate at the spill kit. All other employees who do not have specific duties to perform are to evacuate the affected area to a location designated by the Supervisor / SEO. |
| Supervisor / SEO | Co-ordination | Minimise the effects of the incident on the environment and persons by removing the source of the spill at least 100m away from the watercourse or cut-off the supply of the spill if the source is not moveable. |
| Supervisor / SEO | Co-ordination | Contain the spill by laying an absorbent sock or boom across the width of the watercourse AT A PRE-DETERMINED LOCATION downstream of the construction area (spill). <ul style="list-style-type: none"> A series of parallel booms may be required. |
| Supervisor / ECO | Co-ordination | Secure the affected area with danger tape. |

| | | |
|----------------------|-----------------|--|
| HSO | Co-ordination | The site shall not be disturbed and no article or substance may be removed (without the consent of the inspector) if there is or likely to be a death, or if there is a loss of limb or part of a limb. However, action can be taken to prevent a further accident, to remove the injured or dead or rescue persons from danger. |
| Engineer / SEO / HSO | Decision-making | <p>The Engineer will assess the situation in consultation with the SEO and HSO and act as required.</p> <ul style="list-style-type: none"> • The risk involved shall be assessed before anyone approaches the scene of the incident. • The HSO will consult the MSDSs. • The scale of the spill will dictate whether the spill will be cleaned up by using the on-site spill kit and in the prescribed manner, or by contacting a Spill Clean-Up Service Provider for assistance. • The SEO will take photographs of the affected area. • No person shall be allowed to approach a spill unless he/she is equipped with the personal protective clothing. |
| SEO | Directions | If a Spill Clean-Up Service Provider is used, assist the emergency services by clearly marking the route to be taken to the spill site. |
| SEO | Co-ordination | Take such measures as the Catchment Management Agency may either verbally or in writing direct within the time specified by such institution. |

SPILLAGE IN A WATERCOURSE

| REMOVAL AND REMEDIATION MEASURES TO BE IMPLEMENTED | | |
|---|-----------------------|---|
| Personnel | Responsibility | Action |
| SEO | Co-ordination | Remove the contaminated sock or boom from the surface of the water. If lose fibres were scattered on the surface to capture hydrocarbons in shallow (still) pools, 'fish' it out with a net. |
| SEO | Co-ordination | Remove the contaminated soil from the banks of the watercourse, to the depth of penetration using a spade or shovel. |
| SEO | Co-ordination | Temporarily store the contaminant in the designated hazardous waste facility at the construction camp. |
| SEO | Co-ordination | Contact a licensed hazardous waste service provider to collect and transport the waste to a licensed hazardous waste landfill site. |
| SEO | Co-ordination | Rehabilitate the banks of the watercourse by replacing the topsoil and planting indigenous plants. |
| SEO | Monitoring | Immediately follow any known spillage of toxic substances into a stream or river with monitoring of the receiving streams or rivers and public health. |
| SEO | Co-ordination | Should water downstream of the spill be polluted, and fauna and flora show signs of deterioration or death, specialist hydrological or ecological advice must be sought for appropriate treatment and remedial procedures to be followed. |
| SEO | Monitoring | Take photographs of the affected area during rehabilitation. |

SPILLAGE IN A WATERCOURSE

| INTERNAL & EXTERNAL COMMUNICATION PLAN | | |
|--|----------------|---|
| Personnel | Responsibility | Action |
| Employee | Reporting | The person responsible for, or who discovers, a hazardous waste spill must report the incident to their immediate Supervisor. |
| Supervisor | Reporting | Report the incident to the SEO, HSO and Resident Engineer. |
| HSO | Reporting | Report the incident to an Inspector (designated under section 28 of the Occupational Health & Safety Act, 1993) within the prescribed period and manner. |
| SEO | Reporting | Report the incident to the Site Agent and / or Manager and the ECO. |
| SEO | Reporting | If the spill is too big for the spill kit, contact a Spill Clean-Up Service Provider. |
| SEO | Reporting | <p>If the spill is going to affect downstream users, inform the Land Owner, the Irrigation Board and water treatment works (if applicable).</p> <ul style="list-style-type: none"> ● Provide the following information to the water treatment works: <ol style="list-style-type: none"> 1. The exact location of the spillage, 2. The time of the spillage, 3. As much information about the nature of the pollution, 4. The name and telephone number of the person contacting them. ● Irrigation Boards control river structures and may be able to divert/or impound the river to protect 'water supply intakes'. |
| SEO | Reporting | <p>Report the incident to the following authorities within 24 hours.</p> <ol style="list-style-type: none"> 1. DEA (Director General), 2. DWS (Director General and Chief Director), 3. SA Police Services, 4. Fire Department, 5. Catchment Management Agency, 6. DEA (provincial Head of Department) or Local Municipality, and 7. Any persons whose health may be affected by the incident. |

| | | |
|------------------------------------|-----------|---|
| SEO | Reporting | <p>Provide the following information:</p> <ol style="list-style-type: none"> 1. The nature of the incident, 2. Any risks posed by the incident to public health, safety & property, 3. the toxicity of substances or by-products released by the incident, and 4. any steps that should be taken in order to avoid or minimise the effects of the incident on public health and the environment. |
| ECO / Applicant / Site Agent / CRE | Reporting | <p>If the nature of the impact constitutes a gross violation of the EA or any legislation:</p> <ul style="list-style-type: none"> • The ECO must report the incident to the applicant. • The applicant must report the incident to the Local Municipality, DEA, and DWS. • The Site Agent and / or Manager must report the incident to their Environmental Group Manager, Divisional MD and CEO. • The Resident Engineer must report the incident to his Superiors. |

SPILLAGE IN A WATERCOURSE

| PRESCRIBED REPORTING PROCEDURE | | |
|---------------------------------------|-----------------------|--|
| Incident recording | | |
| Personnel | Responsibility | Action |
| SEO | Investigation | Conduct an investigation, including interviews, and record all details of the incident. ● The cause must be investigated. |
| SEO | Reporting | Complete an Environmental Incident Report and forward it to all key project personnel, with the exception of the Emergency Services. |
| SEO | Reporting | Within 14 days of the incident, report the incident to the following authorities: 1. DEA (Director General), 2. DEA (Provincial Head of Department), 3. Local Municipality, 4. DWS (Regional Director). |
| SEO | Reporting | Provide the following information: 1. The nature of the incident, 2. The substances involved and an estimation of the quantity released and their possible acute effect on persons & the environment & data needed to assess these effects, 3. Initial measures to minimise impacts, 4. Causes of the incident, whether direct or indirect including equipment, technology, system or management failure, and 5. Measures taken & to be taken to avoid a recurrence of such incident. |
| SEO | Reporting | Submit an action plan within 14 days, or a shorter period of time, if specified by the Regional Director (DWS). |
| SEO | Reporting | The action plan must include the following information: 1. A detailed time schedule of measures taken to: 1.1 Correct the impacts resulting from the incident; 1.2 Prevent the incident from causing any further impact; and 1.3 Prevent a recurrence of a similar incident. |
| Progress reporting | | |
| SEO | Revising | Identify methods for preventing the incident from |

| | | |
|-----|------------|--|
| | Procedures | re-occurring and revise method statements and/or procedures for implementing as early as possible. |
| SEO | Training | <p>Conduct either a toolbox talk or environmental awareness training/re-induction to the all employees and include additional mitigations to avoid a re-occurrence.</p> <ul style="list-style-type: none"> ● Keep the program, including a signed attendance register, in the on-site environmental file. |

SPILLAGE ON LAND

| ACTION TO BE TAKEN | | |
|--------------------|-----------------------|---|
| Personnel | Responsibility | Action |
| Employee | Reporting | The person responsible for, or who discovers, a hazardous substance spill must report the incident to their immediate Supervisor. |
| Supervisor | Reporting | Report the incident to the SEO, HSO and Resident Engineer. <ul style="list-style-type: none"> Note that the SEO will take control of all relevant actions once he/she arrives on the scene. |
| HSO | Reporting | Report the incident to an Inspector (designated under section 28 of the Occupational Health & Safety Act, 1993) within the prescribed period and manner. |
| Supervisor / SEO | Initial investigation | Determine the extent of the spill, i.e. its boundaries, by observing for the following: <ul style="list-style-type: none"> Any visual indication of pollution, Any odours or emissions detected, Any indication of the source of pollution, Any sign of damage to the natural system. The Supervisor / SEO should provide lighting if working at night. |
| Supervisor / SEO | Co-ordination | Sound an alarm/whistle. <ul style="list-style-type: none"> The designated response team consisting of area specific personal and including the environmental leader, will congregate at the spill kit. All other employees who do not have specific duties to perform are to evacuate the affected area to a location designated by the Supervisor / SEO. |
| Supervisor / SEO | Co-ordination | Minimise the effects of the incident on the environment and persons by removing the source of the spill at least 100m away from the watercourse or cut-off the supply of the spill if the source is not moveable. |
| Supervisor / ECO | Co-ordination | Contain the spill to a confined area to prevent the spreading of the spilled chemical or substance. <ul style="list-style-type: none"> Use sand bags or construct earth berms. If relevant, close off all storm water drains with absorbent mats. Do not wash the spill with water as it will cause |

| | | |
|----------------------|-----------------|--|
| | | the spill to spread. |
| Supervisor / ECO | Co-ordination | Secure the affected area with danger tape. |
| HSO | Co-ordination | The site shall not be disturbed and no article or substance may be removed (without the consent of the inspector) if there is or likely to be a death, or if there is a loss of limb or part of a limb. However, action can be taken to prevent a further accident, to remove the injured or dead or rescue persons from danger. |
| Engineer / SEO / HSO | Decision-making | <p>The Engineer will assess the situation in consultation with the SEO and HSO and act as required.</p> <ul style="list-style-type: none"> • The risk involved shall be assessed before anyone approaches the scene of the incident. • The HSO will consult the MSDSs. • The scale of the spill will dictate whether the spill will be cleaned up by using the on-site spill kit and in the prescribed manner, or by contacting a Spill Clean-Up Service Provider for assistance. • The SEO will take photographs of the affected area. • No person shall be allowed to approach a spill unless he/she is equipped with the personal protective clothing. |
| SEO | Directions | If a Spill Clean-Up Service Provider is used, assist the emergency services by clearly marking the route to be taken to the spill site. |

SPILLAGE ON LAND

| REMOVAL AND REMEDIATION MEASURES TO BE IMPLEMENTED | | |
|---|-----------------------|---|
| Personnel | Responsibility | Action |
| SEO | Co-ordination | Remove the contaminated soil to the depth of penetration using a spade or shovel. |
| SEO | Co-ordination | Temporarily store the contaminant in the designated hazardous waste facility at the construction camp. |
| SEO | Co-ordination | Contact a licensed hazardous waste service provider to collect and transport the waste to a licensed hazardous waste landfill site. |
| SEO | Co-ordination | Rehabilitate the area cleared of hazardous waste by replacing the topsoil and planting indigenous plants. |
| SEO | Monitoring | Immediately follow any known spillage of toxic substances with monitoring of the receiving environment, and public health if necessary. |
| SEO | Monitoring | Take photographs of the affected area during rehabilitation. |

SPILLAGE ON LAND

| INTERNAL & EXTERNAL COMMUNICATION PLAN | | |
|--|----------------|---|
| Personnel | Responsibility | Action |
| Employee | Reporting | The person responsible for, or who discovers, a hazardous waste spill must report the incident to their immediate Supervisor. |
| Supervisor | Reporting | Report the incident to the SEO, HSO and Resident Engineer. |
| HSO | Reporting | Report the incident to an Inspector (designated under section 28 of the Occupational Health & Safety Act, 1993) within the prescribed period and manner. |
| SEO | Reporting | Report the incident to the Site Agent and/or Manager and the ECO. |
| SEO | Reporting | If the spill is too big for the spill kit, contact a Spill Clean-Up Service Provider. |
| SEO | Reporting | Report the incident to the following authorities. 1. DEA (Director General), 2. SA Police Services, 3. Fire Department, 4. DEA (Provincial Head of Department) or Local Municipality, and 5. Any persons whose health may be affected by the incident. |
| SEO | Reporting | Provide the following information: 1. The nature of the incident, 2. Any risks posed by the incident to public health, safety & property, 3. the toxicity of substances or by-products released by the incident, and 4. Any steps that should be taken in order to avoid or minimise the effects of the incident on public health and the environment. |
| ECO / Applicant / Site Agent / RE | Reporting | If the nature of the impact constitutes a gross violation of the EA or any legislation: <ul style="list-style-type: none"> • The ECO must report the incident to the applicant. • The applicant must report the incident to the Local Municipality, DEA, and DWS. • The Site Agent and/or Manager must report the incident to their Environmental Group Manager, Divisional MD and CEO. |

| | | |
|--|--|--|
| | | <ul style="list-style-type: none">• The Resident Engineer must report the incident to his Superiors. |
|--|--|--|

SPILLAGE ON LAND

| PRESCRIBED REPORTING PROCEDURE | | |
|---------------------------------------|-----------------------|--|
| Incident recording | | |
| Personnel | Responsibility | Action |
| SEO | Investigation | Conduct an investigation, including interviews, and record all details of the incident. ● The cause must be investigated. |
| SEO | Reporting | Complete an Environmental Incident Report and forward it to all key project personnel, with the exception of the Emergency Services. |
| SEO | Reporting | Within 14 days of the incident, report the incident to the following authorities. 1. DEA (Director General) 2. DEA (Provincial Head of Department), and 3. Local Municipality. |
| SEO | Reporting | Provide the following information: 1. The nature of the incident, 2. The substances involved and an estimation of the quantity released and their possible acute effect on persons & the environment & data needed to assess these effects, 3. Initial measures to minimise impacts, 4. Causes of the incident, whether direct or indirect including equipment, technology, system or management failure, and 5. Measures taken & to be taken to avoid a recurrence of such incident. |
| Progress reporting | | |
| SEO | Revising Procedures | Identify methods for preventing the incident from re-occurring and revise method statements and/or procedures for implementing as early as possible. |
| SEO | Training | Conduct either a toolbox talk or environmental awareness training/re-induction to the employee(s) responsible for the spill and include additional mitigations to avoid a re-occurrence. ● Keep the program, including a signed attendance register, in the on-site environmental file. |

FIRE

| ACTION TO BE TAKEN | | |
|--------------------|----------------|---|
| Personnel | Responsibility | Action |
| Employee | Reporting | The person who starts or discovers a fire must report the incident to their immediate Supervisor. |
| Supervisor | Reporting | Report the incident to the SEO, HSO and Resident Engineer. <ul style="list-style-type: none"> Note that the SEO will take over co-ordination of all relevant actions once he/she arrives on the scene. |
| SEO | Reporting | If there is potential for a fire to spread and endanger life, property or the environment, alert the landowner and Fire Department. |
| Land Owner | Reporting | Alert the owners of adjacent land. |
| HSO | Reporting | Report the incident to an Inspector (designated under section 28 of the Occupational Health & Safety Act, 1993) within the prescribed period and manner. |
| Supervisor / SEO | Co-ordination | Sound an alarm/whistle. <ul style="list-style-type: none"> The designated response team consisting of area specific personnel and including the environmental leader, will congregate at the fire-fighting equipment. All other employees who do not have specific duties to perform are to evacuate the affected area to a location designated by the Supervisor / SEO. |
| SEO | Directions | Assist the Fire Department by clearly marking the route to be taken to the fire. |
| SEO | Co-ordination | Extinguish the fire or assist in doing so. |
| SEO | Co-ordination | Stop the spread of the fire. |
| SEO | Co-ordination | Provide assistance to a fire protection officer or forest officer in the event that they take control over the fighting of a fire. |
| HSO | Co-ordination | The site shall not be disturbed and no article or substance may be removed (without the consent of the inspector) if there is or likely to be a death, or if there is a loss of limb or part of a limb. However, action can be taken to prevent a further accident, to remove the injured or dead or rescue persons from danger. |

FIRE

| REMEDATION MEASURES TO BE IMPLEMENTED | | |
|---------------------------------------|----------------|--|
| Personnel | Responsibility | Action |
| SEO | Assessment | Immediately follow any fire with an assessment of the effects on the environment, public health, safety and property. |
| SEO | Search | Search the scorched earth for reptiles and other creatures that can be rehabilitated and saved. ● Use only a licensed rehabilitation facility. |
| SEO | Monitoring | Monitor for signs of erosion after the first few rains and new flush. ● Manage erosion resulting from a loss in plant basal or aerial cover. ● Ensure that the control measures are not destructive. |
| SEO | Managing | No Vehicles or plant are permitted to drive through burnt areas. |

FIRE

| INTERNAL & EXTERNAL COMMUNICATION PLAN | | |
|--|----------------|--|
| Personnel | Responsibility | Action |
| Employee | Reporting | The person who starts or discovers a fire must report the incident to their immediate Supervisor. |
| Supervisor | Reporting | Report the incident to the SEO, HSO and Resident Engineer. <ul style="list-style-type: none"> Note that the SEO will take control over all relevant actions once he/she arrives on the scene. |
| SEO | Reporting | Report the incident to the Site Agent and/or Manager and the ECO. |
| SEO | Reporting | If there is potential for a fire to spread and endanger life, property or the environment, alert the landowner and Fire Department. |
| Land Owner | Reporting | Alert the owners of adjacent land. |
| HSO | Reporting | Report the incident to an Inspector (designated under section 28 of the Occupational Health & Safety Act, 1993) within the prescribed period and manner. |
| SEO | Reporting | Report the incident to the following authorities. 1. DEA (Director General), 2. SA Police Services, 3. Fire Department, 4. DEA (Provincial Head of Department) or Local Municipality, and 5. Any persons whose health may be affected by the incident. |
| SEO | Reporting | Provide the following information: 1. The nature of the incident, 2. Any risks posed by the incident to public health, safety & property, 3. the toxicity of substances or by-products released by the incident, and 4. any steps that should be taken in order to avoid or minimise the effects of the incident on public health and the environment. |
| ECO / Applicant / Site Agent / RE | Reporting | If the nature of the impact constitutes a gross violation of the EA or any legislation: <ul style="list-style-type: none"> The ECO must report the incident to the applicant. The applicant must report the incident to the Local Municipality, DEA, and DWS. The Site Agent and / or Manager must report the incident to their Environmental Group Manager, |

| | | |
|--|--|--|
| | | <p>Divisional MD and CEO.</p> <ul style="list-style-type: none">• The Resident Engineer must report the incident to his Superiors. |
|--|--|--|

FIRE

| PRESCRIBED REPORTING PROCEDURE | | |
|---------------------------------------|-----------------------|--|
| Incident recording | | |
| Personnel | Responsibility | Action |
| SEO | Investigation | Conduct an investigation, including interviews, and record all details of the incident. ● The cause must be investigated. |
| SEO | Reporting | Complete an Environmental Incident Report and forward it to all key project personnel, with the exception of the Emergency Services. |
| SEO | Reporting | Within 14 days of the incident, report the incident to the following authorities. 1. DEA (Director General), 2. DEA (Provincial Head of Department), and 3. Local Municipality. |
| SEO | Reporting | Provide the following information: 1. The nature of the incident, 2. The substances involved and an estimation of the quantity released and their possible acute effect on persons & the environment & data needed to assess these effects, 3. Initial measures to minimise impacts, 4. Causes of the incident, whether direct or indirect including equipment, technology, system or management failure, and 5. Measures taken & to be taken to avoid a recurrence of such incident. |
| Progress reporting | | |
| SEO | Revising Procedures | Identify methods for preventing the incident from re-occurring and revise method statements and/or procedures for implementing as early as possible. |
| SEO | Training | Conduct either a toolbox talk or environmental awareness training/re-induction to the employee(s) responsible for the spill and include additional mitigations to avoid a re-occurrence. ● Keep the program, including a signed attendance register, in the on-site environmental file. |



CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:

CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

C4.1 CONDITION ASSESSMENT OF THE EXISTING BOSPOORT PIPELINE

**RLM/RWST/OMM/0102/2024/25 - RE-ADVERT:
APPOINTMENT OF A CONTRACTOR FOR THE
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Tender
Part C4: Site Information

C4.1-1

C4.1
Condition Assessment

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Isinyithi Cathodic Protection

Company Reg # : 2002/002423/07
VAT# : 4570234502

P O Box 2905, Witkoppen, 2068
13 Robin Drive, Fourways 2191
T: 011 465-1807
E: pipeline@isinyithi.co.za



CONFIDENTIAL REPORT

CLIENT : Phatwe Consulting Engineers

PROJECT : Bospoort Pipeline

SCOPE : Condition Assessment and Current Drainage Testing

DATE : May 2019

REF : 6705/161259[1]

Responsibility rests with the reader to verify that this is the latest revision

Report by: _____


S Marais

Internal Review: _____


N C Webb







Reports are submitted to clients on a confidential basis;

No reference to the work or test results in any manner will be discussed or made public without written authorisation from the client;

All work is considered proprietary property of the client and is maintained by Isinyithi as such.

Disclaimer: Responsibility rests with the reader to verify the latest revision of the report.

Job Title Bospoort Condition Assessment
Document title Condition Assessment and Current Drainage Test
Project Number 161259
Document Reference 6705

| Revision | Date | Revision Description | | |
|----------|------------|-----------------------------------|--|---|
| 0 | 2019/05/14 | Issued for Information | Prepared By | Checked by |
| | | Name | S Marais | N Webb |
| | | Signature |  |  |
| 1 | 2019/06/24 | Addition of Bigen Africa Comments | Prepared By | Checked by |
| | | Name | S Marais | N Webb |
| | | Signature |  |  |

List of Associated Documentation

| List of Documents | | |
|--|--|-------------|
| Isinyithi Document Reference Number | Description | Date |
| 6705/161259 | Condition Assessment and Current Drainage Test | This Report |
| | | |

| | |
|---|----|
| Executive Summary | 6 |
| 1. INTRODUCTION | 7 |
| 2. METHODOLOGY | 7 |
| 3. RESULTS OF CONDITION ASSESSMENT OF THE PIPELINE OUTSIDE OF CHAMBERS. . | 8 |
| 3.1. Visual examination (Refer to Appendix 2 for photographs) | 8 |
| 3.2. Thickness measurements | 9 |
| 3.3. Pitting measurements | 9 |
| 4. POTENTIAL SURVEY and CURRENT DRAINAGE TEST | 10 |
| 5. CONCLUSIONS | 11 |
| 6. RECOMMENDATIONS | 11 |
| APPENDIX 1: LOCATION OF EXCAVATIONS | 12 |
| APPENDIX 2: Photographs | 13 |
| APPENDIX 3: Pipe to Soil Potential Graphs | 18 |
| ANNEXURE A: Condition Assessment of Valve Chambers (Bigen Africa) | 21 |
| 1. Chamber structures and accessories | 22 |
| 2. Pipework | 22 |
| 2.1. General | 22 |
| 2.2. Site water off-take downstream of Bospoort WTP High Lift Pumping Station | 22 |
| 2.3. Water meter installation downstream of Bospoort WTP High Lift Pumping Station | 22 |
| 2.4. Non-return valve installation at Bospoort WTP | 22 |
| 2.5. First air valve from Bospoort WTP | 22 |
| 2.6. Second air valve from Bospoort WTP | 22 |
| 2.7. Old cross-connection between Bospoort pipeline and Magalies Water Vaalkop pipeline | 23 |

Executive Summary

Isinyithi Cathodic Protection was appointed by Phatwe Consulting Engineers (on behalf of Rustenburg Water Services Trust) to provide a condition assessment of the 1.25km x 450mm diameter Bospoort pipeline.

The bitumen coating is intact other than where there was mechanical damage. Even though the bitumen adhesion is poor, there is minimal corrosion damage to the steel.

There is merit in not replacing this section and cathodically protecting it to prevent further corrosion.

1. INTRODUCTION

Isinyithi Cathodic Protection was appointed by Phatwe Consulting Engineers (on behalf of Rustenburg Water Services Trust) to provide a condition assessment of the 1.25km x 450mm diameter Bospoort pipeline.

Four sites were chosen for visual examination based on coating defects, soil conditions and concrete/soil interface in order to assess the pipe condition in areas of greatest risk. These sites were exposed and examined.

Condition assessment of the valve chambers themselves was undertaken by Bigen Africa. The findings are included as Annexure A

This report provides the findings of the investigation and current drainage tests performed by Mr N Webb, Mr S Marais, Ms N Nel and Ms K Mothoagae of Isinyithi.

2. METHODOLOGY

Defects D010 and D055 were pinpointed by means of DGPS based on the findings of the DCVG survey. The other two sites were a previous leak location and a concrete soil interface at the pump station IV chamber. The positions are shown in the attached Google Earth™ image in Appendix 1.

The sites were excavated by machine and hand to minimise any damage to the coatings during excavation.

The coating was then removed using scrapers and the underlying steel examined visually.

Wall thickness readings were taken using a UT thickness guage calibrated on a 3mm benchmark.

Pit depth was estimated using a vernier.

3. RESULTS OF CONDITION ASSESSMENT OF THE PIPELINE OUTSIDE OF CHAMBERS.

3.1. Visual examination (Refer to Appendix 2 for photographs)

Pump station chamber:

- There is a significant dent in the pipe with possible damage to the internal lining. The dent was not caused by the recent excavation.
- Moisture has penetrated between the bitumen coating and the steel.
- Minor pitting is evident at 3 locations in the excavated area.
- There was no accelerated corrosion visible adjacent to the concrete chamber wall.

D10:

- The extent of the coating damage at defect D10 is in line with the DCVG results (which indicated a significant defect).
- Minor pitting is evident at one location.
- Moisture has penetrated between the bitumen coating and the steel.
- White corrosion product evident at smaller defects, with no pitting evident.

D55:

- Continuity strap across VJ coupling not coated.
- Coating damage on either side of VJ coupling.
- Moisture has penetrated between the bitumen coating and the steel.
- VJ coupling bolts rusted.
- White corrosion product visible

Leak Site:

- Coating changes from sintakote to petrolatum tape to epoxy in excavation.
- Stub pipe welded to pipe (probably for lining repairs).
- New rust spots evident.
- White corrosion product at old coating damage, no pitting.

3.2. Thickness measurements

| Excavation | 450ø Steel Pipe Thickness (mm) | | | | Coating |
|------------------------|--------------------------------|-------|-------|--------|-----------------|
| | Top | Side1 | Side2 | Bottom | |
| Pump station chamber | 5.05 | 5.01 | 5.03 | 5.07 | Bitumen |
| | 5.01 | 5.05 | 5.02 | 5.00 | |
| | 5.14 | 5.07 | 5.08 | 5.09 | |
| D10 | 6.50 | 6.50 | 6.49 | 6.33 | Bitumen |
| | 6.48 | 6.49 | 6.43 | 6.35 | |
| | 6.46 | 6.47 | 6.44 | 6.33 | |
| D55 | 6.38 | 6.45 | 6.32 | 6.52 | Bitumen |
| | 6.30 | 6.39 | 6.33 | 6.57 | |
| | 6.33 | 6.33 | 6.40 | 6.57 | |
| Leak site (upstream) | 4.45 | 4.37 | 4.47 | | Sintakote |
| Leak site (middle) | 5.01 | 5.04 | 5.03 | | Petrolatum tape |
| Leak site (downstream) | 6.34 | 6.32 | 6.29 | | Epoxy |

Rusted VJ Coupling bolts measured diameters at defect D55 :

15.85mm, 15.41mm, 16.05mm and 16.09mm.

3.3. Pitting measurements

(Refer to photographs for “location”)

| Excavation | Pitting | | | | | |
|----------------------|----------|--------|------------|-----|-----|-----------|
| | Location | No. of | Depth (mm) | | | Area (mm) |
| | | | min | max | ave | |
| Pump station chamber | A | 1 | 1.2 | 1.2 | 1.2 | 35x15 |
| | B | 1 | 2.5 | 2.5 | 2.5 | 5x4 |
| | C | 1 | 1 | 1 | 1 | 4x4 |
| D10 | A | 22 | 0.3 | 2.5 | 1 | 100x70 |
| D55 | A | 20 | 0.2 | 1 | 0.3 | 120x80 |
| | B | 60 | 0.2 | 2.5 | 0.4 | 300x100 |
| Leak site | No pits | | | | | |

The observed pitting is not significant in terms of the residual strength of the pipeline and does not require MAOP reduction in terms of ASME B31G analysis.

4. POTENTIAL SURVEY and CURRENT DRAINAGE TEST

The purpose of the current drainage test is to determine the current requirement to provide complete cathodic protection to a pipeline.

The current drainage test is, in essence, a small-scale cathodic protection system which utilises a temporary groundbed, such as earth spikes, a fence or other buried steel structures. It is not necessary to fully protect the whole pipeline during a test, provided the area protected can be identified and the drainage current is known. The test was applied at AV 1. The pipeline potential with respect to soil was monitored during the test to evaluate the effect of the current drained.

Synchronised potential monitoring data loggers were connected to the pipe at the following locations (refer to Appendix 3 for data records) :

Pump station chamber (approx. km 0-000)

Excavation at D10 (approx. km 0-220)

Excavation at D55 (approx. km 0-680)

Excavation at leak site (approx. km 0-930)

Air Valve chamber 2 (approx. km 0-980)

Non return valve chamber (approx. km 1-200)

Current was drained at Air valve chamber 1 (approx. km 0-270) as follows :

| | |
|-------|------|
| 13h05 | 2A |
| 13h25 | 5A |
| 13h56 | 3.5A |
| 14h01 | 3A |
| 14h05 | 2.5A |
| 14h10 | 2A |
| 14h15 | 1.5A |
| 14h20 | 1A |
| 14h25 | 0.5A |

The potential measurements confirm that the pipeline is not subjected to significant stray current interference. This is not unexpected as there are no DC rail systems in the vicinity.

There is a break in continuity (presumably one or more un-bonded V-J couplings) between the leak site and the Magalies Water pipeline crossing. There is a current drain to the pump station as the effect of the current drainage test was noted upstream of the NRV chamber, and no insulating flanges could be located.

Full protection of the continuous section was achieved with a drainage current of 3.5A

Based on this data a current requirement of 3.3mA/m^2 is required to protect the pipe. This is likely to be less once the current drain to the pump station is removed by installing an insulating joint (IF kit).

5. CONCLUSIONS

- There is very little corrosion damage to the steel.
- The bitumen coating is intact other than for mechanical damage. Where it is intact, there is very little adhesion.
- Moisture has penetrated between the coating and the steel.
- There is evidence that the pipeline was under cathodic protection in the recent history.
- A current requirement equivalent to 3.3mA/m^2 is estimated to protect the pipe.
- The current requirement is likely to be less once the current drain at the pump station is removed by installing insulating flanges (IF kit).
- The pipeline is not electrically continuous between the leak site and the Magalies Water crossing.
- The pipeline is not influenced by stray current interference.

6. RECOMMENDATIONS

- It is recommended that the 1.25km section of pipeline not be replaced and that further corrosion should be mitigated by installing cathodic protection.
- Possible damage to the internal lining should be investigated at the significant dent in the pipeline next to the pump station chamber.
- The pipeline should be pressure tested prior to being put into service.
- A Cathodic Protection system will have to be designed to supply 3.3mA/m^2 in order to protect the pipeline.
- If the CP system is installed and maintained, there will still be a small, but finite risk of corrosion leaks in the future as there may be pitting damage on the pipe that has not been identified or evaluated.
- An IF kit needs to be installed at the pump station to electrically isolate it from the pipeline.
- The electrical continuity of the pipeline over its full length must be ensured.

APPENDIX 1: LOCATION OF EXCAVATIONS



APPENDIX 2: Photographs



Pump station chamber, pit A



Pump station chamber, pit B



Pump station chamber, pit C



Excavation at defect D10 pitting area



Excavation at defect D10 coating damage. Note the white corrosion product



Excavation at defect D55. Pitting area A (right), B (left). Note the rusted bolts.



Excavation at defect D55. Pitting area A.



Excavation at defect D55. Pitting area B.





Excavation at leak site. Epoxy coating damaged, no pitting. White corrosion product.




Excavation at leak site. Sintakote (left), petrolatum tape wrapping (right). No pitting.


APPENDIX 3: Pipe to Soil Potential Graphs





Bospoort - D55
Pipe-to-soil Potential Recording
17 April 2019



Bospoort - Leak site
Pipe-to-soil Potential Recording
17 April 2019





ANNEXURE A: Condition Assessment of Valve Chambers (Bigen Africa)

1. Chamber structures and accessories

Refer to the attached photos. Generally the chamber structures and accessories are in a good condition.

The following refurbishment work is recommended:

- New galvanised ladder in the non-return valve chamber at Bospoort WTP;
- Cleaning and re-galvanising of air vents where required;
- Roof slabs to be amended to allow easy access for authorised operation and maintenance but prevent unauthorised access;
- Clean all chambers and seal where ground water is seeping through walls.

2. Pipework

The following refurbishment work is recommended (refer to the attached photos):

2.1. General

- Replace all corroded bolts, nuts and washers.

2.2. Site water off-take downstream of Bospoort WTP High Lift Pumping Station

- Install new flange adaptors at the pressure reducing valves;
- Refurbish pressure reducing valves;
- New standby pressure reducing valve and new flow meter;
- Replace corroded 45° bend with a new one.

2.3. Water meter installation downstream of Bospoort WTP High Lift Pumping Station

Refer to attached “as-built” drawing.

- Assess the feasibility and accuracy of the existing flow meters;
- Install new pipework, with insulating flanges where specified by corrosion engineer;
- Investigate the outflow and disposal of the scoured water.

2.4. Non-return valve installation at Bospoort WTP

- Install new 300mm dia Class 25 non-return valve;
- Inspect pipework lining and coating and refurbish or replace if necessary;
- Install new flange adaptors;
- Install new 80mm dia class 25 air valve.

2.5. First air valve from Bospoort WTP

- Install new pipework and valves;
- Assess the off-take to the houses.

2.6. Second air valve from Bospoort WTP

- Install new pipework and valves.

- 2.7. Old cross-connection between Bospoort pipeline and Magalies Water Vaalkop pipeline
- Open the off-take Tee on the 450mm dia Bospoort pipeline and blank it off as close as possible to the pipeline.



Site water off-take downstream of Bospoort WTP high lift pumping station



Site water off-take downstream of Bospoort WTP high lift pumping station



Water meter and scour installation downstream of Bospoort WTP high lift pumping station



Non-return valve installation at Bospoort WTP



Non-return valve installation at Bospoort WTP



Non-return valve installation at Bospoort WTP



Non-return valve installation at Bospoort WTP



Non-return valve installation at Bospoort WTP



Non-return valve installation at Bospoort WTP




Non-return valve installation at Bospoort WTP



First air valve from Bospoort WTP



First air valve from Bospoort WTP



First air valve from Bospoort WTP




Second air valve from Bospoort WTP



Second air valve from Bospoort WTP



Old cross-connection between Bospoort pipeline and Magalies Water Vaalkop pipeline





CONTRACT NO: RLM/RWST/OMM/0102/2024/25 – RE-ADVERT:

CONSTRUCTION OF THE BOSPOORT BULK PIPELINE

C4.2 GEOTECHNICAL INFORMATION

RLM/RWST/OMM/0102/2024/25 - RE-ADVERT:

**APPOINTMENT OF A CONTRACTOR FOR THE
CONSTRUCTION OF THE BOSPOORT BULK PIPELINE**

Tender
Part C4: Site Information

C4.2-1

C4.2
Geotechnical Information

Employer

Witness 1

Witness 2

Contractor

Witness 1

Witness 2