

MEMBER		No OF	BARS PER MEMB	DIA.	LENGTH		TOTAL NUM- BER	MARK	S C	B E N D I N G				
										A	B	C	D	E/r
AREA 3 RETAINING WALL 3		8	51	Y12	2300	408	01	34	2200	(810) (720) 170	1050	170	(110)	
			51	Y10	2300	408	02	34	2200					
			12	Y10	10100	96	03	20	(10100)					
			12	Y10	10100	96	04	20	(10100)					
			51	Y12	1400	408	05	37	600					
			51	Y10	1200	408	06	37	500					
			51	Y10	1500	408	07	55	110					
			51	Y10	1250	408	08	35	1050					
			7	Y10	10100	56	09	20	(10100)					
			7	Y10	10100	56	10	20	(10100)					
			11	Y10	300	88	11	35	100					
			11	Y10	300	88	12	35	100					
SPlice BARS		7	12	Y10	1100	84	13	20	(1100)					
FOOTING START & END U-BARS		2	6	Y10	1150	12	14	38	500	170	(500)			
WALL END U-BARS		2	12	Y10	1150	24	15	38	500	170	(500)			
DOWEL BARS		7	7	R20	800	49	16	20	(800)					
	8	10	12	16	20	25	32	40	TOT	Date		2025/07/11		
R					97				97	Det. by		S. DEYSEL		
Y		3580	1340						4920	Ref Dwg				
TOT		3580	1340		97				5017	Job No		1006614		
ZUTARİ IMPACT. ENGINEERED.					PORT RICHARDS BAY AREA 3 RETAINING WALL 3 REBAR					Revision		T0		
										Schedule No		BS-RW-07A		