

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|---|----------|----------|-------------|-------------|
| | THE COMPLETION OF SHADED PARKING REPLACEMENT PROJECT | | | | |
| | The Model Preambles for Trades as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of and no claims arising from brevity of description of items fully described in the said Model Preamble will be entertained. | | | | |
| | The contractors prices for all items throughout these bills of quantities shall take account of and include for all of the obligations, requirements and specifications given in the Model Preambles and in any supplementary preamble | | | | |
| A | Preliminaries and General | | | | |
| | OHS Related Requirements - Safety File, PPE etc | Item | 1,00 | R 8 000,00 | R 8 000,00 |
| | Contractors site establishment, dis-establishment etc complete, Including Hoarding during works as per ACSA standards. | Item | 1,00 | R 15 000,00 | R 15 000,00 |
| | ACSA Issue Permits & Induction Costs - Reimbursed Based on Proven Costs - No Mark Up Allowed | Prov Sum | 1,00 | R 20 000,00 | R 20 000,00 |
| B | Landside | | | | |
| 1 | Replace 8 bent existing palisade panels with new | No | 8,00 | | |
| 2 | Landside Walkway Remove rusted roof sheets and replace with new galvanized roof sheets, any fasteners used to be galvanized and on completion roofing to be leak free. Zinalume AZ200 2m wide x 6m long | No | 5,00 | | |
| 3 | Landside Walkway Replace damaged Metal Grey painted 3m down pipe, including shoe, PVC down pipes | No | 5,00 | | |
| 4 | Landside Walkway Any gutters, rusted structure to be replaced with new. The galvanizing is to be carried out to SABS ISO 1461 (SABS 763) standards and guaranteed for 15 years, Surface treatment: Hot dipped galvanized (500g/m ² , 70um). | Item | 1,00 | | |
| 5 | Under cover parking in front of car rental building Parking Bay 3 Remove rusted roof sheets, replace rusted roof sheets with new Zinalume AZ200 sheets min. 2mm thick 2m wide x 6 meters long. All fasteners used to be galvanized. On completion roofing to be leak free. Galvanizing is to be carried out to SABS ISO 1461 (SABS 763) standards and guaranteed for 15 years, Surface treatment: Hot dipped galvanized (500g/m ² , 70um). | No | 55,00 | | |
| 6 | Paint disabled parking bays with Yellow Plascon road marking paint or similar | No | 8,00 | | |
| 7 | Mount on a galvanized pole embedded in concrete, disabled sign at each disabled parking. | No | 8,00 | | |
| 8 | Inside each disabled parking bay paint on the tar in yellow with road marking paint disabled sign | No | 6,00 | | |
| | Shaded Net parking | | | | |
| 9 | Removal of existing Shade Net Structure and replacement with new 6m x 6m Double Vehicle Carport | No | 12,00 | | |
| 10 | Removal of metal supports from former signage, including backfilling ground surface | No | 4,00 | | |
| 11 | PROVISIONAL SUM Provide the amount of R 35 000.00 (thousand rand) for coating of Steel Structures at VIP, Departure & Arrivals Walkways, including surface preparation as per manufacturers recommendations | Item | 1,00 | R 35 000,00 | R 35 000,00 |
| | PRICE SUMMARY | | | | |
| A | SUB TOTAL FOR THE WORKS - EXCLUDING VAT | | | | R |
| B | VALUE ADDED TAX - VAT AT 15% OF A | | | | R |
| C | TOTAL PRICE FOR THE WORKS - INCLUDING VAT - A + B (Price transferred to Form of Offer) | | | | R |