



6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F", "V", "T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

**Carried to Collection**

Section 1  
Bill No. 1  
Preliminaries

R

**SECTION A: PRINCIPAL BUILDING AGREEMENT**

**DEFINITIONS**

Definitions and interpretation (Clause 1).

1 F: ..... V: ..... T: .....

Item

**OBJECTIVE AND PREPARATION**

Offer, acceptance and performance (Clause 2).

2 F: ..... V: ..... T: .....

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: ..... V: ..... T: .....

Item

Design responsibility (Clause 4).

4 F: ..... V: ..... T: .....

Item

Employer's agents (Clause 5).

5 F: ..... V: ..... T: .....

Item

Site representative (Clause 6).

6 F: ..... V: ..... T: .....

Item

Compliance with regulations (Clause 7).

7 F: ..... V: ..... T: .....

Item

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

	Works risk (Clause 8)		
8	F: ..... V: ..... T: .....  Indemnities (Clause 9).  Clause 9.1.1 is deleted and substituted with:  Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.	Item	
9	F: ..... V: ..... T: .....  Works insurances (Clause 10).	Item	
10	F: ..... V: ..... T: .....  Liability insurances (Clause 11).	Item	
11	F: ..... V: ..... T: .....  Effecting insurances (Clause 12).	Item	
12	F: ..... V: ..... T: .....  State Provisions (Clause 13).	Item	
13	F: ..... V: ..... T: .....  Security (Clause 14).	Item	
14	F: ..... V: ..... T: .....  <b><u>EXECUTION</u></b>  Preparation for and execution of the works (Clause 15).	Item	
15	F: ..... V: ..... T: .....  Access to the works (Clause 16).	Item	
16	F: ..... V: ..... T: .....	Item	
<b>Carried to Collection</b>			R
Section 1 Bill No. 1 Preliminaries			



	Contract instructions (Clause 17).			
17	F: ..... V: ..... T: .....  Setting out of the works (Clause 18.3).  The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item		
18	F: ..... V: ..... T: .....  Assignment (Clause 19).	Item		
19	F: ..... V: ..... T: .....  Nominated subcontractors (Clause 20).	Item		
20	F: ..... V: ..... T: .....  Selected subcontractors (Clause 21).	Item		
21	F: ..... V: ..... T: .....  Employer's Direct contractors (Clause 22).	Item		
22	F: ..... V: ..... T: .....  Contractor's Domestic subcontractors (Clause 23).	Item		
23	F: ..... V: ..... T: .....  <b><u>COMPLETION</u></b>  Practical completion (Clause 24).	Item		
24	F: ..... V: ..... T: .....  Works completion (Clause 25).	Item		
<b>Carried to Collection</b>			R	
Section 1 Bill No. 1 Preliminaries				

25	<p>F: ..... V: ..... T: .....</p> <p>Final completion (Clause 26).</p> <p>Latent defects liability period (Clause 27).</p> <p>Clause 27.0 is amended by the addition of the following clauses:</p> <p>"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".</p> <p>"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"</p>	Item		
26	<p>F: ..... V: ..... T: .....</p> <p>Sectional completion (Clause 28).</p>	Item		
27	<p>F: ..... V: ..... T: .....</p> <p>Revision of date for practical completion (Clause 29).</p>	Item		
28	<p>F: ..... V: ..... T: .....</p> <p>Penalty for non-completion (Clause 30).</p>	Item		
29	<p>F: ..... V: ..... T: .....</p> <p><b><u>PAYMENT</u></b></p> <p>Interim payment to the contractor (Clause 31).</p> <p>The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.</p>	Item		
<b>Carried to Collection</b>			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

Recovery of expense and loss (Clause 33).

31	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

Final account and final payment (Clause 34).

32	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

Payment to other parties (Clause 35).

33	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

### **CANCELLATION**

Cancellation by Employer - Contractor's default (Clause 36).

34	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

Cancellation by Employer - Loss and damage (Clause 37).

35	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

Cancellation by Contractor - Employer's default (Clause 38).

36	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

Cancellation - Cessation of the works (Clause 39).

37	F: ..... V: ..... T: .....	Item	
----	----------------------------	------	--

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

**DISPUTE**

Dispute Settlement (Clause 40)

38 F: ..... V: ..... T: .....

Item

**SUBSTITUTE PROVISIONS**

State Clauses (Clause 41)

39 F: ..... V: ..... T: .....

Item

**CONTRACT VARIABLES**

The Schedule: Pre-Tender information (Clause 42).

40 F: ..... V: ..... T: .....

Item

**CONTRACTING AND OTHER PARTIES (Clause 42.1)**

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

Principal Agent: Blue Polar

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

**Carried to Collection**

**R**

Section 1  
Bill No. 1  
Preliminaries

**CONTRACT DETAILS (Clause 42.2)**

Clause 42.2.1

Works Description: Construction of new ablution facilities.

Clause 42.2.2

Site Description: The site is the existing school.

Clause 42.2.3

Work or Installations by Others: NIL

Clause 42.2.4

This Agreement is for a State Contract :- Yes

Payment will be made for materials and goods:- Yes

Dispute resolution :- Abitration.

Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A

Clause 42.2.5

Date on which possession of the site is intended to be given on :-

To be advised.

Clause 42.2.6

Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days.

Completion in Sections are required : NO

Clause 42.2.7

Intended date of practical completion and the penalty per calendar day for the works as a whole :-

**Carried to Collection**

Section 1  
Bill No. 1  
Preliminaries

R

To be advised.

Penalty amount will be R2000/day.

Clause 42.2.8

Intended dates of practical completion and the penalties per calendar day for the works in sections :

N/A

Clause 42.2.9

The law applicable to this agreement shall be that of - Republic of South Africa.

**INSURANCES (Clause 42.3)**

Clause 42.3.1

Contract works insurance to be effected by Contractor for the sum of: Contract Sum

With a deductible of : Not exceeding 5% of each and every claim.

Clause 42.3.2

Supplementary insurance is required : Yes

SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible of 5%).

Clause 42.3.3

Public liability insurance to be effected by Contractor

For the amount of: R 5million

With a deductible of: Not exceeding 5% of each and every claim.

**DOCUMENTS (Clause 42.4)**

Clause 42.4.1

**Carried to Collection**

Section 1  
Bill No. 1  
Preliminaries

R

Waiver of the contractor's lien is required :- YES

Clause 42.4.2

Number of construction document copies to be supplied to the Contractor free of charge :- 1

Clause 42.4.3

Bills of Quantities drawn up in accordance with :-

Standard System of Measuring Building Work - Seventh Edition including all amendments

Clause 42.4.4

Number of days for submission of priced documents : 5 working days from the Letter of Appointment.

Clause 42.4.5

JBCC Engineering General Conditions are to be included in the documents :- No

Clause 42.4.6

The contract value is to be adjusted using CPAP:- NO

**SECTION B: PRELIMINARIES**

**DEFINITIONS AND INTERPRETATION (B1)**

Definitions and Interpretation (B1)

41 F: ..... V: ..... T: .....

**DOCUMENTS (B2)**

Checking of documents (B2.1)

Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.

**Carried to Collection**

Section 1  
Bill No. 1  
Preliminaries

Item

R

42	F: ..... V: ..... T: .....  Provisional Bills of Quantities (B2.2) YES  Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.	Item		
43	F: ..... V: ..... T: .....  Availability of construction documentation (B2.3)	Item		
44	F: ..... V: ..... T: .....  Interests of Agents (B2.4)	Item		
45	F: ..... V: ..... T: .....  Priced documents (B2.5)	Item		
46	F: ..... V: ..... T: .....  Tender submission (B2.6)  Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.	Item		
47	F: ..... V: ..... T: .....  <b><u>THE SITE (B3)</u></b>  Defined works area (B3.1)  The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.  Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.	Item		
<b>Carried to Collection</b>			R	
Section 1 Bill No. 1 Preliminaries				



	The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.			
48	F: ..... V: ..... T: .....  Geotechnical investigation (B3.2)  A desktop geotechnical report is available upon request.	Item		
49	F: ..... V: ..... T: .....  Inspection of the Site (B3.3)	Item		
50	F: ..... V: ..... T: .....  Existing premises occupied (B3.4)	Item		
51	F: ..... V: ..... T: .....  Previous work - dimensional accuracy (B3.5)	Item		
52	F: ..... V: ..... T: .....  Previous work - defects (B3.6)	Item		
53	F: ..... V: ..... T: .....  Services - known (B3.7)	Item		
54	F: ..... V: ..... T: .....  Services - unknown (B3.8)	Item		
55	F: ..... V: ..... T: .....  Protection of trees (B3.9)	Item		
56	F: ..... V: ..... T: .....  Articles of value (B3.10)	Item		
57	F: ..... V: ..... T: .....  Inspection of adjoining properties (B3.11)	Item		
<b>Carried to Collection</b>			R	
Section 1 Bill No. 1 Preliminaries				

58	F: ..... V: ..... T: .....	Item		
<b><u>MANAGEMENT OF CONTRACT (B4)</u></b>				
	Management of the Works (B4.1)			
59	F: ..... V: ..... T: .....	Item		
	Programme for the Works (B4.2)			
60	F: ..... V: ..... T: .....	Item		
	Progress meetings (B4.3)			
61	F: ..... V: ..... T: .....	Item		
	Technical meetings (B4.4)			
62	F: ..... V: ..... T: .....	Item		
<b><u>SAMPLES AND SHOP DRAWINGS (B5)</u></b>				
	Samples of materials (B5.1)			
63	F: ..... V: ..... T: .....	Item		
	Workmanship samples (B5.2)			
64	F: ..... V: ..... T: .....	Item		
	Shop drawings (B5.3)			
65	F: ..... V: ..... T: .....	Item		
<b><u>TEMPORARY WORKS AND PLANT (B6)</u></b>				
	Deposits and fees (B6.1)			
66	F: ..... V: ..... T: .....	Item		
	Enclosure of the works (B6.2)			
<b>Carried to Collection</b>				
Section 1 Bill No. 1 Preliminaries			R	

-15-

	Plant and equipment (B6.4)		
69	F: ..... V: ..... T: ..... Main notice board (B6.5) One notice board shall be provided by the Contractor	Item	
70	F: ..... V: ..... T: ..... Subcontractors notice board (B6.6) (N/A)	Item	
71	F: ..... V: ..... T: ..... <b><u>TEMPORARY SERVICES (B7)</u></b> Location (B7.1)		
72	F: ..... V: ..... T: ..... Water (B7.2) The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item	
73	F: ..... V: ..... T: ..... Electricity (B7.3) The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item	
74	F: ..... V: ..... T: ..... Telecommunication equipment (B7.4) The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item	
75	F: ..... V: ..... T: .....	Item	
	<b>Carried to Collection</b>		R
	Section 1 Bill No. 1 Preliminaries		



[illegible]

## **SECTION C: SPECIFIC PRELIMINARIES**

### **Section C: Specific Preliminaries:**

#### **C1. Proprietary branded products**

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: ..... V: ..... T: .....

Item

#### **C2. Trade Names, etc.**

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: ..... V: ..... T: .....

Item

#### **C3. Contractors responsibility**

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: ..... V: ..... T: .....

Item

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

<p>C4. Overtime</p> <p>Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.</p>			
<p>97 F: ..... V: ..... T: .....</p>	<p>Item</p>		
<p>C5. As built drawings</p> <p>The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.</p> <p>Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.</p>			
<p>98 F: ..... V: ..... T: .....</p>	<p>Item</p>		
<p>C6. Construction Instructions</p> <p>Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:</p> <p>a) Construction Instruction Book:</p> <p>Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.</p> <p>Only instructions issued in such book shall be recognised.</p> <p>b) Daily Record Book:</p>			
<p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section 1 Bill No. 1 Preliminaries</p>		<p>R</p>	



	<p>The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.</p>			
99	<p>F: ..... V: ..... T: .....</p> <p>C7. Labour record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.</p>	Item		
100	<p>F: ..... V: ..... T: .....</p> <p>C8. Plant record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.</p>	Item		
101	<p>F: ..... V: ..... T: .....</p> <p>C9. Encroachment</p> <p>During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.</p>	Item		
102	<p>F: ..... V: ..... T: .....</p> <p>C10. Method Statement</p>	Item		
<b>Carried to Collection</b>			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

	<p>The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.</p>			
103	<p>F: ..... V: ..... T: .....</p> <p>C11. Unauthorised Persons/Workmen on Premises</p> <p>The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect.</p> <p>No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.</p>	Item		
104	<p>F: ..... V: ..... T: .....</p> <p>C12. Mode of Procedure</p> <p>Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.</p> <p>Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.</p>	Item		
105	<p>F: ..... V: ..... T: .....</p>	Item		
<b>Carried to Collection</b>			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

	<p>C13. Location of Temporary Buildings and Temporary Services</p> <p>The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period.</p> <p>There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.</p>			
106	<p>F: ..... V: ..... T: .....</p> <p><b><u>C14. Office accommodation</u></b></p> <p>The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]</p>	Item		
107	<p>F: ..... V: ..... T: .....</p> <p><b><u>C15. Storage Facilities</u></b></p>	Item		
108	<p>The Contractor shall provide a Container for storage of materials.</p>	Item		
109	<p>F: ..... V: ..... T: .....</p> <p>C16. Removal and Making Good of Temporary Works, etc, on Completion</p> <p>The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.</p>	Item		
110	<p>F: ..... V: ..... T: .....</p>	Item		
<b>Carried to Collection</b>			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

111 SUB - TOTAL: FIXED ITEMS

Item

112 SUB - TOTAL: VALUE - RELATED ITEMS

Item

113 SUB - TOTAL: TIME - RELATED ITEMS

Item

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

Section 1

Bill No. 1

Preliminaries

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

**Carried Forward**

**R**

Section 1

Bill No. 1

Preliminaries

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

[illegible]



The costs included herein must incorporate Community Liaison Officer (CLO).

**OCCUPATIONAL HEALTH AND SAFETY**

**General:**

1	Preparation of Contractor's site specific Health and Safety Plan.	Item
2	Submission of the Health and Safety File.	Item
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.	Item
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.	Item
5	Provision of full time Health and Safety Officer for the entire construction period.	Item
6	Induction training of personnel.	No
7	Provision of first aid boxes.	No

**Provision for Personal Protective Equipment and Protective Clothing:**

8	Reflective vests.	No
9	Hard hats.	No
10	Protective foot wear.	No
11	Ear Plugs.	No
12	Dust Masks.	No

**Costs of Medical Certificates and Medical Surveillance:**

13	Initial (baseline) medical examinations.	No
14	Exit Examinations.	No

**Carried to Collection**

Section 1  
Bill No. 2  
Health and Safety

R



**Noise Monitoring:**

- |    |                               |    |
|----|-------------------------------|----|
| 15 | Establishment of noise zones. | No |
| 16 | Audiograms.                   | No |

**C16. Covid-19 Compliance Measures**

- |    |  |      |
|----|--|------|
| 17 | The Contractor is required to price for Covid 19 compliance and the pricing thereof shall be deemed to include all the mandatory requirements. | Item |
|----|--|------|

**Carried to Collection**

**R**

Section 1  
Bill No. 2  
Health and Safety

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

Section 1

Bill No. 2

Health and Safety

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

27

28

29

**Carried Forward to Summary of Section No. 1**

R

Section 1

Bill No. 2

Health and Safety

Section 1



**Removal of asbestos material**

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

**The following shall apply in respect of asbestos removal**

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

**Carried to Collection**

Section 2  
Bill No. 1  
Demolitions

R

**DEMOLISHING AND REMOVING**

1	Demolish pit latrine structure comprising of brick/block work with asbestos roof sheeting, approximate size 8 x 6m wide with 3,5m high top structure and 2,0m deep pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured).	No	1		
2	Demolish pit latrine structure comprising of brick/block work with asbestos roof sheeting, approximate size 7 x 6.5m wide with 3,5m high top structure and 2,0m deep pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured).	No	1		
3	Cart away rubble from demolitions and dispose off site.		Item		
4	Backfill existing hole with G7 fill material in max. 150mm layers and compact to 95% MOD AASHTO density.	m3	50		
5	Allow for compaction tests by an approved laboratory to determine density of filling material.	No	4		
6	Provision of a certificate of safe disposal for asbestos.		Item		

**SUNDRIES**

**Desludging**

7	Clean out pit latrine by desludging including removal of all debris and waste including solid waste as per Health and Safety requirements and make good on completion including disposing of all debris and waste at an authorised municipal waste disposal facility. Contractor to price per seat	No	16		
8	Issue of Certificate of Waste Disposal.		Item		

**Carried to Collection**

R

Section 2  
Bill No. 1  
Demolitions

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

Section 2

Bill No. 1

Demolitions

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

32

33

34

**Carried to Final Summary**

R

Section 2  
Bill No. 1  
Demolitions





**Responsibility for site**

The Contractor is to note that upon possession of the site by himself, and extending until practical completion is achieved, he is solely responsible for the site, site security, general upkeep and cleaning of the site and all other responsibilities in maintaining a construction site in conformance with but not limited to, the Construction Regulations 2014, all local by-laws, all user client regulations, and all Client regulations and procedures. Tenderers are therefore urged to study all available material and to investigate the site fully and areas contiguous to the site, in order to determine the range and extent of responsibility. No additional monetary and/or time claims will be entertained in respect of the above

**Explosives**

No explosives whatsoever may be used for demolition purposes unless otherwise stated

**General**

The Contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum amount of disturbance to adjoining classroom blocks and their students. He shall provide proper protection of the works and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the Principal Agent

Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the Principal Agent

**Carried to Collection**

R

Section 3  
Bill No. 1  
Alterations (Provisional)

Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before refixing including taking off, easing and rehanging, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-varnishing is given separately

**"Taking out and removing doors, windows, etc"**

implies that the door, etc is to be carefully taken down together with the fame, linings, architraves, window sills, etc complete and where brick lintels occur, it must be supported and propped until the openings are built up or new doors or windows built in position

Prices for taking out and removing doors and frames shall include for removing door stops, cabin hooks, etc. and making good floor and wall finishes to match existing

**"Forming openings"** for doors or windows, etc implies that the plaster or any other covering is to be hacked off and an opening formed sufficient in size to receive the building in of the frame and cramps, and the forming of new dampproof courses, lintels, sills, etc. After building in of the new frame, the opening is to be built against the frame, plaster or faced brickwork to be made good both sides and reveals and floor screeds prepared for finishings to match existing

**"Making good"** implies that all necessary repairs are to be made to reinstate articles that may be damaged through the removal or otherwise, and the supplying of any new materials to match existing work, and is to include any necessary repairs to adjacent finishings such as floors, skirtings, plaster, painting, etc and such making good is to match adjoining work in all respects and in all trades

The Contractor will be required to take all dimensions affecting the existing buildings on the site and he will be held solely responsible for the accuracy of all such dimensions where used in the manufacture of new items (doors, windows, fittings, etc)

**Carried to Collection**

Section 3  
Bill No. 1  
Alterations (Provisional)

R

The Contractor to acknowledge that sequencing of the work will be necessary to accommodate the operational aspects of the school. The Contractor to accordingly factor the above requirement in the construction programme and pricing

**"Breaking down and removing"** walls, etc implies that the wall is to be taken down to the extent shown on the drawings or as may be described and that all necessary shoring is to be provided and allowed for to ensure the safety of the building during the pulling down or until new walls are erected and all portions of the remaining walls where disturbed or affected by the removal are to be made good and left ready for plaster or other finishings as described

Where removal is included in the heading, sub-heading or item description, prices shall be deemed to include for the necessary costs of removal and appropriate disposal of materials including but not limited to labour, transportation and disposal costs. No further claims in this regard will be entertained

**"Building up openings"** implies that after the removal of any doors, windows or screens that may be described to be taken down, the opening is to be filled up solid (or to the thickness as shown) with new brickwork and is to include all necessary cutting away to form openings to thoroughly bond to the new work and new finishes to both sides as described.

**Removal of asbestos material**

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

**Carried to Collection**

Section 3  
Bill No. 1  
Alterations (Provisional)

R

**The following shall apply in respect of asbestos removal**

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

**Carried to Collection**

Section 3  
Bill No. 1  
Alterations (Provisional)

R

**REMOVAL OF EXISTING WORK**

**Taking out and removing doors, windows, etc, including thresholds, sills, etc and building up openings in face brick walls, including making good to face brick.**

1	Remove window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01.	No	4
2	Carefully remove and set aside for reuse, window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01.	No	4
3	Reinstall window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01.	No	4

**Taking down and removing roofs, floors, panelling, ceilings, partitions, etc completely**

4	Fibre cement fascia boards and fixings	m	12
5	Fibre cement barge boards and fixings	m	12
6	Pvc rainwater gutters and fixings	m	34

**Carried to Collection**

Section 3  
Bill No. 1  
Alterations (Provisional)

R

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

Section 3

Bill No. 1

Alterations (Provisional)

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

36

37

38

39

40

41

**Carried to Final Summary**

R

Section 3

Bill No. 1

Alterations (Provisional)



**Face bricks**

Bricks shall be ordered timeously to obtain uniformity in size and colour

**Pointing**

Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc

**Samples**

Samples of all masonry building units, except those of walls described as "loadbearing", shall consist of a minimum of 6 units. Samples of building units to be used in walls described as "loadbearing" shall consist of 30 units from every 30 000 units delivered to site

**Trade names**

Where trade names are specified it will read "or equal approved"

**Carried to Collection**

**R**

Section 4  
Bill No. 1  
Masonry



**BRICKWORK AND BLOCKWORK SUNDRIES**

**Galvanized brickwork reinforcement**

1	115mm Wide reinforcement built in horizontally	m	39
	A0 : 0      A1 : 39      A6 : 0      AD : 0		
2	230mm Wide reinforcement built in horizontally.	m	39
	A0 : 0      A1 : 39      A6 : 0      AD : 0		

**FACE BRICK**

**"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):**

3	Half brick wall in beam filling pointed one side including cutting and fitting around roof timbers and bedding roofing solid on top in cement mortar.	m2	10
	A0 : 0      A1 : 10      A6 : 0      AD : 0		
4	One brickwall pointed on both sides.	m2	10
	A0 : 0      A1 : 0      A6 : 10      AD : 0		
5	Half brickwall pointed on both sides.	m2	8
	A0 : 0      A1 : 0      A6 : 8      AD : 0		

**Brick-on-edge header course copings, sills, etc. of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:**

6	220mm Brick on edge sill bedded sloping and jointed in cement mortar and pointed on top, edge and projecting soffit including cutting and fitting between reveals and splay cutting brickwork under.	m	5
	A0 : 0      A1 : 5      A6 : 0      AD : 0		
7	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on both sides.	m	6
	A0 : 6      A1 : 0      A6 : 0      AD : 0		

**Carried to Collection**

Section 4  
Bill No. 1  
Masonry

R

Section 4

Bill No. 1

Masonry

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

43

44

45

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 1

Masonry



Contractor to provide water proofing product that will be 100% resistant to extreme hydrostatic pressure at depth of 2m, from the positive (water from inside) of substrate. Resistant to aggressive chemicals i.e oil, salt water, sewage, weak acids and aggressive sulphate soils. The product must be able to withstand backfilling without protection and must not be subject to deterioration. The product must be able to ensure that the pit structure is fully sealed (100% free from water ingress from outside and it will not penetrate the pit).

The product and its methodology for application must be approved by Principal Agent before it is used.

It is a mandatory requirement for the Contractor to attend training to be provided by Supplier. Proof of attendance will be required prior to application of the approved waterproofing product.

Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent or Engineer. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the waterproofing product is intended to be done.

Contractor to provide a Letter of Compliance confirming that waterproofing has been applied as per Manufacturer's instructions and data sheet.

#### **DAMPPROOFING OF WALLS AND FLOORS**

**One layer of 350 micron embossed dampcourse waterproof sheeting below walls, sills, etc:**

1	Below walls, sills, etc.	m2	5		
	A0 : 5      A1 : 0      A6 : 0      AD : 0				

#### **JOINT SEALANTS ETC**

**Clear Neutral silicone sealant:**

2	In joint sealing and pointing all round external window and door frames.	m	188		
	A0 : 188      A1 : 0      A6 : 0      AD : 0				

**Carried to Collection**

Section 4  
Bill No. 2  
Waterproofing

R

Section 4

Bill No. 2

Waterproofing

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

47

48

**Amount**

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 2

Waterproofing



**CARPENTRY**

**Sundries:**

- |   |  |    |    |  |
|---|--|----|----|--|
| 1 | TRI FIX or equal approved hurricane clip fixed using 10 x 32mm galvanised clout nails (Provisional). | No | 15 |  |
|   | A0 : 0      A1 : 0      A6 : 0      AD : 15  |    |    |  |

**EAVES, VERGES, ETC**

**"Everite Nutec" or equal approved fibre cement**

- |   |   |   |    |  |
|---|---|---|----|--|
| 2 | 12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc.                   | m | 12 |  |
|   | A0 : 12      A1 : 0      A6 : 0      AD : 0   |   |    |  |
| 3 | 85 x 275 x 6mm Barge board drilled and brass screwed to purlin ends including galvanised steel H-profile jointing strips, screws, holes, etc. | m | 12 |  |
|   | A0 : 12      A1 : 0      A6 : 0      AD : 0   |   |    |  |

**Carried to Collection**

Section 4  
Bill No. 3  
Carpentry and Joinery

R

Section 4

Bill No. 3

Carpentry and Joinery

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

50

51

**Amount**

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 3

Carpentry and Joinery





**HANDLES**

- |   |   |    |    |  |
|---|---|----|----|--|
| 1 | "Dorma DPH301B" or equal approved Stainless Steel Straight Tubular Pull handle flange fixing. | No | 21 |  |
|   | A0 : 6      A1 : 5      A6 : 3      AD : 7  |    |    |  |

**Sundries:**

- |   |   |    |    |  |
|---|---|----|----|--|
| 2 | Stainless Steel Hat and coat hook, code DHC - SS-030-A or equal approved. | No | 14 |  |
|   | A0 : 3      A1 : 3      A6 : 2      AD : 6                                |    |    |  |
| 3 | 38mm Diameter black rubber door stop plugged and screwed to wall.         | No | 24 |  |
|   | A0 : 6      A1 : 8      A6 : 3      AD : 7                                |    |    |  |

**SIGN PLATES:**

**All sign plates are to be with engraved blue perspex all in accordance with the standard sign plates for Schools.**

- |   |  |    |   |  |
|---|--|----|---|--|
| 4 | Sign plate plugged and screwed to walls with chromium plated dome headed screws. | No | 7 |  |
|   | A0 : 3      A1 : 2      A6 : 1      AD : 1                                       |    |   |  |

**SUNDRIES**

**Grade 304 stainless steel ware:**

- |   |  |    |   |  |
|---|--|----|---|--|
| 5 | 32mm outside diameter x 1,6mm thick tubular wall mounted side stainless steel grab rail 1,06m girth with two 45 degree and two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews. | No | 2 |  |
|   | A0 : 1      A1 : 1      A6 : 0      AD : 0   |    |   |  |
| 6 | 32mm outside diameter x 1,6mm thick tubular wall mounted around cistern back stainless steel grab rail 1,23m girth with two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews.    | No | 2 |  |
|   | A0 : 1      A1 : 1      A6 : 0      AD : 0   |    |   |  |

**Carried to Collection**

Section 4  
Bill No. 4  
Ironmongery

R

**Satin Grey Plastics or equal approved**

- 7 "Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose.

A0 : 2      A1 : 2      A6 : 2      AD : 2

No

8

**Take delivery (free issued materials) and install :  
Solid Cast brass taps, valves, etc:**

- 8 "Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose.

A0 : 2      A1 : 2      A6 : 2      AD : 2

No

8

**Carried to Collection**

R

Section 4  
Bill No. 4  
Ironmongery

Section 4

Bill No. 4

Ironmongery

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

53

54

55

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 4

Ironmongery



### **ALUMINIUM WINDOWS**

All aluminium windows are to be manufactured by manufacturers who are members of AAAMSA. All aluminium systems to be approved by AAAMSA.

All aluminium work is to be protected by covering with plastic sheeting fixed with low tack adhesive prior to leaving the factory. Plastic sheeting is to remain in place during construction.

All glazing shall be in accordance with SABS 0400 - 1990, SABS 1263 - 1. All safety glazing materials (individual panes) shall be permanently marked. Such marking shall be visible after glazing process. If it is not marked, it is not safety glass.

#### **Bronze anodised aluminium windows glazed with 6.38mm safety laminated glass and plugged to brickwork:**

- |   |   |    |   |  |
|---|---|----|---|--|
| 1 | Window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01. | No | 4 |  |
|   | A0 : 0      A1 : 0      A6 : 0      AD : 4  |    |   |  |

### **HOT DIP GALVANIZED STEEL GATES**

Note: The contractor is to check on site measurements before placing of order.

#### **Security Gate consisting of 25 x 25 x 2mm galvanised mild steel frame with 12mm galvanised mild steel square bars infill placed at 109mm centres, hung with one pair of galvanised mild steel hinges including locks, handles, ironmongery complete and fixed to brickwork:**

- |   |   |    |   |  |
|---|---|----|---|--|
| 2 | Security gate size 900 x 2050mm high (G1).    | No | 4 |  |
|   | A0 : 1      A1 : 1      A6 : 1      AD : 1    |    |   |  |
| 3 | Security double gate size 1800 x 2050mm high. | No | 1 |  |
|   | A0 : 1      A1 : 0      A6 : 0      AD : 0    |    |   |  |

### **LOCKABLE MANHOLE COVERS**

- |   |   |    |   |  |
|---|---|----|---|--|
| 4 | 600mm diameter lockable circular type M4A product or similar approved manhole SANS 1882 medium duty Dough Moulding compound 4A hinged lid and frame cast into concrete upstand. | No | 4 |  |
|   | A0 : 0      A1 : 4      A6 : 0      AD : 0  |    |   |  |

**Carried to Collection**

Section 4  
Bill No. 5  
Metalwork

R

**Take delivery (free issued materials) and install**

- 5 600mm diameter lockable circular type M4A product or similar approved manhole SANS 1882 medium duty Dough Moulding compound 4A hinged lid and frame cast into concrete upstand.

A0 : 0      A1 : 4      A6 : 0      AD : 0

No

4

**Carried to Collection**

R

Section 4  
Bill No. 5  
Metalwork

Section 4

Bill No. 5

Metalwork

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

57

58

59

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 5

Metalwork





Item No		Quantity	Rate	Amount
	<b><u>SECTION 3</u></b>			
	<b><u>BILL No. 10</u></b>			
	<b><u>PLUMBING AND DRAINAGE</u></b>			
	<b><u>(PROVISIONAL)</u></b>			
	<b><u>Quantity Split:</u></b>			
	Note that the total quantity per each item is split into the various buildings and appears below each description as follows:			
	A0 - DWG 04 - Staff Ablutions			
	A1 - DWG 06 - Grade R Ablutions			
	A6 - DWG 14 - Male Ablutions			
	AD - DWG 35 - Female Ablutions			
	<b><u>MODEL PREAMBLES</u></b>			
	The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
	<b><u>RAINWATER DISPOSAL:</u></b>			
	<b><u>Watertite or equal approved Aluminium Gutters and Downpipes:</u></b>			
1	125 x 85 x 0.6mm Ogee domestic gutters including gutter brackets at 600mm centres. A0 : 10      A1 : 8      A6 : 7      AD : 9	m	34	
2	Extra over eaves gutter for stopped end. A0 : 2      A1 : 2      A6 : 2      AD : 2	No	8	
3	Extra over eaves gutter for outlet for 100 x 75mm aluminium downpipe. A0 : 2      A1 : 2      A6 : 2      AD : 2	No	8	
4	100 x 75 x 0.6mm rectangular fluted downpipes fixed to wall with and including proprietary holderbats to 5000L rainwater tanks (elsewhere measured). A0 : 8      A1 : 8      A6 : 8      AD : 8	m	32	
	<b>Carried to Collection</b>			
	Section 4			
	Bill No. 7			
	Plumbing and Drainage (Provisional)			
			R	

5	Extra over rainwater downpipe for bends. A0 : 4      A1 : 4      A6 : 4      AD : 4	No	16
<b><u>TAPS, VALVES, ETC</u></b>			
<b><u>Solid Cast brass taps, valves, etc:</u></b>			
6	"Cobra KM2-200" or other approved 15mm chrome plated metered bib tap with non-hold open feature and flow controller. A0 : 0      A1 : 0      A6 : 0      AD : 2	No	2
7	15mm Ball-o-stop valve. A0 : 0      A1 : 0      A6 : 0      AD : 2	No	2
8	22mm Non Return valve. A0 : 2      A1 : 0      A6 : 0      AD : 0	No	2
<b><u>WASTE UNIONS ETC</u></b>			
<b><u>Outlets, traps, etc:</u></b>			
9	40mm 342/50 CP bottle trap. A0 : 0      A1 : 2      A6 : 0      AD : 0	No	2
10	40mm 342/50 CP bottle trap. A0 : 0      A1 : 2      A6 : 0      AD : 0	No	2
11	40mm 342/50 CP bottle trap. A0 : 0      A1 : 2      A6 : 0      AD : 0	No	2
<b><u>SANITARY PLUMBING</u></b>			
<b><u>PVC waste or vent pipes and fittings:</u></b>			
12	50mm Waste pipe. A0 : 0      A1 : 35      A6 : 0      AD : 0	m	35
13	110mm Pipe and laying in ground or filling not exceeding 2m deep including excavation, filling in and ramming. A0 : 0      A1 : 20      A6 : 0      AD : 0	m	20
<b>Carried to Collection</b>			
Section 4 Bill No. 7 Plumbing and Drainage (Provisional)			R

**uPVC gulleys**

14	200mm Precast concrete gully dish and uPVC lowback assembly complete with 110mm P trap gulley (code UGB 40) including 190mm diameter head (code UGA 40) and grate (code UGG 40), not exceeding 750mm deep, jointed to 110mm drain pipe, including excavations for and encasing in concrete (15MPa crushing strength after 28 days) worked up to form kerb, finished smooth on top in 1:3 cement mortar.	No	4
	A0 : 1      A1 : 1      A6 : 1      AD : 1		
	<b><u>Extra for:</u></b>		
15	50mm Bend.	No	16
	A0 : 0      A1 : 0      A6 : 4      AD : 12		
16	50mm Access bend.	No	7
	A0 : 0      A1 : 0      A6 : 0      AD : 7		
17	Envirosan or equal approved fly screens to top of 110 diameter vent pipe.	No	9
	A0 : 0      A1 : 0      A6 : 0      AD : 9		

**WATER SUPPLIES**

**Polycop pipes:**

Pipes shall be class 10.

**Fixing of pipes**

Unless specifically otherwise stated, descriptions of pipes shall be deemed to include for fixing to walls etc. casting in, building in or suspending not exceeding 1m below suspension level

**Polycop pipes chased in walls:**

Where pipes have been chased in walls, the price for making good of plaster and paint etc shall be deemed to be included in the description of pipe chased in walls.

**Carried to Collection**

R

Section 4  
Bill No. 7  
Plumbing and Drainage (Provisional)

**Reducing fittings:**

Where fittings have reducing ends or branches they are described as 'reducing'. In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained.

**Class 10 Polycop pipes:**

18	15mm Pipe chased into brick walls.	m	25	
	A0 : 0      A1 : 0      A6 : 0      AD : 25			

19	22mm Pipe chased into brick walls.	m	22	
	A0 : 0      A1 : 0      A6 : 0      AD : 22			

**Extra over polycop pipes for compression fittings:**

20	15mm Fittings.	No	40	
	A0 : 0      A1 : 0      A6 : 0      AD : 40			

21	22mm Fittings.	No	35	
	A0 : 0      A1 : 0      A6 : 0      AD : 35			

**Carried to Collection**

R

Section 4  
Bill No. 7  
Plumbing and Drainage (Provisional)

Section 4

Bill No. 7

Plumbing and Drainage (Provisional)

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

62

63

64

65

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 7

Plumbing and Drainage (Provisional)

Item No		Quantity	Rate	Amount
	<p><b><u>SECTION 3</u></b></p> <p><b><u>BILL No. 11</u></b></p> <p><b><u>PAINTWORK</u></b></p> <p><b><u>Quantity Split:</u></b></p> <p>Note that the total quantity per each item is split into the various buildings and appears below each description as follows:</p> <p>A0 - DWG 04 - Staff Ablutions A1 - DWG 06 - Grade R Ablutions A6 - DWG 14 - Male Ablutions AD - DWG 35 - Female Ablutions</p> <p><b><u>MODEL PREAMBLES</u></b></p> <p>The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates</p> <p><b><u>SUPPLEMENTARY PREAMBLES</u></b></p> <p><b><u>Trade Names</u></b></p> <p>Where trade names are specified it will read "or equal approved"</p> <p><b><u>Epoxy paint</u></b></p> <p>The product and its methodology for application must be approved by Principal Agent before it is used.</p> <p>Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the epoxy paint is intended to be done.</p> <p>Contractor to provide a Letter of Compliance confirming that epoxy paint has been applied as per Manufacturer's instructions and data sheet. Proof of payment for the epoxy paint must be provided to the Principal Agent once approval has been granted.</p>			
	<b>Carried to Collection</b>		R	
	<p>Section 4</p> <p>Bill No. 8</p> <p>Paintwork</p>			

**PAINTWORK ETC TO NEW WORK**

**ON WOOD**

**Stop, sand down and prepare wood surfaces and apply one coat wood primer, one undercoat and two coats eggshell enamel paint as per Plascon or equal approved:**

1	On doors	m2	76
	A0 : 21      A1 : 23      A6 : 10      AD : 23		
2	On door frames	m2	24
	A0 : 6      A1 : 7      A6 : 3      AD : 7		

**Prepare and apply two coats carbolenium on:**

3	On exposed timbers.	m2	10
	A0 : 10      A1 : 0      A6 : 0      AD : 0		

**ON FIBRE-CEMENT**

**Prepare and apply two coats pure acrylic roof paint on:**

4	On fascias and barge boards.	m2	5
	A0 : 5      A1 : 0      A6 : 0      AD : 0		

**ON PVC VENT PIPE**

**Prepare and apply two coats black PVA paint:**

5	Vent Pipes	m2	68
	A0 : 23      A1 : 15      A6 : 8      AD : 23		

Carried to Collection

Section 4  
Bill No. 8  
Paintwork

R



Section 4

Bill No. 8

Paintwork

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

67

68

**Amount**

**Carried Forward to Summary of Section No. 4**

R

Section 4

Bill No. 8

Paintwork

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

Bill No	Section 4			
	<b><u>SECTION SUMMARY - BUILDING WORKS</u></b>	<b>Page No</b>		<b>Amount</b>
	Masonry	46		
	Waterproofing	49		
	Carpentry and Joinery	52		
	Ironmongery	56		
	Metalwork	60		
	Plastering	61		
	Plumbing and Drainage (Provisional)	66		
	Paintwork	69		

Item No		Quantity	Rate	Amount
	<b><u>SECTION No. 4</u></b>			
	<b><u>BILL No. 1</u></b>			
	<b><u>EXTERNAL WORKS (PROVISIONAL)</u></b>			
	<b><u>MODEL PREAMBLES</u></b>			
	The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
	<b><u>THE FOLLOWING IN PLATFORMS, ETC.</u></b>			
	<u>Earth filling from excavated material</u>			
1	Dig, load and remove filling selected from spoil heaps on site and deposit as filling in platforms including spreading and compacting to cambers and falls in layers not exceeding 150 mm thick to a minimum of 95% Modified AASHTO dry density.	m3	84	
	<u>Filling supplied by the contractor to form platforms</u>			
2	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	36	
	<u>Surface Preparation:</u>			
3	Trim and level off surface of ground (excavated or filled under this Contract) including excavating or filling, ripping and scarifying as necessary and compacting the whole area for a depth of 300mm to a density of at least 90% Mod. AASHTO maximum density, part to falls.	m2	625	
	<u>Prescribed density tests on filling:</u>			
4	Modified AASHTO Density test.	No	8	
	<b>Carried to Collection</b>			
	Section 5			
	Bill No. 1			
	External Works			
			R	

**THE FOLLOWING IN WALKWAYS**

Breaking up and removing

5	Carefully remove paving of 50mm thick 200x100mm 25MPa Bevel Bond paver blocks on and including sand bedding and set aside for reuse.	m2	102
---	--	----	-----

6	20mm thick sand bed with dry filler sand, Off site to a dumping site to be found by the Contractor.	m3	10
---	---	----	----

Filling supplied by the contractor under walkways

7	20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade	m3	10
---	--	----	----

Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:

8	Under Paving,etc.	m2	310
---	-------------------	----	-----

Prescribed density tests on filling:

9	In-situ dry density test.	No	3
---	---------------------------	----	---

Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:

10	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	310
----	--	----	-----

**Concrete Paving Blocks**

Paving of 50mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:

11	Paving to walkway areas, etc laid to falls.	m2	210
----	---	----	-----

**Take delivery (free issued materials) and install**

12	Paving to walkway areas, etc laid to falls.	m2	200
----	---	----	-----

**Carried to Collection**

Section 5  
Bill No. 1  
External Works

R



**THE FOLLOWING IN ONE BRICK WALL  
(GARDEN WALL)**

**BRICKWORK IN FOUNDATIONS.**

Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):

15	One brick walls.	m2	5
----	------------------	----	---

**Brickwork reinforcement:**

16	230mm Wide reinforcement built in horizontally.	m	50
----	---	---	----

**FACE BRICK**

"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):

17	One brickwall faced on both sides.	m2	10
----	------------------------------------	----	----

Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:

18	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	130
----	---	---	-----

**Carried to Collection**

Section 5  
Bill No. 1  
External Works

R

<b><u>STORMWATER CHANNELS</u></b>					
<u>Excavation not exceeding 2m deep</u>					
19	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	37		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
20	Off site to a dumping site to be found by the Contractor.	m3	37		
<u>Filling supplied by the contractor under channels</u>					
21	G7 Base course material compacted to 98% Mod AASHTO density	m3	12		
22	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	12		
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>					
23	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	92		
24	Extra for 700mm angle	No	4		
25	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4		
<b><u>THE FOLLOWING IN DISABLED ACCESS</u></b>					
<b>Carried to Collection</b>				R	
Section 5					
Bill No. 1					
External Works					

<b><u>SCREEN WALL</u></b>					
<u>Excavation in earth not exceeding 2m deep:</u>					
26	Trenches.	m3	5		
<u>Extra over all excavations for carting away:</u>					
27	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	5		
<u>Risk of collapse of excavations:</u>					
28	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	14		
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>					
29	Backfilling to trenches, holes, etc.	m3	4		
<u>Filling supplied by the contractor under strip footing</u>					
30	G7 Base course material compacted to 98% Mod AASHTO density	m3	1		
31	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	1		
<u>Compaction of surfaces</u>					
32	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	7		
<u>25 Mpa/19mm Concrete</u>					
33	Strip footings.	m3	1		
<b>Carried to Collection</b>				R	
Section 5					
Bill No. 1					
External Works					



	<u>Test blocks:</u>				
34	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	6		
	<u>Reinforcement (Provisional)</u>				
35	High tensile steel reinforcement bars to structural concrete work.	t	0.17		
	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
36	One brick walls.	m2	5		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork reinforcement:</u>				
37	230mm Wide reinforcement built in horizontally.	m	21		
38	Ditto but in foundations.	m	41		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
39	One brickwall faced on both sides.	m2	5		
	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
40	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	10		
	<u>ACCESS RAMPS</u>				
<b>Carried to Collection</b>				R	
Section 5					
Bill No. 1					
External Works					

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

	<u>Excavation not exceeding 2m deep</u>				
41	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	5		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
42	Off site to a dumping site to be found by the Contractor.	m3	5		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
43	G7 Base course material compacted to 98% Mod AASHTO density	m3	2		
44	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	2		
	<u>Coarse river sand filling supplied by the contractor:</u>				
45	Under floors etc.	m3	1		
	<u>Compaction of surfaces:</u>				
46	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	10		
	<u>Prescribed density tests on filling:</u>				
47	In-situ dry density test.	No	2		
	<u>Reinforced 25Mpa/19mm Concrete:</u>				
48	Ramps, Landings, etc.	m3	10		
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
49	Surface beds, slabs, etc to falls and currents.	m2	10		
<b>Carried to Collection</b>				R	
Section 5					
Bill No. 1					
External Works					

	<u>Test blocks:</u>				
50	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	6		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
51	12mm Joints not exceeding 300mm high.	m	10		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
52	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	10		
	<u>Fabric reinforcement:</u>				
53	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	10		
	<u>Waterproofing under Surface beds</u>				
54	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	10		
<b>Carried to Collection</b>					R
Section 5					
Bill No. 1					
External Works					

<u>THE FOLLOWING IN ACCESS DRIVEWAY, ETC.</u>					
<u>Excavation not exceeding 2m deep</u>					
55	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	162		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
56	Off site to a dumping site to be found by the Contractor.	m3	162		
<u>Filling supplied by the contractor under driveways</u>					
57	G7 Base course material compacted to 98% Mod AASHTO density	m3	81		
58	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	81		
<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>					
59	Under floors,etc.	m2	540		
<u>Prescribed density tests on filling:</u>					
60	In-situ dry density test.	No	3		
<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>					
61	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	480		
<u>150-175mm diameter bollards</u>					
62	2100mm long tanalith treated gum pole planted 800mm deep including excavations, cartaways, concrete base etc.	No	30		
<b>Carried to Collection</b>				R	
Section 5					
Bill No. 1					
External Works					

<b><u>THE FOLLOWING IN RETAINING WALLS, ETC.</u></b>						
	<u>Excavation in earth not exceeding 2m deep</u>					
63	Trenches.	m3	8			
	<u>Risk of collapse of excavations:</u>					
64	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	24			
	<u>Keeping excavations free of water:</u>					
65	Keeping excavations free of all water other than subterranean water.			Item		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
66	Off site to a dumping site to be found by the Contractor.	m3	8			
	<u>Filling with approved clean, hard, dry decomposed dolerite filling supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod. AASHTO maximum density:</u>					
67	Behind walls with selected backfilling supplied by the Contractor compacted to 98% Mod ASSHTO density	m3	3			
	<u>Compaction of surfaces</u>					
68	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	8			
	<u>15Mpa/19mm unreinforced concrete</u>					
69	Surface blinding under footings and bases.	m3	0.4			
	<u>30Mpa/19mm reinforced concrete</u>					
70	Strip footings.	m3	2			
<b>Carried to Collection</b>				R		
Section 5						
Bill No. 1						
External Works						

	<u>Test blocks:</u>				
71	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
	<u>Fabric reinforcement:</u>				
72	REF. 395 fabric reinforcement in concrete infill, strip footings.	m2	19		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
73	One brickwalls in foundations	m2	6		
74	One brick walls	m2	13		
	<u>Brickwork reinforcement:</u>				
75	230mm Wide reinforcement built in horizontally.	m	68		
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
76	Extra over brickwork for face brickwork externally.	m2	13		
	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal Architect approved clay face brick size 222 x 106 x 73mm, pointed with recessed joints on all exposed faces:</u>				
77	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	12		
	<u>Openings in Walls etc.</u>				
78	Leave or form 32mm weephole through one brick wall	No	50		
	<u>Membranes</u>				
79	"Geofabric filter blanket wrapped around stone with 300mm side and 300mm end laps, including stitching.	m2	14		
<b>Carried to Collection</b>				R	
Section 5					
Bill No. 1					
External Works					

	<u>Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:</u>				
80	19mm Stone.	m3	1		
	<b><u>THE FOLLOWING IN STORMWATER DRAINAGE, APRONS ETC.</u></b>				
	<b><u>STORMWATER APRONS</u></b>				
	<u>Excavation not exceeding 2m deep</u>				
81	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	30		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
82	Off site to a dumping site to be found by the Contractor.	m3	30		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
83	G7 Base course material compacted to 98% Mod AASHTO density	m3	8		
84	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	8		
	<u>Coarse river sand filling supplied by the contractor:</u>				
85	Under floors etc.	m3	3		
	<u>Compaction of surfaces:</u>				
86	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	54		
	<b>Carried to Collection</b>			R	
	Section 5				
	Bill No. 1				
	External Works				

	<u>Prescribed density tests on filling:</u>				
87	In-situ dry density test.	No	3		
	<u>Reinforced 25Mpa/19mm Concrete:</u>				
88	Surface beds cast in panels on waterproofing.	m3	5		
89	Edge thickening	m3	3		
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
90	Surface beds, slabs, etc to falls and currents.	m2	54		
	<u>Test blocks:</u>				
91	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	6		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
92	12mm Joints not exceeding 300mm high.	m	36		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
93	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	36		
	<u>Fabric reinforcement:</u>				
94	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	54		
	<u>Waterproofing under Surface beds</u>				
95	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	54		
<b>Carried to Collection</b>					R
Section 5					
Bill No. 1					
External Works					



<b><u>STORMWATER CHANNELS</u></b>					
<u>Excavation not exceeding 2m deep</u>					
96	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	82		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
97	Off site to a dumping site to be found by the Contractor.	m3	82		
<u>Filling supplied by the contractor under channels</u>					
98	G7 Base course material compacted to 98% Mod AASHTO density	m3	25		
99	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	25		
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>					
100	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	234		
101	Extra for 700mm angle	No	4		
102	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4		
<b>Carried to Collection</b>				R	
Section 5 Bill No. 1 External Works					

	<u>Sundries:</u>			
103	Create earth berm for stormwater control with in situ material 1,5m wide at base x 500mm high	m	135	
	<b><u>THE FOLLOWING IN SUB-SOIL DRAINAGE, ETC.</u></b>			
	<u>Site Clearance, ETC</u>			
104	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	314	
	<u>Excavation in earth not exceeding 2m deep:</u>			
105	Trenches.	m3	126	
	<u>Extra over all excavations for carting away:</u>			
106	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	76	
	<u>Risk of collapse of excavations:</u>			
107	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	502	
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>			
108	Backfilling to trenches, holes, etc.	m3	50	
	<u>Filling supplied by the contractor under channels</u>			
109	G7 Base course material compacted to 98% Mod AASHTO density	m3	62	
	<u>Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:</u>			
110	19mm Stone.	m3	14	
	<b>Carried to Collection</b>			R
	Section 5			
	Bill No. 1			
	External Works			

	<u>Membrane</u>				
111	""Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching.	m2	188		
	<u>Keeping excavations free of water:</u>				
112	Keeping excavations free from mud and all water including subterranean sources.		Item		
	<u>Compaction of surfaces</u>				
113	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	79		
	<b><u>SOIL DRAINAGE</u></b>				
	<u>110mm Diameter perforated uPVC pipe surrounded with 300 x 300mm section of 20mm stone wrapped in A3 geotextile material.</u>				
114	110mm uPVC pipe.	m	157		
	<u>Extra for:</u>				
115	110mm Tee.	No	8		
116	110mm Y junction.	No	6		
	<b><u>THE FOLLOWING IN SOAKAWAY</u></b>				
	<u>Site Clearance, Etc</u>				
117	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	9		
	<u>Excavation in earth not exceeding 2m deep:</u>				
118	Holes	m3	5		
<b>Carried to Collection</b>				R	
Section 5 Bill No. 1 External Works					

	<u>Extra over all excavations for carting away</u>				
119	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor within 5km from the building site	m3	5		
	<u>Risk of collapse of excavations</u>				
120	Sides of trench and hole excavations exceeding 1,5m deep but not exceeding 3,0m deep	m2	21		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 90% Mod AASHTO density</u>				
121	Backfilling to holes	m3	3		
	<u>Earth filling with stone material supplied by the contractor:</u>				
122	Stone (>63mm).	m3	2		
	<u>Membranes</u>				
123	"BidimGeotextile or equal approved, lined on all sides including the top and bottom faces.	m2	16		
	<u>Keeping excavations free of water</u>				
124	Keeping excavations free of all water other than subterranean water		Item		
	<b><u>THE FOLLOWING IN SECURITY FENCING, ETC</u></b>				
	<u>Gates:</u>				
125	Two leafed vehicular swing gate. Size 5500mm x 1800mm high.	No	1		
	<b><u>Take delivery (free issued materials) and install</u></b>				
126	Two leafed vehicular swing gate. Size 5500mm x 1800mm high.	No	1		
	<u>PADLOCKS</u>				
127	Supply 50 mm "Viro" Padlocks and Keys (or equal approved )	No	2		
	<b>Carried to Collection</b>			R	
	Section 5				
	Bill No. 1				
	External Works				

**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

Section 5

Bill No. 1

External Works

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

**Carried to Final Summary**

**R**

Section 5

Bill No. 1

External Works



**BUDGETARY ALLOWANCES**

6 Provide the sum of R96 000.00 for the wages and salaries for labourers not paid by the previous Contractor and to be paid before the site work commences.

7 Add: Mark-up

Item

96 000.00

%

**Carried to Collection**

R

Section 6  
Bill No. 1  
Provisional Sums

Section 6

Bill No. 1

Provisional Sums

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

90

91

**Carried to Final Summary**

R

Section 6  
Bill No. 1  
Provisional Sums



**BAZIYA PRIMARY SCHOOL  
COMPLETION WORKS  
THE MVULA TRUST SAFE PROGRAMME**

[illegible]