

| Item No  | Quantity | Rate | Amount |
|--|----------|------|--------|
| <b><u>SECTION No. 1 - PRELIMINARIES</u></b>  |          |      |        |
| <b><u>BILL NO. 1</u></b>   |          |      |        |
| <b><u>PRELIMINARIES</u></b>  |          |      |        |
| <b><u>MEANING OF TERMS "TENDER / TENDERER"</u></b>   |          |      |        |
| Any reference to the words "Tender" or "Tenderer" herein and/or in any other documentation shall be construed to have the same meaning as the words "Bid" or "Bidder"  |          |      |        |
| <b><u>PRELIMINARIES</u></b>  |          |      |        |
| The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein. The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause. These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable" |          |      |        |
| <b><u>PRICING OF PRELIMINARIES</u></b>   |          |      |        |
| Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item   |          |      |        |
| Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities  |          |      |        |
| <b>Carried to Collection</b>   |          |      | R      |
| Section No. 1<br>Bill No. 1<br>PRELIMINARIES AND GENERAL<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b>  |          |      |        |

## **SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT**

### **DEFINITIONS**

#### **1 A1.0 DEFINITIONS AND INTERPRETATION**

Clause 1.0

Clause 1.1 Definition of "**Commencement Date**" is added:

**"COMMENCEMENT DATE"** means the date that is 5 working days after site hand over.

Clause 1.1 Definition of "**Construction Guarantee**" is amended by replacing it with the following:

**"CONSTRUCTION GUARANTEE"** means a guarantee at call obtained by the **contractor** from an institution approved by the **employer** in terms of the **employer's** construction guarantee form as selected in the **schedule**

Clause 1.1 Definition of "**Construction Period**" is amended by replacing it with the following:

**"CONSTRUCTION PERIOD"** means the period commencing on the **commencement date** and ending on the date of **practical completion**

Clause 1.1 Definition of "**Corrupt Practice**" is added:

**"CORRUPT PRACTICE"** means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution

Clause 1.1 Definition of "**Fraudulent Practice**" is added:

**Carried to Collection**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

**"FRAUDULENT PRACTICE"** means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of any tenderer and includes collusive practice among tenderers (prior to or after the tender submission) designed to establish tender prices at artificial non-competitive levels and to deprive the tenderer of the benefits of free and open competition

Clause 1.1 Definition of **"Interest"** is amended by replacing it with the following:

**"INTEREST"** means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be in terms of the legislation of the Republic of South Africa, and in particular:

(a) in respect of interest owed by the employer, the interest rate as determined by the Minister of Justice and Constitutional Development from time to time, in terms of section 1(2) of the Prescribed Rate of Interest Act, 1975 (Act No. 55 of 1975), will apply;

and

(b) in respect of interest owed to the employer, the interest rate as determined by the Minister of Finance, from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999), will apply

Clause 1.1 Definition of **"Principal Agent"** is amended by replacing it with the following:

**"PRINCIPAL AGENT"** means the person or entity appointed by the **employer** and named in the **schedule**. In the event of a **principal agent** not being appointed, then all the duties and obligations of a **principal agent** as detailed in the **agreement** shall be fulfilled by a representative of the **employer** as named in the **schedule**

Clause 1.1 Definition of **"Security"** is amended by replacing it with the following:

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

"**SECURITY**" means the form of security provided by the **employer** or **contractor**, as stated in the **schedule**, from which the **contractor** or **employer** may recover expense or loss

Clause 1.6 is amended by replacing the words "prepaid registered post, telefax or e-mail" with "prepaid registered post or telefax"

Clause 1.6.4 is amended by replacing it with the following:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

### **OBJECTIVE AND PREPARATION**

#### **1 A2.0 OFFER, ACCEPTANCE AND PERFORMANCE**

Clause 2.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

#### **2 A3.0 DOCUMENTS**

Clause 3.0

Clause 3.2.1 is amended by replacing "14.1" with "14.0"

Clause 3.7 is amended by the addition of the following:

The **contractor** shall supply and keep a copy of the **JBCC** Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the **site**, to which the **employer**, **principal agent** and **agents** shall have access at all times

Clause 3.10 is amended by replacing the second reference to "**principal agent**" with the word "**employer**"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

|   |   |      |   |  |
|---|---|------|---|--|
| 1   | <p><b>A4.0 DESIGN RESPONSIBILITY</b></p> <p>Clause 4.0</p> <p>Clause 4.3 is amended by replacing it with the following:</p> <p>No clause</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   | Item |   |  |
| 2   | <p><b>A5.0 EMPLOYER'S AGENTS</b></p> <p>Clause 5.0</p> <p>Clause 5.1.2 is amended to include clauses 32.6.3, 34.3 and 34.4 in terms of which the employer has retained its authority and has not given a mandate to the principal agent and in terms of which the employer shall sign all documents.</p> <p>Fixed: _____ Value related: _____ Time related: _____</p> | Item |   |  |
| 3   | <p><b>A6.0 SITE REPRESENTATIVE</b></p> <p>Clause 6.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   | Item |   |  |
| 4   | <p><b>A7.0 COMPLIANCE WITH REGULATIONS</b></p> <p>Clause 7.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   | Item |   |  |
| 5   | <p><b>A8.0 WORKS RISK</b></p> <p>Clause 8.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>  | Item |   |  |
| Carried to Collection   |   |      | R |  |
| Section No. 1<br>Bill No. 1<br>PRELIMINARIES AND GENERAL<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |   |      |   |  |

|   |   |      |   |  |
|---|---|------|---|--|
| 1 | <p><b>A9.0 INDEMNITIES</b></p> <p>Clause 9.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   | Item |   |  |
| 2 | <p><b>A10.0 WORKS INSURANCES</b></p> <p>Clause 10.0</p> <p>Clause 10.0 is amended by the addition of the following clauses:</p> <p><b>10.5 Damage to the Works</b></p> <p>(a) Without in any way limiting the <b>contractor's</b> obligations in terms of the contract, the <b>contractor</b> shall bear the full risk of damage to and/or destruction of the <b>works</b> by whatever cause during construction of the <b>works</b> and hereby indemnifies and holds harmless the <b>employer</b> against any such damage. The <b>contractor</b> shall take such precautions and security measures and other steps for the protection and security of the <b>works</b> as the <b>contractor</b> may deem necessary</p> <p>(b) The <b>contractor</b> shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the <b>works</b> and to rebuild, restore, replace and/or repair the <b>works</b></p> <p>(c) The <b>employer</b> shall carry the risk of damage to or destruction of the <b>works</b> and materials paid for by the <b>employer</b> that is the result of the excepted risks as set out in 10.6</p> <p>(d) Where the <b>employer</b> bears the risk in terms of this contract, the <b>contractor</b> shall, if requested to do so, reinstate any damage or destroyed portions of the <b>works</b> and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof</p> |      |   |  |
|   | <p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section No. 1<br/>Bill No. 1<br/>PRELIMINARIES AND GENERAL<br/><b>QEBE JSS</b><br/><b>PROVISIONAL BILLS OF QUANTITIES</b></p>   |      | R |  |

## 10.6 Injury to Persons or loss of or damage to Properties

- (a) The **contractor** shall be liable for and hereby indemnifies the **employer** against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the **works** unless due to any act or negligence of any person for whose actions the **employer** is legally liable
- (b) The **contractor** shall be liable for and hereby indemnifies the **employer** against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the **site**, whether belonging to or under the control of the **employer** or any other body or person, arising out of or in the course of or by reason of the execution of the **works** unless due to any act or negligence of any person for whose actions the **employer** is legally liable
- (c) The **contractor** shall, upon receiving a **contract instruction** from the **principal agent**, cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the **employer** shall be entitled to cause it to be made good and to recover the cost thereof from the **contractor** or to deduct the same from amounts due to the **contractor**
- (d) The **contractor** shall be responsible for the protection and safety of such portions of the premises placed under his control by the **employer** for the purpose of executing the **works** until the issue of the **certificate of practical completion**

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**

- (e) Where the execution of the **works** involves the risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the **contractor** shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the **works** has been completed
- (f) The **contractor** shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the **works**

### 10.7 High risk insurance

In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the following will apply:

#### 10.7.1 Damage to the works

The **contractor** shall, from the **commencement date** of the **works** until the date of the **certificate of practical completion** bear the full risk of and hereby indemnifies and holds harmless the **employer** against any damage to and/or destruction of the **works** consequent upon a catastrophic ground movement as mentioned above. The **contractor** shall take such precautions and security measures and other steps for the protection of the **works** as he may deem necessary

When so instructed to do so by the **principal agent**, the **contractor** shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the **works** and to rebuild, restore, replace and/or repair the **works**, at the **contractor's** own costs

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**



**10.7.2 Injury to persons or loss of or damage to property**

The **contractor** shall be liable for and hereby indemnifies and holds harmless the **employer** against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of, or caused by a catastrophic ground movement as mentioned above

The **contractor** shall be liable for and hereby indemnifies the **employer** against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the **site**, whether belonging to or under the control of the **employer** or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract

**10.7.3** It is the responsibility of the **contractor** to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the **contractor's** obligations in terms of the contract, the **contractor** shall, within twenty-one (21) **calendar days** of the **commencement date** but before commencement of the **works**, submit to the **employer** proof of such insurance policy, if requested to do so

**10.7.4** The **employer** shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the **contractor's** default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the **contractor** or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the **employer** and the **contractor** and for this purpose all these contracts shall be considered one indivisible whole

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

|   |  |      |   |  |
|---|--|------|---|--|
| 1 | <b>A11.0 LIABILITY INSURANCES</b><br><br>Clause 11.0<br><br>Fixed: _____ Value related: _____ Time related: _____  | Item |   |  |
| 2 | <b>A12.0 EFFECTING INSURANCES</b><br><br>Clause 12.0<br><br>Fixed: _____ Value related: _____ Time related: _____  | Item |   |  |
| 3 | <b>A13.0 No clause</b>   | N/A  |   |  |
| 4 | <b>A14.0 SECURITY</b><br><br>Clause 14.0<br><br>Clauses 14.1 - 14.8 are amended by replacing them with the following:<br><br>14.1 The security to be submitted by the contractor to the employer will be as a payment reduction of up to ten per cent (10%) of the value certified in the payment certificate (excluding VAT)<br><br>14.1.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(A)<br><br>14.1.2 The <b>employer</b> shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the <b>employer</b> complies with the provisions of 33.4 in which event the <b>employer's</b> entitlement shall take precedence over his obligations to refund the payment reduction <b>security</b> or portions thereof to the <b>contractor</b><br><br>14.2 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected:<br><br>14.2.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(B) |      |   |  |
|   | <b>Carried to Collection</b>   |      | R |  |
|   | Section No. 1<br>Bill No. 1<br>PRELIMINARIES AND GENERAL<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b>  |      |   |  |

14.2.2 The **employer** shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the **employer** complies with the provisions of 33.4 in which event the **employer's** entitlement shall take precedence over his obligations to refund the payment reduction **security** or portions thereof to the **contractor**

14.9 Should the **contractor** fail to furnish the **security** in terms of 14.2, the **employer**, in his sole discretion and without notification to the **contractor**, is entitled to change the **contractor's** selected form of **security** to that of a ten per cent (10%) payment reduction of the value certified in the **payment certificate** (excluding VAT), whereafter 14.7 shall be applicable

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

## **EXECUTION**

### **1 A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS**

Clause 15.0

Clause 15.1.1 is amended by replacing it with:

No clause

Clause 15.1.2 is amended by replacing it with:

The **security** selected in terms of 14.0

Clause 15.1 is amended by the addition of the following clause:

15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within fourteen (14) **calendar days** of **commencement date**

Clause 15.2.1 is amended by replacing it with the following clause:

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

Give the **contractor** possession of the **site** within ten (10) **working days** of the **contractor** complying with the terms of 15.1.4

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# 1 A16.0 ACCESS TO THE WORKS

Clause 16.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# 2 A17.0 CONTRACT INSTRUCTIONS

Clause 17.0

Clause 17.1.11 is amended by deleting the words "and the appointment of **nominated** and **selected subcontractors**"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# 3 A18.0 SETTING OUT OF THE WORKS

Clause 18.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# 4 A19.0 ASSIGNMENT

Clause 19.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

|  |   |      |   |  |
|--|---|------|---|--|
| 1  | <p><b>A20.0 NOMINATED SUBCONTRACTORS</b></p> <p>Clause 20.0</p> <p>Clause 20.1.3 is amended by replacing it with the following:</p> <p>No clause</p> <p>Note: See item B9.1 hereinafter for adjustment of attendance on <b>nominated subcontractors</b> executing work allowed for under provisional sums</p> <p>Fixed:_____ Value related:_____ Time related:_____</p> | Item |   |  |
| 2  | <p><b>A21.0 SELECTED SUBCONTRACTORS</b></p> <p>Clause 21.0</p> <p>Clause 21 is amended by replacing it with:</p> <p>No clause</p> <p>Fixed:_____ Value related:_____ Time related:_____</p>   | Item |   |  |
| 3  | <p><b>A22.0 EMPLOYER'S DIRECT CONTRACTORS</b></p> <p>Clause 22.0</p> <p>Fixed:_____ Value related:_____ Time related:_____</p>  | Item |   |  |
| 4  | <p><b>A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS</b></p> <p>Clause 23.0</p> <p>Fixed:_____ Value related:_____ Time related:_____</p>   | Item |   |  |
| <p style="text-align: right;"><b>Carried to Collection</b></p>   |   |      | R |  |
| <p>Section No. 1<br/> Bill No. 1<br/> PRELIMINARIES AND GENERAL<br/> <b>QEBE JSS</b><br/> <b>PROVISIONAL BILLS OF QUANTITIES</b></p> |   |      |   |  |

|   |   |      |   |  |
|---|---|------|---|--|
| <b><u>COMPLETION</u></b>  |   |      |   |  |
| 1   | <b>A24.0 PRACTICAL COMPLETION</b><br><br>Clause 24.0<br><br>Fixed: _____ Value related: _____ Time related: _____   | Item |   |  |
| 2   | <b>A25.0 WORKS COMPLETION</b><br><br>Clause 25.0<br><br>Fixed: _____ Value related: _____ Time related: _____   | Item |   |  |
| 3   | <b>A26.0 FINAL COMPLETION</b><br><br>Clause 26.0<br><br>Fixed: _____ Value related: _____ Time related: _____   | Item |   |  |
| 4   | <b>A27.0 LATENT DEFECTS LIABILITY PERIOD</b><br><br>Clause 27.0<br><br>Fixed: _____ Value related: _____ Time related: _____  | Item |   |  |
| 5   | <b>A28.0 SECTIONAL COMPLETION</b><br><br>Clause 28.0<br><br>Fixed: _____ Value related: _____ Time related: _____   | Item |   |  |
| 6   | <b>A29.0 REVISION OF DATE FOR PRACTICAL COMPLETION</b><br><br>Clause 29.0<br><br>Clause 29.2.5 is amended by replacing it with:<br><br>No clause<br><br>Fixed: _____ Value related: _____ Time related: _____ | Item |   |  |
| <b>Carried to Collection</b>  |   |      | R |  |
| Section No. 1<br>Bill No. 1<br>PRELIMINARIES AND GENERAL<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |   |      |   |  |

|   |   |      |  |   |
|---|---|------|--|---|
| 1 | <p><b>A30.0 PENALTY FOR NON-COMPLETION</b></p> <p>Clause 30.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p><b><u>PAYMENT</u></b></p>   | Item |  |   |
| 2 | <p><b>A31.0 INTERIM PAYMENT TO THE CONTRACTOR</b></p> <p>Clause 31.0</p> <p>Clause 31.5.2 is amended by replacing "14.7.1" with "14.0 and 31.8"</p> <p>Clause 31.8 is amended by replacing it with the following two alternative clauses:</p> <p><b>Alternative A</b></p> <p>31.8(A) Where a <b>security</b> is selected in terms of 14.1; the value of the <b>works</b> in terms of 31.4.1 and <b>materials and goods</b> in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:</p> <p>31.8(A).1 Ninety-five percent (95%) of such value in interim <b>payment certificates</b> issued up to the date of <b>practical completion</b></p> <p>31.8(A).2 Ninety-seven and half percent (97.5%) of such value in interim <b>payment certificates</b> issued on the date of <b>practical completion</b> and up to but excluding the date of <b>final completion</b></p> <p>31.8(A).3 Ninety-nine percent (99%) of such value in interim <b>payment certificates</b> issued on the date of <b>final completion</b> and up to but excluding the final <b>payment certificate</b> in terms of 34.6</p> <p>31.8(A).4 One hundred percent (100%) of such value in the final <b>payment certificate</b> in terms of 34.6 except where the amount certified is in favour of the <b>employer</b>. In such an event the payment reduction shall remain at the adjustment level applicable to the final <b>payment certificate</b></p> <p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section No. 1<br/>Bill No. 1<br/>PRELIMINARIES AND GENERAL<br/><b>QEBE JSS</b><br/><b>PROVISIONAL BILLS OF QUANTITIES</b></p> |      |  | R |

Clause 31.12 is amended by deleting the following:

Payment shall be subject to the **employer** giving the **contractor** a tax invoice for the amount due

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

## 1 A32.0 ADJUSTMENT TO THE CONTRACT VALUE

Clause 32.0

Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:

"due to no fault of the **contractor**"

Add the following clauses: 33.2.9 to 33.2.13:

33.2.9 the **contractor's** failure or neglect to commence with the works on the dates prescribed in the contract

33.2.10 the **contractor's** failure or neglect to proceed with the works in terms of the contract

33.2.11 the **contractor's** failure or neglect for any reason to complete the works in accordance with the contract

33.2.12 the **contractor's** refusal or neglect to comply strictly with any of the conditions of contract or any contract instructions and/or orders in writing given in terms of the contract

33.2.13 the **contractor's** estate being sequestrated; liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa.

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

## 2 A33.0 RECOVERY OF EXPENSE AND LOSS

Clause 33.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**



|   |   |  |  |  |
|---|---|--|--|--|
| 1 | <p><b>A34.0 FINAL ACCOUNT AND FINAL PAYMENT</b></p> <p>Clause 34.0</p> <p>Clause 34.1 is amended by removing "#" next to 34.1</p> <p>Clause 34.2 is amended by inserting "#" next to 34.2</p> <p>Clause 34.13 is amended by replacing "seven (7) <b>calendar days</b>" with "twenty-one (21) <b>calendar days</b>" and deleting the words "subject to the <b>employer</b> giving the <b>contractor</b> a tax invoice for the amount due"</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   |  |  |  |
| 2 | <p><b>A35.0 PAYMENT TO OTHER PARTIES</b></p>  |  |  |  |
|   | <p>Clause 35.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   |  |  |  |
|   | <p><b><u>CANCELLATION</u></b></p>   |  |  |  |
| 3 | <p><b>A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT</b></p>   |  |  |  |
|   | <p>Clause 36.0</p> <p>Clause 36.1 is amended by the addition of the following clauses:</p> <p>36.1.3 refuses or neglects to comply strictly with any of the conditions of contract</p> <p>36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa</p> <p>36.1.5 in the judgement of the <b>employer</b>, has engaged in <b>corrupt</b> or <b>fraudulent practices</b> in competing for or in executing the contract</p> <p>Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "<b>principal agent</b>" with "<b>employer</b>"</p> |  |  |  |
|   | <p style="text-align: right;"><b>Carried to Collection</b></p>  |  |  |  |
|   | <p>Section No. 1<br/>Bill No. 1<br/>PRELIMINARIES AND GENERAL<br/><b>QEBE JSS</b><br/><b>PROVISIONAL BILLS OF QUANTITIES</b></p>  |  |  |  |

Clause 36.0 is amended by the addition of the following clause:

36.3 Remove reference to "No clause", and replace "principal agent" with "employer"

36.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# 1 **A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE**

Clause 37.0

Clause 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

Clause 37.0 is amended by the addition of the following clause:

37.3.5 Replace "ninety (90)" with "one hundred and twenty (120)" and 38.5.4

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# 2 **A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT**

Clause 38.0

Clause 38.5.4 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

Clause 38.0 is amended by the addition of the following clause:

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

38.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

# **1 A39.0 CANCELLATION - CESSATION OF THE WORKS**

Clause 39.0

Clause 39.3.5 is amended by the addition of the following at the end of the sentence:

"within one hundred and twenty (120) **working days** of completion of such a report"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**

|   |   |      |   |  |
|---|---|------|---|--|
| 1 | <p><b><u>DISPUTE</u></b></p> <p><b>A40.0 DISPUTE SETTLEMENT</b></p> <p>Clause 40.0</p> <p>Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"</p> <p>Clause 40.6 is amended by removing the reference to:</p> <p>No clause</p> <p>Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:</p> <p>Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the <b>mediator</b> and related costs</p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p><b><u>SUBSTITUTE PROVISIONS</u></b></p> <p><b>A41.0 STATE CLAUSES</b></p> <p>Clause 41.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p><b><u>CONTRACT VARIABLES</u></b></p> <p><b>A42.0 THE SCHEDULE (C1.2)</b></p> <p>Clause 42.0</p> <p>Tenderers are referred to the C1.2 CONDITIONS OF CONTRACT AND CONTRACT VARIABLES for variables pertaining to this contract</p> <p>Fixed: _____ Value related: _____ Time related: _____</p> | Item |   |  |
| 2 |   | Item |   |  |
| 3 |   | Item |   |  |
|   | <p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section No. 1<br/>Bill No. 1<br/>PRELIMINARIES AND GENERAL<br/><b>QEBE JSS</b><br/><b>PROVISIONAL BILLS OF QUANTITIES</b></p>   |      | R |  |

**SECTION B: JBCC PRELIMINARIES****B1.0 DEFINITIONS AND INTERPRETATION****1 B1.1 Definitions and interpretation**

See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B2.0 DOCUMENTS****2 B2.1 Checking of documents**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**3 B2.2 Provisional bills of quantities**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**4 B2.3 Availability of construction documentation**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**5 B2.4 Interests of agents**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**6 B2.5 Priced documents**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**7 B2.6 Tender submission**

Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Form of Offer and Acceptance DPW-07(EC)"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

**B3.0 THE SITE**1 **B3.1 Defined works area**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

2 **B3.2 Geotechnical investigation**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

3 **B3.3 Inspection of the site**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

4 **B3.4 Existing premises occupied**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

5 **B3.5 Previous work - dimensional accuracy**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

6 **B3.6 Previous work - defects**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

7 **B3.7 Services - known**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

8 **B3.8 Services - unknown**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

9 **B3.9 Protection of trees**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

QEBE JSS

PROVISIONAL BILLS OF QUANTITIES

|  |   |      |   |  |
|--|---|------|---|--|
| 1                                      | <p><b>B3.10 Articles of value</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p>  | Item |   |  |
| 2                                      | <p><b>B3.11 Inspection of adjoining properties</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p> <p><b><u>B4.0 MANAGEMENT OF CONTRACT</u></b></p>                          | Item |   |  |
| 3                                      | <p><b>B4.1 Management of the works</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: R _____</p>   | Item |   |  |
| 4                                      | <p><b>B4.2 Programme for the works</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p>   | Item |   |  |
| 5                                      | <p><b>B4.3 Progress meetings</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p>   | Item |   |  |
| 6                                      | <p><b>B4.4 Technical meetings</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p>  | Item |   |  |
| 7                                      | <p><b>B4.5 Labour and plant records</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p> <p><b><u>B5.0 SAMPLES, SHOP DRAWINGS AND<br/>MANUFACTURERS' INSTRUCTIONS</u></b></p> | Item |   |  |
| 8                                      | <p><b>B5.1 Samples of materials</b></p> <p>Fixed: _____ Value related: _____ Time<br/>related: _____</p>  | Item |   |  |
|  |   |      | R |  |
| Carried to Collection                  |   |      |   |  |
| Section No. 1                          |   |      |   |  |
| Bill No. 1                             |   |      |   |  |
| PRELIMINARIES AND GENERAL              |   |      |   |  |
| <b>QEBE JSS</b>                        |   |      |   |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b> |   |      |   |  |

|  |  |      |
|--|--|------|
| 1  | <b>B5.2 Workmanship samples</b><br>Fixed: _____ Value related: _____ Time related: _____                         | Item |
| 2  | <b>B5.3 Shop drawings</b><br>Fixed: _____ Value related: _____ Time related: _____                               | Item |
| 3  | <b>B5.4 Compliance with manufacturers' instructions</b><br>Fixed: _____ Value related: _____ Time related: _____ | Item |
| <b><u>B6.0 TEMPORARY WORKS AND PLANT</u></b> |  |      |
| 4  | <b>B6.1 Deposits and fees</b><br>Fixed: _____ Value related: _____ Time related: _____                           | Item |
| 5  | <b>B6.2 Enclosure of the works</b><br>Fixed: _____ Value related: _____ Time related: _____                      | Item |
| 6  | <b>B6.3 Advertising</b><br>Fixed: _____ Value related: _____ Time related: _____                                 | Item |
| 7  | <b>B6.4 Plant, equipment, sheds and offices</b><br>Fixed: _____ Value related: _____ Time related: _____         | Item |
| 8  | <b>B6.5 Main notice board</b><br>Fixed: _____ Value related: _____ Time related: _____                           | Item |
| 9  | <b>B6.6 Subcontractors' notice board</b><br>Fixed: _____ Value related: _____ Time related: _____                | Item |

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**



**B7.0 TEMPORARY SERVICES**1 **B7.1 Location**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

2 **B7.2 Water**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

3 **B7.3 Electricity**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

4 **B7.4 Telecommunication facilities**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

5 **B7.5 Ablution facilities**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**B8.0 PRIME COST AMOUNTS**6 **B8.1 Responsibility for prime cost amounts**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**B9.0 ATTENDANCE ON N/S  
SUBCONTRACTORS**7 **B9.1 General attendance**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

8 **B9.2 Special attendance**Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

|   |   |      |   |  |
|---|---|------|---|--|
| 1   | <p><b>B9.3 Commissioning - fuel, water and electricity</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p><b><u>B10.0 FINANCIAL ASPECTS</u></b></p>  | Item |   |  |
| 2   | <p><b>B10.1 Statutory taxes, duties and levies</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p>   | Item |   |  |
| 3   | <p><b>B10.2 Payment for preliminaries</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p>  | Item |   |  |
| 4   | <p><b>B10.3 Adjustment of preliminaries</b></p> <p>Clauses B10.3.1 and B10.3.2 are amended by replacing "within fifteen (15) <b>working days</b> of taking possession of the <b>site</b>" with "when submitting his priced <b>bills of quantities / lump sum document</b>"</p> <p>Fixed: _____ Value related: _____ Time related: _____</p> | Item |   |  |
| 5   | <p><b>B10.4 Payment certificate cash flow</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p><b><u>B11.0 GENERAL</u></b></p>   | Item |   |  |
| 6   | <p><b>B11.1 Protection of the works</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p>  | Item |   |  |
| 7   | <p><b>B11.2 Protection / isolation of existing / sectionally occupied works</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p>  | Item |   |  |
| Carried to Collection   |   |      | R |  |
| Section No. 1<br>Bill No. 1<br>PRELIMINARIES AND GENERAL<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |   |      |   |  |

|   |  |      |
|---|--|------|
| 1 | <b>B11.3 Security of the works</b><br>Fixed: _____ Value related: _____ Time<br>related: _____               | Item |
| 2 | <b>B11.4 Notice before covering work</b><br>Fixed: _____ Value related: _____ Time<br>related: _____         | Item |
| 3 | <b>B11.5 Disturbance</b><br>Fixed: _____ Value related: _____ Time<br>related: _____                         | Item |
| 4 | <b>B11.6 Environmental disturbance</b><br>Fixed: _____ Value related: _____ Time<br>related: _____           | Item |
| 5 | <b>B11.7 Works cleaning and clearing</b><br>Fixed: _____ Value related: _____ Time<br>related: _____         | Item |
| 6 | <b>B11.8 Vermin</b><br>Fixed: _____ Value related: _____ Time<br>related: _____                              | Item |
| 7 | <b>B11.9 Overhand work</b><br>Fixed: _____ Value related: _____ Time<br>related: _____                       | Item |
| 8 | <b>B11.10 Instruction manuals and guarantees</b><br>Fixed: _____ Value related: _____ Time<br>related: _____ | Item |
| 9 | <b>B11.11 As built information</b><br>Fixed: _____ Value related: _____ Time<br>related: _____               | Item |

Carried to Collection

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**

|   |   |      |  |   |
|---|---|------|--|---|
| 1 | <p><b>B11.12 Tenant installations</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p><b><u>B12.0 SCHEDULE OF VARIABLES</u></b></p>   | Item |  |   |
| 2 | <p><b>B12.1 Schedule of variables</b></p> <p>Fixed: _____ Value related: _____ Time related: _____</p> <p>This <b>schedule</b> contains all variables referred to in this document and is divided into pre-tender and post-tender categories. The pre-tender category must be completed in full and included in the tender documents. Both the pre-tender and post-tender categories form part of these <b>Preliminaries</b></p> <p>Spaces requiring information must be filled in, shown as "not applicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the <b>schedule</b>. Key cross reference clauses are italicised in [ ] brackets</p> <p><b>12.1 PRE-TENDER INFORMATION</b></p> <p><b>12.1.1 Provisional bills of quantities</b><br/>[2.2] The quantities are provisional</p> <p style="text-align: right;"><b>YES</b></p> <p><b>12.1.2 Availability of construction documentation</b><br/>[2.3] <i>Construction documentation is complete</i></p> <p style="text-align: right;"><b>YES</b></p> <p><b>12.1.3 Interests of agents</b><br/>[2.4] Details:</p> <p><b>12.1.4 Defined works area</b><br/>[3.1] Details:</p> <p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section No. 1<br/>Bill No. 1<br/>PRELIMINARIES AND GENERAL<br/><b>QEBE JSS</b><br/><b>PROVISIONAL BILLS OF QUANTITIES</b></p> | Item |  | R |

12.1.5 **Geotechnical investigation**

[3.2] Details:

12.1.6 **Existing premises occupied**

[3.4] Specific requirements:

12.1.7 **Previous work - dimensional accuracy**

[3.5] Details:

12.1.8 **Previous work - defects**

[3.6] Details:

12.1.9 **Services - known**

[3.7] Details:

12.1.10 **Protection of trees**

[3.9] Specific requirements:

12.1.11 **Inspection of adjoining properties**

[3.11] Specific requirements:

12.1.12 **Enclosure of the works**

[6.2] Specific requirements:

12.1.13 **Offices**

[6.4.3] Specific requirements:

The **contractor** shall provide, maintain and remove on completion of the works an office for the exclusive use of the **principal agent**, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

12.1.14 **Main notice board**

[6.5] Specific requirements:

The **contractor** shall provide, erect where directed, maintain and remove on completion of the **works** a notice board size 3 x 3m as type Drawing GEN 063, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green. All wording shall be inscribed in dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted sans serif lettering

12.1.15 **Subcontractors' notice board**[6.6] *A notice board is required*

Specific requirements: **NO**

12.1.16 **Water**[7.2] Option A (by **contractor**)**NO**Option B (by **employer** - free of charge)**NO**Option C (by **employer** - metered)**YES****Carried to Collection****R**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

**12.1.17 Electricity****[7.3]** Option A (by **contractor**)**NO**Option B (by **employer** - free of charge)**NO**Option C (by **employer** - metered)**YES****12.1.18 Telecommunications****[7.4]** Telephone**YES**

Facsimile

**YES**

E-mail

**YES****12.1.19 Ablution facilities****[7.5]** Option A (by **contractor**)**YES**Option B (by **employer**)**NO****12.1.20 Protection of existing/sectionally occupied works****[11.2]** Protection is required**NO****Carried to Collection****R**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

12.1.21 **Special attendance**[9.2] **Subcontractor** (1) details:**Subcontractor** (2) details:**Subcontractor** (3) details:**Subcontractor** (4) details:12.1.22 **Protection of the works**

[11.1] Specific requirements:

12.1.23 **Disturbance**

[11.5] Specific requirements:

The **contractor** shall keep the site, structures, etc well watered during operations to prevent dust and shall provide and erect and remove on completion of the **works** all necessary temporary dust screens all to the satisfaction of the **principal agent**

12.1.24 **Environmental disturbance**

[11.6] Specific requirements:

**12.2 POST-TENDER INFORMATION**12.2.1 **Payment of preliminaries**

[10.2] Option A (prorated)

**NO**

Option B (calculated)

**YES****Carried to Collection****R**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**



12.2.2 **Adjustment of preliminaries**

[10.3] Option A (three categories)

**NO**

Option B (detailed breakdown)

**YES**12.2.3 **Additional agreed preliminaries items**

Details:

**Carried to Collection****R**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

**SECTION C: SPECIFIC PRELIMINARIES**

**Section C** contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item

**1 C1.0 CONTRACT DRAWINGS**

The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the **works** and the manner in which they are to be executed

Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the **principal agent**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**2 C2.0 GENERAL PREAMBLES**

The document "Specification of Materials and Methods to be used - PW371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014)." is obtainable on the Department's website (<http://www.publicworks.gov.za/> under "Consultants Guidelines"), and shall be read in conjunction with the **bills of quantities / lump sum document** and be referred to for the full descriptions of work to be done and materials to be used

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **C3.0 TRADE NAMES**

Wherever a trade name for any product has been described in the **bills of quantities / lump sum document**, the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the **principal agent** being obtained prior to the closing date for submission of tenders

If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

2 **C4.0 HIV/AIDS AWARENESS**

It is required of the **contractor** to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the **bills of quantities / lump sum document**. Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained

The **contractor** must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the **principal agent**, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress **payment certificate** until the **contractor** provides satisfactory proof of compliance. The **contractor** shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

**C4.1 AWARENESS CHAMPION**

Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**C4.2 AWARENESS WORKSHOPS**

Selection and appointment of a competent Service Provider approved by the **principal agent**, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi-media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**C4.3 POSTERS, BOOKLETS, VIDEOS, ETC.**

Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the **construction period**, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**C4.4 ACCESS TO CONDOMS**

Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the **construction period**, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

**C4.5 MONITORING**

Monitoring HIV/AIDS awareness of workers, providing the **principal agent** with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the **construction period** and close out, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
 Time related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**QEBE JSS**  
**PROVISIONAL BILLS OF QUANTITIES**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

**Carried Forward****R**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**COLLECTION****Brought Forward****Page  
No****Amount**

R

Total Brought Forward from Page No.

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

**Carried Forward to Summary of Section No. 1**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**





|   |  |    |      |
|---|--|----|------|
| 1   | Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period. | No | Item |
| 2   | Provision of full time Health and Safety Officer for the entire construction period.   | No | Item |
| 3   | Induction training of personnel.   | No |      |
| 4   | Provision of first aid boxes.  | No |      |
| <b><u>Provision for Personal Protective Equipment and Protective Clothing:</u></b>                            |  |    |      |
| 5   | Reflective vests.  | No |      |
| 6   | Hard hats.   | No |      |
| 7   | Protective foot wear.  | No |      |
| 8   | Ear Plugs.   | No |      |
| 9   | Dust Masks.  | No |      |
| <b><u>Costs of Medical Certificates and Medical Surveillance:</u></b>   |  |    |      |
| 10  | Initial (baseline) medical examinations.   | No |      |
| 11  | Exit Examinations.   | No |      |
| <b><u>Noise Monitoring:</u></b>   |  |    |      |
| 12  | Establishment of noise zones.  | No |      |
| 13  | Audiograms.  | No |      |
| <b>Carried to Collection</b>  |  |    | R    |
| Section No. 1<br>Bill No. 2<br>HEALTH AND SAFETY<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |  |    |      |

Section No. 1

Bill No. 2

HEALTH AND SAFETY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

40

41

**Carried Forward to Summary of Section No. 1**

R

Section No. 1

Bill No. 2

HEALTH AND SAFETY

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Bill<br>No   | SECTION SUMMARY - SECTION NO.1 - PRELIMINIARIES AND GENERAL | Page<br>No               | Amount |
|--|---|--------------------------|--------|
| 1  | PRELIMINARIES AND GENERAL                                   | 39                       |        |
| 2  | HEALTH AND SAFETY   | 42                       |        |
| Section No. 1<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |   | Carried to Final Summary |        |
|  |   |                          | R      |

| Item No  |  | Quantity | Rate | Amount |
|--|--|----------|------|--------|
| <b><u>SECTION No. 2 - BUILDING WORKS</u></b>   |  |          |      |        |
| <b><u>BILL No. 1</u></b>   |  |          |      |        |
| <b><u>ALTERATIONS, DEMOLITIONS, ETC.</u></b>   |  |          |      |        |
| <u>Note:</u>   |  |          |      |        |
| For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). |  |          |      |        |
| <b><u>DEMOLITIONS</u></b>  |  |          |      |        |
| <b><u>Ordinary demolitions</u></b>   |  |          |      |        |
| Reference hereunder to cart away shall mean carting off site to a dumping site to be located by the Contractor.  |  |          |      |        |
| <b><u>ROOF COVERINGS, ETC.</u></b>   |  |          |      |        |
| 1  | Take down and cart away galvanised IBR profile roof covering fixed to steel or timber. | m2       | 25   |        |
| 2  | Take down and cart away galvanised steel ridge capping.                                | m        | 3    |        |
| <b><u>CARPENTRY AND JOINERY</u></b>  |  |          |      |        |
| <u>Roof structures</u>   |  |          |      |        |
| 3  | Demolish and cart away timber purlin.  | m        | 20   |        |
| <u>Skirting</u>  |  |          |      |        |
| 4  | Take down and cart away timber skirting.   | m        | 6    |        |
| <u>Externally</u>  |  |          |      |        |
| 5  | Take down and cart away 20 x 220mm timber/fibre cement fascia board.                   | m        | 4    |        |
| <b>Carried to Collection</b>   |  |          |      | R      |
| Section No. 2  |  |          |      |        |
| Bill No. 1   |  |          |      |        |
| ALTERATIONS  |  |          |      |        |
| <b>QEBE JSS</b>  |  |          |      |        |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>   |  |          |      |        |

**CEILINGS AND PARTITIONS**Internally

- |   |  |    |    |
|---|--|----|----|
| 1 | Take down and cart away fibre cement ceilings approximately 2800mm from ground level including all cornices, brandering, supporting structures, etc. | m2 | 17 |
| 2 | Take down and cart away gypsum coved cornice.  | m  | 7  |

**FLOOR COVERINGS**

- |   |  |    |    |
|---|--|----|----|
| 3 | Strip from concrete floors vinyl floor tiling and cart away including preparing screed for new floor covering (elsewhere). | m2 | 14 |
|---|--|----|----|

**IRONMONGERY**General ironmongery

- |   |  |    |   |
|---|--|----|---|
| 4 | Take out from steel door and cart away, cylinder or mortice lockset. | No | 1 |
| 5 | Take off from steel door and cart away, lever furniture set.         | No | 1 |

Pinning Boards

- |   |  |    |   |
|---|--|----|---|
| 6 | Take down and cart away felt backing pinning boards, size approximately 5000 x 1500mm high including filling holes with cement mortar. | No | 2 |
|---|--|----|---|

Chalk Boards

- |   |   |    |   |
|---|---|----|---|
| 7 | Take down and cart away chalk boards, size approximately 4800 x 1200mm high including filling holes with cement mortar. | No | 1 |
|---|---|----|---|

Lockers

- |   |   |    |   |
|---|---|----|---|
| 8 | Take down and cart away double door steel stationery cupboard, size approximately 900 x 450 x 1800mm high including filling holes with cement mortar. | No | 1 |
|---|---|----|---|

**Carried to Collection****R**

Section No. 2

Bill No. 1

ALTERATIONS

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

**PLASTERING**Walls

- |   |  |    |   |
|---|--|----|---|
| 1 | Hack off plaster from brick wall and cart away including preparing to receive new plaster (elsewhere). | m2 | 8 |
|---|--|----|---|

**GLAZING**

- |   |   |    |   |
|---|---|----|---|
| 2 | Take out 4mm thick glass from galvanised steel window including preparing frame to receive new glass (elsewhere). | m2 | 9 |
|---|---|----|---|

**REFURBISHMENT, PREPARATORY WORKS, ETC.**Sundry brickwork refurbishment

- |   |  |    |   |
|---|--|----|---|
| 3 | Replace broken brick in existing face brick wall with matching brick bedded, jointed and pointed in cement mortar to match existing. | No | 8 |
|---|--|----|---|

General repair work

- |   |   |   |   |
|---|---|---|---|
| 4 | Hack plaster from brickwork for a width of 100mm either side of crack, nail galvanised stretch plate over crack with steel nails at 200mm centres to receive plaster (elsewhere). | m | 5 |
|---|---|---|---|

**METAL WORK**Servicing of windows, doors, etc.

- |   |   |    |    |
|---|---|----|----|
| 5 | Service aluminium window, size approximately 600 x 600mm high with top hung opening light including ensuring smooth opening and closing and replacement of missing stays, catches, etc. as necessary to match existing. | No | 24 |
| 6 | Service and adjust existing external double aluminium door and frame, including oiling and easing hinges, preparing to receive new lock, touching up and making good.   | No | 1  |

**Carried to Collection****R**

Section No. 2

Bill No. 1

ALTERATIONS

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Servicing of steel doors,frames,etc.

|   |  |    |   |
|---|--|----|---|
| 1 | Service and adjust existing single steel gate size 900 x 2100mm high, including oiling and easing hinges, secure hinges to wall, touching up and making good.          | No | 1 |
| 2 | Service and adjust existing double steel gate size 1475 x 2100mm high, including oiling and easing hinges, secure hinges to wall, touching up and making good.         | No | 1 |
| 3 | Service and adjust existing double steel gate size 2130 x 2100mm high, including oiling and easing hinges, preparing to receive new lock, touching up and making good. | No | 1 |

Refurbishment by cleaningWalls, concrete columns, tiling, etc.

|   |   |    |     |
|---|---|----|-----|
| 4 | High pressure clean external face brick facade to remove dirt, lichen, moss, etc. complete including recess pointing and jointing in cement mortar, where necessary, to match existing. | m2 | 162 |
|---|---|----|-----|

Carried to Collection

R

Section No. 2

Bill No. 1

ALTERATIONS

QEBE JSS

PROVISIONAL BILLS OF QUANTITIES

Section No. 2

Bill No. 1

ALTERATIONS

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

44

45

46

47

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 1

ALTERATIONS

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**



[illegible]

[illegible]

| Item No |  | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
|         | <b><u>BILL No. 4</u></b>   |          |      |        |
|         | <b><u>CARPENTRY AND JOINERY</u></b>  |          |      |        |
|         | <u>Note:</u>   |          |      |        |
|         | For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).   |          |      |        |
|         | <b><u>CARPENTRY</u></b>  |          |      |        |
|         | <b><u>Purlins, bracing, etc.</u></b>   |          |      |        |
|         | <u>Wrot softwood :</u>   |          |      |        |
| 1       | 50 x 76mm Purlins.   | m        | 20   |        |
|         | <b><u>JOINERY</u></b>  |          |      |        |
|         | <u>Skirtings</u>   |          |      |        |
| 2       | Check timber skirting, realign where necessary and ensure skirting is securely nailed to the wall.   | m        | 33   |        |
| 3       | 16 x 76mm Wrought meranti hollow-backed skirting plugged to wall, with 19mm matching quadrant bead at junction with floor.   | m        | 6    |        |
|         | <b><u>Plastic, fibre cement, etc.</u></b>  |          |      |        |
|         | <u>Work to existing fascia/barge boards</u>  |          |      |        |
| 4       | Check fibre cement fascia boards complete, including joining strips, for alignment/rigidity and where necessary replace missing screws or joining strips to existing members to leave fascia boards secure to rafters. | m        | 20   |        |
|         | <u>Pressed fibre-cement:</u>   |          |      |        |
| 5       | 12 x 228mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc.  | m        | 4    |        |
|         | <b>Carried to Collection</b>   |          |      | R      |
|         | Section No. 2  |          |      |        |
|         | Bill No. 4   |          |      |        |
|         | CARPENTRY AND JOINERY  |          |      |        |
|         | <b>QEBE JSS</b>  |          |      |        |
|         | <b>PROVISIONAL BILLS OF QUANTITIES</b>   |          |      |        |

|   |   |   |    |   |  |
|---|---|---|----|---|--|
| 1   | 80 x 275mm Barge board drilled and brass screwed to timber purlins including galvanised steel H-profile jointing strips, etc. | m | 25 |   |  |
| Carried to Collection   |   |   |    | R |  |
| Section No. 2<br>Bill No. 4<br>CARPENTRY AND JOINERY<br>QEBE JSS<br>PROVISIONAL BILLS OF QUANTITIES |   |   |    |   |  |

Section No. 2

Bill No. 4

CARPENTRY AND JOINERY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

51

52

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 4

CARPENTRY AND JOINERY

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Item No |  | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
|         | <b><u>BILL No. 5</u></b>   |          |      |        |
|         | <b><u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u></b>   |          |      |        |
|         | <u>Note:</u>   |          |      |        |
|         | For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).                 |          |      |        |
|         | <b><u>INTERNAL NAILED UP CEILINGS</u></b>  |          |      |        |
|         | <u>Work to existing ceilings</u>   |          |      |        |
| 1       | Check fibreceement ceiling complete, including cover strips, for alignment/rigidity and where necessary re-nail ceiling or cover strips to existing members to leave ceiling level and secure. | m2       | 69   |        |
|         | <u>4mm Thick fibre-cement boards with and including 6 x 32mm wrought meranti coverstrips over joints:</u>  |          |      |        |
| 2       | Ceilings including 38 x 50mm sawn softwood brandering at 400mm centres with cross brandering at joints, ends of sheets and at light fittings, etc.   | m2       | 17   |        |
|         | <b><u>Cornices</u></b>   |          |      |        |
|         | <u>Work to existing cornices</u>   |          |      |        |
| 3       | Check gypsum plasterboard cornice, realign where necessary and ensure cornice is securely nailed to brandering or wall.  | m        | 33   |        |
|         | <u>Paper covered gypsum cornice with skimmed joints plugged to walls including mitres, etc.:</u>   |          |      |        |
| 4       | 75mm Coved cornice.  | m        | 7    |        |
|         | <b>Carried Forward to Summary of Section No. 2</b>   |          | R    |        |
|         | Section No. 2  |          |      |        |
|         | Bill No. 5   |          |      |        |
|         | CEILINGS, PARTITIONS AND ACCESS FLOORING   |          |      |        |
|         | <b>QEBE JSS</b>  |          |      |        |
|         | <b>PROVISIONAL BILLS OF QUANTITIES</b>   |          |      |        |

[illegible]

| Item No |  | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
|         | <b>BILL No. 7</b>  |          |      |        |
|         | <b><u>IRONMONGERY</u></b>  |          |      |        |
|         | <u>Note:</u><br><br>For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). |          |      |        |
|         | <b><u>IRONMONGERY TO ALUMINIUM</u></b>   |          |      |        |
|         | <b><u>Hooks</u></b>  |          |      |        |
| 1       | 150mm Brass cabin hook and eye screwed to and including 69 x 69 x 32mm chamfered hardwood block plugged to wall.   | No 1     |      |        |
|         | <b><u>Door stops</u></b>   |          |      |        |
| 2       | Black rubber door stop plugged to wall or floor.   | No 1     |      |        |
|         | <b><u>Locksets, etc. provided with two keys and to be masterkeyed</u></b>  |          |      |        |
| 3       | "Union Gower CZ682-24-61SC" or other equal approved satin chrome finish four lever lockset complete with chromium plated lever furniture.  | No 1     |      |        |
|         | <b><u>IRONMONGERY TO METALWORK</u></b>   |          |      |        |
|         | <b><u>Locksets, etc. provided with two keys and to be masterkeyed</u></b>  |          |      |        |
| 4       | "CISA" or other approved 50mm brass padlock with stainless steel shackle.  | No 2     |      |        |
|         | <b><u>Sundries</u></b>   |          |      |        |
| 5       | 50mm Plastic key tag.  | No 1     |      |        |
|         | <b>Carried to Collection</b>   |          | R    |        |
|         | Section No. 2<br>Bill No. 7<br>IRONMONGERY<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b>  |          |      |        |



**PROPRIETARY KITCHEN CUPBOARDS, LOCKERS,  
WRITING BOARDS, SEATS, ETC.****Lockers**

- 1 Powder coated "Grey" steel standard two-door stationary cupboard, size 900mm wide x 450mm deep x 1800mm high, provided complete with four shelves, chromium plated locking mechanism, four times bolted to brickwork with and including 10 x 85mm long masonry anchors.

No

1

**Writing boards**

- 2 "Parrot Products" Educational board with deluxe aluminium perimeter frame, size overall 4890 x 1230mm high, with magnetic chalkboard centre panel fitted with aluminium chalkrail, size 2420 x 1230mm high, two outer fixed leaves, each size 1220 x 1230mm high, two double sided swing leaf panels fitted with heavy duty plastic hinges, each leaf size 1210 x 1230mm high, mounted to wall with and including proprietary wall fixings.

No

1

**Information notice boards**

- 3 "Parrot Products BD 0476" Information board with felt backing and aluminium perimeter frame, size 2400 x 1200mm high, concealed mounted to wall with proprietary wall fixings.

No

4

**Carried to Collection**

R

Section No. 2

Bill No. 7

IRONMONGERY

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Section No. 2

Bill No. 7

IRONMONGERY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

56

57

**Amount****Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 7

IRONMONGERY

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

[illegible]

| Item No  |   | Quantity | Rate | Amount |
|--|---|----------|------|--------|
| <b><u>BILL No. 9</u></b>   |   |          |      |        |
| <b><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></b>  |   |          |      |        |
| <u>Note:</u>   |   |          |      |        |
| For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). |   |          |      |        |
| <b><u>GUTTERS, ETC</u></b>   |   |          |      |        |
| <b><u>Roof gutters, rainwater pipes, etc.</u></b>  |   |          |      |        |
| <u>Work to existing aluminium guttering</u>  |   |          |      |        |
| 1  | Check aluminium gutters complete, including joints, accessories and proprietary fixings to existing members to leave gutters secure to fascia boards. | m        | 20   |        |
| 2  | Check aluminium downpipes complete, including joints, accessories and proprietary fixings.  | m        | 16   |        |
| <u>Powder coated seamless aluminium rainwater gutters, downpipes and accessories</u>   |   |          |      |        |
| 3  | 85 x 125mm Gutter fixed to fascia at maximum 600mm centres with and including proprietary fixings.  | m        | 5    |        |
| 4  | Extra over gutter for forming discharge outlet to suit 75 x 100mm downpipe.   | No       | 2    |        |
| 5  | Extra over gutter for stopped end.  | No       | 2    |        |
| 6  | 75 x 100mm Rainwater downpipe fixed to wall with and including proprietary holderbats.  | m        | 5    |        |
| 7  | Extra over rainwater downpipe for bend.   | No       | 3    |        |
| <b>Carried Forward to Summary of Section No. 2</b>   |   |          |      | R      |
| Section No. 2<br>Bill No. 9<br>PLUMBING AND DRAINAGE<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b>  |   |          |      |        |



| Item No  |  | Quantity | Rate | Amount |
|--|--|----------|------|--------|
| <b><u>BILL No. 11</u></b>  |  |          |      |        |
| <b><u>PAINTWORK</u></b>  |  |          |      |        |
| <u>Note:</u>   |  |          |      |        |
| For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).   |  |          |      |        |
| <b><u>REDECORATION OF EXISTING</u></b>   |  |          |      |        |
| <b><u>PREVIOUSLY PAINTED CONCRETE, PLASTER, ETC</u></b>  |  |          |      |        |
| <u>Scrape down loose or peeling paint, clean off surface contaminants with a sugar soap solution, allow to dry, stop all holes, minor cracks, etc. and apply one coat plaster primer and two coats exterior acrylic emulsion sheen paint on:</u>                   |  |          |      |        |
| 1  | External smooth plastered walls in narrow widths not exceeding 300mm wide. | m2       | 15   |        |
| <u>Scrape down loose or peeling paint, clean off surface contaminants with a sugar soap solution, allow to dry, stop all holes, minor cracks, etc. and apply one coat plaster primer and two coats interior washable acrylic washable emulsion sheen paint on:</u> |  |          |      |        |
| 2  | Internal plastered walls.  | m2       | 82   |        |
| 3  | Internal smooth plastered walls in narrow widths not exceeding 300mm wide. | m2       | 16   |        |
| <b>Carried to Collection</b>   |  |          |      | R      |
| Section No. 2<br>Bill No. 11<br>PAINTWORK<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b>   |  |          |      |        |

PREVIOUSLY PAINTED GYPSUM PLASTERBOARD

Scrape down loose or peeling paint, clean off surface contaminants with a sugar soap solution, allow to dry, stop all holes, minor cracks, etc. and apply one coat plaster primer and two coats interior acrylic emulsion sheen paint on:

|   |                            |    |    |
|---|----------------------------|----|----|
| 1 | Internal ceiling boarding. | m2 | 72 |
|---|----------------------------|----|----|

PREVIOUSLY PAINTED FIBRE CEMENT

Scrape down loose or peeling paint, clean off surface contaminants with a sugar soap solution, allow to dry and apply one coat primer and two coats professional exterior super matt paint on:

|   |                           |    |   |
|---|---------------------------|----|---|
| 2 | Fascias and barge boards. | m2 | 5 |
|---|---------------------------|----|---|

PREVIOUSLY PAINTED METALWORK

Scrape down loose or peeling paint, remove all traces of rust, clean off surface contaminants with a sugar soap solution, allow to dry and apply galvanised iron primer (where necessary) and two coats super universal enamel paint on:

|   |                                     |    |     |
|---|-------------------------------------|----|-----|
| 3 | IBR corrugated steel roof sheeting. | m2 | 134 |
|---|-------------------------------------|----|-----|

Scrape down loose or peeling paint, remove all traces of rust, clean off surface contaminants with a sugar soap solution, allow to dry and apply galvanised iron primer (where necessary) and two coats super universal enamel paint on:

|   |                                |    |   |
|---|--------------------------------|----|---|
| 4 | Steel tubular support columns. | m2 | 3 |
|---|--------------------------------|----|---|

PREVIOUSLY PAINTED TIMBER

Sand down painted surface to bare timber and apply one coat exterior primer, one coat undercoat and two coats flat enamel paint on:

|   |   |    |    |
|---|---|----|----|
| 5 | General surfaces of timber rafters, beams, etc. | m2 | 11 |
|---|---|----|----|

|   |   |   |    |
|---|---|---|----|
| 6 | General surfaces of roof timbers not exceeding 300mm girth. | m | 47 |
|---|---|---|----|

**Carried to Collection**

R

Section No. 2

Bill No. 11

PAINTWORK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

|   |   |    |    |   |  |
|---|---|----|----|---|--|
| <u>Sand down varnished surface to bare timber and apply two coats interior quality clear matt varnish on:</u>                         |   |    |    |   |  |
| 1   | Skirtings not exceeding 300mm girth.                                  | m  | 33 |   |  |
| <b><u>NEW WORKS</u></b>   |   |    |    |   |  |
| <b><u>PAINT ON TIMBER</u></b>   |   |    |    |   |  |
| <u>Prepare and apply three coats exterior quality clear polyurethane varnish on :</u>   |   |    |    |   |  |
| 2   | Skirtings, cornices or rails not exceeding 300mm girth.               | m  | 6  |   |  |
| <b><u>PAINT ON FIBRE-CEMENT</u></b>   |   |    |    |   |  |
| <u>Prime nail heads and H-section jointing strips and apply one coat universal undercoat and two coats eggshell enamel paint on :</u> |   |    |    |   |  |
| 3   | Internal fibre cement board ceilings including priming cover strips.  | m2 | 17 |   |  |
| <u>Prepare and apply one coat plaster primer and two coats quality matt acrylic PVA on :</u>  |   |    |    |   |  |
| 4   | External fibre cement fascia boarding including priming cover strips. | m2 | 1  |   |  |
| 5   | External fibre cement bargeboard including priming cover strips.      | m2 | 8  |   |  |
| <b>Carried to Collection</b>  |   |    |    | R |  |
| Section No. 2   |   |    |    |   |  |
| Bill No. 11   |   |    |    |   |  |
| PAINTWORK   |   |    |    |   |  |
| <b>QEBE JSS</b>   |   |    |    |   |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>  |   |    |    |   |  |



Section No. 2

Bill No. 11

PAINTWORK

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

62

63

64

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 11

PAINTWORK

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**



| Item No |  | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
|         | <b><u>SECTION No. 3 - PREFABRICATED BUILDINGS</u></b>  |          |      |        |
|         | <b><u>BILL No. 1</u></b>   |          |      |        |
|         | <b><u>PLATFORM CONSTRUCTION (ALL TRADES) PROVISIONAL</u></b>   |          |      |        |
|         | <u>Note:</u>   |          |      |        |
|         | For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). |          |      |        |
|         | <b><u>EXCAVATIONS, FILLING, ETC.</u></b>   |          |      |        |
|         | <b><u>Classification of material to be excavated</u></b>   |          |      |        |
|         | Detailed geotechnical data sheets for the area of the works have been included at the back of these Bills of Quantities for the Contractor's information.                      |          |      |        |
|         | <b><u>EXCAVATIONS FOR FOUNDATIONS, ETC.</u></b>  |          |      |        |
|         | <u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>                |          |      |        |
| 1       | Reduced levels under solid floors.   | m3       | 78   |        |
| 2       | Ground beams.  | m3       | 13   |        |
|         | <b><u>Carting away of excavated material</u></b>   |          |      |        |
| 3       | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.  | m3       | 91   |        |
|         | <b><u>Risk of collapse of excavations</u></b>  |          |      |        |
| 4       | Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.  | m2       | 85   |        |
|         | <b>Carried to Collection</b>   |          |      | R      |
|         | Section No. 3  |          |      |        |
|         | Bill No. 1   |          |      |        |
|         | PLATFORM CONSTRUCTION  |          |      |        |
|         | <b>QEBE JSS</b>  |          |      |        |
|         | <b>PROVISIONAL BILLS OF QUANTITIES</b>   |          |      |        |

### Filling

|   |   |    |    |
|---|---|----|----|
| 3 | 50mm Thick layer of approved river sand supplied by the Contractor spread and levelled under floors, etc. | m3 | 26 |
|---|---|----|----|

### Compaction of surfaces

|   |   |    |     |
|---|---|----|-----|
| 4 | Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density. | m2 | 518 |
|---|---|----|-----|

**Weedkillers, insecticides, etc.**

|   |  |    |     |
|---|--|----|-----|
| 5 | Under floors, etc. including forming and poisoning shallow furrows against all foundation walls, filling in furrows and ramming. | m2 | 668 |
|---|--|----|-----|

## Tests

|   |  |    |       |
|---|--|----|-------|
| 6 | Allow for Mod AASHTO density tests on filling. | No | 10.00 |
|---|--|----|-------|

## CONCRETE

|   |  |    |   |
|---|--|----|---|
| 7 | Blinking beneath bases, strip footings, etc cast against excavated surfaces. | m3 | 3 |
|---|--|----|---|

|   |   |    |    |
|---|---|----|----|
| 8 | Rafter slabs cast against excavated surfaces. | m3 | 83 |
|---|---|----|----|

## Surface treatment

|   |  |    |     |
|---|--|----|-----|
| 9 | Powerfloating of concrete surface bed. | m2 | 518 |
|---|--|----|-----|

R

-68-

|   |   |    |       |  |  |
|---|---|----|-------|--|--|
| <b><u>Test blocks and testing</u></b>                             |   |    |       |  |  |
| 1   | Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional) | No | 10    |  |  |
| <b><u>Movement joints</u></b>                                     |   |    |       |  |  |
| 2   | 10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.                             | m  | 100   |  |  |
| <b><u>FORMWORK</u></b>  |   |    |       |  |  |
| <u>Rough formwork (use and waste) to concrete to:</u>             |   |    |       |  |  |
| <b><u>Edges, risers, ends and reveals</u></b>                     |   |    |       |  |  |
| 3   | Edge, riser, etc not exceeding 300mm high.  | m  | 213   |  |  |
| <b><u>REINFORCEMENT (PROVISIONAL)</u></b>                         |   |    |       |  |  |
| <b><u>Bar reinforcement</u></b>                                   |   |    |       |  |  |
| <u>Mild steel rod reinforcement to structural concrete work</u>   |   |    |       |  |  |
| 4   | 10mm Diameter bars.   | t  | 0.383 |  |  |
| <u>High tensile rod reinforcement to structural concrete work</u> |   |    |       |  |  |
| 5   | 10mm Diameter bars.   | t  | 0.383 |  |  |
| 6   | 12mm Diameter bars.   | t  | 0.384 |  |  |
| 7   | 16mm Diameter bars.   | t  | 0.384 |  |  |
| <b><u>Welded mesh reinforcement</u></b>                           |   |    |       |  |  |
| <u>High tensile welded steel mesh reinforcement :</u>             |   |    |       |  |  |
| 8   | Ref: 395 cast into concrete surfaces.   | m2 | 518   |  |  |
| <b>Carried to Collection</b>                                      |   |    |       |  |  |
| Section No. 3   |   |    |       |  |  |
| Bill No. 1  |   |    |       |  |  |
| PLATFORM CONSTRUCTION   |   |    |       |  |  |
| <b>QEBE JSS</b>   |   |    |       |  |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>                            |   |    |       |  |  |

R

**SHEET OR MEMBRANE WATERPROOFING****Sheet or membrane waterproofing to floors**250 Micron "Gunplas USB" green polyethylene sheeting

:

- |   |   |    |     |  |  |
|---|---|----|-----|--|--|
| 1 | Laid flat on prepared sand bed under solid floor. | m2 | 570 |  |  |
|---|---|----|-----|--|--|

**WATERSTOPS, SEALING STRIPS, JOINT SEALANTS, ETC.****Joint sealants**To horizontal concrete surfaces

- |   |  |   |     |  |  |
|---|--|---|-----|--|--|
| 2 | Remove 10 x 15mm hinged blocking piece, insert polycord bond breaker and seal with an approved 2 part polysulphide sealer. | m | 100 |  |  |
|---|--|---|-----|--|--|

**STEEL**Tubular columns

- |   |  |    |    |  |  |
|---|--|----|----|--|--|
| 3 | 101.6mm Diameter x 3.0mm wall thickness hot dipped galvanised steel column, 2700mm long, with 200 x 200 x 6mm base plate welded on to one end and other end having U-shaped bracket, 460mm girth x 250mm long x 3mm plate thickness, eight times holed for bolts, welded on including setting up in position and embedding in concrete | No | 12 |  |  |
|---|--|----|----|--|--|

**Carried to Collection****R**

Section No. 3

Bill No. 1

PLATFORM CONSTRUCTION

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Section No. 3

Bill No. 1

PLATFORM CONSTRUCTION

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

67

68

69

70

**Carried Forward to Summary of Section No. 3**

R

Section No. 3

Bill No. 1

PLATFORM CONSTRUCTION

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Item No |   | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
|         | <p><b><u>BILL No. 2</u></b></p> <p><b><u>5 CLASSROOM BLOCK</u></b></p> <p><u>Note:</u></p> <p>For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).</p> <p><u>Construction Notes:</u></p> <p><b>All construction materials are to be SABS or AGREEMENT South Africa Certified'.</b></p> <p><b>Prefabricated systems are to be presented to the Principal Agent for approval before construction commences.</b></p> <p>Concrete strip footings and slab to be constructed by the main contractor.</p> <p>Chassis construction must run the full length and full width of the unit and consist of structurally welded steel chassis with minimum of 2 x 200 x 75 x 20 x 3mm lip channel longitudinal main members running the length of the building at 1640mm centres, 75 x 50 x 20 x 2.5mm lipped channel cross members set at maximum of 600mm centres. Steps to be supplied where applicable. All structural steel is to be coated with one coat red oxide primer and two coats latex paint.</p> <p>The chassis is to fixed to the slab with 6mm x 50mm long masonry anchors at 500mm centers and including non-shrink grout</p> |          |      |        |
|         | Carried to Collection   |          | R    |        |
|         | <p>Section No. 3</p> <p>Bill No. 2</p> <p>5 CLASSROOM BLOCK</p> <p><b>QEBE JSS</b></p> <p><b>PROVISIONAL BILLS OF QUANTITIES</b></p>  |          |      |        |



External walls to be constructed of 42mm Chromadeck composite laminated polyurethane core panel interlocking system with tongue and groove interlocking joints sealed with an approved silicon sealant including fixing panels mechanically to base rail as per manufactures specifications.

External walls to be finished both sides with 0.5mm pre-painted "Frost white" hot dipped galvanised steel rigidised Chromadek sheeting.

Top of external walls to be fixed to the underside of the roof panel with natural anodised extruded aluminium side wallplate fixed to external wall including pop rivets at 150mm centres and 90mm long roof screws at 450mm centers through both panels. (See attached drawing 501- Roof/Wall Assembly Vertical Sections)

All corner, edge and ridge capping, etc to be formed from 0.58mm Chromadek including rivets, sealant, etc. (See attached drawing 500- corner detail- horizontal section)

All windows to be powder coated aluminium including necessary ironmongery and burglar proofing to opening sections as per schedule.

Windows to be glazed with 6,38mm thick normal strength clear laminated safety glass including gaskets.

Ablution windows to be fitted with obscure or frosted glazing.

The perimeter of the frame to the adjacent surface to be sealed with an approved polysulphide sealant.

**Carried to Collection**

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

External door frames to be powder coated aluminium fitted with neoprene gaskets.

Single external doors to be 0.5mm 44mm Thick framed, ledged, braced and battened stable door, size 813 x 2032mm high, the top leaf comprising 44 x 108mm stiles, top and bottom rails, the bottom leaf comprising 44 x 108mm stiles and top rail and 22 x 215mm bottom rail, both leaves fitted with 22 x 75mm diagonal braces and 44 x 70mm splayed and rebated weatherboards countersunk brass screwed on at maximum 200mm centres and filled with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths,  
each door to be fitted with the following :

1. Three 100 x 44mm sinkless aluminium butt hinges
2. 2209 - 78SS" Euro profile upright cylinder lock case
3. 2 x 18 SC satin chrome double cylinder lock mechanism
4. Heavy duty satin chrome lever handle on 165 x 50 x 8mm cast backplate with cylinder lockset cutout.
5. Splayed and rebated weatherboard fixed to the bottom of the door
6. Stainless steel buffered door stop.

All doors to be finished with apply, one coat pre treatment one coat pink wood primer, one undercoat and two coats water based eggshell enamel.

All lock sets are to be master keyed.

**Carried to Collection**

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Roof structure to be a minimum of 11 degree pitch with a overhang of 300mm on one side and 1500mm the other side over verandah.

The roof is to consist of all necessary lattice ridge beams fixed to gable walls with 4 x 10 x 60mm galvanised bolts, washers and nuts on each side. See attached drawing : (505 - Roof panels to lattice beam detail.)

The roof is to consist of all required beams, supports, etc fixed to columns (elsewhere) for the overhang sections at the entrances and verandah areas of the building

The roof covering composite panel to consist of 0.6mm galvanised pre painted IBR chromadek external surface, 50mm expanded polystyrene core and 0.5mm chromadek plain white sheet soffit.

External and internal 1.2mm galvanised ridge plates to be placed on the surfaces where the roof panels join including fixing to the panel with 4.8 x 18mm sealed rivets fixed at 400mm centres on both sides and fixed to ridge beam with 4 x 8 x 125mm posidrive screws per a panel.

Roof covering to include all ridge flashing, 1.2mm apex splines, closure flashing, powder coated eave cappings, drip flashing and narrow and broad flute closures with polybuttons to be formed from 0.58mm Chromadek including rivets, bolts and drywall screws, etc. (See attached drawing 500- corner detail- horizontal section & 501 Roof/ Wall Assembly Vertical Section)

10 x 75 x 225mm Upvc Bargeboard drilled and fixed to composite panel at verges with 75mm hex posidriver screws at 600mm centres including galvanised steel H-profile jointing strips, etc.

85 x 125mm Powder coated seamless aluminium gutter fixed to proprietary fascia at maximum 600mm centres with and including proprietary fixings.

Four x 75 x 100mm x 2700mm long Powder coated seamless aluminium downpipes fixed to composite panels with and including proprietary holder bat and accessories.

**Carried to Collection**

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Internal walls to be constructed of 42mm Chromadeck composite laminated polyurethane core panel interlocking system with tongue and groove interlocking joints sealed with an approved silicon sealant including fixing panels mechanically to base rail as per manufactures specifications.

Internal walls to be finished both sides with 0.5mm pre-painted "Frost white" hot dipped galvanised steel rigidised Chromadek sheeting.

Bottom of internal walls to be fitted with a aluminium base channel with 4 x 9mm rivets at 300mm centres on both sides and fixed to the floor slab with 6 x 50mm masonry anchors at 500mm centres including non-shrink grout.( See attached drawing 502- Internal Wall Base Detail)

Top of internal walls to be fixed to the underside of the roof panel with natural anodised extruded aluminium side wallplate fixed to internal wall including pop rivets at 450mm centres and 5.2 x 90mm long roof screws at 1000mm centres through both panels.

All corner, edge and ridge capping, etc to be formed from 0.58mm Chromadek including rivets,sealant, etc.

**Carried to Collection**

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Floor finishes to following areas :

1.Classroom 1 (59.5m2): 300 x 300 x 2,5mm Semi-flexible reinforced vinyl floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

2.Classroom 2 (59.5m2): 300 x 300 x 2,5mm Semi-flexible reinforced vinyl floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

3.Classroom 3 (59.5m2): 300 x 300 x 2,5mm Semi-flexible reinforced vinyl floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

4.Classroom 4 (59.5m2): 300 x 300 x 2,5mm Semi-flexible reinforced vinyl floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

5.Classroom 5 (59.5m2): 300 x 300 x 2,5mm Semi-flexible reinforced vinyl floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

**Carried to Collection**

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

All units to be wired to connect to 220volt single phase (connection and supply elsewhere). The electrical installation to be in accordance with SABS 0142-1993 and each unit fitted with a wiring kit consisting of a distribution board, earth leakage , lights , switches, socket outlets and air conditioner isolators. All lights, plugs, geysers, interior and exterior electrical fittings to be insulated in accordance with SABS 0142-1993. Electrical compliance certificate to be issued with each unit.

One double tube fluorescent light per 7m2 floor area.

### **SHOP DETAILS**

The Contractor shall prepare his own shop details. Immediately on receipt of the Architect's drawings, the Contractor shall satisfy himself that the design drawings contain all the information required for the preparation of the shop details. The said shop details and other drawings shall be submitted in duplicate to the Architect for approval at least 1 week before commencement of fabrication. The Contractor's drawings shall be complete in every respect and shall be checked by the Contractor prior to submission. One copy of each drawing will be retained by the Architect and, within 1 week after the date of receipt by the Architect, the other copy will be returned to the Contractor with the Architect comments or written approval, as the case may be. Before the commencement of fabrication, the Contractor shall obtain from the Architect approval of the shop drawings, in writing. The approval given by the Architect relates to structural adequacy and does not absolve the Contractor from the responsibility for dimensional accuracy.

- 1 The Contractor is to allow hereunder for any costs incurred for the preparation and/or approval of shop drawings for the "5 Classroom block "prefabricated building for the contract.

Item

### **Prefabricated Units**

**Note: The contractor it to take note of all the items above when pricing the prefabricated structure.**

**The contractor will be liable for the completion of any item that is not supplied by the prefabrication sub contractor.**

**Carried to Collection**

R

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

|   |   |    |    |  |   |
|---|---|----|----|--|---|
| 1   | Supply, transport and erect of 5 Classroom block size 42740 x 8500mm consisting of the following :<br><br>1.Classroom 1 (59.5m2)<br>2.Classroom 2 (59.5m2)<br>3.Classroom 3 (59.5m2)<br>4.Classroom 4 (59.5m2)<br>5.Classroom 5 (59.5m2)<br>6.Enclosed Verandah (64.11m2)<br><br><b><u>JOINERY</u></b><br><br><u>Bench seats</u><br><br><u>Wrought hardwood</u> | No | 1  |  |   |
| 2   | 32 x 69mm Twice chamfered seating slat countersunk bolted to steel framing (elsewhere) with and including stainless steel round headed bolts and nuts.<br><br><u>Galvanised mild steel</u>  | m  | 36 |  |   |
| 3   | 40 x 40 x 3mm Square tubular, four times welded, bracket three times bolted to wall and floor with and including M10 x 100mm long masonry anchors. (Weight of each bracket = 4.60kg)<br><br><b><u>PROPRIETARY KITCHEN CUPBOARDS, LOCKERS, WRITING BOARDS, SEATS, ETC.</u></b><br><br><u>Lockers</u>   | No | 9  |  |   |
| 4   | Powder coated "Grey" steel standard two-door stationary cupboard, size 900mm wide x 450mm deep x 1800mm high, provided complete with four shelves, chromium plated locking mechanism, four times bolted to brickwork with and including 10 x 85mm long masonry anchors.<br><br><u>Writing boards</u>  | No | 5  |  |   |
| 5   | Educational board with deluxe aluminium perimeter frame, size overall 4000 x 1230mm high, with magnetic chalkboard centre panel fitted with aluminium chalkrail, mounted to wall with and including proprietary wall fixings.   | No | 5  |  |   |
| <b>Carried to Collection</b>  |   |    |    |  | R |
| Section No. 3<br>Bill No. 2<br>5 CLASSROOM BLOCK<br><b>QEBE JSS<br/>PROVISIONAL BILLS OF QUANTITIES</b> |   |    |    |  |   |

|   |   |    |     |  |
|---|---|----|-----|--|
| <u>Pinning boards</u>   |   |    |     |  |
| 1   | Standard wall mounted educational range pin board, size 2400 x 1200mm, with "(Colour - Grey" colour rib pinning surface, the board fixed to walls with proprietary mountings in strict accordance with the Manufacturer's instructions. | No | 10  |  |
| <u><b>SIGNAGE</b></u>   |   |    |     |  |
| <u>3mm Thick x 40mm high bevelled edge polished aluminium plate signs with 20mm high black engraved numerals or letters, countersunk tap screwed to timber door</u> |   |    |     |  |
| 2   | Sign with two numerals enscribed.   | No | 5   |  |
| <u>3mm Thick bevelled edge polished aluminium indicator plate signs with black engraved numerals or letters, countersunk tap screwed to wall.</u>                   |   |    |     |  |
| 3   | 150 x 150 x 3mm Black engraved bevelled edge aluminum fire extinguisher sign indicator plate fixed to wall.   | No | 3   |  |
| <u><b>SCREEDS</b></u>   |   |    |     |  |
| <u>3:1 Cement screeds :</u>   |   |    |     |  |
| 4   | 30mm Thick screed to floors and landings.   | m2 | 300 |  |
| <u><b>FIRE SERVICES</b></u>   |   |    |     |  |
| <u>Portable fire extinguishers:</u>   |   |    |     |  |
| 5   | 4.5 Kg carbondioxide portable fire extinguisher complete with full load, wall hook and bracket, bracket fixed to and including 25 mm wrot Meranti backboard, size 100 x 520mm high with chamfered edges, varnished and fixed to wall.   | No | 3   |  |
| <u>PAINT ON TIMBER</u>  |   |    |     |  |
| <u>Prepare and apply three coats interior quality clear polyurethane varnish on :</u>   |   |    |     |  |
| 6   | Surfaces of hardwood slatted shelving or bench seating.   | m2 | 7   |  |
| <b>Carried to Collection</b>  |   |    |     |  |
| Section No. 3   |   |    |     |  |
| Bill No. 2  |   |    |     |  |
| 5 CLASSROOM BLOCK   |   |    |     |  |
| <b>QEBE JSS</b>   |   |    |     |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>  |   |    |     |  |



Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

72

73

74

75

76

77

78

79

80

**Carried Forward to Summary of Section No. 3**

R

Section No. 3

Bill No. 2

5 CLASSROOM BLOCK

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Item No |   | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
|         | <p><b><u>BILL No.3</u></b></p> <p><b><u>COMBINED ADMIN AND NUTRITION CENTRE</u></b></p> <p><u>Note:</u></p> <p>For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).</p> <p><u>Construction Notes:</u></p> <p><b>All construction materials are to be SABS or AGREEMENT South Africa Certified'.</b></p> <p><b>Prefabricated systems are to be presented to the Principal Agent for approval before construction commences.</b></p> <p>Concrete platforms and ground beams to be constructed by the main contractor.</p> <p>Chassis construction must run the full length and full width of the unit and consist of structurally welded steel chassis with minimum of 2 x 200 x 75 x 20 x 3mm lip channel longitudinal main members running the length of the building at 1640mm centres, 75 x 50 x 20 x 2.5mm lipped channel cross members set at maximum of 600mm centres. Steps to be supplied where applicable. All structural steel is to be coated with one coat red oxide primer and two coats latex paint.</p> <p>The chassis is to fixed to the slab with 8mm x 75mm long masonry anchors at 500mm centers and including non-shrink grout</p> |          |      |        |
|         | <b>Carried to Collection</b>  |          | R    |        |
|         | <p>Section No. 3</p> <p>Bill No. 3</p> <p>COMBINED ADMIN &amp; NUTRITION CENTRE</p> <p><b>QEBE JSS</b></p> <p><b>PROVISIONAL BILLS OF QUANTITIES</b></p>  |          |      |        |

External walls to be constructed of 42mm Chromadeck composite laminated polyurethane core panel interlocking system with tongue and groove interlocking joints sealed with an approved silicon sealant including fixing panels mechanically to base rail as per manufactures specifications.

External walls to be finished both sides with 0.5mm pre-painted "Frost white" hot dipped galvanised steel rigidised Chromadek sheeting.

Top of external walls to be fixed to the underside of the roof panel with natural anodised extruded aluminium side wallplate fixed to external wall including pop rivets at 150mm centres and 90mm long roof screws at 450mm centres through both panels.

All corner, edge and ridge capping, etc to be formed from 0.58mm Chromadek including rivets, sealant, etc.

All windows to be powder coated aluminium including necessary ironmongery and burglar proofing to opening sections as per schedule.

Windows to be glazed with 6,38mm thick normal strength clear laminated safety glass including gaskets.

Ablution windows to be fitted with obscure or frosted glazing.

The perimeter of the frame to the adjacent surface to be sealed with an approved polysulphide sealant.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

External door frames to be natural anodized aluminium fitted with neoprene gaskets.

Single external doors to be 0.5mm 44mm Thick framed, ledged, braced and battened stable door, size 813 x 2032mm high, the top leaf comprising 44 x 108mm stiles, top and bottom rails, the bottom leaf comprising 44 x 108mm stiles and top rail and 22 x 215mm bottom rail, both leaves fitted with 22 x 75mm diagonal braces and 44 x 70mm splayed and rebated weatherboards countersunk brass screwed on at maximum 200mm centres and filled with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths,  
each door to be fitted with the following :

1. Three 100 x 44mm sinkless aluminium butt hinges
2. 2209 - 78SS" Euro profile upright cylinder lock case
3. 2 x 18 SC satin chrome double cylinder lock mechanism
4. Heavy duty satin chrome lever handle on 165 x 50 x 8mm cast backplate with cylinder lockset cutout.
5. Splayed and rebated weatherboard fixed to the bottom of the door
6. Stainless steel buffered door stop.

40mm Thick double external meranti glazed panel door, in two equal leaves with rebated meeting stiles, size overall 1612 x 2032mm high overall, each leaf comprising two unequal lights formed of 105mm wide vertical stiles, top rail, middle rail and double bottom rails framed together and including forming rebates for safety glass (elsewhere), both leaves fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres. 6.3mm mm thick clear laminated safety glass including gaskets each door to be fitted with the following ironmongery :

**Carried to Collection**

R

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

1. Six 100 x 44mm sinkless aluminium butt hinges
- 2."2209 - 78SS" Euro profile upright cylinder lock case
- 3." 2 x 18 SC" Satin chrome double cylinder lock mechanism
4. Heavy duty satin chrome lever handle on 165 x 50 x 8mm cast backplate with cylinder lockset cutout,
5. 2 x AL8052 - 200AS" 200 x 25mm anodised silver aluminium flush bolt with heel,
- 6." 8852SC" Satin chrome dust proof keep including forming mortice in screed.
- 7." 2900SS" Rebate conversion set for Euro profile lock.
8. "DC 477 FS EN size 2-4" CAM motion non hold open door closer.
9. 2 x Stainless steel buffered door stop.
10. Splayed and rebated weatherboard fixed to the bottom of the door

All doors to be finished with apply, one coat pre treatment one coat pink wood primer, one undercoat and two coats water based eggshell enamel.

All lock sets are to be master keyed.

External double gates size 1540 x 2000mm high in two equal leaves to be formed of 32 x 32 x 2.5mm wall thickness mild steel perimeter framing all round with mitred and welded angles, 8 x 20mm flat horizontal bars and the gate filled vertically with 10mm diameter mild steel bars welded to top and bottom rails at maximum 100mm centres, the leaf to receive hasp and staple formed of 40 x 6mm mild steel flat bar welded onto frames and including fitting each leaf with two 50 x 10mm flat bar tee brackets and 16mm round bar pin hinges, fixed to prefabricated walls.

All gates to be fitted with 51mm brass padlock with stainless steel shackle.

Gate to be finished with one coat steel etch primer, one coat universal undercoat and two coats gloss enamel paint.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Roof structure to be a minimum of 11 degree pitch with a overhang of 300mm all round.

The roof is to consist of all necessary lattice ridge beams fixed to gable walls with 4 x 10 x 60mm galvanised bolts, washers and nuts on each side.

The roof is to consist of all required beams, supports, etc fixed to columns (elsewhere) for the overhang sections at the entrances of the building.

The roof covering composite panel to consist of 0.6mm galvanised pre painted IBR chromadek external surface, 50mm expanded polystyrene core and 0.5mm chromadek plain white sheet soffit.

External and internal 1.2mm galvanised ridge plates to be placed on the surfaces where the roof panels join including fixing to the panel with 4.8 x 18mm sealed rivets fixed at 400mm centres on both sides and fixed to ridge beam with 4 x 8 x 125mm posidrive screws per a panel.

Roof covering to include all ridge flashing, 1.2mm apex splines, closure flashing, powder coated eave cappings, drip flashing and narrow and broad flute closures with polybuttons to be formed from 0.58mm Chromadek including rivets, bolts and drywall screws, etc.

10 x 75 x 225mm Upvc Bargeboard drilled and fixed to composite panel at verges with 75mm hex posidriver screws at 600mm centres including galvanised steel H-profile jointing strips, etc.

85 x 125mm Powder coated seamless aluminium gutter fixed to proprietary fascia at maximum 600mm centres with and including proprietary fixings.

Four x 75 x 100mm x 2700mm long Powder coated seamless aluminium downpipes fixed to composite panels with and including proprietary holderbat and accessories.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Internal walls to be constructed of 42mm Chromadeck composite laminated polyurethane core panel interlocking system with tongue and groove interlocking joints sealed with an approved silicon sealant including fixing panels mechanically to base rail as per manufactures specifications.

Internal walls to be finished both sides with 0.5mm pre-painted "Frost white" hot dipped galvanised steel rigidised Chromadek sheeting.

Kitchen area top be fitted with Grade 1 white glazed ceramic tiles size 200 x 200mm sealed to prefabricated panels with 3mm wide joints and grouted in white grout with fungicidal solution additive on walls in splashbacks

Bottom of internal walls to be fitted with a aluminium base channel with 4 x 9mm rivets at 300mm centres on both sides and fixed to the floor slab with 6 x 50mm masonry anchors at 500mm centres including non-shrink grout.

Top of internal walls to be fixed to the underside of the roof panel with natural anodised extruded aluminium side wallplate fixed to internal wall including pop rivets at 450mm centres and 5.2 x 90mm long roof screws at 1000mm centres through both panels.

All corner, edge and ridge capping, etc to be formed from 0.58mm Chromadek including rivets, sealant, etc.

Strong Room (04) walls to be fitted with 0.8mm galvanised steel sheeting fixed into the interior panels including section framing all round with mitred and welded angles and cross braces fixed to panels

Strong Room (04) ceiling to be fitted with hot dipped galvanised security mesh screen, formed of 50 x 50 x 5mm mild steel angle section framing all round with mitred and welded angles and cross braces, the screen covered with weaved screen ex steel mesh or similar approved fixed to the prefabricated walls.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Internal door frames to be natural anodized aluminium fitted with neoprene gaskets.

Single external doors to be 40mm Solid core flush door, size 936 x 2032mm high, with commercial grade veneer both sides and concealed edge strips, each door to be fitted with the following ironmongery :

1. Three 100 x 44mm sinkless aluminium butt hinges
  - 2." 2209 - 78SS" Euro profile upright cylinder lock case
  - 3." 2 x 18 SC" Satin chrome double cylinder lock mechanism
  4. Heavy duty satin chrome lever handle on 165 x 50 x 8mm cast backplate with cylinder lockset cutout
  5. Perspex signs with painted numerals or letters, countersunk tap screwed to doors
  6. Black rubber door stop plugged to wall or floor.
- All lock sets are to be master keyed.

All doors to be finished with apply, one coat pre treatment one coat pink wood primer, one undercoat and two coats water based eggshell enamel.

Floor finishes to following areas :

1. Foyer (19m2) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

2. Administration (16m2) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

3. Principal Office (12m2) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

4. Strong Room (6m2) : 30mm Granolithic screed

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R



(elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

5. Stock room (6m<sup>2</sup>) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

6. Sick Room (4m<sup>2</sup>) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

7. Kitchen (20m<sup>2</sup>) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

8. Store Room (6m<sup>2</sup>) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

9. Dining (24m<sup>2</sup>) : 300 x 300 x 2,5mm Semi-flexible reinforced vinyl quartz floor tiles (screed elsewhere) with 23 x 73mm varnished meranti half round skirting plugged to perimeter of wall with 4.8mm counter sunk pop rivets at 400mm centres including sealing top and bottom of skirting with an approved anti-fungicidal silicone sealant.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Internal plumbing fittings :

1. Sickbay & Kitchen : Hand basin installation

White glazed vitreous china Rectangular washhand basin, size 550 x 400mm, with two tapholes, one taphole stopper, integrated overflow and chainstay hole, mounted to wall on and including two proprietary semi concealed cast iron wall brackets with 10mm bolts including

32mm Chromium plated brass slotted basin waste outlet with plug, chain and chain stay.

40mm Chromium plated brass basin bottle trap.

Two 15mm Chromium plated pillar tap with "Star" handle including flexi hoses and ball stop valves.

2. Kitchen : Sink

Grade 316 stainless steel Inset type sink and drainer unit, size 1200 x 500mm wide overall, with two bowls situated at one end and fitted into opening in worktop (elsewhere) including two 38mm Chromium plated brass slotted sink waste outlet with plug, chain and chain stay and 38mm PVC Sink double trap.

15mm Chromium plated one hole sink mixer with aerated swanneck swivel outlet and flexible connection hoses. and ball-o-stop valves.

3. Geyser Installation :

150 Litre high pressure horizontal water heater mounted in roof space including all vacuum breakers, pressure reducing valves, drainage valves, drip trays and pipework required.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

Internal soil drainage reticulation to be uPVC pipes and fittings with solvent welded straight joints taken to outer wall of building.

Internal water reticulation to be Class 2 copper piping including all capillary fittings with soldered joints and completion fittings taken to the other wall of the building.

All exposed hot water piping and fittings to be fitted with preformed polyethylene foam lagging or similar approved insulation wrapped lagging.

All units to be wired to connect to 220volt single phase (connection and supply elsewhere). The electrical installation to be in accordance with SABS 0142-1993 and each unit fitted with a wiring kit consisting of a distribution board, earth leakage , lights , switches, socket outlets and isolators. All lights, plugs, power skirting, geysers, interior and exterior electrical fittings to be insulated in accordance with SABS 0142-1993. Electrical compliance certificate to be issued with each unit.

#### **SHOP DETAILS**

The Contractor shall prepare his own shop details. Immediately on receipt of the Architect's drawings, the Contractor shall satisfy himself that the design drawings contain all the information required for the preparation of the shop details. The said shop details and other drawings shall be submitted in duplicate to the Architect for approval at least 1 week before commencement of fabrication. The Contractor's drawings shall be complete in every respect and shall be checked by the Contractor prior to submission. One copy of each drawing will be retained by the Architect and, within 1 week after the date of receipt by the Architect, the other copy will be returned to the Contractor with the Architect comments or written approval, as the case may be. Before the commencement of fabrication, the Contractor shall obtain from the Architect approval of the shop drawings, in writing. The approval given by the Architect relates to structural adequacy and does not absolve the Contractor from the responsibility for dimensional accuracy.

**Carried to Collection**

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

R

|   |   |    |      |  |   |
|---|---|----|------|--|---|
| 1   | <p>The Contractor is to allow hereunder for any costs incurred for the preparation and/or approval of shop drawings for the "Combined Administration and Nutrition Centre "prefabricated building for the contract.</p> <p><u>Prefabricated Units</u></p> <p><b>Note: The contractor it to take note of all the items above when pricing the prefabricated structure.</b></p> <p><b>The contractor will be liable for the completion of any item that is not supplied by the prefabrication sub contractor.</b></p> |    | Item |  |   |
| 2   | <p>Supply, transport and erect of administration, dining &amp; nutrition centre combination size 19019 x 9000mm consisting of the following :</p> <p>1. Foyer (19m2)<br/> 2. Administration (16m2)<br/> 3. Principal Office (12m2)<br/> 4. Strong Room (6m2)<br/> 5. Stock room (6m2)<br/> 6. Sick Room (4m2)<br/> 7. Kitchen (20m2)<br/> 8. Store Room (6m2)<br/> 9. Dining (24m2)<br/> 10. Entrance 01 (5m2)<br/> 11. Entrance 02 (5m2)</p> <p><b><u>JOINERY</u></b></p> <p><u>Shelving</u></p>                   | No | 1    |  |   |
| 3   | <p>20mm Thick chipboard, faced both sides in hardwood veneer (Colour white) with and including 10mm thick hardwood edge strips to all exposed edges in sides, divisions and shelves.</p> <p><u>Key boards, cabinets, etc.</u></p>   | m2 | 25   |  |   |
| 4   | <p>Powder coated (White) epoxy steel standard medicine cabinet, size 380mm wide x 610mm high, provided complete with mirror to door, shelves, etc. including building into brickwork.</p>   | No | 1    |  |   |
| Carried to Collection   |   |    |      |  | R |
| Section No. 3<br>Bill No. 3<br>COMBINED ADMIN & NUTRITION CENTRE<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |   |    |      |  |   |

|  |  |    |    |  |   |
|--|--|----|----|--|---|
| 1                                      | Powder coated epoxy steel key cabinet (60 key) provided complete with identification label above each key hook and mechanical combination lock plugged to brickwork.   | No | 1  |  |   |
|  | <u>Window openers</u>  |    |    |  |   |
| 2                                      | 32mm Diameter polished hardwood longarm 1 200mm long fitted with polished brass pole hook, secured in one chromium plated spring clip screwed to and including small polished hardwood block plugged to wall and fitted on hardwood base size 88 x 88mm countersunk for rod plugged to floor, including quadrant planted on. | No | 3  |  |   |
|  | <u>Fittings</u>  |    |    |  |   |
| 3                                      | Reception counter, 3000mm long overall x 600mm wide, including top, doors, drawers, galvanised angle iron fixing brackets and "Gelmar" support posts all as per drawing no. 505E, Plan, Sections and Elevation.  | No | 1  |  |   |
| 4                                      | Kitchen floor cupboard unit, 2959mm long x 622mm wide, including doors, divisions, shelves, forming holes in top for sanitary fittings, etc. all as per drawing no: 506A Plan, Sections and Elevations.  | No | 1  |  |   |
| 5                                      | L-Shape kitchen floor cupboard unit, 4162mm long x 622mm wide, including doors, divisions, shelves, etc. all as per drawing no: 506A Plan, Sections and Elevations.  | No | 1  |  |   |
|  | <u>Bench seats</u>   |    |    |  |   |
|  | <u>Wrought hardwood</u>  |    |    |  |   |
| 6                                      | 32 x 69mm Twice chamfered seating slat countersunk bolted to steel framing (elsewhere) with and including stainless steel round headed bolts and nuts.   | m  | 11 |  |   |
|  | <u>Galvanised mild steel</u>   |    |    |  |   |
| 7                                      | 40 x 40 x 3mm Square tubular, four times welded, bracket three times bolted to wall and floor with and including M10 x 100mm long masonry anchors. (Weight of each bracket = 4.60kg)   | No | 3  |  |   |
| <b>Carried to Collection</b>           |  |    |    |  | R |
| Section No. 3                          |  |    |    |  |   |
| Bill No. 3                             |  |    |    |  |   |
| COMBINED ADMIN & NUTRITION CENTRE      |  |    |    |  |   |
| <b>QEBE JSS</b>                        |  |    |    |  |   |
| <b>PROVISIONAL BILLS OF QUANTITIES</b> |  |    |    |  |   |

**STEELWORK**

All steelwork is to be hot dipped galvanised after fabrication.

**Columns, beams and other members**

Welded roller shutter door support framing in single lengths with flat section base, columns, beams top, bearer and connection plates, bolted to concrete

|   |   |    |     |
|---|---|----|-----|
| 1 | 75 x 75 x 4mm x 8.98kg/m Square hollow section in roller shutter door framing including bolts,nuts and washers. | kg | 113 |
| 2 | Flat plate bearer or base plates holed for bolts and/or welded.   | kg | 25  |

**Bolts to columns, beams etc.**

|   |  |    |    |
|---|--|----|----|
| 3 | 16 x 100mm masonry anchors fixed to floor including non-shrink grout . | No | 16 |
|---|--|----|----|

**METAL SHELVING**

Approved standard epoxy powder coated finish "Colour - Light Cream" wall bands, shelving, brackets, etc.

|   |   |    |     |
|---|---|----|-----|
| 4 | 1830mm Long double slot wall band six times plugged to wall with and including 8 x 80mm long masonry anchors. | No | 34  |
| 5 | 300mm Wide shelf bracket slotted into wall band. (elsewhere)  | No | 170 |
| 6 | 500mm Wide shelf bracket slotted into wall band. (elsewhere)  | No | 34  |

**Carried to Collection**

R

Section No. 3

Bill No. 3

COMBINED ADMIN & NUTRITION CENTRE

**QEBE JSS**

**PROVISIONAL BILLS OF QUANTITIES**

**PROPRIETARY KITCHEN CUPBOARDS, LOCKERS,  
WRITING BOARDS, SEATS, ETC.**Pinning boards

|   |  |    |   |
|---|--|----|---|
| 1 | Standard wall mounted educational range pin board, size 2000 x 1200mm with "(Colour - Grey" colour rib pinning surface, the board fixed to walls with proprietary mountings in strict accordance with the Manufacturer's instructions. | No | 2 |
|---|--|----|---|

**SCREEDS**3:1 Cement screeds :

|   |   |    |     |
|---|---|----|-----|
| 2 | 30mm Thick screed to floors and landings. | m2 | 135 |
|---|---|----|-----|

**SIGNAGE**

3mm Thick x 60mm high bevelled edge polished aluminium plate signs with 40mm high black engraved numerals or letters, countersunk tap screwed to timber door

|    |  |    |   |
|----|--|----|---|
| 3  | Sign with "STAFF ROOM" en scribed.     | No | 1 |
| 4  | Sign with "RECEPTION" en scribed.      | No | 1 |
| 5  | Sign with "STRONG ROOM" en scribed.    | No | 1 |
| 6  | Sign with "PRINCIPAL" en scribed.      | No | 1 |
| 7  | Sign with "SICKROOM" en scribed.       | No | 1 |
| 8  | Sign with "ADMINISTRATION" en scribed. | No | 1 |
| 9  | Sign with "DINING ROOM" en scribed.    | No | 2 |
| 10 | Sign with "KITCHEN" en scribed.        | No | 1 |
| 11 | Sign with "STORE" en scribed.          | No | 1 |

**Carried to Collection**

R

Section No. 3

Bill No. 3

COMBINED ADMIN &amp; NUTRITION CENTRE

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

|  |    |   |   |
|--|----|---|---|
| <u>3mm Thick x 220mm high bevelled edge polished aluminium plate signs with 200mm high black engraved numerals or letters, countersunk tap screwed to timber door</u><br><br>Sign with "NUTRITION CENTRE" en scribed.  | No | 1 |   |
| <u>3mm Thick bevelled edge polished aluminium indicator plate signs with black engraved numerals or letters, countersunk tap screwed to wall.</u><br><br>150 x 150 x 3mm Black engraved bevelled edge aluminum "No Smoking Pictogram" indicator plate fixed to wall. | No | 1 |   |
| 150 x 150 x 3mm Black engraved bevelled edge aluminum fire extinguisher sign indicator plate fixed to wall.  | No | 1 |   |
| <p style="text-align: right;"><b>Carried to Collection</b></p>   |    |   | R |
| Section No. 3<br>Bill No. 3<br>COMBINED ADMIN & NUTRITION CENTRE<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b>  |    |   |   |



**METALWORK**Epoxy powder coated finish roller shutter doors with hood fixed to steel beam

- |   |   |    |   |
|---|---|----|---|
| 1 | Chain operated slatted roller shutter door to suit clear opening size 914mm wide x 1270mm high fitted with proprietary guides, hood, aluminium bottom rail with rubber gasket, etc. and 2 No. sliding lock bolts including 50mm padlock with stainless steel shackle. | No | 1 |
| 2 | Chain operated slatted roller shutter door to suit clear opening size 1800mm wide x 900mm high fitted with proprietary guides, hood, aluminium bottom rail with rubber gasket, etc. and 2 No. sliding lock bolts including 50mm padlock with stainless steel shackle. | No | 1 |

**FIRE SERVICES**Portable fire extinguishers:

- |   |   |    |   |
|---|---|----|---|
| 3 | 4.5 Kg carbondioxide portable fire extinguisher complete with full load, wall hook and bracket, bracket fixed to and including 25 mm wrot Meranti backboard, size 100 x 520mm high with chamfered edges, varnished and fixed to wall. | No | 2 |
|---|---|----|---|

**PAINTWORK**PAINT ON TIMBERPrepare and apply three coats interior quality clear polyurethane varnish on :

- |   |   |    |   |
|---|---|----|---|
| 4 | Surfaces of hardwood slatted shelving or bench seating. | m2 | 2 |
|---|---|----|---|

**MECHANICAL INSTALLATION**

- |   |  |      |           |
|---|--|------|-----------|
| 5 | Provide the Provisional Sum of R 10 000.00 (Ten Thousand Rand) for the supply, delivery and installation of fridge freezer combination unit. | Item | 10,000.00 |
| 6 | Add for profit on the above, if desired.   | Item |           |
| 7 | Allow for attendance upon the specialist installation subcontractor.   | Item |           |

**Carried to Collection****R**

Section No. 3

Bill No. 3

COMBINED ADMIN &amp; NUTRITION CENTRE

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

GAS INSTALLATION

|   |   |      |           |
|---|---|------|-----------|
| 1 | Provide the Provisional Sum of R 50 000.00 (Fifty Thousand Rand) for the supply, delivery and installation of gas piping reticulation complete including pipework, gas burner stoves, valves, bottles, cages, etc. to be undertaken by a specialist firm. | Item | 50,000.00 |
| 2 | Add for profit on the above, if desired.  | Item |           |
| 3 | Allow for attendance upon the specialist installation subcontractor.  | Item |           |

**Carried to Collection**

R

Section No. 3

Bill No. 3

COMBINED ADMIN &amp; NUTRITION CENTRE

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Section No. 3

Bill No. 3

COMBINED ADMIN &amp; NUTRITION CENTRE

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

**Carried Forward to Summary of Section No. 3**

R

Section No. 3

Bill No. 3

COMBINED ADMIN &amp; NUTRITION CENTRE

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Bill No  | SECTION SUMMARY - SECTION NO.3 - PREFABRICATED STRUCTURES | Page No | Amount |
|--|---|---------|--------|
| 1  | PLATFORM CONSTRUCTION                                     | 71      |        |
| 2  | 5 CLASSROOM BLOCK   | 81      |        |
| 3  | COMBINED ADMIN & NUTRITION CENTRE                         | 99      |        |
| Carried to Final Summary   |   |         | R      |
| Section No. 3<br><b>QEBE JSS</b><br><b>PROVISIONAL BILLS OF QUANTITIES</b> |   |         |        |



|  |  |    |     |  |   |
|--|--|----|-----|--|---|
| 1                                      | Demolish and cart away single storey classroom block, size on plan 11500mm long x 7100mm wide x approximately 3000mm high, comprised of sheet metal and fibre-cement roof covering on double pitch timber rafters, plastered and painted brick internal and external walls with timber doors, ground floor concrete surface bed with granolithic floor covering, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site. | No | 1   |  |   |
| 2                                      | Demolish and cart away single storey classroom block, size on plan 15000mm long x 7000mm wide x approximately 3000mm high, comprised of sheet metal and fibre-cement roof covering on double pitch timber rafters, plastered and painted brick internal and external walls with timber doors, ground floor concrete surface bed with granolithic floor covering, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site. | No | 1   |  |   |
| 3                                      | Demolish and cart away mud structure rondavel complete, size 50m2 on plan x 3m high, including concrete surface bed, walls, and roof structure.  | No | 1   |  |   |
|  | <u>Tank stands</u>   |    |     |  |   |
| 4                                      | Demolish and cart away 5000 litre water storage tank including brick tank stand, comprised of plastered and painted brick walls and reinforced concrete slab including grubbing up foundations and backfilling holes with material from the stockpiles on site.  | No | 2   |  |   |
|  | <u>Fencing</u>   |    |     |  |   |
| 5                                      | Take down and cart away stock fencing, 1800mm high, including excavating out timber intermediate, corner or straining posts, at approximately 3000mm centres, backfilling of holes, etc.   | m  | 400 |  |   |
|  | <u>Site clearance</u>  |    |     |  |   |
| 6                                      | Clear the areas to be developed of all rubbish, debris, vegetation, shrubs, bush and small trees not exceeding 200mm girth and remove from site.   | m2 | 518 |  |   |
| 7                                      | Strip topsoil, average 150mm thick, including depositing in stockpiles on site for later re-use.   | m2 | 518 |  |   |
| <b>Carried to Collection</b>           |  |    |     |  | R |
| Section No. 4                          |  |    |     |  |   |
| Bill No. 1                             |  |    |     |  |   |
| BULK EARTHWORKS                        |  |    |     |  |   |
| <b>QEBE JSS</b>                        |  |    |     |  |   |
| <b>PROVISIONAL BILLS OF QUANTITIES</b> |  |    |     |  |   |

**EXCAVATIONS, FILLING, ETC.****OPEN FACE EXCAVATIONS**

- |   |   |    |     |
|---|---|----|-----|
| 1 | Open face excavation in earth in cutting and levelling of site. | m3 | 155 |
|---|---|----|-----|

**Excavations in earth of more difficult character**

- |   |  |    |    |
|---|--|----|----|
| 2 | Extra over excavations in earth for excavation in soft rock. | m3 | 16 |
|---|--|----|----|

**Carting away of excavated material**

- |   |   |    |     |
|---|---|----|-----|
| 3 | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. | m3 | 155 |
|---|---|----|-----|

**Filling**

- |   |   |    |    |
|---|---|----|----|
| 4 | G5 Material, selected and supplied by the contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 93% modified AASHTO density over site. | m3 | 78 |
|---|---|----|----|

**Compaction of surfaces**

- |   |   |    |     |
|---|---|----|-----|
| 5 | Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density. | m2 | 518 |
|---|---|----|-----|

**Tests**

- |   |  |    |      |
|---|--|----|------|
| 6 | Allow for Mod AASHTO density tests on filling. | No | 4.00 |
|---|--|----|------|

**Carried to Collection****R**

Section No. 4

Bill No. 1

BULK EARTHWORKS

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Section No. 4

Bill No. 1

BULK EARTHWORKS

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

101

102

103

**Carried Forward to Summary of Section No. 4**

R

Section No. 4

Bill No. 1

BULK EARTHWORKS

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**



[illegible]

**Soakage pits, french drains, etc. (Labour intensive)****Excavations**

Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away

|   |                   |    |   |
|---|-------------------|----|---|
| 1 | Surface trenches. | m3 | 9 |
|---|-------------------|----|---|

**Excavations in earth of more difficult character**

|   |  |    |   |
|---|--|----|---|
| 2 | Extra over excavations in earth for excavation in soft rock. | m3 | 1 |
|---|--|----|---|

|   |  |    |   |
|---|--|----|---|
| 3 | Extra over excavations in earth for excavation in hard rock. | m3 | 1 |
|---|--|----|---|

**Carting away of excavated material**

|   |   |    |   |
|---|---|----|---|
| 4 | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. | m3 | 6 |
|---|---|----|---|

**Risk of collapse of excavations**

|   |   |    |    |
|---|---|----|----|
| 5 | Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. | m2 | 21 |
|---|---|----|----|

**Keeping excavations free of water**

|   |  |      |  |
|---|--|------|--|
| 6 | Allow for keeping the excavations free from water. | Item |  |
|---|--|------|--|

**Filling**

|   |   |    |   |
|---|---|----|---|
| 7 | Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density. | m3 | 3 |
|---|---|----|---|

|   |  |    |   |
|---|--|----|---|
| 8 | 19mm Uniformly graded and washed concrete stone laid loose on filter fabric (elsewhere). | m3 | 6 |
|---|--|----|---|

**Filter fabric**

|   |   |    |    |
|---|---|----|----|
| 9 | Grade 3 needle punched non-woven synthetic fibre filter fabric laid in bottom of chamber. | m2 | 33 |
|---|---|----|----|

**Carried to Collection****R**

Section No. 4

Bill No. 2

SOIL DRAINAGE (PROVISIONAL)

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

|   |   |    |      |
|---|---|----|------|
| <b><u>Pipes, pipe fittings, etc.</u></b>  |   |    |      |
| <u>UTL420 PVC Perforated slotted heavy duty pipe</u>  |   |    |      |
| 1   | 110mm Diameter pipe laid in trench (elsewhere).   | m  | 6    |
| <b><u>THE FOLLOWING IN SEPTIC TANKS (Labour intensive)</u></b>  |   |    |      |
| <b><u>Excavations</u></b>   |   |    |      |
| <u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u> |   |    |      |
| 2   | Holes.  | m3 | 23   |
| <u>Excavations in earth of more difficult character</u>   |   |    |      |
| 3   | Extra over excavations in earth for excavation in soft rock.  | m3 | 2    |
| 4   | Extra over excavations in earth for excavation in hard rock.  | m3 | 1    |
| <b><u>Carting away of excavated material</u></b>  |   |    |      |
| 5   | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.   | m3 | 16   |
| <b><u>Risk of collapse of excavations</u></b>   |   |    |      |
| 6   | Allow for risk of collapse to sides of excavations exceeding 1.5m deep including all necessary timber shoring, etc.   | m2 | 30   |
| <b><u>Keeping excavations free of water</u></b>   |   |    |      |
| 7   | Allow for keeping the excavations free from water.  |    | Item |
| <b><u>Filling</u></b>   |   |    |      |
| 8   | Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc. | m3 | 2    |
| <b>Carried to Collection</b>  |   |    | R    |
| Section No. 4   |   |    |      |
| Bill No. 2  |   |    |      |
| SOIL DRAINAGE (PROVISIONAL)   |   |    |      |
| <b>QEBE JSS</b>   |   |    |      |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>  |   |    |      |

|                                 |   |    |    |  |   |
|---------------------------------|---|----|----|--|---|
|                                 | <u>Weedkillers, insecticides, etc.</u>  |    |    |  |   |
|                                 | <u>Soil insecticide in accordance with SANS 5859</u>  |    |    |  |   |
| 1                               | To bottoms and sides of trenches.   | m2 | 24 |  |   |
|                                 | <b><u>CONCRETE (Labour intensive)</u></b>   |    |    |  |   |
|                                 | <u>Reinforced concrete 30MPa (19mm stone) in:</u>   |    |    |  |   |
| 2                               | Slabs including beams and inverted beams.   | m3 | 3  |  |   |
|                                 | <u>Surface treatment</u>  |    |    |  |   |
| 3                               | Float surface of concrete to a wood float finish.   | m2 | 10 |  |   |
|                                 | <u>Test blocks and testing</u>  |    |    |  |   |
| 4                               | Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional) | No | 1  |  |   |
|                                 | <b><u>FORMWORK (Labour intensive)</u></b>   |    |    |  |   |
|                                 | <u>Rough formwork (use and waste) to concrete to:</u>   |    |    |  |   |
|                                 | <u>Formwork to slabs, beams and stairs</u>  |    |    |  |   |
| 5                               | Soffits of slabs exceeding 1.5 not exceeding 3.5m above bearing level.  | m2 | 9  |  |   |
|                                 | <u>Edges, risers, ends and reveals</u>  |    |    |  |   |
| 6                               | Edge, riser, etc not exceeding 300mm high.  | m  | 8  |  |   |
| Carried to Collection           |   |    |    |  | R |
| Section No. 4                   |   |    |    |  |   |
| Bill No. 2                      |   |    |    |  |   |
| SOIL DRAINAGE (PROVISIONAL)     |   |    |    |  |   |
| QEBE JSS                        |   |    |    |  |   |
| PROVISIONAL BILLS OF QUANTITIES |   |    |    |  |   |

**REINFORCEMENT (PROVISIONAL)**High tensile welded steel mesh reinforcement :

|   |                                       |    |    |
|---|---------------------------------------|----|----|
| 1 | Ref: 395 cast into concrete surfaces. | m2 | 19 |
|---|---------------------------------------|----|----|

**Inspection chambers, catch pits, etc.**Cast iron covers and frames

|   |   |    |   |
|---|---|----|---|
| 2 | 450 x 600mm x 72kg Type 8A coated cast iron double seal manhole cover and frame, including bedding and grouting frame on concrete, locking bar and padlock. | No | 1 |
|---|---|----|---|

Black PVC duct pipe in single lengths :

|   |                           |   |   |
|---|---------------------------|---|---|
| 3 | 150mm Diameter vent pipe. | m | 1 |
|---|---------------------------|---|---|

Extra over PVC duct pipe for fittings :

|   |                   |    |   |
|---|-------------------|----|---|
| 4 | 150mm Plain bend. | No | 1 |
|---|-------------------|----|---|

Septic tanks:

|   |   |    |   |
|---|---|----|---|
| 5 | 6000 Litre polyethylene rotomoulded horizontal septic waste storage tank provided complete with lid, overflow outlet fitted with suitable adaptor, inlet fitted with suitable adapter and setting in position underground (elsewhere measured). | No | 1 |
|---|---|----|---|

|   |   |    |   |
|---|---|----|---|
| 6 | Hole through top of tank lid for 150mm diameter pipe. | No | 1 |
|---|---|----|---|

**Testing**

|   |   |  |      |
|---|---|--|------|
| 7 | Allow for testing the soil drainage and sewer plumbing installation in accordance with the National Building Regulations. |  | Item |
|---|---|--|------|

**Carried to Collection****R**

Section No. 4

Bill No. 2

SOIL DRAINAGE (PROVISIONAL)

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

Section No. 4

Bill No. 2

SOIL DRAINAGE (PROVISIONAL)

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

105

106

107

108

109

**Carried Forward to Summary of Section No. 4**

R

Section No. 4

Bill No. 2

SOIL DRAINAGE (PROVISIONAL)

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Item No  | Quantity   | Rate | Amount |
|--|--|------|--------|
| <b>BILL No. 3</b>  |  |      |        |
| <b><u>STORMWATER DRAINAGE (PROVISIONAL)</u></b>  |  |      |        |
| <u>Note:</u>   |  |      |        |
| For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). |  |      |        |
| <b><u>RAINWATER TANKS AND TANKSTANDS (ALL TRADES)</u></b>  |  |      |        |
| <u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>                |  |      |        |
| 1  | Surface trenches.  | m3   | 60     |
| 2  | Reduced levels under solid floors.   | m3   | 4      |
| <u>Carting away of excavated material</u>  |  |      |        |
| 3  | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.                                      | m3   | 30     |
| <u>Risk of collapse of excavations</u>   |  |      |        |
| 4  | Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.                                    | m2   | 176    |
| <u>Keeping excavations free of water</u>   |  |      |        |
| 5  | Allow for keeping the excavations free from water.   | Item |        |
| <u>Filling, layerworks, etc.</u>   |  |      |        |
| 6  | Earth filling from the excavations and/or stockpiles in backfilling to trenches, underfloors, column bases, etc., compacted to 95% Mod AASHTO dry density. | m3   | 50     |
| <b>Carried to Collection</b>   |  |      | R      |
| Section No. 4  |  |      |        |
| Bill No. 3   |  |      |        |
| STORMWATER DRAINAGE  |  |      |        |
| <b>QEBE JSS</b>  |  |      |        |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>   |  |      |        |

|  |   |    |      |   |  |
|--|---|----|------|---|--|
| 1                                      | Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc. | m3 | 10   |   |  |
|  | <u>Compaction of surfaces</u>   |    |      |   |  |
| 2                                      | Scarify in-situ material to a depth of 150mm and compact to 95% Mod AASHTO density.   | m2 | 30   |   |  |
|  | <u>Tests</u>  |    |      |   |  |
| 3                                      | Allow for Mod AASHTO density tests on filling.  | No | 5.00 |   |  |
|  | <u>Reinforced concrete 25MPa in:</u>  |    |      |   |  |
| 4                                      | Strip foundations cast against excavated surfaces.  | m3 | 4    |   |  |
| 5                                      | Surface beds cast in panels including temporary formwork.   | m3 | 5    |   |  |
|  | <u>Sundries</u>   |    |      |   |  |
| 6                                      | Float surface of concrete to a wood float finish.   | m2 | 50   |   |  |
|  | <u>Rough formwork (use and waste) to concrete to:</u>   |    |      |   |  |
| 7                                      | Edge, riser, etc not exceeding 300mm high.  | m  | 90   |   |  |
|  | <u>High tensile welded steel mesh reinforcement :</u>   |    |      |   |  |
| 8                                      | Ref: 193 cast into concrete surfaces.   | m2 | 50   |   |  |
|  | <u>Brickwork in stock bricks in 5:1 cement mortar :</u>   |    |      |   |  |
| 9                                      | One brick wall.   | m2 | 40   |   |  |
| 10                                     | One brick wall in foundations. (Provisional)  | m2 | 60   |   |  |
|  | <u>Brickwork sundries :</u>   |    |      |   |  |
| 11                                     | Galvanised brick reinforcement 150mm wide built horizontally into brickwork.  | m  | 300  |   |  |
| <b>Carried to Collection</b>           |   |    |      | R |  |
| Section No. 4                          |   |    |      |   |  |
| Bill No. 3                             |   |    |      |   |  |
| STORMWATER DRAINAGE                    |   |    |      |   |  |
| <b>QEBE JSS</b>                        |   |    |      |   |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b> |   |    |      |   |  |



|                                 |  |    |    |  |   |
|---------------------------------|--|----|----|--|---|
|                                 | <u>Ties, cramps, etc.</u>  |    |    |  |   |
| 1                               | 38 x 1,6mm Galvanised hoop iron strap around tank, both ends fitted with once holed 30 x 30 x 3mm thick galvanised flat plate and bolted together with and including M8 bolt and nut.  | No | 10 |  |   |
| 2                               | 38 x 1,6mm Galvanised hoop iron tie down, 1200mm long, one end wrapped around tank strap and twice bolted, the other end folded over and bolted to top of concrete with and including 8 x 60mm masonry anchor.   | No | 40 |  |   |
|                                 | <u>250 Micron "Gunplas USB" green polyethylene sheeting</u>  |    |    |  |   |
|                                 | :  |    |    |  |   |
| 3                               | Laid flat under solid floor and over walls.  | m2 | 50 |  |   |
|                                 | <u>One coat external 1:5 cement plaster on :</u>   |    |    |  |   |
| 4                               | Brick wall.  | m2 | 90 |  |   |
|                                 | <u>Rainwater tanks:</u>  |    |    |  |   |
| 5                               | 5000 Litre polyethylene rotomoulded vertical water storage tank provided complete with lid, overflow outlet and "ASIDI" emblem, fitted with suitable adaptor and setting in position on concrete tankstand (elsewhere measured). (The tanks are to be filled with water for the Practical Completion inspection) | No | 10 |  |   |
| 6                               | Hole through top of tank lid for 100mm diameter pipe.  | No | 10 |  |   |
|                                 | <u>Prepare and apply one coat plaster primer and two coats quality matt acrylic PVA on :</u>   |    |    |  |   |
| 7                               | External smooth plastered walls.   | m2 | 90 |  |   |
| Carried to Collection           |  |    |    |  | R |
| Section No. 4                   |  |    |    |  |   |
| Bill No. 3                      |  |    |    |  |   |
| STORMWATER DRAINAGE             |  |    |    |  |   |
| QEBE JSS                        |  |    |    |  |   |
| PROVISIONAL BILLS OF QUANTITIES |  |    |    |  |   |

Section No. 4

Bill No. 3

STORMWATER DRAINAGE

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

111

112

113

**Carried Forward to Summary of Section No. 4**

R

Section No. 4

Bill No. 3

STORMWATER DRAINAGE

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

[illegible]

|                                 |  |    |      |  |   |
|---------------------------------|--|----|------|--|---|
|                                 | <u>Excavations in earth of more difficult character</u>  |    |      |  |   |
| 1                               | Extra over excavations in earth for excavation in soft rock.   | m3 | 5    |  |   |
| 2                               | Extra over excavations in earth for excavation in hard rock.   | m3 | 3    |  |   |
|                                 | <u>Sundries</u>  |    |      |  |   |
| 3                               | Extra over all excavations for pipe trenches for carting away from the site all surplus material from the excavations (measured net - no allowance for bulking).         | m3 | 8    |  |   |
| 4                               | Imported Sabunga filling as backfill to pipe trenches and compact to 93% modified AASHTO.  | m3 | 8    |  |   |
|                                 | <u>Water supply valve or meter chambers</u>  |    |      |  |   |
| 5                               | Excavate for and build meter chamber size 380 x 670 x 305mm deep overall formed of precast concrete heavy duty meter box (ELM) and lid including filling in and ramming. | No | 4    |  |   |
|                                 | <u>Connections</u>   |    |      |  |   |
|                                 | <u>Connection of new to existing pipes</u>   |    |      |  |   |
| 6                               | Connection of 25mm diameter HDPE to 22mm diameter copper pipes including all necessary reducers, saddles, etc.   | No | 4    |  |   |
|                                 | <u>Taps, valves, etc.</u>  |    |      |  |   |
| 7                               | 40mm Brass gate valve.   | No | 4    |  |   |
|                                 | <u>Testing</u>   |    |      |  |   |
| 8                               | Allow for testing the water supply installation in accordance with the National Building Regulations.  |    | Item |  |   |
| Carried to Collection           |  |    |      |  | R |
| Section No. 4                   |  |    |      |  |   |
| Bill No. 4                      |  |    |      |  |   |
| WATER SUPPLIES                  |  |    |      |  |   |
| QEBE JSS                        |  |    |      |  |   |
| PROVISIONAL BILLS OF QUANTITIES |  |    |      |  |   |

Section No. 4

Bill No. 4

WATER SUPPLIES

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

115

116

**Carried Forward to Summary of Section No. 4**

R

Section No. 4

Bill No. 4

WATER SUPPLIES

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**



|  |   |    |     |   |  |
|--|---|----|-----|---|--|
|  | <u>Sundries</u>   |    |     |   |  |
| 1                                      | Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density.   | m2 | 227 |   |  |
|  | <u>Prescribed Testing</u>   |    |     |   |  |
| 2                                      | Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.                     | No | 5   |   |  |
|  | <u>CONCRETE (Labour intensive)</u>  |    |     |   |  |
|  | <u>Reinforced concrete 25MPa (19mm stone) in:</u>   |    |     |   |  |
| 3                                      | Paving in panels including any necessary formwork.  | m3 | 26  |   |  |
|  | <u>Surface treatment</u>  |    |     |   |  |
| 4                                      | Float surface of concrete to a smooth steel trowelled finish.   | m2 | 227 |   |  |
|  | <u>Test blocks and testing</u>  |    |     |   |  |
| 5                                      | Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional) | No | 5   |   |  |
|  | <u>Movement joints</u>  |    |     |   |  |
| 6                                      | 10mm Thick "Jointex" closed cell polyethylene joint filler with hinged blocking piece between concrete surfaces not exceeding 300mm wide.   | m  | 206 |   |  |
| 7                                      | Remove hinged blocking piece and fill 10 x 15mm cavity with an approved 2 part polysulphide sealer.   | m  | 208 |   |  |
|  | <u>FORMWORK</u>   |    |     |   |  |
|  | <u>Edges, risers, ends and reveals</u>  |    |     |   |  |
| 8                                      | Edge, riser, etc not exceeding 300mm high.  | m  | 418 |   |  |
| <b>Carried to Collection</b>           |   |    |     | R |  |
| Section No. 4                          |   |    |     |   |  |
| Bill No. 5                             |   |    |     |   |  |
| ROADS, PAVING, ETC.                    |   |    |     |   |  |
| <b>QEBE JSS</b>                        |   |    |     |   |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b> |   |    |     |   |  |

REINFORCEMENTReinforcement

|   |  |    |     |
|---|--|----|-----|
| 1 | Ref: 193 High tensile welded steel mesh reinforcement cast into concrete surfaces. | m2 | 232 |
|---|--|----|-----|

SHEET OR MEMBRANE WATERPROOFING (Labour intensive)

250 Micron "Gunplas USB" green polyethylene sheeting  
:

|   |                         |    |    |
|---|-------------------------|----|----|
| 2 | Laid flat under aprons. | m2 | 60 |
|---|-------------------------|----|----|

Carried to Collection

R

Section No. 4

Bill No. 5

ROADS, PAVING, ETC.

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**



Section No. 4

Bill No. 5

ROADS, PAVING, ETC.

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

118

119

120

**Carried Forward to Summary of Section No. 4**

R

Section No. 4

Bill No. 5

ROADS, PAVING, ETC.

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Bill No                         | SECTION SUMMARY - SECTION NO.4 - EXTERNAL WORKS | Page No | Amount |
|---------------------------------|---|---------|--------|
| 1                               | BULK EARTHWORKS                                 | 104     |        |
| 2                               | SOIL DRAINAGE (PROVISIONAL)                     | 110     |        |
| 3                               | STORMWATER DRAINAGE                             | 114     |        |
| 4                               | WATER SUPPLIES                                  | 117     |        |
| 5                               | ROADS, PAVING, ETC.                             | 121     |        |
| Carried to Final Summary        |   |         | R      |
| Section No. 4                   |   |         |        |
| QEBE JSS                        |   |         |        |
| PROVISIONAL BILLS OF QUANTITIES |   |         |        |

| Item No |   | Quantity | Rate | Amount     |
|---------|---|----------|------|------------|
|         | <b><u>SECTION NO.5 - PROVISIONAL SUMS , BUDGETARY ALLOWANCES, ECT.</u></b>  |          |      |            |
|         | <b><u>BILL NO.1</u></b>   |          |      |            |
|         | <b><u>PROVISIONAL SUMS , BUDGETARY ALLOWANCES, ECT.</u></b>   |          |      |            |
|         | <u>Note:</u>  |          |      |            |
|         | For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).                                      |          |      |            |
|         | <b><u>PROVISIONAL SUM</u></b>   |          |      |            |
|         | <b><u>JOINERY FITTINGS</u></b>  |          |      |            |
| 1       | Provided the Provisional sum of R 10 000.00 (Ten Thousand Rand) for the replacement of existing joinery fittings.   | Item     |      | 10,000.00  |
| 2       | Add for profit on the above, if desired.  | Item     |      |            |
| 3       | Allow for attendance on the above, if desired.  | Item     |      |            |
|         | <b><u>ELECTRICAL INSTALLATION</u></b>   |          |      |            |
| 4       | Provided the Provisional sum of R 100 000.00 (One Hundred Thousand Rand) for the installation of the new and refurbishment of existing electrical installations including replacing lights, plugs and sockets, ect. | Item     |      | 100,000.00 |
| 5       | Add for profit on the above, if desired.  | Item     |      |            |
| 6       | Allow for attendance on the above, if desired.  | Item     |      |            |
|         | <b><u>COMMUNITY LIAISON OFFICER (CLO)</u></b>   |          |      |            |
| 7       | Provide the sum of R 45 000.00 (Forty Five Thousand Hundred Rand) for the employment of a CLO.(R 7 500.00 per month x contract period allowance)  | Item     |      | 45,000.00  |
|         | <b>Carried to Collection</b>  |          |      | R          |
|         | Section No. 5   |          |      |            |
|         | Bill No. 1  |          |      |            |
|         | PROVISIONAL SUMS, BUDGETARY ALLOWANCES,EC   |          |      |            |
|         | <b>QEBE JSS</b>   |          |      |            |
|         | <b>PROVISIONAL BILLS OF QUANTITIES</b>  |          |      |            |

|  |  |      |            |  |
|--|--|------|------------|--|
| 1  | Add for profit on the above if required.   | Item |            |  |
|  | <u>PERIMETER FENCING</u>   |      |            |  |
| 2  | Provisional sum of R 800 000.00 ( Eight Hundred Thousand Rand) for the supply and installation of the perimeter fencing to the site as per architects specifications by specialist contractor. | Item | 800,000.00 |  |
| 3  | Add for profit on the above.   | Item |            |  |
| 4  | Allow for attendance upon the specialist installation subcontractor.   | Item |            |  |
|  | <u>BUDGETARY ALLOWANCE</u>   |      |            |  |
|  | <u>REPAIRS TO EXISTING PREFABRICATED CLASSROOMS</u>  |      |            |  |
| 5  | Allow the Budgetary Allowance of R 400 000.00 (Four Hundred Thousand Rand) for the repairs and renovations to existing prefabricated classroom blocks, to be detailed at a later stage.        | Item | 400,000.00 |  |
|  | <u>REPAIRS TO EXISTING VIP TOILETS</u>   |      |            |  |
| 6  | Allow the Budgetary Allowance of R 80 000.00 (Eighty Thousand Rand) for the minor repairs to newly built VIP toilets, to be detailed at a later stage.   | Item | 80,000.00  |  |
|  | <u>SIGNAGE</u>   |      |            |  |
| 7  | Allow the Budgetary Allowance of R 5 000.00 (Five Thousand Rand) for the replacing of the main building signage.   | Item | 5,000.00   |  |
| <b>Carried to Collection</b>               |  |      | R          |  |
| Section No. 5                              |  |      |            |  |
| Bill No. 1                                 |  |      |            |  |
| PROVISIONAL SUMS, BUDGETARY ALLOWANCES, EC |  |      |            |  |
| <b>QEBE JSS</b>                            |  |      |            |  |
| <b>PROVISIONAL BILLS OF QUANTITIES</b>     |  |      |            |  |

Section No. 5

Bill No. 1

PROVISIONAL SUMS, BUDGETARY ALLOWANCES, ECT.

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No****Amount**

123

124

**Carried to Final Summary**

R

Section No. 5

Bill No. 1

PROVISIONAL SUMS, BUDGETARY ALLOWANCES, EC

**QEBE JSS****PROVISIONAL BILLS OF QUANTITIES**

| Section No | FINAL SUMMARY   | Page No | Amount     |
|------------|---|---------|------------|
| 1          | SECTION NO.1 - PRELIMINIARIES AND GENERAL   | 43      |            |
| 2          | SECTION NO.2 - EXISTING BUILDINGS   | 66      |            |
| 3          | SECTION NO.3 - PREFABRICATED STRUCTURES   | 100     |            |
| 4          | SECTION NO.4 - EXTERNAL WORKS   | 122     |            |
| 5          | SECTION NO.5 - PROVISIONAL SUMS , BUDGETARY ALLOWANCES, ECT.  | 125     |            |
|            | Sub - Total   | R       |            |
|            | <b><u>CONTINGENCY PROVISIONS</u></b>  | Item    | 100,000.00 |
|            | Allow the Budgetary Provision of R 100 000.00 ( One Hundred Thousand Rand) for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the Contract Sum. | Item    | 100,000.00 |
|            | Sub - Total   | R       |            |
|            | Add Value - Added Tax at the rate applicable as at Tender closing date.   | R       |            |
|            | Sub - Total   | R       |            |
|            | Carried to Form of Tender   | R       |            |
|            | <b>QEBE JSS<br/>PROVISIONAL BILLS OF QUANTITIES</b>   |         |            |