


GENERATOR COMPLETE WITH SOUND ATTENUATION - SCHEDULE OF REQUIREMENTS									
SYSTEM VOLTAGE AND FREQUENCY			400 Volts, 50 Hz						
SITE LOCATION			Cape Town						
CLIMATIC CONDITIONS			Sea Level						
Altitude			5°C to 40°C						
Ambient Temperature			95%						
Relative Humidity			Samora Machel Police station						
DESIGNATION									

GENERATOR SET			1	2	3
1	Designation & Labelling		Samora Machel Police Station		
2	Overview	Diesel Engine	Perkins/Caterpillar/Volvo/Cummins Installed within sound attenuated canopy on duplex steel base plate with anti-vibration engine/base and base/floor mounts		
3		Alternator	Stamford/Caterpillar/Leroy Somer 400/230V, 50Hz @ 1500rpm, directly coupled to diesel engine with insulation level 'H'		
4		Exhaust System	Dual silencer and exhaust required		
5		Arrangement	Within sound attenuated Canopy - 65dBA @7m		
6		Change-over Panel	Auto change-over panel located in LV room (generator signal to start up by PV Inverter)		
7		Ventilation/Acoustic System	Provided at intake and outlet, inclusive of louvers		
8	Performance Characteristics	Power Rating	240kW prime power rating at 0.8 pf (300kVA)		
9		Maximum Single Step load	144 kW (60%) from cold start		
10		Alternator Rating	Power Rating + 0.8 + 10% for harmonics caused by non-linear loads		
11		Nominal Output Voltage	400/230V, 3 phase, 4 wire adjustable from 346V to 415V nominal voltage for all load conditions.		
12		Frequency	50 Hz		
13		Neutral Earthing	Solidly earthed		
14		Voltage Distortion Across Phases	Not to exceed 1% of the open circuit voltage		
15		Steady State Voltage Variation	Not greater than 1.5% (from nominal) between 0 and 100% full load with specified speed variation and through unity to 0.8pf lagging		
16		Transient Voltage Dip And Recovery Time	Not greater than 10% deviation from steady state nominal voltage and will recover to within 1.5% of the nominal voltage within 250 milliseconds for step load as specified		
17		Voltage Modulation Amplitude	2% ie. $(U_{max} - U_{min} \times 100) / (U_{nom})$		
18		Steady State Speed Regulation	Not greater than 4% deviation from nominal under all loading conditions		
19	Transient Speed Regulation And Recovery Time	Not greater than 6.5% deviation from nominal under all loading conditions with recovery within 2 seconds			
20	Overload Characteristics	Set Overload Capacity	110% of continuous prime power full load rating at rated voltage for 1 in 12 hours		
21		Alternator	Minimum 250% full load at rated voltage for 5 seconds		
22	Fuel System	Bulk Fuel Tank	None		
		Day Fuel Tank	1500 Litre Base mounted welded double skin steel tank comprising - fill connection, vent pipe/breather, sludge drain connection, sight glass level indicator, feed connection, strainer, electronic level gauge (5 preset alarms and level monitoring)		
23		Fuel Shutoff	Individual fusible links above set to operate gravity shutoff valve and both valves monitored by generator system.		
24		Fuel Transfer	Duplex pumps and solenoid valves controlled via central controller. Level transducers in all tanks		
25		Fuel Filtering	Duvalco Semi Bulk Fuel Management system		
26		Fuel Filling Station	Lockable fill point cabinet located externally with fill alarm, tank contents gauge, overflow drain.		
27	Control Panel	Physical dimensions (maximum)	1500(w)x2500(l)x1800(h)		
28		Controller	Deep Sea 8620		
29		Incoming arrangement	185mm. ² Cu PVC SWA ECC cable or 2No. 95mm. ² Cu PVC SWA ECC cable		
30		Protection Circuit breaker	Schneider or equivalent		
31		Displays for hours run and electrical parameters	Digital		
32	Additional Equipment	Rigging Equipment	Welded lifting lugs and jacking pads		
32		Base	skid mounted with duplex anti-vibration mounting		
33		Batteries	Delco maintenance free on hot dip galvanised stand with clear perspex cover. Capacity for four consecutive cranking cycles (20s on and 10s off), and full operating supply to control systems		
34		O&M Manual	Three complete sets hardcopy. One complete set electronically		
35	Testing	Factory	Control functionality, protection devices and alarms, including verification of sensing devices and transducers as requested by the Engineer		
36			Cold start and load acceptance tests		
37			Full load and Maximum load tests for sufficient duration to verify set capacity. Suitable load banks to be provided as required		
38			Substantiation of transient voltage dip by test or certified graphical documentation to approval of the Engineer		
39		Site	Transient voltage and speed performance verification tests		
40	Full functional test of generation system as installed in conjunction with associated set loads and systems, inclusive of all fuels, lube oils and consumables. System synchronisation and load acceptance - Suitable load banks to be provided as required. On completion of all testing, the fuel system shall be full, and lube oil levels shall be full.				
41	General	Colour	Generator Sets - minimum two coats of two pack epoxy paint - Blue		
42		Dimensions	Refer to layout drawing		
43		Acoustic Control	Acoustic louvers and attenuation to reduce noise levels to within 65 dBA @ 7m from generator room		
44		Signage	Statutory & rating and diagram plate		
45		Emmissions	To comply with the Tier 2 emissions standards as defined by the United States Environmental Protection Agency (EPA) or the equivalent European Stage IIIA Standards		
46		Loads	Typically lighting and star delta starting pump motors and inverter batteries		


					ENGINEER:	DRAWN:	DATE:	CHKD	P. SIZE	TITLE:	
					MK	MK	29/10/24	MK	A3	Samora Machel Police Station	
					DRAWING No.: 602			REV	SCALE	Generator Schedule	
								0	nts		
0	Original issue	MK	29/10/24	MK							
REV	DESCRIPTION	BY	DATE	CHKD	FILE NAME:	SHEET:		1 of 2			

Approved in Principle
Justin Mckelvie-King
Pr Eng : 20120548

GENERATOR COMPLETE WITH SOUND ATTENUATION - SCHEDULE OF REQUIREMENTS

SYSTEM VOLTAGE AND FREQUENCY		400 Volts, 50 Hz
SITE LOCATION		Cape Town
CLIMATIC CONDITIONS	Altitude	Sea Level
	Ambient Temperature	5°C to 40°C
	Relative Humidity	95%
DESIGNATION		Samora Machel Police Station

GENERATOR		1	2	3
Fault Conditions	47	High Engine Temperature	shutdown and alarm (audible and output)	
	48	Low Oil Pressure	shutdown and alarm (audible and output)	
	49	Overspeed	shutdown and alarm (audible and output)	
	50	Underspeed	shutdown and alarm (audible and output)	
	51	Low Coolant Level	shutdown and alarm (audible and output)	
	52	High A/C Volts	shutdown and alarm (audible and output)	
	53	Low A/C Volts	shutdown and alarm (audible and output)	
	54	Emergency Stop	shutdown and alarm (audible and output)	
	55	Failure to Start	shutdown and alarm (audible and output)	
Alarm & Indication	56	Set Not in Automatic Mode	indication (flashing led and output)	
	57	Low Fuel Level	indication (flashing led) and alarm (audible and output)	
	58	Water Jacket Heater Faulty	indication (flashing led) and alarm (audible and output)	
	59	Manual Start	indication (flashing led)	
	60	Manual Stop	indication (flashing led)	
	61	Mains Available	indication (flashing led) plus output to auto changeover panel	
	62	Mains	indication (flashing led) plus output to auto changeover panel	
	63	Alternator Available	indication (flashing led) plus output to auto changeover panel	
	64	Alternator on Load	indication (flashing led) plus output to auto changeover panel	
User Programmable Parameters	65	Alterator run down period complex	indication (flashing led) plus output to auto changeover panel	
	66	Low Battery Volts	indication (led) and alarm (audible and output)	
	67	Fuel Valves Closed	indication (flashing led) and alarm (audible and output)	
	68	Room Temperature	indication (flashing led) and alarm (audible and output)	
	69	Alternator Undervoltage (<V)	0 to >V	
	70	Alternator Overvoltage (>V)	<V to 600V	
	71	Under / Over Voltage Delay	0 to 60 seconds	
	72	Start Delay	0 to 60 seconds	
	73	Crank Delay	0 to 60 seconds	
	74	Run up Delay	0 to 60 seconds	
	75	Run on Timer	0 to 60 seconds	
	76	Mains Return Timer	0 to 60 seconds	
	77	Load Transfer Delay	0 to 60 seconds	
	78	Engine Under Speed	50 to 6000 rpm	
	79	Engine Over Speed	50 to 6000 rpm	
	80	Number of Start Attempts, Maximum Crank Time	1 to 10, 1 to 60 seconds	
	81	Low Battery Voltage	8 to 30V	
	82	Overload, Overload Delay	0.5 to 9000kW, 0 to 60 seconds	
	83	Alternator Underfrequency (<f)	0 to >f	
	84	Alternator Overfrequency (>f)	<f to 130Hz	
	85	Under / Over Frequency Delay	0 to 60 seconds	
	86	Voltage Window - Difference Between Gen and Bus	0 to 300V	
	87	Phase Window -Difference between Gen and Bus	0 to 90°	
	88	Dwell Time	0 to 25.0 seconds	
	89	Synchronization Timeout	0 to 1800 seconds	

					ENGINEER:	DRAWN:	DATE:	CHKD	P.SIZE	TITLE: Samora Machel Police Station Generator Schedule	
					MK	MK	29/10/24	MK	A3		
					DRAWING No.:			REV	SCALE		
					602			0	nts		
0	Original issue				MK	29/10/24		MK			
REV	DESCRIPTION				BY	DATE	CHKD	FILE NAME: 2 of 2			