

BOQ for Repairs of 11Kv Bundle Cable

NO.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>BILL NO. 1</u>				
	150mm ² 11kV MV ABC Aluminium 3 core cable	M	1500		
	<u>BILL NO. 2</u>				
	Test bundle, keep healthy portions and remove, decommission and transport of existing damaged cable from site to Salt River depot.	Sum	1		
	<u>BILL NO. 3</u>				
	Supply and install Suspension insulators	Each	20		
	<u>BILL NO. 4</u>				
	Install ABC cable on to existing structures	m	2000		
	<u>BILL NO. 5</u>				
	Supply and install Cu, 150mm XLPE underground cable	m	200		
	<u>BILL NO. 6</u>				
	Install joints on the Bundled cable	EACH	10		
	<u>BILL NO. 7</u>				
	Install joints on the underground cable	EACH	3		
	<u>BILL NO. 8</u>				
	Security and OHS consumables	Months	2		
	PROVISIONAL SUM	EACH	1	R50 000.00	R50 000.00
	SUB TOTAL				
	VAT 15%				
	TOTAL				