

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	THE FOLLOWING IN DEMOLITION OF EXISTING BUILDINGS, DESLUDGING, GRAB UP FOUNDATIONS, BACKFILLING EXCAVATIONS WITH IMPORTED FILL MATERIAL, ETC	H2			
	PRELIMINARIES				
1	Contractor to provide all items required to enable the works	Item	1		R -
2	Compliance with statutory OHS items	Item	1		R -
	<u>ABLUTION FACILITY - DEMOLITION</u>				
	Desludging of Existing Pits	H4			
3	Desludging of existing ablation facility pits of any waste and residue and disposing to an approved disposal site approved by the principal agent.	m3	32,4		R -
	Allow for provision of a disposal certificate	No	1		R -
	Demolition	H4			
4	Demolition of existing building of plastered brick walls and fibre cement roofing approximately 12 x 4m in size including adjoining pit, grubbing up foundations and removal of all excess rubble to a waste disposal site as approved by the principal agent.	No	1		R -
	Backfilling	H4			
5	Backfilling of excavated surfaces with imported fill material supplied by the contractor compacted to 95% MOD AASHTO density in prescribed layers of 300mm layers or fill.	m3	61,2		R -
	Test Certificates	H4			
6	Allow for provision of compaction tests results	No	1		R -
7	Cart away rubble and stock piled material from construction activities	m3	40		R -
	BUDGETARY ALLOWANCE				
	UNPAID AMOUNTS FROM PREVIOUS CONTRACT				
8	Allow the sum of R90 000 (Ninety Thousand Rand) for the payment of unpaid labour, amounts owed to the school and to sub-contractors as a result of default by the previous contractor	Item	1	R 90 000,00	R 90 000,00

Sub Total

R -

VAT @ 15%

R -

TOTAL

R -