

ITEM	REF	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		SECTION NO. 3				
	SANS 1200A/AB/Pricing Assumpt:	COASTAL STRUCTURES				
		SLOPE STABILISATION AT MOLE (Chainage 0+560 to 0+665)				
	C3.1	Site Clearance				
1	C3.1.1	Clear the site and remove debris to an approved on-land dumpsite	m ²	2 050		
	C3.5	Excavation				
2	C3.5.1	Excavate and Stockpile existing material to be reused in revetment construction	m ³	4 300		
	C3.2	Supply and construction of revetment				
3	C3.2.1	Supply and construct Armour 1 slope with rock of grading 900mm	t	9 050		
4	C3.2.2	Supply and construct Filter rock type 1 slope with rock of grading 300mm	t	2 827		
	C3.3	Supply and construction of toe				
5	C3.3.1	Supply and construct Armour 2 toe with rock of grading 800mm	t	5158.4		
	C3.3	Blinding Layer / Void filler				
6	C3.3.1	Supply and construct Blinding Layer with Filter rock type 3 of grading 53mm	t	1 600		
	C3.4	Geotextile				
7	C3.4.1	Supply and Install Grade A10 Bidum	m ²	3 535		
		SLOPE STABILISATION BETWEEN BERTH 1-2 (Chainage 0+740 to 0+821)				
	C3.1	Site Clearance				
8	C3.1.1	Clear the site and remove debris to an approved on-land dumpsite	m ²	3 900		
	C3.5	Excavation				
9	C3.5.1	Excavate and Stockpile existing material to be reused in revetment construction	m ³	4 300		
	C3.2	Supply and construction of revetment				
10	C3.2.1	Supply and construct Armour 2 slope with rock of grading 800mm	t	3 040		
11	C3.2.1	Supply and construct Armour 3 slope with rock of grading 600mm	t	2 400		
12	C3.2.2	Supply and construct Filter rock type 1 slope with rock of grading 300mm	t	1 920		
Carried Forward:						