

**EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<p><b><u>PRELIMINARIES</u></b></p> <p><b><u>SECTION D- SITE ESTABLISHMENT AND ACCOMMODATION</u></b></p> <p><b><u>Contractual obligation</u></b></p> <p>1 Accommodation</p> <p>2 Site office</p> <p>3 Security guards and PPE for workers</p>	<p>Item</p> <p>Item</p> <p>Item</p>	<p>0</p> <p>0</p> <p>1</p>		
	Total Amount carried to final summary				R

**EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

Item	Description	Unit	Qty	Rate	Amount
	<b><u>Bill No. 2</u></b>				
	<b><u>EARTHWORKS</u></b>				
	<b><u>Site Clearance</u></b>				
1	Digging up and removal of rubbish, debris, vegetation, hedges, bushes and trees n.e 200mm girth	m <sup>2</sup>	7		
2	Excavate and cast in foundation concrete on edge	m <sup>3</sup>	35		
3	Stabilizing , levelling to slope, water channelling, kerb preperation on the drive way and levelling to prepare pavement and slope towards the gate rail levels	m <sup>3</sup>	9		
	Total Amount c/f				R

**EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

Item	Description	Unit	Qty	Rate	Amount
	Total Amount b/f				R
	<b>Travelled way, including in-situ preparation of wearing course and selected layer, to :</b>				
4	Minimum of 93% of mod AASHTO density	m <sup>3</sup>	12		
5	Cut to fill compacted to 93% of mod AASHTO density	m <sup>3</sup>	2		
6	Borrow to fill, compacted to 93% of mod AASHTO density	m <sup>3</sup>	14		
7	Lower selected layer, compacted to 93 % of mod AASHTO	m <sup>3</sup>	4		
8	Soft excavation	m <sup>3</sup>	1		
9	Intermediate excavation	m <sup>3</sup>	1		
10	Sand fill, level to lay pave bricks	m <sup>3</sup>	3		
11	Long overhaul (truck haul) to the nearest dumping site	m <sup>3</sup> .km	3		
	Total Amount Carried to Final Summary				R

**EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

Item	Description	Unit	Qty	Rate	Amount
	<b>BILL No 3</b>				
	<b>PAVING WORK</b>				
	<b>Versatile interlocking paving patterns</b>				
	Contractor is requested to prepare and level ground to slope prepare, insecticides areas marked on the drawing before laying paving bricks, sloping of the ground should not come closer to the walls of the covered patio of the hall and other sides of the building				
1	Supply and lay 60mm Grey interlocking paving including 20mm sand bedding.	m <sup>2</sup>	121		
2	Approved herbicide and ant poison under paving	m <sup>2</sup>	109		
3	Other special test requested by SAFCOL (Compaction Test)	m <sup>2</sup>	8		
4	Permanently remove all unwanted weeds from floor	m <sup>2</sup>	23		
5	Providing testing certificate and Pest control	Item	1		
	<b>Plastic Under the paving</b>				
	250micron green or equal approved sisalation laid on or under paving to avoid growing weeds and shrubs				
6	On drive way ( From the gate to the corner of entrance)	m <sup>2</sup>	40		
7	From the front of entrance to the corner drive	m <sup>2</sup>	21		
	Total Amount Carried to Final Summary				R

**EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

Item	Description	Unit	Qty	Rate	Amount
	<p><b>BILL No 4</b></p> <p><b>STORMWATER DRAINAGE / CHANNEL - PROVISIONAL</b></p> <p><b>KERBING, CHANNELING &amp; EDGE STRIPS</b></p> <p>Contractor is requested to be carefully channel water from the slopping side of the ground to the storm water catchpit</p> <p>Concrete well mixed placed on the edge strip of the paving bricks for stability and non movement</p>				
1	Half battered kerb formed	m	55		
2	Rectangular edging elsewhere	m	26		
	Total Amount Carried to Final Summary				R

**EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

Item	Description	Unit	Qty	Rate	Amount
<b>PROVISIONAL SUMS</b>					
1	Allow an amount of R3 000 (Three Thousand Rand) for community liason office (CLO)	Item	1	3 000	R 3 000,00
2	Allow for profit	%			
Total Amount Carried to Final Summary					R

EXTERNAL WORK - SHANZA SKILLS DEVELOPMENT CENTRE  
(Labour and Material Contract)

## FINAL SUMMARY

Item	Description	Page	Total Amount
1	Bill No. 1: Preliminaries	1	R
2	Bill No. 2: Earth works.	3	R
3	Bill No. 2: Paving	4	R
4	Bill No. 4: Storm Water Drainage	5	R
5	Bill No. 5: Provisional Sums	6	R
	Sub-Total		R
	15% VAT		R
	Total Amount Tendered		R