

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

## TRANSNET SOC LIMITED

**TENDER NUMBER: TNPA/2025/06/0004/99874/RFP**

**DESCRIPTION OF THE WORKS: FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS**

**ADDENDUM NO. 001**

**DATED 15 September 2025**

The following information is furnished in addition to, in amplification and substitution of, matters contained in the tender documents issued in respect of the abovementioned work.

### 1. PART C2: PRICING DATA

#### 1.1 THE BILL OF QUANTITIES

#### SCHEDULE A : ROAD CONSTRUCTION P&G

#### SECTION 1200: GENERAL REQUIREMENTS AND PROVISIONS

*Add the following rates to items B12.02(b)(i) and (ii)*

| ITEM NO | DESCRIPTION                      | UNIT   | QUANTITY | RATE      | AMOUNT    |
|---------|----------------------------------|--------|----------|-----------|-----------|
|         | (i) Fixed penalty per occurrence | number | 1        | -5,000.00 | -5,000.00 |
|         | (ii) Time-related penalty        | hour   | 1        | -500.00   | -500.00   |

*Add the following payment item in section 1200*

| ITEM NO       | DESCRIPTION                                                                      | UNIT     | QUANTITY   | RATE       | AMOUNT     |
|---------------|----------------------------------------------------------------------------------|----------|------------|------------|------------|
| <b>B12.03</b> | <b>Training on concrete construction</b>                                         |          |            |            |            |
|               | (a) Allowance for training                                                       | Prov Sum | 1          | 150,000.00 | 150,000.00 |
|               | (b) Handling costs, profit and all other charges in respect of subitem B12.03(a) | %        | 150,000.00 | .....%     |            |

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

## **SCHEDULE B : NEWARK ROAD, SCHEDULE C : VENTURA ROAD and SCHEDULE D : URANIA ROAD**

### **SECTION 7100: CONCRETE PAVEMENTS**

*Change the description of payment items B71.06 (d) in Schedules B,C and D to the following*

| ITEM NO | DESCRIPTION                                                                        | UNIT | QUANTITY | RATE | AMOUNT |
|---------|------------------------------------------------------------------------------------|------|----------|------|--------|
|         | (d) Diamond dowels with pocket formers (stainless steel), 20 mm x 114 mm x 114 mm: | m    | 4600     |      |        |

## **2. PART C3: SCOPE OF WORK**

### **2.1 PART C3.2 CONTRACTOR'S WORKS INFORMATION: WORKS SPECIFICATIONS.**

#### **SECTION B7100: CONCRETE PAVEMENTS**

##### **B7102 MATERIALS**

- (a) Reinforcing steel, tie-bars and dowels

*Replace the 3rd paragraph with the following:*

"Diamond dowels shall be manufactured from stainless steel (complying with the requirements of BS 970 : part 4 for steel 316S16) having a smooth finish to ¼ DIN tolerance of the DN 1013 specification."

##### **B7114 CURING**

*Amend the 1<sup>st</sup> sentence of the 2<sup>nd</sup> paragraph to read as follows:*

"The curing compound shall be sprayed onto the surface at a rate of 0.35 l/m<sup>2</sup> for the White-pigmented solvent resin-based curing compound and 0.7 l/m<sup>2</sup> for the Emulsion wax curing compound or as directed by the engineer by means of a mechanical distributor capable of producing a fine fog-type of spray which will not damage the surface of the concrete."

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

## B7127 MEASUREMENT AND PAYMENT

**Item**

**Unit**

### B71.06 Joints:

*Replace the description of payment item 71.06(d) with the following:*

(d) Diamond dowels with pocket formers (stainless steel), 20 mm x 114 mm x 114 mm:

(i) ..... Installed in  
new concrete ..... number"

## SECTION B8100: TESTING MATERIALS AND WORKMANSHIP

### B8103 THE COSTS OF TESTING

*In the fifth paragraph change "fourteen" to "fifteen"*

#### 3. Extension of the closing date.

The closing date of the tender has been extended to **06 October 2025 @ 16h00**

The following sections in the RFP are replaced to reflect the extended closing date:

- 1) Cover page
- 2) T1.1 Tender Notice and Invitation to Tender
- 3) T1.2 Tender Data

#### WITNESSES:

1. \_\_\_\_\_

2. \_\_\_\_\_

\_\_\_\_\_  
**TENDERER / CONTRACTOR**

#### WITNESSES:

1. \_\_\_\_\_

2. \_\_\_\_\_

\_\_\_\_\_  


\_\_\_\_\_  
**TRANSNET SOC LIMITED**

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

FROM : \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

DATE : \_\_\_\_\_

**TO : Transnet National Ports Authority  
237 Mahatma Gandhi Road  
Durban  
4000  
(Attention: Mrs J McCann - Email. TENDERENQUIRIES@transnet.net)**

Dear Sirs / Madam

**TENDER NUMBER: TNPA/2025/06/0004/99874/RFP**

**DESCRIPTION OF THE WORKS: FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS**

Receipt of **Addendum No. 001** dated **15 September 2025** is hereby acknowledged.

Kind regards

---

**TENDERER**

**NOTE:** This acknowledgement must be signed and returned to this office on or before closing date of tender.

Ref: **TNPA/2025/06/0004/99874/RFP**

ADDENDUM #1

| SCHEDULE A : ROAD CONSTRUCTION P&G |                                                                                                                                 |             | SECTION 1200 |             |             |
|------------------------------------|---------------------------------------------------------------------------------------------------------------------------------|-------------|--------------|-------------|-------------|
| ITEM NO                            | DESCRIPTION                                                                                                                     | UNIT        | QUANTITY     | RATE        | AMOUNT      |
|                                    | <b>GENERAL REQUIREMENTS AND PROVISIONS</b>                                                                                      |             |              |             |             |
| B12.01                             | Compliance with the Occupational Health and Safety Act (OHS) and Regulations (including the Construction Regulations, 2014)     | Lump Sum    | 1            |             |             |
| B12.02                             | Compliance with Environmental Specification (ES):                                                                               |             |              |             |             |
|                                    | (a) Environmental training                                                                                                      | Lump Sum    | 1            |             |             |
|                                    | (b) General compliance with ES                                                                                                  | Lump Sum    | 1            |             |             |
|                                    | (i) Fixed penalty per occurrence                                                                                                | number      | 1            | -5,000.00   | -5,000.00   |
|                                    | (ii) Time-related penalty                                                                                                       | hour        | 1            | -500.00     | -500.00     |
|                                    | (d) Testing of contaminated material                                                                                            | Prov Sum    | 1            | R100 000,00 |             |
|                                    | (e) Handling costs, profit and all other charges in respect of subitem B12.02(c) and (d)                                        | %           | R100 000,00  |             |             |
|                                    | <b>Enterprise Development (CIDB B.U.I.L.D PROGRAM)</b>                                                                          |             |              |             |             |
|                                    | Indirect Targeting for Enterprise Development through Construction Works Contracts, Gazette Notice No.36190 of 25 February 2013 |             |              |             |             |
|                                    | (a) Enterprise Development of Targeted Enterprise or JV partners                                                                |             |              |             |             |
|                                    | (a.1) Needs Analysis and Enterprise Development Plan per Targeted Enterprise                                                    | Item        | 1            | R50 000,00  |             |
|                                    | (a.2) Monitoring and Interim Reporting per Targeted Enterprise                                                                  | Per Quarter | 4            | R160 000,00 |             |
|                                    | (a.3) Project Completion Report per Targeted Enterprise                                                                         | Item        | 1            | R50 000,00  |             |
|                                    | Total (a.1 + a.2 + a.3)                                                                                                         | Prov Sum    |              |             | R260 000,00 |
| B12.03                             | Training on concrete construction                                                                                               |             |              |             |             |
|                                    | (a) Allowance for training                                                                                                      | Prov Sum    | 1            | 150,000.00  | 150,000.00  |
|                                    | (b) Handling costs, profit and all other charges in respect of sub item B12.03(a)                                               | %           | 150,000.00   | .....%      |             |
| 1200                               | CARRIED FORWARD                                                                                                                 |             |              |             |             |

| SCHEDULE B : ROAD CONSTRUCTION - NEWARK ROAD |                                                                                                                                         |        |          | SECTION 7100 |        |
|----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|--------|----------|--------------|--------|
| ITEM NO                                      | DESCRIPTION                                                                                                                             | UNIT   | QUANTITY | RATE         | AMOUNT |
|                                              |                                                                                                                                         |        |          |              |        |
|                                              |                                                                                                                                         |        |          |              |        |
|                                              | BROUGHT FORWARD                                                                                                                         |        |          |              |        |
|                                              |                                                                                                                                         |        |          |              |        |
|                                              | (ii) Unsealed hinge joints, Joint B2, as shown on the drawing (1006614-DRG-12-NW-CC-D002)                                               | m      | 4 200    |              |        |
|                                              | (c) Sealed transverse contraction joints sawn in two separate operations, Joint A1, as shown on the drawing (1006614-DRG-12-NW-CC-D002) | m      | 9 900    |              |        |
|                                              | (d) Unsealed transverse contraction joints, Joint A3, as shown on the drawing (1006614-DRG-12-NW-CC-D002)                               | m      | 17 050   |              |        |
|                                              | (d) Diamond dowels with pocket formers ( <del>mild steel</del> stainless steel), 20 mm x 114 mm x 114 mm:                               |        |          |              |        |
|                                              | (i) Installed in new concrete                                                                                                           | number | 3 350    |              |        |
|                                              | (e) Tie-bars:                                                                                                                           |        |          |              |        |
|                                              | (i) 20 mm diameter, 900 mm long installed in new PJCP                                                                                   | number | 17 000   |              |        |
|                                              | (g) Forming and sealing the joints between asphalt and concrete pavements, Joint F, as shown on the drawing (1006614-DRG-12-NW-CC-D002) | m      | 150      |              |        |
|                                              | (i) Plain isolation joint, Joint D, as shown on the drawing (1006614-DRG-12-NW-CC-D002)                                                 | m      | 7 450    |              |        |
|                                              | (j) Armoured Isolation joint, Joint E, as shown on the drawing (1006614-DRG-12-NW-CC-D002)                                              | m      | 350      |              |        |
|                                              | (k) Forming and sealing diamond dowel joints, Joint A2, as shown on the drawing (1006614-DRG-12-NW-CC-D002)                             | m      | 1 500    |              |        |
| 71,07                                        | <b>Drilling and testing of cores:</b>                                                                                                   |        |          |              |        |
|                                              | (a) 100 mm cores drilled from the pavement                                                                                              | number | 300      |              |        |
|                                              | (b) 150 mm cores drilled from the pavement and tested for compressive strength                                                          | number | 300      |              |        |
| 71,08                                        | <b>Steel reinforcement in concrete pavement:</b>                                                                                        |        |          |              |        |
|                                              |                                                                                                                                         |        |          |              |        |
|                                              |                                                                                                                                         |        |          |              |        |
|                                              |                                                                                                                                         |        |          |              |        |
|                                              |                                                                                                                                         |        |          |              |        |
| 7100                                         | CARRIED FORWARD                                                                                                                         |        |          |              |        |

| SCHEDULE C : ROAD CONSTRUCTION - VENTURA ROAD |                                                                                                                                         |        |          | SECTION 7100 |        |
|-----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|--------|----------|--------------|--------|
| ITEM NO                                       | DESCRIPTION                                                                                                                             | UNIT   | QUANTITY | RATE         | AMOUNT |
|                                               | BROUGHT FORWARD                                                                                                                         |        |          |              |        |
|                                               | (e) Curing with emulsion wax curing compound and movable frame cover                                                                    | m²     | 12 550   |              |        |
| <b>B71.05</b>                                 | <b>Variation in the rate of application of the curing compounds</b>                                                                     |        |          |              |        |
|                                               | (a) White pigmented solvent resin based curing compound                                                                                 | litre  | 1 000    |              |        |
|                                               | (b) Wax based emulsion compound                                                                                                         | litre  | 628      |              |        |
| <b>B71.06</b>                                 | <b>Joints:</b>                                                                                                                          |        |          |              |        |
|                                               | (b) Longitudinal hinge joints:                                                                                                          |        |          |              |        |
|                                               | (i) Sealed hinge joints, Joint B1 and Joint C, as shown on the drawing (1006614-DRG-12-VT-CC-D002)                                      | m      | 1 300    |              |        |
|                                               | (ii) Unsealed hinge joints, Joint B2, as shown on the drawing (1006614-DRG-12-VT-CC-D002)                                               | m      | 600      |              |        |
|                                               | (c) Sealed transverse contraction joints sawn in two separate operations, Joint A1, as shown on the drawing (1006614-DRG-12-VT-CC-D002) | m      | 1 900    |              |        |
|                                               | (d) Unsealed transverse contraction joints, Joint A3, as shown on the drawing (1006614-DRG-12-VT-CC-D002)                               | m      | 3 150    |              |        |
|                                               | (d) Diamond dowels with pocket formers ( <del>mild steel</del> stainless steel), 20 mm x 114 mm x 114 mm:                               |        |          |              |        |
|                                               | (i) Installed in new concrete                                                                                                           | number | 500      |              |        |
|                                               | (e) Tie-bars:                                                                                                                           |        |          |              |        |
|                                               | (i) 20 mm diameter, 900 mm long installed in new PJCP                                                                                   | number | 2 250    |              |        |
|                                               | (g) Forming and sealing the joints between asphalt and concrete pavements, Joint F, as shown on the drawing (1006614-DRG-12-VT-CC-D002) | m      | 50       |              |        |
|                                               |                                                                                                                                         |        |          |              |        |
|                                               |                                                                                                                                         |        |          |              |        |
|                                               |                                                                                                                                         |        |          |              |        |
| 7100                                          | CARRIED FORWARD                                                                                                                         |        |          |              |        |

| SCHEDULE D : ROAD CONSTRUCTION - URANIA ROAD |                                                                                                                                         |                |          | SECTION 7100 |        |
|----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|----------------|----------|--------------|--------|
| ITEM NO                                      | DESCRIPTION                                                                                                                             | UNIT           | QUANTITY | RATE         | AMOUNT |
|                                              | BROUGHT FORWARD                                                                                                                         |                |          |              |        |
|                                              | (e) Curing with emulsion wax curing compound and movable frame cover                                                                    | m <sup>2</sup> | 15 800   |              |        |
| <b>B71.05</b>                                | <b>Variation in the rate of application of the curing compounds</b>                                                                     |                |          |              |        |
|                                              | (a) White pigmented solvent resin based curing compound                                                                                 | litre          | 1 300    |              |        |
|                                              | (b) Wax based emulsion compound                                                                                                         | litre          | 790      |              |        |
| <b>B71.06</b>                                | <b>Joints:</b>                                                                                                                          |                |          |              |        |
|                                              | (b) Longitudinal hinge joints:                                                                                                          |                |          |              |        |
|                                              | (i) Sealed hinge joints, Joint B1 and Joint C, as shown on the drawing (1006614-DRG-12-UR-CC-D002)                                      | m              | 3 600    |              |        |
|                                              | (ii) Unsealed hinge joints, Joint B2, as shown on the drawing (1006614-DRG-12-UR-CC-D002)                                               | m              | 350      |              |        |
|                                              | (c) Sealed transverse contraction joints sawn in two separate operations, Joint A1, as shown on the drawing (1006614-DRG-12-UR-CC-D002) | m              | 2 850    |              |        |
|                                              | (d) Unsealed transverse contraction joints, Joint A3, as shown on the drawing (1006614-DRG-12-UR-CC-D002)                               | m              | 3 250    |              |        |
|                                              | (d) Diamond dowels with pocket formers ( <del>mild steel</del> ) (stainless steel), 20 mm x 114 mm x 114 mm:                            |                |          |              |        |
|                                              | (i) Installed in new concrete                                                                                                           | number         | 750      |              |        |
|                                              | (e) Tie-bars:                                                                                                                           |                |          |              |        |
|                                              | (i) 20 mm diameter, 900 mm long installed in new PJCP                                                                                   | number         | 7 300    |              |        |
|                                              | (g) Forming and sealing the joints between asphalt and concrete pavements, Joint F, as shown on the drawing (1006614-DRG-12-UR-CC-D002) | m              | 100      |              |        |
| <b>7100</b>                                  | <b>CARRIED FORWARD</b>                                                                                                                  |                |          |              |        |

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

**TABLE: B7102**

| Property                                                                                                                                         | Test method         | Specification                                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|------------------------------------------------|
| Tensile stress, 150 % elongation, 7-day cure at 25°C ± 2°C and from 45 % to 55 % Relative Humidity                                               | ASTM D 412 (Die C)  | 0,31 MPa max                                   |
| Flow at 25°C ± 2°C with 15 % slope channel A                                                                                                     | ASTM C 639          | must not flow from channel                     |
| Extrusion rate through 3.18mm opening at 0.62 MPa at Material temperature - 18°C                                                                 | ASTM C 603          | min 75 g/min                                   |
| Extrusion rate through 3.18mm opening at 0.62 MPa at Material temperature 38°C                                                                   | ASTM C 603          | max 250 g/min                                  |
| Relative density /Specific gravity                                                                                                               | ASTM D 792 Method A | 1.01 to 1.51                                   |
| Durometer hardness, at -18°C, Shore A, cured 7 days at 25°C ± 2°C                                                                                | ASTM C 661          | 10 to 25                                       |
| Ozone and UV resistance, after 5,000 hours                                                                                                       | ASTM C 793          | no chalking, cracking or bond loss             |
| Tack-free at 25°C ± 2°C and 45 % to 55% Relative Humidity                                                                                        | ASTM C 679          | less than 75 minutes                           |
| Elongation, 7 day cure at 25°C ± 2°C and 45 % to 55 % Relative Humidity                                                                          | ASTM D 412 (Die C)  | 500 % min.                                     |
| Set to Touch, at 25°C ± 2°C and 45 % to 55 % Relative Humidity                                                                                   | ASTM D 1640         | Less than 75 minutes                           |
| Shelf Life, from date of shipment                                                                                                                | —                   | 6 months min.                                  |
| Bond, to concrete mortar-concrete briquettes, air cured 7 days at 25°C ± 2°C                                                                     | AASHTO T 132        | 0,34 MPa min                                   |
| Movement capability and adhesion, 100 % extension at - 18°C after, air cured 7 days at 25°C ± 2°C, and followed by 7 days in water at 25°C ± 2°C | ASTM C 719          | no adhesive or cohesive failure after 5 cycles |
| Colour                                                                                                                                           |                     | Grey                                           |

The Contractor shall submit a certificate, less than six months old, from an approved testing laboratory, certifying that the sealant conforms to all the specified requirements.

The silicone sealant shall be applied by means of pumping the sealant from a storage container by means of compressed air powered pumping equipment and applied to the joint slot by means of nozzles designed to ensure that the slot is filled with sealant as indicated on the drawings. Application of the sealant into the joint slot by hand shall not be permitted.

The application of the liquid sealant shall not be undertaken when the air temperature is 5 °C or below unless otherwise specified by the manufacturer. All joints shall be clean and dry before applying the sealant and the Engineer may inspect them."

(iv) Additional materials for silicon sealant

*Add the following to this subclause:*

"The back-up material (joint former) installed in the joints and cracks shall be of the closed-cell polyethylene foam type with a minimum density of 30 kg/m<sup>3</sup>, and shall be an approved brand subject to approval by the Engineer."

**(f) Reinforcing steel, tie-bars and dowels**

*Replace the 3rd paragraph with the following:*

"Diamond dowels shall be manufactured from stainless steel (complying with the requirements of BS 970 : part 4 for steel 316S16) having a smooth finish to ¼ DIN tolerance of the DN 1013 specification."

**(g) Curing compound**

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

system which signals when the wand comes off the reference string line and locks the machine at its last position before the wand went off the wire.

After the concrete has been finished by the finishing devices incorporated in the slipform paving equipment, the surface of the concrete shall be checked by the Contractor by means of a scraping straight edge device no less than 4,0 m in length. High areas indicated by the scraping straight edge shall be removed by hand floats. The scraping straight edge shall be used with its blade in a longitudinal direction and operated transversely across the pavement with successive passes lapping the previous pass by at least half the length of the straight edge.

Following the scraping straight edge operation the final concrete surface shall be checked by the same straight edge by gently placing it in successive positions across the slab with any dragging motion. Each position shall lap a previous one by at least half the length of the straight edge."

**(e) Track support**

*Add the following paragraphs:*

"The supporting surface for the tracks of the paver alongside the slab being placed shall be carefully prepared, compacted and maintained by the Contractor in a smooth and firm condition at the proper level and grade until the paving operations have been completed.

Where the tracks of the paver will be running on newly constructed concrete, the paver shall be fitted with urethane grouser pads such that the concrete surface is not damaged in any way. Any damage caused by the paver to any final pavement layer shall be repaired at the Contractor's expense."

**B7111 PLACING, COMPACTING AND FINISHING WITH HAND EQUIPMENT**

**(d) Compacting and finishing**

*Add the following:*

"Vibration with hand vibrators shall be required adjacent to all transverse construction joints.

The bulk density determined from waxed cores in the bottom half of the PJCP pavement slab shall not vary from the density of the top half by more than 3%.

The finishing device shall be sufficient to obtain the required surface regularity as specified in subclause 7122(f)."

**B7114 CURING**

*Amend the 1st sentence of the 2nd paragraph to read as follows:*

"The curing compound shall be sprayed onto the surface at a rate of 0.35 l/m<sup>2</sup> for the White-pigmented solvent resin-based curing compound and 0.7 l/m<sup>2</sup> for the Emulsion wax curing compound or as directed by the engineer by means of a mechanical distributor capable of producing a fine fog-type of spray which will not damage the surface of the concrete."

*Add the following after the fifth paragraph:*

"The exposed surfaces should be covered by using wheeled curing tents immediately after the curing compound has been applied. The concrete shall be covered for at least 6 hours. Where the evaporation rate reaches 1,0 kg/m<sup>2</sup>/hour, the Contractor shall keep all exposed surfaces covered for

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

The unit of measurement shall be the square metre of concrete pavement placed and finished in accordance with the specification and the project specifications. The quantity shall be calculated from the net authorised dimensions, without adjustment for the allowed tolerances.

The tendered rate shall include full compensation for procuring and furnishing all the materials, storing the materials, providing all plant, determining the mix proportions, mixing, transporting, placing and finishing the concrete, including formwork, repairs done to defective work, protecting the pavement against damage, construction joints and process control.

The tendered rate shall also allow for variations in the thickness (e.g. edge thickening at joints) as shown on the drawings.

The tendered rate shall also include full compensation for constructing concrete pavements which cannot be constructed with conventional plant (i.e. varying widths), as envisaged in Section 7100."

*Replace the description of payment item 71.04 with the following:*

| <b>"Item</b>                                                                                      | <b>Unit</b>                    |
|---------------------------------------------------------------------------------------------------|--------------------------------|
| <b>B71.04 Texturing and curing the concrete pavement:</b>                                         |                                |
| (a) Broom texture (PJCP road pavements) .....                                                     | square metre (m <sup>2</sup> ) |
| (b) Bull float finish (LMC subbase) .....                                                         | square metre (m <sup>2</sup> ) |
| (c) Wood float (PJCP sidewalks) .....                                                             | square metre (m <sup>2</sup> ) |
| (d) Curing with white-pigmented solvent resin-based curing compound and movable frame cover ..... | square metre (m <sup>2</sup> ) |
| (e) Curing with emulsion wax curing compound and movable frame cover .....                        | square metre (m <sup>2</sup> ) |

| <b>Item</b> | <b>Unit</b> |
|-------------|-------------|
|-------------|-------------|

**B71.05 Variation in the rate of application of the curing compounds:**

*Add the following subitems:*

|                                                                |            |
|----------------------------------------------------------------|------------|
| "(a) White-pigmented solvent resin-based curing compound ..... | litre (l)  |
| (b) Emulsion wax curing compound .....                         | litre (l)" |

| <b>Item</b> | <b>Unit</b> |
|-------------|-------------|
|-------------|-------------|

**B71.06 Joints:**

*Replace the description of payment item 71.06(d) with the following:*

|                                                                                     |         |
|-------------------------------------------------------------------------------------|---------|
| (d) Diamond dowels with pocket formers (stainless steel), 20 mm x 114 mm x 114 mm:: |         |
| (i) Installed in new concrete .....                                                 | number" |
| (e) Tie-bars:                                                                       |         |

*Add the following items after item 71.06(h):*

FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS  
TNPA/2025/06/0004/99874/RFP

## **SECTION B8100: TESTING MATERIALS AND WORKMANSHIP**

### **B8102 TESTING METHODS**

*Insert the following as a new first paragraph:*

"Where reference is made to TMH test methods in this specification or the standard specifications, it shall be replaced with the relevant current published SANS test method."

### **B8103 THE COSTS OF TESTING**

*Replace subclause B8103(a) with the following:*

#### **"(a) Materials quality control**

Testing shall be undertaken by a combined laboratory facility for process control (where the process control testing can be utilised as acceptance control), acceptance control and correlation testing subject to the following requirements laid down by the Employer:

- (i) The Contractor accepts the test results of the combined laboratory. Should there be any doubts with regard to certain test results, this will be settled by an independent laboratory mutually agreed upon. The cost in such cases will be to the account of the party at fault. The Contractor shall apply in writing, quoting this clause, as to which specific tests are in doubt, providing test reference numbers and details as to the reasons why the test result is in doubt.
- (ii) The Contractor accepts that the Engineer will be in charge of the combined laboratory.
- (iii) The Contractor will be allowed to place a permanent representative in the combined laboratory to observe the laboratory operations. The cost of such representation cannot be claimed as a payment contribution towards payment item B81.04, but will be for the account of the Contractor. The Contractor shall indicate in writing within 14 days of the commencement date if such representation will be required or declined.

The total cost of the combined laboratory for the **fifteen** month **construction** period has been estimated at R 6,000,000.00.

The estimated cost per month to establish and operate the combined laboratory for the contract period as listed above, allows for the following items:

- establishment of laboratory buildings
- salaries and labour for all laboratory staff members
- housing for all laboratory staff members
- transport requirements (based on distance) for staff and material testing
- provision of laboratory equipment (as required for the contract)

A payment item for the monthly contribution from the Contractor's interim payment certificates has been provided under payment item B81.04."

*Amend the heading of clause 8106 to read as follows:*

#### **"B8106 TESTING THE CONCRETE AND COVER TO STEEL REINFORCEMENT"**

*Add the following subclauses:*



**Transnet National Ports Authority**

an Operating Division of **TRANSNET SOC LTD**

[Registration Number 1990/000900/30]

**REQUEST FOR PROPOSAL (RFP)**

**FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE  
ONE: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA  
CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18  
MONTHS**

|                                             |                                                       |
|---------------------------------------------|-------------------------------------------------------|
| <b>RFP NUMBER</b>                           | <b>: TNPA/2025/06/0004/99874/RFP</b>                  |
| <b>ISSUE DATE</b>                           | <b>: 29 AUGUST 2025</b>                               |
| <b>COMPULSORY CLARIFICATION<br/>MEETING</b> | <b>: 08 SEPTEMBER 2025</b>                            |
| <b>CLOSING DATE</b>                         | <b>: <del>30 SEPTEMBER 2025</del> 06 October 2025</b> |
| <b>CLOSING TIME</b>                         | <b>: 16h00</b>                                        |
| <b>TENDER VALIDITY PERIOD</b>               | <b>: 12 WEEKS FROM CLOSING DATE</b>                   |



TRANSNET NATIONAL PORTS AUTHORITY

CONTRACT NUMBER: TNPA/2025/06/0004/99874/RFP

DESCRIPTION OF THE WORKS: FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE 1: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS

|                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|---------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                     | <p><b>A Site visit/walk will take place, tenderers are to note:</b></p> <ul style="list-style-type: none"> <li>• Tenderers are required to wear safety shoes, goggles, long sleeve shirts, high visibility vests and hard hats.</li> <li>• Tenderers without the recommended PPE will not be allowed on the site walk.</li> <li>• Tenderers and their employees, visitors, clients and customers entering Transnet Offices, Depots, Workshops and Stores will have to undergo breathalyser testing.</li> <li>• All forms of firearms are prohibited on Transnet properties and premises.</li> <li>• The relevant persons attending the meeting must ensure that their identity documents, passports or driver's licences are on them for inspection at the access control gates.</li> </ul> <p>Certificate of Attendance in the form set out in the <b>Returnable Schedule T2.2-01</b> hereto must be completed and submitted with your Tender as proof of attendance is required for a <b>compulsory</b> site meeting and/or tender briefing.</p> <p><b>Tenderers are required to bring this Returnable Schedule T2.2-01 to the Compulsory Tender Clarification Meeting to be signed by the Employer's Representative.</b></p> <p><b>Tenderers failing to attend the compulsory tender briefing will be disqualified.</b></p> |
| <b>CLOSING DATE</b> | <p><b>16h00 on <del>30 September 2025</del> 06 October 2025</b></p> <p>Tenderers must ensure that tenders are uploaded timeously onto the system. <b>No late tender submissions will be accepted.</b></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |

## 2. TENDER SUBMISSION

Transnet has implemented a new electronic tender submission system, the e-Tender Submission Portal, in line with the overall Transnet digitalization strategy where suppliers can view advertised tenders, register their information, log their intent to respond to tenders and upload their tender proposals/responses on to the system.

a) The Transnet e-Tender Submission Portal can be accessed as follows:

Log on to the Transnet eTenders management platform website (<https://transnetetenders.azurewebsites.net>).

- Click on "ADVERTISED TENDERS" to view advertised tenders;
- Click on "SIGN IN/REGISTER – for tenderders to register their information (must fill in all mandatory information);



TRANSNET NATIONAL PORTS AUTHORITY

CONTRACT NUMBER: TNPA/2025/06/0004/99874/RFP

DESCRIPTION OF THE WORKS: FOR THE PROVISION OF THE PORT ROAD UPGRADE AND REHABILITATION PHASE 1: UPGRADE AND REHABILITATION OF URANIA, NEWARK, AND VENTURA CONCRETE ROADS WITHIN THE PORT OF RICHARDS BAY FOR A PERIOD OF 18 MONTHS

---

C.2.12 No alternative tender offers will be considered.

---

C.2.13.3 Each tender offer shall be in the **English Language**.

---

C.2.13.5 The *Employer's* details and identification details that are to be shown on each tender offer are as follows:

Identification details:

---

C.2.13.9 Telephonic, telegraphic, facsimile or e-mailed tender offers will not be accepted.

---

C.2.15 The closing time for submission of tender offers is: Time: **16h00** on the

**30 September 2025 06 October 2025**

Location: The Transnet e-Tender Submission Portal: (<https://transnetetenders.azurewebsites.net/>); **NO LATE TENDERS WILL BE ACCEPTED**

---

C.2.16 The tender offer validity period is **12 weeks** after the closing date. Tenderers are to note that they may be requested to extend the validity period of their tender, on the same terms and conditions, if Transnet's internal evaluation and governance approval processes has not been finalised within the validity period.

---

C.2.23 The tenderer is required to submit with his tender:

1. A valid Tax Clearance Certificate issued by the South African Revenue Services.  
**Tenderers also to provide Transnet with a TCS PIN to verify Tenderer's compliance status.**
2. A **valid B-BBEE Certificate** from a Verification Agency accredited by the South African Accreditation System [**SANAS**], or a **sworn affidavit** confirming annual turnover and level of black ownership in case of all EMEs and QSEs with 51% black ownership or more together with the tender;
3. A valid CIDB certificate in the correct designated grading;
4. Proof of registration on the Central Supplier Database;
5. Letter of Good Standing with the Workmen's compensation fund by the tendering entity or separate Letters of Good Standing from all members of a newly constituted JV.

**Note:** Refer to Section T2.1 for List of Returnable Documents

---

C3.11 Only tenders that achieve the minimum qualifying score for functionality will be evaluated further in accordance with the 90/10 preference points systems as described in the Preferential Procurement Regulations.