

**TENDER NUMBER: TNPA/2024/11/0006/82453/RFP**  
**FOR THE: REHABILITATION OF THE SHIP REPAIR FACILITY IN THE PORT OF MOSSEL BAY FOR A PERIOD OF TWENTY-FOUR (24) MONTHS**  
**REQUEST FOR INFORMATION**

**RFI No.** 4      **Date:** **Friday, 09 January 2026**      **Company:** **H&I**

Query No.	Applicable section in tender documents	Page	Section / Item No	Information Required	TNPA Response
1	Part C3	Page 21 of Part C3	Page 21 of Part C3, item 7	<ul style="list-style-type: none"> <li>Rebuild the section of the slipway concrete beams between the transition point where the beams enter the water to the start of the slipway under the water. Only the superstructure shall be rebuilt on top of the existing pile support structure. Drawing 1002-011-3012 also indicates that the whole slipway above and below water get demolished and replaced. Item 1.3 on page 10 of Part C3 also indicates that the slip way must be completely constructed as per the construction drawing provided. At the site inspection it was mentioned that only the portion above water will be rehabilitated.</li> </ul>	The Contractors scope includes for a structural dive survey and assessment to be completed and the assessment report and findings presented to the Client for their approval. This report shall clarify the extent of the scope of replacement or rehabilitation. This is because the previous structural assessment was completed more than 5 years ago and it could be contemplated that further degradation could have occurred during that time
				Clarify the following: 1. What beams must be replaced? Only the above water concrete beams or all the beams above and below water as per the drawing and specification?	Refer Item 1 above
				2. Does all the Rails have to be replaced above and below water ?	Yes
				3. Under what BOQ item must the Beams for the slipway be priced as no BOQ item is provided for any work on the Slipway beams above or below water.	Item 41
				4. Does the Wire cable support get replaced only above water or does it get replaced for the whole slip way including below water as per drawing 1002-001-4000? Where must his be priced in the BOQ?	For the whole slipway length
				5. If only portion above water must be replace then the scope needs to be clearly defined up to what grid line it must be reconstructed in terms of drawing 1002-011-3012.	Refer to 4 above