

ANNEXURE C3.2: SCOPE OF WORK

A) Do the following work on the below listed No.4 Valves in front of Engine room no.4 at Rand Water Zuikerbosch Water Treatment Plant.

- a) Supply and deliver 965mm x 965mm 1225mm brown tinted safety glass (6.2mm) thick.
- b) Glasses to be joined together with industrial clear glass glue to form a pyramid shape.
- c) A pyramid to be mounted on an aluminium base (1245mm x 1245mm) square.
(Casement 30.5) (Silver Colour).
- d) All pyramids and their base to be clamped on the existing steel frames.
- e) All loose galvanized steel frames to be mounted on the concrete slab.

All the above work to be done on the following areas.

- 1. Zuikerbosch Safety File costs.
- 2. Stand-alone valve on None return and the delivery sites.
- 3. Pump set no.27 None return and the delivery sites.
- 4. Pump set no.28 None return and the delivery sites.
- 5. Pump set no.29 None return and the delivery sites.
- 6. Pump set no.30 None return and the delivery sites.
- 7. Pump set no.31 None return and the delivery sites.
- 8. Pump set no.32 None return and the delivery sites.
- 9. Pump set no.33 None return and the delivery sites.
- 10. Pump set no.34 None return and the delivery sites.
- 11. Pump set no.35 None return and the delivery sites.
- 12. Pump set no.36 None return and the delivery sites.
- 12. Aluminium bases for all skylights (Casement 30.5) (Silver Colour).

Aluminium profile bases pictures



Pyramids Picture



ANNEXURE C4: SITE INFORMATION

Rand water Zuikerbosch

Vischagat Road, 3 Rivers East

Vereeniging, 1939

GPS Coordinates: S 26° 41.520 and E 28° 00.061

Successful supplier must submit safety file and attend induction before work commences.

Wearing of safety shoes or boots is compulsory when working on site. Access to the plant will be denied to person/s not wearing safety shoes