

TERMS OF REFERENCE

1. Background

Umngeni-Uthukela Water requires a service provider to reinforce and leak seal the raw water abstraction chamber at Mkondeni.

2. Deliverables/Key Outcomes.

3.1. The work shall cover the following:

- Supply and delivery of complete concrete sealing materials (preferably SIKA product)
- Supply, delivery and installation of concrete ring
- Diversion of river flow
- Sealing of existing chamber

3. Contract term

We anticipate that the contractor will commence after the signing of the contract.

4. Other information

- a) We require the goods / services to be delivered at 7 Portland Road, Mkondeni, Pietermaritzburg, 3201.
- b) Payment will be on 30 days on invoice.

5. Mandatory documentation/requirements

- a) Bidder completed all RFQ Forms
- b) Bidder registered on National Treasury CSD
- c) SBD 4 – Bidders disclosure

6. Pricing

- a) The bidder shall provide the price proposal as detailed in SBD 3.1
- b) The bidders's price must be fully inclusive, and each item must be clearly specified.
- c) All additional costs must be clearly specified and included in the total quotation price, (e.g. transport, labour, etc.).
- d) All prices must be VAT inclusive.
- e) The bidder is responsible for all the cost that they shall incur related to the preparation and submission of the quotation.

BOQ

Item no.	QUANTITY	DESCRIPTION	UNIT OF MEASURE	UNIT PRICE PER M/ UNIT EXCL. VAT (B)	QUOTED PRICE(AXB) EXCL. VAT
1.	20l	Supply and deliver Sika Primer 3N	ea		
2.	20	Supply and deliver Sikaflex Pro 3i-cure	L		
3.	50kg	Supply and deliver Sika Grout 212	ea		
4.	60m	Supply and deliver Sikadur Combiflex Bandage	/m		
5.	10l	Sikadur 31 DW Comp A	ea		
6.	10l	Sikadur 31 DW Comp B	ea		
7.	1	Supply and deliver 2.3mx2.3mx0.5m precast square ring (0.15m thick)	Ea		
8.	100	Divert river flow	m ³		
9.	6	Ream open all precast ring joints (inside and outside)	Ea		
10.	6	Apply Sika Primer 3N to all joints	Ea		
11.	6	Apply Sikaflex Pro 3i-cure to all joints	Ea		
12.	48	Apply Sika Grout 212 to all lift ring holes	Ea		
13.	1	Install additional pre-cast ring and seal	Ea		
14.	6	Cover all joints using the Sikadur Combiflex Bandage System	Ea		
15.	48	Cover all holes using Sikadur Combiflex Bandage System	Ea		
16.	1	Seal sluice gate with Sikadur Combiflex Bandage System	Lot		
17.	1	Fabricate and install access cat ladder	Lot		
	1	10% Contingency	Sum		