

## Pricing Schedule

Project: Supply, Installation & Commissioning of Two (2) 18,000 BTU Air-conditioners – KDS Control Room

Location: Transnet Engineering, Koedoespoort

Contract Type: NEC ECC (Turnkey – Activity Schedule)

Activity No.	Activity Description	Deliverable / Completion Criteria	Cost (Rands)
1	Contract award & mobilisation	Signed contract, approved safety file, induction completed	
2	Site inspection & preparation	Site handover, risk assessment, measurement & marking completed	
3	Supply of equipment & materials	Delivery of 2 x 18,000 BTU air-conditioners, electrical components, and consumables to site	
4	Installation of air-conditioners	Units mounted (indoor & outdoor), refrigerant piping, drainage, cabling, and isolators installed	
5	Electrical installation & compliance	DB board breaker installed, wiring, conduit, labeling, and preliminary inspection completed	
6	Testing of system	Pressure testing, leak testing, load testing, and temperature control verified	
7	Commissioning & certification	Systems commissioned in presence of Transnet, COC & compliance certificates handed over	
8	Handover & training	Operator training, O&M manuals, snag list closed, final handover signed	
<b>Total project cost</b>			