

Private Bag X06
 Honeydew
 2040

To whom it may concern

You are hereby invited to submit a quotation for the delivery of the following goods / services as listed / stated below:

Nelspruit T106 Replace Mast Ladder and Handrail: Scope of work for design, manufacture, supply and replacing rusted Mast ladder and Handrail with similar material

Nelspruit T106: Replacement of Mast ladder and Handrail					
No	Item Description	Unit	Qty	Rate	Total
	MAST WORKS Notes to bidders: Bidders must visit the site to acquaint themselves with the type of work to be carried out before any work can resume. It is COMPULSORY that the service provider take the correct measurements on site before any manufacturing work can be done. A health and safety file and methodology will be required and including accredited riggers who are eligible to climb the mast. Materials specification: the ladder must be hot dipped galvanized SABS approved - All galvanizing to comply with SANS 121 and SANS 14713 and 763				
1	PRICING SCHEDULE				
	Preliminary and General				
1.1	Site establishment for mast works	Item	1		
1	MAST INFORMATION	No:	1	R	

Directors: (NED & Chairperson) Sandile Malinga, (NED) Mabasa Metuse, (NED) Motse Mfuleni, (NED) Precious Sibiyi CA (SA), (NED) Malande Tonjeni CA (SA), (NED) Mxolisi Tsika, (NED) Buyelwa Tunyiswa, (ED & CEO) Mlamli Boo, (ED & Acting CFO) Komathie Govender CA (SA), & (ED & COO) Tebogo Leshope.

Company Secretary: (Acting) Makhotsa Portia Chimombe
SENTECH SOC Ltd Reg no: 1990/001791/30

	4900mm Long cat ladder made of 48 x 3mm CHS stringers, 30 x 5mm flat bar hoops 5No-of at 550mm c/c, 16mm diameter round bar verticals and 16mm diameter round bar rungs like the existing one on site. NB: The sizes needs verifications before manufacture. ➤ From 2nd Guy-rope ➤ Between platform 7th and 8th ➤ Middle cat- ladder = 4.90 m			
2	One Hand- rails above first guy-rope at platform No.4 between Anchor-block B and C. HANDRAIL INFORMATION The HDG and the tube handrail system is a standard system. All stanchions, bends, closures, hand and knee rails and accessories can be sourced as loose components as required from site measure-up. Stanchion attachment details (side to top mount) should be confirmed from site measure-up or have stanchion attachments made to match what you have on site. Length = 2.40m/Stanchion = 1.30m long/Steel pipe diameter = Ø 140mm/Knee width = 80mm – Length = 200mm/Bolt to Bolt = 110mm and Bolt size = M16 - 55mm	No:	1	
3	The ladder and the handrail to be painted like each section with three coats (Primer-grey, Intermediate coat and final coat) • PRIMER COAT (must be able to bond to galvanizing) • INTERMEDIATE COAT (200 Base Grey) • FINAL COAT (Signal Red and White)			
	Subtotal Carried forward to summary page			R

No	Item Description	Total
----	------------------	-------

Directors: (NED & Chairperson) Sandile Malinga, (NED) Mabasa Metuse, (NED) Motse Mfuleni, (NED) Precious Sibiyi CA (SA), (NED) Malande Tonjeni CA (SA), (NED) Mxolisi Tsika, (NED) Buyelwa Tunyiswa, (ED & CEO) Mlamli Boo, (ED & Acting CFO) Komathie Govender CA (SA), & (ED & COO) Tebogo Leshope.

Company Secretary: (Acting) Makhotsa Portia Chimombe
SENTECH SOC Ltd Reg no: 1990/001791/30

	MAST WORKS	
2	Preliminary and General	R
1	Mast ladder	R
1	Handrail	R
Total		R
Total excluding VAT		R
VAT (14%)		
Total including VAT		R

SPECIAL CONDITIONS

- Permission granted to stay on site in tents (to be verified with OC Manager and the Farmer)
- Provide own food & water
- Provide own portable toilet from 1st day of site establishment
- Provide own power
- No sub-contracting of work
- All material must be SABS approved
- Remove all rubble & waste off site
- No chemical spillage on farmer's land
- Sentech will not be held liable for bad weather
- Duration not more than **30** working days
- Initial and final hand over to be attended by site Supervisor / Manager / Business owner
- No fires on site
- Supplier's specifications to be adhered to at all time.
- Working hours – to be confirm by Operations Manager JHB
- Provision to allow Sentech vehicles for emergency work – as discussed at site meeting
- **Quotes to be forward to SCM at Sentech on the deadline simultaneously, otherwise it would lead to automatic disqualification.**

Yours faithfully

Tel: (011) – 471 4400

Directors: (NED & Chairperson) Sandile Malinga, (NED) Mabasa Metuse, (NED) Motse Mfuleni, (NED) Precious Sibiyi CA (SA), (NED) Malande Tonjeni CA (SA), (NED) Mxolisi Tsika, (NED) Buyelwa Tunyiswa, (ED & CEO) Mlamli Boo, (ED & Acting CFO) Komathie Govender CA (SA), & (ED & COO) Tebogo Leshope.

Company Secretary: (Acting) Makhotsa Portia Chimombe
SENTECH SOC Ltd Reg no: 1990/001791/30

Directors: (NED & Chairperson) Sandile Malinga, (NED) Mabasa Metuse, (NED) Motse Mfuleni, (NED) Precious Sibiyi CA (SA), (NED) Malande Tonjeni CA (SA), (NED) Mxolisi Tsika, (NED) Buyelwa Tunyiswa, (ED & CEO) Mlamli Boo, (ED & Acting CFO) Komathie Govender CA (SA), & (ED & COO) Tebogo Leshope.

Company Secretary: (Acting) Makhotsa Portia Chimombe
SENTECH SOC Ltd Reg no: 1990/001791/30