SPECIFICATION FOR ELECTRIFYING TC UTILITIES

ITEM	unit	Total
Supply and install 10mm² x 100m 4-core & Earth round cable		
Supply and install 4x4 waterproof box slide type x8		
Supply and install 4mm² 4 core & earth round cable X50m		
40A 5-pin industrial female plug + male X9		
Supply and install single phase earth leakage X2		
Supply and install DB box 30 mode with 4 neutral bars and earth bar extension type DB X2		
Supply and install 60A 3-phase circuit breaker 5ka 4 pole X 4 Schneider electric		
Supply and install 40A 3-phase circuit breaker x8 Schneider electric		
Supply and Install double socket outlets X 8 craptree		
Supply and install 20A circuit breaker X8 Schneider electric		
Supply and install Surge arrest 4-pole X2 Schneider electric		
Supply and install 2m of 3-phase busbar DIN rail		
Supply and install 2m of single phase busbar DIN rail		
Supply and install 150m cable tray		
30mm² compression glands PVC X10		
20mm² compression gland PVC X20		
63A 3-phase CBI 5ka 4 pole cbi X2		
4x2 PVC extension box with cover X10		
Supply and install Earth bar inside 4X2 extension box X10		
10mm green & yellow Earth wire 50m		
Labeling book x1		
Supply and install db blanks X30		
Removing the existing UPS from block H and connect to TC LAB		
Supply and install 2.5mm² twin and earth round cable x 50m		
6x 50mm fisher plugs x100		
Supply a certificate of compliance X2		
VAT		
GRAND TOTAL		