

BILL 01: A Proposed Storage House Project at Randwater Central Depot - Preliminary and General					
Item	Description	MoU	Qty	Rate	Total
FIXED CHARGE ITEMS					
1,0	The Contractor shall establish the site camp and maintain throughtout the construction period and allow for removal of such upon completion of works				
1,1	Office and Meeting Room complete as per P & G's Guideline	sum	1	R -	R -
1,2	Sanitation	sum	1	R -	R -
1,3	Electricity	sum	1	R -	R -
1,4	Construction Signboard	sum	1		R -
2,0	Safety & Health, Environmental				
2,1	Compliance with OG & S Act & Construction Regulations	sum	1		R -
3,0	Comply, maintain all insurance and statutory contributions, etc.				
3,1	Allowance to comply, maintain all insurance and statutory constructions, etc. (This lump sum shall be devided and paid in accordance to the number of months allocated to the project)	sum	1		R -
TIME RELATED ITEMS					
1,0	Maintain site office and meeting room complete as per P & G's guideline	Month	3	R -	R -
2,0	Water	Month	3	R -	R -
3,0	Sanitation (Services)	Month	3	R -	R -
4,0	Electricity	Month	3	R -	R -
5,0	Site De-Establishment	sum	1		R -
6,0	Supply or hire specialist equipment for the detection of underground services over and above services detected in the drawings	sum	1		R -
7,0	Security on site	Month	3	R -	R -
8,0	Supervision of the works	Month	3		R -
9,0	Community Liason Officer	Month	3		R -
10,0	Environmenta Officer	Month	3		R -
11,0	Quality Officer	Month	3		R -
12,0	Safety Officer	Month	3		R -
					R -

BILL 02: A Proposed Storage House at Randwater Central Depot - Construction					
SN	Description	MoU	Qty	Rate	Total
1,0	SITE PREPARATION & EARTHWORK				
1,1	Site clearance and topsoil removal	sum	1		R -
1,2	Formation compaction to subgrade (including watering and compaction	sum	1		R -
1,3	G5 Subbase - 300mm thick (2 layers of 150mm)	m ³	96		R -
1,4	Blinding concrete - 30mm over the entire area	m ³	10		R -
1,5	DPC - heavy duty plastic membrane (laid over the building)	sum	1		R -
2,0	FOUNDATIONS & RC PILLARS				
2,1	RC pillars - (300 x 300 x 700) includes reinforcement, formwork and concrete	no	22		R -
2,2	Steel poles (supply, galvanized/paint, installation & leveling) - 500mm	no	22		R -
3,0	CONCRETE FLOOR SLAB				
3,1	Concrete floor slab - 200mm thick on DPC	m ³	64		R -
4,0	MASONRY & WALLS				
4,1	Concrete block wall - 4 courses (0.8m high) around perimeter - measured as	m ²	68		R -
5,0	DOORS & OPENINGS				
5,1	Sliding steel doors (sized for each compartment)	no	4		R -
6,0	ROOFING & RAINWATER GOODS				
6,1	Roof covering, purlins/trusses, insulation (if any) and rainwater goods - roof	m ²	320		R -
7,0	EXTERNAL CLADDING (LOUVRES) & INTERNAL PARTITIONS				
7,1	External metal sheet louvre cladding above block wall to top of poles	m ²	270		R -
7,2	Internal wire-mesh partitions (3 partitions x 10.0m long x 3.2m high)	m ²	96		R -
8,0	FLOOR FINISH				
8,1	Final rough wooden floated floor screed 30mm over the entire slab area	m ²	320		R -
9,0	STORMWATER & DRAINAGE				
9,1	Drainage and stormwater control around structure - gullies, channel,	sum	1		R -
					R -

SUMMARY: THE GROSS TOTAL COST OF THE NEW STORAGE HOUSE CONSTRUCTION		
A Proposed New Storage House at Randwater central Depot		
Page No	Description	Amount
1	BILL 01 : Preliminary and Genarals	R -
2	BILL 02 : Construction of the Proposed New Storage House at Randwater central depot	R -
Sub Total 01		R -
VAT (15%)		R -
Gross Total Inclusive		R -