

CONTRACT: 44Q/2025/26

BILL OF QUANTITIES

BILL: C ROADWORKS

SECTION: C6 ANCILLARY ROADWORKS

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
C6.1	SANS 1200 MM	PERMANENT ROAD SIGNS				
		Statutory signs supplied and erected complete on 80mm diameter galvanised steel supports:				
C6.1.1	8.3.6	i) 600mm Type R1 Stop Sign	No	63		
C6.1.2	8.3.6	ii) 600mm Type R2.1 Sign	No	0		
C6.1.3	8.3.6	iii) 600mm Type W332 and IN11.1 combined	No	64		
C6.1.4	8.3.6	iv) 600mm Type W401	No	64		
C6.1.5	8.3.6	v) 600mm Type W402	No	64		
C6.1.6	8.3.6	vi) 600mm Type W306	No	0		
		Construction of speed hump as per drawing 25-CCT-017/G708/00 complete, including saw cutting, breaking out & remove existing, tack coat & asphaltting for:				
C6.1.7		Speed hump with a 5.0m road width	No	19		
C6.1.8		Speed hump with a 5.5m road width	No	7		
C6.1.9		Speed hump with a 7.4m road width	No	5		
C6.2		STREET NAME KERBS				
C6.2.1	8.3.6	Street Name Kerb Details as per drawing 25-CCT-017/G702/00	No	104		
C6.3		ROAD MARKINGS				
		Non-reflectorized paint applied at nominal rate of 0,42 l/m2 for:				
		a) White lines (broken or unbroken)				
C6.3.1	8.4.1	i) 100mm wide	m	1020		
C6.3.2	8.4.1	iii) 300mm wide	m	720		
C6.3.3	8.4.1	iv) RTM11 'Zig-zag'	m	0		
C6.3.4	8.4.1	b) Yellow characters and symbols	m²	66		
C6.3.5	8.4.1	c) White characters and symbols	m²	616		
TOTAL FOR SECTION C6 CARRIED FORWARD TO SUMMARY						