



agriculture, land reform & rural development

Department:
Agriculture, Land Reform and Rural Development
REPUBLIC OF SOUTH AFRICA

Contract No.: DALRRD-RID-FS-001 (2024/2025)

A Tender for Category 6 CE or higher CIDB Registered Contractors

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

Name of Tenderer : _____

Name of duly authorised person : _____

Address : _____

Tel. Number : _____

Cell number : _____

Fax number : _____

E-mail : _____

Receipt number : _____

ISSUED BY:

Chief Director: Supply Chain Management Services
DEPARTMENT OF AGRICULTURE, LAND REFORM
AND RURAL DEVELOPMENT
Private Bag X 4376
Bloemfontein
9300

Tel: (051) 400 4200
Fax: (051) 430 2392

PREPARED BY:

DURAPI CONSULTING (PTY) LTD
Homestead Office Park
37 Homestead Road
Rivonia
Sandton
2128

Tel: (011) 312 8629/8599
Fax: (011) 312 8638



agriculture, land reform & rural development

Department:
Agriculture, Land Reform and Rural Development
REPUBLIC OF SOUTH AFRICA

CONTRACT NO.: DALRRD-RID-FS-001 (2024/2025)

THE TENDER

FOR THE

**APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING
OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER
MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.**

CLOSING DATE: 13 DECEMBER 2024

CLOSING TIME: 11h00

ISSUED BY:

Chief Director: Supply Chain Management Services
DEPARTMENT OF AGRICULTURE, LAND REFORM
AND RURAL DEVELOPMENT
Private Bag X 4376
Bloemfontein
9300

Tel: (051) 400 4200
Fax: (051) 430 2392

PREPARED BY:

DURAPI CONSULTING (PTY) LTD
Homestead Office Park
37 Homestead Road
Rivonia
Sandton
2128

Tel: (011) 312 8629/8599
Fax: (011) 312 8638

CHECKLIST WHEN SUBMITTING BID PROPOSAL/DOCUMENT FOR THE

☐

Contractor

☐

Witness 1

☐

Witness 2

☐

Employer

☐

Witness 1

☐

Witness 2

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

ENSURE THAT PRIOR TO SUBMITTING THE TENDER TO THE DEPARTMENT THE FOLLOWING INFORMATION IS COMPLETED AND ATTACHED.

Submissions will only be considered for acceptance (regarded as being responsive) if the below mentioned requirements were met:

Please indicate YES or NO ✓ Place a Tick in the appropriate column	YES	NO
a) <u>Evaluation for mandatory criteria</u> Only those respondents who are registered with the Construction Industry Development Board or are capable of being so registered within twenty- one (21) working days from the closing date for submission of tenders, in a contractor grading designation of 6CE or Higher class of construction works are eligible to have their submissions evaluated. Joint ventures are eligible to have their submissions evaluated provided that: 1. Every member of a joint venture is registered with the CIDB not later that twenty-one (21) working days from the closing date for tenders. 2. The lead partner has a contractor grading designation in the CE class of construction work; or not lower than one level below the required grading designation in the class of works (CE) construction works under considerations and possess the required recognition status. 3. The combined contractor grading designation calculated in accordance with the Construction Industry Development Regulations is equal to or higher than the required contractor grading designation. Respondents are also requested to indicate their CRS number/s of the registered contractor/s as well as their Joint Venture partner/s (if applicable) in the document.		
Signed Letter of authority on Company Letterhead is attached. <u>Letter of authorisation</u> to sign the submission and where required in tender document. In the case of a <u>one-person</u> concern submitting a tender, this shall be clearly stated on the letter head. In the case of a <u>JOINT VENTURE</u> submitting a tender, include a resolution of <u>each company</u> of the Joint Venture <u>together</u> with a resolution by its members authorising a member of the Joint Venture to sign the documents on behalf of the Joint Venture." i.e. the <u>Joint Venture must submit three Letters</u> of Authority as per the aforesaid Joint Venture requirement.		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Respondent's will be accredited for Free State Province and will be required to demonstrate physical presence within Free State Province by providing one of the following: • a valid municipal services account (water, sanitation, rates and electricity) in the name of the bidder/s or active director/s not older than 6 months from the closing date of the bid <u>or</u> • a valid lease agreement from the lessor <u>or</u> • a letter on the letterhead of the ward councilor/traditional authority/council that must be signed, stamped and dated and must not be older than 6 months from the closing date of the bid.		
<u>Letter of good standing from Department of Labour (COIDA)</u> The respondent is registered and in good standing with respect to Compensation for Occupational Injuries and Diseases Act (COIDA) with Department of Labour or with a licensed compensation insurer. The respondent must submit the letter of good standing. In the event of the respondent being a joint venture/consortium, the letter of good standing of the individual members must also be provided.		
<u>FORM J: Key-personnel/ Supervisory and Management Staff:</u> The Tenderer shall submit/indicate the names of all management and supervisory staff that will be employed to supervise the contract. Please attach CV's and certified copies of qualifications of the proposed key personnel.		
Attendance of a compulsory clarification meeting		
Are all addenda issued completed and returned (if applicable)		

Note: Any submission not complying with the above-mentioned stipulation, will be regarded as non-responsive and will therefore not be considered for further evaluation.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

DOCUMENT LAYOUT

SECTION	HEADING	COLOUR
PART 1: THE TENDER		
PART T1	TENDERING PROCEDURES SECTION T1.1: TENDER NOTICE AND INVITATION TO TENDER SECTION T1.2: TENDER DATA	WHITE PINK
PART T2	RETURNABLE DOCUMENTS SECTION T2.1: LIST OF RETURNABLE DOCUMENTS SECTION T2.2: RETURNABLE SCHEDULES	YELLOW YELLOW
PART 2: THE CONTRACT		
PART C1:	AGREEMENT AND CONTRACT DATA SECTION C1.1: FORM OF OFFER AND ACCEPTANCE SECTION C1.2: CONTRACT DATA SECTION C1.3: CONSTRUCTION GUARANTEE (PRO-FORMA) SECTION C1.4: OCCUPATIONAL HEALTH AND SAFETY AGREEMENT BETWEEN EMPLOYER AND CONTRACTOR	YELLOW YELLOW WHITE WHITE
PART C2:	PRICING DATA SECTION C2.1: PRICING INSTRUCTIONS SECTION C2.2: BILLS OF QUANTITIES	YELLOW YELLOW
PART C3:	SCOPE OF WORKS SECTION C3.1: DESCRIPTION OF WORKS SECTION C3.2: ENGINEERING SECTION C3.3: PROCUREMENT SECTION C3.4: CONSTRUCTION SPECIFICATION SECTION C3.5: PARTICULAR SPECIFICATIONS SECTION C3.6: DRAWINGS	BLUE BLUE BLUE BLUE BLUE GREEN
PART C4:	SITE INFORMATION SECTION C4.1: SITE LOCALITY PLAN SECTION C4.2: ACCESS TO SITE	WHITE WHITE
PART C5:	ANNEXURES APPENDIX A: TENDER DRAWINGS	WHITE

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

THE TENDER

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

TABLE OF CONTENTS.

Reference

Volume 1:

THE TENDER.....	2
PART T1: TENDERING PROCEDURES	4
Section T1.1: Tender Notice and Invitation to Tender	White 5-7
Section T1.2: Tender Data	Pink 8
Section T1.2.1: Conditions of Tender	Pink 8
Section T1.2.2: Tender Data	Pink 8-21
Section T1.2.3: CIDB Standard Conditions of Tender	White 22-37
PART T2: RETURNABLE DOCUMENTS.....	38
Section T2.1: List of Returnable Documents	Yellow..... 39-42
Section T2.2: Returnable Schedules	Yellow..... 43-107

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

SECTION T1.1: TENDERING PROCEDURES

For a proposed contract between **DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT**
(the Employer)

and

(the Contractor)

for **APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.**

Documentation prepared by:

**DURAPI CONSULTING (PTY) LTD
FOR.
DEPARTMENT OF AGRICULTURE, LAND REFORM
AND RURAL DEVELOPMENT (RID-FS).**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

SECTION T1.2: TENDER NOTICE AND INVITATION TO TENDER

FOR:

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

CONTRACT/TENDER NO.: DALRRD-RID-FS-001 (2024/2025)

INVITATION AND SCOPE OF WORK:

The proposed works consist, in general terms,

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

CONDITIONS: Bidders shall be registered with the Construction Industry Development Board (CIDB) and should have a minimum CIDB Contractor grading of **6CE** or higher.

Preferential Procurement Policy Framework Act (PPPFA), Act no. 5 of 2000 and its associated Regulations of 2022. The **80/20** Preference Point system will be applied where a maximum of Eighty (80) tender adjudication points will be awarded for price and Twenty (20) points will be awarded for specific goals.

Bid documents shall be made available on the **21 NOVEMBER 2024**, from one of the offices listed below during the following hours: Monday to Friday 08h30 to 12h45 and 13h30 to 16h00. No documents will be available or issued at the Briefing Session and should, therefore, be collected timeously beforehand.

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT:

Mrs Sibongile Mankahla
136 Charlotte Maxeke Street
SA Eagle Building
Bloemfontein
9300
Tel: (051) 400 4200

A non-refundable bid fee of **R 250, 00** (Two hundred rand) per set of documents, is payable by cash only.

A Compulsory Tender Briefing/ Site Inspection meeting will be conducted **on site, bidders will meet at the Barolong Tribal Council Offices** and thereafter proceed to site in Sediba Village (Thaba Nchu) at **11H00 on 29 November 2024**. **Closing date and time** for the receipt of completed bid documents are **13 DECEMBER 2024 at 11h00**.

NB: ATTENDANCE REGISTER WILL BE CIRCULATED ON SITE WHICH IS IN SEDIBA VILLAGE (+/- 20KM AWAY FROM BAROLONG TRIBAL COUNCIL) WHERE THE ACTUAL BREIFING WILL BE HELD.

Tenders must remain valid for a period of **90 Calendar Days** and **120 Calendar Days** for tenders closing in October, November and December; after the closing date for the submission of tenders, during which period a tender may not be amended or withdrawn and may be accepted at any time by the Department.

The original and completed bid document shall be placed in a sealed envelope clearly marked:

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

SUBMITTING OF TENDERS – PLEASE NOTE: Tenders can only be submitted in the Tender Box in **BLOEMFONTEIN**.

Tenders will be received on the closing date and time shown above. All tenders must be enclosed in sealed envelopes bearing the applicable tender heading and contract number, as well as the closing time and due date, and must be addressed to the **CHIEF DIRECTOR: SUPPLY CHAIN AND FACILITY MANAGEMENT**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

SERVICES, DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT, and must be submitted in the tender box situated at:

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT
136 Charlotte Maxeke Street
SA Eagle Building
Bloemfontein
9300

No telephonic or any other form of communication relating to this bid will be permitted with any other staff by bidder's other than with the named individuals stated below.

All enquiries regarding this bid must be directed to:

ENQUIRIES – TECHNICAL RELATED:

Mr Reshay Takoordeen
DURAPI CONSULTING (PTY) LTD
 Homestead Office Park
 37 Homestead Road
 Rivonia,
 Sandton,
 2128

Tel: (011) 312 8629/8599

Fax: (011) 312 8638

Email: tishan@durapi.co.za or resham@durapi.co.za

OR

Ms. Sibongile Mankahla
 Tel: (051) 400 4200
 Cell: 071 331 6342
 E-mail: sibongile.mankahla@dalrrd.gov.za

ENQUIRIES – SUPPLY CHAIN MANAGEMENT RELATED:

Mr Teboho Makitle	Mr Theotse Khateane
Tel: 051 400 4200	Tel: 051 400 4200
Fax: 086 536 6113	Fax: 086 536 6113
Email: teboho.makitle@dalrrd.gov.za	Email: theotse.khateane@dalrrd.gov.za

Bids will be opened in public. No late submissions will be considered. Telegraphic, telexed, facsimiled or e-mail submissions will not be accepted. Failure to meet the **mandatory requirements** required in this Bid will result in the submissions being deemed null and void and shall be considered non-responsive.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

BID BOX INFORMATION

TENDER NO.: **DALRRD-RID-FS-001 (2024/2025)**

CLOSING DATE: **13 DECEMBER 2024**

YOU ARE HEREBY INVITED TO BID TO THE GOVERNMENT OF THE REPUBLIC OF SOUTH AFRICA
(DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT)

BIDS RECEIVED AFTER THE CLOSING TIME AND DATE ARE LATE AND WILL AS A RULE NOT BE
ACCEPTED FOR CONSIDERATION.

SUBMIT ALL BIDS ON THE OFFICIAL FORMS - DO NOT RETYPE

Bid documents must be deposited in the box, which is identified as the bid box of the:

**DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT
136 CHARLOTTE MAXEKE STREET
SA EAGLE BUILDING
BLOEMFONTEIN
9300
GROUND FLOOR**

**THE BID BOX OF THE OFFICE OF THE DEPARTMENT OF AGRICULTURE, LAND REFORM AND
RURAL DEVELOPMENT IS OPEN 24 HOURS A DAY, 7 DAYS A WEEK. THE BID BOX WILL BE
CLOSED ON THE CLOSING TIME OF BIDS WHICH IS 11:00.**

BIDDERS SHOULD ENSURE THAT BIDS ARE DELIVERED TIMEOUSLY TO THE CORRECT ADDRESS

SUBMIT EACH BID IN A SEPARATE SEALED ENVELOPE

***Note:** Any reference to words "Bid" or "Bidder" herein and/or in any other documentation shall be taken to have the same meaning as the words "Tender" or "Tenderer".

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

SECTION T1.2: TENDER DATA

SECTION T1.2.1: CONDITIONS OF TENDER

This edition incorporates the amendments made in Board Notice 423 Government Gazette No 42622 of 8 August 2019 and erratum notices issued thereafter.

The Standard Conditions of Tender make several references to the Tender Data for details that apply specifically to this tender. The Tender Data shall have precedence in the interpretation of any ambiguity or inconsistency between it and the Standard Conditions of Tender.

Each item of data given below is cross-referenced to the clause in the Standard Conditions of Tender to which it mainly applies.

SECTION T1.2.2: TENDER DATA

The clause numbers in the Tender Data refer to the corresponding clause numbers in the Conditions of Tender.

The additional Conditions of Tender are:

Item		Data
F.1	GENERAL	ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER
C.1.1	Actions	The Employer is the "DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT". The term "bid" in the context of this standard is synonymous with term "tender".
C.1.2	Tender Documents	This document in which are bound the Tendering Procedures, Returnable Documents, Agreements and Contract Data, Pricing Data, Scope of Works, Site Information and Drawings
C.1.3	Interpretation	Add the following new clause: "1.3.3" The tender documents have been drafted in English. The contract arising from the invitation of tender shall be interpreted and construed in English.
C.1.4	Communication and Employer's Agent:	
	The Employer's Agent is:	Durapi Consulting (Pty) Ltd Contact : Tishan Govender/Resham Doorgaparsad

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Data
	Address : Homestead Office Park 37 Homestead Road Rivonia Sandton Postal : PO Box 1838 Faerie Glen,0043 Tel : (011) 312 8629/8599 Fax : (011) 312 8638 E-mail : tishan@durapi.co.za or resham@durapi.co.za
C.2	TENDERER'S OBLIGATIONS ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER
C.2.1	Eligibility: Only those Tenderers who are registered with the CIDB or are capable of being so prior to the evaluation of submissions, in a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum tendered for a Class of construction work, are eligible to submit tenders. Joint ventures are eligible to submit tenders provided that they comply with all three of the following conditions: 1. Every member of a joint venture is registered with the CIDB. 2. The lead partner has a contractor grading designation of not lower than one level below the required grading designation of 6CE of construction work. 3. The combined contractor grading designation calculated in accordance with the Construction Industry Development Regulations is equal to or higher than a contractor designation determined in accordance with the sum tendered for a 6CE class of construction work, is eligible to submit tenders.
C.2.2	Cost of Tendering: Add the following to the clause: "Accept that the Employer will not compensate the tenderer for any costs incurred in attending interviews in the office of the Employer or the Employer's Agent."
C.2.5	Reference documents: The document "GCC 2015 Third Edition". Tenderers, Contractors and Sub-contractorss shall obtain their own copies of this document for tendering purposes and for use for the duration of the Contract. Copies of these documents may be obtained from the Association of South African Quantity Surveyors (011-315 4140), the Master Builders Association (011-205 9000), the South African Association of Consulting Engineers (011-463 2022) or the South African Institute of Architects (011-486 0684).
C.2.7	Clarification meeting: The arrangements for a compulsory clarification meeting are as stated in the Tender Notice and Invitation to Tender. Tenderers must sign the attendance list in the name of the tendering entity. Addenda will be issued to and tenders will be received only from those tendering entities appearing on the attendance list and paid for Bid Documents
C.2.8	Seek clarification: "Request clarification of the tender documents, if necessary, by notifying the Employer's Official or the Employer's Agent indicated in the Tender Notice and Invitation to Tender in writing at least 7 (seven) calendar days before the closing time stated in the foregoing notice and clause 2.15."

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.2	TENDERER'S OBLIGATIONS ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER	
C.2.9	Insurance:	Add the following to the clause: "Accept that the submission of a Tender shall be construed as an acknowledgement by the Employer that he/she is satisfied with the insurance cover that the Contractor will have to effect Contract Works Insurance to be limited to the the Tender amount including VAT plus 20%, and Public Liability to be limited to R 5 000 000 under the contract The Employer will not provide for any insurance as it will be provided for by the Contractor.
C.2.11	Alterations to documents:	Add the following to the clause: "In the event of mistakes having been made on the form of offer inclusive of VAT and the BOQ it must be crossed out in ink at each and every price alteration. And be accompanied by an initial. Corrections in terms of price must not be made by means of a correction fluid such as Tipp-Ex or similar product.If correction fluid has been used on any specific item price, such item will not be considered. No correction fluid must be used in a Bill of Quantities where prices are calculated to arrive at a total amount. If correction fluid has been used the Tender as a whole will not be considered. Tampering with or taking apart the bound document is strictly prohibited. All additional documentation must be stapled into the tender document or attached in a separate file." The Department will reject the bid if the above conditions are not adhered to.
C.2.13	Submitting a tender offer	
	C.2.13.1	Each Tenderer is required to return the complete set of documents as listed in the Tender Data with all the required information supplied and completed in all respects.
	C.2.13.2	Return all returnable documents to the employer after completing them in their entirety, by writing legibly in non-erasable ink.Failure to adhere to this the bid will be disqualified.
	C.2.13.3	Submit the parts of the tender offer communicated on paper as an original plus the number of copies stated in the tender data, with an English translation of any documentation in a language other than English.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.2	TENDERER'S OBLIGATIONS ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER	
	C.2.13.4	Add the following to the clause: "Only duly authorised signatories must sign the original and all copies of the tender offer where required in terms of 2.13.3. In the case of a ONE-PERSON CONCERN submitting a tender, this shall be clearly stated on the company letter head. In case of a COMPANY submitting a tender, include a copy of a resolution by its board of directors authorising a director or other official of the company to sign the documents on behalf of the company. In the case of a CLOSED CORPORATION submitting a tender, include a copy of a resolution by its members authorising a member or other official of the corporation to sign the documents on each member's behalf. In the case of a PARTNERSHIP submitting a tender, all the partners shall sign the documents, unless one partner or a group of partners has been authorised to sign on behalf of each partner, in which case proof of such an authorisation shall be included in the Tender. In the case of a JOINT VENTURE submitting a tender, must include a resolution of each company of the Joint Venture together with a resolution by its members authorising a member of the Joint Venture to sign the documents on behalf of the Joint Venture." Accept that failure to submit proof of Authorisation to sign the tender shall result in a Tender Offer being regarded as non-responsive
	C.2.13.5	The Employer's address for delivery of tender offers: DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT Provincial Shared Service Centre 136 Charlotte Maxeke Street Department of Rural Development Bloemfontein 9300
	C.2.13.6	A two-envelope procedure will NOT be followed.
	C.2.13.9	Telephonic, telegraphic, telex, facsimile or e-mailed tender offers will not be accepted.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.2	TENDERER'S OBLIGATIONS ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER	
C.2.14	Information and Data to be completed in all respects:	Add the following to the clause: "Accept that the Employer shall in the evaluation of tenders take due account of the Tenderer's past performance in executing for similar works of comparable magnitude, and the degree to which he possesses the necessary technical, financial and other resources to enable him to complete the Works successfully within the contract period. Satisfy the Employer and Principal Agent as to his ability to perform and complete the Works timeously, safely and with satisfactory quality, by furnishing details in Section T2.2. Accept that the Employer is restricted in accordance with clause 4.(4) of the Construction Regulations, 2014, to only appoint a contractor whom he is satisfied has the necessary competencies and resources to carry out the work safely.
C.2.15	Closing time:	The closing date and time for submission of tender offers is as stated in the Tender Notice and Invitation to Tender.
C.2.16	Tender offer validity:	The tender offer validity period is 90 calendar days. For tenders closing in October, November and December the tender validity period is 120 calendar days. Add the following to the clause: "If the tender validity expires on a Saturday, Sunday or public holiday, the Tender Offer shall remain valid and open for acceptance until the closure of business on the following working day."
C.2.17	Clarification of tender offer after submission	The Tenderer shall provide clarification of a tender offer in response to a request to do so from the employer during the evaluation of arithmetical errors by the adjustment of certain rates or items prices (or both). No change in the competitive position of tenderers or substance of the tender offer is sought, offered, or permitted.
C.2.18	Provide other material	The Tenderer shall provide, on request by the employer, any other material that has a bearing on the tender offer, the tenderer's commercial position (including notarized joint venture agreements), preferencing arrangements, or samples of materials, considered necessary by the employer for the purpose of a full and fair risk assessment. Should the tenderer not provide the material, or a satisfactory reason as to why it cannot be provided, by the time for submission stated in the employer's request, the employer may regard the tender offer as non-responsive.
C.2.19	Inspections, tests and analysis:	The Tenderer must provide access during working hours to his premises for inspections on request.
C.2.20	Submit securities, bonds and policies:	If requested, submit for the employer's acceptance before formation of the contract, all securities, bonds, guarantees, policies and certificates of insurance required in terms of the conditions of contract identified in the contract data.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.2	TENDERER'S OBLIGATIONS ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER	
C.2.23	Certificates:	The following certificates/ information may be provided with the tender offer: a) Copy of Certificate of Incorporation (if tenderer is a Company), e.g. CM1, CM29, or CM44 b) Copy of Founding Statement (if tenderer is a Closed Corporation), e.g. CK1, or CK2 c) Copy of Partnership Agreement (if tenderer is a Partnership) d) Copy of Identity Document (if tenderer is a One-man concern) e) Copy of Deed of Trust (If a trust is involved). In cases where the tenderer has failed to submit any of the documents above with the tender, the Department reserves the right to, at any time after the closure of the tender, but before the award of the tender, request the tenderer to provide the outstanding documents within 5 (five) calendar days from the date of notification.
ADD THE FOLLOWING NEW CLAUSES:		
"2.24	Canvassing and obtaining of additional information by tenderers:	Accept that no Tenderer shall make any attempt either directly or indirectly to canvass any of the Employers officials or the Employer's agent in respect of his tender, after the opening of the tenders, but prior to the Employer arriving at a decision thereon. No Tenderer shall make any attempt to obtain particulars of any relevant information, other than that disclosed at the opening of tenders."
"2.26	Awards to close family members of persons in the service of the state	In order to adjudicate fairness or eligibility, the questionnaire for the declaration of interests in the tender of persons in service of state in Section T2.2.5 – Form E must be completed."
"2.28	TAX COMPLIANCE	Bidders must ensure compliance with their tax obligations. Bidders are required to submit their unique personal identification number (PIN) issued by sars to enable the organ of state to view the taxpayer's profile and tax status. Application for tax compliance status (TCS) or pin may also be made via e-filing. In order to use this provision, taxpayers will need to register with sars as e-filers through the website www.sars.gov.za. Bidders may also submit a printed TCS together with the bid. In bids where Consortia / Joint Ventures / Sub-contractors are involved, each party must submit a separate proof of TCS / PIN / CSD number. Where no tcs is available but the bidder is registered on the central supplier database (CSD), a csd number must be provided.
"C.2.29	CSD –National Treasury Central Supplier Database (CSD) Registration	Bidders must register on the central supplier database (CSD) to upload mandatory information namely: (business registration/ directorship/ membership/identity numbers; tax compliance status; and banking information for verification purposes). B-BBEE certificate or sworn affidavit for B-BBEE must be submitted to bidding institution. Where a bidder is not registered on the CSD, mandatory information namely: (business registration/ directorship/ membership/identity numbers; Tax compliance status should be submitted with the bid documentation. B-BBEE certificate or sworn affidavit for B-BBEE must be submitted to bidding institution.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.2.30	Local Labour	It is a requirement of this contract that work be executed in such a manner so as to maximise the use of local labour intensive construction methods .”
C.3	THE EMPLOYER’S UNDERTAKINGS ADDITION OR VARIATION TO STANDARD CONDITION OF TENDER	
C.3.1	Respond to requests from the Tenderer:	Replace the contents of the clause with the following: “Respond to a request for clarification received up to seven (5) calendar days before the tender closing time stated in the tender data and notify all Tenderers who drew procurement documents”
C.3.2	Issue Addenda:	If necessary, issue addenda that may amend or amplify the tender documents to each tenderer during the period from the date that tender documents are available until five(5) working days before the tender closing time stated in the Tender Data. If , as a result a tenderer applies for an extension to the closing time stated in the Tender Data, the Employer may grant such extension and,shall then notify all tenderers who drew documents.
C.3.3	Return late tender offers	Return tender offers received after the closing time stated in the Tender Data, unopened, (unless it is necessary to open a tender submission to obtain a forwarding address), to the tenderer concerned.
C.3.4	Opening of tender submissions:	The closing date and time for receipt of tenders is: 13 DECEMBER 2024 Tenders will be received on the closing date and time shown, must be enclosed in a sealed envelope bearing the applicable tender heading and contract number, as well as the closing time and due date, and must be addressed to the: CHIEF DIRECTOR: SUPPLY CHAIN AND FACILITIES MANAGEMENT SERVICES: DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT. Tenders must be submitted in the tender box situated in Bloemfontein : DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT 136 Charlotte Maxeke Street SA Eagle Building Bloemfontein 9300 Ground Floor Only tenders submitted to this tender box will be opened/ considered. Valid tender submissions shall be opened in the presence of tenderers’ agents who choose to attend at the time and place stated in the tender data. Tender submissions for which acceptable reasons for withdrawal have been submitted will not be opened.
C.3.4.1		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.3.11	Evaluation of Tenders:	The tender evaluation method to evaluate all responsive tender offers will be Method 4 (Financial offer, quality and specific goals). Apply the 80/20 Preference Point system where a maximum of eighty 80 tender adjudication points be awarded for price. Twenty (20) points will be awarded for specific goals in terms of the Preferential Procurement Policy Framework Act (Act 5 of 2000) and Preferential Procurement Regulation, 2022. See section T2.2.8, Form H for the Preference model. The financial offer will be scored in terms of formula 2, option 1 of the Standard Conditions of Tender (Section T1.3 of the document).
--------	-------------------------------	--

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

The CRITERIA to be applied in evaluating the proposal is set out in the table below:				
No Submission-0; Poor-1; Average-2; Good-3; Very Good-4; Excellent-5				
QUALITY CRITERIA				
NO.	CRITERIA	WEIGHT	INDICATE VALUE	TOTAL
1	WORK CARRIED OUT BY THE TENDERER Successful completion of similar projects (Culvert Crossing, culverts, concrete storm water conveying structures, roadworks related projects limited to construction, upgrading and rehabilitation projects) in the last five (5) years from a minimum value of R6 500 000.00 as a principal contractor . <i>Attach completion certificates with appointment letters. (No score will be awarded if both the certificate and appointment letter are not attached)</i> NB: Employer's Letterhead / Employer's Stamp Note: Returnable Document = FORM H	35		
2	PROPOSED KEY PERSONNEL – SITE AGENT Site Agent with NQF 6 Qualification in Built Environment: CV and certified copies of qualifications must be attached. <i>(No score will be awarded if CV and copies of qualifications certified within 6 months from tender closing are not attached)</i> NB! Foreign based SAQA evaluated qualifications to be submitted with relevant qualifications and needs to be certified within 6 months and not copy of a copy. Copies must be certified by Commissioner of Oaths Experience will be scored post qualification Note: Returnable Document = FORM J	30		
3	PROPOSED KEY PERSONNEL: FOREMAN Foreman: <i>CV must be attached. (No score will be awarded if CV is not attached)</i> Note: Returnable Document = FORM J	20		
4	PRELIMINARY CONSTRUCTION PROGRAMME Submission of the following comprehensive construction programme indicating all work flow items. Note: Returnable Document = FORM M	15		
Total		100		

The proposal will be evaluated individually on score sheets, by a representative evaluation panel according to the evaluation criteria indicated above. All service providers who scored less than 60 out of 100 points for functionality will not be considered further.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

QUALITY CRITERIA																
NO.	CRITERIA	WEIGHT	INDICATIVE VALUE	TOTAL												
1	SUCCESSFUL COMPLETION OF SIMILAR PROJECTS IN THE LAST FIVE (5) YEARS FROM A MINIMUM VALUE OF R6 500 000.00. ATTACH COMPLETION CERTIFICATES WITH APPOINTMENT LETTER AS A PRINCIPAL CONTRACTOR . (NO SCORE WILL BE AWARDED IF COMPLETION CERTIFICATES AND APPOINTMENT LETTER ARE NOT ATTACHED) Tenderers are required to demonstrate relevant past experience and competency. Tenderers are required to submit full details of, and reliable contactable references for, relevant project which were successfully completed. Projects relevant must be of similar scope, nature and size , completed within the last five (5) years. Successful completion of similar projects in the last 5 years. Similar projects shall be either Culvert Crossing, culverts, concrete storm water conveying structures, roadworks related projects limited to construction, upgrading and rehabilitation projects <table border="1"> <tr> <td>No Submission (score 0)</td> <td>The tenderer has failed to address the question and has not provided any proof of completing a similar project.</td> </tr> <tr> <td>Poor (score 1)</td> <td>One (1) relevant similar project executed successfully by the contractor in the past 5 years</td> </tr> <tr> <td>Average (score 2)</td> <td>Two (2) relevant similar projects successfully executed by the contractor in the past 5 years</td> </tr> <tr> <td>Good (score 3)</td> <td>Three(3) relevant similar projects successfully executed by the contractor in the past 5 years</td> </tr> <tr> <td>Very Good (score 4)</td> <td>Four(4) relevant similar project successfully executed by the contractor in the past 5 years</td> </tr> <tr> <td>Excellent (score 5)</td> <td>More than five(5) relevant similar projects successfully executed by the contractor in the past 5 years and above</td> </tr> </table> No score will be awarded if both the certificate and appointment letter are not attached Note: Returnable Document = FORM H	No Submission (score 0)	The tenderer has failed to address the question and has not provided any proof of completing a similar project.	Poor (score 1)	One (1) relevant similar project executed successfully by the contractor in the past 5 years	Average (score 2)	Two (2) relevant similar projects successfully executed by the contractor in the past 5 years	Good (score 3)	Three(3) relevant similar projects successfully executed by the contractor in the past 5 years	Very Good (score 4)	Four(4) relevant similar project successfully executed by the contractor in the past 5 years	Excellent (score 5)	More than five(5) relevant similar projects successfully executed by the contractor in the past 5 years and above	35		
No Submission (score 0)	The tenderer has failed to address the question and has not provided any proof of completing a similar project.															
Poor (score 1)	One (1) relevant similar project executed successfully by the contractor in the past 5 years															
Average (score 2)	Two (2) relevant similar projects successfully executed by the contractor in the past 5 years															
Good (score 3)	Three(3) relevant similar projects successfully executed by the contractor in the past 5 years															
Very Good (score 4)	Four(4) relevant similar project successfully executed by the contractor in the past 5 years															
Excellent (score 5)	More than five(5) relevant similar projects successfully executed by the contractor in the past 5 years and above															

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

2	EXPERIENCE OF SITE AGENT This Sub Criteria covers the general average experience of the proposed Site Agent (total duration of professional activity at Site Agent level). The candidate must have a minimum of NQF level 6 in built environment. Tenderers are required to submit curriculum vitae for the key personnel proposed to be employed on the project. These curriculum vitae are to include specific details of these individuals including past experience and competence in delivering key similar relevant building project . This evaluation is based on the following weighting: (CV a certified copy of qualifications must be attached) Copies must be certified by a Commissioner of Oaths NB : No score will be awarded to bidder who has not attached CV and certified qualification copies). Experience will be scored post qualification <table border="1"> <tr> <td>No Submission (score 0)</td> <td>No CV Submitted. No minimum qualification Less than 1 year experience in the position</td> </tr> <tr> <td>Poor (score 1)</td> <td>Minimum experience of 1 to 2 years experience as a site agent</td> </tr> <tr> <td>Average (score 2)</td> <td>Minimum experience of 2 to 4 years experience as a site agent</td> </tr> <tr> <td>Good (score 3)</td> <td>Minimum experience of 4 to 6 years experience as a site agent</td> </tr> <tr> <td>Very Good (score 4)</td> <td>Minimum experience of 6 to 8 years experience as a site agent</td> </tr> <tr> <td>Excellent (score 5)</td> <td>Minimum experience of more than 9 years experience as a site agent</td> </tr> </table>	No Submission (score 0)	No CV Submitted. No minimum qualification Less than 1 year experience in the position	Poor (score 1)	Minimum experience of 1 to 2 years experience as a site agent	Average (score 2)	Minimum experience of 2 to 4 years experience as a site agent	Good (score 3)	Minimum experience of 4 to 6 years experience as a site agent	Very Good (score 4)	Minimum experience of 6 to 8 years experience as a site agent	Excellent (score 5)	Minimum experience of more than 9 years experience as a site agent	30		
No Submission (score 0)	No CV Submitted. No minimum qualification Less than 1 year experience in the position															
Poor (score 1)	Minimum experience of 1 to 2 years experience as a site agent															
Average (score 2)	Minimum experience of 2 to 4 years experience as a site agent															
Good (score 3)	Minimum experience of 4 to 6 years experience as a site agent															
Very Good (score 4)	Minimum experience of 6 to 8 years experience as a site agent															
Excellent (score 5)	Minimum experience of more than 9 years experience as a site agent															
3	EXPERIENCE OF FOREMAN This Sub Criteria covers the general average experience of the proposed Foreman (total duration of professional activity at Foreman level) . Tenderers are required to submit curriculum vitae for the Foreman proposed to be employed on the project. These curriculum vitae are to include specific details of these individuals including past experience and competence in delivering key similar relevant building project . This evaluation is based on the following weighting: (CV must be attached) NB : No score will be awarded to bidder who has not attached a CV <table border="1"> <tr> <td>No Submission (score 0)</td> <td>No CV Submitted</td> </tr> <tr> <td>Poor (score 1)</td> <td>More than 2 to 5 year experience as a foreman</td> </tr> <tr> <td>Average (score 2)</td> <td>More than 5 to 8 years experience as a foreman</td> </tr> <tr> <td>Good (score 3)</td> <td>More than 8 to 11 years experience as a foreman</td> </tr> <tr> <td>Very Good (score 4)</td> <td>More than 11 to 14 years experience as a foreman</td> </tr> <tr> <td>Excellent (score 5)</td> <td>14 years and above as a foreman</td> </tr> </table> Note: Returnable Document = FORM J	No Submission (score 0)	No CV Submitted	Poor (score 1)	More than 2 to 5 year experience as a foreman	Average (score 2)	More than 5 to 8 years experience as a foreman	Good (score 3)	More than 8 to 11 years experience as a foreman	Very Good (score 4)	More than 11 to 14 years experience as a foreman	Excellent (score 5)	14 years and above as a foreman	20		
No Submission (score 0)	No CV Submitted															
Poor (score 1)	More than 2 to 5 year experience as a foreman															
Average (score 2)	More than 5 to 8 years experience as a foreman															
Good (score 3)	More than 8 to 11 years experience as a foreman															
Very Good (score 4)	More than 11 to 14 years experience as a foreman															
Excellent (score 5)	14 years and above as a foreman															
	Note: Returnable Document = FORM G															

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

4	CONSTRUCTION PROGRAMME Submission of the following comprehensive construction programme indicating all work flow items in relation to reaching listed project deliverables on time. <table border="1" style="width: 100%;"> <tr> <td style="width: 20%;">Very Poor (score 0)</td> <td>No programme attached.</td> </tr> <tr> <td>Poor (score 1)</td> <td>The programme is poorly compiled and there are major inconsistencies with timing of project deliverables.</td> </tr> <tr> <td>Average (score 2)</td> <td>The programme omits important tasks or the timing of the activities and correlation among them are inconsistent with project deliverables. There is a lack of clarity and logic in the sequence.</td> </tr> <tr> <td>Good (score 3)</td> <td>All key activities are included in the programme, but are not detailed. There are minor inconsistencies between timing and project deliverables.</td> </tr> <tr> <td>Very Good (score 4)</td> <td>All key activities are included and well detailed in the programme. There are no inconsistencies between timing and project deliverables.</td> </tr> <tr> <td>Excellent (score 5)</td> <td>The programme fits the project deliverables well; all important activities are indicated in the programme and their timing and sequencing is appropriate and consistent with project objectives and requirements. There is an excellent degree of detail with links that facilitates understanding of the proposed programme.</td> </tr> </table>	Very Poor (score 0)	No programme attached.	Poor (score 1)	The programme is poorly compiled and there are major inconsistencies with timing of project deliverables.	Average (score 2)	The programme omits important tasks or the timing of the activities and correlation among them are inconsistent with project deliverables. There is a lack of clarity and logic in the sequence.	Good (score 3)	All key activities are included in the programme, but are not detailed. There are minor inconsistencies between timing and project deliverables.	Very Good (score 4)	All key activities are included and well detailed in the programme. There are no inconsistencies between timing and project deliverables.	Excellent (score 5)	The programme fits the project deliverables well; all important activities are indicated in the programme and their timing and sequencing is appropriate and consistent with project objectives and requirements. There is an excellent degree of detail with links that facilitates understanding of the proposed programme.	15	
Very Poor (score 0)	No programme attached.														
Poor (score 1)	The programme is poorly compiled and there are major inconsistencies with timing of project deliverables.														
Average (score 2)	The programme omits important tasks or the timing of the activities and correlation among them are inconsistent with project deliverables. There is a lack of clarity and logic in the sequence.														
Good (score 3)	All key activities are included in the programme, but are not detailed. There are minor inconsistencies between timing and project deliverables.														
Very Good (score 4)	All key activities are included and well detailed in the programme. There are no inconsistencies between timing and project deliverables.														
Excellent (score 5)	The programme fits the project deliverables well; all important activities are indicated in the programme and their timing and sequencing is appropriate and consistent with project objectives and requirements. There is an excellent degree of detail with links that facilitates understanding of the proposed programme.														

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.3.13	Acceptance of tender offer:	Tender offers will only be accepted if: a) The Tenderer submits a duly and dated relevant resolution of their members or their board of directors, as the case may be, on their company letterhead. In the case of a sole proprietor of a single member in a company, it must be clearly indicated in a company letterhead. In the case of a Joint Venture submitting a tender, include a resolution of each company of the Joint Venture together with a resolution signed by all members of the Joint Venture authorizing a member of the Joint Venture to sign the documents on behalf of the Joint Venture. NB: RESOLUTION MUST BE SPECIFIC TO THE PROJECT: APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE REHABILITATION OF SEDIBA ROAD AND CULVERT UPGRADE UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE. b) Bidders must ensure compliance with their tax obligations. Bidders are required to submit their unique personal identification number (PIN) issued by SARS to enable the organ of state to view the taxpayer's profile and tax status. Application for tax compliance status (TCS) or pin may also be made via e-filing. In order to use this provision, taxpayers will need to register with SARS as e-filers through the website www.sars.gov.za. Bidders may also submit printed TCS together with the bid. In bids where Consortia / Joint Ventures / Sub-contractors are involved, each party must submit a separate proof of TCS / PIN / CSD number. Where no TCS is available but the bidder is registered on central supplier database (CSD), a CSD number must be provided. c) The Tenderer is registered with the Construction Industry Development Board in an appropriate contractor grading designation. Proof of Registration in respect of each partner, where a tenderer satisfied the CIDB contractor grading designation requirements through the formation of a joint venture. The Lead partner must have a contractor grading designation of not lower than one level below the required grading designation; d) The Bidder did not tamper, dismantle or remove any documents from the tender document. e) The Tenderer has acknowledged and signed the record of addenda page, and submitted the addendum or addenda, in the event that the addendum or addenda has been issued. f) The Tenderer has attended the compulsory tender clarification meeting as stipulated. g) The Tenderer has completed the form of offer and is signed by the duly authorized person and witnessed. h) The Tenderer submits a letter from the bank or a FAIS registered or NCR registered financial institution with whom he/she has made the necessary arrangements, to the effect that the said institution will be prepared to provide the required performance guarantee. i) The Tenderer is registered and in good standing with respect to Compensation for Occupational Injuries and Diseases Act (COIDA) with Department of Labour or with a licensed compensation insurer. The Tenderer must submit the letter of good standing for built environment projects. In the event of the Tenderer being a joint venture/consortium, the letter of good standing for built environment projects of the individual members must also be provided.
C.3.17	Provide copies of the contract	One signed copy of the contract shall be provided by the Employer to the successful Tenderer.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.4	ADDITIONAL CONDITIONS OF TENDER
The additional conditions of Tender are:	
C.4.1	Compliance with Occupational Health and Safety Act 1993 Tenderers are to note the requirements of the Occupational Health and Safety Act No. 85 of 1993 and the Construction Regulations 2014 issued in terms of Section 43 of the Act. The Tenderer shall be deemed to have read and fully understood the requirements of the above Act and Regulations and to have allowed for all costs in compliance therewith. In this regard the Contractor shall submit, a detailed Health and Safety Plan in respect of the Works in order to demonstrate the necessary competencies and resources to perform the construction work all in accordance with the Act and Regulations. Such Health and Safety Plan shall cover inter-alia the following details: (1) Management Structure, Site Supervision and Responsible Persons including a succession plan. (2) Contractor's induction training programme for Employees, Sub-contractorss and Visitors to the Site. (3) Health and safety precautions and procedures to be adhered to in order to ensure compliance with the Act, Regulations and Safety Specifications. (4) Regular monitoring procedures to be performed. (5) Regular liaison, consultation and review meetings with all parties. (6) Site security, welfare facilities and first aid. (7) Site rules and fire and emergency procedures.
	Tenderers are to note that the Contractor is required to ensure that all Sub-contractorss or others engaged in the performance of the Contract also comply with the above requirements. The Contractor shall prepare and maintain a Health and Safety File in respect of the project, which shall be available for inspection on Site at all times and handed over to the Employer on Final Completion of the project. The Contractor is required to submit to the Employer the Occupational Health and Safety Agreement (included in Part C1.4 of the Contract Document) and a letter of good standing from the Compensation Commissioner, or a licensed compensation insurer, within 14 days after the Commencement Date of the Contract.
C.4.2	Community Liaison Officer It is a requirement of the Contract that a Community Liaison Officer (CLO) be appointed by the Contractor. The primary functions of the CLO shall be to assist the Contractor with the selection and recruitment of targeted labour, to represent the local community in matters concerning the use of targeted labour (and/or enterprises) on the works, and to assist with and facilitate communication between the Contractor, the Principal Agent and the local communities. The method of identifying suitable candidates for the position of CLO, as well as requirements in respect of the employment of the selected candidate, are described in Part C3.3.2: Scope of Work.

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DRDLR-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

CIDB STANDARD CONDITIONS OF TENDER

SECTION T1.2.3: CIDB STANDARD CONDITIONS OF TENDER

As published in Annexure C of the cidb Standard for Uniformity for construction Procurement, Notice 423 Government Gazette No 42622 of 8 August 2019.

C.1 General

C.1.1 Actions

C.1.1.1 The employer and each tenderer submitting a tender offer shall comply with these conditions of tender. In their dealings with each other, they shall discharge their duties and obligations as set out in C.2 and C.3, timeously and with integrity, and behave equitably, honestly and transparently, comply with all legal obligations and not engage in anticompetitive practices.

C.1.1.2 The employer and the tenderer and all their agents and employees involved in the tender process shall avoid conflicts of interest and where a conflict of interest is perceived or known, declare any such conflict of interest, indicating the nature of such conflict. Tenderers shall declare any potential conflict of interest in their tender submissions. Employees, agents and advisors of the employer shall declare any conflict of interest to whoever is responsible for overseeing the procurement process at the start of any deliberations relating to the procurement process or as soon as they become aware of such conflict and abstain from any decisions where such conflict exists or recuse themselves from the procurement process, as appropriate.

Note: 1) A conflict of interest may arise due to a conflict of roles which might provide an incentive for improper acts in some circumstances. A conflict of interest can create an appearance of impropriety that can undermine confidence in the ability of that person to act properly in his or her position even if no improper acts result.

2) Conflicts of interest in respect of those engaged in the procurement process include direct, indirect or family interests in the tender or outcome of the procurement process and any personal bias, inclination, obligation, allegiance or loyalty which would in any way affect any decisions taken.

C.1.1.3 The employer shall not seek and a tenderer shall not submit a tender without having a firm intention and the capacity to proceed with the contract.

C.1.2 Tender Documents

The documents issued by the employer for the purpose of a tender offer are listed in the tender data.

C.1.3 Interpretation

C.1.3.1 The tender data and additional requirements contained in the tender schedules that are included in the returnable documents are deemed to be part of these conditions of tender.

C.1.3.2 These conditions of tender, the tender data and tender schedules which are required for tender evaluation purposes, shall form part of any contract arising from the invitation to tender.

C.1.3.3 For the purposes of these conditions of tender, the following definitions apply:

a) **conflict of interest** means any situation in which:

i) someone in a position of trust has competing professional or personal interests which make it difficult to fulfill his or her duties impartially;

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- ii) an individual or tenderer is in a position to exploit a professional or official capacity in some way for their personal or corporate benefit; or
 - iii) incompatibility or contradictory interests exist between an employee and the tenderer who employs that employee.
- b) **comparative offer** means the price after the factors of a non-firm price and all unconditional discounts it can be utilised to have been taken into consideration;
 - c) **corrupt practice** means the offering, giving, receiving or soliciting of anything of value to influence the action of the employer or his staff or agents in the tender process;
 - d) **fraudulent practice** means the misrepresentation of the facts in order to influence the tender process or the award of a contract arising from a tender offer to the detriment of the employer, including collusive practices intended to establish prices at artificial levels;

C.1.4 Communication and employer's agent

Each communication between the employer and a tenderer shall be to or from the employer's agent only, and in a form that can be readily read, copied and recorded. Communications shall be in the English language. The employer shall not take any responsibility for non-receipt of communications from or by a tenderer. The name and contact details of the employer's agent are stated in the tender data.

C.1.5 Cancellation and Re-Invitation of Tenders

C.1.5.1 An employer may, prior to the award of the tender, cancel a tender if-

- a) due to changed circumstances, there is no longer a need for the engineering and construction works specified in the invitation;
- b) funds are no longer available to cover the total envisaged expenditure; or
- c) no acceptable tenders are received.
- d) there is a material irregularity in the tender process.

C.1.5.2 The decision to cancel a tender invitation must be published in the same manner in which the original tender invitation was advertised

C.1.5.3 An employer may only with the prior approval of the relevant treasury cancel a tender invitation for the second time.

C.1.6 Procurement procedures

C.1.6.1 General

Unless otherwise stated in the tender data, a contract will, subject to C.3.13, be concluded with the tenderer who in terms of C.3.11 is the highest ranked or the tenderer scoring the highest number of tender evaluation points, as relevant, based on the tender submissions that are received at the closing time for tenders.

C.1.6.2 Competitive negotiation procedure

C.1.6.2.1 Where the tender data require that the competitive negotiation procedure is to be followed, tenderers shall submit tender offers in response to the proposed contract in the first round of submissions. Notwithstanding the requirements of C.3.4, the employer shall announce only the names of the tenderers who make a submission. The requirements of C.8 relating to the material deviations or qualifications which affect the competitive position of tenderers shall not apply.

C.1.6.2.2 All responsive tenderers or at least a minimum of not less than three responsive tenderers that are highest ranked in terms of the evaluation criteria stated in the tender data shall be invited to enter into competitive negotiations based on the principle of equal treatment, keeping confidential the proposed solutions and associated information.

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

Notwithstanding the provisions of C.2.17, the employer may request that tenders be clarified, specified and fine-tuned in order to improve a tenderer's competitive position provided that such clarification, specification, fine-tuning or additional information does not alter any fundamental aspects of the offers or impose substantial new requirements which restrict or distort competition or have a discriminatory effect.

C.1.6.2.3 At the conclusion of each round of negotiations, tenderers shall be invited by the employer to revise their tender offer based on the same evaluation criteria, with or without adjusted weightings.

Tenderers shall be advised when they are to submit their best and final offer.

C.1.6.2.4 The contract shall be awarded in accordance with the provisions of C.3.11 and C.3.13 after tenderers have been requested to submit their best and final offer.

C.1.6.3 Proposal procedure using the two stage-system

C.1.6.3.1 Option 1

Tenderers shall in the first stage submit technical proposals and, if required, cost parameters around which a contract may be negotiated. The employer shall evaluate each responsive submission in terms of the method of evaluation stated in the tender data, and in the second stage negotiate a contract with the tenderer scoring the highest number of evaluation points and award the contract in terms of these conditions of tender.

C.1.6.3.2 Option 2

C.1.6.3.2.1 Tenderers shall submit in the first stage only technical proposals. The employer shall invite all responsive tenderers to submit tender offers in the second stage, following the issuing of procurement documents.

C.1.6.3.2.2 The employer shall evaluate tenders received during the second stage in terms of the method of evaluation stated in the tender data, and award the contract in terms of these conditions of tender.

C.2 Tenderer's obligations

C.2.1 Eligibility

C.2.1.1 Submit a tender offer only if the tenderer satisfies the criteria stated in the tender data and the tenderer, or any of his principals, is not under any restriction to do business with employer.

C.2.1.2 Notify the employer of any proposed material change in the capabilities or formation of the tendering entity (or both) or any other criteria which formed part of the qualifying requirements used by the employer as the basis in a prior process to invite the tenderer to submit a tender offer and obtain the employer's written approval to do so prior to the closing time for tenders.

C.2.2 Cost of tendering

C.2.2.1 Accept that, unless otherwise stated in the tender data, the employer will not compensate the tenderer for any costs incurred in the preparation and submission of a tender offer, including the costs of any testing necessary to demonstrate that aspects of the offer complies with requirements.

C.2.2.2 The cost of the tender documents charged by the employer shall be limited to the actual cost incurred by the employer for printing the documents. Employers must attempt to make available the tender documents on its website so as not to incur any costs pertaining to the printing of the tender documents.

C.2.3 Check documents

Check the tender documents on receipt for completeness and notify the employer of any discrepancy or omission.

C.2.4 Confidentiality and copyright of documents

Treat as confidential all matters arising in connection with the tender. Use and copy the documents issued by the employer only for the purpose of preparing and submitting a tender offer in response to the invitation.

C.2.5 Reference documents

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

Obtain, as necessary for submitting a tender offer, copies of the latest versions of standards, specifications, conditions of contract and other publications, which are not attached but which are incorporated into the tender documents by reference.

C.2.6 Acknowledge addenda

Acknowledge receipt of addenda to the tender documents, which the employer may issue, and if necessary, apply for an extension to the closing time stated in the tender data, in order to take the addenda into account.

C.2.7 Clarification meeting

Attend, where required, a clarification meeting at which tenderers may familiarize themselves with aspects of the proposed work, services or supply and raise questions. Details of the meeting(s) are stated in the tender data.

C.2.8 Seek clarification

Request clarification of the tender documents, if necessary, by notifying the employer at least five (5) working days before the closing time stated in the tender data.

C.2.9 Insurance

Be aware that the extent of insurance to be provided by the employer (if any) might not be for the full cover required in terms of the conditions of contract identified in the contract data. The tenderer is advised to seek qualified advice regarding insurance.

C.2.10 Pricing the tender offer

C.2.10.1 Include in the rates, prices, and the tendered total of the prices (if any) all duties, taxes except Value Added Tax (VAT), and other levies payable by the successful tenderer, such duties, taxes and levies being those applicable fourteen (14) days before the closing time stated in the tender data.

C.2.10.2 Show VAT payable by the employer separately as an addition to the tendered total of the prices.

C.2.10.3 Provide rates and prices that are fixed for the duration of the contract and not subject to adjustment except as provided for in the conditions of contract identified in the contract data.

C.2.10.4 State the rates and prices in Rand unless instructed otherwise in the tender data. The conditions of contract identified in the contract data may provide for part payment in other currencies.

C.2.11 Alterations to documents

Do not make any alterations or additions to the tender documents, except to comply with instructions issued by the employer, or necessary to correct errors made by the tenderer. All signatories to the tender offer shall initial all such alterations.

C.2.12 Alternative tender offers

C.2.12.1 Unless otherwise stated in the tender data, submit alternative tender offers only if a main tender offer, strictly in accordance with all the requirements of the tender documents, is also submitted as well as a schedule that compares the requirements of the tender documents with the alternative requirements that are proposed.

C.2.12.2 Accept that an alternative tender offer must be based only on the criteria stated in the tender data or criteria otherwise acceptable to the employer.

C.2.12.3 An alternative tender offer must only be considered if the main tender offer is the winning tender.

C.2.13 Submitting a tender offer

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

C.2.13.1 Submit one tender offer only, either as a single tendering entity or as a member in a joint venture to provide the whole of the works identified in the contract data and described in the scope of works, unless stated otherwise in the tender data.

C.2.13.2 Return all returnable documents to the employer after completing them in their entirety, either electronically (if they were issued in electronic format) or by writing legibly in non-erasable ink.

C.2.13.3 Submit the parts of the tender offer communicated on paper as an original plus the number of copies stated in the tender data, with an English translation of any documentation in a language other than English, and the parts communicated electronically in the same format as they were issued by the employer.

C.2.13.4 Sign the original and all copies of the tender offer where required in terms of the tender data. The employer will hold all authorized signatories liable on behalf of the tenderer. Signatories for tenderers proposing to contract as joint ventures shall state which of the signatories is the lead partner whom the employer shall hold liable for the purpose of the tender offer.

C.2.13.5 Seal the original and each copy of the tender offer as separate packages marking the packages as "ORIGINAL" and "COPY". Each package shall state on the outside the employer's address and identification details stated in the tender data, as well as the tenderer's name and contact address.

C.2.13.6 Where a two -envelope system is required in terms of the tender data, place and seal the returnable documents listed in the tender data in an envelope marked "financial proposal" and place the remaining returnable documents in an envelope marked "technical proposal". Each envelope shall state on the outside the employer's address and identification details stated in the tender data, as well as the tenderer's name and contact address.

C.2.13.7 Seal the original tender offer and copy packages together in an outer package that states on the outside only the employer's address and identification details as stated in the tender data.

C.2.13.8 Accept that the employer will not assume any responsibility for the misplacement or premature opening of the tender offer if the outer package is not sealed and marked as stated.

C.2.13.9 Accept that tender offers submitted by facsimile or e-mail will be rejected by the employer, unless stated otherwise in the tender data.

C.2.14 Information and data to be completed in all respects

Accept that tender offers, which do not provide all the data or information requested completely and, in the form, required, may be regarded by the employer as non-responsive.

C.2.15 Closing time

C.2.15.1 Ensure that the employer receives the tender offer at the address specified in the tender data not later than the closing time stated in the tender data. Accept that proof of posting shall not be accepted as proof of delivery.

C.2.15.2 Accept that, if the employer extends the closing time stated in the tender data for any reason, the requirements of these conditions of tender apply equally to the extended deadline.

C.2.16 Tender offer validity

C.2.16.1 Hold the tender offer(s) valid for acceptance by the employer at any time during the validity period stated in the tender data after the closing time stated in the tender data.

C.2.16.2 If requested by the employer, consider extending the validity period stated in the tender data for an agreed additional period with or without any conditions attached to such extension.

C.2.16.3 Accept that a tender submission that has been submitted to the employer may only be withdrawn or substituted by giving the employer's agent written notice before the closing time for tenders that a tender is to

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

be withdrawn or substituted. If the validity period stated in C.2.16 lapses before the employer evaluating tender, the contractor reserves the right to review the price based on Consumer Price Index (CPI).

C.2.16.4 Where a tender submission is to be substituted, a tenderer must submit a substitute tender in accordance with the requirements of C.2.13 with the packages clearly marked as "SUBSTITUTE".

C.2.17 Clarification of tender offer after submission

Provide clarification of a tender offer in response to a request to do so from the employer during the evaluation of tender offers. This may include providing a breakdown of rates or prices and correction of arithmetical errors by the adjustment of certain rates or item prices (or both) . No change in the competitive position of tenderers or substance of the tender offer is sought, offered, or permitted.

Note: Sub-clause C.2.17 does not preclude the negotiation of the final terms of the contract with a preferred tenderer following a competitive selection process, should the Employer elect to do so.

C.2.18 Provide other material

C.2.18.1 Provide, on request by the employer, any other material that has a bearing on the tender offer, the tenderer's commercial position (including notarized joint venture agreements), preferencing arrangements, or samples of materials, considered necessary by the employer for the purpose of a full and fair risk assessment.

Should the tenderer not provide the material, or a satisfactory reason as to why it cannot be provided, by the time for submission stated in the employer's request, the employer may regard the tender offer as non-responsive.

C.2.18.2 Dispose of samples of materials provided for evaluation by the employer, where required.

C.2.19 Inspections, tests and analysis

Provide access during working hours to premises for inspections, tests and analysis as provided for in the tender data.

C.2.20 Submit securities, bonds and policies

If requested, submit for the employer's acceptance before formation of the contract, all securities, bonds,

guarantees, policies and certificates of insurance required in terms of the conditions of contract identified in the contract data.

C.2.21 Check final draft

Check the final draft of the contract provided by the employer within the time available for the employer to issue the contract.

C.2.22 Return of other tender documents

If so instructed by the employer, return all retained tender documents within twenty-eight (28) days after the expiry of the validity period stated in the tender data.

C.2.23 Certificates

Include in the tender submission or provide the employer with any certificates as stated in the tender data.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.3 The employer's undertakings

C.3.1 Respond to requests from the tenderer

C.3.1.1 Unless otherwise stated in the tender Data, respond to a request for clarification received up to five (5) working days before the tender closing time stated in the Tender Data and notify all tenderers who collected tender documents.

C.3.1.2 Consider any request to make a material change in the capabilities or formation of the tendering entity (or both) or any other criteria which formed part of the qualifying requirements used to prequalify a tenderer to submit a tender offer in terms of a previous procurement process and deny any such request if as a consequence:

- a) an individual firm, or a joint venture as a whole, or any individual member of the joint venture fails to meet any of the collective or individual qualifying requirements;
- b) the new partners to a joint venture were not prequalified in the first instance, either as individual firms or as another joint venture; or
- c) in the opinion of the Employer, acceptance of the material change would compromise the outcome of the prequalification process.

C.3.2 Issue Addenda

If necessary, issue addenda that may amend or amplify the tender documents to each tenderer during the period from the date that tender documents are available until three (3) working days before the tender closing time stated in the Tender Data. If, as a result a tenderer applies for an extension to the closing time stated in the Tender Data, the Employer may grant such extension and, shall then notify all tenderers who collected tender documents.

C.3.3 Return late tender offers

Return tender offers received after the closing time stated in the Tender Data, unopened, (unless it is necessary to open a tender submission to obtain a forwarding address), to the tenderer concerned.

C.3.4 Opening of tender submissions

C.3.4.1 Unless the two-envelope system is to be followed, open valid tender submissions in the presence of tenderers' agents who choose to attend at the time and place stated in the tender data. Tender submissions for which acceptable reasons for withdrawal have been submitted will not be opened.

C.3.4.2 Announce at the meeting held immediately after the opening of tender submissions, at a venue indicated in the tender data, the name of each tenderer whose tender offer is opened and, where applicable, the total of his prices, number of points claimed for its BBEE status level and time for completion for the main tender offer only.

C.3.4.3 Make available the record outlined in C.3.4.2 to all interested persons upon request.

C.3.5 Two-envelope system

C.3.5.1 Where stated in the tender data that a two-envelope system is to be followed, open only the technical proposal of valid tenders in the presence of tenderers' agents who choose to attend at the time and place stated in the tender data and announce the name of each tenderer whose technical proposal is opened.

C.3.5.2 Evaluate functionality of the technical proposals offered by tenderers, then advise tenderers who remain in contention for the award of the contract of the time and place when the financial proposals will be opened. Open only the financial proposals of tenderers, who score in the functionality evaluation more than the minimum number of points for functionality stated in the tender data, and announce the score obtained for the technical proposals and the total price and any points claimed on BBEE status level. Return unopened financial proposals to tenderers whose technical proposals failed to achieve the minimum number of points for functionality.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C.3.6 Non-disclosure

Not disclose to tenderers, or to any other person not officially concerned with such processes, information relating to the evaluation and comparison of tender offers, the final evaluation price and recommendations for the award of a contract, until after the award of the contract to the successful tenderer.

C.3.7 Grounds for rejection and disqualification

Determine whether there has been any effort by a tenderer to influence the processing of tender offers and instantly disqualify a tenderer (and his tender offer) if it is established that he engaged in corrupt or fraudulent practices.

C.3.8 Test for responsiveness

C.3.8.1 Determine, after opening and before detailed evaluation, whether each tender offer properly received:

- a) complies with the requirements of these Conditions of Tender,
- b) has been properly and fully completed and signed, and
- c) is responsive to the other requirements of the tender documents.

C.3.8.2 A responsive tender is one that conforms to all the terms, conditions, and specifications of the tender documents without material deviation or qualification. A material deviation or qualification is one which, in the Employer's opinion, would:

- a) detrimentally affect the scope, quality, or performance of the works, services or supply identified in the Scope of Work,
- b) significantly change the Employer's or the tenderer's risks and responsibilities under the contract, or
- c) affect the competitive position of other tenderers presenting responsive tenders, if it were to be rectified.

Reject a non-responsive tender offer, and not allow it to be subsequently made responsive by correction or withdrawal of the non-conforming deviation or reservation.

C.3.9 Arithmetical errors, omissions and discrepancies

C.3.9.1 Check responsive tenders for discrepancies between amounts in words and amounts in figures. Where there is a discrepancy between the amounts in figures and the amount in words, the amount in words shall govern.

C.3.9.2 Check the highest ranked tender or tenderer with the highest number of tender evaluation points after the evaluation of tender offers in accordance with C.3.11 for:

- a) the gross misplacement of the decimal point in any unit rate;
- b) omissions made in completing the pricing schedule or bills of quantities; or
- c) arithmetic errors in:
 - (i) line item totals resulting from the product of a unit rate and a quantity in bills of quantities or schedules of prices; or
 - (ii) the summation of the prices.

C.3.9.3 Notify the tenderer of all errors or omissions that are identified in the tender offer and either confirm the tender offer as tendered or accept the corrected total of prices.

C.3.9.4 Where the tenderer elects to confirm the tender offer as tendered, correct the errors as follows:

- a) If bills of quantities or pricing schedules apply and there is an error in the line item total resulting from the product of the unit rate and the quantity, the line item total shall govern and the rate shall be corrected. Where there is an obviously gross misplacement of the decimal point in the unit rate, the line item total as quoted shall govern, and the unit rate shall be corrected.
- b) Where there is an error in the total of the prices either as a result of other corrections required by this checking process or in the tenderer's addition of prices, the total of the prices shall govern and the

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

tenderer will be asked to revise selected item prices (and their rates if bills of quantities apply) to achieve the tendered total of the prices.

C.3.10 Clarification of a tender offer

Obtain clarification from a tenderer on any matter that could give rise to ambiguity in a contract arising from the tender offer.

C.3.11 Evaluation of tender offers

The Standard Conditions of Tender standardize the procurement processes, methods and procedures from the time that tenders are invited to the time that a contract is awarded. They are generic in nature and are made project specific through choices that are made in developing the Tender Data associated with a specific project.

Conditions of tender are by definition the document that establishes a tenderer's obligations in submitting a tender and the employer's undertakings in soliciting and evaluating tender offers. Such conditions establish the rules from the time a tender is advertised to the time that a contract is awarded and require employers to conduct the process of offer and acceptance in terms of a set of standard procedures.

The CIDB Standard Conditions of Tender are based on a procurement system that satisfies the following system requirements:

Requirement	Qualitative interpretation of goal
Fair	The process of offer and acceptance is conducted impartially without bias, providing simultaneous and timely access to participating parties to the same information.
Equitable	Terms and conditions for performing the work do not unfairly prejudice the interests of the parties.
Transparent	The only grounds for not awarding a contract to a tenderer who satisfies all requirements are restrictions from doing business with the employer, lack of capability or capacity, legal impediments and conflicts of interest
Competitive	The system provides for appropriate levels of competition to ensure cost effective and best value outcomes.
Cost effective	The processes, procedures and methods are standardized with sufficient flexibility to attain best value outcomes in respect of quality, timing and price, and least resources to effectively manage and control procurement processes.

The activities associated with evaluating tender offers are as follows:

- a) Open and record tender offers received
- b) Determine whether or not tender offers are complete
- c) Determine whether or not tender offers are responsive
- d) Evaluate tender offers
- e) Determine if there are any grounds for disqualification
- f) Determine acceptability of preferred tenderer
- g) Prepare a tender evaluation report
- h) Confirm the recommendation contained in the tender evaluation report

C.3.11.1 General

The employer must appoint an evaluation panel of not less than three persons conversant with the proposed scope of works to evaluate each responsive tender offer using the tender evaluation methods and associated evaluation criteria and weightings that are specified in the tender data.

C.3.12 Insurance provided by the employer

If requested by the proposed successful tenderer, submit for the tenderer's information the policies and / or certificates of insurance which the conditions of contract identified in the contract data, require the employer to provide.

C.3.13 Acceptance of tender offer

Accept the tender offer; if in the opinion of the employer, it does not present any risk and only if the tenderer:

- a) is not under restrictions, or has principals who are under restrictions, preventing participating in the employer's procurement;

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

- b) can, as necessary and in relation to the proposed contract, demonstrate that he or she possesses the professional and technical qualifications, professional and technical competence, financial resources, equipment and other physical facilities, managerial capability, reliability, experience and reputation, expertise and the personnel, to perform the contract;
- c) has the legal capacity to enter into the contract;
- d) is not; insolvent, in receivership, under Business Rescue as provided for in chapter 6 of the Companies Act No. 2008, bankrupt or being wound up, has his/her affairs administered by a court or a judicial officer, has suspended his/her business activities or is subject to legal proceedings in respect of any of the foregoing;
- e) complies with the legal requirements, if any, stated in the tender data; and
- f) is able, in the opinion of the employer, to perform the contract free of conflicts of interest.

C.3.14 Prepare contract documents

C.3.14.1 If necessary, revise documents that shall form part of the contract and that were issued by the employer as part of the tender documents to take account of:

- a) addenda issued during the tender period,
- b) inclusion of some of the returnable documents and
- c) other revisions agreed between the employer and the successful tenderer.

C.3.14.2 Complete the schedule of deviations attached to the form of offer and acceptance, if any.

C.3.15 Complete adjudicator's contract

Unless alternative arrangements have been agreed or otherwise provided for in the contract, arrange for both parties to complete formalities for appointing the selected adjudicator at the same time as the main contract is signed.

C.3.16 Registration of the award

An employer must, within twenty-one (21) working days from the date on which a contractor's offer to perform a construction works contract is accepted in writing by the employer, register and publish the award on the cidb Register of Projects.

C.3.17 Provide copies of the contracts

Provide to the successful tenderer the number of copies stated in the Tender Data of the signed copy of the contract as soon as possible after completion and signing of the form of offer and acceptance.

C.3.18 Provide written reasons for actions taken

Provide upon request written reasons to tenderers for any action that is taken in applying these conditions of tender but withhold information which is not in the public interest to be divulged, which is considered to prejudice the legitimate commercial interests of tenderers or might prejudice fair competition between tenderers.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND
CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

PART T2: RETURNABLE DOCUMENTS

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

SECTION T2.1: LIST OF RETURNABLE DOCUMENTS

THE TENDERER MUST SUBMIT THE FOLLOWING DOCUMENTS WITH THIS TENDER. IF THE DOCUMENTS ARE NOT INCLUDED IN THE DOCUMENT, THE DEPARTMENT WILL NOT CONSIDER THIS TENDER.

Clause referred to in Standard Conditions of Tender	Document
C.2.1	Tenderers must provide their CRS Numbers of the registered Contractor as well JV Partner*. CRS numbers of Tenderers or JV partners needs to be filled in below: <u>Tenderer/Leading JV Partner</u> CRS Number : _____ Name of Company: _____ <u>JV Partner</u> CRS Number : _____ Name of Company: _____ <u>JV Partner</u> CRS Number : _____ Name of Company: _____ *NB: Recent printout from CIDB website indicating the CRS number will also be accepted. All contractors, even tendering in JV, must be registered with CIDB. The lead partner has a contractor grading designation of not lower than one level below the required grading designation of 6CE of construction work.
C.2.3	Attendance of the Compulsory Tender Clarification meeting as stipulated.
C.2.4	Form of offer must be completed and signed by duly authorized person and witnessed.
C.2.3	Tampering with or taking apart the bound document is strictly prohibited. All additional documentation must be stapled into the tender document or attached in a separate file." Corrections in terms of price must not be made by means of a correction fluid such as Tipp-Ex or similar product.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

	"In the event of mistakes having been made on tender document it must be crossed out in ink and be accompanied by an initial at each and every price alteration".
C.2.4	The Tenderer submits a duly and dated relevant resolution of their members or their board of directors, as the case may be, on their company letterhead. In the case of a sole proprietor of a single member in a company, it must be clearly indicated in a company letterhead. In the case of a sole proprietor of a single member in a company, it must be clearly indicated in a company letterhead. In the case of a Joint Venture submitting a tender, include a resolution of each company of the Joint Venture together with a resolution signed by all members of the Joint Venture authorizing a member of the Joint Venture to sign the documents on behalf of the Joint Venture.
C.2.5	Bidders must ensure compliance with their tax obligations. Bidders are required to submit their unique personal identification number (PIN) issued by SARS to enable the organ of state to view the taxpayer's profile and tax status. Application for tax compliance status (TCS) or pin may also be made via e-filing. In order to use this provision, taxpayers will need to register with SARS as e-filers through the website www.sars.gov.za. Bidders may also submit a printed TCS together with the bid. In bids where Consortia / Joint Ventures / Sub-contractors are involved; each party must submit a separate proof of TCS / PIN / CSD number. Where no TCS is available but the bidder is registered on the central supplier database (CSD), a CSD number must be provided.
C.2.6	The Tenderer must acknowledge and sign the record of addenda page, and submitted the addendum or addenda, in the event that the addendum or addenda has been issued
C.2.7	The Tenderer submits letter from the bank or a FAIS registered or NCR registered financial institution with whom he/she has made the necessary arrangements, to the effect that the said institution will be prepared to provide the required performance guarantee.
C.2.8	N/A
C.2.9	The Tenderer is registered and in good standing with respect to Compensation for Occupational Injuries and Diseases Act (COIDA) with Department of Labour or with a licensed compensation insurer. The Tenderer must submit the letter of good standing for built environment projects. In the event of the Tenderer being a joint venture/consortium, the letter of good standing for built environment projects of the individual members must also be provided

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

THE TENDERERS ARE ENCOURAGED TO REGISTER AND SUBMIT THE FOLLOWING NATIONAL TREASURY CENTRAL SUPPLIER DATABASE (CSD) DETAILS WITH THIS TENDER.

Document

Tenderers shall provide their **CSD Supplier Number (Master Registration Number)** and **Tax Compliance PIN Number** in the space provided below:

NB: In cases where a bidder intends to form a Joint Venture, the CSD Supplier Number (Master Registration Number) and Tax Compliance PIN shall also be provided in the space provided below, i.e., the lead partner and Joint Venture partner/s.

If any sub-contractors are proposed their CSD Supplier Number (Master Registration Number) and Tax Compliance PIN numbers shall be provided in Form A.

If the documents are not included in the document, the tender will be regarded as being NON-RESPONSIVE.

Tenderer/Leading JV Partner

Name of Company:

CSD Supplier Number: (Master
Registration Number)

Tax Compliance PIN number:

JV Partner 1

Name of Company:

CSD Supplier Number: (Master
Registration Number)

Tax Compliance PIN number:

JV Partner 2

Name of Company:

CSD Supplier Number: (Master
Registration Number)

Tax Compliance PIN number:

***NB: All contractors, even tendering in JV, must be registered with National Treasury Central Supplier Database**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

- SECTION T2.1.1: FORM A: SCHEDULE OF PROPOSED SUBCONTRACTORS**
- SECTION T2.1.2: FORM B: PREFERENCE POINTS CLAIM FORM IN TERMS OF THE PREFERENTIAL PROCUREMENT REGULATIONS 2017 (SBD 6.1)**
- SECTION T2.1.3: FORM C: RECORD OF ADDENDA TO TENDER DOCUMENTS**
- SECTION T2.1.4: FORM D: AUTHORITY OF SIGNATORY**
- SECTION T2.1.5: FORM E: STATUS OF CONCERN SUBMITTING TENDER**
- SECTION T2.1.6: FORM F: BIDDERS DISCLOSURE (SBD 4)**
- SECTION T2.1.7: FORM G: SCHEDULE OF PLANT AND EQUIPMENT**
- SECTION T2.1.8: FORM H: SCHEDULE OF WORK CARRIED OUT BY THE TENDERER**
- SECTION T2.1.9: FORM I: CERTIFICATE OF TENDERER'S VISIT TO THE SITE**
- SECTION T2.1.10: FORM J: KEY-PERSONNEL/ SUPERVISORY AND MANAGEMENT STAFF**
- SECTION T2.1.11: FORM K: COMPLIANCE WITH OHSA (ACT 85 OF 1993)**
- SECTION T2.2.12: FORM L: CSD SUPPLIER NO AND TAX COMPLIANCE PIN**
- SECTION T2.1.13: FORM M: PRELIMINARY PROGRAMME**
- SECTION T2.1.14: FORM N: ESTIMATED MONTHLY EXPENDITURE**
- SECTION T2.1.15: FORM O: ALTERATIONS BY TENDERER**
- SECTION T2.1.16: FORM P: FINANCIAL REFERENCES**
- SECTION T2.1.17: FORM Q: SUPPLIER MAINTENANCE FORM**
- SECTION T2.1.18: FORM R: COMPENSATION FOR OCCUPATIONAL INJURIES AND DISEASES ACT (COIDA)**
- SECTION T2.1.19: FORM S: LETTER OF INTENT FOR PERFORMANCE GUARANTEES**
- SECTION T2.1.20: FORM T: DECLARATION CERTIFICATE FOR LOCAL LABOUR PARTICIPATION**
- SECTION T2.1.21: FORM U: COMPULSORY ENTERPRISE QUESTIONNAIRE**

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

RETURNABLE SCHEDULES

SECTION T2.1.1: FORM A: SCHEDULE OF PROPOSED SUBCONTRACTORS

We notify you that it is our intention to employ the following Sub-contractors for work in this contract.

If we are awarded a contract, we agree that this notification does not change the requirement for us to submit the names of proposed Subcontractors in accordance with requirements in the contract for such appointments. If there are no such requirements in the contract, then your written acceptance of this list shall be binding between us. The contractor is to obtain approval if he/she intends to change the submitted list of Sub-contractors.

In Bids where sub-contractors are involved, each party must submit a separate proof of TCS / PIN / CSD number together with the bid. Where no TCS is available but the sub-contractor is registered on the Central Supplier Database (CSD), a CSD number must be provided. (Refer to Clause F2.28) Alternatively, where a subcontractor is not yet registered on the National Treasury CSD, submission of a Valid Tax Clearance Certificate together with the bid is compulsory. (Refer to Clause F2.28)

1. Will any portion of the contract be sub-contracted? Yes ☐ / No ☐
2. If yes, indicate:
 - (i) The name of the proposed sub-contractor, the nature and extent of the work to be sub-contracted and the previous experience with the sub-contractor in the table below.

	Name and address of the proposed Sub-contractor	Nature and extent of work	Previous experience with Sub-contractor
1.			
2.			
3.			
4.			

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- 3 What percentage of the contract will be sub-contracted, the B-BBEE status level of the sub-contractors and whether they are an EME/QSE, must be stated in the table below and specify, by ticking the appropriate box, if subcontracting with an enterprise in terms of Preferential Procurement Regulations, 2017:

Designated Group: An EME or QSE which is at last 51% owned by:											
Name of proposed Sub Contractor	% of the work that will be sub-contracted	B-BBEE status level of the sub-contractor	Black people	Black people who are youth	Black people who are women	Black people with disabilities	Black people living in rural or under-developed areas or townships	Cooperative owned by black people	Black people who are military veterans	Any EME	Any QSE
			EME	EME	EME	EME	EME	EME	EME	EME	EME
			QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE
			EME	EME	EME	EME	EME	EME	EME	EME	EME
			QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE
			EME	EME	EME	EME	EME	EME	EME	EME	EME
			QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE
			EME	EME	EME	EME	EME	EME	EME	EME	EME
			QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE
			EME	EME	EME	EME	EME	EME	EME	EME	EME
			QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE
			EME	EME	EME	EME	EME	EME	EME	EME	EME
			QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE	QSE

Signature of person authorised to sign the tender:

Date:

Contractor
 Witness 1
 Witness 2
 Employer
 Witness 1
 Witness 2

SECTION T2.1.2: FORM B: PREFERENCE POINTS CLAIM FORM IN TERMS OF THE PREFERENTIAL PROCUREMENT REGULATIONS 2022: (SBD 6.1)

This preference form must form part of all tenders invited. It contains general information and serves as a claim form for preference points for specific goals.

NB: BEFORE COMPLETING THIS FORM, TENDERERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF THE TENDER AND PREFERENTIAL PROCUREMENT REGULATIONS, 2022

1. DEFINITIONS

- (a) **“tender”** means a written offer in the form determined by an organ of state in response to an invitation to provide goods or services through price quotations, competitive tendering process or any other method envisaged in legislation;
- (b) **“price”** means an amount of money tendered for goods or services, and includes all applicable taxes less all unconditional discounts;
- (c) **“rand value”** means the total estimated value of a contract in Rand, calculated at the time of tender invitation, and includes all applicable taxes;
- (d) **“tender for income-generating contracts”** means a written offer in the form determined by an organ of state in response to an invitation for the origination of income-generating contracts through any method envisaged in legislation that will result in a legal agreement between the organ of state and a third party that produces revenue for the organ of state, and includes, but is not limited to, leasing and disposal of assets and concession contracts, excluding direct sales and disposal of assets through public auctions;
- (e) **“the Act”** means the Preferential Procurement Policy Framework Act, 2000 (Act No. 5 of 2000); and
- (f) **“Historically Disadvantaged individuals”** means a person historically disadvantaged by unfair discrimination on the basis of race: Provided that a person historically disadvantaged on the basis of race refers to Africans, Coloureds, Indians and people of Chinese descent who are South African citizens by birth or descent; or who became citizens of the Republic of South Africa by Naturalisation -
 - Before 27 April 1994; or
 - On or after 27 April 1994 and who would have been entitled to acquire citizenship by naturalization prior to that date.

2. GENERAL CONDITIONS

2.1 The following preference point systems are applicable to invitations to tender:

- the 80/20 system for requirements with a Rand value of up to R50 000 000 (all applicable taxes included); and

2.2 To be completed by the organ of state

- a) The applicable preference point system for this tender is the 80/20 preference point system.
- b) 80/20 preference point system will be applicable in this tender. The lowest/ highest acceptable tender will be used to determine the accurate system once tenders are received.

2.3 Points for this tender (even in the case of a tender for income-generating contracts) shall be awarded for:

- (a) Price; and
- (b) Specific Goals.

2.4 To be completed by the organ of state:

The maximum points for this tender are allocated as follows:

	POINTS
PRICE	80
SPECIFIC GOALS	20
Total points for Price and SPECIFIC GOALS	100

- 2.5 Failure on the part of a tenderer to submit proof or documentation required in terms of this tender to claim points for specific goals with the tender, will be interpreted to mean that preference points for specific goals are not claimed.
- 2.6 Tenderers that fail to claim points for specific goals or that fail to fully complete the table in paragraph 2.12 below, will not be awarded points for specific goals.
- 2.7 Tenderers that make a calculation error when claiming points as per the table in paragraph 2.12 below, will not be awarded points for specific goals. Please take note of the examples on how to calculate points for specific goals as per paragraph 2.12 below.
- 2.8 Tenderers that fail to submit the correct SBD 6.1 form as issued by the Department of Agriculture, Land Reform and Rural Development, will not be awarded points for specific goals.
- 2.9 The organ of state reserves the right to require of a tenderer, either before a tender is adjudicated or at any time subsequently, to substantiate any claim in regard to preferences, in any manner required by the organ of state.

2.10 Tenderers who wish to claim points in terms of the table in paragraph 2.12 below need to provide proof for each point claimed as guided below:

2.10.1 Historically Disadvantaged individuals (HDI):

- **Attach a copy of Identity Document (ID) and company registration document.**

2.10.2 Who is female:

- **Attach a copy of Identity Document (ID) and company registration document.**

2.10.3 Who has a disability:

- **Attach a certified copy or original doctor's letter confirming the disability.**

2.10.4 Who is youth (a person that is not older than 35 years on the closing date of a bid):

- **Attach a copy of Identity Document (ID) and company registration document.**

2.11 The Department will use the Central Supplier Database and documents submitted by the tenderer to verify the points claimed for specific goals.

2.12 **Specific goals for the tender and points claimed are indicated per the table below.**

3. (Note to organs of state: Where either the 90/10 or 80/20 preference point system is applicable, corresponding points must also be indicated as such.

Note to tenderers: The tenderer must indicate how they claim points for each preference point system.)

The specific goals allocated points in terms of this tender	Number of points allocated (80/20 system)	Percentage ownership equity (To be completed by the tenderer)	Number of points claimed (80/20 system) (To be completed by the tenderer)
I. HDI	8		
II. Who is female	5		
III. Who has a disability	2		
IV. Specific goal: Who is youth	2		
V. Specific goal: Locality	3		

The number of points claimed for specific goals, are calculated as follow:

- (I) A maximum of 8 points may be allocated to tenderers who had no franchise in national elections before the 1983 and 1993 Constitution, on the following basis:
 - **Percentage ownership equity** x 8 ÷ 100 = number of points claimed.
- (II) A maximum of 5 points may be allocated for to tenderers who is female, on the following basis:
 - **Percentage ownership equity** x 5 ÷ 100 = number of points claimed.
- (III) A maximum of 2 points may be allocated to tenderers who has a disability, on the following basis:
 - **Percentage ownership equity** x 2 ÷ 100 = number of points claimed.
- (IV) A maximum of 2 points may be allocated to tenderers who are youth, on the following basis:
 - **Percentage ownership equity** x 2 ÷ 100 = number of points claimed.
- (V) A maximum of 3 points may be allocated to tenderers for locality, on the following basis:
 - **Percentage ownership equity** x 3 ÷ 100 = number of points claimed.

2.13 It is important to note that failure by a tenderer to complete the table in paragraph 2.12 in full, will result in points for specific goals not to be allocated.

3. FORMULAE FOR PROCUREMENT OF GOODS AND SERVICES

3.1. POINTS AWARDED FOR PRICE

3.1.1 THE 80/20 PREFERENCE POINT SYSTEMS

A maximum of 80 points is allocated for price on the following basis:

80/20

$$Ps = 80 \left(1 - \frac{Pt - Pmin}{Pmin} \right)$$

Where

Ps = Points scored for price of tender under consideration

Pt = Price of tender under consideration

Pmin = Price of lowest acceptable tender

3.2. FORMULAE FOR DISPOSAL OR LEASING OF STATE ASSETS AND INCOME GENERATING PROCUREMENT

3.2.1. POINTS AWARDED FOR PRICE

A maximum of 80 points is allocated for price on the following basis:

80/20

$$Ps = 80 \left(1 + \frac{Pt - P_{max}}{P_{max}} \right)$$

Where

Ps = Points scored for price of tender under consideration

Pt = Price of tender under consideration

Pmax = Price of highest acceptable tender

4. POINTS AWARDED FOR SPECIFIC GOALS

- 4.1. In terms of Regulation 4(2); 5(2); 6(2) and 7(2) of the Preferential Procurement Regulations, preference points must be awarded for specific goals stated in the tender. For the purposes of this tender the tenderer will be allocated points based on the goals stated in the table in paragraph 2.12 above as may be supported by proof/ documentation stated in the conditions of this tender.
- 4.2. In cases where organs of state intend to use Regulation 3(2) of the Regulations, which states that, if it is unclear whether the 80/20 or 90/10 preference point system applies, an organ of state must, in the tender documents, stipulate in the case of—
- (a) an invitation for tender for income-generating contracts, that either the 80/20 or 90/10 preference point system will apply and that the highest acceptable tender will be used to determine the applicable preference point system; or
 - (b) any other invitation for tender, that either the 80/20 or 90/10 preference point system will apply and that the lowest acceptable tender will be used to determine the applicable preference point system,
- then the organ of state must indicate the points allocated for specific goals for both the 90/10 and 80/20 preference point system.
- 4.3 A consortium or joint venture may, based on the percentage of the contract value managed or executed by their members, be entitled to claim points in respect of specific contract participation goals.
- 4.4 A tenderer will not be awarded points for HDI if it is indicated in the tender documents that such a tenderer intends sub-contracting more than 25% of the value of the contract to any other enterprise that does not qualify for the same number or more points for equity ownership.

- 4.5 A tenderer awarded a contract as a result of preference for contracting with, or providing equity ownership to a HDI, may not subcontract more than 25% of the value of the contract to a tenderer who is not a HDI or does not qualify for the same number or more preference for equity ownership.

5. SUB-CONTRACTING

- 5.1 Will any portion of the contract be sub-contracted?
(***Tick applicable box***)

YES	☐	NO	☐
-----	--------------------------	----	--------------------------

- 5.1.1 If yes, indicate:

- i) What percentage of the contract will be subcontracted: %
- ii) The name of the sub-contractor:
- iii) Points claimed for HDI by the sub-contractor:

6. DECLARATION WITH REGARD TO COMPANY/FIRM

6.1. Name of company/firm:

6.2. Company registration number:

6.3. TYPE OF COMPANY/ FIRM

Partnership/Joint Venture / Consortium
One-person business/sole propriety
Close corporation
Public Company
Personal Liability Company
(Pty) Limited
Non-Profit Company
State Owned Company

[TICK APPLICABLE BOX]

- 6.4. I, the undersigned, who is duly authorised to do so on behalf of the company/firm, certify that the points claimed, based on the specific goals as advised in the tender, qualifies the company/ firm for the preference(s) shown and I acknowledge that:

- i) The information furnished is true and correct;
- ii) The preference points claimed are in accordance with the General Conditions as indicated in paragraph 1 of this form;
- iii) In the event of a contract being awarded as a result of points claimed as shown in paragraphs 1.4 and 4.2, the contractor may be required to furnish documentary proof to the satisfaction of the organ of state that the claims are correct;

- iv) If the specific goals have been claimed or obtained on a fraudulent basis or any of the conditions of contract have not been fulfilled, the organ of state may, in addition to any other remedy it may have –
- (a) disqualify the person from the tendering process;
 - (b) recover costs, losses or damages it has incurred or suffered as a result of that person's conduct;
 - (c) cancel the contract and claim any damages which it has suffered as a result of having to make less favourable arrangements due to such cancellation;
 - (d) recommend that the tenderer or contractor, its shareholders and directors, or only the shareholders and directors who acted on a fraudulent basis, be restricted from obtaining business from any organ of state for a period not exceeding 10 years, after the *audi alteram partem* (hear the other side) rule has been applied; and
 - (e) forward the matter for criminal prosecution, if deemed necessary.

..... SIGNATURE(S) OF TENDERER(S)	
SURNAME AND NAME:	
DATE:	
ADDRESS:	

SECTION T2.1.3: FORM C: RECORD OF ADDENDA TO TENDER DOCUMENTS

We confirm that the following communications received from the Employer before the submission of this tender offer, amending the tender documents, have been taken into account in this tender offer:

Date		Title of Details
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		
9.		
10.		

Attach additional pages if more space is required.

Signature of person authorised to sign the tender:

Date:

SECTION T2.1.4: FORM D: AUTHORITY OF SIGNATORY

Signatories for companies, closed corporations and partnerships must establish their authority **BY ATTACHING TO THIS FORM, ON THEIR ORGANISATIONS'S LETTERHEAD STATIONERY**, a copy of the relevant resolution by their Board of Directors, Members or Partners, duly signed and dated.

An **EXAMPLE** is shown below for a COMPANY:

MABEL HOUSE (Pty) Ltd

By resolution of the Board of Directors taken on *20 May 2000*, *MR A.F JONES*

has been duly authorised to sign all documents in connection with Contract no CON 0005, and any contract which may arise therefrom, on behalf of *Mabel House (Pty) Ltd*.

SIGNED ON BEHALF OF THE COMPANY:

(Signature of Managing Director)

IN HIS CAPACITY AS:

Managing Director

DATE:

20 May 2000

SIGNATURE OF SIGNATORY:

(Signature of A.F Jones)

As witnesses:

1.

2.

Signature of person authorised to sign the tender:

Date:

SECTION T2.1.5: FORM E: STATUS OF CONCERN SUBMITTING TENDER
1. GENERAL

State whether the tenderer is a company, a closed corporation, a partnership or a one-man concern.
(Make an X in the appropriate space below)

Company ☐ Closed Corporation ☐ Partnership ☐

One-man concern ☐ Joint Venture ☐

2. INFORMATION TO BE PROVIDED

(Block letters)

2.1 If the tenderer is a Company:

- (a) Affix a certified copy of the Certificate of Incorporation to this page.
- (b) List the Directors.

2.2 If the tenderer is a Closed Corporation:

- (a) Affix a certified copy of the Founding Statement to this page.
- (b) List the Members.

2.3 If the tenderer is a Partnership:

List the partners.

2.4 If the tenderer is a One-man concern:

Provide the full name and ID number of the person.

2.5 If the tenderer is a Joint Venture:

- (a) Affix a certified copy of the Founding Statement of each partner of the JV to this page.
- (b) Affix JV agreement.

3. REGISTERED FOR VAT PURPOSES IN TERMS OF THE VALUE-ADDED TAX ACT, (Act Nr. 89 of 1991) (Make an X in the appropriate space below)

Yes ☐ / No ☐ Registration nr.:

Signature of person authorised to sign the tender:

Date:

SECTION T2.1.6: FORM F: BIDDERS DISCLOSURE (SBD 4)

1. PURPOSE OF THE FORM

Any person (natural or juristic) may make an offer or offers in terms of this invitation to bid. In line with the principles of transparency, accountability, impartiality, and ethics as enshrined in the Constitution of the Republic of South Africa and further expressed in various pieces of legislation, it is required for the bidder to make this declaration in respect of the details required hereunder.

Where a person/s are listed in the Register for Tender Defaulters and / or the List of Restricted Suppliers, that person will automatically be disqualified from the bid process.

2. BIDDER'S DECLARATION

2.1. Is the bidder, or any of its directors / trustees / shareholders / members / partners or any person having a controlling interest in the enterprise, employed by the state?.....YES/NO

2.1.1. If so, furnish particulars of the names, individual identity numbers, and, if applicable, state employee numbers of sole proprietor/ directors / trustees / shareholders / members/ partners or any person having a controlling interest in the enterprise, in table below.

Full Name	Identity Number	Name of State Institution

2.2. Do you, or any person connected with the bidder, have a relationship 1 the power, by one person or a group of persons holding the majority of the equity of an enterprise, alternatively, the person/s having the deciding vote or power to influence or to direct the course and decisions of the enterprise.

with any person who is employed by the procuring institution?.....YES/NO

2.2.1. If so, furnish particulars:

.....

.....

2.3. Does the bidder or any of its directors / trustees / shareholders / members / partners or any person having a controlling interest in the enterprise have any interest in any other related enterprise whether or not they are bidding for this contract?.....YES/NO

2.3.1. If so, furnish particulars:

.....

.....

3. DECLARATION

I,..... the undersigned (name).....
submitting the accompanying bid, do hereby make the following statements that I certify to be true and complete in every respect:

3.1. I have read and I understand the contents of this disclosure;

3.2. I understand that the accompanying bid will be disqualified if this disclosure is found not to be true and complete in every respect;

3.3. The bidder has arrived at the accompanying bid independently from, and without consultation, communication, agreement or arrangement with any competitor. However, communication between partners in a joint venture or consortium will not be construed as collusive bidding.

3.4. In addition, there have been no consultations, communications, agreements or arrangements with any competitor regarding the quality, quantity, specifications, prices, including methods, factors or formulas used to calculate prices, market allocation, the intention or decision to submit or not to submit the bid, bidding with the intention not to win the bid and conditions or delivery particulars of the products or services to which this bid invitation relates.

3.5. The terms of the accompanying bid have not been, and will not be, disclosed by the bidder, directly or indirectly, to any competitor, prior to the date and time of the official bid opening or of the awarding of the contract.

3.6. There have been no consultations, communications, agreements or arrangements made by the bidder with any official of the procuring institution in relation to this procurement process prior to and during the bidding process except to provide clarification on the bid submitted where so required by the institution; and the bidder was not involved in the drafting of the specifications or terms of reference for this bid.

3.7. I am aware that, in addition and without prejudice to any other remedy provided to combat any restrictive practices related to bids and contracts, bids that are suspicious will be reported to the Competition Commission for investigation and possible imposition of administrative penalties in terms of section 59 of the Competition Act No 89 of 1998 and or may be reported to the National Prosecuting Authority (NPA) for criminal investigation and or may be restricted from conducting business with the public sector for a period not exceeding ten (10) years in terms of the Prevention and Combating of Corrupt Activities Act No 12 of 2004 or any other applicable legislation.

**I CERTIFY THAT THE INFORMATION FURNISHED IN PARAGRAPHS 1, 2 and 3 ABOVE IS CORRECT.
I ACCEPT THAT THE STATE MAY REJECT THE BID OR ACT AGAINST ME IN TERMS OF PARAGRAPH 6 OF PFMA SCM INSTRUCTION 03 OF 2021/22 ON PREVENTING AND COMBATING ABUSE IN THE SUPPLY CHAIN MANAGEMENT SYSTEM SHOULD THIS DECLARATION PROVE TO BE FALSE.**

Signature

Date

Position

Name of Bidder

SECTION T2.1.7: FORM G: SCHEDULE OF PLANT AND EQUIPMENT

The following are lists of major items of relevant equipment that I/we presently own or lease and will have available for this contract or will acquire or hire for this contract if my/our tender is accepted.

- (a) Details of major equipment that is owned by and immediately available for this contract.
Proof of ownership must be attached.

Quantity	Description, size, capacity, etc.

Attach additional pages if more space is required.

- (b) Details of major equipment that will be hired, or acquired for this contract if my/our tender is acceptable.
Proof of lease agreement must be attached or a letter of intent from a hiring company.

Quantity	Description, size, capacity, etc.

Attach additional pages if more space is required.

Signature of person authorised to sign the tender:

Date:

SECTION T2.1.8: FORM H: SCHEDULE OF WORK CARRIED OUT BY THE TENDERER

The tenderer shall list in the spaces provided below the successfully completed projects of similar scope, nature and size in the past 5 years. This information shall be deemed to be material to the award of this tender.

Employer (Name, Tel No, Fax No)	Consulting Engineer (Name, Tel No, Fax No)	Nature Of Work	Value Of Work	Year Completed
Completed				

Signature of person authorised to sign the tender:

Date:

SECTION T2.1.9: FORM I: CERTIFICATE OF TENDERER'S VISIT TO THE SITE

This is to certify that I,

Representative of (Tenderer).....

Of (address)

.....

.....

Telephone No:

Fax No:

Visited and carefully examined the Site on the day of 20

In the company of (Engineer's representative)

Signature (Tenderer's Representative)

Signature (Engineer's Representative)

SECTION T2.1.10: FORM J: KEY-PERSONNEL/ SUPERVISORY AND MANAGEMENT STAFF

The Tenderer shall, submit the name of all supervisory staff that will be employed to supervise Contract. **Please attach CV**. The Tenderer shall also include an organogram of the project team and the company structure.
NB: No points will be awarded if the bidder has not attached CV)

1. Position	Site Agent
Name	
Indicate Years of Experience as a Site Agent	
Duties and List of duties as a Site Agent	
Currently Employed by Tenderer (Y/N)	
Signature	
2. Position	Foreman
Name	
Indicate Years of Experience as a Foreman	
Duties and List of duties as a Foreman	
Currently Employed by Tenderer (Y/N)	
Signature	

SECTION T2.1.11: FORM K: COMPLIANCE WITH OHSA (ACT 85 OF 1993)

Tenderers are required to satisfy the Employer and the Engineer as to their ability and available resources to comply with the above by answering the following questions and providing the relevant information required below.

1. Is the Contractor familiar with the OHSA (ACT 85 of 1993) and its Regulations? Yes ☐ / No ☐

2. Who will prepare the Contractor's Health and Safety Plan? (Section T2.2.18 – Form R) (Provide a copy of the person/s curriculum vitae/s or company profile). Yes ☐ / No ☐

3. Does the Contractor have a health and safety policy? (if yes, provide a copy). How is this policy communicated to all employees? Yes ☐ / No ☐

4. Does the Contractor keep records of safety aspects of each construction site? If yes, what records are kept? Yes ☐ / No ☐

5. Does the Contractor conduct monthly safety meetings? If yes, who is the chairperson of the meeting, and who attend these meetings? Yes ☐ / No ☐

6. Does the Contractor have a safety officer in his employment, responsible for the overall safety of his company? Yes ☐ / No ☐
 If yes, please explain his duties and provide a copy of his CV.

7. Does the Contractor have trained first aid employees? If yes, indicate, who. Yes ☐ / No ☐

8. Does the Contractor have a safety induction training programme in place? (If yes, provide a copy) Yes ☐ / No ☐

Signature of person authorised to sign the tender:

Date:

SECTION T2.1.12: FORM L: CSD SUPPLIER NO AND TAX COMPLIANCE PIN

Bidders registered on the **National Treasury Central Supplier Database (CSD)** are required to submit their unique **Personal Identification Number (PIN)** issued by SARS in the space provided below as stipulated in Clause F2.28.

Bidders may also submit a **printed TCS** together with the bid.

In bids where Consortia / Joint Ventures / Sub-contractors are involved, each party **must** submit a separate proof of **TCS / PIN / CSD** number.

Where no TCS is available but the bidder is registered on the Central Supplier Database (CSD), a **CSD number** must be provided

Alternatively the tenderer must submit a valid tax clearance certificate together with the Bid, including Valid Tax Clearance Certificates for the Joint Venture partner/s and Subcontractors proposed.

The certificates may be stapled into the tender document without taking the tender document apart or may be attached in a separate file to the tender document.

If the documents are not included in the document, the tender will be regarded as being NON-RESPONSIVE.

Tenderer/Leading JV Partner

Name of Company:

CSD Supplier Number: (Master
Registration Number)

Tax Compliance PIN number:

JV Partner 1

Name of Company:

CSD Supplier Number: (Master
Registration Number)

Tax Compliance PIN number:

JV Partner 2

Name of Company:

CSD Supplier Number: (Master
Registration Number)

Tax Compliance PIN number:

***NB: All contractors, even tendering in JV, must be registered with National Treasury Central Supplier Database**

SECTION T2.1.13: FORM M: PRELIMINARY PROGRAMME

The Tenderer shall attach a preliminary programme reflecting the proposed sequence and tempo of execution of the various activities comprising the work for this Contract. The programme shall be in accordance with the information supplied in the Contract, requirements of the Project Specifications and with all other aspects of the Tender.

Note: The programme must be based on the completion time as specified in the Contract Data. (No points will be awarded to the bidder if a detailed program is not attached)

SECTION T2.1.14: FORM N: ESTIMATED MONTHLY EXPENDITURE

The tenderer shall, in the table below, state the estimated cash flow on the contract based on his preliminary programme, his tendered unit rates and his submission of payment certificates to the Employer. Amounts for Contract Price Adjustment shall not be included.

[illegible]

From what sources will you fund the above amount (e.g. funds internally available, bank overdraft, loan, partner (his source), etc.)

.....

.....

.....

Signature of person authorised to sign the tender:

Date:

[illegible]

Date:

SECTION T2.1.16: FORM P: FINANCIAL REFERENCES
Financial Statements

I/We agree, if required, to furnish an audited copy of the latest set of financial statements together with my/our Directors' and Auditors' report for consideration by the Employer.

Details of Company's Bank

I/We hereby authorise the Employer/Engineer to approach all or any of the following banks for the purposes of obtaining a financial reference:

DESCRIPTION OF BANK DETAIL	BANK DETAILS APPLICABLE TO TENDERER'S HEAD OFFICE
Name of tenderer	
Name of account holder at Bank	
Name of bank	
Branch name	
Branch code	
Street address	
Postal address	
Name of manager	
Telephone number	
Fax number	
Account number	
Number of years above account has been with bank	
Credit facilities available (state amount)	

Tenderer's Tax Details

Tenderer's VAT vendor registration number:

Tenderer's SARS tax reference number:

OFFICE:

1/We understand that the Department will not assume responsibility for any delayed payments, as a result of incorrect information supplied.

Page 23 of

Supplier Account Details

(Please note that this account MUST be in the name of the supplier. No 3rd party payments allowed).

Account Name

Account Number

Branch Name

Branch Number

Account Type ☐ Cheque Account
☐ Savings Account
☐ Transmission Account
☐ Bond Account
☐ Other (Please Specify)

ID Number

Passport Number

Company Registration Number

*CC Registration

*Please include CC/CK where applicable

Practise Number

Bank stamp

It is hereby confirmed that this details have been verified against the following screens

ABSA-CIF screen

FNB-Hogans system on the CIS4

STD Bank-Look-up-screen

Nedbank- Banking Platform under the Client Details Tab

When the bank stamps this entity maintenance form they confirm that all the information completed by the entity is correct.

Contact Details

Business

Area Code Telephone Number Extension

Home

Area Code Telephone Number Extension

Fax

Area Code Fax Number

Cell

Cell Code Cell Number

Email Address

Contact Person:

Supplier Signature Regional Office Sender

Print Name Print Name

Rank

Date (dd/mm/yyyy)

Date (dd/mm/yyyy)

PLEASE RETURN TO THE RELEVANT REGIONAL OFFICE THAT SUPPLIED THE FORM OR THE FOLLOWING ADDRESS:

NB: All relevant fields must be completed

SECTION T2.1.18: FORM R: COMPENSATION FOR OCCUPATIONAL INJURIES AND DISEASES ACT (COIDA)
--

Please attach Compensation for Occupational Injuries and Diseases Act (COIDA) to this page

Evidence of registration and proof of good standing for building and construction projects with a compensation insurer who is approved by the Department of Labour in terms of Section 80 of the Compensation for Occupational Injuries and Diseases Act (Act No 130 of 1993) (COIDA) **MUST be attached** to this returnable schedule.

Note to Tenderer:

In the event of the Tenderer being a joint venture/consortium, the Letter of good standing for built environment projects of the individual members must also be provided.

SIGNED ON BEHALF OF THE TENDERER:.....

SECTION T2.1.19: FORM S: LETTER OF INTENT FOR PERFORMANCE GUARANTEES

The Tenderer must attach to this page an original letter from a Bank or a FAIS registered or NCR registered financial institution with whom he has made the necessary arrangements, to the effect that the said institution will be prepared to provide the required performance guarantee when asked to do so.

SIGNED ON BEHALF OF THE TENDERER:.....

SECTION T2.1.20: FORM T: DECLARATION CERTIFICATE FOR LOCAL LABOUR PARTICIPATION
1. Definitions
1.1 Targeted Labour

Individuals, employed by the contractor in the performance of the contract, who are defined as the target group in the contract and who permanently reside in the target area or who are recognized as being residents of the target area on the basis of identification and association with and recognition by the residents of the target area

1.2 Target Group

For this project the contract does not specify the target group based on gender, age or disability. However, specifically excluded from the Target Group is the contractor's own staff unless such staff are also from the Target Area.

1.3 Target Area

For this project, the target area is defined as Mangaung Metropolitan Municipality, In the Free State Province.

1.4 Labour Maximisation

Labour maximisation shall contribute a minimum of 10%.

2. Conditions associated with the granting of preferences

The tenderer, undertakes to:

- 1) engage one or more targeted labour in accordance with the provisions of the SANS 1914-4 as varied in section 3 hereunder;
- 2) accept the sanctions set out in Section 2 below, should such conditions be breached;
- 3) complete the Targeted Labour (CPG) calculation form contained in Section 5 below; and
- 4) complete the Supporting Contract Participation Goal Calculation contained in Section 6 below.

3. Variation to the targeted construction procurement specification SANS 1914-4

The variations to SANS 1914-4 are set out below. Should any requirements of the variations conflict with requirements of SANS 1914-4 the requirements of the variations shall prevail

Calculations shall be based as a % of targeted labour costs of the Tender Sum (excluding VAT) and not calculated in accordance with methods 1 or 2 in Annexure A of SANS 1914-4.

4. Sanctions

In the event that the Tenderer fails to substantiate that any failure to achieve the Contract Participation Goal was due to quantitative under runs, the elimination of items, or any other reasons beyond the Contractor's control which may be acceptable to the Employer, it shall be liable to pay to the Employer a financial penalty calculated in the following manner:

$$P = 0,50 \times \frac{(D - D_0)}{100} \times N_A$$

Where D = tendered Contract Participation Goal percentage.

D₀ = the Contract Participation Goal which the Employer's representative based on the credits passed, certifies as being achieved upon completion of the contract.

N_A = Net Amount (Actual contract expenditure, excluding VAT)

P = Rand value of penalty payable

Tender Contract Participation Goal in respect of targeted labour

I/We hereby tender a Contract Participation Goal of% in compliance with the Employer's Socio-Economic Requirements.

The undersigned, who warrants that he/she is duly authorized to do so on behalf of the firm or sole proprietor confirms that he/she understands the conditions under which such preferences are granted.

Signature:

Name:

Duly authorized to sign on behalf of:

Telephone:

Fax:

5. Supporting Targeted Labour (CPG) calculation

TYPE OF TARGETED LABOUR	TOTAL ESTIMATED WORKING HOURS	RATE	TOTAL ESTIMATED WAGE COST
Permanent labour*			
Temporary labour			
SMME labour			
		Total	

*Note: A tenderer may only claim permanent staff as eligible for preference points if said staff are also from the Target Area. Permanent staff are considered to be those who have been continuously employed by the tenderer for at least three months prior to the commencement of this project.

SIGNED ON BEHALF OF THE TENDERER:.....

SECTION T2.1.21: FORM U: COMPULSORY ENTERPRISE QUESTIONNAIRE**FORM W : Annex L**

(normative)
Compulsory Enterprise questionnaire

The following particulars must be furnished. In the case of a joint venture, separate enterprise questionnaires in respect of each partner must be completed and submitted.

Section 1: Name of enterprise:

Section 2: VAT registration number, if any:

Section 3: cidb registration number, if any:

Section 4: Particulars of sole proprietors and partners in partnerships

Name*	Identity number*	Personal income tax number*

* Complete only if sole proprietor or partnership and attach separate page if more than 3 partners

Section 5: Particulars of companies and close corporations

Company registration number

Close corporation number

Tax reference number

Section 6: The attached SBD4 must be completed for each tender and be attached as a tender requirement.

Section 7: The attached SBD 6 must be completed for each tender and be attached as a requirement.

Section 8: The attached SBD8 must be completed for each tender and be attached as a requirement.

Section 9: The attached SBD9 must be completed for each tender and be attached as a requirement.

The undersigned, who warrants that he / she is duly authorised to do so on behalf of the enterprise:

i) authorizes the Employer to obtain a tax clearance certificate from the South African Revenue Services that my / our tax matters are in order;

ii) confirms that the neither the name of the enterprise or the name of any partner, manager, director or other person, who wholly or partly exercises, or may exercise, control over the enterprise appears on the Register of Tender Defaulters established in terms of the Prevention and Combating of Corrupt Activities Act of 2004;

Signed

Date

.....

.....

Name

Position

.....

.....

Enterprise Name

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

C1.2 CONTRACT DATA**PART 1: DATA PROVIDED BY THE EMPLOYER****CONDITIONS OF CONTRACT**

The General Conditions of Contract for Construction Works, Third Edition, 2015, published by the South African Institution of Civil Engineering, is applicable to this Contract and is obtainable from www.saice.org.za.

Copies of these Conditions of Contract may be obtained from the South African Institute of Civil Engineering, tel: 011 805 5947.

REF No.	CLAUSE	VARIATIONS AND ADDITIONS TO CONDITIONS OF THE CONTRACT
1.1.1.13		The Defect Liability Period is 12 months .
1.1.1.14		The time for achieving practical completion is 8 months .
1.1.1.15		Name of Employer: DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT
1.2.1.2		Address of Employer: Physical 136 Charlotte Maxeke Street Bloemfontein 9300 Telephone No: (051) 400 4200 Postal Private Bag X 20546 Bloemfontein 9300
1.1.1.26		The Pricing strategy is a Re-Measurable Contract.
3.1.1		The Project manager shall obtain the specific approval from the Department in accordance to the Supply Chain Delegation of Authority before executing any of his functions or duties according to the following Clauses of the General Conditions of Contract: 1 Clause 6.3: Variations. 2 Clause 5.12: Extension of Time for Practical Completion. 3 Contingencies 4 Handover. 5 Completion.
5.3.1		The Documentation required before commencement with Works execution are: • Health and Safety Plan (Refer to Clause 4.3) • Initial programme (Refer to Clause 5.6) • Security/ Performance Guarantees (Refer to Clause 6.2) • Works Insurance (Refer to Clause 8.6) • Cash flow Projections • COIDA Certificate
5.3.2		The time to submit documentation required before commencement with Works execution is 14 calendar days.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

5.4.2	The access and possession of Site shall not be exclusive to the Contractor but as set out in the Site information.
5.8.1	The non-working days are Sundays. The special non-working days are: 1. All statutory holidays as declared by national or Regional Government. 2. The year-end break commencing and ending on dates as specified by SAFCEC.
5.13.1	The penalty for failing to complete the Works is: the lesser of R 6 028.48 or 4 cents / R 100 of the offered total of prices excluding VAT per calendar day.
5.16.3	The latent defect period is 5 years.
6.5.1.2.3	The percentage allowances to cover overhead charges are: • 25% of the gross remuneration of workmen and foremen actual engaged in the day work. • 10% on the net cost of material actual used. No allowance will be made for work done, or for materials and equipment, for which day work rates have been quoted at tender stage.
6.10.1.5	The percentage advance on materials not yet built into the permanent works is 80%.
6.10.3	The limit of retention money is 10% of the net tender amount (maximum 5%)
8.2.1	The Contractor shall protect the Works properly and shall so arrange his operations that the minimum danger and inconvenience are caused to the public and vehicle and pedestrian traffic. For this purpose, he shall, inter alia, provide and maintain sufficient roads sign, lights, barricades, fencing, and guarding as may be necessary or required by the engineer or by any act, regulation, or statutory authorities. All operations required in connection with the execution and completion of the works and temporary works shall, as far as the provisions for the Contract permit, not unnecessarily or in any improper manner encroach upon the use of public roads or upon access to private property and the Contractor hereby indemnifies the employer against any claims, demands, damage and cost that may arise in this regard. Compensation for such obligations shall be included in the Contractors prices for provision and general costs, except in as provision is made in the specifications for payment in respect of specific items pertaining to those obligations.
8.6.1.1.2	The value of plant and materials supplied by the Employer to be included in the insurance sum is R0.00.
8.6.1.3	The limit of indemnity for liability insurance is R 5 000 000.00
10.5.1	Dispute resolution shall be by ad-hoc adjudication if necessary.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

**APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE
UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT
CROSSING UNDER MANGAUNG METRO MUNICIPALITY:
FREE STATE PROVINCE.**

THE CONTRACT

PART C1	AGREEMENT AND CONTRACT DATA.....	65 - 146
PART C2	PRICING DATA	147 – 149
PART C3	SCOPE OF WORKS.....	150 - 259
PART C4	SITE INFORMATION.....	260 - 263
PART C5	APPENDICES.....	264 -267

PART C1: AGREEMENTS AND CONTRACT DATA

INDEX

Section	Description	Page No
C1.1	FORM OF OFFER AND ACCEPTANCE.....	126
C1.2	CONTRACT DATA.....	130
C1.3	FORM OF GUARANTEE.....	134
C1.4	OCCUPATIONAL HEALTH AND SAFETY AGREEMENT.....	138

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

C1.1 FORM OF OFFER AND ACCEPTANCE\ (AGREEMENT)**OFFER****APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.**

The Employer, identified in the Acceptance signature block, has solicited offers to enter into a contract in respect of the following works:

The Bidder, identified in the Offer signature block below, has examined the documents listed in the Bid Data and addenda thereto as listed in the Bid Schedules, and by submitting this Offer has accepted the Conditions of Bid.

By the representative of the Bidder, deemed to be duly authorised, signing this apart of this Form of Offer and Acceptance, the Bidder offers to perform all of the obligations and liabilities of the Contractor under the Contract including compliance with all its terms and conditions according to their true intent and meaning for an amount to be determined in accordance with the Conditions of Contract identified in the Contract Data.

THE OFFERED TOTAL OF THE PRICES INCLUSIVE OF VALUE ADDED TAX ISRand *[in words]*: R*[in figures]*

(Should there be a discrepancy between the amount in words and the amount in figures then the amount in figures shall govern.)

This Offer may be accepted by the Employer by signing the Acceptance part of this Form of Offer and Acceptance and returning one copy of this document to the Bidder before the end of the period of validity stated in the Bid Data, whereupon the Bidder becomes the party named as the Contractor in the Conditions of Contract identified in the Contract Data.

It is expressly agreed that no other matter whether in writing, oral communication or implied during the period between the issue of the Bid documents and the receipt by the Bidder of a completed signed copy of this Agreement shall have any meaning or effect in the contract between the parties arising from this Agreement.

FOR THE TENDERER:

Signature(s)

Name(s)

Capacity

(Name and address of organisation)

Name and Signature
Of Witness

Date

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

ACCEPTANCE**APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.**

By signing this part of this Form of Offer and Acceptance, the Employer identified below accepts the Bidder's Offer. In consideration thereof, the Employer shall pay the Contractor the amount due in accordance with the, Conditions of Contract identified in the Contract Data. Acceptance of the Bidder's Offer shall form an agreement, between the Employer and the Bidder upon the terms and conditions contained in this Agreement and in the, Contract that is the subject of this Agreement.

The terms of the contract, are contained in

Section 1.1 (which includes this Agreement)

Section 1.2 (which includes this Agreement)

Section 2 Form of Bid

And drawings and documents or parts thereof, which may be incorporated by reference into Section 1 to Section 7 above.

Deviations from and amendments to the documents listed in the Bid Data and any addenda thereto listed in the Bid Schedules as well as any changes to the terms of the Offer agreed by the Bidder and the Employer during this process of offer and acceptance, are contained in the Schedule of Deviations attached to and forming part of this Agreement. No amendments to or deviations from said documents are valid unless contained in this Schedule, which must be duly signed by the authorised representative(s) of both parties.

The Bidder shall within two weeks after receiving a completed copy of this Agreement, including the Schedule of Deviations (if any), contact the Employer's agent (whose details are given in the Contract Data) to arrange the delivery of any bonds, guarantees, proof of insurance and any other documentation to be provided in terms of the, Conditions of Contract identified in the Contract Data. Failure to fulfil any of these obligations in accordance with those terms shall constitute a repudiation of this Agreement.

Notwithstanding anything contained herein, this Agreement comes into effect on the date when the Bidder receives one fully completed original copy of this document, including the Schedule of Deviations (if any). Unless the Bidder (now Contractor) within five working days of the date of such receipt notifies the Employer in writing of any reason why he cannot accept the contents of this Agreement, this Agreement shall constitute a binding contract between the parties.

It is expressly agreed that no other matter whether in writing, oral communication or implied during the period between the issue of the Bid documents and the receipt by the Bidder of a completed signed copy of this Agreement shall have any meaning or effect in the contract between the parties arising from this Agreement.

FOR THE EMPLOYER:

Signature(s)

Name(s)

Capacity

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT
136 Charlotte Maxeke Street
SA Eagle Building
Bloemfontein
9300

Name and Signature
Of Witness

Date

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

SCHEDULE OF DEVIATIONS

Notes:

1. The extent of deviations from the bid documents issued by the Employer prior to the bid closing date is limited to those permitted in terms of the Conditions of Bid.
2. A Bidder's covering letter shall not be included in the final contract document. Should any matter in such, letter, which constitutes a deviation as aforesaid become the subject of agreements reached during the process of, offer and acceptance, the outcome of such agreement shall be recorded here.
3. Any other matter arising from the process of offer and acceptance either as a confirmation, clarification or change to the bid documents and which it is agreed by the Parties becomes an obligation of the contract shall also be recorded here.
4. Any change or addition to the bid documents arising from the above agreements and recorded here shall also be incorporated into the final draft of the Contract.

1	Subject _____
	Details _____
2	Subject _____
	Details _____
3	Subject _____
	Details _____
4	Subject _____
	Details _____
5	Subject _____
	Details _____

By the duly authorised representatives signing this Schedule of Deviations, the Employer and the Bidder agree to and accept the foregoing Schedule of Deviations as the only deviations from and amendments to the documents listed in the Bid Data and addenda thereto as listed in the Bid Schedules, as well as any confirmation, clarification or change to the terms of the offer agreed by the Bidder and the Employer during this process of offer and acceptance.

It is expressly agreed that no other matter whether in writing, oral communication or implied during the period between the issue of the bid documents and the receipt by the Bidder of a completed signed copy of this Agreement shall have any meaning or effect in the contract between the parties arising from this Agreement.

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

FOR THE TENDERER:

Signature(s) _____

Name(s) _____

Capacity _____

(Name and address of organisation) _____

Name and Signature
Of Witness _____

Date _____

FOR THE EMPLOYER:

Signature(s) _____

Name(s) _____

Capacity _____

DEVELOPMENT

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL

136 Charlotte Maxeke Street
SA Eagle Building
Bloemfontein
9300emfontein, 9300Name and Signature
Of Witness _____

Date _____

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PART 1: DATA PROVIDED BY THE EMPLOYER**CONDITION OF CONTRACT**

The General Conditions of Contract for Construction Works 3rd Edition (2015), published by the South African Institution of Civil Engineering, is applicable to this Contract.

Copies of these conditions of contract may be obtained from the South African Institution of Civil Engineering (Tel 011-805 5947).

REF CLAUSE No.	
1.1.1.9	Name of Contractor.....
1.2.1.2	Address of Contractor: Physical:..... Postal:..... e-mail:.....Telephone no.:.....Fax No:.....
6.2.1	The security to be provided by the Contractor shall be Performance Guarantee/ Bond of 10% of the Contract Sum.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

VARIATIONS TO THE CONDITIONS OF CONTRACT ARE:**Clause****4.4.3 Liability for subcontractors**

Add the following to Clause 4.4.3 after the last sentence:

"The Contractor shall not subcontract any part of the Contract without the prior written consent of the Engineer, which consent shall not be unreasonably withheld."

5.3.3 Time to instruct commencement of the Works

Add the following to Clause 5.3.3 after the last sentence:

"The Contractor shall not commence working until they have an approved project specific health and safety plan in terms of the Occupational Health and Safety Act, 1993: Construction Regulations, 2003 and complied with the initial requirements thereof."

5.14.1 Practical Completion

Replace the last sentence of the second paragraph:

"Should the Engineer ... on the Due Completion Date" *with the following:*

"Should the Engineer not issue such a list within 14 days, Practical Completion shall be deemed to have been achieved on the said fourteenth day."

5.14.2 Issue of Certificate of Practical Completion

Replace "the Engineer" in the second line with the following:

", the Contractor shall notify the Engineer, who shall inspect the Works and the Engineer"

5.14.4 Certificate of Completion

Replace "the Engineer" in the second and third line of the first paragraph with:

", the Contractor shall notify the Engineer, who shall inspect the works and the Engineer"

6.10.4 Delivery, dissatisfaction with and payment of payment certificate

Replace "28 days" in the seventh line with "30 days".

6.11 Variations exceeding 15 per cent

Replace "15 per cent" in the heading, the marginal heading and the tenth line with "20 per cent".

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD
AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

C1.3 PERFORMANCE GUARANTEE (PRO-FORMA)**GUARANTOR DETAILS AND DEFINITIONS**

Guarantor means
Physical address

Guarantor's signatory 1 Capacity

Guarantor's signatory 1 Capacity

Employer means **DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL
DEVELOPMENT**

Contractor means

Agent means

(Compiler to insert name of agent)

Works means

(Compiler to provide reference number and title of contract)

Site means

(Compiler to enter site as described in the Contract Data)

Agreement means the General Conditions of Contract for Construction Works 2010

Contract Sum i.e. the total of prices in the Form of Offer and Acceptance inclusive of VAT

Amount in figures R

Amount in words (Rand)

Guaranteed Sum means the maximum aggregate amount of R

Amount in words (Rand)

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- 1 The Guarantor's liability shall be limited to the amount of the Guaranteed Sum as follows:

GUARANTOR'S LIABILITY	PERIOD OF LIABILITY
Maximum Guaranteed Sum (not exceeding 10 % of the contract sum) in the amount of: (Rands) (R)	From and including the date of issue of this Construction Guarantee and up to and including the date of the only practical completion certificate or the last practical completion certificate where there are sections, upon which this Construction Guarantee shall expire.

- 2 The Guarantor hereby acknowledges that:

- 2.1 Any reference in this Guarantee to the Agreement is made for the purpose of convenience and shall not be construed as any intention whatsoever to create an accessory obligation or any intention whatsoever to create a suretyship.

- 2.2 Its obligation under this Guarantee is restricted to the payment of money.

- 3 Subject to the Guarantor's maximum liability referred to in clauses 1, the Guarantor hereby undertakes to pay the Employer the sum certified upon receipt of the documents identified in sub-clauses 3.1 to 3.3:

- 3.1 A copy of a first written demand issued by the Employer to the Contractor stating that payment of a sum certified by the Principal Agent in an interim or final payment certificate has not been made in terms of the Agreement and failing such payment within seven (7) calendar days, the Employer intends to call upon the Guarantor to make payment in terms of sub-clause 3.2

- 3.2 A first written demand issued by the Employer to the Guarantor at the Guarantor's physical address with a copy to the Contractor stating that a period of seven (7) calendar days has elapsed since the first written demand in terms of sub-clause 4.1 and that the sum certified has still not been paid therefore the Employer calls up this Guarantee and demands payment of the sum certified from the Guarantor.

- 3.3 A copy of the said payment certificate which entitles the Employer to receive payment in terms of the Agreement of the sum certified in clause 3.

- 4 Subject to the Guarantor's maximum liability referred to in clause 1, the Guarantor undertakes to pay the Employer the Guaranteed Sum or the full outstanding balance upon receipt of a first written demand from the Employer to the Guarantor at the Guarantor's physical address calling up this Guarantee stating that:

- 4.1 The Agreement has been cancelled due to the Contractor's default and that the Guarantee is called up in terms of clause 4. The demand shall enclose a copy of the notice of cancellation; or

- 4.2 A provisional sequestration or liquidation court order has been granted against the Contractor and that the Guarantee is called up in terms of clause 4. The demand shall enclose a copy of the court order.

- 5 It is recorded that the aggregate amount of payments required to be made by the Guarantor in terms of clauses 3 and 4 shall not exceed the Guarantor's maximum liability in terms of clause 1.

- 6 Where the Guarantor is a registered insurer and has made payment in terms of clause 4, the Employer shall upon the date of issue of the final payment certificate submit an expense account to the Guarantor showing how all monies received in terms of the Guarantee have been expended and shall refund to the Guarantor any resulting surplus. All monies refunded to the Guarantor in terms of this Guarantee shall bear interest at the prime overdraft rate of the Employer's bank compounded monthly and calculated from the date payment was made by the Guarantor to the Employer until the date of refund.

- 7 Payment by the Guarantor in terms of clause 3 or 4 shall be made within seven (7) calendar days upon receipt of the first written demand to the Guarantor.

- 8 The Employer shall have the absolute right to arrange his affairs with the Contractor in any manner which the Employer deems fit and the Guarantor shall not have the right to claim his release from this Guarantee on

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

account of any conduct alleged to be prejudicial to the Guarantor

- 9 The Guarantor chooses the physical address as stated above for all purposes in connection herewith.
- 10 This Guarantee is neither negotiable nor transferable and shall expire in terms of clause 1, or payment in full of the Guaranteed Sum or on the Guarantee expiry date, whichever is the earlier, where after no claims will be considered by the Guarantor. The original of this Guarantee shall be returned to the Guarantor after it has expired
- 11 This Guarantee, with the required demand notices in terms of clauses 3 or 4, shall be regarded as a liquid document for the purpose of obtaining a court order.
- 12 Where this Guarantee is issued in the Republic of South Africa the Guarantor hereby consents in terms of Section 45 of the Magistrate's Courts Act No 32 of 1944, as amended, to the jurisdiction of the Magistrate's Court of any district having jurisdiction in terms of Section 28 of the said Act, notwithstanding that the amount of the claim may exceed the jurisdiction of the Magistrate's Court.

Signed at Date

Guarantor's
Signatory 1 Guarantor's
Signatory 2

Witness 1 Witness 2

Guarantor's seal or stamp

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

LIST OF INSTITUTIONS FROM WHICH CONTRACT SURETIES CAN BE ACCEPTED:

1. ABSA Bank
2. Credit Agricole Indosuez (South Africa Branch)
3. Development Bank of South Africa
4. FirstRand Bank
5. ING Bank N.V. (South Africa Branch)
6. Investec Bank
7. Landbank
8. National Housing Finance Co.
9. Nedcor Bank
10. South African Reserve Bank
11. Standard Bank
12. AIG South Africa
13. Credit Guarantee Insurance Co
14. Emerald Insurance Company
15. Federated Employers Mutual Assurance Co
16. Global Insurance Company
17. Guardrisk Insurance Company
18. Hannover Re:
19. Home Loan Guarantee Company
20. Lion of Africa Insurance Company
21. Metropolitan Life
22. Metropolitan Odyssey Ltd
23. MUA Insurance
24. Mutual & Federal Insurance Company
25. Rand Mutual Assurance Company
26. Regent Insurance Company
27. SA Eagle Insurance Company
28. Lombard Insurance

NB: List of institutions is not limited to the above mentioned; the tenderer may use any other accredited institution to offer contract sureties.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

C1.4 OCCUPATIONAL HEALTH AND SAFETY AGREEMENT

This agreement is mandatory for all contractors appointed by the DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT .

This agreement is between:

THE CONTRACTOR:

Herein represented by

In his capacity asBeing duly authorized hereto hereinafter referred to as "contractor".

Compensation Commissioner Number:

(Attach a copy of the Registration Certificate to this agreement)

Company : Name:

Registration Number:

CEO : Name:

ID Number:

Physical Address:

.....

And the

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT
(Hereinafter referred to as "the Department")

1. DEFINITIONS

- | | | |
|-----|-------------------------------|---|
| 1.1 | CONTRACTOR | Means the "Contractor" as defined in the "Principal Contract" Annexed hereto in his capacity as mandatory. |
| 1.2 | MANDATORY | Includes an agent, contractor or subcontractor for work to be done or service rendered, but without derogating from his status in his own right as an employer of people or user of equipment, machinery, tools or materials. |
| 1.3 | THE PRINCIPAL CONTRACT | Means the contract annexed hereto as annexure "A". |

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- 1.4 **DEPARTMENT** Means the DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT .
- 1.5 **RISK CONTROL OFFICER** A person appointed in writing by Department.
- 1.6 Any definitions contained in any Statute hereinafter mentioned shall have the meaning allocated to it by the specific statute.

2. OBJECTIVE

- 2.1 Whereas Department and the Contractor have entered into a contract for service (work) as fully indicated in the "Principle Contract" and whereas the "Contractor" agreed to indemnify Department against the risks stated hereunder whether foreseeable or not, and, whereas it is agreed between the parties that it is of cardinal importance to safeguard both Department and the Contractor's obligation in terms of relevant legislation as well as to extend the obligation as a company and/or legal person and/or person as an entity concerned with health, safety and the environment.
- 2.2 These rules are applicable to all contractors performing work for Department within the jurisdictional area of the Department and on any premises which are owned, rented or developed by the Department.
- 2.3 The Department acts through those officials or persons who are generally or specifically charged with the responsibility, in terms of legislation, as well as any other official or person who is generally or specifically charged with the control and supervision of the project.

IT IS HEREBY AGREED AS FOLLOWS:

3. INDEMNITIES

- 3.1 The "Contractor" hereby indemnifies the "Department" against any loss in respect of all claims, proceeding, damages, costs and expenses arising out of any claim or proceeding pertaining to the non compliance by the "Contractor" of any statutory requirements and/or requirements regarding the following Acts in particular pertaining to the provisions of:
- 3.1.1 The Occupational Health and Safety Act 85 of 1993 (as amended), including the Construction Regulations, 2014 as promulgated on 07 February 2014, in terms of Section 43 of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993), in Government Gazette No. 25207 and Regulation Gazette No. 7721. See Annexure B.
- 3.1.2 The Health Act 63 of 1977.
- 3.1.3 Road Traffic Act 29 of 1989 (as amended).
- 3.1.4 Environment Conservation Act 73 of 1989.
- 3.1.5 The National Water Act 36 of 1998.
- 3.1.6 The Criminal Procedure Act 51 of 1977.
- 3.1.7 The Explosives Act 26 of 1956.
- 3.1.8 The Arms and Ammunition Act 75 of 1969.
- 3.1.9 Compensation for Occupational Injuries and Diseases Act 130 of 1993.
- 3.1.10 The Labor Relations Act 66 of 1995.
- 3.1.11 The Unemployment Insurance Act 30 of 1966 (as amended).
- 3.1.12 The Basic Conditions of Employment Act 75 of 1997 (as amended).
- 3.1.13 Standards Act 29 of 1993.
- 3.1.14 any statutory provisions in any act and/or any law or bylaw of any local government and/or any published official standard incorporated into any statute or bylaw relating to the completion of the work set out in the "Principal Contract".
- 3.1.15 Any other health and safety standard prescribed by the "Department".
- 3.2 The "Contractor" shall ensure that he familiarises himself with the requirements of the above legislation and that he, his employees and any subcontractor will comply with all the statutory

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

provisions contained in them.

- 3.3 The "Contractor" shall indemnify the "Department" in respect of any physical loss or damage to any plant, equipment or other property belonging to the "Contractor" or for which he is responsible and he hereby indemnifies the "Department" against any loss in respect of all claims, proceedings, damages, costs and expenses consequent upon the loss of or damage to any plant, equipment or other property belonging to, or which is the responsibility of, any subcontractor, agent or employee of the subcontractor.
- 3.4 The "Contractor" shall and hereby indemnifies the "Department" against any liability, loss, claim or proceedings whatsoever, whether arising in common law or by statute, consequent on personal injuries to or the loss of health or death of any person whatsoever arising out of or in the course of or caused by the execution of the "Principal Contract".
- 3.5 The "Contractor" shall and hereby indemnifies the "Department" against any liability, loss, claim or proceedings consequent on loss of or damage to any movable or immovable property arising out of or in the course of or caused by the execution of the "Principal Contract" and due to any act or omission of the "Contractor", his agents, servants or subcontractors.

4. PERFORMANCE SAFE WORKING PRACTICE

- 4.1 The "Department" requires a high standard of safe work performance from all employees and expects that the standard be maintained by the "Contractor" within the "Department's" jurisdictional area or on its premises.
- 4.2 Irrespective of human considerations, the maintaining of these health and safety rules shall be the execution of the prescribed legal requirements. These rules are not to hinder the "Contractor" in rendering services or indemnify the "Contractor" from any legal responsibility to ensure healthy and safe work circumstances.
- 4.3 The "Department" shall assist the "Contractor" in any practical considerations to accommodate the healthy and safe execution of work and therefore require co-operation in the execution of these safety rules.

5. LOCK OUT PROCEDURE

- 5.1 When power or air driven machines or equipment, electrical apparatus or pipe lines are examined, repaired, adjusted, cleaned, lubricated or serviced in any other way than normal servicing, then all isolating switches, -levers, valves or appliances must be put in the "off" or "closed" position and locked.
- 5.2 Should more than one team work on a machine, then each person in control of a team, must put a separate lock on the switch, lever, valve or appliance.

6. CRANES, VEHICLES AND HOISTING

- 6.1 For each crane or hoisting equipment used, the "Contractor" must submit a valid and recent test certificate or other form of the last examination of the machine or equipment, to the "Department".
- 6.2 Only trained personnel with written permission and where determined by Law, with a valid driver's license, may be allowed to operate any electrical diesel or petrol driver overhead crane, hydraulic or electrical hoisting equipment, self driven forklift, tractor or any other crane or vehicle. No employee of the "Contractor" may perform any overhead work or work on an overhead crane or hoisting equipment or work near cranes or crane rail, before:
 - i) An agreement was concluded with the "Department".
 - ii) Approval has been obtained from the "Department" to perform the work.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- iii) All applicable danger – and warning symbolic signs are put into position, or exemption, if applied for, is in operation.

6.3 The “Contractor” shall be wholly responsible for any loss or damage to cranes, hoisting equipment, plant, machines or equipment brought onto the work site by the “Contractor”

7. MACHINE VALANCES, PROTECTION AND FENCING

- 7.1 No machine valances, protection or fencing may be removed from machines, manholes, etc without the written permission of “Department” if applicable exemption procedures were not appropriated.

8. SCAFFOLD, LADDERS, TOOLS AND EQUIPMENT

- 8.1 No equipment or appliance belonging to “Department” may be used without written permission from “Department”.
- 8.2 Unless prior arranged, “Contractors” must bring sufficient tools and equipment to the site to finish the contract, including offices and storerooms. The mentioned equipment remains the responsibility of the “Contractor” with respect to loss, damage and theft.
- 8.3 In exceptional cases, where tools and equipment belonging to “Department” are used to finish the contract, the said equipment and tools are used on own risk and the “Contractor” indemnifies “Department” from any claims that may arise. The said indemnity must be in writing, as well as information regarding the loan period, identification and condition of tools and equipment. The “Contractor” is responsible for the returning of said tools and equipment in the same condition or better. The “Contractor” is responsible to “Department” for any damage or excessive wear of such tools or equipment and material.

9. EXCAVATIONS

- 9.1 Before any excavations commence, written permission must be obtained from “Department” to confirm the location of existing electrical cables, water pipes, etc.
- 9.2 All excavations and obstructions in floor, tar and dirt surfaces must be fenced effectively and safeguarded between sundown and sunup with a sufficient amount of red/yellow warning lights and symbolic signs.
- 9.3 The surrounding area must be kept clean, safe and tidy during excavation. Excess material may not obstruct unnecessarily.
- 9.4 If any property is in danger during excavation, it must be supported and the proposed support work must be submitted to the Department of Labour (OHS) and “Department” for approval.
- 9.5 Written permission must be obtained from “Department” to grant admittance to restricted areas as well as areas where dangerous or poisonous gases are present.

10. FIRST AID

- 10.1 The “Contractor” must provide and maintain a first aid box equipped according to legal requirement where more than (5) five persons are employed. The first aid box must be in the care of a person with a competency certificate from one of the following organizations:

- (i) SA Red Cross Association;
- (ii) St Johns Ambulance;
- (iii) SA First Aid League; or
- (iv) A person or organization approved by the Chief inspector for this purpose.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- 10.2 A visible notice must be put up on any work premises with the name of the person responsible for first aid. In an emergency "Department's" Ambulance / Fire Department or emergency services may be contacted at

11. FLAMMABLE LIQUIDS

- 11.1 The "Contractor" shall be held responsible for the necessary precautionary fire prevention measures. No smoking signs must be put up where applicable. The "Contractor's" employees must be informed of "Department's" fire prevention measures and evacuation procedures.

12. COMPENSATION BY CONTRACTOR

- 12.1 The "Contractor" shall be held responsible for all loss of and damage to property, the death or injury of persons, the resultant loss or damage suffered as well as all law suits, claims, costs, charges, fines and expenses due to negligence, violation of statutory liability or neglect of the "Contractor" or the "Contractor's" employees.

13. TRANSGRESSION OF RULES AND MISBEHAVIOUR

- 13.1 The "Contractor" is warned that any act(s) leading to damage or loss of employees of the "Contractor" or the "Department" shall not be tolerated. The "Department" may (without any reason) demand that any employee of the "Contractor" be withdrawn from the principal "Contract" or site.

14. INCIDENT REPORTING

- 14.1 All incidents referred to in Section 24 of the Occupational Health and Safety Act and or other incidents shall be reported, by the "Contractor", to the Department of Labour, as well as to the "Department" and should such an incident take place outside normal working hours, on a Saturday, Sunday or Public holiday to The "Department" shall further be provided with a written report relating to any incident.
- 14.2 The "Department" will obtain an interest in the issue of any formal inquiry conducted in terms of the Occupational Health and Safety Act in any incident involving the "Contractor" and/or his employees and/or his subcontractors.
- 14.3 The "Contractor" undertakes to report to "Department" anything deemed to be unhealthy and/or unsafe and that he undertakes to verse his employees and/or subcontractors in this regard.

15. LIAISON AND SUPERVISION

- 15.1 The "Contractor" hereby undertakes to liaise on a regular basis with the designated Risk Control Officer and "Department" representative regarding any hazards or incidents that may be identified or encountered during the performance of the "Principal Contract".

16. SERVICE INTERRUPTION

- 16.1 Should any work done by the "Contractor" cause a possible interruption, written permission must be obtained from "Department", before such work commences. The "Contractor" may not switch on or off any compressed air, steam, oxygen, vacuum supply or electrical supply without written permission from the "Department".

17. CONFIDENTIALITY

- 17.1 The "Contractor" and his employees shall regard all data, documentation and information of the contract and related documentation as confidential.

- 17.2 Lost documentation/plans or related documentation shall immediately be reported in writing to the

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

"Department".

- 17.3 The "Contractor" shall not put up any advertisements or billboard at the site without permission.
- 17.4 The "Contractor" shall not take photographs of the contract site or part thereof or any work process or part thereof, without written permission from the "Department", or have photographs taken, published or let it be published.

18. CONTRACT SITE AND PRESERVATION

- 18.1 Employees of the "Contractor" shall not be allowed entrance to the site unless a valid identity document, issued by "Department", is displayed. The mentioned documents shall only be valid for a limited period, where after it must be renewed.

19. COMPLETION OF WORK

- 19.1 The "Contractor" or his employees shall not leave the contract site before the "Department" is satisfied that the contract is completed according to the requirements and standards set out in the contract and that the working site is left in a satisfactory and safe condition.

20. LIQUOR, DRUGS, DANGEROUS WEAPONS AND FIREARMS

- 20.1 The "Contractor" shall ensure that no liquor, drugs, dangerous weapons or firearms be brought onto the premises.

21. SEARCHES

- 21.1 The "Contractor" and any person engaged in the contract work may at any time be searched by "Department" appointed security personnel and all packages, suitcases, etc. must be presented to the access control point for examination prior to them being brought onto the property or leaving the property.

22. GENERAL CONDITIONS

- 22.1 Notwithstanding anything to the contrary in this agreement, it is hereby specifically determined that the "Contractor- "
- 22.1.1 shall have acquainted himself and be conversant with the contents of all statutory provisions applicable to the health and safety of workers and other persons on the site including the execution of the work, and in particular the conditions contained in the Occupational Health and Safety Act, 1993 (Act 85/1993), and the regulations promulgated in terms thereof, and shall comply therewith meticulously and in all aspects and/or take care that it is complied with;
- 22.1.2 shall be obliged to immediately execute all instructions given to him by an authorized representative of "Department" in order to ensure and uphold the implementation and enforcement of the provisions referred to in sub-paragraph 1, to the satisfaction of the said representative;
- 22.1.3 shall indemnify the "Department" against any or all liability which may be incurred by the "Department" as a result of the omission of the "Contractor", his employees, sub-contractors and/or representatives to comply with the provisions referred to in sub-paragraph 1, or to ensure that it shall be complied with;
- 22.1.4 shall undertake to pay upon demand any and/or all legal costs and other expenses which "Department" may have incurred as a consequence of any criminal charges or other proceedings pending against, or involving the "Department" as a result of the contravention or non-compliance by the "Contractor", his employees, sub-contractors and/or

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

representative of any of the statutory provisions referred to in sub-paragraph 1.

22.1.5 Should the "Contractor" neglect to immediately execute any health and safety written orders issued to him, or to his employee in charge of the works, in terms of the stipulations of sub-paragraph 2, the "Department" shall be entitled to suspend the execution of the works and take the necessary steps to execute or have such order executed. Under these circumstances the contractor shall be obliged to pay "Department", upon demand, all costs and expenses incurred by "Department", in order to execute or have the said orders executed.

22.1.6 Should the abovementioned steps not establish a healthy and safe work environment the "Department" will be entitled to terminate the contract without incurring any further costs or claims from the contractor?

23. "CONTRACTOR" IDENTIFICATION BOARD

23.1 The "Contractor" shall provide on any work premises a temporary identification board containing at all worksites the following information:

Company name

On behalf of which division/department the work is being done

The contact number and name of the person representing the "Contractor"

The contact number and name of the person representing "Department"

24. ACKNOWLEDGEMENT

24.1 The "Contractor" hereby acknowledges that he has read and received a copy of the "Principal Contract" and agrees to be bound by and undertakes to observe all the terms and conditions of the "Principal Contract". This appointment is made in terms of Section 37(2) of the Occupational Health and Safety Act, 85 of 1993.

25. EXCEPTIONS AND OMISSIONS

26. REMARKS

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

THE CONTRACTOR

SIGNED AT ON THIS DAY OF

WITNESSES:

.....
THE CONTRACTOR

1.

2.

THE DEPARTMENT

SIGNED AT ON THIS DAY OF

WITNESSES:

.....
THE DEPARTMENT

1.

2.

INDEMNITY CERTIFICATE

Contractor :

Employer : DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

Contract :

I/we Hereafter the "Contractor"

"Contractor" hereby indemnifies the Department against any claim of whatever sort which may arise directly or indirectly from the execution by me/us of the above-mentioned contract and which may be instituted against "Department", as well as of any loss or damage which the "Department" suffers or expenditure the "Department" incurs to prevent responsibility for such claim, loss or damage, whatever the cause of such claim may be or whatever loss or damage the "Department" suffers.

THUS done and signed at on this day of 200....

WITNESSES:

1.

.....
CONTRACTOR

2.

.....
DEPARTMENT

R 2
REVENUE STAMP



Contractor



Witness 1



Witness 2



Employer



Witness 1



Witness 2

ACKNOWLEDGEMENT CERTIFICATE

I, in my capacity as.....

Duly authorized hereto.....representing

..... Contractors, acknowledge receipt
Of a copy of the Department's safety manual for contractors and the under mentioned person as my supervisor
regarding all works and services which must be executed by the Contractor. The appointment is done in terms of the
Occupational Health and Safety Act, 1993 (Act 85/1993).

SIGNED AT ON 200...

I, accept the abovementioned appointment, and
declare that I am familiar with the contents of the Department Safety Manual for contractors.

CASUALTIES REGISTRATION NUMBER

SIGNED AT ON 200....

SIGNATURE:

WITNESSES: 1.

2.

A copy of this certificate shall be submitted to the "Department" before any work commences.

R 2
REVENUE STAMP

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

PART C2 PRICING INSTRUCTION

C2.1 Pricing Instructions

- 1 The Bills of Quantities have been drawn up in accordance with the Standard System of Measuring Building Work (as amended) published and issued by the Association of South African Quantity Surveyors (Sixth Edition (Revised)), 1999. Where applicable the:
 - a) Civil engineering work has been drawn up in accordance with the provisions of the latest edition of SABS 1200 Standardized Specifications for Civil Engineering Works.
 - b) Mechanical work has been drawn up in accordance with the provisions of the Model Bills of Quantities for Refrigeration, Air-Conditioning, and Ventilation Installations, published by the South African Association of Quantity Surveyors, July 1990).
 - c) electrical work has been drawn up in accordance with the provisions of the Model Bills of Quantities for Electrical Work, published by the South African Association of Quantity Surveyors, (July, 2005).

- 2 The agreement is based on the General Conditions of Contract for Construction Works 2015, prepared by The South African Institution of Civil Engineering, Third Edition.

- 3 The "Model Preambles for Trades – 1999 Edition" as recommended and published by the Association of South African Quantity Surveyors, as referred to hereafter, will be applicable on this contract.

This document will be available at the Quantity Surveyor's office during normal office hours if needed.

- 4 It will be assumed that prices included in the Bills of Quantities are based on Acts, Ordinances, Regulations, By-laws, International Standards and National Standards that were published 28 days before the closing date for Bids. (Refer to www.stanza.org.za or www.iso.org for information on standards).

- 5 The drawings listed in the Scope of Works used for the setting up these Bills of Quantities are kept by the quantity surveyor and can be viewed at any time during office hours up until the completion of the works.

- 6 Reference to any particular trademark, name, patent, design, type, specific origin or producer is purely to establish a standard for requirements. Products or articles of an equivalent standard may be substituted.

- 7 Where any item is not relevant to this specific contract, such item is marked N/A (signifying "not applicable")

- 8 The Contract Data and the standard form of contract referenced therein must be studied for the full extent and meaning of each and every clause set out in Section 1 (Preliminary and General) of the Bills of Quantities

- 9 The Bills of Quantities is not intended for the ordering of materials. Any ordering of materials, based on the Bills of Quantities, is at the Contractor's risk.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

- 10 The amount of the Preliminary and General Section to be included in each monthly payment certificate shall be assessed as an amount prorated to the value of the work duly executed in the same ratio as the preliminaries bears to the total of prices excluding any contingency sum, the amount for the Preliminary and General Section and any amount in respect of contract price adjustment provided for in the contract.
- 11 Where the initial contract period is extended, the monthly charge shall be calculated on the basis as set out in 10 but taking into account the revised period for completing the works.
- 12 The amount or items of the Preliminary and General Section shall be adjusted to take account of the theoretical financial effect which changes in time or value (or both) have on this section. Such adjustments shall be based on adjustments in the following categories as recorded in the Bills of Quantities:
 - a) an amount which is not to be varied, namely Fixed (F)
 - b) an amount which is to be varied in proportion to the contract value, namely Value Related (V); and
 - c) an amount which is to be varied in proportion to the contract period as compared to the initial construction period excluding revisions to the construction period for which no adjustment to the contractor is not entitled to in terms of the contract, namely Time Related (T).
- 13 Where no provision is made in the Bills of Quantities to indicate which of the three categories in 12 apply or where no selection is made, the adjustments shall be based on the following breakdown:
 - a) 10 percent is Fixed.
 - b) 15 percent if Value Related
 - c) 75 percent is Time Related.
- 14 The adjustment of the Preliminary and General Section shall apply notwithstanding the actual employment of resources in the execution of the works. The contract value used for the adjustment of the Preliminary and General Section shall exclude any contingency sum, the amount for the Preliminary and General Section and any amount in respect of contract price adjustment provided for in the contract. Adjustments in respect of any staged or sectional completion shall be prorated to the value of each section.

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

C2.2 BILL OF QUANTITIES

For the purposes of this Bill of Quantities, the following words shall have the meanings hereby assigned to them:

Unit	:	The unit of measurement for each item of work as defined in the Standardized, Project or Particular Specifications
Quantity	:	The number of units of work for each item
Rate	:	The payment per unit of work at which the Bidder bids to do the work
Amount	:	The quantity of an item multiplied by the bid rate of the (same) item
Sum	:	An amount bid for an item, the extent of which is described in the Bill of Quantities, the Specifications or elsewhere, but of which the quantity of work is not measured in units

The units of measurement indicated in the Bill of Quantities are metric units. The following abbreviations may appear in the Bill of Quantities:

mm	=	millimetre
m	=	metre
km	=	kilometre
km-pass	=	kilometre-pass
m ²	=	square metre
m ² -pass	=	square metre-pass
ha	=	hectare
m ³	=	cubic metre
m ³ -km	=	cubic metre-kilometre
kW	=	kilowatt
kN	=	kilo newton
kg	=	kilogram
t	=	ton (1 000 kg)
%	=	per cent
MN	=	mega newton
MN-m	=	mega newton-metre
No.	=	Number of items
PC Sum	=	Prime Cost Sum
Prov Sum	=	Provisional Sum

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>GENERAL REQUIREMENTS AND PROVISIONS</u>				
	Environmental Management				
	Monitoring of compliance with and reporting on the EMP	Prov.Sum	1		
	Stake holders Liaison				
	Remuneration of the Project Liaison Officer and members of the Project Liaison Committee:				
	(a) Project Liaison Officer	month	8		
	(b) Project Liaison Committee	Prov.Sum	1		
	(c) Training	Prov.Sum	1		
	(d) Handling costs and profit with respect to SDA 8.10 (a), (b) & (c)	%	10%		
	Safety				
	Health and safety plan	lump Sum	1		
	Implementation of health and safety plan	month	8		
	Dayworks				
	Personnel				
	(a) Unskilled Labourer	hour	8		
	(b) Semi-Skilled Labourer	hour	8		
	(c) Skilled Labourer	hour	8		
	Construction equipment				
	(b) Vibratory roller	hour	8		
	(e) TLB (CAT 416 or similar)	hour	8		
	(f) Excavator	hour	8		
	(h) Watercart (10 000 litre)	hour	8		
	Carried forward				

	DESCRIPTION	UNIT	QUAN- TITY	Rate	Amount
ITEM	Brought forward				
	(i) Other equipment				
	(ii) Grid roller	hour	8		
	(iii) Other equipment	hour	8		
	Vehicles				
	(a) Light Vehicle	km	1'0		
	(b) Flatbed Truck	km	1'0		
	(c) Dump Truck	km	1'0		
	(d) Other Vehicles	km	1'0		
	<u>CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS</u>				
	The Contractor's general obligations:				
	Fixed obligations	lump sum	1		
	Value-related obligations	lump sum	1		
	Time-related obligations	month	8		
	Contract sign board	No	2		
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	Rate	Amount
	Brought forward				
	<u>FACILITIES FOR THE ENGINEER</u>				
	Site Accomodation				
	Offices and conference room	No	2		
	Laboratories	No	1		
	Store rooms inside the laboratory	No	1		
	Car ports	No	2		
	Ablution unit (X2) (equipped as specified)	Month	8		
	Items mearsured by number				
	Office swivel chair	No	2		
	Office desk with 3 drawers (at least one lockable drawer)	No	1		
	Conference table	No	1		
	Steel filing cabinets with drawers	No	1		
	Wash hand basins complete with taps and drains	No	1		
	Fire extinguishers, 9,0kg, all purpose dry powder type, complete, mounted on wall with brackets.	No	1		
	Carried forward				

[illegible]

ITEM	DESCRIPTION	UNIT	QUAN- TITY	Rate	Amount
	Brought forward				
	Fixed Costs	Sum	1		
	Running costs	month	8		
	<u>ACCOMMODATION OF TRAFFIC</u>				
	Accommodating of pedestrian and non-motorised traffic				
	Accommodation of pedestrian and non-motorised traffic	month	8		
	Accommodation of vehicular traffic	month	8		
	Maintenance of temporary deviations				
	Grading of temporary deviations and existing roads used as detours	km	2		
	Watering of temporary deviations and existing roads used as detours	kl	200		
	Other road maintenance work ordered by the Engineer	Prov Sum	-		
	Handling cost, profit and all other charges in respect of item C1.5.6.11	%	10%		
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	Rate	Amount
	Brought forward				
	Temporary traffic control facilities				
	Delineators including mounting bases and ballast:				
	(b) Double sided, reversible left or right	No	100		
	Flagmen	man-shift	640		
	Traffic calming device				
	(c) 150mm high x 6m wide x 5m long speed control humps	No	8		
	Movable Stop/Go sign	No	4		
	Provision of safety equipment for visitors				
	Provision of reflective safety vests for visitors	No	5		
	<u>CLEARING AND GRUBBING</u>				
	Clearing				
	Clearing with machines and some hand labour where necessary	ha	1'00		
	Clearing with hand labour only when labour enhanced work is specified	ha	1'00		
	Removal of buildings and structures				
	Building (concrete and masonry structures)	Lump.Sum -			
	LOADING AND HAULING				
	Hauling material for use in the Works and off-loading it on site of the works				
	(a) Soil, gravel, crushed stone and pavement layer material	m ³ - km	2000		
	Total for Chapter 1 - Carried to summary				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>GENERAL REQUIREMENTS AND TRENCHING FOR SERVICES</u>				
	Location, identification, protection and relocation of existing services				
	Permanent services relocation or protection work by others	PC.Sum	1		
	Handling costs and profit in respect of item C2.1.1.2 above	%			
	Permanent services relocation or protection work by the Contractor	Prov.Sum	1		
	Existing services location, detection and verification				
	Using hand excavation to locate, expose and verify services	m ³	75		
	Dealing with water during services				
	Dealing with surface water	Lump sum	1		
	Dealing with sub-surface water	Lump sum	1		
	Total for Schedule - Carried forward				

ITEM	DESCRIPTION	UNIT	QTY	Rate	Amount
	Brought forward				
	<u>CULVERTS</u>				
	Rectangular culvert with prefabricated elements;				
	Prefabricated portal culverts; walls and roof combination (2400mm x 1200mm 75S)	m	100		
	<u>CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS</u>				
	Concrete kerbing:				
	Prefabricated kerbing				
	(a) Prefabricated Barrier kerb, SABS 927 fig 6	m	100		
	(b) Transition kerb class 25/19	m	50		
	Cast in situ kerbing				
	(a) 30 Mpa Concrete edge beam (100mm X 150mm)	m ³	35		
	(b) 30 Mpa Concrete edge beam (300mm X 300mm) at intersections	m ³	5		
	(c) 30 Mpa Concrete edge beam (150mm X 250mm) at for handrails	m ³	2		
	Linings for open drains:				
	Cast in situ concrete Class 25/19 lining for chutes with stone pitching	m ³	54		
	cast insitu concrete class 25/19 for v-drains	m ³	45		
	Class U2 surface finish to cast in situ concrete	m ²	500		
	Carried forward				

[illegible]

CHAPTER 5

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>EARTHWORKS AND PAVEMENT LAYERS CONSTRUCTION</u>				
	ROADBED				
	Roadbed construction and compaction				
	Compaction of in-situ material to 90 % of MDD (In situ-G9)	m ³	2200		
	Excavate material to spoil sites designated by the Employer				
	Excavate material to spoil from roadbed construction, material obtained from:				
	(a) Soft excavation	m ³	2000		
	(b) Boulder excavation Class A	m ³	100		
	(d) Hard excavation (other than by blasting)	m ³	100		
	Removal of unsuitable material to spoil				
	In layer thicknesses of 200 mm and less				
	(a) Stable material	m ³	500		
	<u>ROAD PAVEMENTLAYERS</u>				
	Construction of pavement layers				
	Construction of layers using conventional construction methods				
	(a) Lower Selected subgrade layer thickness of 150mm (G7) material compacted to 90% MDD	m ³	2800		
	(b) Upper selected subgradelayer thickness of 150mm (G7) material compacted to 90% MDD	m ³	2600		
	(k) Gravel subbase (unstabilized material) layer thickness of 150 mm(G7) compacted to 93% MDD:	m ³	2 500		
	(n) Gravel base (Chemically stabilized material) layer thickness of 125 mm(C4) compacted to 100% MDD:	m ³	1 600		
	Construction of layers using labour enhancement:				
	(m) Sand layer	m ³	300		
	Carried forward				

[illegible]

CHAPTER 6

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>SEGMENTAL BLOCK PAVING LAYERS</u>				
	Segmental block paving				
	Concrete block paving Type S-A interlocking paving blocks, 80mm thick, for the roadway	m ²	13000		
	Concrete block paving Type S-A interlocking paving blocks, 60mm thick, for the sidewalk	m ²	40		
	Provision and application of approved herbicide and ant poison				
	Provision of material	PC sum	1		
	Contractor's charges and profit added to the prime cost sum	%	10%		
	Total for Schedule - Carried forward				

CHAPTER 11

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>ANCILLARY ROAD WORKS</u>				
	PITCHING, STONEMWORK, CAST IN SITU CONCRETE FOR PROTECTION AGAINST EROSION				
	Stone pitching				
	Grouted stone pitching on a concrete bed	m ²	220		
	Provision of approved herbicides and ant poison				
	Provison of materials	PC.Sum	1		
	Contractor's charges and profit added to the prime cost sum	%	10%		
	<u>NON-STRUCTURAL GABIONS</u>				
	Foundation trench excavation:				
	Excavating all material situated within the following depth ranges below the surface level:				
	(a) 0 m to 1,5 m	m ³	180		
	Extra over sub-item C11.2.1.1 for excavation in hard material, irrespective of depth	m ³	20		
	Excavating soft material within 1,5 m below the surface level using labour enhanced construction methods:	m ³	35		
	Excavating intermediate material within 1,5 m below the surface level using labour enhanced construction methods:	m ³	20		
	Surface preparation for bedding the gabion boxes and mattresses	m ²	560		
	Gabion boxes and mattresses:				
	Galvanized gabion boxes (1,0 m wide by 1,0 m deep)				
	(a) by 2,0 m long mesh Type 80 with 3.7mm Class A	m ³	120		
	Galvanized gabion mattresses (1,0 m diaphragm spacing, 6,0 m long by 2,0 m wide)				
	(a) by 0,3 m deep mesh Type 80 with 3.7mm Class A	m ³	250		
	Geotextile				
	Bidim U14 or similar (MacTex N 20,2 (195g/sqm)	m ²	1000		
	Carried forward			R	-

ITEM	DESCRIPTION	UNIT	QUAN- TITY	RATE	AMOUNT
	Brought forward				
	ROAD RESTRAINT SYSTEMS Erecting of guardrails at 3.81m spacing Complete galvanized system compliant to SANS 1350 (a) On timber posts (ref to drawing...) m 260 (b) Extra over C11.4.1.1(a) and C11.4.1.1(b) for excavating holes of posts using labour enhanced methods (soft and intermediate) m 20 Terminal section for 3.81 guardrails comprising of: (a) End wings to SANS 1350 No 4 Additional guardrail posts for 3.81 m system Timber No 20 On steel posts No 40 Reflective plates Steel plates No 60 Nailing of gang nail plates on top of timber guardrails posts No 110 ROAD SIGNS Road sign boards with painted or coloured semi-matt background. Symbols, lettering and borders in Class I retro-reflective material, where the sign board is constructed from: Regulatory signs, permanent (a) 600 mm diameter (1,4 mm chromadek flatsheeting) No 10 Warning signs, permanent (a) 600 mm diameter (1,4 mm chromadek flatsheeting) No 10 Extra over on item C11.6.1 for using Background of retro-reflective material of: (a) Class I m ² 50 Lettering, symbols and borders of retro-reflective material of: (a) Class III m ² 50				
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	RATE	AMOUNT
	Brought forward				
	Road sign supports (overhead road sign structures excluded):				
	Steel tubing (50 x 50 x 2mm Square tubing)(2m long)	No	20		
	Timber (100mm diameter)	m	20		
	Excavation and backfilling for road sign supports (not applicable to kilometre posts)				
	Excavating soft material and backfilling	m³	50		
	Excavating soft or intermediate material and backfilling using labour enhanced construction methods	m³	20		
	Extra over item C11.6.5.1 and 2 for cement-treated soil backfill	m³	40		
	Extra over item C11.6.5.1 for hard material excavation	m³	5		
	ROAD MARKINGS AND ROAD STUDS				
	Road markings				
	White lines broken or unbroken (Arcrylic paint, 100 mm wide)	km	2		
	Yellow lines broken or unbroken (Arcrylic paint, 100 mm wide)	km	2		
	White lettering and smbols (Arcrylic paint)	m²	100		
	Yellow lettering and smbols (Arcrylic paint)	m²	50		
	Labour enhanced hand painted white lines broken or unbroken (Arcrylic paint, 100 mm wide)	m²	250		
	Labour enhanced hand painted Yellow lines broken or unbroken (Arcrylic paint, 100 mm wide)	m²	100		
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	RATE	AMOUNT
	Brought forward				
	Setting out and premarking the lines (excluding traffic-island markings, lettering and symbols)	km	2		
	LANDSCAPING AND PLANTING PLANTS				
	TRIMMING				
	Hand trimming	m ²	200		
	Preparing the area for grassing				
	Topsoiling within the road reserve where the following material is used				
	(a) Topsoil obtained from within the road reserve or borrow areas	m ³	250		
	Grassing				
	The planting of grass cuttings (type of grass indicated)	ha	0'2		
	Unspecified work for landscaping Provisional sum	Prov sum	1		
	Anti-erosion compound or hydraulic mulches (specify type)	kg	200		
	<u>FINISHING THE ROAD AND ROAD RESERVE AND TREATING OLD ROADS</u>				
	Finishing the road and road reserve				
	Single carriageway road	km	2		
	<u>MISCELLANEOUS</u>				
	Allowance for additional earthworks and shapping of river and river banks	Prov Sum	1		
	Total for Schedule - Carried forward				R0'00

CHAPTER 13

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>STRUCTURES</u>				
	FOUNDATIONS				
	Additional foundation investigation				
	Provisional sum allowed for additional investigations	Prov sum	1		
	EXCAVATIONS				
	Excavating soft material situated within the following successive depth				
	(a) 0 m up to 1.5 m	m³	750		
	Extra over sub item C13.1.3.1 for excavation in hard material irrespective of depth	m³	150		
	Extra over sub item C13.1.3.1 for excavation by hand	m³	150		
	Access and drainage				
	Access	lump sum	1		
	Drainage	lump sum	1		
	Backfill to excavations utilising				
	Material from excavation	m³	50		
	Imported material	m³	100		
	Soil cement	m³	250		
	Fill within a restricted area (extra over item C5.2.2)	m³	10		
	Haul in excise of 1.0 KM on excavated material and on material imported for back filling, foundation fill, and fill for caissons	m³- km	5000		
	Over break in excavation in hard material	m²	100		
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	RATE	AMOUNT
	Brought forward				
	Foundation fill consisting of: Rock fill Concrete blinding 15/19 FALSEWORK, FORMWORK AND CONCRETE FINISH Vertical form work to provide Class F1 surface finish to: (i) Wingwalls walls (ii) Wingwalls Foundations sides (iii) Apron slab sides (iv) Culvert floor sides	 m ³ m ³ m ² m ² m ² m ²	 300 50 20 10 20 40		
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	RATE	AMOUNT
	Brought forward				
	<u>STEEL REINFORCEMENT FOR STRUCTURES</u>				
	Reinforcement for:				
	(a) 230mm thick culvert floor slab				
	(i) High-yield-stress steel bars (type Y)	t	4		
	(b) 250mm thick Deck slab				
	(c) Apron slab				
	(i) Mesh Ref No.245	m ²	300		
	(d) Wingwalls				
	(i) Mild steel bars (type R)	t	2		
	(ii) High-yield-stress steel bars (type Y)	t	5		
	CONCRETE FOR STRUCTURES				
	Cast in situ concrete				
	Strength of concrete				
	(a) Concrete Class 30/19				
	(i) 230mm thick culvert floor slab and ground beams	m ³	120		
	(ii) 300mm thick Wingwalls	m ³	20		
	(b) Concrete Class 25/19				
	(i) Apron slab and edge beams	m ³	100		
	(ii) Mass Concrete	m ³	50		
	(e) Grout				
	(i) Dura Grout infill	m ³	1		
	Curing and surface protection of cast in situ concrete as and where specifically				
	(i) Wingwalls walls	m ²	65		
	(ii) Wingwalls Foundations sides	m ²	65		
	(iii) Apron slab sides	m ²	80		
	(iv) Deck slab sides	m ²	375		
	Carried forward				

ITEM	DESCRIPTION	UNIT	QUAN- TITY	RATE	AMOUNT
	Brought forward				
	JOINTS				
	Filled joints:				
	(a) 10mm thick "jointex" or similar approved				
	(i) Between wingwalls and culvert walls	m ²	7		
	(ii) Between apron slabs and culvert floor	m ²	11		
	(iii) Between apron slabs and wingwalls	m ²	2		
	(b) 12mm Bitumen impregnated softboard joint				
	(i) Construction joints	m ²	12		
	Sealing Joints with				
	(i) "Dow Corning 888" or similar approved	m	95		
	(ii) Polysulphide Sealant	m	50		
	Ancillary Structural Elements				
	Polycrrete railings	m	30		
	Provision for Demolition Works	Prov Sum	1		
	Total for Schedule - Carried forward				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>TESTING MATERIAL AND JUDGEMENT OF WORKMANSHIP</u> Special tests requested by the Engineer Employers's contribution to other special tests (a) Specify test (i) Handling costs and profit in respect of item C20.1.2.2(a)	PC Sum %	1 10%		
	Total for Schedule - Carried forward				

EMPLOYER : DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO : DALRRD-RID-FS-001 (2024/2025)

CONTRACT TITLE : APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE
UGRADING OF 2,01KM SEDIBA ROAD AND CULVERT
CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE
STATE PROVINCE.

SECTION	DESCRIPTION	AMOUNT
CHAPTER 1	GENERAL REQUIREMENTS AND PROVISIONS	R -
CHAPTER 2	SERIVCES	R -
CHAPTER 3	DRAINAGE	R -
CHAPTER 4	EARTHWORK AND PAVEMENT LAYERS: MATERIALS	R -
CHAPTER 5	EARTHWORK AND PAVEMENT LAYERS: CONSTRUCTION	R -
CHAPTER 6	CONCRETE LAYERS	R -
CHAPTER 11	ANCILLARY ROAD WORKS	R -
CHAPTER 13	STRUCTURES	R -
CHAPTER 20	QUALITY ASSURANCE	R -
	SUB TOTAL	R -
	CONTINGENCIES (10%)	R -
	SUB TOTAL (EXCL. VAT)	R -
	15% VALUE ADDED TAX (VAT)	R -
	TOTAL (INCL VAT)	R -
AMOUNT IN WORDS		

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

THE CONTRACT PART C3 SCOPE OF WORK

CONTENTS

C3.1	DESCRIPTION OF THE WORKS	167
1.1	Employer's Objectives	167
1.2	Overview of the Works	167
1.3	Extent of the Works	167
1.4	Location of the Works	168
C3.2	ENGINEERING	168
2.1	Design Services and Activity Matrix	168
2.2	Drawings	169
2.3	Design Procedures	170
C3.3	PROCUREMENT	170
3.1	Preferential Procurement Procedures and Requirements	170
3.2	Use of Local Labour	170
3.3	Subcontractors, SMME's, Females and Youth	171
C3.4	CONSTRUCTION SPECIFICATIONS	172
	Part A : GENERAL	172
A1	Nature of the Ground	172
A2	Construction Programme	172
A3	Site Facilities Available	173
A4	Site Facilities Required	174
A5	Features Requiring Special Attention	174
A6	Applicable Standards and Particular Specifications	184
	Part B : VARIATIONS TO THE STANDARDISED SPECIFICATIONS	185
PSA	General	185
	Part C : PARTICULAR SPECIFICATIONS	190
PY	Day works	191

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

STATUS

In the event of any discrepancy between the Scope of Works and a part or parts of the COTO and SANS 1200 Standardized Specifications, the Bill of Quantities or the Drawings, the Project Specifications shall take precedence and prevail in the Contract.

The Project Specifications form an integral part of the Contract Documents and supplement the Standard Specifications.

In the event of any discrepancy with a part or parts of the Standard Specifications, the Schedule of Quantities or the drawings, the Particular or Project Specifications shall take precedence.

The Standard Specifications, which form part of this contract, have been written to cover all phases of work normally required for road contracts, and they may therefore cover items not applicable to this particular contract.

C3.1: DESCRIPTION OF THE WORKS

3.1.1 EMPLOYER'S OBJECTIVES

The employer's objective is to upgrade the existing Culvert crossing and existing gravel road in Sediba under Mangaung Metro Municipality.

The Employer wishes through this Project to create Job opportunities for the people of Thaba Nchu by introducing Labour Intensive Construction methods and techniques. This initiative aims to produce employment to curb the high levels of unemployment that the people of Thaba Nchu face.

3.1.2 OVERVIEW OF THE WORKS

This Project consists of the upgrade of the existing gravel road to a paved road and construct a 21m (length) culvert culvert crossing. Total length of the road is 2,01 km. The project will further consist of the construction of stormwater management systems. The Works shall be completed in accordance with the terms as specified in this Contract Document.

3.1.3 EXTENT OF THE WORKS

The Works to be carried out by the Contractor under this Contract comprises mainly of the following:

- a) Contractor's establishment on site
- b) Compliance with OHS requirements
- c) Provisions of temporary workforce
- d) Site Clearance
- e) 2,01 km of 80mm interlocking paving blocks,
- f) Mass earthworks (for proposed pavement structure),
- g) Prefabricated concrete kerbing,
- h) Lined Stormwater channels,
- i) Cleaning and shaping of existing unlined stormwater channels,
- j) Gabions,
- k) Edge beams,
- l) Road markings and signs,
- m) Traffic calming devices
- n) Cleaning up the Site and reinstating all access roads to at least their original condition;
- o) De-establishment of site on completion of the works.

The above merely provides an overview to describe the extent of the contract and in no way relieves the Contractor of fulfilling the full scope of the works described in the tender documentation.

NOTE: Tenderers are required to allow in their tendered prices for the supply of all necessary materials and equipment, the supply and use of tools, the provision, operation and maintenance of all Contractor's

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

plant and equipment, the supply and supervision of all labour and workmanship and everything and every service necessary for the construction, completion and maintenance of the Works in the manner required by the Contract and to the entire satisfaction of the Engineer.

3.1.3.2 Available facilities

The Contractor shall make his own arrangements with the necessary authorities for the supply of electricity, telephones, water for testing as well as potable water for drinking.

3.1.4 LOCATION OF THE WORKS

This project is located in the town of Thaba Nchu which is 63km east of Bloemfontein and 17km east of Botshabelo.

LOCATION	POSITION	LONGITUDE	LATITUDE
SEDIBA ACCESS ROAD (Thaba Nchu)	Start	26°56'36.88"E	29°1'42.56"S
	End	26°57'16.66"E	29°0'58.41"S



3.1.5 Access to Works site

The provided coordinates may be used to access the site.

No restriction on access to the Site of Works will be placed on persons or vehicles involved with the execution of the Works but personnel must comply with the security and safety requirements of the Municipality. The Contractor must keep the Employer informed of staff changes. The making good of any damage caused by non-observance of such restrictions will be for the Contractor's account.

Any vehicle used to transport and/or equipment on Site, shall not exceed the maximum permissible axles loading as allowed under the Provincial regulations.

3.1.6 Services known to be in the vicinity of the site

Existing services on site include water pipes, sewer pipes, roads, telephone cables and electrical cables.

3.1.7 Changes to scope of work

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

It is a condition of this contract that the employer reserves the right to limit the total expenditure on the Works due to possible budget constraints. Should the tender sum exceed the budgeted amount, the scope of the works may be reduced at any time before or during the contract period to ensure that the final contract amount does not exceed the budgeted amount.



Contractor



Witness 1



Witness 2



Employer



Witness 1



Witness 2

C3.2 ENGINEERING

3.2.1 DESIGN SERVICES AND ACTIVITY MATRIX

The following responsibilities for design and related documentation are applicable to this Contract:

Design Stage	Works designed by
Concept, feasibility and overall process	Engineer
Basic engineering and detail layouts at tender stage	Engineer
Final design for construction stage	Engineer
Temporary works	Contractor
Preparation of as built drawings	Contractor

3.2.2 Employer's design

The Employer's design is based on available information and the finalisation of details may need to take place after the existing services have been exposed.

3.2.3 Contractor's design

Where the Contractor is to supply the design of designated parts of the permanent Works or temporary Works he shall supply full working drawings supported by a professional engineer's design certificate.

3.2.4 Drawings

The drawings form part of the tender document and are issued for tender purposes only.

The appointed Contractor will be supplied with one A1 paper print and a pdf copy on CD of each of the drawings. This print and pdf copy are issued free of charge and the Contractor will need to make or obtain any additional prints he may require at his own cost.

The Contractor shall use only the dimensions stated in figures on the Drawings in setting out the Works, and dimensions shall not be scaled from the Drawings, unless required by the Engineer. The Engineer will, on the request of the Contractor in accordance with the provisions of the Conditions of Contract, provide such dimensions as may have been omitted from the Drawings.

The Contractor shall ensure that accurate as-built records are kept of all infrastructure installed or relocated during the Contract. The position of pipe bends, junction boxes, duct ends and all other underground infrastructure shall be given by either co-ordinates, or stake value and offset. Where necessary, levels shall also be given. A marked-up set of drawings shall also be kept and updated by the Contractor. This information shall be *supplied* to the Engineer's Representative on a regular basis.

All information in possession of the Contractor, required by the Engineer and/or the Engineer's Representative to complete the as-built/record drawings, must be submitted to the Engineer's Representative before a Certificate of Completion will be issued.

The Drawings prepared by the Employer for the permanent Works are listed and bound in a separate volume. The Employer reserves the right to issue amended and/or additional drawings during the Contract.

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

C3.3 PROCUREMENT

3.3.1 PREFERENTIAL PROCUREMENT PROCEDURES AND REQUIREMENTS

The system of measurement of preferential procurement points shall be as defined in the Section T1.3: Tender Data.

3.3.1.1 Requirements

The Employer intends through this Contract to provide work opportunities for the local residents.

This Contractor shall therefore employ local labour where possible.

3.3.2 Employment targets

3.3.2.1 Employment of local community labour

It is a requirement of the Employer that the contractor appoints and use the local labour.

The service provider is therefore required to limit the use of non-local labour to key personnel only and to employ only local labour on this Contract.

The service provider shall fill in the relevant forms regarding "Key Personnel" and state how many non-local key personnel he intends to employ in the various categories.

The numbers stated in the "Key Personnel" forms shall be strictly controlled during the Contract Period and any increase in numbers shall be subject to the approval of the Project Manager.

The service provider will be expected to procure, deliver and ensure security of material.

The service provider will also be expected to train, supervise and ensure quality on the project.

Local Labour comprising of NARYSEC participants and local community labourers will be utilized for

3.3.2.2 Employment of women

The target for employment of women is 30% of the total workforce.

3.3.2.3 Employment of youth

The target for employment of youth (18-25 years of age) is 30% of the total workforce.

3.3.2.4 Employment of disabled people

A minimum of one (1) disabled person must be employed on this contract.

3.3.2.5 Remuneration of local labourers

The minimum wages shall be those prescribed by SAFCEC for the area in which the works fall.

3.3.3 Contractor's Staff

it is required that the Site Agent for this project to have a NQF level 5 qualification. If the contractor fails to produce such person a suitable Site Agent will be appointed by the Client and paid in full by the Contractor.

3.3.3.1 SUB CONTRACTORS, SMME's, FEMALES & YOUTH

The DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT has a National Rural Youth Services Cooperatives (NARYSEC) Programme, which entails training of rural youth at EFT Colleges. In order for the youth to complete their training and get certificates, they have to get onsite experiential training; hence the DALRRD will place some students to be trained under this contract. The extent of the training required by these youth will be explained upon the appointment of the contractor. The Client will provide daily stipend for all NARYSEC employed.

The Employer reserves the right to delay payments to the Contractor should the Contractor fail to provide any item of the required documentation timeously.

In the event of any discrepancy between the requirements of this Clause and the Procurement Policy, the Procurement Policy shall take precedence.

C3.4 MANAGEMENT

3.4.1 Management of the Works

Though not bound in or issued with this tender document, the following SANS 1921 Construction and Management Requirements for Works Contracts as approved by the Council of the South African Bureau of Standards shall apply to this Contract. The Contractor shall be in possession of these Standards and shall keep a copy of the said document on site for reference by him and the Employer's Agent for the duration of the Contract.

SANS 1921 Part 1	General Engineering and Construction Works
SANS 1921 Part 3	Structural Steelwork
SANS 1921 Part 5	Earthworks Activities which are to be performed by hand
SANS 1921 Part 6	HIV/AIDS Awareness

These Specifications are not issued with this volume but are available at the Contractor's expense from: Standards South Africa. Details are given in Section C3.5.1 above.

3.4.1.1 Planning and programming

In addition to Clause 5.6 of the GCC 2015, the work must be programmed such that the work be completed no later than the month of June 2018. The total duration of the Contract must be indicated by the Contractor. The Contractor will supply the Employer's Agent with the programme with his/her tender called the tender programme. Within 3 weeks of being awarded the WORKS, the Contractor shall provide the Employer's Agent with a revised tender programme to be called the Contract Programme to be approved by the Employer's Agent and used for progress monitoring of the Contractor's construction activities.

Interim progress payment shall not be certified by the Employer's Agent based on the Contract Programme Progress. Payment shall be certified based on actual work done.

The Contractor shall submit within the period stated in the Contract Data the said Contract Programme

3.4.1.1.1 Submitted programme

The Contractor's programme, required in terms of Clause 5.6.1 of GCC 2015, shall be in a bar chart form.

In addition to the requirements of Clause 5.6.1 of GCC 2015, the Contractor's programme shall show:

- a) The various activities, related to a time scale, for each element of the Works, including those of Nominated and/or Subcontractors, in sufficient detail to be able to assess construction progress,
- b) Critical path activities and their dependencies,
- c) Key dates in respect of work to be carried out by others,
- d) Key dates in respect of information to be provided by the Engineer and/or others,

If any change to the critical path occurs, the Contractor shall as soon as practicable notify the Engineer in writing.

The Contractor's programme and method statement will not be accepted as the basis for claims for additional compensation without due reference to all relevant associated factors.

3.4.1.1.2 General Allowances

When drawing up his programme, the Contractor shall, take into consideration and make allowance for, inter alia:

- a) Expected weather conditions and their effects,
- b) Known physical conditions or artificial obstructions,
- c) Searching for, dealing with and carrying out alterations to the existing services,

- d) The accommodation of public access and traffic,
- e) The provision and implementation of the health and safety plan in terms of the Construction Regulations, 2014 of the Occupational Health and Safety Act, and
- f) The design, testing and approval of the concrete mixes.

3.4.1.2 Review of progress

The Contractor shall review his progress each month and should progress lag behind the latest accepted programme, by more than 2 weeks, he shall submit a revised programme and method statement of how he proposes to make up the lost time. If, in the opinion of the Engineer, such revised programme will not make up the lost time, the Engineer shall have the right to request the Contractor to reorganize his work in a manner which will ensure an acceptable programme. Claims for additional payment to meet any costs incurred due to such re-organisation will not be accepted.

3.4.1.3 Methods and procedures

3.4.1.3.1 Method statements

When requested by the Engineer, the Contractor shall submit, within 2 weeks (14 days) of date of such written request, a method statement detailing the Contractor's proposed construction procedure of certain elements of the Works.

No work shall commence before the method statement has been submitted and approved. The approval shall not relieve the Contractor from his responsibilities in terms of the General Conditions of Contract.

3.4.1.3.1 Neatness of the site

The general neatness and tidiness of the vicinity of Senekal are of particular concern. The Works will be visible to the public. The Contractor shall, therefore, on a day to day basis, keep the area of the Works in a condition acceptable to the Engineer.

3.4.1.4 Weather conditions

3.4.1.4.1 Extension of time for completion resulting from abnormal rainfall

Extension of time for completion will not be considered for normal rainfall but only for abnormal rainfall or saturated conditions and will be calculated in accordance with the following method:

- a) The Contractor shall, in his programme, allow for the anticipated number of working days on which work could be delayed - as given in the Schedule below.
- b) Extension of time will be calculated for each calendar month or part thereof over the full period for the completion of the Work, plus any approved extension thereof, as follows:
 - i) A delay caused by abnormal rainfall will only be accepted for extension of time if, in the opinion of the Engineer, it delays an item or items which lie on the critical path determined by the Contractor's programme. Only delays on working days will be considered.
 - ii) Abnormal rainfall will be considered to be days, as approved, on which rain delayed operations, less the anticipated number of days given in the Schedule below.
 - iii) The net extension of time determined for each month, which may be negative, shall accumulate algebraically to determine the net number days for extension of time due to abnormal rainfall, but a negative total at the end of the construction period will not be taken into account.
 - iv) Where a portion of a month is involved, a pro rata number of days shall be calculated.

SCHEDULE

Anticipated number of working days on which work could be delayed as a result of rainfall and saturated conditions.

Month	Nn (days)	Rn (mm)
January	9	104,1
February	8	87,6
March	6	51,4
April	5	54,5
May	2	22,4
June	1	14
July	1	8,2
August	1	9,2
September	2	11,0
October	4	39,3
November	7	70,4
December	10	89,9
Total	56	562

Source: worldweatheronline.com

X = 20 and Y = 10

The additional clauses to the General Conditions of Contract are:

Extensions of time in respect of clause 42 in respect of abnormal rainfall shall be calculated using the following formula for each calendar month or part thereof:

$$V = (Nw - Nn) + \frac{(Rw - Rn)}{X}$$

Where:

V = Extension of time in calendar days in respect of the calendar month under consideration.

Nw = Actual number of days during the calendar month on which a rainfall of 10 mm or more has been recorded.

Nn = Average number of days in the relevant calendar month, (as derived from existing rainfall records provided in the table above), on which a rainfall of Y mm or more per day has been recorded for the calendar month.

Rw = Actual average rainfall in mm recorded for the calendar month under consideration.

Rn = Average rainfall in mm for the calendar month as derived from existing rainfall records as provided in the table above.

For purposes of the Contract Nn, Rn, X and Y shall have those values assigned to them in the South African Weather Service's rainfall records of the nearest station to the site.

If V is negative and its absolute value exceeds Nn, then V shall be taken as equal to minus Nn.

The total extension of time shall be the algebraic sum of all monthly totals for the period under consideration, but if the total is negative the time for completion shall not be reduced due to subnormal rainfall. Extensions of time for part of a month shall be calculated using pro rata values of Nn and Rn.

This formula does not take account flood damage which could cause further or concurrent delays and will be treated separately as far as extension of time is concerned.

The factor (Nw - Nn) shall be considered to represent a fair allowance for variations from the average in the number of days during which rainfall exceeds 10 mm. The factor (Rw-Rn) shall be considered to represent a fair allowance for variations from the average in the number of days during which the rainfall did not exceed 10 mm but wet conditions prevented or disrupted work.

For the purpose of applying the formula, accurate rain gauging shall be taken at a suitable point on the Site and the Contractor shall at his own expense, take all necessary precautions to ensure that rain gauges cannot be interfered with by unauthorized persons.

3.4.1.4.2 Recording of weather

The Contractor shall provide a rain gauge as directed by the Engineer and precautions shall be taken to restrict access to the rain gauge by unauthorised persons.

3.4.1.5 Quality plans and control

The Contractor shall prepare a quality management plan to be followed during the course of the Contract.

The quality management plan shall

- i. clearly indicate the methods, programmes, procedures and other methods that the Contractor intends using as process control to ensure compliance of materials and workmanship with the requirements of the Contract (process control testing)
- ii. Include the proof of status of calibration of all measuring devices that are to be used during the course of the Contract.

3.4.1.6 Environment

3.4.1.6.1 Protection of the environment

3.4.1.6.1.1 Environment management plan

The Contractor shall comply with the provisions of the environmental management specification.

3.4.1.6.1.2 Fires and burning of vegetation

No fires may be lit except at places approved by the relevant authority. The Contractor shall ensure that the fire hazard on and near the Site is reduced to a minimum and shall take immediate and effective steps to extinguish any fire that may break out.

Burning of vegetation and trees cleared from the Site and/or any other material may only be done on site if permitted in writing by the relevant authority, and shall then be strictly controlled by a competent supervisor, shall be carried out strictly in accordance with any directions given and shall be carried out solely at the risk of the Contractor.

3.4.1.6.1.3 Preservation of flora and fauna and soil conservation

The Contractor shall:

- a) take all precautions to prevent:
 - i) the erosion of soils and/or
 - ii) loss of or injury to domestic and other animals from any lands used or occupied by the Contractor;
- b) refrain from destroying, removing or clearing trees, timber and scrub to any extent greater than is necessary for the execution of the Contract,
- c) take care to cause the minimum of disturbance to the fauna and flora.
- d) erect temporary fences on the servitude lines during the construction period to prevent loss of fauna. The fences shall be removed as soon as construction and testing are complete.
- e) take precautions to keep the risk of fire to a minimum,
- f) arrange that timber for firewood be obtained only from such places as may be approved by the Engineer;

- g) take such measures as to ensure that his employees are aware of all laws and restrictions governing the hunting, disturbing, capturing or destroying of animals and birds in the vicinity of the camp or the Works or the taking of fish from any water ; and
- h) prohibit all firearms from the site and temporary camps.

3.4.1.7 Format of communications

Communications and instructions shall be given in writing and sent either by post, or facsimile. Site instructions shall be given in the Site Communication Book, which shall be a triplicate book provided by the Contractor.

3.4.1.8 Management meetings

The Contractor will be required to attend the following site meetings during the term of the contract:

- a) An inaugural site meeting to be held within three weeks after the Commencement Date.
- b) Monthly site meetings from the order to commence the Works until the Completion of the Works.
- c) Monthly Health and Safety meetings.

3.4.1.9 Daily records

Daily records of all site activities and progress of work shall be kept by the Contractor. Any possible causes for delay to the Contract or which may result in additional costs to the Employer shall be recorded as clearly as possible. The records shall also include the plant on Site and personnel employed. The records shall be kept at all times in the Engineer's Site Office.

3.4.1.9.1 Monthly labour returns

The Contractor shall submit with each statement for payment a labour return showing the Number Person Days and Labour Days recorded for the Contract. The returns shall be similar to the format approved by the Engineer.

3.4.1.10 Lighting

Should the Contractor wish to undertake work when natural lighting is inadequate for the type of work to be performed, he shall, at his own expense, provide and maintain in good and safe condition adequate high-powered flood lighting for all the work areas where he is operating.

3.4.1.11 Payment certificates

The statement to be submitted by the Contractor in terms of Clause 6.10 of the General Conditions of Contract shall be prepared in accordance with the standard payment certificate prescribed by the Engineer and shall be provided electronically in Microsoft Excel format.

All costs incurred by the Contractor resulting from the preparation and submission of the statements shall be borne by the Contractor.

3.4.2 Site establishment

3.4.2.1 Services and facilities existing and/or provided by the Employer

3.4.2.1.1 Water and power supply and other services

The Contractor shall make his own arrangements and pay all installation and consumption charges for the supply of water, electrical power and other services required.

3.4.2.1.2 Camps and depot

The Contractor may erect his site offices and storage depot within the boundaries of the area indicated by the Engineer.

No housing is available and the Contractor shall make his own arrangements to house his employees and transport them to and from the Site. All arrangements for housing workmen shall be made in accordance with and subject to applicable regulations and requirements.

3.4.2.2 Facilities provided by the Contractor

3.4.2.2.1 Facilities for the Engineer

The Contractor shall provide for the use of the Engineer, maintain and service, as applicable, the following facilities as specified in SANS 1200 AB and SDAB:

- a) two name-boards,
- b) one furnished office,
- c) conference room (furnished),
- d) latrine and ablution facilities,
- e) carport for 2 vehicles,
- f) 1 x Smart Phone
- g) photo-copying machine,
- h) I7, 12GB Ram notebook computer and A3 printer / scanner,
- j) survey equipment,
- k) two survey assistants,
- m) a site instruction book,
- n) protective clothing,
- o) safety equipment,
- p) medical facilities,
- q) nine 150 mm concrete cube moulds and a temperature-controlled cube-curing water bath,

Unless specified otherwise, on completion of the Works these facilities shall revert to the Contractor who shall remove them from the site excluding items f, g and h.

The term "use of the Engineer" will be deemed to include, as appropriate, use by the Engineer's staff and the Engineer's Representative and his staff.

3.4.3 Existing services

3.4.3.1 Treatment of existing services

3.4.3.1.1 Continuance of operation of existing services

All existing services shall be maintained in operation, unless prior arrangements have been made with the relevant authority and written permission for an interruption of the service has been granted and adequate notice has been given to the affected residents.

3.4.3.1.2 Continuous operation of existing works

The construction works take place around existing services. Existing works must remain in operation at all times. The Contractor shall ensure that, wherever possible, the Employer's personnel have unhindered access to, and use of, all parts of the existing works at all times, as necessary.

The Contractor's operations shall also be carried out in such a way as to minimize the formation of dust and the fouling of water in the existing works.

The Contractor shall provide sufficient notice to the Engineer when he intends to interrupt the operations of the existing works in order to effect connections with the new works. Approval for such work will be given only when the timing of the work is suitable to the Employer.

3.4.3.1.3 Connection to existing services

All connections to the existing systems shall be undertaken in a manner and at times to be approved by the Engineer. It is anticipated that this work may have to be done at night in order to minimise inconvenience to users. No claims for additional payment will be considered in this regard.

3.4.3.1.4 Permits and way leaves

A wayleave from the Electrical Board of the Mangaung Metro Municipality will be required prior to the Contractor commencing work on Site.

3.4.4 Health and safety

3.4.4.1 Health and safety requirements and procedures

3.4.4.1.1 General

In addition to Sub clause 5.7 of SANS 1200 A (5.4 of SANS 1200 AA; 5.8 of SANS 1200 AD; 5.3 of SANS 1200 AH) and the Occupational Health and Safety Specification provide, the Contractor shall comply with the Occupational Health and Safety Act (Act No. 85 of 1993) (OHS Act) and in particular its Construction Regulations, 2014.

3.4.4.1.2 Health and Safety Plan

Without limiting his obligations and liabilities in terms of the Construction Regulations, 2014 of the OHS Act, the Contractor, in his Health and Safety Plan to be submitted in terms of Clause 5.3.1 of the Project Data, shall inter alia deal with the safety provisions he will set up in respect of the aspects specified in the Specification Data and the Standard Specification.

The Health and Safety Plan shall be neatly set out in a lever-arch type file, with labelled dividers for each section

A copy of the approved Health and Safety Plan shall be kept on Site and made available upon request.

3.4.4.1.3 Safety of general public

Open excavations and other hazardous conditions on site shall be barricaded and precautions shall be taken to protect the public from the same in terms of the OHS Act (Clause 4.3.10.2).

As the Works are on an operating water treatment works site, the Contractor shall take special precautions to prevent access to any danger areas on the Works, e.g. by temporary barricades, notices and/or fencing.

The Contractor shall direct, control, facilitate and safeguard all pedestrian traffic during construction of the Works, provide all notices, and arrange for watching and lighting in accordance with the requirements of the relevant authorities

3.4.4.1.4 Sanitary conditions

Unhygienic habits and other behavior that may cause contamination of any part of the Works or the surrounding areas are strictly prohibited. The Contractor shall ensure that sanitary conditions prevail throughout the Site and that all his workmen are aware of, and comply with, this rule.

3.4.4.1.5 Protection of the public

Open excavations and other hazardous conditions on site shall be barricaded and precautions shall be taken to protect the public from the same in terms of the OHS Act.

As the Works are on an operating reservoir site, the Contractor shall take special precautions to prevent access to any danger areas on the Works, e.g. by temporary barricades, notices and/or fencing.

The Contractor shall direct, control, facilitate and safeguard all pedestrian traffic during construction of the Works, provide all notices, and arrange for watching and lighting in accordance with the requirements of the relevant authorities.

3.4.4.1.6 Excavations

Without limiting his responsibility for the safety of his workers in any excavation, the Contractor shall ensure the safety of his workers in trenches and excavations deeper than 1,0 m. in terms of the provisions of the OHS Act. The Contractor may choose to batter excavations to a safe slope if sufficient space is available, or adequately shore the excavations.

C3.4.4.1.7 Health and safety specialist

The Contractor shall employ a health and safety specialist, with suitable and proven qualifications, either on full-time or part-time basis, for the duration of the Contract.

This specialist shall assist with the preparation of the health and safety plan required in terms of the Specification Data, shall provide on-going training for all construction staff (at least 1 hour per week whilst work on site is in progress, in the form of weekly tool-box talks), and shall assist with the upkeep of the Health and Safety Plan and associated regular inspections etc.

C3.4.6.1.8 Monthly health and safety reports

The health and safety specialist required in terms of the Specification Data, shall submit a report to the Engineer at the monthly site meetings, detailing the state of health and safety on the sites over the last month, new risk assessments added, potential new risks, new precautions taken, and summarising the results of various inspections required in terms of the health and safety plan, etc.

If this report is not submitted at each monthly site meeting, the Engineer shall impose a fine of R 1 000.00 on the Contractor, in each instance.

C3.5 HEALTH AND SAFETY

3.5.1 HEALTH AND SAFETY REQUIREMENTS AND PROCEDURES

(a) Construction Regulations, 2014

The Contractor shall be required to comply with the Occupational Health and Safety Act, 1993: Construction Regulations, 2014. Non-compliance with these regulations, in any way whatsoever, will be adequate reason for suspending the Works.

The Contractor shall in terms of regulation 5(1) provide a comprehensive health and safety plan detailing his proposed compliance with the regulations, for approval by the Employer.

The Contractor shall at all times be responsible for full compliance with the approved plan as well as the Construction Regulations and no extension of time will be considered for delays due to non-compliance with the abovementioned plan or regulations.

A payment item is included in the Bill of Quantities to cover the Contractor's cost for compliance with the OHS Act and the abovementioned regulations.

3.5.2 PROTECTION OF THE PUBLIC

Refer to the Occupational Health and Safety Act, 1993 and the Construction Regulations, 2014.

3.5.3 BARRICADES AND LIGHTING

Refer to the Occupational Health and Safety Act, 1993 and the Construction Regulations, 2014.

3.5.4 TRAFFIC CONTROL ON ROADS

Refer to the Occupational Health and Safety Act, 1993 and the Construction Regulations, 2014.

3.5.5 MEASURES AGAINST DISEASE AND EPIDEMICS

Refer to the Occupational Health and Safety Act, 1993 and the Construction Regulations, 2014.

3.5.6 AIDS AWARENESS

Refer to the Occupational Health and Safety Act, 1993 and the Construction Regulations, 2014.

C3.6 CONSTRUCTION**3.6.1 Existing services****3.6.1.1 Damage to services**

The Contractor is required to carry out all of his construction activities with due caution in order to prevent damage to existing services and infrastructure. The Contractor shall repair or arrange to repair any damage to known existing services at his own cost.

The Contractor shall repair or arrange to repair any damage to known existing services at his own cost.

3.6.1.2 Reinstatement of services and structures damaged during construction

The Contractor shall immediately inform the Engineer of any damage to existing services or structures. The Contractor shall take immediate steps to reinstate any damaged services.

3.6.2 Disposal sites

The Contractor shall locate suitable sites, off site for the disposal of cleared vegetation, rubble, unsuitable material, excavation or surplus material. The Contractor shall obtain the Engineer's approval for the site he proposes to use.

Surplus excavation, other than described above, will be spread on site at locations indicated by the Engineer.

3.6.3 Alterations, additions, extensions and modifications to existing works

The Contractor shall satisfy himself that the dimensional accuracy, alignment, levels and setting out of existing structures or components thereof are compatible with the proposed works (including modifications). If the Contractor finds any discrepancy, he shall immediately notify the Engineer in writing of the discrepancy before proceeding with any construction which may be affected by the discrepancy.

Should the Contractor detect any defect(s) in existing structures or works which are likely to affect the integrity or quality of work executed by himself, he shall immediately notify the Engineer in writing. The Engineer will inspect the defect(s) and, if necessary, issue an instruction regarding how the defect(s) are to be repaired. The Contractor shall then execute those repairs to existing structures or works which are prescribed by the Engineer.

3.6.4 FEATURES REQUIRING SPECIAL ATTENTION**3.6.4.1 Aids awareness**

The Contractor is to have sufficient signage regarding HIV/AIDS, notifying the workers of the dangers, and where to obtain the counselling etc.

3.6.4.2 Site maintenance

During progress of the work and upon completion thereof, the Site of the Works shall be kept and left in a clean and orderly condition. The Contractor shall store materials and equipment for which he is responsible in an orderly manner, and shall keep the Site free from debris and obstructions.

3.6.4.3 Testing and quality control

3.6.4.3.1 Contractor to engage services of an independent laboratory

Notwithstanding the requirements of the Specifications pertaining to testing and quality control, the Contractor shall engage the services of an approved independent laboratory to undertake all testing of materials, the results of which are specified in, or may reasonably be inferred from, the Contract. These results will be taken into consideration by the Engineer in deciding whether the quality of materials utilised and workmanship achieved by the Contractor comply with the requirements of the Specifications. The foregoing shall apply irrespective of whether the specifications indicate that the said testing is to be carried out by the Engineer or by the Contractor.

The Contractor shall be responsible for arranging with the independent testing laboratory for the timeous carrying out of all such testing specified in the Contract, at not less than the frequencies and in the manner specified. The Contractor shall promptly provide the Engineer with copies of the results of all such testing carried out by the independent laboratory.

For the purposes of this clause, an "independent laboratory" shall mean a laboratory certified by the South African National Accreditation Systems (SANAS) or approved by the engineer in writing which is not under the management or control of the Contractor and in which the Contractor has no financial interest, nor which has any control or financial interest in the Contractor.

3.6.4.3.2 Additional testing required by the Engineer

In addition to the provisions of Sub clause 3.6.4.3.1: Contractor to engage services of an independent laboratory, the Engineer shall be entitled at times during the Contract to require that the Contractor arrange with the independent laboratory to carry out any such tests, additional to those described in Sub clause 3.6.4.3.1, at such times and at such locations in the Works as the Engineer shall prescribe. The Contractor shall promptly and without delay arrange with the independent laboratory for carrying out all such additional testing as required by the Engineer, and copies of the test results shall be promptly submitted to the Engineer.

3.6.4.3.3 Costs of testing

- (a) Tests in terms of Sub clause 3.6.4.3.1
The costs of all testing carried out by the independent laboratory in accordance with the requirements of Sub clause 3.6.3.1 above shall be borne by the Contractor and shall be deemed to be included in the tendered rates and prices for the respective items of work as listed in the Bill of Quantities and which require testing in terms of the Specifications. No separate payments will be made by the Employer to the Contractor in respect of any testing carried out in terms of Sub clause 3.6.4.3.1

Where, as a result of the consistency of the materials varying or as a result of failure to meet the required specifications for the work, it becomes necessary to carry out additional tests (e.g. re-tests on rectified work and/or replacement materials), the costs of such additional testing shall be for the Contractor's account.

- (b) Additional tests required by the Engineer
The costs of any additional tests required by the Engineer in terms of Sub clause 3.6.4.3.1: Additional testing required by the Engineer, shall be reimbursed to the Contractor against substitution of the Provisional Sum allowed therefore in the Bill of Quantities; provided always that the costs of any such additional tests ordered by the Engineer, the results of which indicate that the quality of the materials utilised and/or the standard of workmanship achieved are/is not in accordance with the specifications, shall not be reimbursable to the Contractor.

3.6.4.4 Contractor supplied equipment

The Contractor shall when required to supply any testing, measuring and/or survey equipment for the Engineer's use provide calibration certificates or verification certificates (as appropriate) for all equipment. This shall apply for both shared equipment as well as for equipment specified to be provided for the Engineer's use on site.

Calibration or verification, by certified authorities shall be subject to the Engineer's approval:

- prior to the delivery of any equipment to the Engineer and
- thereafter at intervals as prescribed for the relevant equipment but not less than every twelve (12) months

The calibration/verification certificate for each item of equipment shall be submitted to the Engineer for approval prior to its use or within seven (7) days of subsequent re-calibration/verification.

Unless otherwise provided for in the bill of quantities the cost of providing the above specified equipment.

Failure to submit certificates shall result in payment for the equipment being withheld.

3.6.4.5 Subcontractors

All matters pertaining to subcontractors (including Nominated Subcontractors) and the work executed by them shall be dealt with directly between the Engineer and the Contractor in the context of all subcontract work being an integral part of the Works for which the Contractor is responsible.

The Engineer will not liaise directly with any subcontractors nor will he issue instructions concerning the subcontract works directly to any subcontractor.

All matters arising from the subcontract agreements shall be dealt with directly between the Contractor and the subcontractors and the Engineer will not become involved.

3.6.4.6 Opening up and closing down of designated borrow pits

Measurement and payment for opening up and closing down designated borrow pits, including removing and stockpiling overburden and restoring the Site, shall be made under item 8.3.4 of SANS 1200 D. This item applies to all borrow material required under this Contract.

The requirements of Sub clause 5.2.2.2 of SANS 1200 D regarding the opening up, maintenance and closing down of borrow pits shall be adhered to.

3.6.4.7 Monthly statements and payment certificates

The statement to be submitted by the Contractor in terms of Clause 6.10 of the Conditions of Contract shall be prepared by the Contractor at his own cost, strictly in accordance with the standard payment certificate prescribed by the Engineer, in digital electronic computer format. The Contractor shall, together with a copy of the digital electronic computer file of the statement, submit two (2) A4 size paper copies of the statement.

For the purposes of the Engineer's payment certificate, the Contractor shall subsequently be responsible, at his own cost, for making such adjustments to his statement as may be required by the Engineer for the purposes of accurately reflecting the actual quantities and amounts which the Engineer deems to be due and payable to the Contractor in the payment certificate.

The Contractor shall, at his own cost, make the said adjustments to the statement and return it to the Engineer within three (3) normal workings days from the date on which the Engineer communicated to the Contractor the adjustments required. The Contractor shall submit to the Engineer five (5) sets of A4 size paper copies of such adjusted statement, together with a copy of the electronic digital computer file thereof.

Any delay by the Contractor in making the said adjustments and submitting to the Engineer the requisite copies of the adjusted statement for the purposes of the Engineer's payment certificate will be added to the times allowed to the Engineer in terms of Clause 6.10.4 of the Conditions of Contract to submit the signed payment certificate to the Employer and the Contractor. Any such delay will also be added to the period in which the Employer is required to make payment to the Contractor.

3.6.4.8 Workmanship and quality control

The onus to produce work that conforms in quality and accuracy of detail to the requirements of the Specifications and Drawings rests with the Contractor, and the Contractor shall, at his own expense, institute a quality control system and provide suitably qualified and experienced engineers, foremen, surveyors, materials technicians, other technicians and technical staff, together with all transport, instruments and equipment to ensure adequate supervision and positive control of the Works at all times.

The cost of supervision and process control, including testing carried out by the Contractor, will be deemed to be included in the rates tendered for the related items of work.

The Contractor's attention is drawn to the provisions of the various Standardized Specifications regarding the minimum frequency of testing required. The Contractor shall, at his own discretion, increase this frequency where necessary to ensure adequate control.

On completion and submission of every part of the work to the Engineer for examination and measurement, the Contractor shall furnish the Engineer with the results of the relevant tests, measurements and levels to demonstrate the achievement of compliance with the Specifications.

C3.6.5 VARIATIONS AND ADDITIONS TO SANS 1200 STANDARDIZED SPECIFICATIONS AND PARTICULAR SPECIFICATIONS

The Specification Data gives amendments and additions to the specifications that are listed in the List of Applicable Specifications. Clause headings are prefixed by the letters "SD" followed by alphabetic and numeric characters which identify the specification and main clause of the applicable specification. Sub-clauses are numbered sequentially. The clause reference to which a sub-clause refers, either to amend or to add to, is given after the sub-clause heading. Where the Specification Data sub-clause is an addition and there is no appropriate clause in the applicable specification to which to link it, no clause reference is given in the heading.

Should any requirement of the Specification Data conflict with any requirement of the specifications listed, the requirement of the Specification Data shall prevail.

1. Management

- 1.1 Although not bound in or issued with this document, the following Standardised Specifications for Civil Engineering Construction, as amended in the Project Specifications, form part of this document. (Notwithstanding Sub clause 2.2 of SANS 1200A*, the edition specified below shall apply).

SANS 1200 A	-	1986: General
SANS 1200 AB	-	1986: Engineer's Office

- 1.2 The following Standard and Particular Specifications, as bound in this document, and as amended in the Project Specifications, shall apply:

Project Specific Health and Safety Specification
Environmental Best Practice Specifications: Construction

2. Construction

- 2.1 Although not bound in nor issued with this document, the following Standardised Specifications for civil Engineering Construction, as amended in the Project Specifications, form part of this document and, notwithstanding Sub-clause 2.2 of SANS 1200 A*, the editions specified below shall apply:

SANS 1200 A	:	GENERAL (1986)
SANS 1200 AB	:	ENGINEER'S OFFICE (1986)
SANS 1200 C	:	SITE CLEARANCE (1982)
SANS 1200 D	:	EARTHWORKS (1990)
SANS 1200 ME	:	SUBBASE

SANS 1200 MK**KERBING AND CHANNELLING**

- Note 1 The Standard Specifications are not bound into the tender and contract documents, but are available at the Tenderer's/Contractor's expense from the South African Bureau of Standards in Pretoria, Private Bag X191, PRETORIA, 0001.
- Note 2 Each of the Standard Specifications contains an appendix, which in turn lists further specifications, which are not bound into the tender and contract documents.
- Note 3 Both of the Standard Specifications, as well as those specifications that are listed in the appendix to the Standard Specifications, shall apply to the Contract to the same extent as if each of these specifications had been bound into the tender/contract documents.

SDA GENERAL**SDA 1 SCOPE**

REPLACE THE CONTENTS OF SUBCLAUSE 1.1, INCLUDING THE NOTES, WITH THE FOLLOWING:

"1.1 This specification covers requirements, principles and responsibilities of a general nature which are generally applicable to civil engineering construction and building works contracts, as well as the requirements for the Contractor's establishment on the Site."

SDA 2 INTERPRETATIONS**PSA2.1 APPLICATION**

Save by arrangement with the Employer's Agent, the Contractor will not be restricted in the use of resources and in particular in the use of mechanical plant.

SDA 2.3 DEFINITIONS

IN THE OPENING PHRASE BETWEEN THE WORDS "specification" AND "the following", INSERT THE WORDS "the definitions given in the Conditions of Contract and".

(a) General

ADD THE FOLLOWING DEFINITIONS:

" 'General Conditions' and 'Conditions of Contract': The General Conditions of Contract specified for use with this Contract, together with the Contract Data (GCC 2015) as applicable.

'Specified': As specified in the Standardized Specifications, the Drawings or the Project Specifications. 'Specifications' shall have the corresponding meaning."

The terms "ESCOM", "ESC" and "Electricity Supply Commission" shall mean "Eskom".

The terms "GPO", "P&T", "Department of Posts and Telecommunications" and "Telkom" shall mean "Telkom SA Limited".

Except for references to the Bureau itself, and to the (official) SANS mark, the term "SANS" shall mean "SANS".

The term "Schedule of Quantities" and "Bill of Quantities" shall mean the same.

The term "Project Specification" shall mean that portion of the Scope of the Works that completes and/or amends the standardised and standard specifications.

(c) Measurement and payment

REPLACE THE DEFINITIONS FOR "Fixed charge", "Time-related charge" AND "Value-related charge" WITH THE FOLLOWING:

" 'Fixed charge': A charge that is not subject to adjustment on account of variations in the value of the Contract Price or the time allowed in the Contract for the completion of the work.

'Time-related charge': A charge, the amount of which varies in accordance with the Time for Completion of the Works, adjusted in accordance with the provisions of the Contract.

'Value-related charge': A charge, the amount of which varies pro rata with the final value of the measured work executed and valued in accordance with the provisions of the Contract.' "

SDA 2.4 ABBREVIATIONS

(a) Abbreviations relating to standard documents

ADD THE FOLLOWING ABBREVIATION:

"CKS: SABS Co-ordinating Specification."

SDA2-8 Items in Bill of Quantities - Principle (Subclause 2.8.1)

In the fourth line of Subclause 2.8.1, after the word "specification", add: "or in the measurement and payment clause of the standard specification, particular specification or Specification Data".

Add the following paragraphs:

"The Contractor shall be deemed to have inspected and examined the Site and its surroundings and information available in connection therewith and to have satisfied himself before submitting his tender as to

- (a) the form and nature of the Site and its surroundings, including subsurface conditions,
- (b) the hydrological and climatic conditions,
- (c) the extent and nature of work and materials necessary for the execution and completion of the Works,
- (d) the means of access to the Site and the accommodation he may require

and, in general, shall be deemed to have obtained all information as to risks, contingencies and all other circumstances which may influence or affect his tender.

The Contractor shall be deemed to have based his tender on the technical data given in the Documents and, if in the performance of the Contract any circumstances shall differ from the said technical data, which difference causes delay or additional Cost, the Contractor shall be entitled to make a claim in accordance with Clause 10.1.1.

The Contractor shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for the Works and of the rates and prices stated in the priced Bill of Quantities and the Schedule of Rates and Prices (if any) or in the specification, which rates and prices shall (except in so far as otherwise provided in the Contract) collectively cover full payment for the discharge of all his obligations under the Contract and all matters and things necessary for the proper completion of the Works."

SDA 3 MATERIALS

SDA 3.1 QUALITY

ADD THE FOLLOWING AT THE END OF SUBCLAUSE 3.1:

"All manufactured materials supplied shall be new materials unless the contrary is specified. All materials specified to be in accordance with SABS Specifications shall bear the SABS mark, where such a mark is available for the type of product."

SDA 4 PLANT

SDA 4.1 SILENCING OF PLANT

REPLACE THE CONTENTS OF SUBCLAUSE 4.1 WITH THE FOLLOWING:

"The Contractor's attention is drawn to the applicable regulations pertaining to noise and hearing conservation, framed under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) as amended.

The Contractor shall at all times and at his own cost, be responsible for implementing all necessary steps to ensure full compliance with such regulations, including but not restricted to the provision and use of suitable and effective silencing devices for pneumatic tools and other plant which would otherwise cause a noise level in excess of that specified in the said regulations.

Where appropriate, the Contractor shall further, by means of temporary barriers, effectively isolate the source of such noise in order to comply with the said regulations."

SDA4-2 CONTRACTOR'S OFFICES STORES AND SERVICES

ADD THE FOLLOWING ATE THE END OF SUBCLAUSE 4.2:

The latrine services required by the General Conditions of Contract and Clause 28 of the Construction Regulations, shall be of the chemical type and shall be readily accessible to workers at all areas of the site.

The Contractor shall make all the necessary arrangements with the relevant local authority for the disposal of the contents of the toilets on a regular basis.

The suitable first aid services required in terms of Subclause 4.2 of SANS 1200 A shall include, inter alia, a First Aid cabinet fully equipped and maintained with at least the minimum contents as listed in the Annexure (Regulation 3) to the General Safety Regulations of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), to deal with accidents and ailments which are likely to occur during the construction period.

The Contractor shall provide personal safety equipment and facilities as required by Regulation 2 of the General Safety Regulations of the Occupational Health and Safety Act, 1993 (Act 85 of 1993).

SDA 5 CONSTRUCTION

SDA5-1 Survey

SDA5-1.1 Setting out of the Works. (Subclause 5.1.1)

Before commencing any construction, the Contractor shall check the relative positions and levels of all reference pegs and bench marks and inform the Engineer of any discrepancy.

Add to Subclause 5.1.1

"The Contractor shall be responsible for the true and proper setting out of the Works and for the correctness of the position, levels, dimensions and alignment of all parts of the Works and for the provisions of all necessary instruments, appliances and labour in connection therewith.

The Contractor shall carefully protect and preserve all benchmarks, sight-rails, pegs and other things used in setting out the Works.

The checking of any setting-out or of any line or level by the Engineer shall not relieve the Contractor of his responsibility for the correctness thereof.

If at any time during the progress of the Works, any error shall appear or arise in the position, levels, dimensions or alignment of any part of the Works, the Contractor, on being required to do so by the Engineer, shall at his own expense rectify such error to the satisfaction of the Engineer, but if such error is based on incorrect data supplied in writing by the Engineer or if there is any delay in providing the particulars required, the Contractor shall, in respect of that delay and the Cost of such RETICULATION, be entitled to make a claim in accordance with Clause 10.1.1."

The Contractor shall advise the Engineer of any conflict between the position of any part of the Works and an existing feature.

SDA 5.2 WATCHING, BARRICADING, LIGHTING AND TRAFFIC CROSSINGS.

ADD THE FOLLOWING AFTER THE SECOND SENTENCE OF SUBCLAUSE 5.2:

"The Contractor shall, in connection with the Works, provide and maintain all signs, signboards, lights, barriers, barricades, fencing and watching when and where:

- a) specified in or reasonably to be inferred from the Contract, or
- b) required by any competent statutory or other authority, or
- c) required by the Engineer for the protection of the Works or for the safety or convenience of the public or others;

provided that, if the Engineer shall instruct the Contractor to provide any sign, signboard, light, barrier, barricade, fencing or watching not included in paragraphs (a), (b) or (c), such requirement shall constitute a variation by the Engineer in terms of Clause 6.4 of the General Conditions of Contract".

All temporary signs shall be of the type and size required for rural roads, as applicable, as specified in the "Southern African Development Community Road Traffic Signs Manual" and Chapter 13, [Roadworks Signing] of the South African Road Traffic Signs Manual".

Unless the closing of streets, accesses and thoroughfares has been properly arranged, the Contractor shall accommodate and provide for through traffic, traffic at crossings and vehicular access to houses and buildings at all times. If necessary, safe ramps to mount road kerbs shall be provided where traffic is to be diverted.

SDA 5.3 PROTECTION OF EXISTING STRUCTURES

REPLACE "Machinery and Occupational Safety Act, 1983 (Act No 6 of 1983)" *WITH* "Occupational Health and Safety Act, 1993 (Act No 85 of 1993), as amended," *AND INSERT THE FOLLOWING AFTER* "(Act No. 27 of 1956)": "as amended".

SDA 5.4 PROTECTION OF OVERHEAD AND UNDERGROUND SERVICES

REPLACE THE HEADING AND THE CONTENTS OF SUBCLAUSE 5.4 WITH THE FOLLOWING:

"SDA 5.4 LOCATION AND PROTECTION OF EXISTING SERVICES

SDA 5.4.1 Location of existing services

Before commencing with any work in an area, the Contractor shall ascertain the presence and actual position of all services which can reasonably be expected by an experienced and competent contractor to be present on, under, over or within the Site.

Without in any way limiting his liability in terms of the Conditions of Contract in relation to damage to property and interference with services, the Contractor shall, in collaboration with the Engineer, obtain the most up-to-date plans as are available, showing the positions of services existing in the area where he intends to work. Neither the Employer nor the Engineer offers any warranty as to the accuracy or completeness of such plans and because services can often not be reliably located from plans, the Contractor shall ascertain the actual location of services depicted on such plans by means of careful inspection of the Site.

Thereafter, the Contractor shall, by the use of appropriate methodologies, carefully expose the services at such positions as are agreed to by the Engineer, for the purposes of verifying the exact location and

position of the services. Where the exposure of existing services involves excavation to expose underground services, the further requirements of subclauses 4.4 and 5.1.2.2 of SABS 1200 D (as amended) shall apply.

The aforesaid procedure shall also be followed in respect of services not shown on the plans but which may reasonably be anticipated by an experienced Contractor to be present or potentially present on the site.

All services, the positions of which have been determined as aforesaid at the critical points, shall henceforth be designated as 'known services' and their positions shall be indicated by the Contractor on a separate set of drawings, a copy of which shall be furnished to the Engineer without delay.

As soon as any service which has not been identified and located as described above is encountered on, under, over or within the site, it shall henceforth be deemed to be a known service and the aforesaid provisions pertaining to locating, verifying and recording its position on the balance of the site shall apply. The Contractor shall notify the Engineer immediately when any such service is encountered or discovered on the Site.

Whilst he is in possession of the Site, the Contractor shall be liable for all loss of or damage as may occur to

- (a) known services, anywhere along the entire lengths of their routes, as may reasonably be deduced from the actual locations at which their positions were verified as aforesaid, due cognizance being taken of such deviations in line and level which may reasonably be anticipated, and
- (b) any other service which ought reasonably to have been a known service in accordance with the provisions of this clause.

The Contractor shall also be liable for consequential damage in regard to (a) and (b), whether caused directly by the Contractor's operations or by the lack of proper protection.

No separate payment will be made to the Contractor in respect of his costs of providing, holding available on the Site and utilising the said detecting and testing equipment, nor for any costs incurred in preparing and submitting to the Engineer the Drawings as aforesaid. These costs shall be deemed included in the Contractor's other tendered rates and prices included in the Contract.

Payment to the Contractor in respect of exposing services at the positions agreed by the Engineer and as described above will be made under the payment items (if any) as may be provided for in the respective sections of the specifications pertaining to the type of work involved.

SDA 5.4.2 Protection during construction

The Contractor shall take all reasonable precautions and arrange its operations in such a manner as to prevent damage occurring to all known services during the period which the Contractor has occupation and/or possession of the Site.

Services left exposed shall be suitably protected from damage and in such a manner as will eliminate any danger arising therefrom to the public and/or workmen, all in accordance with the requirements of the prevailing legislation and related regulations.

Unless otherwise instructed by the Engineer, no services shall be left exposed after its exact position has been determined and all excavations carried out for the purpose of exposing underground services shall be promptly backfilled and compacted. In roadways, the requirements of subclause 5.9 of SABS 1200 DB should be observed. In other areas compaction is to be to 90% modified AASHTO density.

SDA 5.4.3 Alterations and repairs to existing services

Unless the contrary is clearly specified in the Contract or ordered by the Engineer, the Contractor shall not carry out alterations to existing services. When any such alterations become necessary, the Contractor shall promptly inform the Engineer, who will either make arrangements for such work to be executed by the owner of the service, or instruct the Contractor to make such arrangements himself.

Should damage occur to any existing services, the Contractor shall immediately inform the Engineer, or when this is not possible, the relevant authority, and obtain instructions as to who should carry out repairs. In urgent cases, the Contractor shall take appropriate steps to minimise damage to and interruption of the

service. No repairs of telecommunication cables or electric power lines and cables shall be attempted by the Contractor.

Before the commencement of any excavation the Contractor shall confirm the name and telephone number of the relevant officials directly concerned with the known or suspected services, shall acquaint himself with the position of the control points of the services and shall have readily available the equipment necessary to shut-off and isolate any such service. The Contractor shall liaise with the relevant authorities or controlling bodies for the necessary temporary closure of any services during construction.

PSA5.5 DEALING WITH WATER ON THE WORKS

The Contractor's attention is drawn to the fact that, apart from normal dealing with stormwater and seepage water which may influence the construction of the permanent Works, special arrangements and de-watering measures will have to be made to control and/or remove water for the protection of excavations.

PSA5.8 GROUND AND ACCESS TO THE WORKS

Refer also Clause C3.1.4

The Contractor shall provide temporary access to the Works and to the dumping areas/ spoil site, as may be required by him and to the approval of the Employer's Agent.

PSA5.9 WORKMAN'S COMPENSATION ACT

All labour employed on the Site shall be covered by the Workmen's Compensation Act. The Contractor shall pay in full, such amounts, as are due in terms of the Act, including the payment of the necessary levies.

The manner in which Workman's Compensation will be handled, shall be resolved by the Contractor with all the relevant parties at the commencement of the Contract.

SDA 5.7 SAFETY

REPLACE THE CONTENTS OF SUBCLAUSE 5.7 WITH THE FOLLOWING:

"Pursuant to the provisions of the Conditions of Contract, and without in any way limiting the Contractor's obligations thereunder, the Contractor shall at his own expense (except only where specific provision (if any) is made in the Contract for the reimbursement to the Contractor in respect of particular items), provide the following:

- (a) Provide to its Employees on the site of the works, all safety materials, clothing and equipment necessary to ensure full compliance with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) as amended (hereinafter referred to as the Act) at all times, and shall institute appropriate and effective measures to ensure the proper usage of such safety materials, clothing and equipment at all times;
- (b) Provide, install and maintain all barricades, safety signage and other measures to ensure the safety of workmen and all persons in, on and around the site, as well as the general public;
- (c) Implement on the site of the works, such procedures and systems and keep all records as may be required to ensure compliance with the requirements of the Act at all times;
- (d) Implement all necessary measures so as to ensure compliance with the Act by all subcontractors engaged by the Contractor and their employees engaged on the works;
- (e) Full compliance with all other requirements pertaining to safety as may be specified in the Contract.

The Employer and the Engineer shall be entitled, although not obliged, to make such inspections on the site as they shall deem appropriate, for the purpose of verifying the Contractor's compliance with the requirements of the Act. For this purpose, the Contractor shall grant full access to the site of all parts of the site and shall co-operate fully in such inspections and shall make available for inspection all such documents and records as the Employer's and/or Engineer's representative may reasonably require.

Where any such investigations reveal, or where it comes to the Engineer's attention that the Contractor is in any way in breach of the requirements of the Act or is failing to comply with the provisions of this clause, the Engineer shall, in accordance with the provisions of Clause 5.11.2 (GCC 2015) of the Conditions of Contract, be entitled to suspend progress on the works or any part thereof until such time as the Contractor has demonstrated to the satisfaction of the Engineer, that such breach has been rectified.

The Contractor shall have no grounds for a claim against the Employer for extension of time and/or additional costs if the progress on the works or any part thereof is suspended by the Engineer in terms of this clause, and the Contractor shall remain fully liable in respect of the payment of penalties for late completion in accordance with the provisions of Clause 5.13.1 (GCC 2015) of the Conditions of Contract should the Contractor fail to complete the Works on or before the specified due completion date in consequence of the suspension.

Persistent and repeated breach by the Contractor of the requirements of the Act and/or this clause shall constitute grounds for the Engineer to act in terms of Clause 9.2.1.1 (GCC 2015) of the Conditions of Contract and for the Employer to cancel the Contract in accordance with the further provisions of the said Clause 9.2.1 (GCC 2015)."

ADD THE FOLLOWING SUBCLAUSES TO CLAUSE 5:

SDA 5.9 SITE MEETINGS

The Contractor or his authorised agent will be required to attend regular site meetings, which shall normally be held once a month on dates and at times determined by the Engineer, but in any case, whenever reasonably required by the Engineer. Unless otherwise indicated in the Contract or instructed by the Engineer, such meetings shall be held at the Contractor's offices on the site. At such monthly meetings, matters such as general progress on the works, quality of work, problems, claims, payments, and safety shall be discussed, but not matters concerning the day-to-day running of the Contract.

SDA 6 TOLERANCES

ADD THE FOLLOWING SUBCLAUSE TO CLAUSE 6:

"SDA 6.4 USE OF TOLERANCES

No guarantee is given that the full specified tolerances will be available independently of each other, and the Contractor is cautioned that the liberal or full use of any one or more of the tolerances may deprive him of the full or any use of tolerances relating to other aspects of the work.

Except where the contrary is specified, or when clearly not applicable, all quantities for measurement and payment shall be determined from the 'authorised' dimensions. These are specified dimensions or those shown on the Drawings or, if changed, as finally prescribed by the Engineer, without any allowance for the specified tolerances. Except if otherwise specified, all measurements for determining quantities for payment will be based on the 'authorised' dimensions.

If the work is constructed in accordance with the 'authorised' dimensions plus or minus the tolerances allowed, the calculation of quantities will be based on the 'authorised' dimensions, regardless of the actual dimensions to which the work has been constructed.

When the work is not constructed in accordance with the 'authorised' dimensions plus or minus the tolerances allowed, the Engineer may nevertheless, at his sole discretion, accept the work for payment. In such cases no payment shall be made for quantities of work or material in excess of those calculated for the 'authorised' dimensions, and where the actual dimensions are less than the 'authorised' dimensions minus the tolerance allowed, quantities for payment shall be calculated based on the actual dimensions as constructed."

SDA 7 TESTING

SDA 7.1 PRINCIPLES**SDA 7.2 APPROVED LABORATORIES**

REPLACE THE CONTENTS OF SUBCLAUSE 7.2 WITH THE FOLLOWING:

"Unless otherwise specified in the relevant specification or elsewhere in the Project Specification, the following shall be deemed to be approved laboratories in which design work, or testing required in terms of a specification for the purposes of acceptance by the Engineer of the quality of materials used and/or workmanship achieved, may be carried out:

- (a) Any testing laboratory certified by the South African National Accreditation Systems (SANAS) in respect of the nature and type of testing to be undertaken for the purposes of the Contract;
- (b) Any testing laboratory owned, managed or operated by the Employer or the Engineer;
- (a) Any testing laboratory established and operated on the Site by or on behalf of the Employer or the Engineer.
- (d) Any other laboratory that the Engineer approves in his absolute discretion."

SDA 8 MEASUREMENT AND PAYMENT**SDA 8.1 MEASUREMENT****SDA 8.1.1 Method of measurement, all sections of the Schedule**

IN THE SECOND LINE OF SUBCLAUSE 8.1.1, AFTER THE WORDS"

standardized specification or in" *ADD "BETWEEN THE WORDS "specification" AND "the following", INSERT THE WORDS"* the measurement and payment clause of the standard specification, particular specification or".

DELETE THE WORDS "and South West Africa".

SDA 8.1.2 Preliminary and General item or section**SDA 8.1.2.1 Contents**

REPLACE THE LAST SENTENCE OF SUBCLAUSE 8.1.2.1(b) WITH THE FOLLOWING:

"Separate items will be scheduled to cover the fixed, value-related and time-related components of the Contractor's preliminary and general costs."

SDA 8.1.2.2 Tendered sums

REPLACE THE CONTENTS OF THIS SUBCLAUSE WITH THE FOLLOWING:

"Except only where specific provision is made in the Specifications and/or the Schedule of Quantities for separate compensation for any of these items, the Contractor's tendered sums under items SDA 8.3 and SDA 8.4 shall collectively cover all charges for:

- Risks, costs and obligations in terms of the Conditions of Contract and of this standardized specification;
- Head-office and site overheads and supervision;
- Profit and financing costs;
- Expenses of a general nature not specifically related to any item or items of the permanent or temporary work;
- providing such facilities on site as may be required by the Contractor for the proper performance of the Contract and for its personnel, including, but without limitation, providing offices, storage facilities, workshops, ablutions, services such as water, electricity, sewage and rubbish disposal, access roads and all other facilities required, as well as for the maintenance and removal on completion of the works of these facilities and cleaning-up of the site of the Contractor's establishment and reinstatement to not less than its original condition;

- Providing the facilities for the Engineer and his staff as specified in the Contract and their removal from the site on completion of the Contract;
- Erection, maintenance and removal of temporary fencing and barricades;
- Dealing with water (Subclause 5.5);
- Access to works (Subclause 5.8); and
- Providing and maintaining the fire-fighting equipment, as well as training the work teams in their use."

SDA 8.2 PAYMENT

SDA 8.2.1 Fixed-charge and value-related items

REPLACE THE CONTENTS OF SUBCLAUSE 8.2.1 WITH THE FOLLOWING:

SDA 8.2.1.1 Fixed-charge items

"Payment of fixed charges in respect of item 8.3.1 will be made as follows:

- (a) EIGHTY PER CENT (80%) of the sum tendered will be paid when the facilities have been provided and approved;
- (b) The remaining TWENTY PER CENT (20%) will be paid when the works have been completed, the facilities have been removed and the site of the Contractor's establishment has been cleared and cleaned to the satisfaction of the Engineer.

No adjustment will be made to the sum tendered in respect of item 8.3.1 should the value of the works finally executed or the time for completion vary in any way from that specified in the tender.

SDA 8.2.1.2 Value-related items

Payment for the sum tendered under item 8.3.2 will be made in three separate instalments as follows:

- (a) The first instalment, which is 40% of the sum, will be paid when the Contractor has fulfilled all his obligations to date under this specification, the General Conditions of Contract and the Contract Data (GCC 2015), and when the value of work certified for payment, excluding materials on site and payments for preliminary and general items, is equal to not less than 5% of the total value of the work listed in the Schedule of Quantities.
- (b) The second instalment, which is 40% of the sum, will be made when the amount certified for payment, including retention moneys but excluding this second instalment, exceeds 50% of the tender sum.
- (c) The final payment, which is 20% of the sum, will be made when the works have been certified as completed and the Contractor has fulfilled all his obligations to date under this Specification, the General Conditions of Contract and the Contract Data (GCC 2015).

Should the value of the measured work finally completed be more or less than the tender sum, the sum tendered under item 8.3.2 will be adjusted up or down in accordance with the provisions of Clause 6.11.1 (GCC 2015) of the Conditions of Contract amended to clause 6.11 of the variation of the conditions of contract, and this adjustment will be applied to the third instalment."

SDA 8.2.2 Time-related items

REPLACE THE CONTENTS OF SUBCLAUSE 8.2.2 WITH THE FOLLOWING:

"Subject to the provisions of subclauses 8.2.4, payment under item 8.4.1 (time-related item) will be made monthly in equal amounts, calculated by dividing the sum tendered for the item by the tendered Contract period in months, provided always that the total of the monthly amounts so paid for the item is not out of proportion to the value of the progress of the Works as a whole."

Notwithstanding the stipulation of Subclause 8.2.2, an approved extension of time will only entitle the Contractor to payment in terms of clause 5.12.3 of GCC 2015.

SDA 8.3 SCHEDULED FIXED-CHARGE AND VALUE-RELATED ITEMS

REPLACE THE CONTENTS OF SUBCLAUSE 8.3.1 WITH THE FOLLOWING:

"SDA 8.3.1 Fixed preliminary and general charges Unit: sum

The sums tendered shall include full compensation for all fixed-charge preliminary and general charges as described in subclause SDA 8.1.2.2. Payment will be made as described in subclause SDA 8.2.1.1.

Payment for "operation and maintenance of facilities for the Engineer", in accordance with Subclause 8.4.2.1 will not be authorized by the Engineer until the name board has been erected and approved.

SDA 8.3.2 Value-related preliminary and general charges Unit: sum

The sums tendered shall include full compensation for all value-related preliminary and general charges as described in subclause SDA 8.1.2.2. Payment will be made as described in subclause SDA 8.2.1.2."

SDA 8.4 SCHEDULED TIME-RELATED ITEMS

REPLACE THE CONTENTS OF SUBCLAUSE 8.4 WITH THE FOLLOWING:

"SDA 8.4.1 Time-related preliminary and general charges Unit: sum

The sum tendered shall include full compensation for all time-related preliminary and general charges as described in subclause SDA 8.1.2.2. Payment will be made as described in subclause SDA 8.2.2."

SDA 8.5 SUMS STATED PROVISIONALLY BY THE ENGINEER

REPLACE THE CONTENTS OF SUBCLAUSE 8.5 WITH THE FOLLOWING:

"SDA 8.5.1 Works executed by the subcontractor

(a) Description of item to which Prime Cost Sum applies Unit: Prov Sum

(b) Charge required by Contractor on subitem (a) above Unit: %

Subitems (a) and (b) will be provided in the Schedule of Quantities for each different Subcontract included in the Contract.

The Contractor shall be reimbursed under subitem (a), in substitution of the respective Provisional Sums (if any) allowed in the Schedule of Quantities, the amounts actually paid or payable by the Contractor to the respective Nominated Subcontractors, in accordance with the provisions of Clause 6.6 of the Conditions of Contract.

The Contractor shall be paid under subitem (b), either:

(a) where the unit of measurement for subitem (b) was specified as being a percentage, the respective percentage, as stated by the Contractor in its tender, of the amount certified by the Engineer for payment under the related subitem (a), all in accordance with the provisions of Clause 6.6.1.2.1 of the Conditions of Contract, or

(b) where the unit of measurement for subitem (b) was specified as being a lump sum, an amount which is in the same proportion to the amount certified for payment under subitem (a) and the tendered lump sum is to the amount of the Provisional Sum stated under subitem (a) in accordance with the provisions of Clause 6.6.1.2.2.

The percentage or sum (as applicable) paid under subitem (b) as aforesaid, shall be deemed to include for full and final compensation to the Contractor for all costs as may be incurred and all charges and profits associated with the engagement, supervision, administration and management of the Nominated Subcontractor required of him in fulfilling its obligations under the Contract as the Principal Contractor."

SDA 8.5.2 Works executed by Nominated Subcontractors

(a) Work to be executed by a Nominated Subcontractor Unit: Prov Sum

(b) Overheads, charges and profit on item (a) above Unit: % or sum

Subitems (a) and (b) will be provided in the Schedule of Quantities for each different Nominated Subcontract included in the Contract.

The Contractor shall be reimbursed under subitem (a), in substitution of the respective Provisional Sums (if any) allowed in the Schedule of Quantities, the amounts actually paid or payable by the Contractor to the respective Nominated Subcontractors, in accordance with the provisions of Clause 45 of the Conditions of Contract.

The Contractor shall be paid under subitem (b), either:

- (a) where the unit of measurement for subitem (b) was specified as being a percentage, the respective percentage, as stated by the Contractor in its tender, of the amount certified by the Engineer for payment under the related subitem (a), all in accordance with the provisions of Clause 45.1.2.1.1 of the Conditions of Contract, or
- (b) where the unit of measurement for subitem (b) was specified as being a lump sum, an amount which is in the same proportion to the amount certified for payment under subitem (a) and the tendered lump sum is to the amount of the Provisional Sum stated under subitem (a) in accordance with the provisions of Clause 45.1.2.1.2.

The percentage or sum (as applicable) paid under subitem (b) as aforesaid, shall be deemed to include for full and final compensation to the Contractor for all costs as may be incurred and all charges and profits associated with the engagement, supervision, administration and management of the Nominated Subcontractor required of him in fulfilling its obligations under the Contract as the Principal Contractor."

SDA 8.6 PRIME COST ITEMS

REPLACE SUBCLAUSE 8.6 WITH THE FOLLOWING:

"SDA 8.6 PRIME COST SUMS

- | | | |
|-----|---|--------------|
| (a) | Description of item to which Prime Cost Sum applies | Unit: PC Sum |
| (b) | Charge required by Contractor on subitem (a) above | Unit: % |

Subitems (a) and (b) will be provided in the Schedule of Quantities for each different item to which a Prime Cost Sum applies.

The Contractor shall be reimbursed under subitem(s) (a) in substitution of the respective Prime Cost Sums included in the Contract, the actual price(s) paid or payable by him in respect of the goods, materials or services supplied, but excluding any charges for the Contractor's labour, profit, carriage, establishment or other charges related to such goods, services or materials.

The Contractor shall be paid under subitem (b), the respective percentage, as stated by the Contractor in his tender, of the amount certified by the Engineer for payment under the related subitem (a). The percentages tendered by the Contractor for each respective subitem (b) included in the Schedule of Quantities shall be deemed to be in full and final compensation to the Contractor in respect of any charge by the Contractor for labour, carriage profit, establishment and for any other charges related to the goods, services or materials supplied under the related subitem (a).

If the Contractor shall have omitted within his tender to insert a tendered percentage under subitem (b), or tendered a zero percentage, the Contractor's tendered rate for subitem (b) shall be deemed to be zero and the Contractor shall not be entitled to any payment under subitem (b).

Note in connection with additional tests required by the Engineer:

When a PC sum is included in the Schedule of Quantities for additional tests required by the Engineer, the Contractor shall be responsible for both the cost of normal testing as described in subclause SDA 8.1.2.2 of the Project Specifications and for the cost of any additional test that indicates that the specifications have not been complied with."

SDA 8.7 DAYWORK

REPLACE THE CONTENTS OF SUBCLAUSE 8.7 WITH THE FOLLOWING:

"Measurement and payment shall be in accordance with the provisions of Clause 6.5.1.1 (GCC 2015) of the Conditions of Contract."

ADD THE FOLLOWING ITEMS:

**"SDA 8.9 COMPLIANCE WITH OHS ACT AND REGULATIONS
(INCLUDING THE CONSTRUCTION REGULATIONS 2014)**

Unit: sum

The tendered sum shall include full compensation to the Contractor for compliance with all the requirements of the OHS Act and Regulations (including the Construction Regulations 2014) at all times for the full duration of the Contract, as described in C3.6.1 (for CIDB document format). The successful tenderer shall provide the Engineer with a complete breakdown of this tendered sum.

This sum will be paid to the Contractor in equal monthly amounts subject to proper/substantial compliance."

**2) COMPLIANCE WITH ENVIRONMENTAL MANAGEMENT PLAN AND REGULATIONS
PRODUCED BY EMPLOYERUnit: sum**

This sum will be paid to the Contractor in equal monthly amounts subject to proper/substantial compliance.

"SDA 8.10 COMMUNITY LIASON AND COMMUNITY RELATIONS

Unit: month

- a) A total amount of R 6500.00 is to be paid to the community liaison officer for the duration of the construction of this project.

Add this new clause:

"4.23 Community participation"

Community participation consists of engagement of Project Steering Committees (PSC).

A PSC will be established for the project, by the Ward Councillor.

The functions of the PSC will be to:

- Assist in monitoring the project.
- Ensure that the community provide assistance to the contractor to ensure that he can execute the contract in accordance with the specifications and within time.
- Encourage the community to participate in the Labour Intensive construction.
- Identify skills, skilled personnel and suppliers in the towns.

The PSC will not have the power to:

- Give any instructions to the contractor, except through the engineer.
 - Become involved in the daily operations of the contractor or interfere with the contract works.
- b) A monthly meeting will be held with the PSC to discuss relevant matters. The site agent and resident engineer will attend the meetings. The contractor will have to report on progress, deviations from the programme, financial matters community related aspects, general problems and co-operation at the meeting. The PSC members will not receive any remuneration for attending, and they must provide their own transport."
- c) Payment will be R300.00 per sitting.

This sum will be paid to the Contractor in equal monthly amounts subject to proper/substantial compliance."

"SDA 8.11 Training of Targeted Labour

- a) The contractor shall provide all the necessary on-the-job training to targeted labour to enable such labour to master the basic work techniques required to undertake the work in accordance with the requirements of the contract in a manner that does not compromise worker health and safety.
- b) The cost of the formal training of targeted labour will be funded by the provincial office of the Department of Labour. This training should take place as close to the project site as practically possible. The contractor, must access this training by informing the relevant provincial office of the Department of Labour in writing, within 14 days of being awarded the contract, of the likely number of persons that will undergo training and when such training is required. The employer must be furnished with a copy of this request.
- c) The contractor shall be responsible for scheduling the training of workers and shall take all reasonable steps to ensure that each beneficiary is provided with a minimum of six (6) days of

formal training if he/she is employed for 3 months or less and a minimum of ten (10) days if he she is employed for 4 months or more.

- d) The contractors shall do nothing to dissuade targeted labour from participating in the above-mentioned training programmes.
- e) An allowance equal to 100% of the task rate or daily rate shall be paid by the contractor to workers who attend formal training, in terms of d) above.
- f) Proof of compliance with the requirements of a) to f) above must be provided by the Contractor to the Employer prior to submission of the final payment certificate.

(i)	Technical Training	Prov. Sum
(ii)	HIV/AIDS	Prov. Sum
(iii)	Handling cost and profit in respect subitem B12.04(i) and (ii)	

SDAB EMPLOYER'S AGENT'S OFFICE (SANS 1200 AB)

SDAB3 MATERIALS

SDAB3.1 NAMEBOARDS

Notwithstanding the provision of Sub-clause 3.1, one name board shall be erected and the board shall comply with the format and size to be provided by the Employer's Agent.

This name board shall be erected and maintained at the main service road and entrance to the Site at the main road.

The Contractor shall not erect any signs, notices or advertisements on or adjacent to the Site of Works other than the project nameboard specified herein without the written approval of the Employer's Agent. The Contractor may, when applicable, permit each of his/her Sub-contractors to display one signboard of less than 2 m² in size at the Contractor's camp or Site office.

All nameboards and signboards shall be removed by the end of the Defects Liability Period.

SDAB3.2 OFFICE BUILDING

One office complete with furnishings as specified, must be provided by the Contractor for the Employer's Agent.

Although ski-cabins or similar structures will be acceptable as offices even if they might not comply with the requirements specified for floor area and ceiling height, the use of such structures will be subject to the approval of the Employer's Agent.

The Contractor shall be required to consult with the Employer's Agent prior to the supply and erection of the office.

SDAB3.3 CARPORTS

A carport to provide for two motor vehicles shall be erected adjacent to the Employer's Agent's office for exclusive use. The carport shall have side cladding and shall be constructed in such a way as to shelter the parked vehicles from the prevailing winds, sun and driven rain.

SDAB3.4 ABLUTION AND LATRINE FACILITIES

The Contractor shall, in addition to catering for his/her own staff, provide ablution and latrine facilities adjacent to the Employer's Agent's office for the exclusive use of the Employer's Agent and his/her staff. The facilities shall consist of a shower, hand washbasin and a water born latrine. The facility shall be clean and maintained in a hygienic condition for the duration of the Contract.

SDAB3.5 HEATING AND COOLING FACILITIES (Sub-clause 3.2(j))

The Contractor shall supply and install in the offices specified under SDAB3.2 an air-conditioning unit with cooling and heating capacity of at least 2 500 k/cal.

SDAB3.6 REFRESHMENTS FOR THE EMPLOYER'S AGENT AND HIS/HER STAFF

Tea and/or coffee shall be provided by the Contractor for Employer's Agent, and the Employer's Agent's staff, at reasonable intervals throughout any working day for the duration of the Construction period.

SDAB4 PLANT

SDAB4.1 TELEPHONE AND FAX (Sub-clauses 4.1 and 5.4)

In terms of Sub-clause 4.1, the Employer's Agent allowed a PC sum of R 1,900 per month for the duration of the Contract to defray costs associated with cellular telephone expenses.

The Contractor shall arrange the provision of the Employer's Agent's on site communication system. All costs and accounts shall be payable by the Contractor for the duration of the construction period.

A WIFI facility with 10 GB per month data shall be provided in the Employer's Agent's Office and the cost of this shall be payable by the Contractor. The Contractor shall be required to bear the cost of transmissions and consumables such as paper, maintenance etc.

Upon completion of the Works the ownership of the WIFI facility shall revert to the Employer.

SDAB4.2 SURVEY EQUIPMENT

The Contractor shall provide the following survey equipment on the Site from the commencement to the completion of the Works:

- (a) 1 No. Tachometer capable of reading to 20 seconds of arc with tripod; 1 No. Employer's Agent's automatic level with tripod and staff;
- (b) 2 x Tachometer staffs with staff bubble;
- (c) 2 x levelling staffs graduated in 5 mm intervals with staff bubble;
- (d) 6 No. Ranging rods;
- (e) 1 No. 3 m pocket tape
- (f) 1 No. 30 m Fiberglass measuring tape,
- (g) 1 No. 100 mm steel measuring tape; and
- (h) All steel pegs, shovels, picks, etc. which the Employer's Agent's Representative may require for the duration of the Contract.

The instruments may, by arrangement, be shared between the Contractor and the Employer's Agent's Representative.

The Contractor shall maintain the equipment in good working order and keep it clean throughout the contract period. The Contractor shall keep the equipment continuously insured against any loss, damage, or breakage and the Contractor shall indemnify the Employer's Agent and the Employer against any claims in this regard. Upon completion of the Works, the ownership of the equipment shall revert to the Contractor.

SDAB4.3 FIRST-AID KIT AND PROTECTIVE CLOTHING

The Contractor shall provide and maintain, in compliance with the OHS Act and regulations (including the construction regulations 2003), on the Site of Works two first-aid kits to deal with unforeseen accidents and snakebite which may occur during the normal on-Site operations.

The Contractor shall provide two sets of safety helmets, safety footwear and rubber boots for the exclusive use of the Employer's Agent and his/her staff.

SDAB5 CONSTRUCTION**SDAB5.1 NAMEBOARDS**

Delete the words "on completion of the contract," and substitute it with:

"...by the end of the defects liability period, or at such other earlier time as the Employer's Agent may instruct or approve."

SDAB5.2 SERVICES FOR OFFICE AND ABLUTIONS

The Contractor shall provide, at his/her own cost, a constant supply of potable water and electric power to the Employer's Agent's office and ablutions facility.

Two survey assistants shall be allocated to the Employer's Agent by the Contractor. The assistants shall be able to read and write either Afrikaans or English and shall be available to the Employer's Agents as assistant's at all reasonable times during the construction period.

SDAB8 MEASUREMENT AND PAYMENT

SDAB8.2.2 Employer's Agent's Office..... Unit: Sum

(Fixed Charge and Time Related Item)

The tendered sum for an office shall include all costs for the installation and maintenance and removal of carports (SDAB3.3), ablutions and latrine (SDAB3.4), heating and cooling facilities (SDAB3.5), refreshments (SDAB3.6), the installation and maintenance of computer facilities (SDAB 4.4), the provision of a first-aid kit and protective clothing (SDAB4.3), and services (SDAB5.2).

SDAB8.2.3 Employer's Agent's WIFI Unit: Sum

(Fixed Charge and Time Related Item)

The tendered sum for Employer's Agent's Wi-Fi shall include all costs for the installation and maintenance (SDAB 4.1) for the duration of the Contract. The Contractor will be required to bear all costs relating to telephone calls, data use and printing.

SDAB8.2.4 Survey Equipment and Assistants Unit: Sum

(Fixed Charge and Time related item)

The tendered sum shall include all costs for the supply and maintenance of the survey equipment (SDAB4.2) and the employment of assistants for the Employer's Agent (SDAB5.5).

SDAB8.2.5 Digital Camera Unit: Sum

(Prime Cost Item)

The tender sum shall include all costs for the supply, service and maintenance of the camera as specified in SDAB4.5.

SDAB8.2.6 Name Board..... Unit: Prov Sum

(Fixed Charge and Time related item)

The actual cost to the Tenderer shall include all costs for the supply, maintenance and removal of two nameboards (SDAB3.1) from the provisional sum allowed by the Employer's Agent.

SDC SITE CLEARANCE

SDC 3 MATERIALS

SDC 3.1 DISPOSAL OF MATERIAL

ADD THE FOLLOWING:

"The Contractor shall obtain his own dumping sites for the disposal of material and all transport costs shall be included in the rates tendered for site clearance."

No overhaul will be paid for any spoil material and the Contractor shall allow for all haulage costs in his tendered rates.

SDC 5 CONSTRUCTION

SDC 5.1 AREAS TO BE CLEARED AND GRUBBED

ADD THE FOLLOWING:

"Pipeline routes shall be cleared to a distance of 1,5 m on both sides of the pipeline centre line. Route pegs or markers shall not be destroyed or damaged during clearing operations."

SDC 5.2 CUTTING OF TREES

SDC 5.2.3 Preservation of trees

SDC 5.2.3.2 Individual trees

REPLACE THE LAST SENTENCE WITH THE FOLLOWING:

"An amount of R1 500, 00 will be deducted from moneys due to the Contractor as a penalty for every tree that is damaged or removed unnecessarily."

SDC 5.3 CLEARING

Clearing shall include the loading, removal and disposal of garbage as directed by the Employer's Agent.

SDC 5.5 RECLEARING OF VEGETATION

ADD THE FOLLOWING:

"When areas have to be re-cleared on the written instructions of the Engineer, such re-clearing shall be carried out at the Contractor's own cost and the Contractor is therefore advised not to clear the areas too soon.

SDC 5.10 DEMOLITION OF CONCRETE

The Contractor is to ensure that forces caused by the demolition process do not induce stress on the remaining parts of the structures or on other existing structures that may cause cracking. Use is to be made of suitable energy absorbing materials during the demolition process. The structures/sections of structures to be demolished are indicated on the drawings. The strength of the existing reinforced concrete is to be expected to be in excess of 30 MPa.

The Contractor may only proceed to cut reinforcing upon written instruction of the Employer's Agent.

The Contractor is to submit a proposed work method and planning schedule for each type of demolition to the Employer's Agent for approval before work commences.

The following types of structures are to be demolished:

- Mass concrete
- Rectangular openings of various sizes in reinforced concrete walls with varying depths – typically the existing sand filter floors.
- Bulk reinforced concrete demolition such as a plinths, sections of structures or complete structures
- The breaking of concrete shall be to lines as indicated on the drawings.

The following methods of demolition will **not** be permitted:

- The use of thermal lancing
- The use of any explosion method
- The use of poisonous chemicals

The following methods of demolition shall be considered **as acceptable**:

- Diamond impregnated wire or blade sawing
- Jack hammers
- Wood peckers or nibblers
- Hydro cutting
- Air cutting
- Any other method as indicated by the Employer's Agent

SDC 5.11 DEMOLITION OF BUILDING WORK

The Contractor is to ensure that the demolition process does not induce stresses on the existing structure that may cause cracking of the concrete. Use is to be made of energy absorbing materials under the demolition area to protect existing concrete surfaces. The building work to be demolished is indicated on the drawings. All material to be stored in a designated store and no materials shall be taken off site without consent from the Employer's Agent or Employer.

SDC 8 MEASUREMENT AND PAYMENT

SDC 8.2 PAYMENT

SDC 8.2.1 Clear and grub

REPLACE THE FIRST LINE WITH THE FOLLOWING:

"The area designated by the Engineer to be cleared and grubbed will be measured in square metre to the nearest square metre"

ADD THE FOLLOWING:

"The rate tendered for clearing and grubbing shall cover the cost of disposal and the total haulage cost of the material off the site as directed in SDC 3.1 and the protection of erf pegs"

ADD THE FOLLOWING ITEMS IN SUBCLAUSE 8.2:

"SDC 8.2.11 Take down and re-erect existing fences

Unit: m

The rate shall cover the cost of taking down the fences, coiling wire, sorting, stacking and guarding all materials, the cost of loading, transporting and off-loading such materials, the cost of re-erecting the fence in its original position using the dismantled material, the cost of temporary bracing of the fencing sections not taken down and the cost of appurtenant materials that may be required to restore the fence to its original condition before dismantling.

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

BID NO: DALRRD-RID-FS-00XX (2023/2024)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UPGRADING OF SEDIBA CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

Amendments made to COTO are included in the following Chapters:

CHAPTER 1	:	GENERAL
CHAPTER 2	:	SERVICES
CHAPTER 3	:	DRAINAGE
CHAPTER 4	:	EARTHWORK AND PAVEMENT LAYERS: MATERIALS
CHAPTER 5	:	EARTHWORK AND PAVEMENT LAYERS: MATERIALS
CHAPTER 6	:	CONCRETE LAYERS
CHAPTER 7	:	MAINTAINANCE AND REPAIR OF CONCRETE LAYERS
CHAPTER 8	:	PRETREATMENT AND REPAIR OF EXISTING LAYERS
CHAPTER 9	:	ASPHALT LAYERS
CHAPTER 10	:	SURFACE TREATMENTS
CHAPTER 11	:	ANCILLARY ROAD WORKS
CHAPTER 12	:	GEOTECHNICAL APPLICATIONS
CHAPTER 13	:	STRUCTURES
CHAPTER 14	:	REPAIR AND REHABILITATION OF STRUCTURES
CHAPTER 15	:	Reserved for future use
CHAPTER 16	:	Reserved for future use
CHAPTER 17	:	Reserved for future use
CHAPTER 18	:	Reserved for future use
CHAPTER 19	:	Reserved for future use
CHAPTER 20	:	QUALITY ASSURANCE

C3.5.4 PROJECT SPECIFICATIONS**COTO SERIES 1000: GENERAL****SECTION B 1100: DEFINITIONS AND TERMS****B1115 GENERAL CONDITIONS OF CONTRACT**

REPLACE CLAUSE 1115 WITH THE FOLLOWING:

"The General Conditions applicable to this Contract shall be the General Conditions of Contract for Construction Works, 3rd Edition (2015); and published by the South African Institution of Civil Engineering.

All references to the COTO General Conditions of Contract, 2020 in the COLTO Standard Specifications for Road and Culvert crossing Works for State Road Authorities, 2020 shall be deleted and replaced where applicable by references to the Conditions of Contract stated in this clause as detailed in table B1115. The context of the reference to the GCC is also noted.

The Contractor shall note that whereas every effort has been made to include all of the affected clauses in the table, there may be some omissions. In every case, however, the Conditions of Contract specified in this clause and amended in the Contract Document shall apply and the Contractor shall be responsible for interpretation of the equivalent clause.

TABLE B1115

COLTO Standard Specifications		Reference to COTO General Conditions of Contract 2020 shown in the Standard Specifications		Equivalent reference to General Conditions of Contract for Construction, 3 rd edition, 2015, applicable to this Contract	
Clause No	Page No	Clause No	Description or Reference	Clause No	Description or Reference amended to
1115	1100-2		Definition of GCC		Definition GCC 2015
1202	1200-2	15	Construction programme	5.6	Programme
1204	1200-2		General reference to GCC		Applicable to GCC 2015
1206	1200-3	14	Setting out of works		Clause amended in 1206 of Specifications
1209(a)	1200-4		General references to GCC		Applicable to GCC 2015
1209(e)	1200-5	52	Valuation of material brought onto site	6.10.2	Valuation of material brought onto site
1210	1200-5	54	Certificate of practical completion	5.14.2	Certificate of Practical Completion
1212(1)	1200-7	49	CPA on alternative designs	6.8	CPA on alternative designs
1215	1200-9	45	Extension of time for completion due to abnormal rainfall	5.12	Extension of time for completion due to abnormal rainfall
1217	1200-10	35	Care of the works	8.2	Care of the works
1303(ii)	1300-1		General reference to GCC		Applicable to GCC 2015
1303(iii)	1300-1	49	Price adjustment Item 13.01 (a)	6.8	Price adjustment Item 13.01 (a)
1303 (iii)	1300-2	49	Price adjustment Item 13.01 (b)	6.8	Price adjustment Item 13.01 (b)
1303 (iii)	1300-1	53	Variations exceeding 15%	6.11	Variations exceeding 15%
1303 (iii)	1300-2	53	Variations exceeding 15%	6.11	Variations exceeding 15%
1303	1300-2	12	Payment Item 13.01 (c)	5.3	Payment Item 13.01 (c)
1303	1300-2	45	Payment Item 13.01 (c)	5.12	Payment Item 13.01 (c)
1403(c) (ii)	1400-4	40 (1)	Variation for rented accommodation	6.4.1	Variation for rented accommodation
1505	1500-3	40	Variation for temporary drainage	6.4	Variation for temporary drainage
Item 15.08	1500-8	48	Payment of Provisional Sum	6.6	Payment of Provisional Sum
Item 15.09	1500/8	48	Payment of Provisional Sum	6.6	Payment of Provisional Sum
Item 15.11	1500-8	48	Payment of Provisional Sum	6.6	Payment of Provisional Sum
Note (2)	3100-4	40	Payment for prospecting for materials	6.4	Payment for prospecting for materials

COLTO Standard Specifications		Reference to COTO General Conditions of Contract 2020 shown in the Standard Specifications		Equivalent reference to General Conditions of Contract for Construction, 3 rd edition, 2015, applicable to this Contract	
Clause No	Page No	Clause No	Description or Reference	Clause No	Description or Reference amended to
3204(b) (iii)	3200-2	40	Payment for oversize material	6.4	Payment for oversize material
3303(b)	3300-2	2	Employers Agent's decisions, with reference to materials classification	3	Employers Agent's decisions, with reference to materials classification
Item 44.06	4400-3		General reference to GCC, PC Sums	6.6.2	General reference to GCC, PC Sums
Item 45.06	4500-3		General reference to GCC, PC Sums	6.6.2	General reference to GCC, PC Sums
5803 (c)	5800-3	40	Variation, for landscaping	6.3	Variation, for landscaping
5805 (d)	5800-4	40	Variation, for grassing	6.3	Variation, for grassing
Item 58.10	5800-10	48	Payment for Extra Work	6.6	Payment for Extra Work
8103 (c)	8100-1	40	Variation, for testing material	6.3	Variation, for testing material
Item 81.02	8100-26		General reference to GCC, Provisional Sums	6.6	General reference to GCC, Provisional Sums
Item 81.03	8100-26	22	Clearance of site on completion, with reference to core drilling	5.15.1	Clearance of site on completion, with reference to core drilling

"B1156 OTHER DEFINITIONS

The COTO Standard Specification for Roads and Culvert crossings has been written for all Contractors, Employers and Employers Agents. Similarly, the works and the site are not defined and the general nature of the entities and elements that collectively constitute construction under a contract are characterized by the use of lower-case letters throughout.

These project specifications continue to use lowercase spellings in order to avoid the appearance of the capitalised and non-capitalised words to describe or prescribe the same elements of work required on this project. However, for the purposes of this contract, the following definitions shall apply:

Contractor

The Contractor and contractor is the same persona defined under clause 1.1.1.9 of the General Conditions of Contract, but who will only be formally identified by the completed Form of Acceptance C1.1.2 in this document and which will be bound into the final contract document.

Employer

The Employer and employer is the same persona and is defined in C1.2.2 Contract Data, and clause 1.1.1.15 of the General Conditions of Contract.

Employers Agent

The Employers Agent and employers agent is the same persona and is defined in C1.2 Contract Data, and clause 1.1.1.16 of the General Conditions of Contract.

Site

The site is defined in clause 1.1.1.29 of the General Conditions of Contract. It is bound by the limits of construction as shown in the drawings (if any) or the title of the project and extends to also include the following:

- Areas outside the construction zone areas where accommodation of traffic is placed.
- All haul roads constructed by the Contractor for purposes of access.
- Any non-adjacent sites specified in the contract documentation.
- The Contractors and his Sub-Contractors camp sites
- Site used for storage of material and equipment for use in the permanent works.
- Areas required for temporary access roads only when approved by the Employers Agent.

Works

The works is described in Part C3 of this document and is as defined in clause 1.1.1.33 of the General Conditions of Contract.

Prime cost

Is a specific type of Provisional Sum for which payment is made on the production of invoices showing the cost price of the implementation or installation of the service required. Services rendered in this manner carry a mark-up for which a rate is offered at tender stage to cover all the tenderer's handling, supervision and liability costs and profit in providing the item or services as per sub-clause 6.6.

Provisional Sum

Is a sum which is specified in the contract as a provisional sum, for the execution of any part of the works or the supply of plant, materials or services under sub-clause 6.6

B1157 SABS/SANS SPECIFICATIONS

Where reference is made in this specification or the standard specifications to SABS/SANS specifications, the latest published national standard shall be applicable. Use:

[https://www.sabs.co.za/content/uploads/files/SABS%20Catalogue%20February%202012%20\(aculvert crossingd\).pdf](https://www.sabs.co.za/content/uploads/files/SABS%20Catalogue%20February%202012%20(aculvert%20crossingd).pdf)

for the most up-to-date versions of the various standards.

B1158 AGGREGATE SIZE

Where reference is made in this specification or the standard specifications to aggregate size, nominal aggregate size or maximum aggregate size, the aggregate size as listed shall be replaced with the new corresponding aggregate size as indicated in the following table:

Aggregate size	New aggregate size
26,5	28
19	20
13,2	14
9,5	10
6,7	7
4,75	5
2,36	2
1,18	1

B1159 COMMERCIAL SOURCE

A source of supply of materials which is chosen by the Contractor. The Contractor shall take full responsibility for the quality of all materials and services supplied from commercial sources.

B1160 LABOUR-OPTIMISING CONSTRUCTION

The cost-effective employment of as great a portion of labour as is practically and technically feasible to produce the standard of construction required by the specifications. Therefore, the economic substitution of plant and mechanical equipment with available labour using hand tools, on condition that this method is not more expensive than the conventional construction practices.

B1161 STRESS-ABSORBENT MEMBRANE INTERLAYER (SAMI)

A layer of stone chippings and bitumen rubber constructed between successive pavement layers for the purpose of absorbing stress.

B1162 PROCESS CONTROL

Process control means all testing required to be carried out in order to ensure that the completed permanent works comply with the specifications and drawings. All such testing

will be subject to inspection and approval by the Employers Agent. The contractor is responsible for process control testing. The cost of testing for process control is deemed included in the rates tendered for each item. The minimum frequency of testing for process control should comply with Section 8300 of the standard specifications: Quality Control.

B1163 ACCEPTANCE CONTROL

Acceptance control means whatever testing the Employers Agent carries out over and above the process control testing already carried out in order to decide on the acceptability of any work submitted by the contractor. Such testing will be carried out at the cost of the employer.

Both the process control testing carried out by the Contractor and acceptance control testing by the Employers Agent shall be carried out by an accredited laboratory.

B1164 PRE-TREATMENT

Treatment of the existing surfacing and base prior to a bituminous overlay or reseal. Pre-treatment can include but is not limited to the following actions:

- Patching, inclusive of saw cutting, excavation, priming and/or tacking, and backfilling with asphalt
- Milling out existing asphalt surfacing and/or base layer, priming and/or tacking, and backfilling with paver-laid asphalt
- Repairing edge breaks, inclusive of saw cutting, excavation, priming and/or tacking, and repairing with asphalt
- Crack sealing, inclusive of cleaning, and applying herbicide, primer and sealant
- Slurry seal surface treatment."

B1165 FREE HAUL DISTANCE

The free-haul distance in regard to any material which is moved shall be 1,0 km.

B1166 CLASSES OF EXCAVATION

No distinction will be made between soft and intermediate excavation."

CHAPTER 1: 1.1GENERAL PREAMBLE**B1202 SERVICES**

In the second paragraph, delete the word "utility" at the end of the second line.

In the final paragraph, replace "clause 15" in the second line with "clause 5.6"

In the final paragraph delete the second and third sentences starting with 'Should' and replace with the following:

Drawings provided indicate all known services on the site. However, before any work can commence the Contractor shall verify the actual position of each station and bring to the attention of the Employers Agent any service that is not recorded. As the Contractor is not authorized to remove or replace these facilities he shall:

- i) Give preliminary notice, in writing to the relevant service provider, that the services on the site will require removal or protection prior to works being carried out in the vicinity of each station. The Contractor shall advise the service provider of
 - a) The number of services, their locations and station ID numbers and
 - b) The proposed dates when work will commence in the vicinity of each service.
- ii) In addition to the above preliminary notice, give the service provider 14 days written notice of the intention to commence work in the vicinity of each facility.
- iii) Upon completion of the work in the vicinity of each facility, the Contractor shall notify the service provider, in writing, that work is complete and the service may be reinstated.

Any delay resulting from the removal/replacement of a service shall not be the subject of a claim, it being deemed that the Contractor shall employ the services of the service provider as a subcontractor.

No payment will be made for inconvenience to the Contractor due to services crossing the site or any authority working on such services, nor will delays caused by such works be accepted as a basis for claiming an extension of time for completing the works.

"BC1.2.4.1 COMMUNITY LIAISON AND COMMUNITY RELATIONS Unit: month

- d) A total amount of R 6500.00 is to be paid to the community liaison officer for the duration of the construction of this project.

Add this new clause:

"4.23 Community participation"

Community participation consists of engagement of Project Steering Committees (PSC).

A PSC will be established for the project, by the Ward Councillor.

The functions of the PSC will be to:

- Assist in monitoring the project.
- Ensure that the community provide assistance to the contractor to ensure that he can execute the contract in accordance with the specifications and within time.
- Encourage the community to participate in the Labour-Intensive construction.
- Identify skills, skilled personnel and suppliers in the towns.

The PSC will not have the power to:

- Give any instructions to the contractor, except through the engineer.
 - Become involved in the daily operations of the contractor or interfere with the contract works.
- e) A monthly meeting will be held with the PSC to discuss relevant matters. The site agent and resident engineer will attend the meetings. The contractor will have to report on progress, deviations from the programme, financial matters community related aspects, general problems

and co-operation at the meeting. The PSC members will not receive any remuneration for attending, and they must provide their own transport."

- f) Payment will be R300.00 per sitting.

This sum will be paid to the Contractor in equal monthly amounts subject to proper/substantial compliance."

"BC 1.2.4.2 Training of Targeted Labour

- g) The contractor shall provide all the necessary on-the-job training to targeted labour to enable such labour to master the basic work techniques required to undertake the work in accordance with the requirements of the contract in a manner that does not compromise worker health and safety.
 - h) The cost of the formal training of targeted labour will be funded by the provincial office of the Department of Labour. This training should take place as close to the project site as practically possible. The contractor, must access this training by informing the relevant provincial office of the Department of Labour in writing, within 14 days of being awarded the contract, of the likely number of persons that will undergo training and when such training is required. The employer must be furnished with a copy of this request.
 - i) The contractor shall be responsible for scheduling the training of workers and shall take all reasonable steps to ensure that each beneficiary is provided with a minimum of six (6) days of formal training if he/she is employed for 3 months or less and a minimum of ten (10) days if he she is employed for 4 months or more.
 - j) The contractors shall do nothing to dissuade targeted labour from participating in the above-mentioned training programmes.
 - k) An allowance equal to 100% of the task rate or daily rate shall be paid by the contractor to workers who attend formal training, in terms of d) above.
 - l) Proof of compliance with the requirements of a) to f) above must be provided by the Contractor to the Employer prior to submission of the final payment certificate.
- | | | |
|------|--|-----------|
| (iv) | Technical Training | Prov. Sum |
| (v) | HIV/AIDS | Prov. Sum |
| (vi) | Handling cost and profit in respect subitem B12.04(i) and (ii) | |

BA1.2.7.1 PROGRAMME OF WORK

(a) General requirements

CHANGE THE WORDING OF THE FIRST SENTENCE TO READ AS FOLLOW: "The contractor shall base his initial programme of work on the scope of work when the contractor receives an appointment and defined scope of work, and...."

AMEND THE WORD "network" IN THE FOURTH LINE OF THE FIRST PARAGRAPH TO READ "bar (Gantt) chart".

ADD THE FOLLOWING AS A CONTINUATION OF THE FIRST PARAGRAPH:

"In drawing up the programme the Contractor shall make allowance for the following:

- i) All special non-working days defined in the Contract Data.
- ii) The expected delays defined in B1215: Extension of time resulting from inclement weather as a terminal float.
- iii) The following restricted working conditions:
 - During the Contractor's annual shutdown period between December and January, the Contractor shall maintain two-way traffic within the contract limits.
 - No Sunday works.

- iv) Meeting the requirements of the Environmental Management Plan (EMPI).
- v) The time needed for preparation and approval of the various mix designs specified in the relevant construction sections of the Scope of Works.

This initial programme shall realistically account for the forecast cashflow within the defined contract period."

ADD THE FOLLOWING AFTER THE THIRD PARAGRAPH:

"The bar-chart programme to be provided by the contractor shall show the various activities in such detail as may be required by the Employers Agent. Progress in terms of the programme shall be updated monthly by the contractor in accordance with the progress made by the contractor.

In compiling the programme of work, the contractor shall indicate and make due allowance for the following, as specified elsewhere in the contract documents:

The requirements regarding the accommodation of traffic and areas that may be occupied at any time for construction purposes (as indicated on the drawings and specified in Section 1500 of the specifications)

Requirements regarding the training of labourers and Emerging Contractors (ECs).

The requirements for work to be undertaken by labourers and work to be undertaken by ECs as tendered."

INSERT THE FOLLOWING PARAGRAPHS:

"c) Additional programme requirements

In addition to the requirements of clauses B1204(a) and B1204(b), and of clause 5.6 of the General Conditions of Contract, the programme of work shall include the following details:

- i) A work breakdown structure that identifies all major activities.
- ii) Scheduled start and end dates for each activity.
- iii) Linkages between activities that clearly identify sequence, floats and critical path.
- iv) Intended working hours and resource allocations (plant and labour).
- v) Production rates.
- vi) Monthly cashflow projections.
- vii) Key dates in respect of information required or due delivery."
- viii) The Contractor's payment weekends
- ix) A risk assessment schedule with mitigating plans of issues that could prevent the due completion date being met.

A Gantt chart programme shall be provided, showing the various activities in such detail as the Employers Agent may require. Should the Employers Agent require an electronic version of the programme for review purposes, the Contractor shall supply the programme in a format compatible with the Employers Agents software.

d) Programme revisions

The programme will be reviewed at the monthly site meetings at which the Contractor shall provide sufficient detail that will allow the comparison of completed work per activity against the original approved programme. Failure to comply with these requirements entitles the Employers Agent to use a programme based on his own assumptions to evaluate claims for extension of time for completion of the works, or for additional compensation. The Contractor shall indicate what resources and programme changes he intends to implement in order to remedy any activity that may have fallen behind. The Employers Agent may demand from the Contractor

a major revision of the programme. Such a revision shall be submitted for approval within fourteen days of the demand."

BA1.2.8 WORKMANSHIP AND QUALITY CONTROL

INSERT THE FOLLOWING HEADING AFTER THE TITLE:

"a) General

INSERT THE FOLLOWING AS SUB-CLAUSES AFTER THE FIRST PARAGRAPH:

b) Quality Systems

"The Contractor shall implement a quality assurance system that replicates an ISO 9002 and appoint a quality manager who shall ensure that members of the Contractor's staff comply with the requirements of the quality system. The quality system and the methods used to implement it shall be described in a quality plan produced by the Contractor. The quality manager shall be resident on site full time.

The Contractor shall submit the quality assurance system he proposes using to the Employers Agent, for his approval, within two weeks of the site handover. The system shall record the lines and levels of responsibility and indicate the method by which testing procedures will be conducted. Once accepted by the Employers Agent the Contractor shall not deviate from it unless written notification of proposed changes has similarly been submitted and approved.

The system shall provide for a method statement for each construction activity for which a pay item is provided in the Pricing Schedule. Each method statement shall be submitted to the Employers Agent for his approval two weeks prior to commencement of the activity. Where appropriate the Contractor shall make use of the employer's manuals in preparing his method statements. No construction activity shall commence before the Employers Agent has approved the Contractor's quality assurance system."

ADD THE FOLLOWING AT THE END OF THE THIRD PARAGRAPH:

"The Employers Agent shall, however, undertake acceptance control tests for the judgement of workmanship and quality, without accepting any obligations vested with the contractor in terms of the contract with specific reference to quality of materials and workmanship. Such acceptance control test done by the Employers Agent shall not relieve the contractor of his obligations to maintaining his own quality control system."

ADD THE FOLLOWING AT THE END OF THIS CLAUSE:

"The Employers Agent shall for the purpose of acceptance control and products and workmanship, assess test results and measurements in accordance with provisions of Section 8300 of the standard specifications (quality control scheme 2). Where small quantities of work are involved, a lot shall mean a full day's production for a specific item of work subject to acceptance control testing."

BA1.2.7.2 THE SETTING OUT OF WORK AND PROTECTION OF BEACONS

REPLACE THE FIRST PARAGRAPH WITH THE FOLLOWING:

"The contractor shall comply with all legal provisions in regard to surveying and setting out work.

The particulars of the basic reference pegs and benchmarks are recorded on the drawings. Additional reference pegs and benchmarks may be established from time to time by the Employers Agent, as deemed necessary. The Contractor shall be responsible for the true and proper setting-out of the Works and for the correctness of the position, levels,

dimensions and alignment of all parts of the Works and for the provision of all necessary instruments, appliances and labour in connection therewith.

The Contractor shall carefully protect and preserve all benchmarks, site-rails, pegs and other things used in setting out the works. The checking of any setting-out or of any line or level by the Employers Agent shall not relieve the Contractor of his responsibility for the correctness thereof."

DELETE "and of clause 14 of the general conditions of contract" in the sixth paragraph.

ADD THE FOLLOWING PARAGRAPH:

"The Contractor shall take care that property beacons, trigonometrical survey beacons or setting-out beacons are not displaced or destroyed without the consent of the Employers Agent. Property beacons and trigonometrical survey beacons that have been displaced or destroyed shall be replaced by a registered land surveyor, who shall certify such replacement.

The cost of replacing all beacons displaced or destroyed during the course of the contract without the consent of the Employers Agent shall be the Contractor's responsibility and included in the tender rates".

ADD THE FOLLOWING AS THE PENULTIMATE PARAGRAPHS:

"The road, culvert crossing position and other access/service roads have not been set out. The horizontal alignments shown on the drawings reflect the centre line of the new roads. The contractor shall appoint an experienced and reputable land surveyor to stake the road at 20 m intervals using these alignments and shall take cross-sections of the road formation and adjacent area at 10 m intervals in mountainous areas and 20 m intervals in other areas to a distance of at least 10 m wider than the new road toe-lines. The cross-sections shall clearly define shoulder break lines, drains and batter slopes of existing cuts and fills. The cross-sections of a particular section of the road to be constructed shall be submitted to the Employers Agent for his approval at least 7 days before the time envisaged by the contractor when such a section of road will be constructed. These cross-sections shall then be used for the calculation of quantities.

The reference beacons shown on the drawings shall be used for the purpose of staking and taking cross-sections. The appointed land surveyor shall in addition also construct sufficient reference markers corresponding to the staked line to ensure that accurate measurements can be made.

No additional or extra over payment will be made for staking the road centre line or for taking cross-sections and full compensation therefore shall be deemed to be included in the rates tendered and paid for the various items of work included in this contract."

BA1.2.3.10 NOTICES, SIGNS AND ADVERTISEMENTS

Delete the fourth paragraph and replace with the following:

"All signboards erected in accordance with the drawings shall be removed at the same time as the de-establishment of the Contractor's camp. Payment under subitem B13.01 for the final instalment of 15% of the tendered lump sum shall not be made unless all the advertisements, notices and temporary signs have been removed. A typical signboard layout is included as part of the tender drawings".

BA1.12 TAKING-OVER CERTIFICATE

ADD THE FOLLOWING PARAGRAPHS AFTER ITEM (H):

"In addition to the above itemized sections of the works and regardless of the degree of beneficial occupation by the Employer, the outstanding works contained in the lists produced by the Contractor and the Employers Agent shall be considered for practical completion only if the following criteria have been met:

- (i) The estimated cost to complete the listed outstanding work is less than 2% of the tendered value of work plus the cost of any variation or extra work orders, but excluding CPA and VAT.
- (ii) The written lists of outstanding items of work can be completed within 28 days of the lists having been issued.
- (iii) Any information in the Contractor's possession, which is required by the Employers Agent and has been requested in writing, has been supplied.

If any of the listed criteria (i) through (iii) are not met at the date of the Contractor's notice of application, the Employers Agent is to reject the application without providing any corresponding list of outstanding work. If an application is rejected, the Contractor shall rectify what has been identified as deficient before submitting a new notice of application."

BA1.2.3.2 CONTRACTOR'S ACTIVITIES IN RESPECT OF PROPERTY OUTSIDE THE ROAD RESERVE AND OF SERVICES MOVED, DAMAGED OR ALTERED

ADD THE FOLLOWING AS LAST PARAGRAPH TO SUB-CLAUSE (d):

"These written statements shall be handed to the Employers Agent before the final certificate will be issued. Failing to obtain these written statements from all landowners and authorities concerned, the Defects Notification Period will be extended including all conditions related to such an extension, until such time that all these statements are obtained.

The obtaining of any such written statements will not relieve the Contractor of the execution of any of his obligations to the satisfaction of the landowner or authority concerned, and to the approval of the Employers Agent."

UNDER SUB CLAUSE (e) REPLACE THE OPENING PARAGRAPH WITH:

"Should the Contractor use land not provided by the Employer for the purpose of his own establishment, Employers Agent's offices and laboratory, or storing of equipment or materials required for construction or disposal, it shall be subject to the following:"

AND ADD THE FOLLOWING SUBSUBCLAUSE:

- "(vi) That lease agreements are concluded with the owner or owners of such land for the full period that such areas are required. The leases shall provide for possible extensions to match the duration of the contract. The lease agreements shall also provide for the contract being terminated by Contractor's default or liquidation and the resulting possibility for them to be taken over by a succeeding Contractor.
- (vii) That copies of lease agreements shall be submitted to the Employers Agent prior to signature by the signing parties, and copies lodged with the Employers Agent after signing. Notwithstanding the Employers Agent's approval of the conditions of a lease the Contractor shall be solely responsible for adherence to the terms of the agreements."
- (viii) Adherence to the principles of the environmental management plan and legal obligations".

ADD THE FOLLOWING SUB-CLAUSE:

"f) Cleaning of public roads

Where material is spilled on public roads during the haul of material, the road shall be cleaned immediately."

BA1.2.3.4 EXTENSION OF TIME RESULTING FROM ABNORMAL RAINFALL

**CHANGE THE EXISTING HEADING OF CLAUSE 1215 TO READ AS FOLLOWS:
"EXTENSION OF TIME RESULTING FROM INCLEMENT WEATHER" AND REPLACE
THIS CLAUSE WITH THE FOLLOWING:**

"Delays caused by inclement weather events may be considered as extension to the time for completion only if the Employers Agent agrees that the event (and not the consequence of the event) occurred during the working hours of a working day (based on a twenty three (23) day working month) within the contract period and caused all progress on an item or items of work on the critical path of the Contractor's approved programme (including revisions thereof) brought to a halt. Each day, or portion of a day so agreed will accrue as 'n' days of delay over the duration of the contract. The summary of accrued agreed 'n' delays shall be recorded at each site meeting.

In the case of the inclement weather event being rainfall, no limitation is placed on the quantity, severity or duration of the event as being the cause of delay except, if it is an exceptional climatic condition then it shall not be measured as a delay event under this clause, but shall be considered for delay under the general conditions of contract clause 5.12. Expressly excluded from the measurement of 'n' days are consequential delays, which are taken to mean delays to critical path activities attributable to the weather event but occurring after (i.e., outside of and distinctly separate from) the duration of the weather event itself.

The Contractor shall make provision in his approved programme (including revisions thereof) of work for expected N working days caused by inclement weather. This provision shall be shown as a terminal float on the approved programmes. Any extension to the time for completion caused by inclement weather delays will only apply once the agreed cumulative 'n' delays exceed $N = \sum n$ days. On this contract $N = 24$

"For the purpose of calculation and extension of time due to climatic conditions in terms of clause 5.12.2.2 of the General Conditions of Contract the number of days in excess of the number of working days anticipated to be lost due to climatic conditions shown in Table B1215/1 shall be taken into account:

Table B1215/1: ANTICIPATED DAYS LOST DUE TO CLIMATIC CONDITIONS

MONTH	WORKING DAYS
January	3
February	4
March	4
April	2
May	1
June	1
July	1
August	1
September	1
October	2
November	3
December	1

The Employers Agent will certify a day lost due to climatic conditions only if:

- No work on the critical path according to the latest approved programme for completion of the works could be carried out during that specific working day or if;
- Only 30% or less of the work force and plant planned for that specific day, could work.

The extension of time as a result of climatic conditions will be calculated monthly as being equal to the absolute value of the number of days certified by the Employers Agent as lost due to climatic conditions, less the number of days in Table B1215/1. The total extension of time for the contract will be the sum of the monthly extensions.

Extensions of time for a six-day working week and portions of a month shall be calculated at a pro rate.

If approved extensions of time extend the completion date beyond the start of the Christmas shut-down as defined in the Appendix to Tender, the holiday period shall not be considered as working days. Any remaining extension of time shall be calculated from the first working day in January the following year."

BA1.2.3.22 WAYLEAVES/AGREEMENTS AND PERMITS

Add the following after paragraph 3:

"Although the information provided here will assist the Contractor in selecting the necessary machinery and construction water requirements, it is still the responsibility of the Contractor to ensure that he familiarize himself with the condition on site. No claims relating to the improper use of equipment or the compaction of sand will be entertained."

BA1.2.3.21 WATER

ADD THE FOLLOWING:

“Water for use on site other than municipal, shall be subject to the required permit from Department of Water Affairs (DWA). This shall include such extraction points as rivers, dams, streams, and boreholes.

Use Table B1219 below to determine the suitability of water for construction purposes.

TABLE B1219: WATER CLASSIFICATION FOR CONSTRUCTION: TESTING

		Water Quality Classification Code						
		H0	H1	H2	H3	H4	H5	
Property	Unit	Pure water (AR)	Clean water (Rain)	Treated water (Municipal)	Silty (muddy) water with low salt content	Highly mineralized chloride sulphate water (brackish)	Waste brack, sewage, marsh, sea, etc. water	Method
PH*	-	7.0	5.7 – 7.9	4.5 – 6.5	4.5 – 8.5	9.0	-	SABS M113 SM 11 – 1990
Dissolved solids*	ppm	0	1000	1500	3000	-	-	SABS 213 SM213 - 1990
Total hardness*	-	None	None	Temporary	Temporary	Permanent	-	SABS 215 SM 215 – 1971
Suspended matter	ppm	0	2000	2000	5000	-	-	SABS 1049 SM 1049 – 1990
Electrical conductivity	mS/m	0	200	200	500	-	-	SABS 1057 SM 1057 – 1982
Sulphates (SO4)	ppm	0	200	300	500	1000	-	SABS 212 SM 212 – 1971
Chlorides (Cl)	ppm	0	500	1000	3000	5000	-	SABS 202 SM 202 – 1983
Alkali Carbonates (CO3) & Bicarbonates (HCO3)	ppm	0	500	1000	1000	2000	-	SABS 241 – 1999
Sugar	-	Negative	Negative	Negative	Negative	Negative	-	SABS 833
Quality of water required		Untreated layer works	✓	✓	✓	✓	Investigate the effect on the quality of the material	
		Chemically treated layer works	✓	✓	✓	Investigate the effect on the quality of the material		
		Concrete mass	✓	✓	✓	Investigate the effect on the quality of the material		
		Concrete prestressed	✓	✓	References: 1. Concrete Technology – Dr S Fulton (1989) 2. Materials Manual (PAWC)			
		Slurry & emulsion	✓	✓				
		Soil/gravel tests	✓	✓				
		Chemical or control tests	✓	✓				

- A primary property. The quality of the water is that quality where all three of the primary properties are within the limits.
- The tabulated single values are maximum value except in the case of the pH value for pure water, which must be 7.0

BA1.2.7.5 USE OF EXPLOSIVES

REPLACE PARAGRAPH (g) WITH THE FOLLOWING:

"The contractor shall, seven (7) days before each blasting operation is carried out, advise the Employers Agent thereof in writing. Any such blasting operation shall be confirmed with the Employers Agent twenty-four (24) hours prior to execution. The contractor shall make all the necessary arrangements to keep the public and the provincial traffic authorities fully informed with regard to the closures of the road for blasting purposes."

ADD THE FOLLOWING PARAGRAPH:

"Where blasting needs to be carried out within the road reserve of the existing road, it shall only be allowed between 11:00 and 14:00. The road may not be closed for a period longer than thirty (60) minutes during which time all blasting shall be carried out, debris removed from the road surface and the road made safe and passable for traffic. Where blasting operations are undertaken in close proximity of temporary deviations, the contractor shall implement all such safeguarding measures as may be required and instructed by the Employers Agent."

B1223 WORK ON, OVER, UNDER OR ADJACENT TO RAILWAY LINES

ADD THE FOLLOWING:

"The official specifications referred to shall be the latest edition of Specification E7, Part 2, of Transnet Limited.

The contractor shall prepare detailed drawings to indicate exactly which methods (including any phased work required) will be used to dismantle the existing road-over-rail culvert crossing and to construct the new road-over-rail culvert crossing.

Site work in connection with structures over railway lines shall not commence before the said drawings have been approved by Transnet Limited. No additional payment will be made nor will any claims be considered due to delays or inconvenience that may arise if the provisions of the E7 Specification of Transnet Limited have not been complied with.

The contractor shall make provision in his tendered rates and sums for arrangements to accommodate the rail traffic and occupy the railway reserve, and to prepare and submit the drawings as specified."

BA1.2.3.5 HANDING OVER OF ROAD RESERVE

ADD THE FOLLOWING PARAGRAPH:

"The total length of the road reserve between the specified limits of construction will be handed over to the contractor on the commencement date. Reference shall, however, be made to the requirements of Section 1500 of these specifications where limitations in respect of work-areas are specified. In the event of the non-adherence by the contractor in terms of the mentioned specifications, the Employers Agent shall withdraw such sections of the road reserve as may be justified to ensure suitable progress of the works or safe passage of traffic.

In addition to the specified repairs, the Contractor shall also carry out any maintenance work within the road reserve that the Employers Agent may require. Such maintenance shall typically comprise the clearing and repair of drainage, any structural damage caused by traffic during the contract period and the maintenance of existing road signs.

Any such work shall be as ordered by the Employers Agent and shall be carried out as daywork."

BA1.2.3.7 LEGAL AND CONTRACTUAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC AND THE EMPLOYER

ADD THE FOLLOWING NEW PARAGRAPH:

The Contractor shall be required to comply with the Occupational Health and Safety Act, 1993: Construction Regulations, 2014 (the regulations) as promulgated in Government Gazette No 37305 and Regulation Gazette No 10113 of 7 February 2014. Non-compliance with these regulations, in any way whatsoever, will be adequate reason for suspending the works.

The proposed type of work, materials to be used and potential hazards likely to be encountered on this contract are detailed in the project specifications, bill/schedule of quantities/pricing schedule and drawings, as well as in the employers' health and safety specifications (regulation 4(1) of the Construction Regulations 2014, which are bound in the contract document/will be issued separately by the employer.

The Contractor shall in terms of regulation 5(1) provide a comprehensive health and safety plan detailing his proposed compliance with the regulations, for approval by the employer.

The Contractor shall at all times be responsible for full compliance with the approved plan as well as the Construction Regulations and no extension of time will be considered for delays due to non-compliance with the above-mentioned plan or regulations.

A payment item is / Payment items are included in the bill/schedule of quantities/pricing schedule to cover the Contractor's cost for compliance with the OHS Act and the above-mentioned regulations".

B1229 SABS CEMENT SPECIFICATIONS

DELETE THIS CLAUSE.

ADD THE FOLLOWING TO THIS SUBCLAUSE:

"Where reference is made in this Specification or the Standard Specifications to the cement specifications, e.g., SANS 471: Portland cement and rapid hardening Portland cement, it shall be replaced with the new specification:

SANS ENV 197-1 Cement composition, specifications and conformity criteria Part 1: Common cements.

On this contract CEM II/B-L 32.5N cement shall be used.

ADD THE FOLLOWING NEW CLAUSES:

"BA1.2.5 MATERIALS

(a) General

The Contractor, when using materials that are required to comply with any standard specification, shall, if so ordered, furnish the Employers Agent with certificates showing that the materials do so comply.

Where so specified, materials shall bear the official mark of the appropriate authority. Samples ordered or specified shall be delivered to the Employers Agent's office on the site free of charge.

Where materials are specified under trade names tenders must be based on these materials. Alternative materials may be submitted as alternative tenders and the Employers Agent may, after receipt of tenders, approve the use of equivalent

materials. The tender must be clearly marked as an alternative tender, failing which the tender may be rejected.

Unless otherwise specified, all proprietary materials shall be used and placed in strict accordance with the relevant manufacturer's current published instructions.

Unless anything to the contrary is specified, all manufactured articles or materials supplied by the Contractor for the permanent works shall be unused.

Earth, stone, gravel, sand, and all other materials excavated or present on the site or within the road reserve, or in borrow areas shall not become the property of the Contractor but will be at his disposal only in so far as they are approved for use on the contract.

Existing structures on the site shall remain the property of the employer and except as and to the extent required elsewhere in the contract, shall not be interfered with by the Contractor in any way.

Materials to be included in the works shall not be damaged in any way and, should they be damaged on delivery or by the Contractor during handling, transportation, storage, installation or testing they shall be replaced by the Contractor at his own expense.

All places where materials are being manufactured or obtained for use in the works, and all the processes in their entirety connected therewith shall be open to inspection by the Employers Agent (or other persons authorized by the Employers Agent) at all reasonable times, and the Employers Agent shall be at liberty to suspend any portion of work which is not being executed in conformity with these specifications.

The Contractor shall satisfy himself that any quarry selected for use provides the necessary mined material in accordance with the specification.

(b) Banned materials

No tar fluid products shall be used in the construction works.

B1231 REPORTING OF ACCIDENTS/INCIDENTS

The Contractor shall report every accident/incident which occurs on the road, within the extent of the works, to the Employers Agent, within twenty-four (24) hours of such accident occurring, irrespective of whether such accident has a bearing on damage to the works or to persons, property or things. The report must be in writing and must contain full particulars of the accident. Photographs of each accident shall also be included in the report. The Employers Agent has the right to conduct any or all enquiries, either on the site or elsewhere, as to the causes and consequences of any such accident. The Contractor shall also keep a comprehensive record of all accidents which occur on the road and shall make such record available to the Employers Agent on demand.

BA1.2.5.2 MIX DESIGNS

Before commencing with certain construction activities, the Contractor shall, except where specified otherwise in the relevant construction sections in the Scope of Works, apply the following procedures with regards to mix designs:

- Taking and submitting samples of the relevant materials.
- Undertake the required mix design(s) or allow the Employers Agent to undertake them.
- Produce, where required, laboratory, production/plant and/or trial mix(es).
- Undertake the required adjustments to the mix design(s) and reproduce required laboratory, production/plant and/or trial mix(es).
- Complete trial section(s) where required.
- Await the Employers Agent's approval of the mix design(s) and trial section(s).

1.1.2 LABOURENHANCEMENT**(a) General**

The following provisions shall apply in respect of those portions of the works that are specified in C3.1.3 to be executed using labour-optimising construction methods.

(b) Restrictions on the use of electrical and mechanical plant and equipment

Except to the extent specified in Part C1.2 Annexure D, Part C3.1.3 and Part 3.3, and notwithstanding anything to the contrary which may be stated in, or be reasonably inferred from any provisions elsewhere contained in the contract, the contractor shall use only labour and non-mechanically or non-electrically powered hand tools, equipment or plant in the execution and completion of all such portions of the works listed in Part C3.1.3 and Part 3.3 that are to be constructed by labour-optimising construction methods; provided always that the Employers Agent may at his sole discretion and at any time, or upon receipt of a fully motivated written application from the contractor, authorize the contractor to use such electrical or mechanical plant and equipment as he may deem appropriate or necessary under the circumstances, in the execution of such portions of the works otherwise required, in terms of Part C3.1.3 and Part 3.3, to be constructed using labour-optimising construction methods only.

(c) Classification of excavations

Notwithstanding anything to the contrary which may be contained elsewhere in the Specifications, excavations shall be classified according to the specified method of excavation as follows:

- (i) Excavations which are:
- not specified in Part C3.1.3 and Part 3.3 as required to be executed using labour-optimising construction methods; and
 - specified in Part C3.1.3 and Part 3.3 as required to be executed using labour-optimising construction methods but which, notwithstanding, are executed by the contractor using mechanical plant and equipment prohibited in terms of the project specifications, either with the prior authorisation of the Employers Agent or in breach of the provisions of the specifications, shall be classified in accordance with the provisions of the standard specifications.
- (ii) Excavations which are specified in Part C3.1.3 and Part 3.3 as being required to be executed using labour-optimising construction methods and which are so executed, shall be classified in accordance with table B1233/1.

TABLE B1233/1: CLASSIFICATION OF EXCAVATION

Classification	Number of blows required for a DCP penetration of 100 mm	
	Granular soil	Cohesive soil
Soft	≤30	≤ 10
Hard	> 30	> 10

- (iii) Where only excavation in soft material is required in terms of Part C3.1.3 to be executed using labour-optimising methods, the classification for the purposes of determining the cut-off point for labour-optimising excavation shall be made in terms of subclause (ii) above, and the excavation beyond the cut-off point shall be in terms of subclause (i) above.
- (iv) Classification of material specified to be excavated using labour-optimising construction methods, but not in fact excavated by such methods, whether in compliance with an instruction from the Employers Agent, or in accordance with a concession granted by the Employers Agent or through default of the contractor, shall be made in terms of sub subclause (i) above.

B1234 TRAINING

Structured training shall be provided to temporary personnel involved in the contract in accordance with the provisions set out elsewhere in this document. The contractor's selection of the candidates shall be approved by the project liaison committee and the Employers Agent, subject to the required entrance levels. All training courses must be offered through approved accredited training organizations.

The contractor shall provide the following for the training:

- (a) A venue with sufficient lighting, electric power points and furniture
- (b) All necessary stationery, consumables and study material
- (c) Transport to and from the training venue if the training is not delivered on site
- (d) Wages for candidates attending Engineering (technical) skills training during working hours
- (e) Payment to approved training organizations for the provision of training.

NB: Only technical skills may take place during normal working hours. All training courses shall commence within one month of handing over the site and be complete before the end of the contract period.

BC2.1.30 PROJECT LIAISON OFFICER (PLO)

The contractor or his appointed agent will appoint a project liaison officer (PLO) after consultation with the local communities, the Employers Agent and the employer. The contractor shall direct all his liaison efforts with the local communities through the appointed officer. The contractor shall, however, accept the appointed as part of his management personnel.

(a) Duties of the project liaison officer

The project liaison officer's duties will be:

- (i) To be available on site daily between the hours of 08:00 and 12:00 and at other times as the need arises. His normal working day will extend from 08:00 in the morning until 17:00 in the afternoon.
- (ii) To determine, in consultation with the contractor, the needs of the temporary labour for relevant skills training. He will be responsible for the identification of suitable trainees and will attend one of each of the training sessions.
- (iii) To communicate daily with the contractor and the Employers Agent to determine the labour requirements with regard to numbers and skill, to facilitate in labour disputes and to assist in their resolution.
- (iv) To assist in and facilitate in the recruitment of suitable temporary labour and the establishment of a "labour desk".
- (v) To attend all meetings in which the community and/or labour are present or are required to be represented.
- (vi) To assist in the identification, and screening of labourers from the community in accordance with the contractor's requirements.
- (vii) To inform temporary labour of their conditions of temporary employment and to inform temporary labourers as early as possible when their period of employment will be terminated.
- (viii) To attend disciplinary proceedings to ensure that hearings are fair and reasonable.

- (ix) To keep a daily written record of his interviews and community liaison.
- (x) To attend monthly site meetings to report on labour and RDP matters.
- (xi) All such other duties as agreed upon between all parties concerned.
- (xii) To submit monthly returns regarding community liaison as illustrated in this document (forms to be provided by the Municipality).

(b) Payment for the project liaison officer

A special pay item is incorporated in Section 1200 of the bill of quantities relating to payment of the liaison officer on a provisional sum basis. This payment shall only be made for the period for which the duties of the liaison officer are required. The remuneration of the PLO shall be determined by the employer in terms of the Sectorial Determination 2: Civil Engineering Sector (Task Grade 3).

(c) Period of employment of the project liaison officer

The period of employment of the project liaison officer shall be as decided upon jointly by the contractor, Employers Agent and employer at a maximum period of a six months basis, but with the option of renewal.

B1235 SUBCONTRACTORS

Over and above the stipulations of the Conditions of Contract, regarding subletting of part of the works, it is a condition of the contract that an approved subcontractor shall not sublet part of his work, covered in his appointment by the main contractor, to another subcontractor without the consent and approval of the Employers Agent. Subletting shall in all cases be critically considered by the Employers Agent.

In addition to the provisions of the Conditions of Contract regarding subcontracting of the works, it is a requirement of this contract that an approved subcontractor shall not further subcontract work subcontracted to him by the main contractor, to another subcontractor without the consent and approval of the Employers Agent. Subcontracting shall in all cases be critically considered by the Employers Agent. The Employers Agent reserves the right to limit the extent or the volume of work subcontracted by the contractor, should he deem it necessary in terms of progress or quality of workmanship.

B1236 WORKMEN'S COMPENSATION ACT

All labour employed on the site shall be covered by the Compensation for Occupational Injuries and Deceases Act (COIDA). The contractor shall pay in full, including the payment of the necessary levies, such amounts, as are due in terms of the Act. The contractor at the commencement of the contract shall resolve the manner in which Workmen's Compensation will be handled. Amounts paid by the contractor shall not be included in the wage rates but shall be covered by the contractor to be deemed as included in his General Obligations rates in Section 1300 of the bill of quantities.

B1237 OWNERSHIP OF REDUNDANT ROAD SIDE FURNITURE AND OTHER MATERIALS

Ownership of all redundant road side furniture and other materials will remain the property of the Employer unless otherwise specified by the Employers Agent and shall be taken to the Municipality.

B1238 MEASUREMENT AND PAYMENT

Item	Unit
BC2.1.29 Training	
(a) Engineering (technical) skills	provisional (Prov) sum

- (b) Training venue Lump Sum
- (c) Remuneration of workers undergoing technical skills training.....provisional (Prov) sum
- (d) Construction handling costs, profit and all other charges in respect of subitems B12.01 (a) & (c)
 - (i) Engineering (technical) skills..... percentage (%)
 - (ii) Remuneration of workers undergoing technical skills training..... percentage (%)

Payment under subitems B12.01(a), shall be the amounts actually paid to the training institutions and shall be made in accordance with the provisions of the Conditions of Contract.

The lump sum tendered for subitem B12.01(b) shall include full compensation for the provision of a suitable training venue, for all necessary lighting, furniture, stationery, consumables and study material, and for transportation of the workers to and from the training venue. Payment of the lump sum will be made in two instalments as follows:

- (i) The first instalment, 75% of the lump sum, will be paid after the contractor has met all his obligations regarding the provision of the training venue as specified.
- (ii) The second and final instalment, 25% of the lump sum, will be paid after the contractor has met all his obligations regarding the provision of all the training programmes specified in the document.

Payment under subitem B12.01(c) shall be the actual sum paid to workers undergoing technical skills training. The contractor will not be reimbursed directly for his administrative costs which will be deemed to be included in the rates tendered for item B13.01.

The percentages tendered for subitem B12.01(d) shall be the percentages of the amounts actually reimbursed to the contractor under subitems B12.01(a), and (c) and shall be in full and final compensation in respect of the contractor's handling costs, profit, mentoring, record-keeping, reporting and all other charges in connection with providing the services.

BC2.1.30 .. Remuneration of the Project Liaison Officer and members of the Project Liaison Committee:

- (a) Project Liaison Officerprovisional (Prov) sum
- (b) Project Liaison Committeeprovisional (Prov) sum

The provisional sum provided shall cover the salary of the duly elected and approved CLO.

The tendered percentage is a percentage of the amounts actually spent under the items, which shall include full compensation for the handling costs of the Contractor, and the profit in connection with the remuneration of the Project Liaison Officer and Committee.

BC2.1.31 Penalties

- a) Targeted Labourpercentage point

The penalty for item (a) for not attaining at least the tendered number of person-days (refer to Part T2: Returnable Documents) will be calculated as follows:

In the event that the Tenderer fails to substantiate that any failure to achieve the Contract Participation Goal was due to quantitative under runs, the elimination of items, or any other reason beyond the Contractor's control which may be acceptable to the Employer, it shall be liable to pay to the Employer a financial penalty calculated in the following manner:

The penalty for failure to achieve the Contract Participation Goal shall be applied at a rate of 100% of the value by which the accumulative value of the measurable elements fails to meet the tendered CPG in the table below and shall be applied on a pro-rata basis according to a monthly evaluation of achievements against the targets tendered by the contractor in T2.3.5 item 6 broken down to monthly expenditure.

A further penalty for failure to achieve the Contract Participation Goal in terms of training shall be applied at a rate of 100% of the value by which the accumulative value of the measurable elements fails to meet the planned training targets, based on the Provisional Sum amount, as submitted by the Contractor within 22 working days as specified in clause 5.3.1 of the contract data. The training penalty shall be applied on a pro-rata basis according to a monthly evaluation, starting the second month of the contract, of achievements against the targets planned by the contractor.

BC2.1.32 Excavation for existing services:

- (a) Excavation and carting away of excavated material in search of existing services in soft material situated in the following depth ranges:
 - (i) 0m to 2m..... cubic metre (m³)
 - (ii) 2m to 3m..... cubic metre (m³)
- (b) Extra over B12.04(a) for excavation in hard material in close vicinity of services using picks, jackhammers, power tools etc. Where no blasting or machine excavation is permitted..... cubic metre (m³)

The unit of measurement shall be the cubic metre of material excavated between the various depth ranges to locate existing services.

The tendered rate shall include full compensation for plant, equipment to carry out the work, loading, transporting (including all haul), unloading and disposing of the material at approved dumping sites provided by the contractor.

BC2.1.33 Protection, removal, realignment and replacement of services

- (a) Utility Services/Telkom, Fibre Optic Cables:
 - (i) The protection, removal, realignment and replacement of Services..... prime cost (PC) sum
- (b) Utility Services/ Municipality
 - (i) The protection, removal, realignment and replacement of Services..... prime cost (PC) sum
- (c) Utility Services/ Eskom
 - (i) The protection, removal, realignment, and replacement of Services..... prime cost (PC) sum
- (d) Handling costs and profit with respect to item B12.04(a), (b) & (c).....%

The prime cost items shall be paid in accordance with the provisions of the General Conditions of Contract as amended by Particular Conditions of Contract. The tendered percentages are percentages of the amount actually spent under the prime-cost items, which shall include full compensation for the profit in connection with providing the specified service.

C1.3.2 Contract sign boards

BC1.3.2 Contract Sign BoardsNumber (No)

The unit of measurement for item BC1.3.2 of Contract sign board is Numbers (No) the total numbers of the approved contract sign boards must be 2 (Two) provided and erected by the Contractor in the positions on site indicated by the Engineer. The contract rate for item C1.3.2 shall include full compensation for all costs associated with providing, erecting and for the later removal of the contract signboards as soon as the Works have been completed. Refer to Drawing in the tender document

BC2.1.36 Installation of new street lights complete including cabling, excavations and backfill to Electrical Engineer's Specification.....provisional sum

The unit of measurement shall be the above items is for payment to service providers and their sub-contractors for the installation and relocation of the street lights.

The tendered rate shall include full compensation for furnishing and erection of the street lights, including the cabling, excavations and backfill as detailed on the drawings.'

BC2.1.37 Handling Cost and Profit on Item B12.07..... %

The percentages tendered for subitem B12.08 shall be the percentages of the amounts actually reimbursed to the contractor under subitems B12.07 and shall be in full and final compensation in respect of the contractor's handling costs in connection with providing the service.

BC2.1.38 Signalised intersectionprovisional sum

The unit of measurement shall be the above items is for payment to service providers and their sub-contractors for the installation of traffic signals.

The tendered rate shall include full compensation for furnishing and erection of the traffic lights, including the sleeves, cabling, excavations and backfill as detailed on the drawings and setting of the traffic signals according to the approved drawings.'

BC2.1.39 Handling Cost and Profit on Item B12.07..... %

The percentages tendered for subitem B12.010 shall be the percentages of the amounts actually reimbursed to the contractor under subitems B12.08 and shall be in full and final compensation in respect of the contractor's handling costs in connection with providing the service."

CHAPTER 1: 1.3 CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS

GENERAL REQUIREMENTS

(i) Legal and Contractual Requirements and responsibilities to the public

ADD THE FOLLOWING AFTER THE FIRST PARAGRAPH:

"Before the establishment of the Contractor's camp at an approved site, the area will first be fenced off and, if required by the Employers Agent, 150 mm of topsoil and vegetation removed to temporary stockpiles as described in Section 1700

ADD THE FOLLOWING AS A SECOND PARAGRAPH

"Legislation imposes mutual obligations on the Employer and Contractor in the performance of their duties to society and to the built and natural environment. To assist the Contractor in understanding and assessing his obligations, and thus to make allowances for the cost of compliance with this legislation, the following additional specifications are included in the project specifications.

Section C3.3 of the Scope of Works contains provisions that regulate the Contractor's construction methods for compliance with Government's initiatives towards black economic empowerment. It also contains information on criteria used in the procurement process. No separate payment mechanism has been made available for the Contractor to allow for his compliance with relevant black economic empowerment legislation. The Contractor shall include such costs in the existing payment items under section B1303: Payment. However, non-compliance with the provisions of this section may lead to the imposition of penalties."

Section C4.3 of the Site Information contains the Environmental Management Plan (EMPI) for this project. Its provisions regulate the Contractor's construction methods to ensure responsible conduct and treatment of the environment relevant to the project. Payment subitem B13.01(d) makes allowance for the Contractor to price for environmental compliance duties as well as the duties of the Designated/dedicated Environmental Officer (DEO) as prescribed in this section. The contractor shall comply with all statutory and contractual requirements of the Environmental Management Programme.

Section C1.2 Annexure C of the Contract Data contains the specifications that regulate the Contractor's construction methods so far as to ensure health and safety of his employees and of the public. New pay item has been made available under this section to allow the Contractor to make separate provision for the cost of health and safety measures during the construction process.

ADD THE FOLLOWING NEW SUBCLAUSES:

"(d) Safety of Contractor's and sub-Contractor's workforce

The Contractor is responsible for the safety of its workforce and for the safety of subcontract employees employed on the site.

(e) Contractor's ablution facilities

"The Contractor shall, at each area where work is being undertaken, provide on a daily basis at least one (1) portable chemical latrine unit per thirty (30) workers for use by construction workers employed on the project. The latrine units shall be serviced daily and kept in a hygienic and orderly state to the satisfaction of the Employers Agent. No separate payment shall be made for this requirement and it shall be deemed to be included in the rates tendered for the Contractor's time-related obligations."

(f) Monthly reporting

When submitting any information required and interim certificates for payment, the Contractor shall use the Employer's standard forms and formats. No payment can be made before the Contractor is registered as a vendor on the Employer's system.

The Contractor shall submit payment certificates for all work rendered in the Employer's financial year within that specific year.

The Contractor shall submit and update on a monthly basis all the appendices to the site meeting minutes and a cash flow forecast for the works.

The Contractor shall complete monthly reports regarding training, empowerment, capacity building, small Contractor development, labour and staff returns and any such aspects on the Employer's standard forms. This information shall also be reported on monthly for all sub-Contractors employed.

The above information shall form part of supporting documentation required for making interim payments in terms of the General Conditions of Contract.

Allowance has been made for these requirements in the Pricing Schedule under pay item B13.01(e) Monthly Reporting. Failure to comply may result in payments being withheld"

PART C MEASUREMENT AND PAYMENT

Item	Unit
-------------	-------------

BC1.2.1 The Contractor's establishment including general obligations

ADD THE FOLLOWING PAY SUB-ITEM:

“(2.1) Environmental obligation	month
“(2.2) Monthly reporting cost	month
“(2.5) Security on site	month

INSERT THE FOLLOWING PARAGRAPH AFTER THE FOURTH PARAGRAPH:

"Should the combined total tendered for subitems (a), (b), and (c) exceed 15% of the tender sum (excluding CPAF, contingencies and VAT), the tenderer shall state his reasons in writing for tendering in this manner."

ADD THE FOLLOWING SUB-SUB-CLAUSE DEFINING THE CONTRACTOR'S GENERAL OBLIGATIONS:

“(iv) Complying with the requirements and conditions of the additional specifications relating to the Government's Black Economic Empowerment and the Environmental Management Program.

Replace "clause 49" in the 4th, 8th and 10th paragraphs with "sub-clauses 6.8".

DELETE THE FOURTH LAST PARAGRAPH COMMENCING "The tendered rate per month for sub-item B13.01(c) ..." AND REPLACE WITH:

"The tendered rate per month for sub item B13.01 (c) represents full compensation for that part of the Contractor's general obligations that are mainly a function of construction time. The tendered sum will be paid monthly, pro rata for parts of a month, from the Commencement Date until the end of the period for completion of the works, plus any extension thereof as provided in Clause 5.12 of the General Conditions of Contract.

Payment for time related costs arising from extensions of time granted by the employer, where the Contractor is fairly entitled to such compensation in terms of Clause 5.12 of the General Conditions of Contract, will be calculated by taking account only of pay items for

which the unit of measurement is "month". All pay items for which the unit of measurement is "month" are deemed to be based on 23 working days per month."

The Contractors' annual holiday period in December / January as provided for in the Contractor's program shall be non-working days and shall not form part of the period of Time for Completion, and measurement and payment for time related items and costs shall not apply to this period."

ADD THE FOLLOWING AT THE END OF THE LAST SECTION ON PAYMENT:

"Payment of the rate per month for subitems B13.01(d), (e), and (f) shall include full compensation for all the Contractor's obligations relevant to environmental compliance, monthly reporting and security on site (as per clause 4 of the GCC 2015).

The tendered rates for subitems 13.01(d), (e), and (f) shall apply in the same manner as pay subitem B13.01(c).

A Contractor who tenders zero for this pay item shall not be relieved of his statutory obligations. A nil rate offered shall be deemed not to be an omission, but to be a deliberate notice that costs have been included in the tendered rates for individual items of work, or in other preliminary and general pay items.

CHAPTER 1: 1.4 FACILITIES FOR THE ENGINEER**A1.4.3 General**

ADD THE FOLLOWING AT THE END OF THE FIRST PARAGRAPH:

"Burglar-proofing shall comply with the requirements of CKS 338.

The facilities to be provided for the engineer in terms of these specifications shall be fenced off by a two metre high veranda type security fence with diamond mesh on the vertical portion and barbed wire on the overhang. A security gate shall be provided in the fence which shall be guarded at all times by an acceptable watchman provided by the contractor.

The engineer's establishment may be incorporated within the contractor's establishment provided that the preceding requirements are met to the satisfaction of the engineer.

Separate payment shall be made for the provision and erecting of the security fence and gate as indicated on the drawings, but the cost in respect of the provision of a watchman at all times by the contractor shall be deemed to be included in the contractor's tendered rate for item B13.01(c)."

(b) Offices

ADD THE FOLLOWING SUBSUBCLAUSES:

- "(xiv) General-purpose steel cupboards with four shelves.
- (xvi) The electric refrigerator shall have a capacity of at least 200 litres.
- (xvii) Bookcases with four shelves.
- (xviii) Voltage stabilizer.
- (xix) Steel plan cabinets shall be able to accommodate one/two hundred and fifty A0-sized drawings hanging vertically from approved holders.
- (xx) Floodlights at the offices and laboratory of the supervisory staff shall be controlled by a photocell for security purposes.
- (xxi) The cellphones and car kits supplied to the engineer's site staff shall be supplied for the duration of the contract. The prime cost sum shall also include for the cost of all telephone calls in connection with contract administration."

ADD THE FOLLOWING SUBCLAUSE:

"(i) Computers and printers

When instructed by the Employers Agent, the contractor shall provide approved new computer equipment, including software and printers for use by the Employers Agent's site personnel. The type of equipment and software shall be as instructed by the Employers Agent and payment for equipment and maintenance shall be made through item B14.12.

All equipment provided shall be kept fully serviceable at all times by the contractor. The contractor shall repair/replace any defective equipment within 48 hours after notification by the Employers Agent's staff. The contractor shall also be responsible to provide all paper and ink cartridges required by the Employers Agent.

At the end of the contract, the equipment and software shall revert back to the contractor."

BC1.4.7.3 SERVICES

(b) Water, electricity and gas**ADD THE FOLLOWING:**

"The power supply shall be regulated by a suitable voltage regulator in order to maintain a constant current and voltage level at all times to prevent damage to the office and laboratory equipment and related machinery during power surges. Payment for the voltage regulator shall be deemed to be included in the rates tendered for the supply of power. In the event of damage to the office and laboratory equipment and related machinery because of a faulty voltage regulator, the contractor shall be liable for payment of all repair or replacement costs of such damaged items."

(c) Maintenance**REPLACE THE CONTENTS OF THIS SUBCLAUSE WITH THE FOLLOWING:**

"The contractor shall supply all labour, equipment and materials required for keeping the offices, ablution units, car-ports at the offices, in a neat and clean condition, and shall immediately undertake repairs requested by the Employers Agent to the offices, ablution units, car-ports, rented houses. The contractor is not responsible for keeping rented houses in a clean and neat condition, nor for tending to or caring for the gardens."

PART C: MEASUREMENT AND PAYMENT

Item	Unit
BC 1.4.3 Office and laboratory fittings, installations and equipment:	
(a) Items measured by number:	
CHANGE SUBITEM (i) TO READ AS FOLLOWS:	
"(i) 220/250 volt power points including voltage stabilizers and regulators as specified	number (No)"
ADD THE FOLLOWING SUBSUBITEMS:	
"(xiv) General-purpose steel cupboards with four shelves.....	number (No)
(xvi) The electric refrigerator shall have a capacity of at least 200 litres.....	number (No)
(xvii) Bookcases with four shelves.....	number (No)
(xviii) Voltage stabilizer.....	number (No)
(xix) Steel plan cabinets shall be able to accommodate one hundred and fifty A0-sized drawings hanging vertically from approved holders.....	number (No)
(xx) Floodlights at the offices and laboratory of the supervisory staff shall be controlled by a photocell for security purposes.....	number (No)
(xix) Steel plan cabinets	number (No)
(xx) Floodlights complete with poles and minimum 500 watt globes.....	number (No)

The tendered rate for subitem BC1.4.3(a)(xx) shall include for the operation of the lights from sunset to dawn for the full duration of the contract."

(b) Prime-cost items and items paid for in a lump sum:

REPLACE THE DESCRIPTION OF SUBSUBITEM BC1.4.3(b)(i) WITH THE FOLLOWING:

- "(i) Provision of cellphones complete with car kits fitted to vehicles as directed, including all fees and the cost of phone calls in connection with the administration of the contract..... Prime Cost (PC) Sum
- (ii) Handling costs and profit in respect of subitem 14.03(b)(ix) above.....percentage (%)"

Item

Unit

BC1.4.1.1 Provision of Photostat facilities

AMEND THIS PAYITEM DESCRIPTION TO READ "provision of copying facilities" AND IN THE PAYMENT PRESCRIPTION, AMEND "photocopier" TO READ "combination colour printer/copier/scanner/facsimile machine".

Item	Unit
BC1.4.1.2 Supply of computer hardware and software:	
(a) Supply of computer equipment and software	Prime Cost (PC) sum
(b) Handling cost and profit in respect of subitem B14.12(a)	percentage (%)

Expenditure under this item shall be made in accordance with the Conditions of Contract.

The tendered percentage is a percentage of the amount actually spent under subitem B14.12(a), which shall include full compensation for the handling costs of the contractor, and the profit in connection with providing the specified equipment."

CHAPTER 1: 1.5 ACCOMMODATION OF TRAFFIC

A1.5.1 SCOPE

ADD THE FOLLOWING:

"It is a requirement of this specification that traffic is accommodated taking into account the provisions of the latest edition of the South African Road Traffic Signs Manual (SARTSM). The latest version for use in the accommodation of traffic is volume 2, chapter 13 of the June 1999 edition. Copies of this publication are available from Government Printers –Tel: (012) 334 4507/8/9 or (012) 334 4510 Fax: (012) 323 9574. elsa.herbst@gpw.gov.za.

This section also covers the provision of additional information signs for motorists and the release of any notices to the media and public."

A1.5.3.2 GENERAL REQUIREMENTS

(a) Safety

ADD THE FOLLOWING PARAGRAPH:

"The contractor shall be responsible for maintaining the existing road surface both within the works area and the advance warning and termination areas in a safe and trafficable condition for the duration of the contract.

The Contractor shall within 7 (seven) working days after receipt of a 3rd party claim acknowledge receipt to the claimant. The Employers Agent shall be copied on all correspondence regarding 3rd party claims. The Contractor shall at the monthly site meeting report on the status and outcome of the 3rd party claims."

(b) Providing temporary deviations

ADD THE FOLLOWING PARAGRAPH:

"The contractor shall keep the provincial traffic police, the municipal traffic department and the Employers Agent fully informed of changes in the normal traffic flow and obtain their approval for these changes."

(e) Access to properties

ADD THE FOLLOWING:

"Where the alignment of the new road coincides with the alignment of the existing road, accesses to private properties will have to be operational and maintained during the constructional period. No separate payment will be made for providing acceptable and safe access across the new road at all times during construction of the road."

(f) Approval of temporary deviations

ADD THE FOLLOWING:

"The Contractor's programme for the accommodation of traffic must be approved by the Employers Agent on site. The Employers Agent shall also have the power to stop any work at any time if the road signs are not compliant with the prescribed requirement and/or if the non-compliance is deemed to place the safety of the travelling public at risk.

If, after any temporary deviation has been constructed, any changes are considered necessary or desirable, the proposal shall be submitted to the Employers Agent for his approval.

The contractor shall keep the provincial traffic police, the municipal traffic department and the Employers Agent fully informed of changes in the normal traffic flow and obtain their approval for these changes"

(i) Traffic Safety Officer

ADD THE FOLLOWING AFTER SUBCLAUSE (viii):

- "(ix) be responsible for contacting all the relevant authorities in the event of an accident on the site of the works
- (x) arrange for the removal of broken down vehicles that obstruct the normal traffic flow

The contractor shall provide the traffic safety officer with all the necessary resources to carry out his duties as specified, inter alia, light delivery van (LDV), personnel, warning signs and revolving amber flashing lights. A warning sign with the words "CONTRACTOR TRAFFIC CONTROL" in clearly legible letters shall be mounted on the vehicle at least 1,5 m above ground level to be clearly visible. The vehicle shall be equipped with two revolving amber-coloured flashing lights with a minimum intensity of 55 W. The flashing lights shall be switched on and the warning sign be displayed at all times when the vehicle is used on the site.

No separate payment will be made for the traffic safety officer, his vehicle, personnel and equipment and the cost thereof shall be included in the contractor's cost for his establishment and general obligations (section 1300)."

ADD THE FOLLOWING SUB-CLAUSES:

"(j) Site Personnel

The Contractor shall ensure that all his personnel, excluding those who are permanently office bound, are equipped with reflective safety jackets and that these are worn at all times when working on or near to the travelled way. Any person found not wearing a reflective jacket under these circumstances shall be removed from the site until such time as he is in possession of and wearing a reflective jacket. Reflective safety jackets shall be kept in good condition and any jackets that are, in the opinion of the Employers Agent, ineffective shall be immediately replaced by the Contractor.

(k) Liaison with Mangaung Metro Municipality Traffic Department

The Contractor shall obtain permission and approval of his traffic management plan from the municipality in writing prior to any work starting on any section of the work.

(l) Other requirements

The following other requirements must be adhered to for the entire contract period:

- i) The travelling public shall have the right of way on public roads and the Contractor shall make use of approved methods to control the movement of his equipment and vehicles so as not to constitute a hazard on the road.
- ii) The Contractor's tendered rates for the relevant items in the schedule of quantities shall include full compensation for all possible additional costs which may arise from the above and no claims for extra payment due to inconvenience as a result of the modus operandi will be considered.
- iii) "Normal working hours" (referred to in Clause 5.8 of the General Conditions of Contract) will, because of heavy peak hour traffic volumes, be restricted to between 30 minutes after sunrise and 30 minutes before sunset.

**BA1.5.5.7 TEMPORARY TRAFFIC-CONTROL FACILITIES TRAFFIC ACCOMMODATION
FACILITIES AND SAFETY DEVICES**

REPLACE THE FIRST SENTENCE OF THE FIRST PARAGRAPH WITH THE FOLLOWING:

"The Contractor shall provide, erect and maintain the necessary traffic-control devices, road signs, channelization devices, barricades, warning devices and road markings (hereinafter referred to as traffic-control devices) in accordance with these special provisions and as shown on the drawings and in the SARTSM, Vol 2 (May 2012) and remove them when no longer required. It shall be incumbent upon the Contractor to see to it that the abovementioned traffic-control devices are present where required at all times and are functioning properly.

All temporary road signs, devices, sequences, layouts and spacings shall comply with the requirements set out in the National Road Traffic Act, 1996 (Act No 93 of 1996), the National Road Traffic Regulations, 2000 of the relevant authorities and on the drawings or as instructed by the Employers Agent.

The contractor shall indemnify the employer against all proceedings, claims, actions, damages and costs which may arise from or be related to the absence or improper functioning or placement of road traffic signs, barricades, traffic-control facilities, channelization devices and warning devices."

REPLACE THE LAST SENTENCE OF THE SECOND PARAGRAPH WITH THE FOLLOWING:

"Traffic-control facilities lost or damaged by the Contractor shall be replaced at his own cost. Where it can be proved that loss of or damage to such facilities is beyond the Contractor's control and not the result of his actions or omissions, the Employers Agent may order the facilities to be replaced and paid for at scheduled rates."

REPLACE THE THIRD PARAGRAPH WITH THE FOLLOWING:

"The type of construction, spacing and placement of traffic-control devices shall be in accordance with the SARTSM, Vol 2 (May 2012). The recommended arrangements of the traffic control devices illustrated and/or drawings issued by the Employers Agent shall not be departed from without prior approval of the Employers Agent. The arrangements expected to be most commonly used in the contract are given on the tender drawings.

The details shown for spacing and placement of traffic-control facilities may, however, be revised at the discretion of the Employers Agent where deemed necessary to accommodate local site geometry and traffic conditions."

b) Road signs and barricades

ADD THE FOLLOWING:

"The Contractor shall be responsible for the protection and maintenance of all signs, and shall at his own cost replace any that have been damaged, lost, or stolen.

All temporary road signs required to remain in position for some time shall be pole mounted as shown on the drawings. All temporary road signs required to be moved more often shall be mounted on portable supports for the easy moving of signs to temporary positions. The only permitted method of ballasting the sign supports shall consist of durable sandbags filled with sand of adequate mass to prevent signs from being blown over by wind. The cost of the sandbags shall be included in the tendered rates for the various types of temporary road signs.

The covering of permanent road signs, if applicable, shall be by utilizing a suitable and durable covering that shall be pulled over the sign in the form of a hood and fastened to the signposts. Plastic bags or other materials and fastened by means of

adhesive tape shall not be permitted. The cost of covering of permanent road signs shall be included in the tendered rates of items B15.01 and 15.10."

c) Channelization devices and barricades

ADD THE FOLLOWING:

"The use of drums as channelization devices shall not be permitted. Drums may however be used to set up barriers as provided for in sub-clause 1503(d).

TW 401 and TW402 delineators shall be used at all times and comply with the following requirements:

- (i) comply with the manufacturing and reflective requirements of the SARTSM and the blades shall be reversible with dimensions as indicated on the drawings.
- (ii) have smooth and round edges and be mounted on a post and base. All components shall be of durable plastic material;
- (iii) It shall be nominally 1 000 mm high x 250 mm wide and the bottom edge of the delineator shall not be more than 200 mm above the road surface;
- (iv) be capable of withstanding the movement of passing vehicles and gusting winds up to 60km/h in typical working conditions without falling over. To achieve this, the base shall be at least 0,18m² and ballasted by its own weight or with sandbags filled with sand;
- (v) together with its mounting be designed such that it will collapse in a safe manner under traffic impact.

Traffic cones manufactured in a fluorescent red-orange or red plastic material may be used only at short term lane deviations during daylight. Cones shall not be used on their own, but shall be interspersed with delineators at a ratio not exceeding 3:1. Cones used on all deviations shall be 750mm high. Lane closures which continue into the night time shall be demarcated by delineators only.

On section of road where the centerline has been obliterated, delineators shall be provided on both road edges at minimum 200m spacing on straight sections and at least 3 (three) visible on all curves."

d) Barriers

ADD THE FOLLOWING:

"Barriers for preventing vehicles from leaving the permitted lanes shall be movable barriers with an approved safety shape design (e.g., New Jersey, F-shape or single slope). Temporary movable barriers shall be obtained from suppliers and placed between the existing road and the construction areas. They shall comply with the requirements of either of the following specifications:

- (i) The European Specification EN 1317 with containment level H1, or
- (ii) The American Federal Highways Administration Specification NCHRP Report 350 with containment level TL4.

When applying these specifications, the Contractor must take cognizance of his liabilities relating to the installation of temporary works to provide protection to the permanent Works and safety to his personnel and select a barrier system appropriate to his chosen work methodology. Particularly pertinent is the working width rating of a barrier system; the displacement width of the system shall not exceed the available safe width to the nearest edge of the construction. All moveable barriers shall be installed in accordance with the manufacturer's

instructions or generally accepted best practice and shall be submitted to the Employers Agent for review and comment.

Where instructed by the Employers Agent, the terminal sections of moveable barriers may be a proprietary type or may be Contractor designed to attenuate head-on impacts of at least NCHRP Test Level 1 (50 km/h, 2 000 kg) or EN1317 Containment Level H1 (80 km/h, 1 500 kg)."

e) Warning devices

ADD THE FOLLOWING:

"All construction vehicles and plant used on the works shall be equipped with rotating amber flashing lights and warning boards as specified. All vehicles and plant before being allowed onto the site shall obtain a clearance permit from the Employers Agent.

(i) Vehicle mounted flashing lights

Rotating amber flashing lights (min 55 W) shall have an amber lens of minimum height of 200 mm and shall be mounted in such a way as to be highly visible from all directions. The lights on construction vehicles shall not be switched on while vehicles are being operated on unrestricted sections of a public road, but shall be switched on while construction vehicles are operating within the accommodation of traffic area, as the vehicles decelerate to enter a construction area, and as the vehicles accelerate to the general speed when entering the road from a construction area. Lights on plant shall operate continuously while the plant is working alongside sections of road open to public traffic

All LDV's and cars operating on site shall also be equipped with rotating amber flashing lights which shall be placed so as to be highly visible and operated continuously while the vehicles are maneuvering in or out of traffic or are travelling or parked alongside roads open to public traffic.

Rotating lights and the "construction vehicle" signs on the Contractor's vehicles and plant shall not be paid for separately but shall be included in the rates covering the use of the vehicles.

The Contractor shall apply and maintain lights together with temporary mounting brackets, to the approval of the Employers Agent. Vehicles and plant that do not comply with these requirements shall be removed from the site.

It shall be a requirement that the Contractor also provides the Employers Agent's site personnel with warning lights for their vehicles (a maximum of four lights are required) without any additional payment.

(ii) Sign mounted flashing lights

Two amber flashing lights shall be vertically mounted on top of the traffic signs at each end of each traffic accommodation section as shown on the drawings. The lights shall be operated during the hours of darkness.

ADD THE FOLLOWING SUB-CLAUSES:

“(g) Safety jackets

The contractor shall ensure that all his personnel, excluding those who are permanently office bound, are equipped with reflective safety jackets and that these are worn at all times when working on or near to the travelled way. Any person found not wearing a reflective jacket under these circumstances shall be removed from the site until such time as he is in possession of and wearing a reflective jacket.

Reflective safety jackets shall be kept in good condition and any jackets that are, in the opinion of the engineer, ineffective shall be replaced immediately by the contractor.

(h) Other traffic control measures ordered by the Employers Agent

The Employers Agent may instruct the Contractor to provide any other road sign, reflective tape, etc. not measured in standard pay items. Such road signs shall conform to the requirements of the SARTSM, or specification provided by the Employers Agent. Similarly, in order to ensure that the travelling public is kept fully informed and warned on matters relating to the accommodation of traffic, construction sign posting and the effect of the construction on the free flow of traffic through the site, the Employers Agent may arrange for advertising in the press and/or for other forms of publicity.

(i) Flagmen

Flagmen shall be provided where shown on the drawings or required by the specification and payment will be included in the monthly cost for accommodation of traffic. Payment for flagmen will only be done if instructed by the Employers Agent.

Flagmen shall be adequately trained in the standard flagging techniques as described in the SARTSM – Vol 2 (May 2012) (refer to figure 13.23 of detail 13.23.1) and be provided with conspicuous clothing such as safety jackets utilizing retro-reflective and / or fluorescent panels in red, yellow and / or white.

Flagmen shall have in their possession, at all times, certification that they have attended and passed an accredited course in flagging techniques before being allowed onto the construction site.

Flags shall be made from bright red or red-orange material and shall be square with a minimum side length of 600mm. The flag shall be attached to a staff at least 1,0m in length.

In terms of lateral clearance and safety, flagmen shall stand on the shoulder of the lane of traffic that is being controlled and under no circumstances shall flagmen be permitted to stand within the traffic lane. In order to obtain maximum visual impact for the travelling public, flagmen shall stand-alone."

BA1.5.7.10 WIDTH AND LENGTH OF TEMPORARY DEVIATIONS

REPLACE THE CONTENTS OF THIS CLAUSE WITH THE FOLLOWING:

"The effective carriageway width for any two-way traffic accommodated on an existing bituminous surfaced road shall not be less than 6,8 m. No single lane shall be less than 3,4 m wide.

Where the traffic is accommodated in half-widths, the effective lane width for one-way traffic shall not be less than 3,4 m."

B A1.5.7.10 TEMPORARY DRAINAGE WORKS

ADD THE FOLLOWING TO THE LAST PARAGRAPH:

"The construction of temporary culverts shall be in accordance with section 2200. Temporary culverts no longer required shall be removed as directed by the engineer. Excavations shall be backfilled with suitable granular material and compacted to the densities specified by the engineer."

B A1.5.7.10(b) TEMPORARY DRAINAGE WORKS

ADD THE FOLLOWING TO THE LAST PARAGRAPH:

"The construction of temporary culverts shall be in accordance with section 2200. Temporary culverts no longer required shall be removed as directed by the Employers Agent. Excavations shall be backfilled with suitable granular material and compacted to the densities specified by the Employers Agent."

B A1.5.7.10(e) GRAVELLING OF TEMPORARY DEVIATIONS OR OF EXISTING ROADS USED AS TEMPORARY DEVIATIONS

ADD THE FOLLOWING TO THE SECOND PARAGRAPH:

"The gravel material laid on existing roads used as diversions shall comply with the following:

Maximum size	: 37,5 mm
Oversize index (Io)	: 0 (% retained on 37,5 mm sieve)
Shrinkage products (Sp)	: 100 - 240 (linear shrinkage x % passing 0,425 mm sieve)
Grading coefficient (Gc)	: 16 - 34 [(% passing 26,5 mm - % passing 2,0 mm) x % passing 4,75 mm/100]
CBR	: ≥ 15 at 93% of modified AASHTO density."

BA1.5.7.6 EXISTING ROADS USED AS DIVERSIONS

ADD THE FOLLOWING:

"The Contractor shall indemnify the employer against all proceedings, claims, actions, damages and costs which may arise from or be related to damage to vehicles or property or injury to persons as a result of loose stones or aggregates on the road surface or as a result of bituminous applications during the construction of the works.

The Contractor shall arrange his activities so that construction traffic and equipment do not unnecessarily obstruct public traffic or force it to a complete standstill. The flow of public traffic shall always take precedence and the Contractor shall not stop or delay public traffic to make way for construction traffic."

BA1.5.7.11 ACCOMMODATION OF TRAFFIC WHERE THE ROAD IS CONSTRUCTED IN HALF-WIDTHS

ADD TO THE FIRST PARAGRAPH:

"Sections where road marking has not been done shall be regarded as being under construction and not fully opened."

DELETE THE FOURTH PARAGRAPH STARTING WITH: "The number of sections..."

ADD THE FOLLOWING AS A FINAL PARAGRAPH TO THIS CLAUSE:

"The Contractor shall programme the works in such a way to maintain two-way traffic within the contract limits during the Contractor's annual shutdown period between December and January. The Contractor shall further ensure that there is no vertical step between two opposing traffic lanes. Failure to comply with these specifications will entitle the Employers Agent to apply a lane occupation levy."

ADD THE FOLLOWING CLAUSE:

"B A1.5.7.10(g) RETRO-REFLECTIVE MATERIAL

"Retro-reflective material for temporary signs shall comply with the requirements of SABS 1519-1 for weathered material. Tests shall be carried out with a field retro-

reflectometer and the testing procedure and classification are described in clause B8118. The value of the coefficient of Retro-Reflection shall be at least 60% of the values indicated in table B8118/1.

B1519 ACCOMMODATION OF PEDESTRIAN TRAFFIC

The Contractor shall pay specific attention to the accommodation of pedestrian traffic along the cross roads where the safety of pedestrians could be compromised as a result of the works.

Where pedestrians have to cross the site, the Contractor shall ensure that the pedestrians are safeguarded and shall be able to cross the site without being endangered. The pedestrians should not be able to enter areas where works are taking place.

Should a walkway be required, it shall have a clear opening of at least 1,2 m wide and 2,1 m high and shall be uniformly illuminated at all times. The surface of the walkway shall be free from obstructions and shall be clearly signposted to guide the pedestrians towards the walkway. If steps are required to reach the level of the walkway, these shall comply with the OHS act and have proper handrails. No ramps shall be steeper than 1 in 8.

Payment for compliance to this requirement shall be deemed to be included in the rates tendered for accommodation of traffic."

PART C MEASUREMENT AND PAYMENT

INSERT THE FOLLOWING PARAGRAPH AFTER THE HEADING:

"The Contractor's tendered rates for the relevant items in the schedule of quantities shall include full compensation for all possible additional costs which may arise from the above and no claims for extra payment due to inconvenience as a result of the *modus operandi* will be considered."

REPLACE ITEM 15.01 WITH THE FOLLOWING:

"Item	Unit
BC 1.5.13	Accommodating traffic and maintaining temporary
deviations.....	month
(Month)	

The unit of measurement shall be the month measured as per item 13.01(c).

The tendered rate shall include full compensation for the general obligations and incidental cost-items necessary for the accommodation of traffic and the construction and maintenance of diversions, including roads constructed in half widths and existing roads that are being used as diversions, during the construction period and during the maintenance period where such items of cost are not specially paid for under the pay items provided under this section in the Schedule of Quantities. It shall also include full compensation for the provision of all equipment, including tools, transport, labour, supervision, guards, and temporary traffic aids, including all relocation and re erection as may be required for the execution of all the works (including moving and re-erecting temporary plastic New Jersey Barriers), required for the proper and safe accommodation of traffic as specified and as shown on the drawings. It shall also include, where necessary, communications equipment required to regulate traffic, for the provision and maintenance of temporary drainage, arranging for the moving of services, attending to traffic problems, complying with the requirements of the Road Signs Manual, and for providing temporary access to private properties.

The tendered rate shall also include full compensation for flagmen as required in accordance with the drawings.

The provision of temporary traffic control facilities including all road signs will be measured and paid for under Item B15.03. The tendered rate shall include the re use of the signs for

all the closures at any locations and full maintenance including the replacement of damaged signs.

The tendered rate shall also include the provision of a full-time traffic safety officer, assistants, special vehicles for 24 hour maintenance, inspection, dealing with all accommodation of traffic related issues including and reporting of accidents."

BC 1.5.4 Earthworks for temporary deviations

ADD THE FOLLOWING:

"Payment under this item will only be applicable to temporary deviations for the accommodation of traffic and will not be used for frontage/service roads used for the accommodation of traffic. Payment for frontage/service roads used for the accommodation of traffic will be made under section 3300."

BC 1.5.7 Temporary traffic control facilities

(a) Flagmen

Replace the 1st paragraph of the payment description to the following:

"The unit of measurement shall be a full day and night worked by flagmen **only when instructed by the Employers Agent**. A man-day shall be deemed to comprise of a number of shifts within a twenty four hour period. Shifts of 12 hours and less shall be measured as half of a man-day."

Add the following to the measurement sub-paragraph "(a) Flagmen":

"For this contract the cost for providing flagmen for traffic accommodation as indicated on the drawings shall be deemed to be included in the tendered rates under item B15.01. Payment under item B15.03(a) will be made only in instances where, **upon an instruction by the Employers Agent**, additional flagmen are to be provided.

Payment for flagmen who assist with the safe entry and exit of the Contractor's vehicles from closures or turning points, or guiding the traffic around the Contractor's plant will be deemed to be included in the Contractor's Safe Work Procedure and shall not be claimed under item B15.03 (a)."

REPLACE THE DESCRIPTION OF SUBITEMS (g) AND (h) WITH THE FOLLOWING:

- "(g) Rectangular Road signs, TGS-, TIN-, and TW-series
(Excluding TW-series delineators and
barricades).....square metre (m²)
- (h) Delineators TW401/TW402
(250 mm x 1 000 mm sides):
(i) Single (size indicated) number (No)
(ii) Double sided blade (size indicated) number (No)

ADD THE FOLLOWING NEW SUB-ITEM:

- "(n) Other traffic control measures ordered by the Employers Agent
(i) Provision of other traffic control measures provisional (Prov) sum
(ii) Handling costs and profit in respect of sub-item B15.03(n)(i) percentage (%)

Expenditure under this payment item, (e.g., media releases or other signs to deliver information to the public shall be made in accordance with sub-clause 6.6 of General Conditions of Contract for the supply and installation of any additional signs or other traffic control measure ordered by the Employers Agent in accordance with clause B1503(g).

The tendered percentage is a percentage of the actual amount spent under subitem B15.03(n)(i), which shall include full compensation for the handling costs of the Contractor, and the profit in connection with providing other signs and traffic control measures ordered by the Employers Agent."

Under heading "General", make the following amendment:

Insert "Only items additional to those shown on the drawings are scheduled for payment" after "site" in the fourth last line of this paragraph.

At the end of the item under the heading "General" the last sentence shall be replaced by the following:

"Facilities which are stolen or become unserviceable, in particular delineators, shall be replaced promptly at no additional cost. All signs not in their correct position for whatever reason shall be noted and reported to the Employers Agent daily as part of the Traffic Safety Officer's duties. In this event, the fixed penalty of R5 000 shall not be deducted but the time-related penalty of R500 per hour shall remain applicable as per B1502(k)."

Delete payment items 15.08 and 15.09 as maintenance of the road and/or bypasses are paid under Section 3900

Add the following paragraph to pay item B15.03(l) payment description:

"The barriers shall be placed at the traffic control facilities to manage traffic and also alongside the work area as instructed by the Employers Agent."

Item

BC1.5.12 Gravelling and repair of temporary deviations and existing gravel roads used as temporary deviations:

ADD THE FOLLOWING:

"Payment under this item will only be applicable to temporary deviations for the accommodation of traffic and will not be used for frontage/service roads used for the accommodation of traffic. Payment for gravelling of frontage/service roads used for the accommodation of traffic will be made under section 3400."

REPLACE ITEM 15.10 WITH THE FOLLOWING:

"Item

Unit

BC1.5.13 Accommodation of traffic where the road is constructed in half-widths.....kilometre (km)

The unit of measurement shall be the kilometre measured along the centre line of the roads to be constructed, upgraded or rehabilitated in half-widths as directed by the engineer.

The accommodation of traffic in half-widths shall be measured once only along the centre line of the road, irrespective of the number of times necessary to accommodate traffic over any particular part of the road.

This also applies to cases where the traffic is initially accommodated on one half of the road and later on the other half. The limits for any particular part of road on which traffic has to be accommodated in half-widths shall be the distance measured between the beginning and end of the particular work area and not between the two furthestmost temporary road signs on either side of the particular section of road under construction.

The tendered rate shall include full compensation for providing all Constructional Plant, equipment, tools, transport, labour, supervision, guards and all other incidentals necessary

for the proper and safe handling of traffic as specified, for all additional costs and work resulting from accommodating the traffic in half-widths, and for dismantling, storing and if necessary re-using, moving, transporting and re-erecting temporary road signs, barricades and all other traffic-control facilities necessary to accommodate traffic in half-widths, irrespective of the number of times necessary to move such traffic-control facilities.

Payment will be made in three instalments as follows:

- (a) The first instalment, 25% of the length of road where the traffic is accommodated in half-widths, will be paid after the contractor has met all his obligations regarding the widening of the shoulder or any phased construction for the accommodation of traffic.
- (b) The second instalment, 35% of the length of road where the traffic is accommodated in half-widths, will be paid after the contractor has met all his obligations regarding the construction of the one half of the road complete to final road levels, excluding the second application of slurry.
- (c) The third and final instalment, 40% of the length of road where the traffic is accommodated in half-widths, will be paid after the contractor has met all his obligations regarding the construction of the remainder of the road complete to final road levels, including the second application of slurry to the first half.

Payment for the provision of temporary traffic-control facilities shall be made under item B15.03 and shall be paid for once only, irrespective of the type of work to be executed or the number of times that the temporary traffic-control facilities have to be moved and re-used."

ADD THE FOLLOWING NEW ITEMS:

"Item	Unit
-------	------

BC1.5.13. Provision of traffic safety equipment for visitors

- | | | |
|-----|---|--|
| (a) | Emergency rotating mini light bar for mobile use..... | |
| | number (No) | |
| (b) | 'Construction' sticker for vehicles with 100 mm high lettering..... | |
| | number (No) | |
| (c) | Safety jackets | |
| | number (No) | |

The unit of measurement shall be the number of each item provided as specified, and approved by the Employers Agent.

The tendered rates for the various safety items shall include full compensation for provision thereof and maintenance in good working order."

Item	Unit
------	------

BC1.5.13 Media releases and public relations:

- | | | |
|-----|--|---------------------|
| (a) | Media releases and public relations | Prime Cost (PC) Sum |
| (b) | Handling costs and profit in respect of
subitem B15.15(a) | percentage (%) |

The prime cost sum is provided to cover costs related to media releases and public notices as instructed by the Employers Agent."

CHAPTER 1 :1.7 LOADING AND HAULING

A1.7.2 DEFINITIONS

(a) Overhaul material

ADD THE FOLLOWING TO SUBCLAUSE (i):

"Overhaul material shall also include the following:

Any material, irrespective of type which is removed from existing pavements and spoiled, or which is hauled direct to other parts of the site or to approved stockpiles or from stockpiles to a working area."

REPLACE THE LAST PARAGRAPH WITH THE FOLLOWING:

"No overhaul shall apply to materials from commercial sources. The contractor's tendered rates for all materials from commercial sources shall be deemed to include full compensation for hauling the materials to its point of use on the site."

b) Overhaul

ADD THE FOLLOWING PARAGRAPHS:

"All haul within the boundaries of the site will be regarded as free haul, and no payment will be made for overhaul on this contract unless provision is made therefore in specific items. Payment for overhaul will only be considered for material disposed of, or hauled beyond the limits of the site, in which case a free-haul distance of 1,0km measured from the site boundaries will be applicable and shall be measured as the product of the volume of material hauled and the overhauled distance.

No overhaul will be payable for materials imported from commercial sources and from designated borrow pits alongside the road."

A1.7.3.1 MEASUREMENT AND PAYMENT

DELETE "(restricted overhaul) "FROM PAYMENT ITEM B16.01

CHAPTER 1 :1.6 CLEARING AND GRUBBING

BA1.6.1 SCOPE

ADD THE FOLLOWING AFTER "grubbing" IN THE FIRST PARAGRAPH:

"Including the demolishing and disposal of structures, shelters, dwellings and out-buildings within the new road reserve".

ADD THE FOLLOWING AS A FINAL PARAGRAPH:

"Clearing and grubbing for the construction of site offices shall not be measured separately and shall be deemed to be included in the rates tendered for item B13.01."

BA1.6.2 DEFINITION

(c) Conservation of topsoil

ADD TO THE END OF THE 1ST PARAGRAPH:

"The depth of topsoil removed shall be reliant on the terrain, suitability of material and topsoil requirements of the work. Generally, the Contractor will not be required to remove topsoil to more than an average depth of 250mm unless approved by the Employers Agent before commencing with topsoil removal from any particular area."

REPLACE THE SECOND PARAGRAPH OF THIS CLAUSE WITH THE FOLLOWING:

"After clearing and grubbing, all topsoil shall be removed to either windrows alongside the construction area or to stockpile. Where ordered by the Employers Agent, any topsoil that shall be required for the topsoiling of new banks and cuts, but which cannot be accommodated within the construction site, shall be loaded and hauled to the designated stockpile area where it shall be placed in temporary stockpiles for later use in the rehabilitation of the site affected by construction activities. Where new borrow pits are to be opened up the topsoil shall first be removed (independently of the overburden) and placed in temporary stockpiles at the edge of the borrow pit. The moving of topsoil from windrow or the loading of topsoil from temporary stockpiles and the placing and spreading thereof on cut or fill slopes or on borrow pit spoil sites, is covered in Section 5800."

PART C MEASUREMENT AND PAYMENT

Item

BC1.6.1 Clearing and grubbing

REPLACE THE LAST PARAGRAPH WITH THE FOLLOWING:

"The tendered rates shall include full compensation for all work necessary for the clearing and grubbing of the surface, the demolishing and disposal of structures, shelters, dwellings and out-buildings, the removal of all vegetation, shrubs, trees and tree stumps (except large trees and stumps as defined in item 17.02), cutting of branches, backfilling of cavities, the removal, transporting (including all haul) and disposal of material at approved dumping sites provided by the contractor, and all additional costs incurred to clear and grub the surfaces to the Employers Agent's satisfaction."

ADD THE FOLLOWING PAYMENT ITEM:

"Item

Unit

BC1.6.9.1 Temporary stockpiling or blading to windrow of topsoil:

- (a) Blading to windrow alongside the areas demarcated for side drain

excavation..... cubic
metre (m³)

- (b) In temporary stockpiles after loading material into trucks including 2,0km
free haul cubic
metre (m³)

The unit of measurement shall be the cubic metre of topsoil bladed to windrow or temporarily stockpiled. The volume of topsoil shall be measured in cut, calculated from the difference in cross-sections of the natural ground level before the commencement of clearing to cross-sections taken after the removal of the topsoil.

The Contractor shall constantly liaise and agree with the Employers Agent as to the depth of topsoil to be removed. Where, in the opinion of the Employers Agent, material that would normally be classed as in-situ material has also been excavated, the excavation shall be backfilled and compacted with selected material at the Contractor' expense. Should material that is deemed by the Employers Agent not to be topsoil, be removed and stockpiled together with material classed as topsoil, the Contractor shall be responsible for the removal of this unsuitable soil from the stockpile and the replacement of the quantity of topsoil contaminated by the unsuitable material at his cost. The quantity of topsoil to be replaced shall be determined by the Employers Agent.

The rates tendered shall include for the excavation of the topsoil and blading to windrow or where required, the loading and hauling thereof to temporary stockpile as well as the maintenance of the stockpile until re-use of the material. The rates tendered shall also include for all supervision required to ensure that only topsoil is removed."

BC 1.6.10 Demolition, removal and disposal off site of miscellaneous structures consisting of:

- (a) Unreinforced concrete cubic metre (m³)
(b) Reinforced concrete cubic metre (m³)

The unit of measurement shall be the cubic metre of concrete removed from each structure in the road reserve as instructed by the Employers Agent.

The tendered cubic meter rate for each structure shall include full compensation for the complete demolition of the structure (including foundations to 0,5 m below natural ground level) and the transportation (including all haul) and disposal of all debris at approved dumping sites provided by the contractor.

SECTION B 1800: DAYWORKS

ADD THE FOLLOWING NEW SECTION

BC1.2.1 SCOPE

This section covers the listing of day work items in accordance with the Conditions of Contract, determining payment for work which cannot be quantified in specific units in the bill/schedule of quantities/pricing schedule, or for work ordered by the Employers Agent during the construction period which was not foreseen at tender stage and for which no applicable rate exists in the bill/schedule of quantities/pricing schedule.

BC1.2.1 ORDERING OF DAYWORK

No day works shall be undertaken unless written authorization has been obtained from the Employers Agent.

BC1.2.1 MEASUREMENT AND PAYMENT

Item	Unit
-------------	-------------

BC1.2.8 Personnel during normal working hours:

- | | |
|-------------------------------|----------|
| (a) Unskilled labour | hour (h) |
| (b) Semi-skilled labour | hour (h) |
| (c) Skilled labour | hour (h) |
| (d) Ganger | hour (h) |

Item	Unit
-------------	-------------

BC1.2.8.2 Personnel outside normal working hours:**(a) Outside normal working hours and on Saturdays:**

- | | |
|--------------------------------|----------|
| (i) Unskilled labour | hour (h) |
| (ii) Semi-skilled labour | hour (h) |
| (iii) Skilled labour | hour (h) |
| (iv) Ganger | hour (h) |

(b) Sundays and public holidays:

- | | |
|--------------------------------|----------|
| (i) Unskilled labour | hour (h) |
| (ii) Semi-skilled labour | hour (h) |
| (iii) Skilled labour | hour (h) |
| (iv) Ganger | hour (h) |

Item	Unit
-------------	-------------

BC1.2.8.2 Equipment/Plant:

- | | |
|--|----------|
| (a) LTB | hour (h) |
| (b) Tipper truck 6m3 | hour (h) |
| (c) Grader (111.9 kilowatts or equivalent) | hour (h) |
| (d) Compressor and 2 jack hammers | hour (h) |
| (e) Excavator (25 TON) | hour (h) |
| (f) Front-end loader | hour (h) |

- (g) Vibrating pedestrian roller (Bomag 60).....hour
(h)

Item	Unit
-------------	-------------

BC1.2.8.4 Materials:

- | | | |
|--|----------------|-----|
| (a) Procurement of materials..... | Provisional | sum |
| (Prov sum) | | |
| (b) Contractor's handling costs, profit and all other charges in respect of sub item B18.04(a) | percentage (%) | |

Item	Unit
-------------	-------------

BC 1.2.8.3 Transport:

- | | |
|--------------------------------------|----------------|
| (a) LDV | kilometre (km) |
| (b) Flatbed truck (min 5 tonne)..... | kilometre (km) |

The unit of measurement for items B18.01 and B18.02 shall be the hour for the item of equipment/plant or personnel. Non-working hours for transport breakdown, lack of operator or any other reason shall not be measured. The time shall be taken from the time that the personnel and/or plant/equipment depart until return.

Measurement shall only be for work instructed and directed by the Employers Agent, where the Employers Agent considers no other appropriate rate is available in the bill/schedule of quantities/ pricing schedule. Prior to the commencement of any work by the personnel described under items B18.01 and B18.02, the Contractor must obtain written consent from the Employers Agent regarding the classification of all labourers in terms of 'unskilled', 'semi-skilled' and 'skilled' personnel.

The tendered rates for labour for items B18.01 and B18.02 shall include full compensation to cover overhead charges and profit, leave pay, bonuses, subsistence, allowances, employer's contributions, additional payment for overtime where applicable, insurances, housing, site supervision, use of small hand tools and appliances, non-mechanical plant and equipment and consumable stores and for all administrative, supervisory, operative and contingent costs relating to the supply of personnel.

The tendered rates for plant for item B18.03 shall be an all-inclusive hire charge for the use of the vehicle and driver or plant/equipment and operator and shall apply only to vehicles, plant and equipment nominated in writing by the Employers Agent, for all administrative, supervisory, operative and contingent cost and profit relating to the running of the Plant.

The unit of measurement for sub item B18.04(a) shall be the amounts actually paid for the procurement of materials to be purchased and shall be made in accordance with the provision of the Conditions of Contract. Only the actual quantities of materials used, as verified by the Employers Agent, shall be paid for.

The percentage tendered for sub item B18.04(b) shall be the percentage of the amounts actually paid for the procurement of materials as ordered under sub item B18.04(a) and shall be in full and final compensation in respect of the Contractor's handling costs, profit and all other charges in connection with the procurement and supply of the materials to the point of usage.

The unit of measurement for item B18.05 shall be the kilometre distance that the vehicle travelled for transporting personnel and/or plant. All travelling shall be approved by the Employers Agent.

The tendered rate for item B18.05 shall include full compensation for the cost of the vehicle including fuel, maintenance, depreciation and running costs.

The above-mentioned tendered rates shall be in full compensation for the various items as specified and no further profit shall be paid.”

COTO SERIES CHAPTER 3: DRAINAGE**SECTION B 2100 1.3 DRAINS****BC3.1.1 SCOPE**

AMEND THE FIRST PARAGRAPH TO READ:

"This section covers all work both rehabilitative and new work in connection with the excavation and construction of open drains, subsoil drainage and banks and dykes at the locations and to the sizes, shapes, grades and dimensions as shown on the drawings or as directed by the Employers Agents, and the test flushing of subsoil drains."

AMEND THE FIRST PARAGRAPH TO READ:

"This section covers all work both rehabilitative and new work in connection with the excavation and construction of open drains, subsoil drainage, banks and dykes at the locations and to the sizes, shapes, grades and dimensions as shown on the drawings or as directed by the Employers Agent, and the test flushing of subsoil drains."

BA3.1.5.2 SUBSOIL DRAINAGE**(a) Materials****(i) Pipes**

AMEND THIS SUBCLAUSE BY ADDING THE FOLLOWING TO THE END OF THE THIRD PARAGRAPH:

"(category - heavy duty) or SABS 1601 (stiffness class 350)

The pipes to be used shall be either slotted uPVC pipes or perforated HDP pressure pipes, 100 mm ID."

(ii) Natural permeable material

ADD THE FOLLOWING TO THE 3rd PARAGRAPH:

"The crushed stone shall be coarse (19 mm nominal) and shall be washed clean of all fines."

REPLACE THIS SUBSUBCLAUSE WITH THE FOLLOWING:

(iii) Synthetic-fibre filter fabric**(1) Composition and manufacturing**

The geotextile shall be a synthetic polymer material manufactured in a continuous permeable homogeneous sheet (in rolls) by one of the following methods:

- Non-woven, mechanically bonded (continuous fibre spunbonded, needle-punched)

The synthetic material polymer shall be one or more of the following:

- Polyester
- Polypropylene
- Polyethylene

On account of the temperature and moisture susceptibility of polyamide, this synthetic product is not considered acceptable.

(2) Classification

Geotextiles shall be classified into the following main grades according to typical usage.

- Grade 1: Very good installation conditions, e.g., subsurface drains with relatively smooth trench walls, small to medium size filter stone (9,5 mm to 19 mm) dumped from the edge of a shallow drain, and where careful handling of the geotextile is expected.
- Grade 2: Normal installation conditions, not as good as grade 1, e.g., larger subsurface drains with rough trench walls, large size filter stone (37,5 mm) dumped from a height onto the geotextile-lined drain, and where normal handling of geotextile is expected.
- Grade 3: Adverse conditions, e.g., foundation drainage, gabions and gabion mattresses, light rock protection, rock fills and light separation of materials, separation and reinforcement of fill layers, light river protection works, and where rough handling of the geotextile is expected.
- Grade 4: Adverse conditions where strength is more important than permeability, e.g., foundation drainage, gabions and gabion mattresses, rock protection, earth encapsulation, separation, and reinforcement of fill and rockfill layers, heavier river protection works, and where rough handling of the geotextile is expected.
- Grade 5: As for grade 4, but where additional strength is required, e.g., in heavy separation, earth and rock encapsulation, river protection works, and shore revetment works.
- Grade 6: As for grade 5 but where maximum strength is required and where permeability will be relatively unimportant.

The minimum requirements for each grade are listed below in table B2104/2. Under normal circumstances grades 1, 2, 3, 4 and 5 will be specified while grade 6 will be specified in special cases where maximum strength is required by special design considerations.

The various grades and the corresponding typical usage above shall be regarded as a guideline only. The actual grade of geotextile to be used on the work will be as stated in the bill/schedule of quantities/pricing schedule as required by the Employers Agent.

(3) Durability

A geotextile is required to comply with the following specifications:

- Resistance to chemical attack
- The geotextile shall withstand the level of aggressiveness of the soil and ground water given below without significant loss of its strength and hydraulic properties during its design life of 25 years:

Soil and ground water with a pH in the range of 4 to 12 (pH to be determined by Method A20, TMH1, 1986).

Soil (as paste) and ground water containing salts with a conductance of up to 1,0 S/m (conductivity to be determined by Method A21T, TMH1, 1986).

- Resistance to ultra-violet light

The geotextile shall maintain at least 80% of its original strength after direct exposure to sunlight of 1 500 hours.

- Resistance to rot

The geotextile shall be entirely rot-proof and shall not support the growth of algae, bacteria or fungi.

(4) Selection

The geotextile required shall satisfy the criteria for the grade of geotextile as specified in the bill/schedule of quantities/pricing schedule or project specifications.

The contractor shall, at least 45 days before the installation of the geotextile, submit to the Employers Agent samples of the geotextile he proposes to use, so that the Employers Agent may carry out the appropriate tests specified in subclause B2104(a)(iii)(6) and in clause 8114, and confirm the use thereof if he is satisfied that the geotextile meets the specified requirements. No extra payment shall be made for providing the samples for testing.

(5) Properties

The various grades of geotextile as classified above shall comply with the general requirements as listed below in table B2104/2.

TABLE B2104/2: GRADES OF GEOTEXTILES

Properties	Limiting values*					
	Grade 1	Grade 2	Grade 3	Grade 4	Grade 5	Grade 6
Thickness	As specified by the manufacturer					
Mass per unit area g/m ²	100	140	200	240	300	350
Tensile strength kN/m	6	10	13	18	25	30
Penetration load kN	1,0	1,5	2,5	3,0	4,0	5,0
Penetration resistance* (max) mm	35	30	25	18	16	10
Permeability litre/s/m ²	25	20	15	15	10	5

*Notes:

- *(1) The minimum values of properties are listed, except for penetration resistance where the maximum values are given.
- (2) Thickness shall be as specified by the manufacturer for the specific product offered.
- (3) The values given in the table shall apply to all geotextiles, irrespective of the type of material used. Where these values differ from the values in Table 1 of the Code of Practice SANS 10221: The Testing of Geotextiles, the values of Table B2104/2 shall apply.

(6) Testing

The tests to be carried out on geotextiles relate to the material and the method of manufacture and are used mainly to ascertain that the correct grade of geotextile is supplied, and that the material is equivalent in quality to that selected and specified for use on the works. The contractor shall, on instruction of the Employers Agent, submit a certificate by an approved laboratory to prove compliance with the specified qualities without additional cost to the employer.

Thickness (mm): The thickness of the material shall be specified by the contractor (or supplier). Thickness and compressibility tests shall be carried out in accordance with SANS 10221 to check that the material supplied conforms to the thickness specified by the contractor.

Mass per unit area (g/m²): Testing shall be carried out in accordance with SANS 10221.

Tensile strength (kN/m): Testing shall be carried out in accordance with SANS 10221.

Penetration load (kN): Testing shall be carried out in accordance with SANS 10221.

Puncture resistance (mm): Testing shall be done in accordance with test procedures laid down by the CSIR, Pretoria, and repeated in Clause 8114.

Permeability (litre/s/m²): Testing shall be carried out in accordance with SANS 10221."

(vi) Galvanized woven wire mesh

REPLACE THE CONTENTS OF THIS SUBSUBCLAUSE WITH THE FOLLOWING:

"Galvanized woven wire mesh manufactured from 3,5 mm diameter wire, 250 mm x 250 mm in area with 12 mm x 12 mm maximum mesh size, and fitted with a frame made from 25 mm x 5 mm galvanized flat steel, shall be secured at the outlets of subsoil drainage systems with 4 x M6 galvanized bolts, in accordance with the details on the drawings. The mesh shall be welded to the frame before the whole unit is galvanized."

(c) Construction of subsoil drainage system

ADD THE FOLLOWING SUBCLAUSE:

"(v) Proving of pipes in subsoil drainage systems

On completion of the pipe laying and prior to backfilling, all pipe joints shall be surveyed as proof of their installation to line and level. After backfilling the pipes shall be proved by pulling through a cylindrical cleaning brush followed by a wooden mandrill $\pm$ 400 mm long and 5 mm in diameter less than the bore of the pipe. Proving of pipes shall not be paid for separately and the cost thereof shall be deemed to be included in the rate tendered for laying the pipe."

REPLACE THE HEADING OF CLAUSE 2106 WITH THE FOLLOWING:

"BA3.1.7.5 MANHOLES, OUTLET STRUCTURES, JUNCTION BOXES AND CLEANING EYES"

INSERT ", junction boxes" AFTER "manholes" IN THE FIRST LINE.

PART C MEASUREMENT AND PAYMENT

Item

BC3.1.1 Excavation for open drains:

ADD THE FOLLOWING TO THE PENULTIMATE PARAGRAPH:

"The tendered rate shall also include full compensation for trimming the open drains."

ADD "subclause B1231(c) and in" AFTER "in" IN THE LAST LINE OF THE LAST PARAGRAPH.

**"Item
Unit**

BC3.1.2 Excavation for subsoil drainage systems:

ADD THE FOLLOWING SUBITEM:

"(c) Extra over subitem B21.03(a) for excavating
through stabilized layers of existing pavement..... cubic metre (m³)"

ADD "Subclause B1231(c) and in" AFTER "in" IN THE SIXTH LINE OF THE SECOND PARAGRAPH.

ADD THE FOLLOWING TO THE SECOND PARAGRAPH:

"Excavation in stabilized pavement material shall be paid only in subitem (c) and shall not be paid as an extra over for hard material in subitem (b). For subitem (c), the tendered rate shall also include full compensation for backfill with soilcrete."

REPLACE ITEM 21.04 WITH THE FOLLOWING:

"Item

Unit

BC3.1.5 Impermeable backfilling to subsoil drainage systems:

- (a) Using the excavated material cubic metre (m³)
- (b) Using imported selected material cubic metre (m³)
- (c) Extra over subitems B21.04(a) and (b) for
soil cement (soilcrete) backfilling (percentage
of cement indicated) cubic metre (m³)

The unit of measurement shall be the cubic metre of completed backfill, measured in place in the subsoil drainage systems and calculated in accordance with the authorized dimensions.

If excavations are carried out in excess of the dimensions authorized by the Employers Agent, the quantity of backfilling will nevertheless be based on authorized dimensions.

The tendered rates shall include full compensation for procuring, furnishing, transporting, placing and compacting the backfilling to 90% of modified AASHTO density. The tendered rate for subitem B21.04(b) shall, in addition, include full compensation for supplying selected material from approved sources, including a free haul of 1,0 km.

The tendered rate for subitem B21.04(c) shall be additional to the rates tendered for subitems B21.04(a) and (b) and shall include full compensation for all incidentals required for the complete backfilling with soil cement as specified by the Employers Agent."

Item

BC3.1.13 Concrete outlet structures, manhole boxes, junction boxes and cleaning eyes for subsoil drainage systems

ADD THE FOLLOWING TO THE PAYMENT PARAGRAPH:

"The tendered rate shall also include full compensation for procuring and finishing the galvanized woven wire mesh, cutting, waste, installing the wire mesh at outlets and keeping the wire mesh in the pipe openings clean for the duration of the contract period."

ADD THE FOLLOWING ITEMS:

"Item

Unit

CHAPTER 3: PREFABRICATED CULVERTS

BA3.2.1 SCOPE

ADD THE FOLLOWING:

"This section also covers work in connection with retaining existing culverts, the extension of existing culverts and the cleaning of the in- and outlets and barrels of existing culverts, as well as the installation of new culverts in existing roads and access roads.

This section also covers the replacing and/or lengthening of existing culverts, modification of and repairs to existing catch pits."

BA3.2.5 MATERIALS

ADD THE FOLLOWING:

"Numbered precast culverts to be constructed in accordance with this section of the specifications are measured and paid for under Schedule B: Structures of the bill of quantities."

b) Portal and rectangular prefabricated concrete culvert units

REPLACE THIS SUB-CLAUSE WITH THE FOLLOWING:

"Precast concrete units shall comply with the requirements of the latest SANS 986:2006 specification.

Prior to the manufacture of any units the manufacturer shall submit his Quality Plan to be approved by the Employers Agent before delivery of any units to site. As part of the Quality Plan submitted for approval copies of calibration certificates of both gauges used for proof loads and cover meters used at the factory shall be supplied to the Employers Agent. The originals of these certificates shall at all stages also be available for inspection at the factory premises. The manufacturer shall check each precast unit for cover compliance, and random checking of units shall not be permitted. The Employers Agent's representative may visit the factory at any stage to ascertain adherence to the quality plan as well as to check covers before delivery to site. Any substandard cover shall result in the batch being rejected. Should the manufacturer not be adhering to their Quality Plan the Employers Agent may exercise the right to reject the use of products from the manufacturer concerned. The Employer shall also be informed in all such cases.

For durability requirements due to the reduced cover provided for pre-cast culverts all durability testing shall be done in accordance with Clause B6404(h) shall fall within the severe category."

ADD THE FOLLOWING SUB-CLAUSE:

"(j) Unplasticised Poly-vinyl chloride pipes (PVC-U)

All PVC-U pressure pipes shall comply with the requirements of SANS 966-1 and PVC-U solid wall sewer pipes shall comply with SANS 791. Pipe ends will be spigot with integral socket and rubber ring seals."

BA3.2.7.1 CONSTRUCTION METHODS

ADD "AND SEQUENCE "TO THE HEADING

REPLACE THE 2ND PARAGRAPH WITH THE FOLLOWING:

"Culverts shall generally be lengthened according to the "embankment method". The Contractor shall at all times ensure that the existing drainage is at all times maintained and

any damage caused as a result of blocked culverts during construction shall be repaired at the Contractor's expense.

New culverts shall generally be constructed according to the "trench method" unless otherwise indicated on the drawings.

The bottom of the excavation for culverts that are to be replaced or lengthened shall be inspected by the Employers Agent prior to the placing of the bedding material. If the material is found to be suitable, it shall be ripped to a depth of 150mm below the bottom of bedding level and re-compacted to at least 93% Mod. AASHTO density.

When instructed by the Employers Agent, measures shall be taken to reduce the effect of unsuitable material at the positions of prefabricated culverts. This will entail the additional excavation of a minimum of 1 m of in-situ material to a minimum width of 4 m, the even chamfering of the sides of the excavation to a grade of 1:4 and backfilling the excavation with imported fill material with at least G10 quality compacted to 90% of modified AASHTO density. Additional excavation as described above will be paid for under item 33.07. Backfilling of the excavation will be measured and paid for under item 33.01."

DELETE THE THIRD PARAGRAPH AND SUBSTITUTE WITH THE FOLLOWING:

"For the purposes of this contract, culverts shall be installed according to the "trench method."

ADD AT THE END:

All pipework and respective backfilling, including ducts and any water pipes laid under this contract, shall be completed and tested and approved, before the commencement of the sub-base layer.

BC3.2.7.2 EXCAVATION FOR CONSTRUCTION BY TRENCH METHOD

(a) Depth of excavation

ADD THE FOLLOWING AFTER THE FIRST SENTENCE OF THE FIRST PARAGRAPH:

"The maximum overall depth of the trench shall, however, not exceed 2,0 m."

ADD THE FOLLOWING SUB-CLAUSE:

"(c) Extension of existing culverts

The requirements of this clause are also applicable to the extension of existing culverts."

BC3.2.7.7 LAYING AND BEDDING OF PREFABRICATED CULVERTS

(a) Concrete pipe culverts

ADD THE FOLLOWING AFTER THE FIRST PARAGRAPH:

"When instructed by the Employers Agent or when measures are required to reduce the effect of unsuitable material below culverts, the pipe joints shall be sealed with a 500 mm wide strip of Bituthene 3000 or an approved equivalent material glued symmetrically around the joint, using an adhesive recommended by the manufacturer of Bituthene. A 150 mm wide strip of adhesive shall be applied to the edges of the Bituthene. An overlap of 150 mm shall be provided and the two layers of Bituthene at the overlap shall be glued together over the full area of 150 mm x 500 mm."

(i) Class A bedding

ADD THE FOLLOWING:

"12 mm thick Flex cell or an approved equivalent material shall be placed in the concrete bedding below all pipe joints."

(b) Portal and rectangular culverts

- (i) Cast in situ floor slabs

ADD THE FOLLOWING:

"Where the bottom of the excavation consists of soft material, suitable for the founding of culverts; such material must be compacted to a minimum of 93% of Mod AASHTO density, to a depth of 150 mm, before the screed and/or cast in situ floor slab is constructed thereon."

- (iii) Placing the portal portions of culverts

ADD THE FOLLOWING:

"When instructed by the Employers Agent or when measures are required to reduce the effect of unsuitable material below culverts, the culvert joints shall be sealed with a 500 mm wide strip of Bituthene 3000 or an approved equivalent material glued symmetrically around the joint, using an adhesive recommended by the manufacturer of Bituthene. A 150 mm wide strip of adhesive shall be applied to the edges of the Bituthene."

(f) General

ADD THE FOLLOWING:

"Where the grade of the culvert is such that it would require a trench deeper than 2,0 m, the culvert shall be constructed in stages as the fill progresses. The construction shall normally begin at the outlet or downstream end of the culvert and backfilling shall be done in horizontal layers starting at the lower end."

No additional payment will be made under section 3300 or under this section for constructing the fill or culverts in stages as described above."

BC3.2.7.10 BACKFILLING OF CULVERTS

Substitute the portion of the second sentence in the ninth paragraph reading: "...approved soil or gravel mixed with 5% of Portland cement..." with the following:

"...approved gravel of G6 or better quality and CEM V S-V 32,5 cement mixed in proportion of 1:12..."

"BC3.2.7.11 INLET AND OUTLET STRUCTURES, CATCHPITS, MANHOLES AND SKEW-END PIECES FOR PORTAL AND RECTANGULAR CULVERTS

Inlet and outlet structures for prefabricated culverts, catchpits, manholes, and skew-end pieces for portal and rectangular culverts shall be constructed in accordance with the details on the drawings."

(i) Prefabricated energy dissipaters in outlet structures

REPLACE THE PARAGRAPH WITH THE FOLLOWING:

"When shown on the drawings or instructed by the Employers Agent, the contractor shall supply and install prefabricated reinforced-concrete blocks in outlet structures. The blocks shall be Class 20/19 concrete manufactured to the dimensions shown on the drawings or listed in the bill/schedule of quantities/pricing schedule. All concrete work shall comply with the requirements of Series 6000."

ADD THE FOLLOWING SUBCLAUSES:

"(j) Prefabricated concrete cover slabs for kerb inlets

Prefabricated reinforced-concrete cover slabs for kerb inlets, complete with steel supporting structures, shall be manufactured and installed in accordance with the details on the drawings. All concrete work shall comply with the requirements of Series 6000.

(k) Building in pipework

Pipework shall be built into concrete as shown on the drawings. The pipework shall be set into exact position in the shutters before the concrete is placed and the concrete thoroughly compacted and worked around the pipework. Alternatively, at the discretion of the Employers Agent and at no extra cost, unless specifically provided for in the bill/schedule of quantities/pricing schedule, holes may be left or formed in the concrete into which the pipework shall be set, whereupon the space around the pipework shall be caulked with concrete having just sufficient water to ensure water tightness and thereafter the caulking shall be properly cured.

The joint between the old and fresh concrete shall be made in accordance with clause 6408: Construction joints.

Where pipes enter brickwork, they shall be caulked into the wall and rendered with mortar.

(l) Manholes for Telkom

Manholes required for Telkom shall be for jointing, pulling or for change of direction and shall be constructed in accordance with the details shown on the drawings. As these manholes generally finish somewhere in the layerworks of the pavement, these layerworks shall first be constructed to the level of the top of the manhole roof slab. Excavation for the manhole shall then be carried out as neatly as possible, the manhole constructed and the minimal backfill space filled with either soil cement for brick walls or combined with the concrete if the walls are concrete. Finally, once all structural concrete has attained its design strength, the overlying layerworks shall be constructed, then the manhole shaft/opening constructed so that the cover is completely flush with the adjacent asphalt surfacing.

The contractor shall allow in his programme for a suitable delay in the layerworks while the various Telkom manholes are being constructed."

(a) Excavation and backfilling

AMEND THE FIRST PARAGRAPH OF CLAUSE 2212(A) TO READ AS FOLLOWS:

"The width of excavation shall be the net external dimensions of structure plus 0,5 metre working space along or around the structure. The specifications given elsewhere in this section for backfilling the culverts shall apply mutatis mutandis to inlet and outlet structures, catchpits and manholes. If wet soilcrete is used with vibrators, the extra working space shall be reduced to 150 mm."

BC3.2.7.14 SERVICE DUCTS SLEEVING OR LINING OF EXISTING CULVERTS

INSERT THE FOLLOWING AT THE END OF THE 1ST PARAGRAPH:

“(v) HDPE Sleeve Pipes

HDPE sleeve pipes shall be:

1. Corrugated cable ducts complying with the requirements of SANS IEC 61386-24: 2005 for sleeves to be laid in trenches.
2. HDPE pipes for drilling shall be manufactured from PE63 – PN4 and shall comply with the requirements of SANS 427."

INSERT THE FOLLOWING AS A NEW 4TH PARAGRAPH

"Where drilling is required for installation of service ducts, a drilling pit shall be excavated on the one side of the road from where drilling is to be conducted. The pit shall be of adequate size to permit free standing of the operator and drilling equipment. On the other side of the road, a receiving pit is to be excavated. Both pits shall be backfilled after completion of the drilling, using the excavated material compacted in 150mm layers to a minimum density of 93% of modified AASHTO. Drilling shall be carried out from the one side of the road in positions and to levels as shown on the drawings and/or as instructed by the Employers Agent. The hole shall be of adequate size to accommodate the required service duct. The permissible deviation in level of the hole between the two sides of the road shall not exceed 500mm. The service duct shall be installed through the drilled hole and shall be extended to above ground."

ADD THE FOLLOWING AT THE END OF THE PENULTIMATE PARAGRAPH

"Before closing, all sleeves or ducts shall be proved as specified in sub-sub-clause B2104(b)(v)."

REPLACE THE LAST PARAGRAPH WITH THE FOLLOWING:

"The end of each duct shall be marked with a 300 mm x 300 mm x 100 mm Class 20/19 concrete marker block. A 200 mm x 100 mm galvanized steel or aluminium plate with the size, number and depth of pipes stamped on the surface shall be affixed to the top of the marker block. Each duct marker shall be at least 50 mm proud of the finished surface level."

ADD THE FOLLOWING TO THE SEVENTH PARAGRAPH:

"The Telkom uPVC ducts for the optical fibre cable are required to be placed in special bedding, padding and backfilling as specified in clause B2219."

ADD THE FOLLOWING NEW CLAUSES:

- (a) This clause specifies the characteristics, testing and installation of bedding, padding and backfilling material for Telkom uPVC ducts.

The following conditions apply:

Bedding: The material constituting the even floor of an excavated trench onto which a pipe or a bank of pipes are laid being either undisturbed in-situ material or an imported layer of suitable material as specified hereinafter.

Padding: The material installed around and/or between pipes up to a level of at least 150 mm above the pipe or bank of pipes: The padding material must be 150 mm below and to the sides of ducts.

Backfilling: The material installed above the padding material layer to complete the refilling of an excavated trench.

- (b) Bedding, padding and backfill material shall be installed with a moisture content as near to optimum as possible to ensure that optimum compaction is achieved. The Employers Agent may, if he considers it necessary, direct the contractor to carry out tests, which the Employers Agent shall specify, to determine the optimum and actual moisture content of any material being used. Should the results of such tests require it, the Employers Agent may direct the contractor to add water to material which is too dry or to dispose of material which is too moist or import suitable material.
- (c) Under no circumstances shall material, which is saturated with water, be used for bedding, padding and backfill.
- (d) The contractor shall pay particular attention to the proper compaction of bedding, padding and backfilling material.

A higher standard of compaction effort will be insisted upon in all cases where fine materials are approved as bedding and padding.

- (e) The bedding shall cover the full width of the trench in a uniform layer of the required thickness and shall be compacted by means of one pass by a vibratory plate compactor.
- (f) Care must be taken to ensure that the ducts are completely surrounded by the padding material.

On completion of the placement of the padding material, the top surface shall be compacted by means of one pass by a vibratory plate compactor.

- (g) The compaction of backfill shall be by means of a vibratory plate compactor.
- (h) During the compaction of padding and backfill material, the contractor shall exercise due care to ensure that pipes and pipe joints are not disturbed or damaged in any way.

The material to be used for the bedding and padding shall be coarse-grade crushed stone as specified in clause 2104(a) of the standard specifications.

ie The crushed stone shall be graded crushed stone conforming to the following grading requirements:

Sieve size	% Passing
26,5 mm sieve	100%
13,2 mm	60 - 85%
6,7 mm	Minimum 15%
2,36 mm	Maximum 15%

Note: The following items will be supplied by Telkom and delivered to site:

- (i) uPVC pipes
- (ii) copper earth conductor wires
- (iii) danger tape conductor

The contractor must inform Telkom at least three weeks before the pipes are required for installation.

- (i) Where directed by the Employers Agent, copper earth conductors shall be installed. Joints in conductors shall be by means of approved clamps.
- (ii) Where indicated on the drawings, ducts shall be protected with precast concrete slabs.

PIPE JACKING

The basis of payment for a jacked pipeline takes cognizance of the fact that, although the Employers Agent may design and specify the pipeline, he cannot provide detailed drawings and dimensions for the jacking structure and its thrust and reception pits, because these depend on equipment and methods that the contractor intends to use for carrying out the work. Therefore, the Employers Agent will require, prior to the commencement of any work, a method statement which will include a schedule of the dimensions of the pits, equipment to be used and construction methodology which will be applicable to all operations from the excavation of the thrust pit to the end of the operation and the subsequent removal of temporary works, and making good.

The contractor is responsible for the complete design of the jacking structure and of the jacked pipeline and all subsequent costs must be priced and included in the priced schedule. This will include the following:

- (i) The design and the preparation of all drawings.
- (ii) All labour, plant, tools, equipment, materials, transport, consumable stores, services, samples, temporary excavations, and everything of a temporary or permanent nature required to carry out the work.

B2218 MEASUREMENT AND PAYMENT

Item	Unit
-------------	-------------

BC3.2.1 Excavation culvert structures:*ADD THE FOLLOWING SUB-ITEM:*

Item	Unit
-------------	-------------

BC (c) Extra-over sub-item B22.01C3.2.1 (a) for excavation by hand (m ³)	cubic metre
--	-------------

The unit of measurement shall be the cubic metre of material excavated by means of labour using hand tools only. This item shall only apply where the dimensions of the area to be excavated are such as to render excavation by machinery impractical and where the Employers Agent has specifically ordered or authorised excavation by hand. This item shall not apply where machine excavation would have been possible but the Contractor chooses to use hand excavation instead.

The tendered extra-over rate shall include full compensation for all additional costs in excavating the material using hand held tools."

BC3.2.2 Backfilling:*REPLACE THE DESCRIPTION OF SUBITEM 22.02(c) WITH THE FOLLOWING:*

"(c) Extra over subitems B22.02(a) and (b) for soil cement (soilcrete) backfilling (percentage of cement indicated)"

ADD THE FOLLOWING SUBITEMS:

"(d) Special backfilling for Telkom optical fibre, uPVC ducts all as specified cubic metre (m³)"

(e) Special bedding and padding for Telkom optical fibre uPVC pipes as specified cubic metre (m³)

(f) Installation of earth wire in backfilling (including jointing) and danger tape as supplied by Telkom.....metre (m)"

ADD THE FOLLOWING PARAGRAPHS:

"The payment shall also apply to backfill adjacent to and over corrugated metal arch culverts. The quantity shall be calculated in accordance with the details of backfilling as indicated on the drawings.

The backfilling against concrete footings shall be paid for under item B61.04.

The tendered rate shall include full compensation for all additional work necessitated by working in the confined area, special equipment required to achieve the specified compaction and the material as described in clause B2211."

Item	
-------------	--

BC3.2.3 Concrete pipe culverts

ADD THE FOLLOWING TO THE SECOND PARAGRAPH:

"The tendered rates shall also include full compensation for supplying and installing 500mm wide Flexcell or an approved equivalent material in the concrete bedding below pipe joints."

Item**BC3.2.5 Portal and rectangular culverts****ADD THE FOLLOWING TO THE SECOND PARAGRAPH:**

"The tendered rates shall also include full compensation for supplying and installing 500mm Flexcell or an approved equivalent material."

Item**Unit****BC3.2.7 Cast in situ concrete and formwork:****ADD THE FOLLOWING SUBITEM:**

"(f) In concrete collars at the joints between new and existing prefabricated pipe culverts, including formwork, as shown on the drawings (class of concrete indicated) cubic metre (m³)"

REPLACE ITEM 22.14 WITH THE FOLLOWING:**"Item****Unit**

BC Removing and stacking existing prefabricated culverts (all sizes)metre (m)

The unit of measurement shall be the metre of existing culvert removed and stacked as instructed by the Employers Agent.

The tendered rate shall include full compensation for lifting, loading, transporting to stack, off-loading and stacking the culverts. The free-haul distance is 5,0 km.

Payment for the excavation and backfilling (including all layerworks) required to remove and stack existing prefabricated culverts will be made separately under items B22.01 and B22.02."

REPLACE ITEM 22.26 WITH THE FOLLOWING:**"Item****Unit****B22.26 Hand excavation:**

- (a) To determine the positions of existing services:
- (i) In roads..... cubic metre (m³)
- (ii) In all other areas..... cubic metre (m³)
- (b) To expose existing services to 0,6 m on either side of the service cubic metre (m³)

The unit of measurement shall be the cubic metre of material excavated within the lengths and widths authorised by the Employers Agent and the depth required to expose the service. Excavation in excess of the authorised dimensions will not be measured for payment.

The tendered rates shall include full compensation for all excavation, backfilling, compacting to 90% of modified AASHTO density, disposing of surplus excavated material, demarcating excavations with approved safety tape, keeping the excavations safe, dealing with surface or subsurface water, taking special care to ensure that services are not damaged in any way, and all other operations required to complete the work. The tendered rates shall also include for transporting surplus excavated material for a free-haul distance of 1,0 km.

No distinction will be made between hard and soft materials, nor will distinctions be made between the various types of service to be exposed or the depths to which excavations are taken.

When instructed by the Employers Agent, the reinstatement of the pavement layers, surfacing and kerbing will be measured for payment under item 22.27.

NB The contractor shall supply adequate supervision of labourers excavating to expose services. Damage to a service caused by the contractor shall be repaired at his expense, to the satisfaction of the owner of the service and the Employers Agent."

REPLACE ITEM 22.28 WITH THE FOLLOWING:

"Item	Unit
B22.28 Extra over items B22.03 and B22.05 for supplying end units for culverts with a skew angle:	
(a) Pipe culverts (type and diameter indicated)	number (No)
(b) Portal and rectangular culverts (type and size indicated)	number (No)

The unit of measurement for providing manufactured end units for skew culverts shall be the numbers of such skew-end units supplied for each type and size of prefabricated culvert, irrespective of the angle of skew.

The tendered rate shall be an extra over the prices for items B22.03 and B22.05 and shall include for all additional costs involved in manufacturing, supplying and laying the skew-end units."

ADD THE FOLLOWING ITEMS:

"Item	Unit
BC3.2.23 Breaking into existing drainage structures and building in pipes of the following diameter (Pipe diameter to be stated)	number (No)

The unit of measurement shall be the number of each size of pipe built into existing drainage structures in accordance with the details on the drawings or as instructed by the Employers Agent.

The tendered rates shall include full compensation for supplying all labour, constructional plant and materials required, for all excavation, breaking into existing drainage structures, building pipes into the newly formed accesses, sealing around the pipes and making the joints watertight, breaking out existing benching and channeling where required and reconstructing them complete with granolithic rendering to suit the new pipe arrangement, backfilling and compacting to 90% of modified AASHTO density, transporting (including all haul) and disposing of all surplus excavated material and debris to approved dumping sites provided by the contractor, and dealing with the flows in the existing structures.

No distinction will be made between different types of structure.

Item	Unit
-------------	-------------

BC3.2.23 Breaking into existing stormwater pipes of the following sizes to construct new drainage structures (pipe diameter to be stated)

number (No)

The unit of measurement shall be the number of each size of pipe which is broken into to construct a new drainage structure.

The tendered rates shall include full compensation for supplying all labour, constructional plant and materials required, for breaking into the existing pipes, transporting (including all haul) and disposing of the debris at approved dumping sites provided by the contractor, dealing with the flow in the existing pipes during breaking into the pipes and during construction of the drainage structures, and for all additional costs incurred when building new drainage structures around existing pipes. The drainage structures are measured for payment under other items.

Item

Unit

CHAPTER 3: 3.3 CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES AND CONCRETE LINING FOR OPEN DRAINS

B A3.3.1 SCOPE

ADD THE FOLLOWING TO THIS CLAUSE:

"This section also covers the replacement of damaged concrete kerbing, channeling and lining."

B A3.3.7 EXECUTION OF THE WORKS

b) Prefabricated concrete kerbing and channeling

ADD "plinths," AFTER "concrete" IN THE FIRST LINE OF THE FIRST PARAGRAPH.

ADD "and prefabricated concrete plinths" AFTER "kerb units" IN THE SECOND LINE OF THE SECOND PARAGRAPH.

ADD "and prefabricated concrete plinths" AFTER "concrete kerbs" IN THE FIRST LINE AND "plinths" AFTER "kerbs" IN THE SECOND LINE OF THE LAST PARAGRAPH.

REPLACE "1:4:8/25" IN THE SECOND LINE OF THE LAST PARAGRAPH WITH "1:4:8/38".

ADD THE FOLLOWING:

"A 10 mm wide joint formed in inert filler shall be provided every 10 metres through the kerbing and channeling. The colour of the filler shall match the colour of the kerbing.

Curved kerbing of radius less than one metre shall be cast in situ. Units for curved kerbing of radius greater than 1 m up to 4 m shall be of nominal length 0,3 m. Units for curved kerbing of radius greater than 4 m up to 20 m shall be of nominal length 0,5 m. Units for radius exceeding 20 m shall be of nominal length 1 m. Any associated channeling shall also comply with the above requirements."

(e) Cast in situ kerbs and channels

ADD THE FOLLOWING:

"Cast in situ kerbs, channels and edge beams shall be provided with a contraction joint every 2 m and an expansion joint every 20 m. The contact area of the contraction joint shall be painted with two coats of bitumen. Alternatively, joints may be cut and finished to a depth of 50 mm. The expansion joint shall consist of 12 mm thick Flexcell or an approved equivalent placed between adjoining concrete sections. The top part of the joint shall be sealed with a 12 mm x 12 mm silicone sealant. All joints shall be provided for the full depth of the concrete."

g) Concrete-lined open drains

ADD THE FOLLOWING TO THE LAST PARAGRAPH:

"Alternatively, the surface could be sprayed with invert bituminous emulsion as soon as possible after the excavations have been trimmed and compacted. The sprayed surfaces shall be maintained until the concrete lining is cast. The nominal rate of application of the emulsion shall be 0.5 litre/m² unless otherwise instructed by the Employers Agent."

(k) Cutting existing bituminous surfacing and pavement layers

REPLACE THE PARAGRAPH WITH THE FOLLOWING:

"Where the Employers Agent instructs kerbing, edge beams, channeling or concrete-lined drains to be constructed against existing bituminous surfacing and pavement layers, the

full depth of the bituminous surfacing and pavement layers shall be accurately cut with a mechanical saw to the required line and level before the kerbing, edge beams, channeling or concrete-lined drain is constructed. The cut edge shall be vertical for kerbing, edge beams, concrete-lined drains and channeling. The concrete shall be placed directly against the cut edge without formwork. All material outside the cut edge shall be removed to the required depth before the concrete is placed, and the debris shall be disposed of at approved dumping sites provided by the contractor. The bituminous surfacing shall be protected and kept clean to the Employers Agent's satisfaction."

ADD THE FOLLOWING SUBCLAUSE:

"(l) Removal of existing kerb and channel

Where shown on the drawings and/or indicated by the Employers Agent, the existing kerb and channel shall be removed and transported to spoil as directed."

PART C MEASUREMENT AND PAYMENT

REPLACE THE DESCRIPTION OF ITEM 23.02 WITH THE FOLLOWING:

"Item	Unit
BC3.3.2 Concrete kerbing-channeling combination, including joints (class of concrete indicated for cast in situ concrete):	
(a) (Description of type with reference to drawing)	
(i) Radius 1 m to 4 m	metre (m)
(ii) Radius 4.01 m to 20 m	metre (m)
(iii) Straight and to radius not less than 20 m	metre (m)
(b) (Etc. for other types)	metre (m)
(i) Radius 1 m to 4 m	metre (m)
(ii) Radius 4.01 m to 20 m	metre (m)
(iii) Straight and to radius not less than 20 m	metre (m)

The unit of measurement shall be the metre of concrete kerbing or kerbing and channeling combination complete as constructed, measured along the front face of the kerb.

The tendered rate shall include full compensation for the additional costs involved in setting out, preparing and constructing as specified on curves with radii less than 20 m."

AMEND ITEM B23.14 AS FOLLOWS:

"Item	Unit
B C3.3.14 Cutting bituminous surfacing and pavement layers for concrete kerbing, channeling or concrete-lined drains"	

DELETE IN LINE 3 OF THE 1ST PARAGRAPH OF THE PAYMENT ITEM DESCRIPTION:

"Irrespective of the depth cut".

REPLACE THE DESCRIPTION OF ITEM 23.15 WITH THE FOLLOWING:

"Item	Unit
-------	------

B C3.3.15 Energy dissipaters in outlet structures ..(indicate class of concrete and size), **complete as shown on the drawings** number (No)"

ADD THE FOLLOWING:

"The tendered rate shall include full compensation for procuring, furnishing and installing the precast concrete blocks as specified."

ADD THE FOLLOWING PAYMENT ITEMS:

"Item	Unit
--------------	-------------

B C3.3.16 Demolition and removal of existing kerbs and/or channel (specify maximum size)	cubic metre (m ³)
---	-------------------------------

The unit of measurement shall be the cubic metre (m³) of material measured in situ before demolition or excavation.

The tendered rate shall include full compensation for breaking up the existing concrete or reinforced concrete to a specified 300mm maximum size, removal from site to an approved spoil site, clearing the excavation of all loose debris and to backfill the excavation where new concrete is not required. Overhaul will be paid under item 23/B16.02.

Item	Unit
-------------	-------------

B23.17 Pedestrian ramps at intersections	number (No)
---	-------------

The unit of measurement is the number of pedestrian ramps.

The tendered rate shall include full compensation for removing existing kerbing if required, for procuring and placing the precast concrete blocks, placing with finishing and contraction joints in the concrete surround and all other incidentals to complete the construction all in accordance with the drawings."

Item	Unit
-------------	-------------

B23.18 Tactile pedestrian kerb ramp complete as per National Technical Requirements 1: Pedestrian Crossings	number (no)
--	-------------

This item includes all items to construct one tactile pedestrian ramp complete and in accordance with the National Technical Requirements 1: Pedestrian Crossings, 15 December 2016, Version 6.

The tendered rate shall include full compensation for all labour, constructional plant and materials required for the construction of one tactile pedestrian ramp, complete, as shown on the details in Annexure C5.4. The tendered rate shall also"

Item	Unit
-------------	-------------

B23.19 Accessories	
---------------------------	--

- | | |
|---|-------------|
| (a) 400mm wide tactile warning tiles..... | Number (No) |
| (b) 400mm wide tactile guidance tiles..... | Number (No) |
| (c) Bollards. Supply and installation of concrete bollard. 25MPa Concrete and reinforced with 4 X Y10's. Installed at depth of 400mm below NGL. | |
| (i) 250mm diameter, 1200mm long, Exposed aggregate finish..... | Number |
| (No) | |
| (ii) 250mm diameter, 1200mm long, Smooth finish..... | Number (No) |

The tendered rate shall include full compensation for procurement, delivery and installation as per the approved drawings and as shown on the details in Annexure C5.4.

**B23.20 Cutting concrete sidewalk surfacing to a depth exceeding
50 mm but less than 100 mm.....
metre (m)**

The unit of measurement shall be the metre of concrete cutting kerbing or kerbing and channeling combination complete as constructed, measured along the front face of the kerb.

The tendered rate shall include full compensation for the additional costs involved in setting out, preparing and constructing as specified on curves with radii less than 20 m."

SECTION B 3200: SELECTION, STOCKPILING AND BREAKING DOWN THE MATERIALS FROM BORROW PITS, CUTTINGS AND EXISTING PAVEMENT LAYERS AND PLACING AND COMPACTING THE GRAVEL LAYERS

B3203 STOCKPILING THE MATERIAL

SECTION B 3300: MASS EARTHWORKS**B3302 MATERIALS****b) Fill**

ADD THE FOLLOWING UNDER ITEM (IV):

"The maximum swell at 100% Mod AASHTO compaction shall not be more than 2%."

B3303 CLASSIFICATION OF CUT AND BORROW EXCAVATION

CLASSIFICATION OF CUT AND BORROW EXCAVATION SHALL BE REVISED AS FOLLOWS:

"a) Classes of excavation**(ii) Intermediate excavation**

No distinction shall be made between soft and intermediate excavation, and all intermediate excavation shall be classified and measured as soft excavation."

B3305 TREATING THE ROADBED**a) Removing unsuitable material**

REPLACE "or" IN THE EIGHT LINE OF THE THIRD PARAGRAPH WITH "and" AND ADD THE FOLLOWING:

"For the purpose of this contract, excavation and removal of in situ clayey material over areas where the road is in a fill condition shall be classified as removal of unsuitable material, irrespective of the stability or moisture condition of the in-situ material".

(c) Preparing and compacting the roadbed

DELETE THE LAST SENTENCE OF THE FIRST PARAGRAPH "If necessary, roadbed depth of compaction." AND REPLACE AS FOLLOWS:

"Where demarcated by the Employers Agent, prior to the roadbed being scarified, the excess in situ material forming part of the present roadway, and within the limits of the roadbed, and in close proximity of the layer works, but falling within the limits of the layerworks, shall be bladed to controlled level in order to achieve the required level and necessary depth of compaction."

d) In situ treatment of roadbed

ADD THE FOLLOWING AFTER THE SECOND PARAGRAPH:

"Shales and mudstone shall be treated as directed by the Employers Agent."

B3306 CUT AND BORROW**e) The temporary stockpiling of materials**

REPLACE THE CONTENTS OF THIS SUBCLAUSE WITH THE FOLLOWING:

"The Contractor shall plan his activities in such a manner so that materials excavated from borrow areas and cuttings can be directly transported to and placed at the designated points.

The temporary stockpiling of material will not be paid for separately unless instructed by the Employers Agent, and full compensation will be deemed to have been included in the rates tendered for the various payment items for work for which the stockpiled material is to be used."

g) General

ADD THE FOLLOWING AFTER THE FIRST SENTENCE OF THE SECOND PARAGRAPH:

"The final cut surface in hard excavation shall not be more than 0,5 m below the specified slope face, measured at right angles to the strike and dip directions of the slope face."

B3307 FILLS

a) General

ADD THE FOLLOWING:

"Where existing embankments are to be widened, or where new embankments are to be constructed adjacent to existing embankments, the existing side slopes shall be benched as specified in subclause 3307(d) and in accordance with the details on the drawings.

In addition, the material in the fill widening shall, unless otherwise instructed by the Employers Agent, be compacted as follows:

- (i) where the thickness exceeds 1,5 m, it shall be compacted to a minimum of 93% modified AASHTO density to a depth of at least 1,5 m below the final road level; or
- (ii) where the thickness is less than 1,5 m, the in situ roadbed and fill material shall be compacted to 93% modified AASHTO density."

c) Constructing a pioneer layer

ADD THE FOLLOWING AT THE END OF THE FIRST PARAGRAPH:

"Where instructed by the engineer or shown on the drawings, the pioneer layer shall be wrapped in a Grade 5 geotextile."

d) Benching

REPLACE THE FIRST SENTENCE OF THE SECOND PARAGRAPH WITH THE FOLLOWING:

"The dimensions of benches as well as the extent to which existing fills have to be cut back to form benches shall be as indicated on the drawings or indicated by the Employers Agent."

ADD THE FOLLOWING AFTER THE SECOND PARAGRAPH:

"In order to obtain sufficient working width for road-building equipment when the existing road fill is widened, it may be necessary to form benches that extend beyond the normal road prism or to cut back into the existing road fill or both. The Contractor shall submit his proposals in this regard to the Employers Agent for approval before proceeding with such work. The Contractor will be paid in accordance with the relevant payment items for work required to obtain a working width of up to 4 m. Additional work required to provide a working width in excess of 4 m shall be at the Contractor's expense."

ADD THE FOLLOWING SUBCLAUSES:**"(k) Constructing a coarse fill layer**

Coarse fill (so-called pioneer/rock fill layer as indicated on the drawings) shall consist of material which conforms with G10 specifications as per TRH 14: table 13 and shall be compacted to 90% of modified AASHTO density. The coarse fill shall be constructed to a specified thickness as indicated on the drawings.

(l) Construction of fabric-reinforced fill

The fabric used shall be Grade 3 or approved equivalent and the fill (placed and compacted over the length of the fabric, perpendicular to the face of the fill), shall be weathered sandstone. The fabric shall be folded over at 300 mm vertical intervals as shown on the drawings. The edge of the fill shall be satisfactorily shored or supported to enable compaction to be achieved."

B3308 FINISHING THE SLOPES**(d) General****ADD THE FOLLOWING:**

"Where existing cut and fill slopes are excessively eroded or where slippages occurred in slopes, the slopes are to be reinstated by means of backfilling with suitable gravel material. All loose material and vegetation shall first be removed from the eroded cut and fill slopes before backfilling may commence from the bottom of the cut or fill. The backfill material shall be benched into the existing slopes and compacted to 90% of modified AASHTO density, using suitable small compaction equipment e.g., Bomag walk-behind rollers or hand-held compaction tools. Benching shall be executed to the dimensions shown on the drawings. Upon completion of the backfilling operation the cut and fill slopes shall be neatly finished as specified."

B3310 CONSTRUCTION TOLERANCES**ADD THE FOLLOWING SUBCLAUSE:****"(c) Layer thicknesses**

The thickness tolerances referred to in clauses 8205 and 8305 for the 150 mm natural gravel fill layer compacted to 93% of modified AASHTO density, shall be as follows:

	D ₉₀	D _{max}	D _{average}
Fill layer	30 mm	40 mm	10 mm"

B3312 MEASUREMENT AND PAYMENT**General directions****(3) Work in restricted areas****DELETE THE CONTENTS OF THIS SUBCLAUSE AND REPLACE IT WITH THE FOLLOWING:**

"No additional or extra over payment will be made for work in restricted or confined areas."

AMEND THE DESCRIPTION OF ITEM 33.01 AS FOLLOWS:

"Item

B33.01 Cut and borrow to fill, including all haul (source borrow pit, cut, side drain, and stockpile)"

REPLACE THE FIFTH MEASUREMENT AND PAYMENT PARAGRAPH WITH THE FOLLOWING:

"The tendered rates shall include full compensation for procuring, furnishing and placing the material, including excavating as if in soft excavation, the cutting of benches, the transporting of material over the haul distance, for preparing, processing, shaping, watering, mixing, and compacting the materials to the densities or in the manner specified herein and for removing and disposing of up to 5% oversize material from the road after processing, including all haul."

AMEND THE DESCRIPTION OF ITEM 33.04 AS FOLLOWS:

"Item

**B33.04 Cut to spoil, including all haul.
Material obtained from:"**

REPLACE THE FOURTH MEASUREMENT AND PAYMENT PARAGRAPH WITH THE FOLLOWING:

"The tendered rates for cut to spoil shall include full compensation for excavating from the road prism and roadbed in the various classes of excavation, for loading, transporting the material over the haul distance, off-loading and disposing of the material as specified, including shaping and levelling-off any piles of spoil material."

ADD THE FOLLOWING ITEMS:

"Item	Unit
B33.20 Extra over item B33.01 for fill (G7) constructed from material obtained from commercial source, including all haul...	cubic metre (m ³)

The unit of measurement shall be as measured in item B33.01.

The tendered rate shall be paid extra over the rates applicable to item B33.01, and shall include full compensation for procuring, irrespective of hardness of excavation, furnishing, and transporting the material from an approved source irrespective of distance hauled."

B33.21 Roadbed constructed with material obtained from commercial sources or sources provided by the Contractor, including all haul

(a) Compaction to 93% of modified AASHTO density (G7) cubic metre (m³)

The unit of measurement is the cubic metre of material measured in the compacted roadbed. The quantity measured shall be calculated by the method of average end areas from levelled cross-sections prepared from the ground line after clearing and grubbing and the removal of topsoil and the completion of any preparatory roadbed treatment which may have been ordered by the Employers Agent, but prior to the construction of the fill, and the final specified or authorised cross-section superimposed at 20 m intervals along the centre line of the road. All measurement shall be neat and no payment will be made for that part of the roadbed placed in excess of the authorised cross-section shown on the drawings or instructed by the Employers Agent, irrespective of the tolerances in workmanship allowed under the contract. Where the roadbed has subsided under the fills, the quantities shall be adjusted to make allowance for such subsidence, as set out in the note at the beginning of clause 3312. Measurement of fill shall distinguish between the alternative methods of processing and compacting.

Where measurement by cross-sections is considered by the Employers Agent to be impractical, the compacted volume of the material may be taken as equal to 70% of the loose volume of material in the hauling vehicles as an alternative method of measurement.

The tendered rates shall include full compensation for the procuring, furnishing and transporting the materials over an unlimited free-haul distance from the sources to the site, for placing, preparing, processing, shaping, watering, mixing and compacting the materials to the densities or in the manner specified, and for removing and disposing of all oversize material from the road after processing, including transport for the haul distance to approved dumping sites provided by the Contractor.

Payment shall distinguish between the various methods of processing and compacting specified, as itemised above.

SECTION B 3400: PAVEMENT LAYERS OF GRAVEL MATERIAL**B3402 MATERIALS****a) General**

REPLACE THE FIRST PARAGRAPH WITH THE FOLLOWING:

"Gravel material shall be obtained from approved commercial sources or approved sources provided by the contractor."

ADD THE FOLLOWING AT THE END OF THE SECOND PARAGRAPH:

"For chemically stabilised layers the material shall conform to the requirements in table B3402/5.

For bitumen stabilised layers the material shall conform to the requirements in table B3402/6.

For cold in situ recycled layers the target grading shall be as indicated in table B3402/6"

ADD THE FOLLOWING AFTER THE SECOND PARAGRAPH:

"Distinction shall be made between crushed and natural G4, G5 and G6 materials. Where the crushing and/or screening of these materials has been specified, the combined grading shall conform to the grading limits specified for G4 class material in Table B3402/1.

The same shall apply for all materials obtained from commercial sources."

REPLACE THE GRADING SECTION IN TABLE 3402/1 WITH:

Grading	Nominal aperture size of sieve (mm)	Percentage passing through sieve by mass			The percentage by mass passing the 2,00mm sieve shall not be less than 20% not more than 70%
		Crushed material Nominal max size		Uncrushed material	
		37,5 mm	28 mm		
	53			100	
	50			95 - 100	
	37,5	100		85 – 100	
	28	86 - 95			
	20	73 - 86	87 - 96	61 - 91	
	14	61 - 76	73 – 86		
	5	37 - 54	43 - 61	31 - 66	
2	23 – 40	27 – 45	20 – 50		
0,425	11 – 24	13 – 27	10 – 30		
0.075	4 - 12	5 - 12	5 - 15		

Note: Refer to standard COLTO table for COLTO grading if required

REPLACE TABLE 3402/5 WITH:

"TABLE B3402/5: REQUIREMENTS FOR CHEMICALLY STABILISED LAYERS

Classification	C1	C2	C3	C4
Material before treatment	At least G2 quality	At least G4 quality	At least G5 quality	At least G6 quality
PI after treatment	Non-plastic	Non-plastic	6 max. *(1)	6 max. *(1)
UCS (MPa) *(2)	6 min.	4 min.	1,5 min	0,75 min.
ITS (kPa) *(3)	-	-	250 min.	200 min.
WDD (% loss)	5 max.	10 max.	20 max.	30 max.

Note:

*(1)

For materials derived from the basic crystalline rock group, the Plasticity Index after stabilization shall be non-plastic.

- * (2) Unconfined Compressive Strength @ 100% Mod. AASHTO density
- * (3) Indirect tensile Strength @ 100% Mod. AASHTO density (Rapid Curing)
- * (4) Wet/Dry Durability according to Method B 8110"

b) Compaction requirements

AMEND THE COMPACTION REQUIREMENTS AS FOLLOWS:

"The compaction requirements for the layers to be constructed under this contract are:

New Road construction:

Selected layer 150mm (G6)	93% of mod AASHTO density
Lower Subbase layer 150mm (G6)	95% of mod AASHTO density
Lower Subbase layer 150mm (C4)	96% of mod AASHTO density
Upper Subbase layer 150mm (C3)	97% of mod AASHTO density
Shoulder & gravel wearing course 150mm (G6)	95% of mod AASHTO density

Rehabilitation of existing road

Subbase layer 150mm (C3)	96% of mod AASHTO density
--------------------------	---------------------------

CHANGE THE COMPACTION REQUIREMENTS FOR STABILIZED SUBBASES TO READ AS FOLLOWS:

"96% and 97% as required for lower subbase and upper subbase respectively, for chemically stabilized material."

ADD THE FOLLOWING SUBCLAUSE:

"(d) Material requirements

When the values listed in tables 3402/1, 3402/2, 3402/3 and 3402/4 cannot be attained with the type and quantity of stabilizing agent specified in section 3500 in the project specifications and on the borrow pit plans, the Employers Agent will authorise the contractor to vary and/or amend the quantity and possibly the type of stabilizing agent as well in order to obtain the required values."

ADD TABLE B3402/7 AFTER TABLE 3402/6:

"TABLE B3402/7: REQUIREMENTS FOR EMULSION TREATED MATERIALS

Criteria	E1	E2
Material before treatment	G1 to G3	G4 to G5
After treatment:		
- Minimum CBR @ 100% modified AASTHO density	150%	100%
- Minimum UCS @ 100% modified AASHTO density	1 200 kPa	700 kPa

B3403 CONSTRUCTION

ADD THE FOLLOWING SUBCLAUSES:

"(f) Treatment of in situ material or existing pavement layers as new pavement layers

Where the in situ material or existing pavement layers are classified as suitable for new pavement layers and have to be reconstructed as prescribed by the Employers Agent, the material or layers shall be scarified, watered and compacted to a percentage of modified

AASHTO density. The density and compaction depth will be prescribed by the Employers Agent.

When additional material has to be imported to obtain the required level and layer thickness, and when the thickness of the layer of imported material would be less than the specified layer thickness after compaction, the in situ material or existing pavement layers shall be scarified, the necessary imported material placed, and this combined material mixed and compacted to the full specified depth of the layer.

The imported material will be measured and paid for under item 34.01 and the in situ material will be measured and paid for under item B34.04.

(g) Temporary stockpiling of material

The contractor shall plan his activities so that materials excavated from borrow areas and cuttings or imported from commercial sources can be directly transported to and placed at the designated points.

The temporary stockpiling of material will not be paid for separately unless instructed by the Employers Agent, and full compensation will be deemed to have been included in the rates tendered for the various payment items for work for which the material is to be used.

This subclause does not apply to the excavation and temporary stockpiling of existing pavement layers as instructed by the Employers Agent, in terms of subclause B3403(h), as these will be measured and paid for separately under item 32.06.

(h) Storing recovered pavement material

Excavated pavement material intended for reprocessing but which cannot be reprocessed in place or cannot, in the opinion of the Employers Agent, be placed in a windrow next to the excavation, nor directly placed in position anywhere else, shall be transported to approved stockpile or dumping sites with written permission from the Employers Agent.

Stockpile sites for material to be recycled or reprocessed shall be located as approved by the Employers Agent.

The stockpile site shall be cleaned, and all stones, vegetation and other materials which may cause contamination shall be removed. The site shall be graded smooth with an adequate slope to ensure proper drainage of water. If instructed by the Employers Agent, the surface shall be watered and compacted to a depth of at least 150 mm and to a density of 90% of modified AASHTO density. The compacted surface shall be firm. Upon completion, the surface shall be swept clean.

Stockpile sites shall be large enough to allow the different types of material to be stockpiled without overlapping or exceeding the limits of the prepared site. Enlargement of the stockpile sites after the stockpiles have been placed will not be permitted without the Employers Agent's approval.

Upon completion of the work, the stockpile sites shall be rehabilitated in accordance with the Employers Agent's instructions.

(h) Existing asphalt base or surfacing

Existing asphalt base or surfacing which cannot be broken down effectively to be used as part of the recovered pavement material, shall be separately excavated from the existing pavement layers and disposed of at approved dumping sites"

B3405 CONSTRUCTION TOLERANCES**(a) Level**

REPLACE THE TABLE IN THE SUB-SUB-CLAUSE WITH THE FOLLOWING:

	H_{90}	H_{max}
Selected layers	25 mm	33 mm
Sub-base layers	15 mm	20 mm
Base layers	12 mm	15 mm
Shoulders		25 mm
Subbases and shoulders below precast concrete interlocking paving blocks	15 mm	20 mm

ADD THE FOLLOWING:

"Level control for the various pavement layers shall be done at least at the following intervals in the longitudinal direction:

Layer	Interval
Selected layer, sub-base, shoulders and wearing course	20 m
Base	10 m

ADD THE FOLLOWING AT THE END OF THE CLAUSE:

"If a selected subcontractor lays the precast concrete interlocking block paving, the contractor shall nevertheless be responsible for ensuring that the top levels of the subbases comply with the specifications. This could entail removing high spots and filling in depressions as specified in clause B7304."

(b) Layer thicknesses

REPLACE THE TABLE IN THE SUB-SUB-CLAUSE WITH THE FOLLOWING:

	D_{90}	D_{max}	D_{ave}
Selected layers	25 mm	35 mm	8 mm
Sub-base layers	18 mm	24 mm	5 mm
Base layers	15 mm	22 mm	5 mm
Shoulders		30 mm	0 mm

ADD THE FOLLOWING:

"The construction tolerances of clause 3405 shall apply to layers constructed from reprocessed material, but when a gravel layer is placed on top of an existing layer without the existing layer being trimmed to prescribed levels, the thickness tolerances of subclause (b) do not apply."

(e) Cross-section

DELETE THE SECOND PARAGRAPH AND REPLACE WITH THE FOLLOWING:

"The normal cross-fall of the road wearing course where the road is in a straight horizontal alignment, is specified as shown on the drawings.

At any cross-section the measured cross-fall between any two points shall be at least 2,8% and not more than 3,5%. At any cross-section the actual level at any point shall not be higher than 10 mm above the computed level from the cross-section as specified and the actual level, if lower than the computed level, shall not be lower by more than that derived from the specifications for longitudinal grade and cross-fall deviations.

(f) Surface regularity

ADD THE FOLLOWING:

"Where transverse construction joints in base layers are made between newly and previously constructed sections, the contractor shall exercise level control at such joints by installing level poles at 5 m intervals on either side of the joint of the layer covering at least a 30 m length into the newly constructed section."

B3406 QUALITY OF MATERIALS AND WORKMANSHIP

REPLACE THE SECOND PARAGRAPH WITH THE FOLLOWING:

"Test results and measurements will be assessed in accordance with the provisions of Section 8300"

B3407 MEASUREMENT AND PAYMENT

DELETE THE FIRST PARAGRAPH AND REPLACE IT WITH THE FOLLOWING:

"Note: No additional or extra over payment shall be made for work in restricted or confined areas. Provision is also made for the construction of pavement layers with material procured from commercial sources. The costs of procuring and transporting the material from the source to the required position on site, shall be included in the tendered rates."

ADD THE FOLLOWING ITEMS:

	"Item"	Unit
B34.14	Pavement layers constructed from gravel supplied from commercial sources or sources provided by the Contractor, including all haul	
(a)	Gravel selected layer (G6) compacted to:	
i)	93% of modified AASTHO density for a compacted layer thickness of 150mm cubic metre (m ³)	
(c)	Gravel subbase (unstabilised gravel G6) compacted to:	
i)	95% of modified AASTHO density for a compacted layer thickness of 150mm cubic metre (m ³)	
ii)	97% of modified AASTHO density for a compacted layer thickness of 150mm cubic metre (m ³)	
(d)	Gravel subbase (chemically stabilised material) compacted to:	
i)	95% of modified AASTHO density for a compacted layer thickness of 100mm C4..... cubic metre (m ³)	
ii)	96% of modified AASTHO density for a compacted layer thickness of 100mm C3..... cubic metre (m ³)	
(e)	Gravel base (unstabilised gravel G6) compacted to:	
i)	98% of modified AASTHO density for a compacted layer thickness of 150mm cubic metre (m ³)	
ii)	100% of modified AASTHO density for a compacted layer thickness of 150mm cubic metre (m ³)	
(f)	Gravel base (chemically stabilised material) compacted to:	

- i) 97% of modified AASTHO density
for a compacted layer thickness of 150mm C4..... cubic metre (m³)
 - ii) 98% of modified AASTHO density
for a compacted layer thickness of 150mm C3..... cubic metre (m³)
- (g) Gravel shoulders compacted to:
 - (ii) 95% of modified AASHTO density for a compacted
layer thickness of 200 mm..... cubic metre (m³)
- (h) Gravel wearing course compacted to:
 - (ii) 95% of modified AASHTO density for a compacted
layer thickness of 150 mm..... cubic metre (m³)

The unit of measurement is the cubic metre of compacted pavement layer and the quantity shall be calculated by the method of from the authorized dimensions of the completed layer.

The tendered rates shall include full compensation for procuring, furnishing and transporting the materials over an unlimited free-haul distance from the sources to the site, for placing, preparing, processing, shaping, watering, mixing and compacting the materials to the densities or in the manner specified, and for removing and disposing of all oversize material from the road after processing, including transport for the haul distance to approved dumping sites provided by the contractor."

CHAPTER 5: EARTHWORKS AND PAVEMENT LAYERS: CONSTRUCTION

CHAPTER 5.1. ROADBED

a) Hard material

Where detailed in the Contract Documentation, or as instructed by the Engineer, the roadbed shall be treated in-situ by breaking up formations of hard materials in order to achieve a uniform standard of compaction and to improve the subsurface drainage ahead of the fill or the road pavement layers.

Treatment in-situ shall consist of ripping the roadbed, or drilling and blasting the roadbed using explosives, or drilling and splitting the roadbed using non-explosive, expansive, rock-breaking products. The depth of ripping or drilling shall increase uniformly from the centre of the roadbed to the edges, on cambered sections of road.

(j) In-situ treatment by ripping

Unless indicated otherwise in the Contract Documentation, or instructed by the Engineer, the depth of ripping in the centre of the roadbed shall not be less than 300 mm and at the edges of the roadbed not less than 500 mm.

On super elevation sections or cross-fall sections the in-situ treatment shall have a cross-fall parallel to the pavement cross-fall and a uniform minimum depth of 400 mm.

Shales and mudstones shall also be treated in-situ as described above or removed to the required depth if so, specified in the Contract Documentation. After ripping, the hard roadbed material shall be broken down by rolling until the maximum dimension of any material fragment does not exceed 200 mm. The material shall then be compacted by means of a specified number of passes by a selected type of roller or by a combination of various rollers.

CHAPTER 5.4 STABILISATION

B5.4.1 SCOPE

Add the following as a 3rd paragraph:

"The use of recyclers for cold in situ recycling purposes is also covered in this section, which includes cement, and lime stabilisation of base and subbase layers consisting of gravel and/or crushed stone material as described in sections 3400 and 3600.

This section also covers the selection supply and construction of in-situ recycled bitumen emulsion and foam bitumen stabilized materials."

BB5.4.5 MATERIALS

a) Chemical stabilizing agents

~~DELETE SUB-CLAUSES (II) ORDINARY PORTLAND CEMENT AND (III) PORTLAND BLAST-FURNACE CEMENT AND REPLACE WITH THE FOLLOWING:~~

"Cement shall comply with the relevant requirements of SANS 50197-1:2000. The use of strength classes greater than 32,5 shall not be permitted.

On this contract CEM II A-S (32.5) N shall be used for stabilization purposes."

ADD THE FOLLOWING:

"The stabilizing agents for the gravel selected layer, the gravel subbase and the gravel base, and the modifying agent for the gravel base shall be as indicated on the design sheets. The quantities of stabilizing and modifying agents indicated in the bill of quantities are based on the percentages indicated on the design sheets.

The upper selected layer in cuts shall be stabilized with lime or cement if necessitated by moisture or other conditions.

The Employers Agent may instruct the contractor to alter the type or percentage of stabilizing or modifying agent after tests on the site during construction."

(i) Road lime

ADD THE FOLLOWING:

"Road lime shall be calcium type lime."

(e) Water

REPLACE THE ENTIRE SUBCLAUSE WITH THE FOLLOWING:

"Water for the foaming process or emulsion dilution shall not contain any deleterious material in harmful concentrations that could be detrimental to the foaming process or cause emulsions to break prematurely. Only approved sources of water shall be used and shall be tested for compatibility with the bitumen before approval shall be given. Generally, water suitable for human consumption shall be regarded as suitable."

ADD THE FOLLOWING SUBCLAUSE:

"(f) Chemical modifying agents

The modifying agent under normal circumstances shall be slaked road lime, calcium type. The nominal rate of application for tender purposes as a percentage of the mass of the material to be modified and compacted to the required modified AASHTO density shall be as follows:

Gravel base (temporary works) : 2%

The Employers Agent will instruct the contractor to amend the percentage and possibly the type of modifying agent after tests on the site during construction."

A5.4.7.3

CHEMICAL STABILIZATION

a) Preparing the layer

INSERT THE FOLLOWING BEFORE THE FIRST PARAGRAPH:

"Moisture content tests shall not be undertaken more than one day in advance of in situ stabilization operations. Care shall be taken to ensure that samples are representative of the in situ material. Checks shall be conducted when wet weather occurs between initial testing and work commencing on any section."

ADD THE FOLLOWING:

"The material to be stabilized shall be spread and pre-shaped, so that a true cross-fall is obtained. The upper level of the spread material shall be such that any indentations and depressions caused by construction equipment shall be above or at final cutting level. Enough extra material must be allowed for, so that no filling whatsoever is carried out. The final operation on the base prior to final compaction will be cutting and never making up of levels."

b) Applying the stabilizing agent

REPLACE THE SECOND SENTENCE OF THE SECOND PARAGRAPH WITH THE FOLLOWING:

"Spreading shall only commence when the Employers Agent is satisfied that the correct quantity of stabilizing agent has been placed on the layer and has given permission that the stabilizing agent may be spread uniformly over the entire surface to be treated."

(d) Mixing in the stabilizing agent

ADD THE FOLLOWING:

"The contractor shall prepare a trial section for each type of material without any extra payment to demonstrate his proposed mixing process before extensive mixing commences.

After approval has been obtained, the mixing process and equipment shall remain unaltered unless otherwise instructed by the Employers Agent.

The fact that the Employers Agent has approved the mixing process shall not relieve the contractor of his obligations in respect of the mixing specified elsewhere in the specifications. It will serve only as a guideline to ensure that the specified mixing requirements can actually be met."

(f) Compaction

ADD THE FOLLOWING:

"Where the gravel base is chemically modified with road lime to modify certain physical properties of the gravel material and not for purposes of cementation, the base shall be compacted by means of two roller passes with a heavy pneumatic roller after the stabilizing agent has been mixed in and the material watered as specified in subclauses 3503(d) and (e) respectively. After twenty-four (24) hours the base shall be loosened by ploughing to its full depth, and be shaped, compacted and finished in accordance with the specifications.

When cutting final levels, the top of the layer shall be lightly watered to reduce the risk of dragging the material and cause shear cracks. The blade of the grader shall be tilted forward to reduce the dragging effect. Under no circumstances shall material be imported from the windrow to make up for low spots or depressions caused by any construction equipment."

h) Curing the stabilized work

ADD THE FOLLOWING TO METHOD (II):

"The covering material shall be placed by end-tipping, spread, and not compacted until the underlying layer has cured for at least 7 days."

ADD THE FOLLOWING TO PARAGRAPH:

"Method (iii) and (iv) shall not be applicable."

ADD THE FOLLOWING TO PARAGRAPH (iv):

"As soon as the prime has sufficiently dried out and ball penetration tests allow so, and no longer than two weeks after the application of the prime, the layer must be surfaced or covered with the subsequent layer."

i) Construction limitations

**REPLACE THE FOURTH PARAGRAPH STARTING WITH "No stabilization ..."
WITH THE FOLLOWING:**

"No stabilization shall be done during windy conditions, wet weather or with falling air temperatures (7°C and dropping), or during rising air temperatures (when the air temperature is below 3°C).

Moisture content tests shall not be undertaken more than one day in advance of in situ stabilization operations. Care shall be taken to ensure that samples are representative of the in situ material. When wet weather occurs, checks shall be conducted between initial testing and work commencing on any section.

The surface temperature of a compacted stabilized layer shall not be allowed to fall below 1°C during the first three (3) days after stabilization. The Contractor shall be responsible for taking the necessary precautions to prevent the layer from freezing.

All stabilized layers damaged by rain, frost or by the formation of ice in the layer shall be removed and replaced by the Contractor at his own expense.

The Contractor shall make allowance for these requirements in his construction programme."

**IN TABLE 3503/1, DELETE "8 hours" FOR ORDINARY PORTLAND CEMENTS
AND CEMENT BLENDS AND REPLACE WITH "6 hours".**

ADD THE FOLLOWING SUBCLAUSE:

"(j) General

The contractor shall at all times supply all workers exposed to chemical stabilizing or modifying agents with approved protective apparel, eyewear and masks, and no person without such apparel, eyewear and masks may be permitted to work with or be exposed to the chemical agents. Precautionary measures shall also be taken to ensure that any livestock and the public will not be exposed to the chemical agents, for instance when they are carried by the wind.

Any biscuit layers or bowls, identified by the hollow sound caused when a chain is dragged over the stabilized layer, shall be removed and repaired prior to surfacing. The repairs shall be for the account of the contractor. Before surfacing is allowed, ball penetration tests shall be carried out."

A5.4.8 QUALITY OF MATERIALS AND WORKMANSHIP

Add the following after the second paragraph:

"The test results and measurements will be judged in accordance with the provisions of Section 8300."

Add the following paragraphs:

"The Employers Agent shall be notified 24 hours in advance to enable him to conduct tests himself.

Sample preparation and testing for cement stabilization testing shall be done by means of the Rapid Cure Method as described in clause B8110.

The stabilized material sampled from the layer for the compaction of modified AASHTO briquettes, shall be prepared according to SANS 3001; GR54, i.e., discard material coarser than a 37,5 mm test sieve, and compacted according to SANS 3001; GR31.

Any delamination of the completed layer (biscuiting), identified by the hollow sound caused when a chain is dragged over the stabilized layer, shall be removed and repaired prior to the

construction of subsequent layers. The repair method shall be approved by the Employers Agent. No payment will be made for repairs.

ADD THE FOLLOWING CLAUSES:

"BA5.4.6 PLANT AND EQUIPMENT FOR COLD IN SITU RECYCLING

All cold in situ recycling shall be done utilising purpose-built wheel-mounted in situ recycling machines. The following specifications are applicable to such machines. Where the Contractor intends using any other type of machine to recycle (e.g., a modified track-mounted milling machine) he shall submit for the approval of the engineer a full motivation for using such a machine, including a detailed work plan describing the recycling / mixing process and subsequent compaction / levelling processes that will produce a layer that meets the specified end product requirements.

(a) In situ recycling machines

In situ recycling shall be carried out using a special-purpose recycling machine to break down and recover material from the prescribed horizon in the upper layers of the existing pavement, blended together with any imported material, stabilising agent(s), water and any other specified additives. The machine employed shall be capable of achieving the required grading and consistency of mix in a single pass.

In addition, the recycling machine shall meet the following requirements:

- (i) Be factory-built by a proprietary manufacturer having a demonstrable track record and manufacturing history in producing such equipment;
- (ii) If older than 10 years, the machine shall be certified by the manufacturer or manufacturer's authorized agent to confirm operational fitness-for-purpose dated not more than 3 months earlier than the date on which it commences work on the contract;
- (iii) Have a level-control system to maintain the cut depth within a tolerance of ± 10 millimeters of the required depth during continuous operation;
- (iv) The milling / mixing drum (the "cutter") shall have a minimum cut width of 2 metres with a facility to change the speed of rotation. The machine shall be capable of recycling to the maximum depth specified in a single pass;
- (v) The cutter shall rotate within an enclosed chamber (the mixing chamber) into which water and any liquid stabilising agents are injected under pressure at the specified application rate relative to the mass of material in the mixing chamber.
- (vi) The cutter shall be mounted on a swing arm that is separate from the housing of the mixing chamber, thereby allowing the volume of the mixing chamber to increase as the depth of cut increases.
- (vii) Have a liquid application system dedicated to adding water to the material in the mixing chamber;
- (viii) Where a bitumen stabilising agent is to be applied, a second separate liquid application system shall be fitted to the mixing chamber. Such system shall be appropriate for the addition of either bitumen emulsion or foamed bitumen;
- (ix) All liquid application systems shall be controlled by a micro-processor / flow meter combination that accurately regulates pump delivery (flow rate) with the speed of advance.
- (x) All liquid application systems shall include a dedicated spraybar that spans the full width of the mixing chamber. Each spraybar shall be equipped with multiple injection nozzles mounted equidistant along the length of the bar at a maximum interval of 200mm with the ability to close off selected nozzles, thereby allowing the width of application to be preset;
- (xi) Where two liquid application systems are used, the water application spraybar shall be mounted below the other spraybar (relative to the direction of rotation of the cutter) such that the recycled material encounters the water spray before the stabilising agent; and
- (xii) The recycler shall have sufficient power to recover and mix the existing pavement material together with all additives to produce a homogeneously mixed material whilst pushing (or pulling) bulk supply tanker(s).

- (xiii) For foamed bitumen the liquid application system mounted on the recycler shall have the following additional features:
- Each injection nozzle on the spraybar shall be fitted with an expansion chamber (the so-called "Mobil system") for foaming the bitumen;
 - Functioning gauges on the bitumen supply line for monitoring temperature and pressure;
 - The ability to demonstrate that all expansion chambers are free of blockages in both the water and bitumen feed lines;
 - A means of producing a representative sample of foamed bitumen at any stage during normal operations (i.e., a "test nozzle"); and
 - The micro-processor shall continuously monitor the actual bitumen consumption whilst working and provide a running total that allows immediate reconciliation with theoretical (calculated) consumption.

Before any recycling work commences, the Contractor shall submit a specification sheet (obtained from the manufacturer) stating the capacity, pressure and temperature limits for each liquid application system that will be used to treat the recycled material.

The recycling machine that the Contractor intends deploying shall be subject to the engineer's approval and he shall be entitled to reject a machine which, in his opinion, may not be capable of producing a consistent product when recycling to the specified depth(s).

(b) Plant for compacting and finishing the treated layer

The treated material exiting from the rear of the recycler shall be processed using suitable compaction equipment and graders to achieve a layer that meets the specified requirements. Sufficient plant and equipment shall be deployed to enable the treated material to be processed and finished off within the time limitations specified below.

(i) Primary compaction

Initial compaction shall be undertaken immediately behind the recycling machine using a vibrating single-drum padfoot roller selected in accordance with the following guidelines:

TABLE B3511/1 GUIDELINES FOR SELECTION OF PRIMARY ROLLERS

Minimum static mass of roller (tons)	Final layer thickness			
	< 150mm	150 – 200mm	200 – 250mm	> 250mm
	12	14	16	20
Minimum amplitude at frequency range	1.8mm @ 30 – 35Hz			

It will be advantageous if the roller is equipped with an integrated compactometer device to indicate and record the level of density that is achieved with each successive pass of the roller. These records can be used by the Contractor for process control to indicate that the maximum density has been achieved.

(ii) Secondary compaction

After primary compaction and shaping of the layer a smooth drum vibrating roller with a static mass not less than 10 tons and not more than 14 tons shall be used to compact the upper portion of the layer.

(iii) Finishing of the layer

After the final level of the layer has been obtained a pneumatic-tyred roller (PTR) with a minimum static mass of 18 tons and mounted on at least seven (7) tyres shall be used to finish off the layer.

(c) Bulk tankers

Only tankers with a capacity exceeding ten thousand (10 000) litres shall be deployed to supply the recycling machine with water and/or liquid stabilising agents. Tankers containing a bitumen stabilising agent shall be fitted with appropriate tow hitches, one in front and one at the rear, thereby allowing the tanker to be pushed from behind by the recycling machine, and to push a water tanker in front. No leaking tanker will be permitted on the site.

Where a bituminous stabilising agent is added, each tanker shall be equipped with:

- (i) A thermometer reflecting the temperature of the contents in the bottom half of the tank; and
- (ii) A rear feed valve (minimum internal diameter of 75mm when fully opened) that is capable of draining the contents of the tank.

B3512 CONSTRUCTION OF LAYERS BY MEANS OF COLD IN SITU RECYCLING**(a) Requirements before recycling commences**

- (i) Stabilization mix design procedure for cold in situ recycling

The following mix design procedure shall be followed as a minimum requirement for each stabilization type:

Within 30 days of the Contractor taking possession of the site, the Contractor shall commence with the mix design process. This process shall be carried out on samples of neat materials extracted from the full depth of the recycling horizon. Bulk samples shall be extracted by means of the recycling machine proposed for the stabilisation work. For each material uniform section identified, two separate bulk samples shall be extracted from the recycling horizon and used in the stabilization mix design process. The location at which such samples are taken shall be indicated by the engineer.

Stabilisation mix designs shall be undertaken by the engineer to determine:

- details for blending the recycled material with imported material (where necessary);
- application rates for stabilising agent(s);
- target strengths achieved from such application rates; and
- impact of material variations (sensitivity analysis)

Stabilisation mix designs shall be carried out in accordance with the latest edition of the following best practice guideline publications:

- Cementitious stabilisation: SAPEM, SANRAL M5 manual and TRH 13
- Bituminous stabilisation: SAPEM and TG2

The Contractor shall construct a trial section for the approved mix design developed for the first uniform section. Recycling work may only commence once the trial section has been approved by the engineer. Thereafter, it will be incumbent on the Contractor to obtain the necessary approval for the relevant mix design for each uniform section ahead of the recycling work. Should the situation arise where the Contractor has not followed the mix design procedure to obtain the required approval of the engineer recycling work shall cease until such time as the prescribed process for approval has been followed. The Contractor shall have no recourse for costs incurred as a consequence of such a delay.

- (ii) Setting out and control of the work for cold in situ recycling

Unless otherwise stated in the specifications, the Contractor shall establish his own reference and level beacons for the setting-out and control of the works.

(1) Layers constructed utilising existing levels

The existing horizontal alignment shall be retained and only minor modifications made to the vertical alignment, as described below.

The Contractor shall establish a series of level control poles placed at a constant offset on both sides of the road at a maximum interval length indicated in clause B3405(a). At each level control location, the Contractor shall record the existing road surface levels at the centre-line and at the outer limits of each lane and prepare a series of graphs (for sections not less than 2.0km in length) with the recorded levels plotted at an exaggerated scale against the km distance. Final levels for the new stabilised layer shall be selected in accordance with a "best-fit" principle, taking into account the following:

- the required camber or super elevation details at each location;
- the minimum requirements governing changes in grade (longitudinal grade line);
- the thickness of the existing base layer; and
- minimising the amount of pre-work required (pre-treatment and/or importing new material) before recycling can commence.

At least two weeks before recycling work is scheduled to commence on any specific section, the Contractor shall select the best-fit design levels and submit these proposals to the engineer (both as a schedule of longitudinal grade, cross-fall and final surface levels, as well as a drawing with the design lines superimposed on the existing levels) for approval or amendment.

The engineer will take control measurements to determine the accuracy and adequacy of the reference beacons / control poles, and may instruct the Contractor to correct any faulty work and to take and provide such additional measurements and details as may be deemed necessary.

Survey work will not be measured and paid for separately and compensation for any work involved in staking, setting out, taking levels, determining the final surface elevations and transferring these design levels on to the level control poles (including the cost of all labour materials and reinstatement if required for any reason) will be deemed to be included in the rates for the relevant payment items for cold in situ recycling. No payment will be made for any inconvenience or delay caused by compliance with these requirements.

(2) Layers constructed utilising new levels

Layers shall be constructed according to new design levels as indicated on the drawings.

(iii) Production Plan

Prior to the start of a shift, the Contractor shall prepare a production plan detailing his proposals for the forthcoming shift's work. As a minimum, this plan shall include a sketch showing:

- the overall layout of the length and width of road intended to be recycled during the day, broken into the number of parallel cuts required to achieve the specified width of treatment;
- the location of and overlap width (minimum 150mm) at each longitudinal joint between adjacent cuts, together with the location of the inner and outer wheel paths of each lane affected by recycling;
- the sequence and length of each cut to be recycled before starting on the adjacent or following cut; and

- an estimate of the time required for recycling each cut and for finishing off the work.

(iv) Preparing the surface

Before any recycling work commences, the surface of the existing road shall be prepared by:

- cleaning all vegetation, garbage and other foreign matter including road studs from the full road width, including any adjacent lanes or shoulders that are not to be recycled;
- removing any standing water;
- pre-milling to remove high-spots and/or pre-pulverising where ordered;
- providing a reference line to assist the operator to accurately steer the recycling machine, and
- record the location of all road marking features (e.g., extent of barrier lines) that will be obliterated by recycling.

(v) Surface shape and level requirements

Where surface defects are to be corrected and/or modifications made to the grade line, instructions will be issued detailing the new surface level requirements. These may be achieved prior to recycling by either pre-milling to remove in situ material, by pre-pulverising, pre-shaping and pre-compacting the pulverised material, or by importing material and accurately spreading on the existing road surface, as described below.

(vi) Pre-milling

Where instructed, pre-milling shall be undertaken using a milling machine (not a recycling machine) to:

- Remove isolated high spots and/or make minor modifications to crest vertical curves by accurate milling. The material resulting from such milling operations shall remain on the road, behind the milling machine, where it shall be spread across the width of recycling and rolled with a smooth-drum roller or loaded onto trucks and disposed of as directed;
OR
- Break down (pulverise) badly cracked asphalt layers, and/or sections where thin asphalt overlays are delaminating. To ensure that the milling operation achieves the required degree of pulverisation, the depth of milling shall be constantly monitored and adjusted so that the bottom of the milling drum remains within the lower half of the cracked / delaminating asphalt layer. Where an acceptable degree of pulverisation cannot be achieved, the machine shall be operated in reverse (i.e., downcutting) with the same controls applied to the depth of milling. If such reverse milling fails to produce an acceptable degree of pulverisation, the asphalt layer shall be milled off and removed. The pulverised asphalt material generated from such pre-milling shall remain on the road, behind the milling machine, where it shall be spread across the width of recycling and rolled with a smooth-drum roller.

(vii) Pre-pulverising existing pavement material

Pre-pulverising shall only be undertaken on instruction from the engineer for the purpose of:

- breaking down excessively hard material;
- loosening the material across the road width so that it can be cross-mixed by grader;
- exposing the loosened (fluffed-up) material to the atmosphere to promote drying; or
- loosening the material in the existing pavement so that it can be loaded and removed from site.

The depth of pre-pulverising shall be carefully controlled throughout the operation to ensure that the cut horizon always remains at least 25mm above the bottom of the subsequent recycling / stabilisation horizon.

Unless the objective of pre-pulverising is to dry the material, a water tanker shall be coupled to the recycling machine and sufficient water added to allow the material to be compacted to a minimum density of 95% of the mod AASHTO density. Except where the material is to be cross-mixed, it shall be compacted immediately behind the recycler before using a grader to pre-shape the material in accordance with final level requirements.

(viii) Cross-mixing

Where cross-mixing is ordered, the material shall be bladed by grader or utilising other mixing equipment to achieve a uniform blend of material throughout the layer. The layer shall be compacted and shaped before being in situ recycled,

(ix) Addition of imported material

Where instructed to import material for blending and/or as make-up material for the purpose of shape, level or material grading correction, the prescribed material shall be imported and spread on the existing road surface prior to recycling. The method of placing and spreading the imported material shall be such as to achieve the required surface levels and will require the use of a paver, motor grader or other such plant. All imported material shall be pre-compacted to a minimum of 95% of the mod AASHTO density.

Nowhere shall the thickness of imported material exceed the recycling depth.

(b) The recycling process

(i) Before starting

Prior to starting to recycle, the production planned for the day shall be approved by the engineer and the following checks carried out:

- All relevant temperatures shall be measured and recorded, including:
 - air temperature;
 - the material in the recycling horizon; and
 - the contents of all bulk supply tankers (including water).
- All plant and equipment is on site and the operators of the different machines are adequately trained and briefed on their particular tasks.
- The recycling machine has been prepared and set up for the first cut. Such preparations shall include:
 - checking that the mixing chamber is free of any material build-up that may affect the functioning of the application nozzles on all relevant spraybars;
 - the cutting tools have sufficient remaining life to complete the first cut without stopping;
 - all relevant liquid application systems are functioning, free of blockages and the in-line filters are clean. Where a bitumen stabilising agent is applied, a relevant check-sheet (similar to the example forms included in the Appendices of SAPEM and TG2) shall be diligently followed, signed off and submitted to the engineer;
 - the on-board computer has been correctly set up and the input data verified;
 - the spraybar is set up with the correct nozzles selected to achieve the required width of application;
- Bulk supply tanker(s) are coupled correctly to the recycling machine, all feed pipes are properly connected, bled of air and free of leaks. Where a bitumen stabilising agent is applied, the feed pipe shall only be connected immediately before work is about to start. Where the

stabilising agent is foamed bitumen; the outlet plumbing on the tanker shall be checked and any "cold plug" of bitumen removed before attaching the feed pipe.

- Where cement or lime is spread by hand on the road surface ahead of the recycling machine, the bag spacing shall be checked at random intervals and recorded.
- A clear guideline is in place for the recycling machine to follow and is correctly aligned relative to the road geometry.
- The integrated compactometer system on the primary roller properly functioning and has been set up to record the correct relevant data.

(ii) Recycling

The recycling machine shall be set up and operated to ensure that:

- The speed of advance is regulated (below the maximum allowable of 10m/min) to achieve;
 - adequate pulverisation of all bound materials in the existing pavement to produce a material that meets the grading requirements;
 - operating pressures and flow rates in all liquid application systems that remain within the limits prescribed by the manufacturer of the machine.
- The depth of recycling coincides with the line and level specified for the bottom horizon of the new stabilised layer. The bottom of cut horizon shall be checked at least once every 100m of cut using a suitable T-bar to dip from a stringline pulled between the relevant final level reference marks on the level control poles.
- The planned width of overlap along all longitudinal joints is maintained and the line of cut does not deviate laterally by more than 50mm from that required (measured from the operator's guideline that shall be positioned for each and every cut).
- The process is continuous with a minimum number of stops. Transverse joints that occur every time the recycling machine stops are properly treated to achieve continuity of stabilisation and moisture across the resulting joint.
- The application rate of liquid stabilising agent(s) and water is uniformly continuous across the required width of treatment, including all longitudinal joints.
- The temperature across the width of material exiting the mixing chamber shall be checked at least once every 100m using a digital thermometer with a laser beam target held no more than 100mm above the material. Where the temperature varies consistently by more than 3°C along a particular longitudinal strip $\pm 200\text{mm}$ wide, the recycling machine shall be stopped and the relevant application nozzles on all spraybars that coincide with the offending strip shall be checked for blockages.
- The moisture content of the treated material is continuously monitored and the application of water adjusted to achieve a uniform moisture content as specified.
- The mixed material exiting from behind the recycling machine is struck off by the rear door of the mixing chamber with sufficient pressure applied to obtain a uniform surface that is free of valley lines, empty pockets and particle segregation.

The advance speed of the recycling machine and the speed of rotation of the recycling drum shall be set to obtain the required grading and sufficient mixing of all components (recycled material and additives) so that a homogeneous material is produced.

(c) Primary compaction

Recycling machines are configured such that their rear wheels run on top of the treated material towards the outer extremities of the cut. To prevent introducing a

density differential across the width of cut, primary compaction shall be completed prior to any grader work commencing. If the treated material is pre-shaped by grader prior to being compacted, the work shall be summarily rejected.

A single-drum vibrating roller shall be deployed to compact the recycled material immediately behind the recycling machine. This roller shall travel forwards and backwards at a constant speed (maximum 3km/hr (50m/min)), remaining within the confines of the recycled cut. Recycled material covering the outer extremities of cut shall be moved at regular intervals (± 5 m) to expose the cut line, thereby allowing the operator to remain within the cut width.

Successive lengths of recycled / treated material shall be compacted (each approximately 50m in length).

Rolling shall continue on each section until the maximum achievable density has been reached. Where an integrated compactometer device is utilised normally rolling have to continue until the device indicates that no further density is being achieved over at least 80% of the length of the section (i.e. maximum achievable density has been reached). Should the device indicate a consistent loss of density at any point during primary compaction (as indicated over two successive recording passes), rolling on that section normally has to be terminated and the roller moved forward to start compacting the next section.

After each day's production, the Contractor shall provide the engineer with his process control records of the densities achieved for primary compaction. Where a compactometer device was used an electronic copy of the data file containing detailed compaction records for the day's work shall be provided to the engineer. As a minimum, the records shall include the number of passes made on each section of every cut made by the recycling machine, the compaction achieved on every cut as well as the following data for each 2m interval along the length of each cut:

- the compactometer reading (where applicable);
- the amplitude of vibration; and
- the advance speed of the roller.

These records will constitute the Contractor's Process Control for primary compaction.

A "roller pass" shall be defined as a single unidirectional pass made by the roller. Where the roller travels forwards and backwards over the same point, it would have made "2 passes".

A "recording pass" is a roller pass where the compactometer readings are stored (recorded) and used for comparison purposes. Recording passes are always in one direction of travel only. Recordings shall be made commencing with the first pass and every alternative subsequent pass that is made (i.e. 1, 3, 5, 7, etc.)

The primary compaction process shall follow at the same rate as the recycling operation. The Contractor shall ensure that a sufficient number of rollers are available to achieve this.

(d) Final levels and secondary compaction

- (i) After completing the primary compaction on all adjacent cuts that make up the width of pavement that is recycled in one shift, the surface shall be pre-shaped and final levels cut before final compaction is applied. Pre-shaping shall address the lateral shift of material resulting from the surface inclination (cross-fall). The moisture in the layer shall be controlled during this process. No roller will be allowed onto the layer during the pre-shaping process to prevent the lamination phenomenon (biscuiting) occurring,

Secondary compaction shall then be applied using the smooth-drum vibrating roller operating in low amplitude vibration mode. The outer cut extremities shall be exposed as a guide for the roller operator to ensure that the

compaction effort is directed only on to the recycled material (thereby preventing any "bridging across" from the unrecycled pavement).

B3513 REMEDIAL WORK

Should final mixing or compaction not be completed within the time limits specified in subclause B3505(g), or the layer be damaged, but subject to the provisions of clauses 1220 and 3306(c) of the Standard Specifications, the layer shall be ripped up, broken down and all oversize lumps removed. The procedures outlined in subclauses B3505(d) and (e) shall then be repeated at the contractor's expense, adding half the amount of bitumen originally specified for the initial application.

B3514 PROTECTION AND MAINTENANCE

(a) Trafficking the completed layer

(i) Cementitious stabilization

Under no circumstance shall traffic be allowed to travel on layers of cement stabilized material.

(b) Maintenance of the stabilized layer

Until the surfacing is applied, the Contractor shall maintain the surface integrity of the new layer by deploying staff on a daily basis to visually monitor all sections under traffic and take immediate action as soon as signs of raveling are detected. Such action shall include the local application of dilute emulsion (applied by hand using a large paint brush) or the application of a further fog spray.

Where damage occurs as a consequence of the surfacing not being applied within the time limits specified in clause B3513 (c) below, the Employers Agent shall have the right to summarily reject the affected layer and the Contractor will have no recourse for the costs he incurs in removing the layer and replacing it with fresh stabilized material."

PART C MEASUREMENT AND PAYMENT

C5.1.5 In-situ treatment of roadbed in hard material

ADD THE FOLLOWING:

The unit of measurement shall be the cubic meter of material treated in-situ as specified. The quantity shall be calculated from the authorized dimensions of the in-situ treatment.

The tendered rates for items C5.1.5.1 and C5.1.5.2 shall include full compensation for ripping or for drilling and blasting, shaping, scarifying, sizing, mixing of in-situ and imported material if required, processing and compacting the material as specified.

Payment shall distinguish between in-situ treatment by ripping only and in-situ treatment by drilling and blasting.

REPLACE ITEM C5.1.5.1 AS FOLLOWS:

BC5.1.5.1	In-situ treatment of 150 mm base layer by ripping, stabilizing and compact to 97% MDD	cubic meter (m3)
-----------	---	------------------

REPLACE THE FIRST PARAGRAPH WITH THE FOLLOWING:

"No additional or extra over payment shall be made for stabilization work in restricted or confined areas."

Item**C5.4.1 Chemical stabilization extra over un-stabilized compacted layers**

REPLACE THE FIRST PARAGRAPH WITH THE FOLLOWING:

"The unit of measurement shall be the cubic meter of stabilized material, the quantity of which shall be determined in accordance with the final in-situ authorised dimensions of the layers treated as instructed by the Employers Agent. Additional material Pre-shaped to allow for finishing by cutting only will not be included in the measurement."

ADD THE FOLLOWING TO THE PAYMENT PARAGRAPH:

"The tendered rate shall also include full compensation for working in restricted areas on top of and alongside culverts where necessary."

Item**BC5.4.5 Chemical stabilizing agent**

REPLACE THE THIRD PARAGRAPH WITH THE FOLLOWING:

"Subject to the provisions of clause 1220, the quantity of stabilizer will be determined in accordance with the authorised rate of application and layer dimensions. Extra stabilizer added for wastage and higher pre-shaping levels will not be included in the quantity."

REPLACE ITEM 35.07 AS FOLLOWS:

"Item	Unit
BC5.4.7 Bituminous stabilization:	
(a) By conventional construction methods using bitumen emulsion (extra over unstabilized compacted layer)	cubic metre (m ³)
(b) By in-situ recycling:	
(i) Using bitumen emulsion.....	cubic metre (m ³)
(ii) Using foam bitumen.....	cubic metre (m ³)

The unit of measurement shall be cubic meter of materials stabilized. The quantity shall be determined in accordance with the authorised dimensions of the completed layer.

The tendered rate for bituminous stabilization shall include full compensation for breaking up the existing pavement layer, including existing bituminous surfacing where applicable, to a specified depth, breaking down and preparing the material, mixing in of the stabilizing agent(s) as specified, placing and compacting the material as well as protection and maintenance of the layer, conducting control tests, measuring and demarcating the work where layers are reprocessed partly and protecting the adjacent pavement including its repair should it be damaged.

Material which is temporarily bladed to windrow for the removal of an underlying layer and then bladed back and compacted, will be classified as in-situ reconstruction and paid for under this item.

The tendered rate shall exclude surface enrichment as specified in subclause B3511(d)(iv) which shall be paid for under item B35.16."

Item**Unit**

BC5.4.8 Bituminous stabilizing agent:*REPLACE SUBITEM (c) WITH THE FOLLOWING:*

"(c) 70/100 penetration-bitumen used in foaming process..... ton (t)"

Item	Unit
-------------	-------------

BC5.4.9 Additive for bituminous stabilization:*REPLACE THE DESCRIPTION OF SUBITEM (a) WITH THE FOLLOWING:*

."(a) Cement (CEM II (32.5) N) ton (t)"

ADD THE FOLLOWING ITEMS:

Item	Unit
-------------	-------------

B35.14 Extra over subitem 34.01(d) for complete modification of the gravel base as specified in subclause B3503(f) (thickness indicated) cubic metre (m³)

The unit of measurement shall be the cubic metre of gravel base, the physical properties of which have been modified using road lime as specified in subclause B3503(f). The quantity will be calculated in accordance with the authorised dimensions of the base treated as instructed by the Employers Agent.

The tendered rate shall be extra over the rate tendered for subitem 34.01(d) for constructing the unstabilized layer and shall include full compensation for the complete processing of the base as specified in subclause B3503(f).

The road lime will be paid for under item 35.02.

Item	Unit
-------------	-------------

B35.15 Establishment of bitumen emulsion or foam bitumen recycling/milling machines on site lump sum

The tendered lump sum shall include full compensation for the provision of any number of recycling machine(s) on the site, moving on site and the subsequent removal thereof.

This work shall be paid for by way of a lump sum, 75% of which will become payable when all the equipment is on site and the first section of roadway has been recycled. The remaining 25% will become payable after all the in-situ recycling work has been completed and the equipment has been removed from the site.

Payment will not distinguish between the number of machines provided on the site simultaneously or the number of times a machine is brought onto and/or removed from the site or as a replacement for defective plant.

All recycling machine movements needed on site shall be included in the rate for this item.

Item	Unit
-------------	-------------

B35.16 Surface enrichment square metre (m²)

The unit of measurement shall be square metre of completed surface enriched area completed.

The tendered rate shall include full compensation for supplying the diluted bitumen emulsion required, the application of the diluted bitumen emulsion and the slushing of the layer using an appropriate pneumatic tyre roller."

ADD THE FOLLOWING NEW PAYMENT ITEMS:

Item	Unit
B35.17 Sampling of in situ material for mix design procedure	Number (No)

The unit of measurement shall be the number of positions for sampling of in situ material for the mix design procedure.

The tendered rate shall include full compensation for all costs to make available, operate and to transport the recycling machine and other equipment to the sampling position. To provide the required traffic accommodation in terms of section B1500. The tendered rate shall further include full compensation for breaking up the pavement for sampling and temporary patching the disturbed road way by adding make-up material, watering, compacting and surfacing with a cold asphalt material. The tendered rate shall also include full compensation for all transport, labour and other incidentals required for the sampling process.

Item	Unit
B35.18 Removal from site of surplus material	cubic metre (m³)

The unit of measurement shall be the cubic metre of surplus material removed from site. The quantity shall be taken as 70% of the loose volume measured in trucks. Accurate load records shall be kept on site and submitted to the Employers Agent on a daily basis.

The tendered rate shall include full compensation for gathering the surplus material by windrowing or pushing it into heaps, for loading and transporting to a designated spoil or stockpile site including haul for a free haul distance of 1km, for offloading and either spreading the material or placing in neat stockpiles. It shall further include for all labour, plant, equipment and incidentals required to remove the material as specified."

Item	Unit
-------------	-------------

B35.19 In situ recycling

- (a) Chemically stabilized sub-base layer compacted to 95% of modified AASHTO density, using:
- (i) Non-cemented material (150 mm layer thickness)..... cubic metre (m³)
 - (ii) Cemented material (150 mm layer thickness) cubic metre (m³)
- (b) Chemically stabilized sub-base layer compacted to 97% of modified AASHTO density, using:
- (i) Non-cemented material (150 mm layer thickness)..... cubic metre (m³)
 - (ii) Cemented material (150 mm layer thickness) cubic metre (m³)

The unit of measurement shall be the cubic metre of in situ recycled pavement layer, the quantity of which shall be calculated in accordance with the authorized dimensions of the completed layer.

The tendered rate shall include full compensation for setting out the works, preparing and providing the production plan, preparing the existing road surface where required, breaking up the existing pavement layer to the specified depth, breaking down and preparing the material utilizing a in situ recycling machine, spreading and mixing the stabilizing agent but excluding the cost of supplying the stabilizing agent, any extra water required, placing and compacting (primary and secondary) the material, cutting final levels as well as the protection and maintenance of the layer, conducting process control and daily monitoring, measuring and demarcating the work where layers are reprocessed partly, protecting the adjacent pavement and its repair should it be damaged.

It shall further include for all labour, plant, equipment and incidentals required to in situ recycle the layer as specified.

The engineer reserves to himself the right to vary the thickness of the layer to be stabilized by up to 20 mm, and the contract rate for this work shall not be amended by such change.

The tendered rate shall include full compensation for breaking down the material to comply with the specified grading requirements.

Item**Unit****B35.20 Extra over item B35.19 for adding extra material:**

- (a) Sub-base layer (G6) cubic metre (m³)

The unit of measurement shall be a cubic metre of material added on the instruction of the engineer, which quantity shall be taken as 70% of the loose volume measured in trucks, unless instructed by the engineer that the quantity be determined by way of cross-sections.

The tendered rate shall include full compensation for procuring, adding and spreading the material to the existing pavement layer to be in situ recycled, and for haul over a free haul distance of 2,0 km except for material obtained from commercial sources where all haul will be deemed to be included. It shall further include for levelling and compacting the material to a nominal density of 95% of the modified AASHTO density.

SECTION B 3600: CRUSHED-STONE BASE**B3602 MATERIALS****a) Requirements for crushed aggregate**

AFTER THE FIRST SENTENCE DELETE THE REMAINDER OF THE PARAGRAPH AND REPLACE WITH THE FOLLOWING:

"The aggregate shall not contain more than 0,1% by mass of unwanted material such as wood, coal or similar organic material.

Aggregates containing mica, such as granite, gneiss, mica schist, pegmatite, sandstone shall not contain more than 2% by mass of free mica, especially muscovite, when assessed by visually separating the particles, or more than 4% by volume when assessed by means of microscopic slides.

Aggregate containing easily detectable quantities (more than 1%) of olivine, serpentine and sulphide minerals such as pyrites and marcasite, must be considered with caution, and may warrant additional evaluation to the satisfaction of the Employers Agent. Argillaceous rocks may only be used if specified in the project specifications, or with the Employers Agent's written approval.

Soft or weathered particles shall be controlled by the Durability Mill Index values specified in B3602(e) Durability.

Provision has been made in clause B8108(b)(iii), calculation, for the determination and calculation of the Apparent Density for aggregates with a total water absorption greater than 1,5%, when total water absorption is determined according to TMH1 methods B14 and B15."

ADD THE FOLLOWING:

"G1 material shall be used for the waterbound macadam base.
G2 material shall be used for the GEMs (also called emulsion-treated bases or ETB)."

c) Grading requirements

REPLACE ENTIRE CLAUSE WITH THE FOLLOWING:

"The target grading, after compaction, shall be as near as possible to the mean of the specified grading envelope listed in table B3602/1 and shall be continuous with no marked gaps or excessive quantities of any particular size. The mean grading of each lot (minimum of 4 but preferably 6 test points per lot) shall conform to the approved target grading plus or minus the tolerances specified in table B3602/4. However, no target grading plus tolerance can be set outside the original grading envelope in table B3602/1."

Table 3602/1

IN TABLE 3602/1 DELETE "85% of bulk relative density" AND REPLACE WITH:

"88% of Apparent Relative Density".

REPLACE THE GRADING SECTION IN TABLE 3602/1 WITH:

Grading	Nominal aperture size of sieve (mm)	Percentage passing through sieve by mass
---------	---	--

		Nominal max size			
		G1	G2	G3	
		37.5mm	37.5mm	37,5 mm	28 mm
	37,5	100	100	100	
	28	86 - 95	86 - 95	86 - 95	
	20	73 - 86	73 - 86	73 - 86	87 - 96
	14	61 - 76	61 - 76	61 - 76	73 - 86
	5	37 - 54	37 - 54	37 - 54	43 - 61
	2	23 - 40	23 - 40	23 - 40	27 - 45
	0,425	11 - 24	11 - 24	11 - 24	13 - 27
	0,075	6 - 10	6 - 10	6 - 10	5 - 12

Note:

Refer to standard COLTO table for COLTO grading if required

REPLACE TABLE 3602/4 WITH:

TABLE B3602/4

Sieve size (mm)	Permissible deviations by mean values (% by mass)		Permissible deviations by individual values (% by mass)	
	Nominal maximum size (mm)			
	37,5	26,5	37,5	28
28	± 5		± 5	
20	± 5	± 5	± 7	± 7
14	± 5	± 5	± 7	± 7
5	± 5	± 5	± 7	± 7
2	± 4	± 4	± 5	± 5
0,425	± 3	± 3	± 5	± 5
0,075	± 2	± 2	± 3	± 3

Note:

Refer to standard COLTO table for COLTO grading if required

ADD THE FOLLOWING NEW SUB-CLAUSE:

“e) Durability

The durability property of aggregates derived from the basic crystalline group shall be assessed by means of the Ethylene Glycol Durability Index. When tested in accordance with the method prescribed in B 8105(g) the Durability Index shall not exceed four.

In addition, the 10% FACT value obtained after soaking in ethylene glycol for four days shall not be less than 50% of that obtained on the unsoaked sample. Where any values are obtained that fall outside the above requirements, a detailed assessment of the quarry shall be undertaken together with a specialist mineralogical evaluation of both the coarse as well as fine fractions in order to assess the long-term durability properties of the material.

For Basic crystalline rocks, Arenaceous rocks, Argillaceous rocks and Diamictites the Durability Mill Index (DMI) shall be less than 125. For all other rock types the Durability Mill Index (DMI) shall not be more than 420, subject to the % passing the 0,425mm sieve not increasing by more than 8 percentage points during the Durability Mill test.”

B3604 CONSTRUCTION**b) Compaction**

REPLACE THAT LAST SENTENCE OF THE FIRST PARAGRAPH WITH:

"The density of the layer shall be tested at each third of the layer thickness."

IN THE FOURTH LINE OF THE FIRST PARAGRAPH, REPLACE THE WORDS "after slushing" WITH "before slushing".

ADD THE FOLLOWING AT THE END OF THE FIRST PARAGRAPH:

"Provision has been made in sub subclause B8108(b)(iii):

Calculation for the determination and of the apparent density for aggregates having a total water absorption exceeding 1,0% when determined or according with TMH methods B14 and B15."

c) Surfacing preparation of the base

REPLACE THE FINAL PARAGRAPH IN SUBSUBCLAUSE 3604(C)(I) WITH:

"Slushing of the base, is compulsory and shall be carried out within 48 hours after completion of the compaction. Even if the specified density is achieved without slushing or before completion of the slushing process, the full slushing process must still be completed."

DELETE SUB-SUB-CLAUSE (II) MULTI-STAGE PROCESS (WATER OR SLURRY ROLLING).

REPLACE THE HEADING OF SUBCLAUSE (g) WITH THE FOLLOWING:

"(g) Work in restricted areas"

B3605 PROTECTION AND MAINTENANCE

REPLACE "moisture content of the layer" IN THE FIRST PARAGRAPH WITH "moisture content of the upper 50mm of the layer."

ADD THE FOLLOWING TO THE END OF THE SECOND SENTENCE:

"as determined according to TMH 1 method A7."

B3607 QUALITY AND WORKMANSHIP

DELETE "8200 or" IN THE SECOND PARAGRAPH.

B3608 MEASUREMENT AND PAYMENT

Delete the first paragraph and replace it with the following:

"Note: No additional or extra over payment shall be made for work in restricted or confined areas."

Item

Unit

B36.01 Crushed-stone base:

ADD THE FOLLOWING SUBITEM:

"(g) Constructed from type G1 material obtained from approved commercial source, bituminous stabilized and

compacted to 88% of apparent relative density (E1)
 (layer thickness indicated).....cubic metre (m³)"

ADD THE FOLLOWING TO THE PAYMENT PARAGRAPH:

"The temporary stockpiling of material shall not be paid for separately and full compensation shall be deemed to have been included in the rates tendered for the various payment items in which the material is to be used."

The unit of measurement shall be the cubic meter of completed crushed-stone base in place and compacted to the specified density. The quantity shall be calculated from the net authorised dimensions of the layer as shown on the drawings or prescribed by the engineer. No adjustments shall be made to the net specified dimensions for level and thickness tolerances, overbuilding and/or other wastage.

AMEND THE DESCRIPTION OF ITEM 36.03 AS FOLLOWS:

"Item	Unit
B36.03 Crushed-stone base trial section (thickness indicated) constructed in accordance with the provisions of clause 3603	cubic metre (m³)"

REPLACE THE FIRST MEASUREMENT AND PAYMENT PARAGRAPH WITH THE FOLLOWING:

"The unit of measurement shall be the cubic metre of completed trial section approved by the engineer."

ADD THE FOLLOWING ITEMS:

"Item	Unit
B36.16 Granular emulsion mix (GEMs) constructed from type G2 material obtained from commercial sources and compacted to 102% of modified AASHTO density, nominal maximum size of stone 37,5 mm.....	cubic metre (m³)

The unit of measurement shall be the cubic metre of completed granular emulsion mix in place and compacted to the specified density. The quantity shall be calculated from the authorised dimensions of the layer as shown on the drawings or prescribed by the engineer.

The tendered rate shall include full compensation for mixing, placing and preparing the final surface of the GEMs layer. It shall also include compensation for hauling the aggregates over an unlimited free-haul distance from commercial sources and for correcting the layers, as well as for testing, protecting and maintaining the work as specified."

SECTION B3700: PLANT-MIXED PAVER-LAID PAVEMENT LAYERS

B3701 SCOPE

ADD THE FOLLOWING:

"This section also covers the selection and supply of materials, mixing and processing of plant-mixed bitumen emulsion stabilised materials. The TG2 Guideline, 2nd addition, May 2009 is referenced."

B3702 MATERIALS

(a) Stabilizing agents

ADD THE FOLLOWING:

"(vi) Bituminous stabilizing agents

The bitumen stabilising agent for this project shall be 60% anionic stable-grade bitumen emulsion produced from 70/100 road-grade bitumen complying with the SABS 307 specification.

(vii) Fillers

Where the relevant mix design indicates the use of an active filler to enhance the durability properties of the stabilised material, the stabilising additive shall be one of the following agents depending on the outcomes of mix design results:

(1) Road Lime

Road lime shall conform to the requirements of SABS 824: Lime for soil stabilisation, and the packaging shall bear the SABS mark.

(2) Portland Cement

Portland cement shall comply with the requirements of SABS ENV 197-1: 'Cement Composition, specifications and conformity Criteria Part 1: Common Cements'. The cement to be used for bitumen emulsion stabilisation shall be CEM II 32,5N"

The maximum application rate of active filler shall be 1% by mass or as directed by the Employers Agent."

(b) Aggregates

ADD THE FOLLOWING SUBSUBCLAUSE:

"(1) Recovering of asphalt materials

Where the existing surface consists of asphalt surfacing, it will be milled off to depths indicated by the Employers Agent and the recovered material shall be transported to carefully controlled stockpiles for possible re-use on this contract for the bituminous stabilised base layer.

Reclaimed asphalt material, deemed to be unsuitable for bitumen stabilisation due to the nature of the existing asphalt surfacing, or where the surfacing is too thin or variable, shall be transported to a separate stockpile for future use as gravel material.

(2) Re-use of recovered asphalt materials

Materials for the plant-mixed bituminous stabilised base shall be obtained from approved stockpiles of reclaimed asphalt pavement, screened and blended with new G2 imported aggregate from commercial sources. The quality of the G2 material shall meet the requirements of Table 3602/1 of the Standard Specification. The mix should comply with the grading envelope for BSM1 - emulsion treated materials, Table B37.02/1 below. The blending ratio will be determined experimentally on site for optimum reuse of reclaimed asphalt. The limitations of clause 3402(a) last paragraph will apply.

Table B37.02/1

Sieve Size (mm)*	Percent Passing*
50	100
37,5	87-100
26,5	77-100
19,5	66 - 100
13,2	67 - 100
9,6	49 - 100
6,7	40 - 100
4,75	35 - 95
2,36	25 - 78
1,18	18 - 65
0,600	12 - 54
0,425	10 - 50
0,300	8 - 43
0,150	3 - 30
0,075	2 - 20

*Reference: TG2 Figure 4.2 as amended

In addition, the material to be stabilised shall conform to the following requirements:

Table B37.02/2

Test or Indicator	Value
Soaked CBR*	>80%
Plasticity Index*	<10
Grading Modulus	1,75 min. to 2,5 max

*Reference: TG2 Table 3.2"

(e) Water

ADD THE FOLLOWING:

"Water used for diluting emulsions shall be clean and free from so many salts as will break the emulsions during dilution, and shall be tested for compatibility with the prescribed stabilizing agent."

B3703 REQUIREMENTS TO BE MET BEFORE A PAVEMENT LAYER MAY BE CONSTRUCTED

ADD THE FOLLOWING SUBCLAUSE:

"(a) Composition of bitumen emulsion treated material

The rate of application of bitumen emulsion shall be governed by the materials to be used.

The minimum requirements of the treated material on test specimen sizes of BSM1 as per the TG2 Guideline using testing methods 3, 4 and 5 shall be:

Table 3703/1

Sample – diameter	Test Parameter	Minimum	Maximum
-------------------	----------------	---------	---------

100 mm	Unconfined Compressive Strength at 100% of modified AASHTO density	1 200 kPa	3 500 kPa
100 mm	Indirect Tensile Strength at 100% of modified AASHTO density (equilibrium)	225 kPa	
150 mm	Indirect Tensile Strength at 100% of modified AASHTO density (equilibrium)	175 kPa	
100 mm	Indirect Tensile Strength at 100% of modified AASHTO density (wet)	100 kPa	

The application rate of bitumen emulsion will be determined from mix design procedures described in TG2 Guideline for 'Level 2' mix designs, conducted on the various blends and the residual bitumen will vary between a minimum of 1,0% and maximum of 3,0% (by mass). The Employers Agent will carry out these mix designs and determine the required binder content. A nominal application rate of 1,0% (by mass) of cement or lime shall be included as an active filler for the bitumen emulsion."

ADD THE FOLLOWING SUBCLAUSE:

"(b) Setting-out and control of the work

The contractor shall programme his operations so that the paving work progresses in a logic and systematic manner.

The Contractor shall establish his own reference and level beacons for the setting-out and control of the works. The existing horizontal and vertical alignment shall be retained and only minor modifications made to the vertical alignment, as described below.

The Contractor shall establish a series of level control poles placed at a constant offset on either side of the road at 20 m intervals. At each 20 m location, the Contractor shall record the existing road surface levels at the center-line and at the dividing lines between the lanes or as directed by the Employers Agent on either side of the Centre-line and prepare a series of graphs (for sections not less than a section length) with the recorded levels plotted at an exaggerated scale against the km distance. Final levels for the new stabilised layer shall be selected in accordance with a 'best-fit principle, taking into account the following:

- the required camber or super-elevation details at each location;
- the minimum requirements governing changes in grade (longitudinal grade line);
- the thickness of the existing base layer; and
- the existing levels of footways plus accesses to properties.

The Contractor shall select the best-fit design levels and these proposals shall be delivered to the Employers Agent (both as a schedule of longitudinal grade, cross-fall and final surface levels, as well as a drawing with the design lines superimposed on the existing levels) for approval or amendment at least two weeks before paving work is scheduled to commence on any specific section.

The Employers Agent will take control measurements to determine the accuracy and adequacy of the reference/control beacons, and may instruct the Contractor to correct any faulty work and to take and provide such additional measurements and details as may be deemed necessary. Survey work will not be measured and paid for separately and compensation for any work involved in staking, setting out, taking levels, determining the final surface elevations and transferring these design levels on to the level control poles (including the cost of all labour materials and reinstatement if required for any reason) will be deemed to be covered by the rates tendered and paid for the various items of work included in this contract. No payment will be made for any inconvenience or delay caused by compliance with these requirements."

ADD THE FOLLOWING:

“The bitumen stabilising agent shall be mixed into the aggregate using plant specifically developed for that process as described in Chapter 6.4.1 of the TG2 Guideline.

No mixing shall be undertaken if the temperature of any of the aggregate materials that will be used in the mix is less than 5°C. The temperature of the material shall be measured not less than 150 mm below the surface of the stockpile. No mixing shall commence if the threat of rain is present.

Bitumen emulsion treated material may only be stockpiled if the conditions set out in TG2 Guideline Chapter 2.6.1.1 are met.

The mixing plant shall be capable of thoroughly mixing the material, blending the bituminous stabilising agent, active filler and water in approved pre-selected proportions and rates.

Care shall be taken to prevent segregation and excessive loss of moisture between the time the materials are mixed and when they are compacted on the road.”

(b) Spreading**ADD THE FOLLOWING:**

“The choice of paver shall take into account the constraints imposed by paving width and thickness of the layer as described in Chapter 6.4.3.1 of the TG2 Guideline.

The contractor shall take note of the limitations of paving >200 mm layers as set out in the TG2 Guideline, Chapter 6.4.3.3, and use the trial section to overcome the limitations. Paving of a BSM-emulsion treated base shall be restricted to a single layer.”

(c) Compaction**ADD THE FOLLOWING SUBSUBCLAUSE:**

“(iv) In plant mixed paver laid base

Paving and compaction shall be in accordance with Chapter 6.4.3.4 of the TG2 Guideline with respect to paver set up, paving the layer, construction joints and compacting the paved BSM1 layer.

The BSM layer shall be compacted to an average density of 100 % modified AASHTO density with not less than 98% modified AASHTO per single test.

Before final compaction, the surface of the emulsion treated base layer shall be enriched with a 1:1 mixture of water from an approved source and 60% Anionic stable grade bituminous emulsion at an application rate of 0.4 to 0,5 l/m². Payment for surface enrichment shall be done according to pay item B37.06.”

(d) Construction joints**ADD THE FOLLOWING:**

“The number of construction joints shall be minimised as far as possible within the daily production rate and accommodation of traffic constraints.”

ADD THE FOLLOWING SUBCLAUSE:**“(f) Plant and Equipment**

The new stabilized base shall be constructed by in-plant mixing and laid by a paver.

(i) Mixing Plant

Only an approved purpose built mixing plant like a high energy pugmill type mixer may be deployed on the site. As a minimum the mixing plant shall have the following features:

- Able to accurately blend pre-determined proportions of different input materials whilst simultaneously adding the correct amount of bitumen stabilizing agent, water and active filler.
- Consistently producing a homogenous product

(ii) Paver and Screed

Only an approved purpose built paver may be deployed on the site. As a minimum the paver shall have the following features:

- A screed attached to the paver, which uniformly pre-compact the material to the highest achievable level of density.
- A screed attached to the paver, which is equipped with tamper bars and vibrators to effect compaction.
- Paver with tracks and not wheels to avoid damage to the geogrid when paving on top.

(iii) Compaction Equipment

The rolling guidelines as set out in TG2 Guideline will apply and the contractor shall determine through the trial section the best technique and equipment to achieve the desired compaction density.

As in the guideline TG2, the following rollers for compacting the paved material will be used:

(a) Primary roller

Primary compaction shall be undertaken using a tandem-smooth-drum vibrating roller static mass not less than 10 tons and not more than 12 tons. The roller shall be fitted with an integrated "intelligent compaction system" (e.g. Hamm HCQ GPS Navigator system, or similar) having the following features:

- an accelerometer device fitted to the frame that continuously measures the rebound emanating from the force applied by the vibration (known as a compactometer);
- a system that continuously determines the location of the roller within an accuracy of 0.1 m in the horizontal plane (a device mounted on the roller that reads signals emanating from satellites (GPS system) or fixed stations (land-based laser system));
- an on-board micro-processor that simultaneously receives, stores and analyses the continuous data streams emanating from the compactometer and the location device. The data stored shall include the following information for each pass made by the roller at intervals not exceeding 2 m in the longitudinal direction (direction of travel) over the width of the roller:
 - the time that the data is stored,
 - the advance speed of the roller and direction of travel,
 - the amplitude of the applied vibration and compactometer reading.
- a display monitor mounted in the cab of the roller that shows the path of the roller for a minimum distance of 50 m, colour-coded to show (for intervals not exceeding 2.0 m) whether the

reading from the compactometer is increasing, remaining constant or decreasing;

- a “flash drive” facility for downloading a complete record of the day's compaction, and
- software for analysing the compaction data on a remote computer. Such analyses shall include:
 - summary of data for specified lots (lengths varying from 2.0 m to 100.0 m) for each strip (cut width) compacted, and
 - summary of data for specific lots for the full half width of road, including the facility to plot contours of compactometer values.

(b) Roller for finishing

A pneumatic-tyred roller with a “load per tyre” rating >1750 kg shall be used to finish off the new layer (mild slushing) and for final compaction.”

ADD THE FOLLOWING SUBCLAUSE:

“(g) Construction in confined areas

Some construction work will be carried out in confined areas. No additional payment will be made as described for ‘restricted areas’ in Clause 3508 of the specifications. The method of construction in these confined areas will depend largely on the contractor's constructional plant. However, the contractor shall note that measurement and payment will be in accordance with the specifications and drawings irrespective of the method used, and that the rates and amounts tendered shall be deemed to include full compensation for any special equipment or construction methods or for any difficulty encountered in working in confined areas and narrow widths, and at or around obstructions, and that no extra payment will be made nor will any claim for payment be considered on account of these difficulties.

Where the construction of paved bitumen stabilised materials (BSM) is to be carried out at existing structures or alongside kerbs and channels and/or traffic islands, no separate payment will be made for working in close proximity to these elements and the contractor shall include for having to work close up to the elements in his tendered rates for the construction of the BSM layers.”

ADD THE FOLLOWING SUBCLAUSE:

“(h) Daily production plan

Prior to the start of work every day, the Contractor shall provide the Employers Agent with a production plan detailing his proposals for the forthcoming day's work. As a minimum, this production plan shall include:

details of the section of road to be milled and or paved during the day, the start and end stake values, the sequence of cuts and overlap details for all longitudinal joints”

ADD THE FOLLOWING SUBCLAUSE:

“(i) Opening to traffic and protecting the surface of the new layer

The Contractor shall organise his daily operations such that sufficient time is allowed for the surface of the completed layer to dry back to a moist state after finishing.

Where the constructed sections show signs of travelling, the cause and extent of such travelling shall be investigated and, based on the results of these investigations, the Employers Agent will determine the required remedial measures to be taken by the Contractor.”

B3705 CURING

ADD THE FOLLOWING:

“For bitumen stabilised layers, the surfacing layer shall only be placed on the completed layer once the moisture content in the upper 100 mm of the layer is less than 50% of the optimum moisture content.”

B3706 PROTECTION AND MAINTENANCE

REPLACE THE FIRST AND SECOND PARAGRAPHS WITH THE FOLLOWING:

“The Contractor shall protect the completed base layers from all damage until the surfacing is applied. Any damage occurring to the completed base or any defects which may develop due to faulty workmanship, shall be made good by the Contractor at his own expense and to the satisfaction of the Employers Agent.

Repairs shall be made in a manner approved by the Employers Agent to ensure an even and uniform surface.

During working and construction of the base, precautionary measures shall be taken to prevent kerbs and channeling and concrete work from being damaged or shifted. Care shall be taken to protect all precast units from chipping and breakage. Concrete kerbing and channeling, as well as other structures adjacent to the road, shall be protected against staining by bitumen. Any work stained by bitumen shall be broken down and replaced, unless all such bitumen is completely removed so as not to show any stains. Painting over stained work will not be allowed.

Where construction is carried out adjacent to existing structures, care shall be exercised to avoid damage to concrete elements, expansion joints, manholes, catch pits, etc. Damage caused to any element forming part of the permanent works shall be repaired at the Contractor's cost.

The Contractor shall make good careless or excessive demolition at his own expense. New construction shall be in accordance with the drawings and the Specifications. The Contractor will be held responsible for the timely adjustment of all covers and frames in advance of surrounding construction, whether they are indicated on the drawings or by the Employers Agent or not. No claims for delays arising from the failure of the Contractor to effect the necessary adjustments in good time will be allowed.

Due care shall be exercised when working around existing gullies or kerb inlets so as not to cause blockages. This shall be achieved either by covering them with steel plates during the recycling process, or by removing all trapped material immediately after the recycling operation.”

B3707 TRIAL SECTION

IN THE SECOND PARAGRAPH, REPLACE THE FIRST SENTENCE WITH THE FOLLOWING:

“Where ordered by the Employers Agent, the Contractor shall execute trial sections in accordance with the directives included under Section 6.7 in the TG2 Guideline. Trial sections shall be at least a section length of half the road width and located to suit the Contractor's programme of work. During the trial section, the contractor shall also demonstrate that compliance with the level and thickness tolerances can be achieved, as well as the compaction dry densities specified “

B3708 TOLERANCES

ADD THE FOLLOWING:

"Routine inspection and tests will be carried out by the Employers Agent to determine the quality of the materials and workmanship for compliance with the requirements of this section."

(a) Construction tolerances

ADD THE FOLLOWING:

"Measurements for construction tolerances shall be taken immediately after completion of the layer and before opening to traffic. Where the existing granular base abuts kerbs or channels, the new work shall extend to the edge of these facilities unless otherwise specified by the Employers Agent. The new base shall be constructed in sympathy with the existing levels, cross-section profile and cross-fall, unless otherwise specified."

ADD THE FOLLOWING SUBCLAUSE:

"(c) Bituminous stabilizing agents

The average rate of application of bitumen emulsion as measured from consumption records shall be within 0,3 percentage points of the specified application rate."

ADD THE FOLLOWING SUBCLAUSE:

"(d) Chemical stabilising agents

The average application rate of cement or lime used for chemical stabilisation, and as an active filler for bitumen stabilisation, as determined from application records shall be within 0,1 percentage points of the specified application rate."

ADD THE FOLLOWING SUBCLAUSE:

"(e) Uniformity of mix of bituminous stabilized mixes

For each day's work, two bulk samples of approximately 50kg mass shall be taken prior to being compacted and retained in sealed bags. The samples shall be transported to the laboratory and used immediately to manufacture specimens for Indirect Tensile Strength (ITS) testing. The procedure recommended in paragraph 6.8.3 of the TG2 Guideline shall be followed to manufacture and cure the specimens and determine the relevant ITS values. The minimum ITS values as specified in Table 3703/1 must be achieved.

At least two full samples of the bitumen stabilised material shall be taken daily and tested for compliance. Full records of the sample position, time and date of sampling and results, shall be kept by the contractor and made available to the Employers Agent."

B3709 ROUTINE INSPECTION AND TESTS

REPLACE THE ENTIRE CLAUSE WITH THE FOLLOWING:

"Routine inspection and tests will be made to determine the quality of the materials and workmanship for compliance with the requirements of in plant mixed paver laid bitumen stabilized materials.

The quality of the completed work shall be determined from the results of tests that show:

- The relevant strength of the material in the bitumen stabilized layer; which will be evaluated by the relevant ITS specifications,
- The dry density of the compacted material; and
- The thickness of the completed layer.

The statistical judgement schemes to be used to determine whether the in-situ density requirements specified are being complied with shall be those set out in Section 8200 (Scheme 1). Judgement plan A will be applied for judging measurements of the levels and thicknesses of the pavement layer and Judgement plan B for judging measurements of in-situ densities.

In-situ density measurements shall be taken after completing the recycling operation. Nuclear density gauges can be used on site to determine density. As the recycled mix will contain bitumen, the measured moisture content may be overstated, resulting in lower dry densities being reported. A sample for determining the moisture content in the laboratory shall be taken from each test location and be used in the calculation of the dry density. Random standard sand replacement tests (ASTM D1556 or AASHTO T191) shall also be carried out and compared with the results from the nuclear density gauge.

Despite acceptance of the above properties by the statistical methods, the work submitted may be rejected when other properties (which are not controlled by statistical methods) fail to comply with the requirements of the specifications. Where there are other causes for rejection such as obviously defective workmanship, excessively variable properties, visible signs of poor workmanship, or similar considerations which constitute sufficient ground for rejecting the work without any further testing, the Employers Agent may reject the work. Indirect tensile strength shall not be controlled by statistical methods.

Control samples on the bitumen emulsion or bituminous binder shall be taken daily by the contractor. The date of sampling, and batch number of the binder shall be recorded and kept by the contractor, and made available to the Employers Agent. Data from these samples may be used in quality control by the Employers Agent."

ADD THE FOLLOWING CLAUSE:

"B3711 WEATHER LIMITATIONS

No mixing work shall be undertaken during misty or wet conditions, nor shall any work commence if there is a risk that it may not be complete before such conditions set in. Similarly, work shall not be undertaken if the ambient temperature is below 5 °C and the temperature of the material being worked is below 5°C. No further work, other than finishing and compaction, shall be permitted if the ambient temperature drops below 5 °C during operations.

The contractor shall take the necessary precautions to ensure that no layer work is undertaken if cold weather is forecast (temperatures below 4°C) for three days following construction. All stabilized layers damaged by frost or ice shall be removed and replaced at the contractor's own cost. The contractor shall allow for these requirements in his programme and no claims in this regard shall be considered."

ADD THE FOLLOWING CLAUSE:

"B3712 OPERATIONAL LIMITATIONS

The Contractor shall arrange his milling and paving operations in such a manner as to minimize the disruption to public traffic. Rehabilitation operations shall be carefully planned and executed in accordance with the following limitations:

- (a) Individual work areas shall be clearly demarcated with traffic signs, delineators and traffic control facilities as specified.
- (b) The individual work areas shall be planned in such a manner that all paved pavement layers are completed as specified in Clause B3704 (i) for each day's production.
- (c) Within individual working areas, the Contractor shall make adequate provision for drainage of water from the road surface during construction. No separate payment will be made for the provision and use of standby pumps, dewatering equipment or cutting of drainage slots and/or channels to effectively drain the roadway surface were instructed by

the Employers Agent in the interests of safety for the travelling public. The Contractor shall make due allowance for this drainage in this tendered rate.

(d) Delineators shall be placed along any longitudinal step exceeding 40 mm between adjacent halves of the road. The maximum allowable step within a lane open to traffic shall be restricted to 0 mm. If, due to plant breakdown or other unforeseen circumstances, a longitudinal or transverse step higher than 20 mm occurs within a lane, the strip shall be feathered off by means of compacted asphalt over a distance of 500 mm."

ADD THE FOLLOWING CLAUSE:

"B3713 GEO-REINFORCING LAYER

(a) Quality and standard

A mechanical stabilizing or geo-reinforcing layer shall be installed on top of the treated roadbed after the existing surface and base have been milled off and the roadbed treated. The quality of the stabilizing layer shall conform to the following:

- i) The mechanical stabilization element shall be a polypropylene geogrid manufactured in accordance with a management system which complies with the requirement of BS EN ISO 9001:2008. If required by the Employers Agent, the Contractor shall provide evidence of the manufacturer's certification of its Quality Assurance System.
- ii) The geogrid class shall be 'punched and stretched' to create ribs having orientations in three equilateral directions. The resulting triangular-shaped apertures are defined by ribs having a high degree of molecular orientation which is continuous through the node.
- iii) The rib pitch shall be 40 mm. The open area aspect ratio shall be 85% or more.
- iv) The isotropic stiffness ratio of the grid, expressed as the ratio of the minimum / maximum radial stiffness at low strain, shall be greater than 0.75 (5)
- v) The junction efficiency shall be 90% (1, 5); aperture stability shall be 610 N.mm/deg at a reference moment of 5.0 kg-cm (2, 5).
- vi) The tension strength at maximum strain of 4% shall be 40 kN/m in each direction at Young modulus of 70 GPa.
- vii) The reinforcing grid shall be inert to all chemicals naturally found in soils and shall have no solvents at ambient temperature. It shall not be susceptible to hydrolysis, shall be resistant to aqueous solutions of salts, acids and alkalis, and shall be non-biodegradable. The reinforcing grid shall have a minimum of 2% finely divided carbon black, as determined by BS 2782: Part 4:Method 452B:1993, well dispersed in the polymer matrix to inhibit attack by ultra violet light.

Notes:

1. Load transfer capability determined in accordance with GRI-GG2 and GRI-GG1 and expressed as a percentage of ultimate tensile strength.
2. In-plane torsional rigidity measured in accordance with US Army Corps of Employers Agents Methodology for measurement of Torsional Rigidity (Kinney, T.C. Aperture Stability Modulus Rev 3.1.2000).
3. Modulus tests carried out within the scope and principle of ISO 10319:1996.
4. All geometrical values are typical
5. Declared at the 95% confidence limits

(b) Construction

- i) Subgrade preparation

The subgrade shall be levelled and treated as directed by the Employers Agent after milling out/excavation of the existing base. The geogrid or stabilizing layer shall be laid flat and level.

ii) Placing of the stabilizing layer/geogrid

Heavy-duty gloves shall be worn when handling the geogrid. The geogrid shall be placed parallel to the center line of the road or as directed by the Employers Agent.

iii) Overlap

The minimum overlap shall be 300 mm and not more than 600 mm. Overlaps shall be secured and maintained during the filling operation. If necessary, this is generally achieved by placing small heaps of the filling material locally over the overlaps ahead of the filling operation. For this specific project the filling operation will mean the laying of the BSM1 material.

iv) Placing the overlay/pavement layer

Care shall be taken to avoid damage to the geogrids. A paver machine with tracks shall be used to avoid damage to the grid. "

B3710 MEASUREMENT AND PAYMENT

REPLACE ITEM 37.01 WITH THE FOLLOWING ITEM:

Item	Unit
B37.01 Stabilized crushed stone G2 base, mixed with RA (reclaimed asphalt) in plant mixed and paver laid, compacted to min 100%(average) of Modified AASHTO density and min 98% (single test):	
(a) 150 mm thick.....	cubic metre (m ³)
(b) 200 mm thick.....	cubic metre (m ³)

The unit of measurement shall be the cubic metre of completed stabilized crushed stone, mixed with RA (reclaimed asphalt), the quantity of which shall be calculated in accordance with the authorized dimensions of the layer as shown on the drawings or as directed by the Employers Agent.

The tendered rate shall include full compensation for procuring, furnishing and placing all materials, which include RA (reclaimed asphalt), including full compensation for compacting, and correcting the stabilized layers, including protecting and maintaining the work, as specified, but shall exclude the provision of the stabilizing agents, fillers and a surface enrichment layer.

The tendered rate shall also include the crushing and screening of the reclaimed asphalt and mixing it with the crushed stone material in an approved plant and for correcting the grading to comply with a BSM1 material as specified in the project specifications.

The tendered rate shall also include full compensation for hauling the material (mixed with reclaimed asphalt) for an unlimited free-haul distance where material is obtained from commercial sources or milling and hauling it from stockpile to the mixing plant to the point on the site where required."

Item	Unit
B37.03 Stabilizing agent	

CHANGE THE UNIT OF MEASUREMENT FOR SUBITEM (e) TO LITRE (l)

“(e) Bitumen Emulsion, 60% anionic stable grade .litre (l)”

ADD THE FOLLOWING TO THE END OF THE FIRST SENTENCE OF PARAGRAPH ONE:

“..., except for item (e) where the unit of measurement shall be litre (l).”

REPLACE ITEM 37.05 WITH THE FOLLOWING:

Item	Unit
B37.05 Trial section of pavement layer.....square metre (m ²)	

The unit of measurement shall be the square metre of paved pavement executed as a Trial Section, as ordered by the Employers Agent. Where the Trial Section is successful, this item shall be measured and paid in addition to the various related work items. Where a Trial Section fails to achieve the specified result for any reason whatsoever, no payment shall be affected under this item, nor shall any payment be made under the various related items for the failed work.

The tendered rate shall include full compensation for all additional costs incurred as a consequence of designating the section of work a Trial Section, including all costs relating to low productivity. The tendered rate for the trial section shall also include for constructing the base layer on top of the mechanical stabilizing layer/ geogrid layer."

ADD THE FOLLOWING PAYMENT ITEM:

Item	Unit
B37.06 Surface enrichment.....	square metre (m ²)

The unit of measurement shall be square metre of completed surface-enriched area completed.

The tendered rate shall include full compensation of supplying the diluted bitumen emulsion required, the application of the diluted bitumen emulsion and the mild slushing of the layer using an appropriate pneumatic tyre roller."

ADD THE FOLLOWING PAYMENT ITEM:

Item	Unit
B37.07 Geo-reinforcing layer complete (Triax TX170 or similar).....	square
metre (m ²)	

The unit of measurement shall the square metre of roadbed covered with the reinforcing layer placed, complete as specified and accepted by the Employers Agent.

The tendered rate shall include full compensation for procuring, providing, placing and fixing all materials (irrespective of the quantity of stabilizing layer required), overlapping and cut-offs included, and for all transport, equipment, tools, labour, tying down the layer, supervision and all other cost necessary for installing and protecting the layer until the base layer has been placed. The tendered rate shall also include full compensation for all

special preparatory work required. If it is necessary to repair the roadbed, separate payment will be made therefor under the appropriate items of payment.

SECTION B3800: BREAKING UP EXISTING PAVEMENT LAYERS**B3804 PLANT AND EQUIPMENT****(a) Milling equipment**

ADD THE FOLLOWING PARAGRAPH:

"No payment shall be made for moving the milling machine on the site."

B3805 CONSTRUCTION**(b) Milling****(iii) Asphalt**

ADD THE FOLLOWING NEW PARAGRAPH:

"The material originating from the milling of the existing asphalt layers shall become the property of the employer and shall be stockpiled at sites indicated by the Employers Agent. Overhaul on milled material for distances in excess of 1,0 km shall be paid in accordance with item 16.02 of Section 1600."

(vi) General

ADD THE FOLLOWING:

"The requirements for accommodation of traffic during milling operations shall be as specified in Section 1500 of the standard specifications as supplemented by Part B of the project specifications. In particular, the limitations on barricaded length to a maximum of 2,5 km and only during daylight hours are to be taken into account in programming the milling operations. If traffic is to be accommodated over milled areas overnight it shall be a requirement that the vertical longitudinal edge drop-off is not greater than 25 mm in depth and the transverse drop-off at the start and end of each section of work is tapered to a slope not steeper than 1:5 (vertical: horizontal) and all milled areas have been thoroughly cleaned before opening to public traffic. The total length of lane with milled areas open to traffic shall, at any time, not exceed 1,0 km even if the sections of milled areas are not contiguous.

Where milling depths in excess of 25 mm are prescribed, the contractor shall have the option for partial milling within the depth limitations described above and the work area limitations specified for accommodation of traffic. The payment category, according to depth of milling, shall remain applicable to the prescribed depth. The contractor shall programme the works to ensure that no areas with milled depth in excess of 25 mm will remain exposed overnight. The contractor shall phase the milling operation with the production rates for asphalt backfill and overlays. No standing time will be paid for milling equipment or haulage vehicles where stoppage of the milling operations is necessary to comply with the above requirements.

Where milling is to be done at existing structures, care shall be exercised to avoid damage to concrete elements, expansion joints, nosings to expansion joints, manholes, catchpits etc. Damage caused to any element forming part of the permanent works shall be repaired at the contractor's cost.

The floor of the milled excavation shall be cleaned by brooming out all loose materials. The exposed floor of the excavation shall be lightly sprayed with water to identify cracks. The Employers Agent shall be given the opportunity to inspect the milled surface for cracks and loose patches and any cracks and loose patches shall be repaired in accordance with the relevant sections of the specification."

(c) Treatment of pavement excavation floor

ADD THE FOLLOWING:

"Milled surfaces shall be swept clean by brooming out all loose materials. The exposed floor of the excavation shall be lightly sprayed/sprinkled with water to identify cracks. The Employers Agent shall then be given the opportunity to inspect the milled surface for any cracks. All cracks greater than 3 mm in width shall be sealed as specified in Section 4800 of the standard specifications and Section B4800 of the project specifications. A tack coat of 30% stable-grade emulsion shall then be applied to the milled surface and sides of the excavation before the excavation is backfilled or paved with asphalt in layers not exceeding 40 mm compacted thickness."

B3807 MEASUREMENT AND PAYMENT**(a) General****ADD THE FOLLOWING SUBSUBCLAUSE:**

"(vi) Providing the milling machine and moving the milling machine on site

No separate payment shall be made for providing the milling machine on site or for moving the milling machine on site. The size and numbers of milling machines required on site shall be determined by the contractor in accordance with the scope of the work and the approved works programme, noting that approval of the works programme shall be subject to compliance with the accommodation of traffic constraints. Temporary removal of milling machines from site and the re-establishment of the machines shall be subject to the approval of the Employers Agent and shall be in accordance with the approved works programme. No additional payments shall be made for the temporary removal and re-establishment of milling plant."

(b) Overhaul**REPLACE WITH THE FOLLOWING:**

"No overhaul shall be paid on material originating from the milling of the existing asphalt layers, irrespective of whether the contractor intends to utilise the material for recycling or reworking or whether the material is transported to a dump site. The contractor shall include for overhaul in the rates tendered."

DELETE SUBCLAUSE (c) AND REPLACE WITH THE FOLLOWING:

"(c) No additional or extra payment shall be made for work in restricted or confined areas."

(d) Items of payment**Item**

B38.02 Milling out existing bituminous material with an average milling depth

IN THE SECOND PARAGRAPH INSERT THE WORDS "to any location within the site of the works" AFTER "providing milling equipment."

COLTO SERIES 4000: ASPHALT PAVEMENTS AND SEALS

SECTION B 4100: PRIME COAT

B4102 MATERIALS

b) Aggregate for blinding

ADD THE FOLLOWING SENTENCE:

"Blinding of the primed surface with aggregate shall only be permitted to facilitate vehicular access to adjoining properties"

B4103 EQUIPMENT

ADD THE FOLLOWING BEFORE THE FIRST PARAGRAPH:

"Before any storage, dilution or spraying operations commence the contractor has to provide a safety and security and environmental protection method statement for approval of the Employers Agent. All personnel involved, including brooming, prime distributor, storage and production yard operators and labour shall wear the necessary protective clothing. Appropriate fire extinguishers and medical aid devices must be provided in working order. The Employers Agent reserves the right to stop the contractor's operation or order any person from the site who does not adhere to the above."

B4104 WEATHER AND OTHER LIMITATIONS

REPLACE PARAGRAPH (G) WITH THE FOLLOWING:

"(g) When at any position within the layer the moisture content of a granular base layer is more than 50% of the optimum moisture content determined according to SANS 3001 – GR30 In the event of rain after priming, the base shall be allowed to dry out to meet the above moisture content requirement prior to surfacing."

B4106 APPLICATION OF THE PRIME COAT

REPLACE PARAGRAPH (C) WITH THE FOLLOWING:

"The type of prime and application rate best suited for the base shall be determined during construction. The Contractor shall provide about 20ℓ of each prime and apply it at different application rates with a brush on the base. The Employers Agent will then instruct the type of prime and application rate to be used. No payment shall be made for tests to determine the type of prime.

The nominal application rate of the prime shall be 0,7 litre/m².

Unless directed otherwise by the Employers Agent or indicated on the drawings, the edges of the primed surface shall be 150mm wider than the edges of the surfacing. "

ADD THE FOLLOWING SUB-CLAUSE:

"(j) Application in areas treated by reworking and construction of a new base shall be primed using a mechanical distributor complying with sub-clause 4103(a). The edges of the previously constructed or existing surfacing shall be adequately protected by approved means to ensure that an overlap of prime not exceeding 50mm is sprayed onto the previously constructed or existing surfacing."

B4108 TOLERANCES

REPLACE THE FIRST PARAGRAPH WITH THE FOLLOWING:

"The actual spray rates measured at spraying temperature shall not deviate by more than 8.0% from that ordered by the Employers Agent. The Employers Agent may, at his discretion, conditionally accept application rates falling outside this tolerance at reduced payment in accordance with Table B4108/1.

TABLE B4108/1: PAYMENT REDUCTION FACTORS FOR CONDITIONALLY ACCEPTED PRIME COAT

Deviation specified spray rate at spraying temperature. (%)	Payment reduction factor of tendered rate.
±8,0	1.00
±9,0	0.97
±10,0	0.95
±11,0	0.90
±12,0	0.85
±13,0	0.80

Any deviation outside these limits shall not be paid for, however, the Employers Agent shall have the right to instruct the Contractor to make up any deficiency, or blind excessive prime without additional payment. Where so instructed, the material for blinding shall consist of approved, but shall consist of screened 5mm nominal single size aggregate. The use of crusher dust for blinding shall not be permitted. If under-spraying occurs, and it is accepted by the Employers Agent, only the actual quantities applied shall be paid for."

B4109 TESTING

ADD THE FOLLOWING:

"No payment will be made if this condition is not adhered to. The Contractor shall provide, at his cost, representative samples of every batch of prime delivered onto site."

B4110 MEASUREMENT AND PAYMENT

ADD THE FOLLOWING BEFORE THE PAYMENT ITEMS:

"No additional or extra over payment will be made for work in restricted or confined areas."

SECTION B 4200: ASPHALT BASE AND SURFACING**B4202 MATERIALS****a) Bituminous binders****(iii) Homogeneous modified binders***REPLACE THE LAST SENTENCE WITH:*

"The modified binder to be used in the 40mm continuously graded asphalt shall be A-E2.

The homogeneous modified binder shall be manufactured according to the guidelines contained in "Technical Guideline: The use of Modified Bituminous Binders in Road Construction (TG 1-2007): Asphalt Academy". The base bitumen shall conform to SABS 307, or a blend of SABS 307 grades. The type as well as percentage of modifier is not prescribed, however the contractor shall indicate in the Pricing Schedule what polymer he shall be using. The properties of the homogeneous modified binder shall comply with the relevant requirements for binder class A-E2 as listed in table B4202/12.

TABLE B4202/12: PROPERTIES OF POLYMER-MODIFIED BINDER FOR HOT-MIX ASPHALT

Property	Unit	Test Method	Binder Class
			A-E2
Softening Point ¹	°C	MB-17	65-85
Dynamic Viscosity@165°C	Pa.s	MB-18	≤0.6
Force Ductility @ 5°C	N	EN 13703	Report ³
Elastic Recovery @ 15°C	%	MB-4	>60
Storage Stab @ 160°C)	°C	MB-6	≤5
Flash Point	°C	ASTM: D93	≥230
Complex shear modulus: $G^* \sin \delta$ @10 rad/s	°C	AASHTO:TP5	Report
Creep Stiffness	MPa	AASHTO:TP1	Report
Properties after ageing (RTFOT)			MB-3
Diff in Softening Point	°C	MB-17	-2 to +8
Elastic Recovery @ 15°C	%	MB-4	>50
Mass change	%	MB-3	≤1.0
Torsional Recovery @ 25°C	%	MB-5	Report
Dynamic Viscosity @ 165°C	Pa.s	MB-18	Report ²

Notes:

1. The prescribed test method is based on not using stirrers although it has been reported that the use of stirrers has shown no difference in test results. For referencing purposes no stirrers should be used.
2. No limits are given and the values should be recorded for reporting purposes only as they may be used in future specifications.
3. No values given but the test can be used to rank various binders according to their low temperature cohesion properties.

b) Aggregates

ADD THE FOLLOWING PARAGRAPH TO THE INTRODUCTORY DESCRIPTION:

"Asphalt mixes shall be manufactures using different individual single size coarse aggregates fractions and crushed fine aggregates blended to conform to the specified grading requirements. The use of natural sands shall not be permitted.

All aggregate in excess of 5mm shall consist of individual nominal single sized aggregate.

The Contractor shall note that commercial suppliers may not be able to supply all the required single size aggregates, in which instance arrangements will have to be made for additional onsite screening. No additional payment shall be made for screening aggregate. The use of crusher run type materials shall not be permitted, with the exclusion of crusher dust (<5mm)."

(v) Absorption

Add the following sentence:

"In addition, the total binder absorption of the combined coarse and fine aggregate blend shall not exceed 0,5%"

(viii) Grading

*DELETE THE SECOND PARAGRAPH COMMENCING WITH "The target grading..." AND ADD THE FOLLOWING PARAGRAPHS **

"The grading limits for the combined aggregate grading for the asphalt base shall be as specified in table 4202/6: Continuously graded 28m maximum.

The grading limits for the combined aggregate grading for the asphalt surfacing shall be as specified in table 4202/7: Continuously graded medium grade.

(x) Rolled-in chippings

REPLACE TABLE 4202/11 WITH:

TABLE B4202/11

Sieve size (mm)	Chip size - Percentage passing by mass	
	20 mm	14 mm
20,0	100	
14,0	0 – 20	100
10,0	0 – 5	0 – 20
7	0 – 1	0 – 5
0,425	0,5 max	0,5 max

Note:

Refer to standard COLTO table for COLTO grading if required

ADD THE FOLLOWING NEW SUB-ITEM:

"(xi) Moisture content

The moisture content of aggregates, sampled from the cold feed belt, shall not exceed the following limits at the time that it is introduced into the mix:

- Coarse aggregate 2%
- Fine aggregate 4%"

c) **Fillers**

DELETE THE SECOND LAST SENTENCE OF THE FIRST PARAGRAPH AND REPLACE WITH:

"With the exception of stone mastic asphalt, in no instance shall more than 2% by mass of active filler be used in the mixes."

ADD THE FOLLOWING AFTER THE LAST PARAGRAPH:

"For tender purposes the active filler shall be hydrated lime"

B4203 COMPOSITION OF ASPHALT BASE AND SURFACING MIXTURES

IN THE FIRST PARAGRAPH, THIRD LAST LINE, AFTER "or active filler content" ADD:

"or aggregate content"

REPLACE THE FIFTH PARAGRAPH WITH THE FOLLOWING:

"The design of the asphalt mixes shall be in accordance with "Interim Guidelines For The Design Of Hot-Mix Asphalt In South Africa (June 2001)", and appropriate research results. The mix properties and requirements shall be as specified in the project specifications"

The relevant asphalt mixes for the base and surfacing layers shall comply with the requirements in table B4203/1.

REPLACE TABLE 4202/6 WITH:

TABLE B4202/6

	Sieve size (mm)	Maximum nominal size (mm)	
		Continuously graded	
		37,5	28
		Percentage passing sieve by mass	
PERCENTAGE THROUGH SIEVE BY MASS	37,5	100	
	28	86 – 95	100
	20	73 – 86	87 – 96
	14	61 – 76	73 – 85
	10	52 – 68	64 – 79
	5	37 – 54	43 – 61
	2	23 – 40	28 – 44
	1	17 – 32	20 – 35
	0,600		15 – 30
	0,300	9 – 21	11 – 24
	0,150	6 – 17	8 – 19
	0,075	4 – 12	5 – 12
NOMINAL PROPORTIONS BY MASS	Aggregate	95%	94,5%
	Bitumen (grade according to project specifications)	4%	4,5%
	Active filler*	1,0%	1,0%

* Active filler for tender purposes to be hydrated lime.

- Notes:
1. For recycled asphalt the nominal mix ratios of recovered asphalt, new aggregate, new bituminous binders, and active mineral filler to be used for tender purposes, shall be as specified in the project specifications.
 2. Refer to standard COLTO table for COLTO grading if required

REPLACE TABLE 4202/7 WITH:

TABLE B4202/7

		Continuously graded		
		Coarse	Medium	Fine
PERCENTAGE THROUGH SIEVE BY MASS	28	100		
	20	100		
	14	85 – 97	100	
	10	70 – 92	85 – 100	100
	5	50 – 70	56 – 77	66 – 89
	2	27 – 45	33 – 48	42 – 59
	1	21 – 35	25 – 40	31 – 51
	0,600	16 – 28	18 – 32	24 – 40
	0,300	12 – 20	11 – 23	16 – 28
	0,150	8 – 15	7 – 16	10 – 20
	0,075	4 – 10	4 – 10	4 – 12
NOMINAL PROPORTION S BY MASS	AGGREGATE	93,5%	93,5%	93,0%
	BITUMEN (GRADE ACCORDING TO PROJECT SPECIFICATIONS)	5,5%	5,5%	6,0%
	ACTIVE FILLER	1,0%	1,0%	1,0%

Note:

Refer to standard COLTO table for COLTO grading if required

REPLACE TABLE 4203/1 WITH:

TABLE B4203/1: ASPHALT MIX REQUIREMENTS: BASE AND SURFACING

Property	Continuously graded base mixes	Continuously graded surfacing mixes
Voids in the mix	4 - 6	4 - 6
Voids in Mineral Aggregates (VMA) (%)	Min 14	Min 14
Voids filled with binder (%)	65 - 75	65 - 75
Binder film thickness (microns)	5.5 – 8.0	5.5 – 8.0
Filler bitumen ratio	1 – 1.5	1 – 1.5
Adhesion (Immersion Index) C5		84% min.
Modified Lottmann @ 7% voids (TSR)	> 0.7	> 0.7
Air permeability @ 7% voids (cm ²)	Max 1 x 10 ⁻⁸	Max 1 x 10 ⁻⁸
Indirect tensile strength @ 25°C (kPa)	Min 1000	Min 1000
Dynamic Creep Modules @ 40°C (MPa)	Min 20	Min 20
Marshall Stability @ 60°C (kN)	8 – 18	8 – 18
Marshall Flow (mm)	2 – 6	2 – 6
Stability /Flow (kN/mm)	>2.5	Min 2.5
Wheel tracking test using Model Mobile Load Simulator (MMLS)* (100,000 repetitions)		Max 2 mm
Superpave Gyratory Test**: % Voids @ Nfinal (300 gyrations)		Min 2

B4204 PLANT AND EQUIPMENT

(f) Vehicles

REPLACE THE SECOND PARAGRAPH WITH THE FOLLOWING:

To minimize temperature loss all vehicles used for transporting asphalt to the site shall be fitted with thermal asphalt covers (canvas covers not acceptable) irrespective of the prevailing climatic conditions or distance of transport."

B4205 GENERAL LIMITATIONS AND REQUIREMENTS AND THE STOCKPILING OF MIXED MATERIAL

b) Moisture

AMEND THE LAST PARAGRAPH AS FOLLOWS:

INSERT "and/or primed base" AFTER "surfacing" IN THE THIRD LINE OF THE FIRST SENTENCE.

REPLACE THE LAST SENTENCE WITH "In such case the base shall be allowed to dry out to meet the above moisture content requirement prior to placing the surface layer."

c) Surface Requirements**(iii) Tack Coat**

ADD THE FOLLOWING PARAGRAPH:

"Hand spraying shall only be permitted on areas approved by the Employers Agent. The binder distributor shall be capable to apply the binder evenly over the full area. The equipment shall comply with clause 4103. Tack coat shall be applied to all transverse and longitudinal joints by hand utilizing a paint brush."

B4206 PRODUCING AND TRANSPORTING THE MIXTURE**b) Production of the mixture****(ii) Using drum-type mixer plants**

ADD THE FOLLOWING:

"Pre-blending of aggregate fractions shall not be permitted and the Contractor shall ensure that sufficient cold-feed bins are installed to accommodate each individual aggregate fraction, including the filler."

c) Transporting the mixture

DELETE THE SECOND SENTENCE IN THIS PARAGRAPH.

ADD THE FOLLOWING SUB-CLAUSE:

"f) Approval of asphalt mixture

Before any asphalt is placed on the road, the Employers Agent shall approve the mix design. The approval process shall be as follows:

The Contractor shall prepare and submit a laboratory design mix with test results at four different bitumen contents. The design mix shall be submitted on the prescribed form D3 of TMH 10: "Instruction for the Completion of As-Built Materials Data Sheets" with all the necessary test results completed. In addition, the proposed asphalt mixture shall be subjected to gyratory testing. All the expenses in preparing and submitting the laboratory design mix shall be to the Contractor's cost.

Samples of all aggregate and bitumen shall be submitted with the laboratory design mix to enable the Employers Agent to carry out check design testing as necessary. The above design and aggregate shall be submitted to the Employers Agent at least six weeks before it is intended to commence with any asphalt production.

After approval is obtained for the laboratory design mix, a plant mix at varying binder contents of approximately 5 to 10 tons each shall be produced. The purpose of the plant mix is for the Contractor to prove that the laboratory design mix can be produced successfully. The Employers Agent shall conduct the necessary testing

on the plant mix. The plant mix shall not be placed on the road. During the production of the plant mix, the Employers Agent shall be afforded the opportunity to inspect the asphalt plant.

After the plant mix is approved, permission shall be given for laying a trial section at varying binder contents in accordance with the requirements of section 4211 of the specifications. The Employers Agent may require that the mix be further assessed by means of CSIR Wheel Tracking or MMLS testing, the cost of which will be borne by the Employer. Mass production of asphalt shall only commence after approval of the trial section, which should be given within a maximum of ten days.

The Employers Agent may instruct the Contractor at any time to halt his paving process and to review the whole or part of the above process should a change of aggregate properties occur, the specified asphalt requirements not being met and/or a consistent asphalt mixture not be produced."

B4208 JOINTS

ADD THE FOLLOWING TO THIS CLAUSE:

"Where the difference in level between the new work and the existing road surface exceeds 25mm, joints shall be treated as follows:

Transverse steps at the end of a day's work shall be tapered off at a slope of 1 vertical to 20 horizontal (1:20) to tie in with the existing surface. The tapered section shall be removed before surfacing is recommenced and a joint formed in accordance with clause 4208 of the specification.

Longitudinal joints exposed to traffic shall be provided with a taper of compacted asphalt material over the full length of the exposed joint. The width of the taper shall be at least 5 times the difference in level between the old and new work.

All costs involved in the provision and removal of these temporary ramps shall be deemed to have been included in the rates tendered for the relevant asphalt pay item."

B4210 COMPACTION

ADD THE FOLLOWING TO THIS CLAUSE:

"No traffic shall be allowed on the newly compacted surface before the mat has cooled to ambient temperature.

At least 1/3 of the cores drilled on the completed asphalt base layer to determine the density, should be drilled on joints."

B4211 LAYING OF TRIAL SECTION

ADD THE FOLLOWING TO THE END OF THE FIRST PARAGRAPH:

"As the purpose is not to calibrate any equipment, etc., the Contractor shall calibrate the equipment and refine the mix design at his own cost."

ADD THE FOLLOWING:

"For conventional asphalt, a trial section of about 60 m shall be laid based on the results of the laboratory design mix. The first 20 m shall be 0,5% less than the design binder content, the next 20 m at the design binder content design and the last 20 m at 0,5% over the design binder content. Volumetric properties, indirect tensile strength on briquettes shall all be checked against the criteria set in tables B4203/2 and B4203/3 for all three sections. Gyratory compaction tests should be carried out on the samples obtained from the trial sections at the different binder contents.

B4213 CONSTRUCTION TOLERANCES AND FINISH REQUIREMENTS

(a) Construction tolerances**(v) Surface regularity**

DELETE THIS SUBCLAUSE AND REPLACE WITH THE FOLLOWING:

"Roughness of the surfacing will be determined by using a profilometer capable of producing a Class 1 vertical measurement resolution, and a Class 3 longitudinal sampling distance as defined in ASTM standard (E950-94). Prior to using the profilometer it shall have successfully completed a validation trial against the Instrument of Reference (Face Dipstick ®) used by the South African National Roads Agency Limited.

The profilometer shall be used to record the longitudinal profile in both wheel tracks of the traffic lanes. The two wheel tracks shall be 1,75 m apart, and the Employers Agent shall indicate the exact position of the wheel tracks. Should the two tracks not be measured simultaneously during the same pass, then procedures shall be implemented to ensure that the longitudinal profile data recorded for the two wheel tracks are at the same longitudinal location on the road. The measured longitudinal profiles will then be processed using the Quarter-Car simulation model with parameter values as defined in ASTM standard (E1170-92) for Ride Meter-Vehicle Mounted. The simulated suspension mentioned will then be linearly accumulated and divided by the length to yield 100 m IRI (international roughness index) values in units of mm/m or m/km for each wheel track. The last 50 metres, and the joining first 50 metres of adjacent sections will be evaluated as a 100 m section in the direction of vehicle travel.

The left and the right 100 m IRI values will then be averaged to produce the Average IRI as follows:

$$\text{Average 100 m IRI} = \frac{100 \text{ m IRI (Left Wheel track)} + 100 \text{ m IRI (Right Wheel track)}}{2}$$

The average 100 m IRI for surfacings placed on layers which have been milled, or constructed, by the contractor shall be judged differently from surfacings placed as an overlay on existing surfacing.

- (1) The average 100 m IRI for surfacing placed on layers that have been milled or constructed by the contractor shall be evaluated and judged according to table B4213/2 to determine whether the 100 m section needs corrective work or payment adjustment.
- (2) For surfacing placed as an overlay on existing surfacing the average 100 m IRI values for the new surfacing and the average 100 m IRI values of the existing surfacing shall both be used in table B4213/2 to determine whether the 100 m section needs corrective work or pavement adjustment. For this surfacing the payment adjustment factor applicable shall be the difference between the payment adjustment factors applicable to the new surfacing and the existing surfacing plus 1,0.

TABLE B4213/2: PAYMENT ADJUSTMENT

100 m IRI values (mm/m or m/km)*	Payment adjustment factor
< 0,90	1,050
0,91 to 0,95	1,040
0,96 to 1,00	1,030
1,01 to 1,05	1,020
1,06 to 1,10	1,010
1,11 to 1,20	1,000
1,21 to 1,30	0,990
1,31 to 1,40	0,975
1,41 to 1,50	0,955
1,51 to 1,60	0,930
1,61 to 1,70	0,900

> 1,70	Not acceptable
--------	----------------

* This is the average 100 m IRI value per lane.

For overlay work on existing surfacing, the limits for payment adjustment factors shall be 1,050 and 0,900.

On sections where the average 100 m IRI on the existing surfacing is < 1,20 and the average 100 m IRI on the new surfacing does not worsen to > 1,20 no payment adjustment factor will be applicable. Should the average 100 m IRI value on the new surfacing worsen to > 1,20 payment adjustments will be applicable as shown in table B4213/2. Should the average 100 IRI value on the new surfacing worsen to > 1,70 corrective work will be necessary.

Any corrective work required shall be made by the removal, through milling of the total asphalt layer width placed during a single pass of the paver over the 100 m section in question, followed by reinstatement. The contractor shall submit his method statement for any corrective work to the Employers Agent for approval, prior to commencing with any corrective work. Corrective work shall be done at the contractor's expense and shall be completed prior to determining pavement thickness. After completion of the corrective work, the 100 m sections shall be re-evaluated according to the abovementioned procedure.

Any adjustment in the payment of asphalt surfacing will be made by multiplying the full payment for item B42.11 at contract rates (including pre-coated chippings where relevant) by the payment adjustment factor in or derived from table B4213/2. The payment adjustment shall apply to the total asphalt layer width placed during a single pass by the paver over the 100 m sections in question.

The longitudinal profile and the 100 m IRI values shall be determined using a profilometer furnished and operated by the contractor or on his behalf in the presence of the Employers Agent.

No direct payment will be made to the contractor for measurement and analysis of profiles and all costs shall be included in the rates tendered for the relevant pay items as provided in the bill of quantities schedule. It is recommended that frequent measurements be made during the initial set up of the paver and over the progress of the project. However, as an absolute minimum, measurements shall be provided to the Employers Agent after 10%, 50% and 100% of the surfacing area has been completed."

(c) Gradings

REPLACE TABLE 4213/1 WITH:

TABLE B4213/1: AGGREGATE GRADING TOLERANCES

Size of aggregate passing Sieve size (mm)	Permissible deviation from target grading (%)
28	± 5
20	± 5
14	± 5
10	± 5
7	± 5
5	± 4
2	± 4
1	± 4
0,600	± 4
0,300	± 3
0,150	± 2
0,075	± 1*

* When statistical methods are applied the permissible deviation for the 0,075 fraction is ± 2%.

(d) Binder content

DELETE "or clause 8305" IN THE THIRD LINE.

ADD THE FOLLOWING:

"The allowable deviation from target value for the bitumen content of SMA asphalt mixes shall be 0,3% as for continuously graded asphalt."

(e) Voids

ADD THE FOLLOWING:

"The void content shall not deviate from the approved production mix void content by more than 1%."

(f) Construction tolerances for overlays

(iii) *REPLACE PARAGRAPHS THREE AND FOUR OF SUB-SUB-ITEM (III) TO READ:*

"The calculated average thickness of the overlay for each day's production shall be the nominal specified thickness $\pm 3\text{mm}$. No additional payment shall be made for inlays not adhering to this specification."

ADD THE FOLLOWING TO THE FIFTH PARAGRAPH:

"The nominal thickness of the asphalt scratch coat shall be as indicated on the drawings."

ADD THE FOLLOWING SUBCLAUSE:

“(g) Construction tolerances for inlays,

USE THE SAME WORDING AS PER CLAUSE 1513 (F) WITH THE FOLLOWING CHANGES:

REPLACE PARAGRAPHS THREE AND FOUR OF SUB-SUB-ITEM (III) TO READ:

"The calculated average thickness of the inlay for each day's production shall be the nominal specified thickness $\pm 5\text{mm}$. No additional payment shall be made for inlays not adhering to this specification."

REPLACE THE WORD "overlay" WITH "inlay" FOR THE ENTIRE SUBCLAUSE.

(h) Air-void tolerance

The actual air voids may not deviate by more than 1 percentage point from the air voids in the approved production mixture."

B4214 QUALITY OF MATERIAL AND WORKMANSHIP

b) Coring of asphalt layers

ADD THE FOLLOWING:

"A suitable coring machine shall be available on a daily basis when asphalt paving is taking place. Cores shall only be drilled, when the road temperature is 20°C or less. Core holes shall be filled with hot mix asphalt and compacted, all within 24 hours of the core being drilled. Coring shall be carried out within 48 hours after the paving has been completed and supplied to the Employers Agent. The test results of cores shall be submitted to the Employers Agent within 24 hours after coring."

c) Routine inspection and tests**ADD THE FOLLOWING PARAGRAPHS:**

"The Contractor shall keep accurate records of:

- (i) The position where every truckload of asphalt is paved (chainage, lane, time and date).
- (ii) The temperatures of the asphalt in the trucks both at the mixing plant and at the paving equipment immediately prior to discharging the load.
- (iii) The truck and load number from which control samples are taken. All samples taken shall be appropriately numbered.

Test results and measurements will be assessed in accordance with the provisions of section 8300."

ADD THE FOLLOWING SUB-CLAUSE:**d) Special tests**

n-Heptane-Xylene Equivalent (Spot test) (AASHTO-T102)

If the Employers Agent suspects that bitumen or asphalt has been overheated, he may order that the bitumen, or the bitumen recovered from the asphalt, be subjected to the Spot Test. Recovery of binder for use in the Spot Test shall be carried out according to an approved method.

Any bitumen having an n-Heptane-Xylene equivalent in excess of 36, or in excess of the manufacturers test result on the dispatched stock, shall be considered to have been overheated and shall be deemed to be rejected unless proven otherwise."

ADD THE FOLLOWING CLAUSES:**"B4216 RUMBLE STRIPS**

300 mm wide prefabricated rumble strips with 10 mm nominal-sized aggregate (Petrocol, Freyssinet or approved equivalent) shall be placed as instructed by the Employers Agent.

B4217 COLD PREMIX

Cold premix should preferably be mixed in a concrete mixer, but may be mixed by hand. When a concrete mixer is used, the mixing process must be stopped as soon as the mixture is evenly black. Further mixing may result in stripping.

(a) Mixture ratios

To prepare a cold continuously graded premix with $\pm 5\%$ nett bitumen content (per weight) the following volumetric method can be used:

Mix 1 part 13,2 mm aggregate,
two parts 6,7 mm aggregate, and
one part coarse river sand.

Then use $7\frac{1}{2}$ parts of the above mixture, dampen lightly, and 1 part KMS 60% (cationic premix grade emulsion) and mix with spades or in a concrete mixer.

By covering the mixture with a canvas, it can be stored for ± 5 days.

The contractor shall make a test section for approval and it should be noted that an accurate grading and surfacing is required."

B4215 MEASUREMENT AND PAYMENT

AMEND THE FOLLOWING PAYMENT ITEM:

Item	Unit
B42.08 100mm cores in asphalt paving	number (no)

AMEND THE 1ST SENTENCE BY ADDING THE FOLLOWING AFTER THE WORD "drilled....":

"irrespective of depth of core."

Item	Unit
B42.11 Asphalt layer constructed for rehabilitation purposes in accordance with the provisions of sub-subclause 4213(f)(ii) or 4213(f)(iii):	

REPLACE SUBITEMS (a), (b), (c) AND (d) WITH THE FOLLOWING:

- | | | |
|------|--|----------|
| "(a) | Base or inlays constructed with asphalt
40/50 penetration bitumen, 26,5/20,0 mm
maximum aggregate size: | |
| (i) | Continuously graded: | |
| (1) | In layers not exceeding 50 mm
average thickness | ton (t) |
| (2) | In layers exceeding 50 mm
average thickness but constructed in
multiple layers not exceeding 50 mm
in thickness..... | ton (t) |
| (b) | Base or inlays constructed with asphalt
A-E2 homogeneous modified binder, 26,5/20,0 mm
maximum aggregate size: | |
| (i) | Continuously graded: | |
| (1) | In layers not exceeding 50 mm
average thickness | ton (t) |
| (2) | In layers exceeding 50 mm
average thickness but constructed in
multiple layers not exceeding 50 mm
in thickness..... | ton (t) |
| (c) | Surfacing, overlay or inlay constructed with asphalt
50-70 penetration grade bitumen, 14 mm maximum aggregate size: | |
| (i) | Continuously graded: | |
| (1) | Up to 35 mm nominal thickness | ton (t) |
| (d) | Surfacing, overlay or inlay constructed with new asphalt
A-E2 homogeneous modified binder, 14 mm
maximum aggregate size: | |
| (i) | Continuously graded: | |
| (1) | Up to 50 mm nominal thickness | ton (t)" |

INSERT THE FOLLOWING PARAGRAPHS AFTER THE 1ST PARAGRAPH:

"The unit of measurement for subitem (a) shall be the ton of asphalt base placed in compacted layer thickness not exceeding 40mm, and measured according to certified weighculvert crossing tickets issued in respect of the mixture used.

The unit of measure for subitem (b) shall be the ton of asphalt overlay placed to the nominal thickness specified if placed in terms of B4213(f)(iii) and placed to the specified level if placed in terms of B4213(f)(ii), and measured according to certified weighculvert crossing tickets issued in respect of the mixture used.

No payment shall be made for excess width and wastage of asphalt, and the mass of such excess or wasted material shall be deducted from the recorded delivery for payment purposes. For layers constructed in terms of clause B4213(f)(iii) no payment shall be made for asphalt in excess of the mean spread rate(s), which shall be determined as follows:

$$S = \frac{1000}{AXB} \text{ m}^2/\text{ton where,}$$

$$S = \text{Mean spread rate in m}^2/\text{ton}$$

$$A = \text{Average bulk relative density achieved on the road in ton/m}^3$$

$$B = (\text{specified asphalt thickness in mm}) + 5\text{mm}$$

ADD THE FOLLOWING TO THE 3RD PARAGRAPH:

"The tendered rate shall also include full compensation for joint forming, temporary ramping of construction joints between paving operations when new work is opened to traffic (including ramping material), breaking up and disposal of temporary ramps and waste material, weighing the material on the specified weighculvert crossing and cleaning the surface."

ADD THE FOLLOWING PAYMENT ITEMS:

Item	Unit
B42.21 Rumble strips.....	metre (m)

The unit of measurement shall be the metre length of 300 mm wide, approved rumble strip placed in accordance with the Employers Agent's instructions.

The tendered rate shall include full compensation for procuring and furnishing all materials, manufacturing the strips, applying the tack coat and placing the strips in accordance with the manufacturer's instructions on the instruction of the Employers Agent.

Item	Unit
B42.22 Removal of existing bituminous material by milling as directed by the Employers Agent	cubic metre (m³)

The unit of measurement shall be the cubic metre of material removed by milling. The quantity shall be calculated in accordance with the authorised dimensions or as directed by the Employers Agent.

The tendered rate shall include full compensation for providing a milling machine on the site and all additional measure, adjustments and costs for the removal of material by milling, for loading and transporting (including all haul) to approved spoil sites provided by the contractor and for cleaning of the milled area.

Item	Unit
B42.23 Cut longitudinal joints in asphalt surfacing (state specified thickness and type of asphalt mix):	
(a) (Thickness, mm), (mix type).....	metre (m)
(b) (Thickness, mm), (mix type).....	metre (m)

The unit of measurement shall be the metre of longitudinal joint cut in asphalt surfacing constructed to the thickness specified. No payment will be made for providing transverse joints.

The tendered rates shall include full compensation for providing a cutting wheel mounted on a suitable and stable vehicle, pre-marking the position of the joint to be cut, cutting and removal of cut-off portion of asphalt and for the asphalt discarded during the cutting process. The tendered rates shall also include for the application of a tack coat along the vertical face of the joint and the application of the surface seal of mineral-filled bitumen emulsion as specified."

Item	Unit
B42.24 Traffic calming measures:	
(a) 3.5m wide speed hump as per drawings.....	number (No)
(b) Raised pedestrian crossing as per drawings	number (No)

The unit of measurement shall be the number of speed bumps or raised pedestrian crossings completed as per the drawings and instructed by the employers agent.

The tendered rates shall include full compensation for providing all material, labour and plant to complete the speed bumps or raised pedestrian crossings. Rate to exclude the road markings and road signs that will be measure and paid for under the respective sections.

SECTION B4600: BITUMINOUS SINGLE SEAL WITH SLURRY (CAPE SEAL)**B4602 GRADES OF BINDER TO BE USED****(a) Tack coat**

ADD THE FOLLOWING:

"The tack coat shall be a 70/100 penetration-grade bitumen."

(b) Second application of binder

ADD THE FOLLOWING:

"The binder used in the second application shall be a 60% spray-grade emulsion."

B4603 CONSTRUCTION BEFORE SLURRY APPLICATION**(a) Application of tack coat and aggregate**

ADD THE FOLLOWING AFTER THE FIRST PARAGRAPH:

"If the bituminous binder used for the tack coat is of 70/100 penetration-grade bitumen, the 19 mm aggregate for the first layer shall be pre-coated with a bituminous based pre-coating fluid, at 12 litre/m³ as specified in subclause 4302(d).

A second application of a 60% -65%% spray-grade emulsion shall then be applied to the surface of the 19 mm aggregate.

The aggregate to be used with the tack coat shall conform to the grading requirements for a 19,0 mm nominal size Grade 1 surfacing aggregate."

(b) Initial rolling

DELETE "subsubclause 4307(b)(ii)" AND REPLACE WITH "subsubclause B4307(b)(ii)".

(c) Broom drag and final rolling of aggregate

DELETE "subsubclause 4307(b)(iii)" AND REPLACE WITH "subsubclause B4307(b)(iii)".

B4604 SLURRY**(c) Composition of slurry**

ADD THE FOLLOWING TO THE FIRST PARAGRAPH:

"The slurry shall be applied and spread by hand. Under no circumstances will the application of the slurry by means of a spreader box be allowed."

ADD THE FOLLOWING:

"The aggregate used for slurry shall comply with the requirements of table 4302/11. The first slurry shall be a fine slurry 'coarse' to 'medium grade' and the second slurry shall be fine slurry 'fine' grade. For tender purposes the mix proportions of the slurry shall be based on mass."

ADD THE FOLLOWING AFTER THE SECOND PARAGRAPH:

"The slurry consistency when measured in accordance with ASTM D3910 Section 6.1 shall be between 30 mm and 40 mm."

(d) Mixing of slurry

REPLACE THE LAST SENTENCE IN THE FIRST PARAGRAPH WITH:

"Only the use of batch mixers will be permitted."

(e) Application of slurry

IN THE FIRST SENTENCE OF THE THIRD PARAGRAPH INSERT THE WORDS "one or" BEFORE "two layers".

DELETE THE FIFTH AND SIXTH PARAGRAPHS AND REPLACE WITH:

"The measurement of slurry application rate shall be the dry mass of aggregate in kg/m² applied per m² of surfacing and the total nominal rate of application shall be 13 kg/m² if only the 1st slurry layer is applied, and 15 kg/m² in total if the 1st and 2nd slurry layers are applied. Payment for slurry application variations shall be based only on the actual total rate of slurry application of the completed Cape Seal."

ADD THE FOLLOWING AFTER THE EIGHTH PARAGRAPH (NOW THE SEVENTH PARAGRAPH):

"Both the first and second layer of slurry shall be spread to the full final width of the primed surface."

CHANGE THE EIGHTH LINE OF THE TENTH PARAGRAPH (NOW THE NINTH PARAGRAPH) AS FOLLOWS:

"..... pneumatic-tyred roller. However, each layer of slurry shall be"

ADD THE FOLLOWING TO THE NINTH PARAGRAPH:

"This layer of slurry shall be compacted thoroughly by pneumatic tyred roller to the satisfaction of the Employers Agent. The compaction shall be carried out as soon as the emulsion has cured sufficiently so that there will be no picking up of the slurry by the tyres of the roller and not later than on the first working day following that on which that slurry seal was placed."

ADD THE FOLLOWING BEFORE THE FIRST SENTENCE OF THE TENTH PARAGRAPH:

"As soon as possible, but not later than four (4) weeks after the first layer of slurry has been applied, the second layer of slurry shall be placed. The second application of slurry shall not be applied less than four (4) days or more than four (4) weeks after the second application of bituminous binder. The binder shall be given sufficient time to dry before the second layer of slurry is applied."

ADD THE FOLLOWING TO THE FOURTEENTH PARAGRAPH:

"A moist burlap drag shall be drawn behind the squeegees in order to ensure an even textured finish."

ADD THE FOLLOWING PARAGRAPH AFTER THE EIGHTEENTH PARAGRAPH:

"The road shall not be opened to traffic until the slurry has, in the opinion of the Employers Agent, completely cured and the bitumen has set sufficiently so as not to be picked up by the wheels of passing traffic. The contractor shall not allow construction equipment, which is likely to cause damage, over the completed surface."

B4605 MEASUREMENT AND PAYMENT

ADD THE FOLLOWING BEFORE THE PAYMENT ITEMS:

"No additional or extra over payment will be made for work in restricted or confined areas."

REPLACE THE DESCRIPTION OF PAYMENT ITEM 46.01 WITH THE FOLLOWING:

"Item	Unit
B46.01	Bituminous single seal with 20,0 mm aggregate and slurry (double layer)
(a)	70/100 penetration grade bitumen as a tack coat and 60% or 65% spray-grade emulsion in the penetration spray..... square metre (m ²)

ADD THE FOLLOWING AT THE END OF THE PAYMENT CLAUSE FOR THIS ITEM:

"The cost of providing the slurry seal over the final primed width shall be included in the rate for providing the seal with slurry over the bituminous surfaced width."

COLTO SERIES 5000: ANCILLARY ROADWORKS**SECTION B 5100: PITCHING, STONEMASONRY AND PROTECTION AGAINST EROSION****B5102 MATERIALS****a) Stone**

REPLACE THE 2ND PARAGRAPH WITH THE FOLLOWING:

"Unless suitable stone can be located on site, the stone for pitching shall come from commercial sources but, from whatever source, its use shall be subject to the prior approval of the Employers Agent."

c) Sand**(ii) Sand for bedding**

Replace this sub-sub-clause with the following:

Sand for bedding used for paving blocks shall not contain any deleterious impurities and shall comply with the requirements given in table B5102/1.

TABLE B5102/1

Sieve size (mm)	Percentage passing
10	100
5	95 – 100
2	73 – 86
1	43 - 78
0,600	25 – 60
0,300	10 - 30
0,150	5 – 15
0,075	5 - 10

Note:

Refer to standard COLTO table for COLTO grading if required

B5106 SEGMENTAL BLOCK PAVING**d) Edge beams**

ADD THE FOLLOWING PARAGRAPH:

"Where concrete edge beams are constructed the relevant specifications under section 2300 shall apply."

SECTION B 5600: ROAD SIGNS**B5601 SCOPE**

REPLACE "South African Road Traffic Signs Manual" IN THE SECOND PARAGRAPH WITH:

"SADC Road Traffic Signs Manual"

B5602 MATERIALS**(a) Structural steel**

REPLACE THE SECOND PARAGRAPH WITH THE FOLLOWING:

"All structural steel, including tubes, shall be galvanized in accordance with the requirements of SABS 763 for type A1 or B1 articles, as applicable."

REPLACE THE SECOND SENTENCE OF THE FIRST PARAGRAPH WITH THE FOLLOWING:

"Channels, square tubes, angle irons and other steel members on the reverse side of the sign boards and steel tubes for sign supports shall be painted in accordance with the following specifications : SABS 926 for a two-pack zinc-rich epoxy primer, SABS 681 for the undercoat, and SABS 1413 for a chloro-rubber finishing coat."

(g) Retro-reflective material

IN THE FIRST SENTENCE REPLACE "SABS 1519" WITH "SANS 1519-1:2014" AND DELETE "and the adhesion requirements of CRS 191".

REPLACE THE THIRD LAST PARAGRAPH WITH THE FOLLOWING:

"The contractor shall provide proof that Classes I and III of the retro-reflective commercial products to be used have been generally and successfully used in South Africa during the last three years.

Classes I and III retro-reflective materials shall be warranted against any abnormalities as described in SABS 1519 for 7 and 10 years respectively."

ADD THE FOLLOWING AFTER THE SECOND LAST PARAGRAPH:

"Should a contractor manufacture signs without the necessary approval it shall be deemed that the contractor unconditionally guarantees the sign for the full period of seven years. Should failure of the sign due to suspected incompatibility of materials (in the opinion of the Employers Agent) occur within seven years, the contractor shall remanufacture the sign and re-erect the sign at no cost to the employer."

ADD THE FOLLOWING TO THE LAST PARAGRAPH:

"Reflective sheeting shall be applied to sign faces strictly in accordance with the retro-reflective material manufacturer's specifications. Legend and background materials shall be supplied by the same manufacturer. Every batch of material used for signs on the contract shall be identified by a batch number. A certificate of all materials' compliance with SANS 1519-1:2014 shall be submitted to the Employers Agent within 3 months of the material being used. An outdoor weathering test will not be required."

ADD THE FOLLOWING:

"Retro-reflective materials shall comply with the requirements of SANS 1519-1:2014.

Mixing 3M Scotchlite, Kiwalite or any other approved products on the same sign will not be permitted. The contractor will also be required to produce lifespan guarantees as well

as SANS approved certificates with regard to the retro-reflective material specified or tendered for.

When measured in accordance with SANS 1519-1:2014, the coefficient of retro-reflection of a retro-reflective material shall not be less than the appropriate value given in Table 1 of SANS 1519-1:2014 (duplicated as table B8118/1 in these specifications).

The colour of the retro-reflective material shall match the specified colour and shall not be faded to such an extent that its effectiveness is unacceptably impaired in the opinion of the Employers Agent. The surface of the material shall be undamaged and free from scratches, stains or other marks.

When, in the opinion of the Employers Agent, the retro-reflective material does not comply with the above requirements, the contractor shall replace the defective material at his own cost, to the satisfaction of the Employers Agent.

When measured in accordance with SANS 1519-1:2014, the coefficient of retro-reflection of a retro-reflective material shall not be less than the appropriate value given in Table 1 of SANS 1519-1:2014."

(k) Back vinyl

IN THE SECOND SENTENCE REPLACE "SABS 1519" WITH "SANS 1519-1:2014" AND DELETE THE REST OF THE SENTENCE.

ADD THE FOLLOWING SUBCLAUSES:

"(l) Chromadek sections

Chromadek sections shall be 1,2 mm thick and shall comply with the details on the drawings.

(m) Temporary covers for road signs

When required, existing road signs shall be fully or partially covered with burlap or 0,5 mm thick black plastic or other approved material to obscure destinations that are temporarily inapplicable or irrelevant. As reflective material loses its retro-reflective and adhesive qualities in poorly ventilated conditions, 25 mm diameter holes spaced at maximum intervals of 300 mm shall be cut in the plastic to render it permeable.

The covers shall be neatly applied and firmly fixed in position so that they will be able to withstand strong gusts of wind or eddies caused by passing traffic."

B5603 MANUFACTURING OF ROAD SIGN BOARDS AND SUPPORTS

a) Road sign boards

ADD THE FOLLOWING:

"The Contractor shall make every effort to ensure that signboards are correct in all respect and before dispatching the boards from the manufacturer's factory shall provide the Employers Agent with a 100mm x 150mm colour photograph of each sign face for approval of the correctness of the legend. Such approval will not imply final acceptance of the board. If the Contractor is in any doubt as to the correctness of the sign detail, the sign designer shall be contacted for verification."

(ii) Steel profile road signboards

ADD THE FOLLOWING:

"Chromadek section shall be assembled in accordance with the details of Standard Plans SP-B-12-Sheets 4 and 5 and SP-B-4-Sheets 33E and 34E.

Where the letter or legends cross the horizontal joints of the sign panels, the letter shall be cut on the joint and both ends folded around the radius.

Retro-reflective material to adjoining Chromadek panels on a sign shall be practical visual match of the specified colour."

B5604 ROAD SIGN FACES AND PAINTING

(b) Preparing surfaces and applying paint and retro-reflective sheeting

ADD THE FOLLOWING TO THE FIRST PARAGRAPH:

"and shall conform to the requirements of TYPE A signfaces, as indicated on the drawings."

ADD THE FOLLOWING SUB-CLAUSE:

"e) Application of retro-reflective material

All sign faces shall be faced with retro-reflective material. Painted front sign faces shall not be used.

Where applied to Chromadek sections, retro-reflective material shall be applied as specified for aluminium section in Clause 5603(d) of the Standard Specification, and of Clause B5603(a)(ii) of this Project Specification."

B5605 STORAGE AND HANDLING

ADD THE FOLLOWING:

"The following shall not be allowed on the sign face:

- Drilling of holes, except for the fastening of overlays
- Application of any form of adhesive
- Cleaning with any chemicals that are not specifically approved by the manufacturer of the retro-reflective material.
- Covering the sign face with an impermeable material that does not allow free circulation of air."

B5606 ERECTING ROAD SIGNS

(b) Excavation and backfilling

ADD THE FOLLOWING AFTER THE FIRST SENTENCE OF THE FIRST PARAGRAPH:

"A 300 mm thick gravel drainage layer shall be placed at the bottom of the excavations and shall be compacted before the excavations are backfilled.

The dimensions of the excavation for the drainage layers shall be over and above that for the footings as shown on the drawings."

c) Erection

ADD THE FOLLOWING:

"After erection the signboard shall be thoroughly cleaned with a cleaning agent approved by the retro-reflective material's manufacturer.

On completion of signs on the road section, the contractor shall clear an area immediately around the sign. The area shall be 10 m wide at the side closest to the road and 5 m wide at the side farthest from the road. The area so cleared shall be treated with an approved chemical growth-retarder in accordance with the supplier's application instructions.

No separate payment shall be made for the clearance, or the procurement and application of the growth retarder."

B5608 DISMANTLING, STORING AND RE-ERECTING EXISTING ROAD SIGNS

ADD THE FOLLOWING:

"Existing overhead and ground mounted road signs that are being replaced by new signs shall be dismantled and disposed of by the Contractor. Where possible the dismantling of the signs shall not be before the replacement sign is erected and displayed. Where dismantling of the sign is required before erection of the replacement sign, the dismantling shall not take place until immediately before work is to commence on the replacement, and the replacement shall be completed and the new sign displayed as soon as possible thereafter (within 72 hours).

Dismantling shall include sign panels and ground mounted sign supports.

Ground mounted sign supports shall be cut off just below ground level. Material excavated for removal of buried poles shall be replaced, and any depression made good using excess material from excavation for new signs.

Payitems are provided in the Pricing Schedule. Payment will differentiate between different types of sign panels."

B5609 MEASUREMENT AND PAYMENT

Item	Unit
B56.01 Road sign boards with painted or coloured semi-matt background. Symbols, lettering, and borders in semi-matt black or in Class I retro-reflective material, where the sign board is constructed from	

AMEND THE LAST TWO LINES OF THE SECOND PARAGRAPH TO READ:

"completion, delivery, installation of the road sign board complete as specified, and the removal and disposal of all vegetation obstructing the motorists' view of the new or replaced sign board."

ADD THE FOLLOWING PAYMENT ITEMS:

Item	Unit
B56.10 Hazard plates (size indicated):	
(a) 600 mm x 150 mm.....	number (No)
(b) 800 mm x 200 mm.....	number (No)

The unit of measurement shall be the number of each size of hazard plate supplied and erected complete in accordance with the details on the drawings.

The tendered rates shall include full compensation for procuring and furnishing all materials, excavating, disposing of excavated material, erecting and painting the hazard plates and posts, and for placing and compacting the soilcrete backfilling.

Item	Unit
B56.11 Dismantling and disposal of road signs:	
(a) Hazard marker signs	number (No)

- (b) Single post signs (other R and W signs) number (No)
- (c) Multiple post signs number (No)

The unit of measurement shall be the number of signs removed.

The tendered rate shall include full compensation for dismantling the sign boards, removing the supports and foundations of ground-mounted signs, disposing of the material and clearing the removal site. It shall also include for all labour, plant, supervision and all other incidentals.

SECTION B 5700: ROAD MARKINGS**B5701 SCOPE**

REPLACE “South African Road Traffic Signs Manual” IN THE SECOND PARAGRAPH WITH:

“SADC Road Traffic Signs Manual”

REPLACE THE WORDS “ordinary road marking paint” with “solvent borne road marking paint”.

Replace “BS 3262” with “EN 1436”.

Replace “Hot melt plastic road marking” with “thermoplastic road marking”.

B5702 MATERIALS

INSERT THE FOLLOWING BEFORE SUBCLAUSE (A) PAINT:

“The selection of the appropriate road marking paint and materials for permanent road markings to ensure conformance with the requirements of this specification rests with the Contractor. Such paint and material shall have technical characteristics (brightness, luminance, skid resistance, durability) equal to or greater than road marking paint and materials specified in subclauses 5702(a), (b) and B5702(c).

Where plastic road-marking material (hot-melt plastic (also known as thermoplastic) and two-component (also known as cold plastic)) is used, the Contractor shall obtain an approved guarantee from the manufacturer that the paint complies with the specification. This shall be submitted to the Employers Agent on request.”

REPLACE SUB-SUBCLAUSE B5702(A)(I) WITH THE FOLLOWING:

“(i) Road marking paint

Road marking paint shall be Type 1 as specified in SANS 731-1. Only paint, manufactured in a SANS approved and accredited facility shall be accepted. The no-pick-up time of road-marking paint shall comply with the Class 1 requirement in accordance with SANS 731-1.

The paint shall be delivered at the site in sealed containers marked in accordance with SANS 731-1.

The viscosity of the paint shall be such that it can be applied without being thinned down.”

(ii) Retro-reflective road-marking paint

ADD THE FOLLOWING:

“When measured in accordance with SABS Method 1261-1998 within a period of two weeks after application, the coefficient of retro-reflected luminance, R_L , shall be at least 150 mcd/m².lx for white markings and 100 mcd/m².lx for yellow markings.”

REPLACE SUB-SUBCLAUSE B5702(A)(III) WITH THE FOLLOWING:

“(iii) Thermoplastic road marking material

b) Roadstuds

Replace the clause with the following:

"Permanent and temporary road studs shall comply with the requirements of the European Standard for road studs IS EN 1463.

The road studs to be used on this contract shall be RSA-1; Ferro Lynx A200 (shanked)."

Road studs for the areas of application shall be supplied and installed in accordance with the requirements set out in Table B5702/1 with reference to IS EN 1463.

TABLE B5702/1

Classification	Area of Application			
	RSA-1	RSA-2	RSA-3	RSA-T
Description	Bi-directional	Bi-directional	Circular Cats-Eye	Bi-directional
Material	Galvanized Cast Iron	Plastic	Glass	Plastic
Design	Type A	Type A	Type A	Type A
Use	Type P	Type P	Type P	Type T
Reflector	Type 1	Type 1	Type 1	Type 2
Reflectivity	R1	R1	R1	Not Specified
Installation System	Anchored	Bonded	Embedded	Self-Adhesive or Bonded
Height above Road	H3	H3	H3	H1
Dimensions (min-footprint)	100mmx80mm	100mmx100mm	100mm dia	100mmx100mm
Colours	W – R - Y	W – R - Y	W	W – R - Y
Road Trials	S1	S1	S1	Not Applicable

Add the following sub-item:

"c) Retro-reflective beads

Retro-reflective glass beads shall be applied to the wet paint, thermoplastic and cold plastic.

The beads shall comply with Class A beads in accordance with EN 1424: 1998, with the following requirements or as approved by the Employers Agent:

- colour : crystal clear
- roundness : > 80%
- size range of : 14 – 200 US Mesh (75 – 1400 Microns)
- refractive index : > 1.5
- specific gravity : ± 2.5
- granulometry :

CUMULATIVE RETAINED MASS		
SIEVE	MINIMUM	MAXIMUM
1700	0	2
1400	0	10
1180	5	30
850	40	80
600	70	100
425	80	100
355	90	100
212	95	100
PAN	100	100

The beads shall be delivered to the site in sealed bags, marked with the name of the manufacturer, the batch number and an inspection seal of SANS, confirming that the beads form part of a lot tested by SANS and comply with the requirements of EN 1424: 1998. Alternatively, the Contractor shall at all times have a SANS certificate on the site, identifying the batches to which the inspection seals apply and certifying that they have been tested by SANS, and comply with the requirement of EN 1424: 1998."

B5704 MECHANICAL EQUIPMENT FOR PAINTING

ADD THE FOLLOWING SENTENCE AT THE END OF THE FIRST PARAGRAPH:

"The road-marking machine shall be fitted with a device to guide the operator to the centre of the line to be painted. This device shall be used at all times of operation.

The machine shall always operate in the direction of the traffic when applying lane markings"

B5705 SURFACE PREPARATION

ADD THE FOLLOWING AT THE END OF THE SECOND PARAGRAPH:

"The onus is on the Contractor to ensure that the surface on which the road markings are to be applied is sufficiently clean and dry to ensure that the quality of the road markings will not be adversely affected. The Contractor is also responsible for protecting road studs from being painted over, and the subsequent cleaning thereof if such over-painting did occur."

B5706 SETTING OUT THE ROAD MARKINGS

INSERT THE FOLLOWING BEFORE THE FIRST PARAGRAPH:

"Where road markings are to be replaced after any construction activity, it is essential that all existing road marking be accurately surveyed and referenced before commencement of such construction activities which will obliterate the existing road markings. The position of barrier lines shall be re-assessed on site by the Employers Agent before the Contractor commences with the road marking."

B5707 APPLYING THE PAINT

INSERT THE FOLLOWING BEFORE THE FIRST PARAGRAPH:

"The Contractor's establishment on site and general obligation shall be deemed to fully include the establishment of the road-marking team, irrespective of the number of times the road-marking team is required to be on site or is required to move within the site.

Provision is also made under item B57.07 for de-establishment and re-establishment in the contract or maintenance period if such action is required by delays not attributable to the Contractor and/or ordered by the Employers Agent."

REPLACE THE SIXTH PARAGRAPH WITH THE FOLLOWING:

"Solvent borne road marking paint shall be applied at a nominal rate of 0,42l/m² or as directed by the Employers Agent. Thermoplastic road marking shall be applied at a nominal rate of 2,5 kg/m² to achieve a minimum thickness of 1,25mm to 1,5mm or as directed by the Employers Agent. The two-component road marking material shall be applied by hand by means of a trowel. The desired symbol or line shall be marked with a tape or a template on the road surface. Thereafter apply the required volume of material and spread uniformly over the entire area. When dry/set, remove the tape or template. A spreading rate of 4,5kg/m² is estimated to achieve a 2,0mm material thickness.

In order to ensure proper coverage on all types of surfaces the Employers Agent may order an increase in the above nominal application rates. Payment for these variations in application rates shall be made under item 57.04.

A daily log-sheet, provided by the Employer, shall be completed and signed by the Contractor and the Employers Agent's representative, recording the quantities of paint and glass beads used on that day and shall be available for inspection at all times. The completed and signed log-sheet for the period covered by a payment certificate shall be attached to the payment certificate."

REPLACE THE LAST PARAGRAPH WITH THE FOLLOWING:

"Solvent-based road marking as specified by the Employers Agent shall be carried out within 14 days of opening the road full width to traffic after the completion of the surfacing.

If in the in the opinion of the Employers Agent, conditions are unsafe, the centre-line shall be painted immediately after 2,0 km of continuous road has received a new asphalt layer, or 4,0 km of continuous road has received a new seal surfacing."

B5708 APPLYING THE RETRO-REFLECTIVE BEADS

IN THE FIRST PARAGRAPH, REPLACE THE NOMINAL APPLICATION RATE OF 0,8KG/LITRE WITH "400gm/m²".

REPLACE THE SECOND PARAGRAPH WITH THE FOLLOWING:

"The thermoplastic road marking material and two-component road marking material shall contain in situ glass beads of minimum content of 25% in order to obtain night visibility (reflectivity). The Contractor shall immediately apply additional glass beads at 400g/m² to obtain immediate reflectivity. The beads shall be sprayed onto the road marking layer by means of a pressure sprayer. Where letter, symbol, traverse line and island road marking is undertaken by hand, the glass beads may be applied by hand if approved by the Employers Agent. Prior to any hand application work, the Contractor shall first request approval from the Employers Agent."

ADD THE FOLLOWING:

"Beads shall be applied in accordance with EN 1424."

B5710 TOLERANCES

ADD THE FOLLOWING PARAGRAPHS TO SUBCLAUSE (C) ALIGNMENT OF MARKINGS:

" When an unbroken line and a broken line are painted alongside each other, the beginning and the end of the unbroken line shall coincide with the beginning of one broken line and the end of another broken line. When existing lines are repainted, the new markings shall not deviate more than 100mm in the longitudinal direction nor 10 mm in the transverse direction from the existing marking.

The alignment of the road studs shall not deviate from the true alignment by more than 10mm and shall be positioned so that the reflective faces are within 5° of a right angle to the centre line of the road."

ADD THE FOLLOWING SUBCLAUSE:**"e) Testing****(1) Plant**

Before painting any permanent road markings, the Contractor shall satisfy himself and the Employers Agent, by painting test lines on a section of pavement other than the section required to be marked:

- (i) that the painting machine is in good working order and properly adjusted;
- (ii) that the operator is fully experienced; and
- (iii) that the machine sprays at the specified rate of paint application.

The Contractor shall bear the cost of all materials and workmanship required for the above plant tests.

In addition, the Contractor shall conduct random paint thickness tests and dip/spread tests as required by the Employers Agent."

B5711 GENERAL

INSERT THE FOLLOWING INTO THE LAST SENTENCE OF THE LAST PARAGRAPH BETWEEN "black paint" AND "or chemical paint remover":

" , bituminous emulsion, slurry"

ADD THE FOLLOWING TO THE LAST PARAGRAPH:

"Where black paint is used, it shall be matt."

ADD THE FOLLOWING CLAUSE:

"The Contractor shall provide temporary traffic control facilities in accordance with Section 1500 of the COLTO's standard specifications for road and culvert crossing works to ensure traffic safety where work is being executed.

Property and/or road signs damaged by the Contractor, his personnel, his agents or sub-Contractors shall be repaired or restored to their condition prior to the damage at his own cost."

B5712 FAULTY WORKMANSHIP OR MATERIAL

ADD THE FOLLOWING PARAGRAPHS TO THIS ITEM:

"The Contractor shall rectify in an acceptable manner and at his own costs; all marking that do not comply with the specified requirements.

While work is in progress, tests shall be carried out on materials and/or the quality of work to ensure compliance with the specified requirements. The sampling methods are specified in SANS 731-1. The sampling methods described in TMH5 shall be followed where applicable."

B5713 PROTECTION

ADD THE FOLLOWING PARAGRAPH

"Traffic cones shall not be smaller than 750mm in height and shall be placed on the road not further than 48m apart. Cones shall not be removed before the paint on the road has hardened to such an extent that it will not be damaged by traffic and the adhesive of the road studs has hardened to such an extent that the studs will not turn or become loose. All

marks on the road caused by traffic driving over wet paint shall be removed by the Contractor at his own cost."

B5714 MEASUREMENT AND PAYMENT

AMEND PAY ITEM B57.05 AS FOLLOWS:

	"Item"	Unit
B57.05	Roadstuds (installation and maintenance)	number (No)"

ADD THE FOLLOWING AFTER THE FIRST SENTENCE OF THE SECOND PARAGRAPH:

"No additional payment will be made should temporary or permanent road studs be replaced if lost or broken during the construction period or during the Defects Notification Period."

	Item	Unit
B57.06	Setting out and pre-marking the lines (excluding traffic island markings lettering and symbols)	kilometre (km)

ADD THE FOLLOWING:

"Referencing of existing barrier lines and other road marking lines prior to milling and other operations, shall be included in the tendered rate for setting out and pre-marking."

SECTION B 5800: LANDSCAPING AND PLANTING PLANTS**B5801 SCOPE AND DEFINITION****a) Scope**

DELETE THIS PARAGRAPH AND REPLACE WITH

"This section includes all areas affected by construction activities. It includes landscaping, grassing, rehabilitation, erosion protections and planting trees and shrubs.

b) Definition**Weeds**

DELETE THE FOLLOWING:

"(as listed in bulletin 413 issued by the Department of Agriculture, Directorate of Agricultural Information)"

AND REPLACE IT WITH:

"(as listed in the Conservation of Agricultural Resources Act)"

B5802 MATERIALS**(a) Fertilizer/soil-improvement material**

REPLACE THE CONTENTS OF THIS SUBCLAUSE WITH THE FOLLOWING:

"The fertilizer/soil-improvement materials to be used shall be one or more of the following types, or as prescribed by the Employers Agent:

- (i) Lime
- (ii) Superphosphate (10,5)
- (iii) Limestone ammonium nitrate
- (iv) 2:3:2(22) + Zn
- (v) 3:2:1(25)
- (vi) Monophosphate
- (vii) Ureum (46)
- (viii) Potassium chloride (50)."

c) Grass seeds

ADD THE FOLLOWING:

"The grass seed mixture shall be as follows:

(i)	Eragrostis teff	1,5	kg/ha
(ii)	Eragrostis curvula	2,0	kg/ha
(iii)	Cenchrus ciliaris Molopo	10,0	kg/ha
(iv)	Chloris gayana Katambora	15,5	kg/ha
(v)	Cynodon dactylon	16,5	kg/ha
		<u>45,5</u>	<u>kg/ha</u>

g) Topsoil

ADD THE FOLLOWING AT THE END OF THE FIRST PARAGRAPH:

"The Contractor shall be responsible for the control of any germination of weed seeds within topsoil used on site."

ADD THE FOLLOWING AT THE END OF THE SECOND PARAGRAPH:

"Areas such as stockpiles, borrow pits and spoil sites shall be stripped of all topsoil before work may commence within the area. Should a larger site for any of the above be required during construction, the Contractor shall refer to the DEO for best practice methods on ensuring the preservation of the additional stripped topsoil."

ADD THE FOLLOWING PARAGRAPH:

"The topsoil shall be kept free of all foreign material generated during construction. This shall include all stone and bituminous products. Topsoiling shall not be accepted should it contain any of the above material."

B5804 PREPARING THE AREAS FOR PLANTS**b) Areas which do not require topsoil****REPLACE:**

"50mm" WITH "20mm " AND "150mm" WITH "20mm"

ADD THE FOLLOWING:

"In areas with large natural rock, i.e. not blasted or excavated rock, these rocks may be placed so as to look like a natural part of the landscape"

ADD THE FOLLOWING SUB-CLAUSE:**"g) Removal of undesirable vegetation**

During the course of the Contract the Employers Agent may instruct the Contractor to physically remove undesirable vegetation from within the road reserve. Such an operation will take place before the flowering stage of the undesirable vegetation upon written instruction from the Employers Agent, but shall not relieve the Contractor of his obligation towards weeding sodded, grassed areas as described under 5806(a) and any area directly affected by any construction activity. Should the Contractor fail to respond to the written instruction from the Employers Agent for the removal of the aforementioned undesirable vegetation before flowering, the Contractor shall be held contractually responsible for any growth or seeding of said vegetation for a period of not less than Twenty four (24) months in the affected area."

B5805 GRASSING**c) Hydroseeding****REPLACE THE FIRST SENTENCE OF THE SECOND PARAGRAPH WITH THE FOLLOWING:**

"The seed shall be fresh and of good quality. The contractor shall provide samples of the seed for germination tests at an early stage. Hydroseeding shall preferably be carried out in the spring or early summer, and the Employers Agent's prior approval of the programme shall be obtained. The seed mixture shall consist of the following species in the stated proportions:

(i)	Eragrostis teff	1,5	kg/ha
(ii)	Eragrostis curvula	2,0	kg/ha
(iii)	Cenchrus ciliaris Molopo	10,0	kg/ha
(iv)	Chloris gayana Katambora	15,5	kg/ha
(v)	Cynodon dactylon	16,5	kg/ha
		<u>45.5</u>	<u>kg/ha</u>

Eragrostis curvula shall be obtained from the University of Potchefstroom and shall be of the ecotype recommended for revegetation of slopes in harsh conditions.

"The top 20mm of prepared topsoil shall be raked away in sections, the seed shall then be spread uniformly within the prepared area. The top 20mm topsoil shall then be raked over the seedbed, ensuring an even thickness. This method is to be systematic, and where applicable, follow the contours of any slopes."

ADD THE FOLLOWING:

"The thickness of the topsoil layer shall be as specified by the Employers Agent. The preparation of the soil of the soil for areas to be grassed is to include scarifying just before sowing the grass seed. Should erosion of any kind (by animal, wind or rain) have occurred before the Contractor applies the grass seed, the slope shall be re-instated, at the Contractor's cost, to its original, erosion free state before seeding.

The types and mixtures of seeds to be used shall be as specified in the project specifications. The Contractor shall be solely responsible for establishing an acceptable grass cover, and any approval by the Employers Agent of seed mixtures intended for use by the Contractor shall not relieve him of his responsibility".

B5807 TREES AND SHRUBS

a) Positions of trees and shrubs

ADD THE FOLLOWING:

"(x) No median shall be planted with shrubs, should the median width be less than 10m wide."

B5808 GENERAL

ADD THE FOLLOWING SUBITEMS:

"f) Weeding

The Contractor shall maintain all areas affected by construction activities free of all undesirable plant species. They shall be removed before the flowering stage of each species. Should the Contractor fail to remove the alien plant species before flowering he shall be held responsible for alien plant removal within the affected area, for an additional period of one year, over and above the contractual one-year defects liability period.

The method for the removal of undesirable plant species shall be either by hand, which shall include the removal of the complete root system, or by chemical means, through the use of a registered selective herbicide. A registered, licensed pest control operator, licensed for the industrial application of herbicides, shall only administer the application of the herbicide.

g) Establishment of vegetation within areas disturbed by construction activities

The Employers Agent shall assess any area within the construction boundaries that has been disturbed by construction activities, but which is not scheduled for formal revegetation within the contract. The assessment shall include whether re-vegetation is required. These disturbed areas, none the less remain the Contractor's responsibility for the removal of alien vegetation (see 5807(e))."

B5809 MEASUREMENT AND PAYMENT

Item	Unit
B58.03	Preparing the areas for grassing

- (c) Topsoiling within the road reserve,
where the following materials are used:

REPLACE SUBSUBITEM (i) WITH THE FOLLOWING:

- "(i) Topsoil obtained from within the road
reserve or borrow areas (including
all haul) cubic metre (m³)"

REPLACE SUBITEM (f) WITH THE FOLLOWING:

- "(f) Stockpiling topsoil (including all haul) cubic metre (m³)"

REPLACE THE THIRD PARAGRAPH OF MEASUREMENT AND PAYMENT ITEMS "(c)
and (d) Placing the topsoil," WITH THE FOLLOWING:

"The tendered rates shall include full compensation for excavating and loading the topsoil,
any royalties or compensation that may be payable in the case of topsoil under subsubitem
B58.03(c)(ii), transport including all haul, off-loading, placing and spreading it to the
required thickness, levelling it off to a smooth surface, for removing any stones as specified
and for roughening the surface to be topsoiled."

*DELETE THE FIRST SENTENCE OF THE LAST PARAGRAPH OF MEASUREMENT
AND PAYMENT ITEMS "(c) and (d) Placing the topsoil."*

COLTO CHAPTER 6 CONCRETE LAYERS**6.2 SEGMENTAL BLOCK PAVING LAYERS****PART C MEASUREMENT AND PAYMENT**

ADD THE FOLLOWING PAY ITEM:

“BC6.2.5 EXISTING PAVING

- a) Lifting up existing paving blocks including neatly stacking on site designated by the Employers agent
(i) All types and sizes Square meter (m²)
- b) Lifting up existing paving blocks and spoil material
(i) All types and sizes Square meter (m²)

The unit of measurement shall be the square meter of existing paving lifted, and stockpiled or spoiled. The quantity shall be calculated from the dimensions shown on the drawings or authorized by the Engineer.

The tendered rate shall include full compensation for removal of the paving, and stockpiling or spoiling with in a free haul distance of 0,5 km, for all other work necessary to complete specified.”

BC6.2.6 TESTING OF BRICKS AS PER SANS 1058:2007.
THE TENDERED UNIT RATE SHALL INCLUDE
FULL COMPENSATION FOR TESTING PER UNIT BATCH.....Square
 metre (m²)

COTO CHAPTER 20: QUALITY ASSURANCE

For the purposes of this contract, the acceptance and rejection of material and workmanship shall be according to Quality Control Scheme 2.

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE REHABILITATION OF SEDIBA ROAD AND CULVERT UPGRADE UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

C3.7 PARTICULAR SPECIFICATIONS

PCL : COMMUNITY LIAISON AND COMMUNITY RELATIONS

PES : LOCATING AND PROTECTING EXISTING SERVICES

PLIS : LABOUR INTENSIVE SPECIFICATION

PCL: COMMUNITY LIAISON AND COMMUNITY RELATIONS**PCL 1 GENERAL**

The construction site is situated in a built-up area and the Contractor shall ensure the least possible disruption of movement of the public during construction. The Contractor shall be responsible for liaison with the Community Liaison Officer (CLO) in respect of construction activities next to private properties and entrances to properties. No separate payment will be made in this regard.

PCL 2 PROJECT STEERING COMMITTEE (PSC)

A Project Steering Committee (PSC) will be established for the project. The functions and powers of the PSC will be as approved by the Mantsopa Local Municipality.

In view of the Contract being executed in various Municipal Wards and to limit representation on the PSC, the PSC will consist of the local Ward Councillors and a total of three community representatives appointed by the Ward Councillors affected by the Works.

The Contractor will liaise with the CLO and Ward Councillors for the permanent appointment of local labour workforce for the duration of the Contract, irrelevant of the work being executed in various wards.

PCL 3 PUBLIC LIAISON OFFICER (PLO)

A Community Liaison Officer (CLO) will be appointed by the Contractor only on instruction of the Employer. In the event of an appointment of a CLO, the contractor shall, however, accept the appointment as part of his management personnel.

PCL 3.1 DUTIES OF THE CLO

The CLO's duties will be the following:

- a. The CLO will liaise with the PSC for the permanent appointment of local labour workforce for the duration of the Contract, irrelevant of the work being executed in various wards.
- b. To be available on site daily between the hours of 07:15 and 10:30 and at other times as the need arises. His normal work day will extend from 07:15 in the morning until 16:45 in the afternoon inclusive of a thirty minute lunch interval.
- c. To determine, in consultation with the Contractor, the needs of the local labour for relevant technical training. He will be responsible for the identification of suitable trainees and will attend one of each of the training sessions.
- d. To communicate with the Contractor and the Engineer to determine the labour requirements with regard to numbers and skill, to identify possible labour disputes and to assist in their resolution.
- e. To attend all meetings in which the community and/or labour is present or is required to be represented. In particular he will attend the first part of the monthly Site Meeting to report on local community labour involvement.
- f. To report to and liaise with the Project Steering Committee.
- g. To inform local labour of their conditions of employment and to inform local labourers as early as possible when their period of employment will be terminated.
- h. To ensure that all labourers who are involved in activities where tasks have been set are fully informed regarding the principle of task work.
- i. To attend disciplinary proceedings to ensure that hearings are fair and reasonable.
- j. To receive and attend to any complaints lodge by PSC and members of the community.

- k. To keep a daily written record of his interviews and community liaison.
- l. All such other duties as agreed upon between all parties concerned.
- m. To prevent any interference with any matter that is in conflict with the relevant contract as approved by the Local Municipality, that could have a direct influence on the technical specification or the conditions of contract as set out in the relevant contract documents.
- n. To ensure that no member of the PSC or any member of the community put any pressure on the consultant and/or the contractor involved to make any financial or other contribution to individuals or the community as a whole without the knowledge of the Municipality.

PCL 3.2 PAYMENT FOR THE CLO

The Contractor shall give to the CLO, at the earliest opportunity, written notice of the termination of the project, provided always that such notice shall not be less than one month.

PES : LOCATING AND PROTECTING EXISTING SERVICES**PES 1 GENERAL**

All services are not known and it will be the responsibility of the contractor to locate and protect all services in the vicinity of the construction work.

PES 2 LOCATION OF EXISTING SERVICES

Before underground or excavation work is carried out, the Contractor shall ascertain the presence and position of all services likely to be damaged or interfered with by his activities. He shall obtain up-to-date plans from the Engineer for this purpose, showing the position of services in the area where he intends to work. As services can often not be reliably located from such plans, the Contractor shall determine the exact position of such services by means of suitable detecting equipment and afterwards by careful hand excavation where necessary in order to expose the services at the positions of possible interference by his activities. This procedure shall also be followed in respect of services not shown on the plans but believed to be present.

All such services, the positions of which have been located at the critical points, shall be designated as 'known' services and their positions shall be indicated on a separate set of Drawings, a copy of which shall be furnished to the Engineer.

While he is occupying the Site, the Contractor shall be liable for all damage caused by him to known services as well as for consequential damage, whether caused directly by his operations or by the lack of proper protection.

PES 3 PROTECTION DURING CONSTRUCTION

The Contractor shall exercise all the necessary care to prevent damage to known services during construction operations. Major excavating equipment and other Plant shall not be operated dangerously close to these services. Where necessary, excavation in close proximity to these services shall be carefully carried out with suitable hand tools, excluding picks wherever their use could damage the services. No additional payment will apply to such more difficult work.

Services left exposed shall be suitably protected from damage.

PES 4 MEASUREMENT AND PAYMENT**Location and protection of existing services:****PES 4.1 Provision of detecting devices for:**

- | | | |
|-----|------------------------------------|------------|
| (a) | <u>Water and sewer pipes</u> | Unit : Sum |
| (b) | <u>Electrical and other cables</u> | Unit : Sum |

The tendered sums shall cover the cost of providing and operating suitable equipment for as long as it is needed to locate all the existing services likely to be affected by the construction activities. Alternatively, an approved specialist firm may be employed to carry out the work.

PES 4.2 Hand excavation necessary for locating and exposing existing services in all material:

- | | | |
|-----|---------------------------|-----------------------|
| (a) | <u>In roadways</u> | Unit : m ³ |
| (b) | <u>In all other areas</u> | Unit : m ³ |

The rates shall cover the cost of excavating by means of hand tools within authorised dimensions, for all precautionary measures to protect the services from damage during excavation and backfilling, and for subsequent backfilling and compacting. Compaction of material in all areas except in roadways shall be to 90% of the modified AASHTO density.

The rate for hand excavation in roadways shall include compensation for compacting excavated or selected backfill material to 93% of modified AASHTO density. Reinstating layerworks and surfacing shall be measured and paid separately.

The tendered rates shall also include for keeping excavations safe, for dealing with surface and subsurface water, for removing surplus excavated material from the Site, for transporting all material within the free-haul distance, and for supplying adequate supervision during both excavation and backfilling operations.

PLIS : LABOUR INTENSIVE SPECIFICATION

PLIS 1 SCOPE

PLIS 1.1. Scope of Specification

All items in the schedule of quantities with a "(L)" added to the item reference, will be classed as a Labour intensive task, and labour intensive principals must be used.

This specification establishes general requirements for activities which are to be executed by hand involving the following :

- (a) trenches having a depth of less than 1.5 metres
- (b) storm water drainage
- (c) low-volume roads and sidewalks

PLIS 1.2. Precedence

Where this specification is in conflict with any other standard or specification referred to in the Scope of Works to this contract, the requirements of this specification shall prevail.

PLIS 1.3. Hand excavatable material

Hand excavatable material is material :

- (a) granular materials :
 - i. whose consistency when profiled may in terms of table 1 be classified as very loose, loose, medium dense or dense; or
 - ii. where the material is a gravel having a maximum particle size of 10 mm and contains no cobbles or isolate boulders, no more than 15 blows of a dynamic cone penetrometer is required to penetrate 100 mm;
- (b) cohesive materials
 - i. whose consistency when profiled may in terms of table 1 be classified as very soft, soft, firm, stiff and stiff / very stiff; or
 - ii. where the material is a gravel having a maximum particle size of 10 mm and contains no cobbles or isolated boulders, no more than 8 blows of a dynamic con penetrometer is required to penetrate 100 mm;

Note : 1) A boulder, a cobble and gravel material is with a particle size greater than 200 mm.

2) A dynamic cone penetrometer is an instrument used to measure the insitu shear resistance of a soil comprising a drop weight of approximately 10 kg which falls through a height of 400 mm and drives a cone having a maximum diameter of 20 mm (cone angle of 60° with respect to the horizontal) into the material being used.

TABLE 1.3 STANDARD TASKS

ACTIVITY	TOOLS	TASK	
Bush clearing	Axe, saw, rope	Medium dense bush (4 to 7 bushes per 100 m ²) 350 m ² /md Dense bush (10 to 15 bushes per 100 m ²) 200 m ² /md Very dense bush (20 to 30 bushes per 100 m ²) 100 m ² /md	
Grass clearing	Slasher, spade, hoe, fork, rake.	Dense grass 85 m ² /md	
Stripping ground cover and grubbing out roots, haul to nearby dump and spread	Pick, shovel, fork, rake	Light vegetation, dig to 50 mm deep 150 m ² /md Medium vegetation, dig to 100 mm deep 75 m ² /md Heavy vegetation, dig to 150 mm deep 40 m ² /md Dig in soft ground to remove roots 42 m ² /md	
Grubbing out roots to 250 mm deep Destumping (removal of stumps and large roots)	Pick, shovel, fork, rake Pick, shovel, axe	Medium dense bush 60 m ² /md	
Removal of bush and tree cuttings	Bush hook, rope, axe, saw	Cut, bundle and load branches, tree trunk pieces, other vegetation 8 m ³ /md	
Boulder removal	Crowbar	Daily paid	
Excavation (measured in place) Loose soil Sticky soil Firm soil Hard stony gravel	Shovel Spade, fork, forked hoe Pick, shovel, spade, hoe Pick, shovel, crowbar	Throwing distance: up to 4 m 4 to 6 m 5 to 6 m ³ /md 4.5 to 5 m ³ /md 2 to 3 m ³ /md 1.5 to 2 m ³ /md 3 to 4.5 m ³ /md 2.5 to 4 m ³ /md 1.5 to 2 m ³ /md 1 to 1.5 m ³ /md	
Loading (measured loose) into: Wheelbarrow Trailer Truck	Shovel	Loose soil or gravel: 12 to 15 m ³ /md 7 to 10 m ³ /md 4 to 6 m ³ /md	
Levelling roadbed (measured loose)	Shovel, spreader	60 m ² /md	
Wheel-barrow haul (measured loose; haul and unload only)	Wheelbarrow (Note production increases 30% for good haul route and decreases 30% for poor haul route)	Equivalent haul distance = length + 10(rise + fall)	Production in loose m ³ /md over average haul route
		20 m	4.44
		40	3.16
		60	2.44
		80	2.00
		100	1.70
		120	1.44
		140	1.28
		160	1.15
		180	1.02
		200	0.95

ACTIVITY	TOOLS	TASK
Picking loose roadbed (bank m3)	Pick, shovel, fork	40 m2/md
Spreading loose material (loose m3)	Shovel, spreader, hoe	Soil 12 loose m3/md Gravel 10 loose m3/md
WATER ING, mixing, spreading and levelling	Shovel, spreader, hoe, string-lines, water bowser	Sandy soil 4.5 m3/md Gravel 3 m3/md (measured tight after compaction)
Compaction and re-levelling	Roller, string lines, straightedge, shovel, spreader.	Depends upon chosen roller (see below)
Compaction by pedestrian-controlled double drum vibro-roller	"Stampede" rollers: R75/50 S R90/55 S	Mass kg 980 1 350 Passes 5 4 Layer 100 mm 100 mm
Loosen material in trench with pneumatic tools	Compressor, pneumatic tools, team of 4 people	Intermediate 19 m3 for team Rock 12 m3 for team
Screen bedding material	Sieve, shovel	7 m3 loose /md
Offload flat-bed truck or trailer	Shovel	15 m3 loose /md
Trench backfill, hand compaction	Shovel, spreader, hand-stamper, WATER ING can	Backfill, compact, clean-up and load spoil 4.5 m3/md
Collecting loose stone	Gloves, wheelbarrows	Up to 20 m 2.5 m3/md 20 to 50 m 2.0 m3/md
Quarrying, prying out cracked rock	Crowbar, gloves, sledgehammer.	Up to 20 m 0.5 to 1 m3/md
Rock crushing	New Dawn Engineering hand-turned rock crusher, shovel	0.25 m3/md (depends on size of feed-stock and size of product)
Backfill trench and compact	Shovel, WATER ING can, hand stamper	3.0 m3/md
Lay kerbing on level base	Shovel, rubber mallet, string-line, trowel, wheelbarrow	Straight 6.5 to 10.0 m/md Curved 2.0 to 5.0 m/md
Stone pitching: Plain stone pitching Grouted stone pitching Wired and grouted stone pitching	Club hammer, gloves, string-line, shovel, wheelbarrow, stiff broom, pliers, short crowbar	10 to 15 m2/md, 200 mm thick 6 to 10 m2/md, 200 mm thick 3 to 5 m2/md, 200 mm thick
Block paving: placing bedding sand, laying blocks, compacting, joint filling, clean up	Shovel, screed rails and beam, rubber mallet, plate compactor, bass broom, wheelbarrow, gloves	16 to 20 m2/md
Stormwater drainage pipes: trimming, bedding, laying, backfilling, compaction	Shovel, rake, boning rods, hand stamper, WATER ING can, rope and ground anchors	450 mm dia concrete: 1.2 m/md (needs team of 10) 600 mm dia concrete: 1.0 m/md (needs team of 10) 450 mm dia plastic: 3.5 m/md (needs team of 5)
Concrete base slab: batch, mix, transport, pour and finish off	Batching boxes, wheelbarrow, shovel, screed beam, wood float	0.8 m3/md (needs team of 5)
Stone masonry walls	Wheelbarrow, shovel, trowel, club hammer, string line, spirit level, batching box.	1.0 m3/md
Gabion work	Gloves, string-line, shovel, wheelbarrow, pliers, short crowbar	1.5 m3/md

PLIS 1.4. Trench excavation

All hand excavateable material in trenches having a depth of less than 1,5 metres shall be excavated by hand.

PLIS 1.5. Compaction of backfilling to trenches (areas not subject to traffic)

Backfilling to trenches shall be placed in layers of thickness (before compaction) not exceeding 100 mm.

Each layer shall be compacted using hand stampers :

to 90% Proctor density;

such that in excess of 5 blows of a dynamic cone penetrometer (DCP) is required to penetrate 100 mm of the backfill, provided that backfill does not comprise more than 10% gravel of size less than 10 mm and contains no isolated boulders, or

such that the density of the compacted trench backfill is not less than that of the surrounding undisturbed soil when tested comparatively with a DCP.

PLIS 1.6. Excavation

All hand excavateable material including topsoil classified as hand excavateable shall be excavated by hand. Harder material may be loosened by mechanical means prior to excavation by hand.

The excavation of any material which presents the possibility of danger or injury to workers shall not be excavated by hand.

PLIS 1.7. Clearing and grubbing

Grass and small bushes shall be cleared by hand.

PLIS 1.8. Shaping

All shaping shall be undertaken by hand.

PLIS 1.9. Loading

All loading shall be done by hand, regardless of the method of haulage.

PLIS 1.10. Haul

Excavation material shall be hauled to its point of placement by means of wheelbarrows where the haul distance is not greater than 150 m.

PLIS 1.11. Offloading

All material, however transported, is to be off-loaded by hand, unless tipper trucks are utilised for haulage.

PLIS 1.12. Spreading

All material shall be spread by hand.

PLIS 1.13. Compaction

Small areas may be compacted by hand provided that the specified compaction is achieved.

PLIS 1.14. Grassing

All grassing shall be undertaken by sprigging, sodding or seeding by hand.

PLIS 1.15. Stone pitching and rubble concrete masonry

All stone required for stone pitching and rubble concrete masonry, whether grouted or dry, must be collected, loaded, off loaded and placed by hand.

Sand and stone shall be hauled to its point of placement by means of wheelbarrows where the haul distance is not greater than 150 m.

Grout shall be mixed and placed by hand.

PLIS 1.16. Manufactured Elements

Element manufactured or designed by the contractor, such as manhole rings and cover slabs, precast concrete planks and pipes, masonry units and edge beams shall not individually, have a mass of more than 320 kg. In addition, the items shall be large enough so that four workers can conveniently and simultaneously acquire a proper handhold on them.

GUIDELINES FOR SUBCONTRACTING AND LABOUR ENHANCEMENT

C3.7.1 DEFINITIONS

The community means individual and communal property owners, organised groups of road users, other interest groups and departments or spheres of government that may be affected by the location, construction, operation and maintenance of the road to which this contract applies.

"Conventional contract" means any contract for the execution of civil engineering or building or similar construction works, in which the liabilities and responsibilities of the two parties thereto are assigned essentially in a manner which is consistent with that set out in the General Conditions of Contract for Road and Culvert crossing Works for State Road Authorities, 1998 (as published by the Committee of Land Transport Officials) or other similar documents.

"Conventional subcontract" shall be similarly and appropriately construed.

"Contract Participation Goal" (or CPG), is the value of goods, services and works, excluding VAT, for which the Contractor proposes to engage labour and subcontractors.

"Contractor" means any person or group of persons in association, or firm, or body corporate who is registered with the Construction Industry Development Board (CIDB) and:

- a) have a contractor grading designation equal to or higher than a contractor grading designation specified for the Contract, or
- b) contractors registered as potentially emerging enterprises with the CIDB who are registered in one contractor grading designation lower than that required in terms of a) above

"Subcontractor" shall be similarly and appropriately construed.

Emerging contractor means an ABE that cannot reasonably be categorised as a conventional contractor defined above.

Affirmable Business Enterprise (ABE): a business which adheres to statutory labour practices, is a legal entity, registered with the South African Revenue Service and a continuing and Independent Enterprise for profit, providing a Commercially Useful Function and:

- a) Which is at least two thirds owned by one or more previously disadvantaged individuals or, in the case of a company, at least two thirds of the shares are owned by one or more previously disadvantaged individual; and
- b) Whose management and daily business operations are in the control of one or more of the previously disadvantaged individuals who effectively own it.

"Key Personnel" means all contracts managers, site agents, materials and survey technicians, trainers, supervisors, foremen, skilled plant operators, and all other personnel in the permanent employ of the Contractor or his subcontractor who possess special skills and/or who play key roles in the Contractor's or subcontractor's operations.

"Worker" for the purposes of this specification means any person, not being one of the defined key personnel of the Contractor or his subcontractor, who is engaged by the Contractor or subcontractor to participate in the execution of any part of the contract works and shall include unskilled labour, semi-skilled and skilled labour, artisans, clerical workers and the like.

"Workforce" means the aggregate body comprising all workers and shall, unless the context dictates otherwise, include the workforces of the Contractor and all his subcontractors.

"Subcontractor" means any person or group of persons in association, or firm, or body corporate (whether formally constituted or otherwise) not being the Contractor, to whom specific portions or aspects of the works are sublet or subcontracted by the Contractor in accordance with the provisions of the contract.

Level of subcontractor means the level of responsibility carried by and the assistance to be provided to the different grades of subcontractor in the execution of subcontracts.

"Project Committee" is the committee comprising out of the Employer's representative, The Engineer or his representative, the Contractor or his representative and the CLO.

"CLO" is the Community Liaison Officer as appointed by the Contractor and paid under the Contract.

C3.7.2 LABOUR ENHANCED CONSTRUCTION

The Contractor's attention is drawn to the fact that it is an objective of the contract to maximise the labour content of certain operations or portions thereof. In this regard, where the specified work allows for a choice between mechanical or labour-enhanced means, the former shall generally be kept to the practical minimum.

The Contractor shall submit on a monthly basis on the date as determined by the Employer, daily labour returns on the prescribed templates to the Engineer indicating the numbers of labour employed on the works and the activities on which they were engaged.

It is also an objective to utilize SMME's / ABE's in the vicinity of the project, the development of these resources in the execution of the project, and by maximising the amount of project funds retained within the project locality.

C3.7.3 TEMPORARY WORKFORCE

a) Record of workforce and subcontractors

The Contractor shall maintain accurate and comprehensive records of all workers engaged on the contract and shall provide to the Engineer at monthly intervals from the commencement of the contract, interim records substantiating the actual numbers of employment opportunities which have been generated to date and the amounts actually paid in respect thereof. Such interim records shall be in a format approved by the Employer. Labour records of emerging contractors, SMME or ABE subcontractors, where applicable, shall also be provided by the Contractor and shall be deemed to form part of the workforce.

The Contractor shall, on completion of the contract, and as a pre-requisite to the release of any retention money, provide the Engineer with independently audited documentary evidence of the total number of employment opportunities actually generated during the contract.

The value of the target amount (minimum Contract Participation Goal) spent on local labour is prescribed in the *PART T2.1 Contract Data*.

b) Recruitment and selection procedures

The Contractor shall be responsible for the final selection of workers and subcontractors to constitute the temporary workforce but in doing so, shall adhere to the procedures adopted by the CLO along the following guidelines:

The Contractor shall advise the Engineer in writing, of the numbers of each category of temporary worker which he requires, together with the personal attributes which he considers desirable that each category of worker shall possess (taking due cognisance of the provisions of the contract relating to training).

The CLO shall take the necessary actions to identify potential workers for the temporary workforce from communities in the vicinity of the works. The details of all persons applying for employment shall be recorded, including inter-alia:

- Name, address, age and sex
- Marital status and number of dependants
- Qualifications and previous work experience (whether substantiated or not)
- Period since last economically active
- Preference for type of work or task.

The CLO shall make a selection of workers from amongst the applicants, taking due cognisance of his requirements for the workforce as supplied by the Contractor and the provisions of the contract in regard to the provision of training to selected members of the workforce and in accordance with the following principles:

No potential temporary worker shall be precluded from selection by virtue of a lack of skill in any suitable operation forming part of the works, unless:

- all available vacancies have been or can be filled by temporary workers who already possess suitable skills; or
- the completion period allowed in the contract, or the remaining portion of the contract period (as the case may be) is insufficient to facilitate the creation of the necessary skills;

The Contractor shall make a final selection from the list provided by the CLO using the following criteria:

- preference shall be given to the long term unemployed and single heads of households
- in so far as is reasonably practicable, give priority to accommodating the applicants' expressed preferences regarding the types of work for which they are selected and shall not be prejudicial to youth over the age of fifteen years and women.

The same provisions shall apply as is in respect of the selection of additional or replacement members of the workforce as may be necessary from time to time during the contract.

c) Terms and Conditions Pertaining to the Employment of the Temporary Workforce and subcontractors

The onus shall be on the Contractor to ensure that all the requirements of all the acts relating to the employment of workers and subcontractors are observed.

d) Labour Relations and Worker Grievance Procedures

In accordance with the provisions of the General Conditions of Contract, the Contractor shall, at his own cost, be fully responsible for the establishment and maintenance of satisfactory labour relations on site and the resolution of all grievances of temporary workers and subcontractors as may occur.

The Contractor shall at all times adhere to the accepted norms and standards of labour relations prevailing generally in the civil engineering construction industry and shall conduct himself in a fair and reasonable manner, within the constraints as may be imposed upon him by the terms of the contract.

In the event of any temporary worker engaged by the Contractor in terms of the contract, being aggrieved on any issue, he shall have the right to nominate and be supported in any inquiry or disciplinary hearing or investigation instituted by the Contractor, by one member of the temporary workforce.

In the event of any grievance not being satisfactorily resolved through the application of normal dispute resolution procedures described above, then either the Contractor or the worker concerned may require that the matter be referred to the PC for further consideration, with a view to facilitating resolution thereof.

C3.7.4 TRAINING OF THE TEMPORARY WORKFORCE

Selected members of the workforce are to be provided at least with structured training by a nominated subcontractor, in accordance with the provisions of this section. The Contractor shall make all necessary allowances in his program of work to accommodate and facilitate the delivery of such structured training.

ABE subcontractor's workforces will be entitled to receive accredited training that will improve on task skills necessary for the execution and successful completion of the various subcontracts. The Contractor, in conjunction with the Engineer, shall monitor each ABE's progress closely and shall identify those who will benefit from structured construction skills training

The technical training shall comprise of items selected from the table in paragraph 7 of this section and which are relevant to this project.

C3.7.5 ACCREDITED TRAINING AND ATTENDANCE

Only qualified trainers employed by training agencies who are accredited by the Civil Engineering Industry Training Scheme (CEITS), or any other institution recognised by the Department of Labour shall deliver all training certificates affirming the successful participation in the various courses and shall be presented to each attendant.

The contractor shall facilitate in the delivery of training, by instructing and motivating the relevant subcontractor regarding his staff's attendance and participation therein.

The contractor shall further make all reasonable efforts to co-ordinate subcontractor's work with that of the delivery of the structured training

The provision of structured training shall not relieve the Contractor of any of his obligations in terms of clause 24 of the General Conditions of Contract and the Contractor shall remain fully liable for the provision, at his own cost, of any other training of the workforce, additional to the structured training, as deemed to be necessary by the Contractor to achieve the execution and completion of the works strictly in accordance with the provisions of the contract.

C3.7.6 PENALTIES FOR NON-COMPLIANCE

Any deliberate failure or neglect by the Contractor to comply with the provisions of this specification, or any deliberate omission or neglect by the Contractor in adhering to or applying the principles as are described and inherent in this specification, shall be deemed to constitute a warrant for the Engineer to act in terms of clause 55.1.5 of the conditions of contract or the penalties specified for non-attaining the prescribed CPG's will be applied and doubled.

C3.7.7 MEASUREMENT AND PAYMENT

ITEM	UNIT
ITEM	UNIT

B12.02	Community Liaison Officer salary	provisional (Prov) sum
--------	----------------------------------	------------------------

The provisional sum provided shall cover the salary of the duly elected and approved CLO.

ITEM	UNIT
-------------	-------------

B12.04	Training
--------	----------

a)	Training of the temporary workforce	
i)	Technical training	provisional (Prov) sum
ii)	HIV/AIDS	provisional (Prov) sum

The provisional sums provided shall cover all the cost for the training of the temporary workforce.

ITEM	UNIT							
B12.02/4	Handling costs	and	profits	in	respect	of	items	
B12.02 and B12.04	percentage (%)							

The tendered percentage is a percentage of the amounts actually spent under the items, which shall include full compensation for the handling costs of the Contractor, and the profit in connection with the training.

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

C3.6 DRAWINGS**LIST OF DRAWINGS PREPARED BY THE EMPLOYER**

The following is the list of drawings prepared by the Employer and applicable to this Contract:

DRAWING NO.	DESCRIPTION
Issued separately	
R1070-CIV-DRG-100	Layout: Locality And List Of Drawings
R1070-CIV-DRG-101	Layout: Site
R1070-CIV-DRG-102	Layout: Long Section And Layout CH(0-580m)
R1070-CIV-DRG-103	Layout: Long Section And Layout CH(580-1160m)
R1070-CIV-DRG-104	Layout: Long Section And Layout CH(1160-1740m)
R1070-CIV-DRG-105	Layout: Long Section And Layout CH(1740-1995m)
R1070-CIV-DRG-400	Details: Road Crossing, Stormwater & Street Cross Section Detail
R1070-CIV-DRG-401	Details: Bellmouth And Street Signs
R1070-CIV-DRG-402	Details: Road Paving Detail
R1070-CIV-DRG-403	Details: Speed Hump & Pedestrian Crossing
R1070-CIV-DRG-404	Details: Speed Hump & Pedestrian Crossing Details
R1070-CIV-DRG-405	Details: Concrete Side Drain-Outlet And Road Crossing Detail
R1070-STR-DRG-001	Layout: Culvert Site Plan
R1070-STR-DRG-002	Detail: Plan Of Culvert
R1070-STR-DRG-003	Detail: Sections, Elevation And Details Of Culvert
R1070-STR-DRG-004	Detail: Sections And Details Of Culvert And Wing Wall
R1070-STR-DRG-005	Detail: Guardrails(1 of 3)
R1070-STR-DRG-006	Detail: Guardrails(2 of 3)
R1070-STR-DRG-007	Detail: Guardrails(3 of 3)
R1070-STR-DRG-008	Detail: General Notes

Note: Although, elsewhere in the Contract Document, drawings are referred to by their generic numbers only, the alphabetic suffix (if any) to a drawing number as given in this List of Drawings denotes the revision of the drawing that is applicable to this document.

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

PART C4 SITE INFORMATION

SITE INFORMATION**1 NATURE OF GROUND AND SUBSOIL CONDITIONS**

Details of the ground condition shall be provided to the appointed Contractor

DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT

CONTRACT NO: DALRRD-RID-FS-001 (2024/2025)

FOR

APPOINTMENT OF A CONTRACTOR TO UNDERTAKE THE UGRADING OF 2,01KM SEDIBA ROAD AND CULVERT CROSSING UNDER MANGAUNG METRO MUNICIPALITY: FREE STATE PROVINCE.

PART C5 APPENDICES

Appendix A : Tender Drawings

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

**APPENDIX A:
Tender Drawings**

Contractor

Witness 1


Witness 2

Employer

Witness 1

Witness 2

DRAWINGS





























REV	DATE	REVISION	CONSULTANT DRAWING NUMBER	CLIENT DRAWING NUMBER
01	2024/08/01	REVISION	R010-000-002	REV
02	2024/08/01	REVISION	R010-000-002	REV
03	2024/08/01	REVISION	R010-000-002	REV
04	2024/08/01	REVISION	R010-000-002	REV
05	2024/08/01	REVISION	R010-000-002	REV
06	2024/08/01	REVISION	R010-000-002	REV
07	2024/08/01	REVISION	R010-000-002	REV
08	2024/08/01	REVISION	R010-000-002	REV
09	2024/08/01	REVISION	R010-000-002	REV
10	2024/08/01	REVISION	R010-000-002	REV
11	2024/08/01	REVISION	R010-000-002	REV
12	2024/08/01	REVISION	R010-000-002	REV
13	2024/08/01	REVISION	R010-000-002	REV
14	2024/08/01	REVISION	R010-000-002	REV
15	2024/08/01	REVISION	R010-000-002	REV
16	2024/08/01	REVISION	R010-000-002	REV
17	2024/08/01	REVISION	R010-000-002	REV
18	2024/08/01	REVISION	R010-000-002	REV
19	2024/08/01	REVISION	R010-000-002	REV
20	2024/08/01	REVISION	R010-000-002	REV
21	2024/08/01	REVISION	R010-000-002	REV
22	2024/08/01	REVISION	R010-000-002	REV
23	2024/08/01	REVISION	R010-000-002	REV
24	2024/08/01	REVISION	R010-000-002	REV
25	2024/08/01	REVISION	R010-000-002	REV
26	2024/08/01	REVISION	R010-000-002	REV
27	2024/08/01	REVISION	R010-000-002	REV
28	2024/08/01	REVISION	R010-000-002	REV
29	2024/08/01	REVISION	R010-000-002	REV
30	2024/08/01	REVISION	R010-000-002	REV
31	2024/08/01	REVISION	R010-000-002	REV
32	2024/08/01	REVISION	R010-000-002	REV
33	2024/08/01	REVISION	R010-000-002	REV
34	2024/08/01	REVISION	R010-000-002	REV
35	2024/08/01	REVISION	R010-000-002	REV
36	2024/08/01	REVISION	R010-000-002	REV
37	2024/08/01	REVISION	R010-000-002	REV
38	2024/08/01	REVISION	R010-000-002	REV
39	2024/08/01	REVISION	R010-000-002	REV
40	2024/08/01	REVISION	R010-000-002	REV
41	2024/08/01	REVISION	R010-000-002	REV
42	2024/08/01	REVISION	R010-000-002	REV
43	2024/08/01	REVISION	R010-000-002	REV
44	2024/08/01	REVISION	R010-000-002	REV
45	2024/08/01	REVISION	R010-000-002	REV
46	2024/08/01	REVISION	R010-000-002	REV
47	2024/08/01	REVISION	R010-000-002	REV
48	2024/08/01	REVISION	R010-000-002	REV








DURAB CONSULTING
Infrastructure Value Development
100% African Owned

**agriculture, land reform
& rural development**
Department of Agriculture and Rural Development
REPUBLIC OF SOUTH AFRICA

REV	DATE	REVISION	CONSULTANT DRAWING NUMBER	CLIENT DRAWING NUMBER
01	2024/08/01	REVISION	R010-000-002	REV
02	2024/08/01	REVISION	R010-000-002	REV
03	2024/08/01	REVISION	R010-000-002	REV
04	2024/08/01	REVISION	R010-000-002	REV
05	2024/08/01	REVISION	R010-000-002	REV
06	2024/08/01	REVISION	R010-000-002	REV
07	2024/08/01	REVISION	R010-000-002	REV
08	2024/08/01	REVISION	R010-000-002	REV
09	2024/08/01	REVISION	R010-000-002	REV
10	2024/08/01	REVISION	R010-000-002	REV
11	2024/08/01	REVISION	R010-000-002	REV
12	2024/08/01	REVISION	R010-000-002	REV
13	2024/08/01	REVISION	R010-000-002	REV
14	2024/08/01	REVISION	R010-000-002	REV
15	2024/08/01	REVISION	R010-000-002	REV
16	2024/08/01	REVISION	R010-000-002	REV
17	2024/08/01	REVISION	R010-000-002	REV
18	2024/08/01	REVISION	R010-000-002	REV
19	2024/08/01	REVISION	R010-000-002	REV
20	2024/08/01	REVISION	R010-000-002	REV
21	2024/08/01	REVISION	R010-000-002	REV
22	2024/08/01	REVISION	R010-000-002	REV
23	2024/08/01	REVISION	R010-000-002	REV
24	2024/08/01	REVISION	R010-000-002	REV
25	2024/08/01	REVISION	R010-000-002	REV
26	2024/08/01	REVISION	R010-000-002	REV
27	2024/08/01	REVISION	R010-000-002	REV
28	2024/08/01	REVISION	R010-000-002	REV
29	2024/08/01	REVISION	R010-000-002	REV
30	2024/08/01	REVISION	R010-000-002	REV
31	2024/08/01	REVISION	R010-000-002	REV
32	2024/08/01	REVISION	R010-000-002	REV
33	2024/08/01	REVISION	R010-000-002	REV
34	2024/08/01	REVISION	R010-000-002	REV
35	2024/08/01	REVISION	R010-000-002	REV
36	2024/08/01	REVISION	R010-000-002	REV
37	2024/08/01	REVISION	R010-000-002	REV
38	2024/08/01	REVISION	R010-000-002	REV
39	2024/08/01	REVISION	R010-000-002	REV
40	2024/08/01	REVISION	R010-000-002	REV
41	2024/08/01	REVISION	R010-000-002	REV
42	2024/08/01	REVISION	R010-000-002	REV
43	2024/08/01	REVISION	R010-000-002	REV
44	2024/08/01	REVISION	R010-000-002	REV
45	2024/08/01	REVISION	R010-000-002	REV
46	2024/08/01	REVISION	R010-000-002	REV
47	2024/08/01	REVISION	R010-000-002	REV
48	2024/08/01	REVISION	R010-000-002	REV



CLIENT DRAWING NUMBER _____





OPTICAL LOSS BUDGET, X					
0.20	1.20	1.40	1.50	10.00	
OPTICAL TOLERANCE BUDGET					
0.20	1.20	0.75	1.25	1.40	2.50

1. Or, approximate to illustrate the fact: 1 length below the lowest end to the lowest of middle, 1.25 lengths.
2. 1 length below the lowest of middle, 1.25 lengths to mid-crotch, 1.50 lengths to mid-thigh, 1.75 lengths to mid-calf, 1.50 length to mid-ankle, 1.25 lengths to heel, 1.00 length to toe.
3. When waistband is wide, dress and skirt a third approach and ease; the third approach and skirt to waist.
4. Mid-thigh length of gathered waistline is to be 5 lengths, (it is 4.5 in.)
5. Or, approach by increments, gradually, one to three over 4 lengths of 2.50, then increase waistline edge of skirt by 1/2 the 5 lengths average.



CLIENT DRAWING NUMBER .

REVISION	NO.	DATE	BY	CHKD.	DESCRIPTION
1	1	2024/08/20	1	1	1
2	2	2024/08/20	1	1	2
3	3	2024/08/20	1	1	3
4	4	2024/08/20	1	1	4
5	5	2024/08/20	1	1	5
6	6	2024/08/20	1	1	6
7	7	2024/08/20	1	1	7
8	8	2024/08/20	1	1	8
9	9	2024/08/20	1	1	9
10	10	2024/08/20	1	1	10
11	11	2024/08/20	1	1	11
12	12	2024/08/20	1	1	12
13	13	2024/08/20	1	1	13
14	14	2024/08/20	1	1	14
15	15	2024/08/20	1	1	15
16	16	2024/08/20	1	1	16
17	17	2024/08/20	1	1	17
18	18	2024/08/20	1	1	18
19	19	2024/08/20	1	1	19
20	20	2024/08/20	1	1	20



NOTES





1. ALL WORK IS TO BE DONE IN ACCORDANCE WITH THE RELEVANT SECTION OF THE SPECIFICATION.
2. ALL CONCRETE IS TO BE CASTED IN ONE LIFT UNLESS OTHERWISE SPECIFIED.
3. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
4. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
5. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
6. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
7. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
8. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
9. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
10. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
11. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
12. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
13. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
14. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
15. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
16. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
17. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
18. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
19. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.
20. THE CONCRETE IS TO BE CURED BY COVERING WITH PLASTIC OR BY OTHER MEANS TO PREVENT CRACKING.



200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)

200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)

REV	DATE	REVISION	PROJECT DESCRIPTION	CONSULTANT DRAWING NUMBER	REV
1	2024/08/20	1	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	1	1
2	2024/08/20	2	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	2	2
3	2024/08/20	3	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	3	3
4	2024/08/20	4	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	4	4
5	2024/08/20	5	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	5	5
6	2024/08/20	6	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	6	6
7	2024/08/20	7	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	7	7
8	2024/08/20	8	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	8	8
9	2024/08/20	9	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	9	9
10	2024/08/20	10	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	10	10
11	2024/08/20	11	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	11	11
12	2024/08/20	12	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	12	12
13	2024/08/20	13	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	13	13
14	2024/08/20	14	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	14	14
15	2024/08/20	15	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	15	15
16	2024/08/20	16	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	16	16
17	2024/08/20	17	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	17	17
18	2024/08/20	18	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	18	18
19	2024/08/20	19	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	19	19
20	2024/08/20	20	200mm PRECAST PANEL, GUTTER APRON AND BASE SLAB LAYOUT (1:100)	20	20



1. ALL WORK IS ACCORDING TO THE BEST AVAILABLE DATA AND DATA SOURCES.
2. ALL INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
3. ALL INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
4. INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
5. THE INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
6. THE INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
7. THE INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
8. THE INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
9. THE INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.
10. THE INFORMATION IS OBTAINED FROM THE BEST AVAILABLE DATA AND DATA SOURCES.

- [illegible]

[illegible]

[illegible]