

| Item No                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Rate | Amount |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|--------|
| <b><u>SECTION No. 1</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |      |        |
| <b><u>BILL No.1</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |      |        |
| <b><u>PRELIMINARIES</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |      |        |
| <p>1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contract Committee and as amended by this Tender Enquiry.</p> <p>2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.</p> <p>3. Tenderers are referred to the above mentioned documents for the full intent and meaning of each clause thereof. These clauses are hereinafter referred to by clause number and heading only.</p> <p>4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.</p> <p>5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.</p> |          |      |        |
| Carried to Collection                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |      | R      |
| Section 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |        |
| Bill No. 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      |        |
| Preliminaries                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |      |        |

6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F", "V", "T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

**SECTION A: PRINCIPAL BUILDING AGREEMENT**

**DEFINITIONS**

Definitions and interpretation (Clause 1).

1 F: ..... V: ..... T: .....

Item

**OBJECTIVE AND PREPARATION**

Offer, acceptance and performance (Clause 2).

2 F: ..... V: ..... T: .....

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: ..... V: ..... T: .....

Item

Design responsibility (Clause 4).

4 F: ..... V: ..... T: .....

Item

Employer's agents (Clause 5).

5 F: ..... V: ..... T: .....

Item

Site representative (Clause 6).

6 F: ..... V: ..... T: .....

Item

Compliance with regulations (Clause 7).

7 F: ..... V: ..... T: .....

Item

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

Section 1  
Bill No. 1  
Preliminaries

|                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |   |  |
|------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|--|
|                                          | Contract instructions (Clause 17).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |   |  |
| 17                                       | F: ..... V: ..... T: .....<br><br>Setting out of the works (Clause 18.3).<br><br>The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out. | Item |   |  |
| 18                                       | F: ..... V: ..... T: .....<br><br>Assignment (Clause 19).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Item |   |  |
| 19                                       | F: ..... V: ..... T: .....<br><br>Nominated subcontractors (Clause 20).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Item |   |  |
| 20                                       | F: ..... V: ..... T: .....<br><br>Selected subcontractors (Clause 21).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Item |   |  |
| 21                                       | F: ..... V: ..... T: .....<br><br>Employer's Direct contractors (Clause 22).                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Item |   |  |
| 22                                       | F: ..... V: ..... T: .....<br><br>Contractor's Domestic subcontractors (Clause 23).                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Item |   |  |
| 23                                       | F: ..... V: ..... T: .....<br><br><b><u>COMPLETION</u></b><br><br>Practical completion (Clause 24).                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Item |   |  |
| 24                                       | F: ..... V: ..... T: .....<br><br>Works completion (Clause 25).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Item |   |  |
| <b>Carried to Collection</b>             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      | R |  |
|                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |   |  |
| Section 1<br>Bill No. 1<br>Preliminaries |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |   |  |

|                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |   |  |
|---------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|--|
| 25                                                      | <p>F: ..... V: ..... T: .....</p> <p>Final completion (Clause 26).</p> <p>Latent defects liability period (Clause 27).</p> <p>Clause 27.0 is amended by the addition of the following clauses:</p> <p>"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".</p> <p>"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"</p> | Item |   |  |
| 26                                                      | <p>F: ..... V: ..... T: .....</p> <p>Sectional completion (Clause 28).</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Item |   |  |
| 27                                                      | <p>F: ..... V: ..... T: .....</p> <p>Revision of date for practical completion (Clause 29).</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Item |   |  |
| 28                                                      | <p>F: ..... V: ..... T: .....</p> <p>Penalty for non-completion (Clause 30).</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Item |   |  |
| 29                                                      | <p>F: ..... V: ..... T: .....</p> <p><b><u>PAYMENT</u></b></p> <p>Interim payment to the contractor (Clause 31).</p> <p>The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.</p>                                                                                                                                                                                                                                                                                                                                                                                                                        | Item |   |  |
| <b>Carried to Collection</b>                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      | R |  |
| <p>Section 1</p> <p>Bill No. 1</p> <p>Preliminaries</p> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |   |  |

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30 F: ..... V: ..... T: ..... Item

Recovery of expense and loss (Clause 33).

31 F: ..... V: ..... T: ..... Item

Final account and final payment (Clause 34).

32 F: ..... V: ..... T: ..... Item

Payment to other parties (Clause 35).

33 F: ..... V: ..... T: ..... Item

### **CANCELLATION**

Cancellation by Employer - Contractor's default (Clause 36).

34 F: ..... V: ..... T: ..... Item

Cancellation by Employer - Loss and damage (Clause 37).

35 F: ..... V: ..... T: ..... Item

Cancellation by Contractor - Employer's default (Clause 38).

36 F: ..... V: ..... T: ..... Item

Cancellation - Cessation of the works (Clause 39).

37 F: ..... V: ..... T: ..... Item

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

**DISPUTE**

Dispute Settlement (Clause 40)

38 F: ..... V: ..... T: .....

Item

**SUBSTITUTE PROVISIONS**

State Clauses (Clause 41)

39 F: ..... V: ..... T: .....

Item

**CONTRACT VARIABLES**

The Schedule: Pre-Tender information (Clause 42).

40 F: ..... V: ..... T: .....

Item

**CONTRACTING AND OTHER PARTIES (Clause 42.1)**

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries



|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |  |  |                                                                                                                                                                                                                                                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>To be advised.</p> <p>Penalty amount will be 5,75c/R100 of Contract Sum.</p> <p>Clause 42.2.8</p> <p>Intended dates of practical completion and the penalties per calendar day for the works in sections :</p> <p>N/A</p> <p>Clause 42.2.9</p> <p>The law applicable to this agreement shall be that of - Republic of South Africa.</p> <p><b><u>INSURANCES (Clause 42.3)</u></b></p> <p>Clause 42.3.1</p> <p>Contract works insurance to be effected by Contractor for the sum of: Contract Sum</p> <p>With a deductible of : Not exceeding 5% of each and every claim.</p> <p>Clause 42.3.2</p> <p>Supplementary insurance is required : Yes</p> <p>SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).</p> <p>Clause 42.3.3</p> <p>Public liability insurance to be effected by Contractor</p> <p>For the amount of: R 5million</p> <p>With a deductible of: Not exceeding 5% of each and every claim.</p> <p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section 1<br/> Bill No. 1<br/> Preliminaries</p> |  |  | <div style="border: 1px solid black; height: 100%; width: 100%; position: relative;"> <div style="position: absolute; top: 0; right: 0; bottom: 0; left: 0;"></div> <div style="position: absolute; bottom: 0; right: 0; width: 50px; height: 50px; border: 1px solid black; text-align: center; vertical-align: middle;">R</div> </div> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**DOCUMENTS (Clause 42.4)**

Clause 42.4.1

Waiver of the contractor's lien is required :- YES

Clause 42.4.2

Number of construction document copies to be supplied to the Contractor free of charge :- 1

Clause 42.4.3

Bills of Quantities drawn up in accordance with :-

Standard System of Measuring Building Work - Seventh Edition including all amendments

Clause 42.4.4

Number of days for submission of priced documents : 5 working days from the Letter of Appointment.

Clause 42.4.5

JBCC Engineering General Conditions are to be included in the documents :- No

Clause 42.4.6

The contract value is to be adjusted using CPAP:- NO

**SECTION B: PRELIMINARIES**

**DEFINITIONS AND INTERPRETATION (B1)**

Definitions and Interpretation (B1)

41 F: ..... V: ..... T: .....

Item

**DOCUMENTS (B2)**

Checking of documents (B2.1)

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.

42 F: ..... V: ..... T: .....

Item

Provisional Bills of Quantities (B2.2) YES

Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.

43 F: ..... V: ..... T: .....

Item

Availability of construction documentation (B2.3)

44 F: ..... V: ..... T: .....

Item

Interests of Agents (B2.4)

45 F: ..... V: ..... T: .....

Item

Priced documents (B2.5)

46 F: ..... V: ..... T: .....

Item

Tender submission (B2.6)

Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.

47 F: ..... V: ..... T: .....

Item

### **THE SITE (B3)**

Defined works area (B3.1)

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.

Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.

The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.

|    |                                                          |      |  |  |
|----|----------------------------------------------------------|------|--|--|
| 48 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Geotechnical investigation (B3.2)                        |      |  |  |
|    | A desktop geotechnical report is available upon request. |      |  |  |
| 49 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Inspection of the Site (B3.3)                            |      |  |  |
| 50 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Existing premises occupied (B3.4)                        |      |  |  |
| 51 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Previous work - dimensional accuracy (B3.5)              |      |  |  |
| 52 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Previous work - defects (B3.6)                           |      |  |  |
| 53 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Services - known (B3.7)                                  |      |  |  |
| 54 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Services - unknown (B3.8)                                |      |  |  |
| 55 | F: ..... V: ..... T: .....                               | Item |  |  |
|    | Protection of trees (B3.9)                               |      |  |  |

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

|                                          |                                                                                                           |      |   |  |
|------------------------------------------|-----------------------------------------------------------------------------------------------------------|------|---|--|
| 56                                       | F: ..... V: ..... T: .....<br>Articles of value (B3.10)                                                   | Item |   |  |
| 57                                       | F: ..... V: ..... T: .....<br>Inspection of adjoining properties (B3.11)                                  | Item |   |  |
| 58                                       | F: ..... V: ..... T: .....<br><b><u>MANAGEMENT OF CONTRACT (B4)</u></b><br>Management of the Works (B4.1) | Item |   |  |
| 59                                       | F: ..... V: ..... T: .....<br>Programme for the Works (B4.2)                                              | Item |   |  |
| 60                                       | F: ..... V: ..... T: .....<br>Progress meetings (B4.3)                                                    | Item |   |  |
| 61                                       | F: ..... V: ..... T: .....<br>Technical meetings (B4.4)                                                   | Item |   |  |
| 62                                       | F: ..... V: ..... T: .....<br><b><u>SAMPLES AND SHOP DRAWINGS (B5)</u></b><br>Samples of materials (B5.1) | Item |   |  |
| 63                                       | F: ..... V: ..... T: .....<br>Workmanship samples (B5.2)                                                  | Item |   |  |
| 64                                       | F: ..... V: ..... T: .....<br>Shop drawings (B5.3)                                                        | Item |   |  |
| 65                                       | F: ..... V: ..... T: .....<br><b><u>TEMPORARY WORKS AND PLANT (B6)</u></b><br>Deposits and fees (B6.1)    | Item |   |  |
| <b>Carried to Collection</b>             |                                                                                                           |      | R |  |
| Section 1<br>Bill No. 1<br>Preliminaries |                                                                                                           |      |   |  |

TMT-DBE-23/24-SAFEOS-ECCL64-2  
VUYISILE JUNIOR SECONDARY SCHOOL  
THE MVULA TRUST SAFE PROGRAMME - OMMITED SCOPE

|                                          |                                                                                                                                                                                                                                                                                                                                          |                       |  |   |
|------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--|---|
| 66                                       | F: ..... V: ..... T: .....<br><br>Enclosure of the works (B6.2)<br><br>The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others. | Item                  |  |   |
| 67                                       | F: ..... V: ..... T: .....<br><br>Advertising (B6.3)                                                                                                                                                                                                                                                                                     | Item                  |  |   |
| 68                                       | F: ..... V: ..... T: .....                                                                                                                                                                                                                                                                                                               | Item                  |  |   |
| Section 1<br>Bill No. 1<br>Preliminaries |                                                                                                                                                                                                                                                                                                                                          | Carried to Collection |  |   |
|                                          |                                                                                                                                                                                                                                                                                                                                          |                       |  | R |

Section 1  
Bill No. 1  
Preliminaries

Section 1  
Bill No. 1  
Preliminaries

Section 1  
Bill No. 1  
Preliminaries

**SECTION C: SPECIFIC PRELIMINARIES****Section C: Specific Preliminaries:****C1. Proprietary branded products**

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: ..... V: ..... T: .....

Item

**C2. Trade Names, etc.**

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: ..... V: ..... T: .....

Item

**C3. Contractors responsibility**

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: ..... V: ..... T: .....

Item

**Carried to Collection**

R

Section 1  
Bill No. 1  
Preliminaries

## C4. Overtime

Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.

97 F: ..... V: ..... T: .....

Item

## C5. As built drawings

The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.

Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.

98 F: ..... V: ..... T: .....

Item

## C6. Construction Instructions

Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:

## a) Construction Instruction Book:

Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.

Only instructions issued in such book shall be recognised.

## b) Daily Record Book:

**Carried to Collection**

**R**

Section 1  
Bill No. 1  
Preliminaries

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                              |   |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------------------------|---|
|     | <p>The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.</p> |      |                              |   |
| 99  | <p>F: ..... V: ..... T: .....</p> <p>C7. Labour record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.</p>                                                                                                                                                                                                                                                                                                                    | Item |                              |   |
| 100 | <p>F: ..... V: ..... T: .....</p> <p>C8. Plant record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.</p>                                                                                                                                                                                                                                                                                                                                          | Item |                              |   |
| 101 | <p>F: ..... V: ..... T: .....</p> <p>C9. Encroachment</p> <p>During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.</p>                                                                                                                                                                                                                                                                        | Item |                              |   |
| 102 | <p>F: ..... V: ..... T: .....</p> <p>C10. Method Statement</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Item |                              |   |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                              |   |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      | <b>Carried to Collection</b> |   |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                              | R |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      | Section 1                    |   |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      | Bill No. 1                   |   |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      | Preliminaries                |   |

|                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |   |  |
|---------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|--|
|                                                   | <p>The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.</p>                                                                                                                                                                                                                                                                                                                                           |      |   |  |
| 103                                               | <p>F: ..... V: ..... T: .....</p> <p>C11. Unauthorised Persons/Workmen on Premises</p> <p>The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect.</p> <p>No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.</p>                                                                                                                                                                                                                                                                                                  | Item |   |  |
| 104                                               | <p>F: ..... V: ..... T: .....</p> <p>C12. Mode of Procedure</p> <p>Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.</p> <p>Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.</p> | Item |   |  |
| 105                                               | <p>F: ..... V: ..... T: .....</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Item |   |  |
| <p><b>Carried to Collection</b></p>               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      | R |  |
| <p>Section 1<br/>Bill No. 1<br/>Preliminaries</p> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |   |  |

|                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |   |  |
|---------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|--|
|                                                         | <p>C13. Location of Temporary Buildings and Temporary Services</p> <p>The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period.</p> <p>There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.</p> |      |   |  |
| 106                                                     | <p>F: ..... V: ..... T: .....</p> <p><b><u>C14. Office accommodation</u></b></p> <p>The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]</p>                                                                                                                                                                                                                                                                                                                                                                                                                                           | Item |   |  |
| 107                                                     | <p>F: ..... V: ..... T: .....</p> <p><b><u>C15. Storage Facilities</u></b></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Item |   |  |
| 108                                                     | <p>The Contractor shall provide a Container for storage of materials.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Item |   |  |
| 109                                                     | <p>F: ..... V: ..... T: .....</p> <p>C16. Removal and Making Good of Temporary Works, etc, on Completion</p> <p>The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.</p>                                                                                                                                                                                                                                                                                                                                                                                                                   | Item |   |  |
| 110                                                     | <p>F: ..... V: ..... T: .....</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Item |   |  |
| <b>Carried to Collection</b>                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      | R |  |
| <p>Section 1</p> <p>Bill No. 1</p> <p>Preliminaries</p> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |   |  |

111

SUB - TOTAL: FIXED ITEMS

Item

112

SUB - TOTAL: VALUE - RELATED ITEMS

Item

113

SUB - TOTAL: TIME - RELATED ITEMS

Item

Section 1

Bill No. 1

Preliminaries

Carried to Collection

R

[illegible]

[illegible]

-161-

The costs included herein must incorporate Community Liaison Officer (CLO).

### **OCCUPATIONAL HEALTH AND SAFETY**

#### **General:**

|   |                                                                                                                                                                                                                                    |    |      |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|
| 1 | Preparation of Contractor's site specific Health and Safety Plan.                                                                                                                                                                  |    | Item |
| 2 | Submission of the Health and Safety File.                                                                                                                                                                                          |    | Item |
| 3 | Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.                                                                                                                                 |    | Item |
| 4 | Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.                                                                                         |    | Item |
| 5 | Provision of full time Health and Safety Officer for the entire construction period.                                                                                                                                               |    | Item |
| 6 | Induction training of personnel.                                                                                                                                                                                                   | No | 1    |
| 7 | Provision of first aid boxes.                                                                                                                                                                                                      | No | 1    |
| 8 | SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc | m  | 280  |
| 9 | Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high.                                                                                                                                                                    | No | 2    |

#### **Provision for Personal Protective Equipment and Protective Clothing:**

|    |                       |    |    |
|----|-----------------------|----|----|
| 10 | Reflective vests.     | No | 25 |
| 11 | Hard hats.            | No | 25 |
| 12 | Protective foot wear. | No | 25 |
| 13 | Ear Plugs.            | No | 75 |

**Carried to Collection**

R

Section 1  
Bill No. 2  
Health and Safety

Section 1  
Bill No. 2  
Health and Safety



Section 1

| Item No |                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Rate | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|--------|
|         | <b><u>SECTION No. 2</u></b>                                                                                                                                                                                                                                                                                                                                                                            |          |      |        |
|         | <b><u>BILL No. 1</u></b>                                                                                                                                                                                                                                                                                                                                                                               |          |      |        |
|         | <b><u>DEMOLITIONS</u></b>                                                                                                                                                                                                                                                                                                                                                                              |          |      |        |
|         | <b><u>MODEL PREAMBLES</u></b>                                                                                                                                                                                                                                                                                                                                                                          |          |      |        |
|         | The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates                                                                                                                                                                           |          |      |        |
|         | <b><u>SUPPLEMENTARY PREAMBLES</u></b>                                                                                                                                                                                                                                                                                                                                                                  |          |      |        |
|         | <b><u>View site</u></b>                                                                                                                                                                                                                                                                                                                                                                                |          |      |        |
|         | Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained |          |      |        |
|         | <b><u>Explosives</u></b>                                                                                                                                                                                                                                                                                                                                                                               |          |      |        |
|         | No explosives whatsoever may be used for demolition purposes unless otherwise stated.                                                                                                                                                                                                                                                                                                                  |          |      |        |
|         | <b><u>General</u></b>                                                                                                                                                                                                                                                                                                                                                                                  |          |      |        |
|         | Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent.                                                                                               |          |      |        |
|         | Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site.                                                                                                                                                                                                                                                                             |          |      |        |
|         | <b>Carried to Collection</b>                                                                                                                                                                                                                                                                                                                                                                           |          | R    |        |
|         | Section 2<br>Bill No. 1<br>Demolitions                                                                                                                                                                                                                                                                                                                                                                 |          |      |        |

**Removal of asbestos material**

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

**The following shall apply in respect of asbestos removal**

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

**Carried to Collection**

R

Section 2  
Bill No. 1  
Demolitions

**DEMOLISHING AND REMOVING**

|   |                                                                                                                                                                                                                                                                             |    |      |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|
| 1 | Demolish pit latrine structure comprising of brick/block work with corrugated roof sheeting, approximate size 5 x 4m wide with 3,5m high top structure and 2,0m deep pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). | No | 1    |
| 2 | Cart away rubble from demolitions and dispose off site.                                                                                                                                                                                                                     |    | Item |
| 3 | Backfill existing hole with G7 fill material in max. 150mm layers and compact to 95% MOD AASHTO density.                                                                                                                                                                    | m3 | 80   |
| 4 | Allow for compaction tests by an approved laboratory to determine density of filling material.                                                                                                                                                                              | No | 6    |
| 5 | Provision of a certificate of safe disposal for asbestos.                                                                                                                                                                                                                   |    | Item |

**SUNDRIES****Desludging**

|   |                                                                                                                                                                                                                                                                                                    |    |      |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|
| 6 | Clean out pit latrine by desludging including removal of all debris and waste including solid waste as per Health and Safety requirements and make good on completion including disposing of all debris and waste at an authorised municipal waste disposal facility. Contractor to price per seat | No | 2    |
| 7 | Issue of Certificate of Waste Disposal.                                                                                                                                                                                                                                                            |    | Item |

**Carried to Collection****R**

Section 2  
Bill No. 1  
Demolitions

[illegible]

| Item No |                                                                                                                                                                                                        | Quantity | Rate | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|--------|
|         | <b><u>SECTION No. 3</u></b>                                                                                                                                                                            |          |      |        |
|         | <b><u>BILL No. 1</u></b>                                                                                                                                                                               |          |      |        |
|         | <b><u>SUNDRY BUILDERS WORK - ALL TRADES</u></b>                                                                                                                                                        |          |      |        |
|         | <b><u>Quantity Split:</u></b>                                                                                                                                                                          |          |      |        |
|         | Note that the total quantity per each item is split into the various buildings and appears below each description as follows:                                                                          |          |      |        |
|         | <b><u>ALTERATIONS</u></b>                                                                                                                                                                              |          |      |        |
|         | <b><u>REMOVAL OF EXISTING WORK</u></b>                                                                                                                                                                 |          |      |        |
|         | <b><u>Breaking up and removing reinforced concrete including cutting off and removing reinforcement</u></b>                                                                                            |          |      |        |
| 1       | Steps                                                                                                                                                                                                  | m3       | 3    |        |
| 2       | 80mm thick ramps and walkways                                                                                                                                                                          | m2       | 14   |        |
| 3       | 300 x 400mm Portion of 100mm thick slab                                                                                                                                                                | No       | 4    |        |
|         | <b><u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)</u></b> |          |      |        |
| 4       | Remove VIP 250 Pit pedestal and prepare surface to receive new VIP 450 pedestal (VIP 450 pedestal elsewhere).                                                                                          | No       | 3    |        |
|         | <b><u>Sundries</u></b>                                                                                                                                                                                 |          |      |        |
| 5       | Install galvanised steel padbolt striker plate with gate stopper, stopping gate from opening outwards                                                                                                  | No       | 4    |        |
| 6       | Install overflow pipe to water storage tank                                                                                                                                                            | No       | 4    |        |
| 7       | Install hot dipped galvanised steel manhole lock bars to fit existing manhole covers                                                                                                                   | No       | 9    |        |
|         | <b>Carried to Collection</b>                                                                                                                                                                           |          |      | R      |
|         | Section 3                                                                                                                                                                                              |          |      |        |
|         | Bill No. 1                                                                                                                                                                                             |          |      |        |
|         | Sundry Builders Work                                                                                                                                                                                   |          |      |        |

Section 3  
Bill No. 1  
Sundry Builders Work

**SANITARY PLUMBING****PVC waste or vent pipes and fittings:**

|    |                  |   |   |
|----|------------------|---|---|
| 14 | 50mm Waste pipe. | m | 6 |
| 15 | 110mm Pipe.      | m | 3 |

**Extra for:**

|    |                   |    |   |
|----|-------------------|----|---|
| 16 | 50mm Bend.        | No | 8 |
| 17 | 50mm Access bend. | No | 4 |

**Manholes:**

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |    |   |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|
| 18 | Manhole size 600 x 600mm not exceeding 3m deep internally to invert level formed of hard burnt half brick sides in 1:3 cement mortar on and including 100mm thick mass concrete (25 MPa at 28 days in 19 mm stone) bottom reinforced with Y10 bars at 200c/c both directions and projecting 150mm beyond sides, cast on 50mm thick concrete Blinding (15Mpa) and mass concrete (15 MPa at 28 days in 12 mm stone) benching, rendered internally in 1:3 cement plaster with with C.I step irons staggered at 300c/c with 150mm thick grade 25 reinforced precast concrete manhole cover rebated for and fitted with and including cast iron double seal cover and frame type 14B in accordance with SABS 558, bedded in 1:3 cement mortar and sealed in to allow including all necessary vitrified clay channels and fittings, excavations, formwork, holes through sides for pipes, etc | No | 1 |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|

**WATER SUPPLIES****Polycop pipes:**

Pipes shall be class 10.

**Fixing of pipes**

Unless specifically otherwise stated, descriptions of pipes shall be deemed to include for fixing to walls etc. casting in, building in or suspending not exceeding 1m below suspension level

**Carried to Collection**

R

Section 3  
Bill No. 1  
Sundry Builders Work

**Polycop pipes chased in walls:**

Where pipes have been chased in walls, the price for making good of plaster and paint etc shall be deemed to be included in the description of pipe chased in walls.

**Reducing fittings:**

Where fittings have reducing ends or branches they are described as 'reducing'. In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained.

**Class 10 Polycop pipes:**

|    |            |   |    |
|----|------------|---|----|
| 19 | 15mm Pipe. | m | 25 |
| 20 | 22mm Pipe. | m | 30 |

**Extra over polycop pipes for compression fittings:**

|    |                |    |    |
|----|----------------|----|----|
| 21 | 15mm Fittings. | No | 18 |
| 22 | 22mm Fittings. | No | 6  |

**Galvanised Steel Pipe**

|    |                            |   |    |
|----|----------------------------|---|----|
| 23 | 22mm galvanised steel pipe | m | 12 |
|----|----------------------------|---|----|

**Taps, valves, etc.**

**Solid cast brass taps, valves, etc.**

|    |                             |    |   |
|----|-----------------------------|----|---|
| 24 | Bib Tap or Similar approved | No | 4 |
|----|-----------------------------|----|---|

**Carried to Collection**

Section 3  
Bill No. 1  
Sundry Builders Work

R

[illegible]

| Item No |                                                                                                                                                                                                                              | Quantity | Rate | Amount |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|--------|
|         | <b><u>SECTION No. 4</u></b>                                                                                                                                                                                                  |          |      |        |
|         | <b><u>BILL No. 1</u></b>                                                                                                                                                                                                     |          |      |        |
|         | <b><u>EXTERNAL WORKS (PROVISIONAL)</u></b>                                                                                                                                                                                   |          |      |        |
|         | <b><u>MODEL PREAMBLES</u></b>                                                                                                                                                                                                |          |      |        |
|         | The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates |          |      |        |
|         | <b><u>THE FOLLOWING IN WALKWAYS</u></b>                                                                                                                                                                                      |          |      |        |
|         | <u>Cutting out and breaking up and removing reinforced concrete including cutting off and removing reinforcement</u>                                                                                                         |          |      |        |
| 1       | 80mm thick ramps and walkways                                                                                                                                                                                                | m2       | 7    |        |
|         | <u>Excavation not exceeding 2m deep</u>                                                                                                                                                                                      |          |      |        |
| 2       | Reducing levels and depositing excavated material in prescribed stock piles on site.                                                                                                                                         | m3       | 44   |        |
|         | <u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>                                                                                      |          |      |        |
| 3       | Off site to a dumping site to be found by the Contractor.                                                                                                                                                                    | m3       | 9    |        |
|         | <u>Filling supplied by the contractor under walkways</u>                                                                                                                                                                     |          |      |        |
| 4       | G7 Base course material compacted to 98% Mod AASHTO density                                                                                                                                                                  | m3       | 13   |        |
| 5       | Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.                                                                     | m3       | 13   |        |
|         | <b>Carried to Collection</b>                                                                                                                                                                                                 |          |      |        |
|         | Section 4                                                                                                                                                                                                                    |          |      |        |
|         | Bill No. 1                                                                                                                                                                                                                   |          |      |        |
|         | External Works                                                                                                                                                                                                               |          |      |        |
|         |                                                                                                                                                                                                                              |          | R    |        |

TMT-DBE-23/24-SAFEOS-ECCL64-2  
VUYISILE JUNIOR SECONDARY SCHOOL  
THE MVULA TRUST SAFE PROGRAMME - OMMITED SCOPE

|                              |                                                                                                                                 |    |    |  |   |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------|----|----|--|---|
|                              | <u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>                                       |    |    |  |   |
| 6                            | Under floors,etc.                                                                                                               | m2 | 87 |  |   |
|                              | <u>Prescribed density tests on filling:</u>                                                                                     |    |    |  |   |
| 7                            | In-situ dry density test.                                                                                                       | No | 4  |  |   |
|                              | <u>Reinforced 25Mpa/19mm Concrete:</u>                                                                                          |    |    |  |   |
| 8                            | Ramps, Landings, etc.                                                                                                           | m3 | 13 |  |   |
|                              | <u>Finishing top surfaces of concrete smooth with a wood float:</u>                                                             |    |    |  |   |
| 9                            | Surface beds, slabs, etc to falls and currents.                                                                                 | m2 | 87 |  |   |
|                              | <u>Test blocks:</u>                                                                                                             |    |    |  |   |
| 10                           | Making and testing of 150x150x150mm concrete strength test cubes (Provisional).                                                 | No | 4  |  |   |
|                              | <u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>                         |    |    |  |   |
| 11                           | 12mm Joints not exceeding 300mm high.                                                                                           | m  | 87 |  |   |
|                              | <u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>                            |    |    |  |   |
| 12                           | 10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.                       | m  | 87 |  |   |
|                              | <u>Fabric reinforcement:</u>                                                                                                    |    |    |  |   |
| 13                           | REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.                                                             | m2 | 87 |  |   |
|                              | <u>Waterproofing under Surface beds</u>                                                                                         |    |    |  |   |
| 14                           | 350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured). | m2 | 87 |  |   |
| <b>Carried to Collection</b> |                                                                                                                                 |    |    |  | R |
| Section 4                    |                                                                                                                                 |    |    |  |   |
| Bill No. 1                   |                                                                                                                                 |    |    |  |   |
| External Works               |                                                                                                                                 |    |    |  |   |

Section 4  
Bill No. 1  
External Works

|                                                                                                                                            |                                                                                                                                                                                                               |    |     |  |  |   |  |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|--|--|---|--|
| <b><u>THE FOLLOWING IN ONE BRICK WALL<br/>(GARDEN WALL)</u></b>                                                                            |                                                                                                                                                                                                               |    |     |  |  |   |  |
| <u>Excavation in earth not exceeding 2m deep:</u>                                                                                          |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 16                                                                                                                                         | Trenches.                                                                                                                                                                                                     | m3 | 59  |  |  |   |  |
| <b><u>Extra over trench and hole excavations in earth for excavation in:</u></b>                                                           |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 17                                                                                                                                         | Soft rock.                                                                                                                                                                                                    | m3 | 18  |  |  |   |  |
| 18                                                                                                                                         | Hard rock.                                                                                                                                                                                                    | m3 | 9   |  |  |   |  |
| 19                                                                                                                                         | Reinforced concrete                                                                                                                                                                                           | m3 | 12  |  |  |   |  |
| <u>Extra over all excavations for carting away:</u>                                                                                        |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 20                                                                                                                                         | Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.                                                                                               | m3 | 42  |  |  |   |  |
| <u>Risk of collapse of excavations:</u>                                                                                                    |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 21                                                                                                                                         | Sides of trench and hole excavations not exceeding 1,5m deep.                                                                                                                                                 | m2 | 237 |  |  |   |  |
| <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>              |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 22                                                                                                                                         | Backfilling to trenches, holes, etc.                                                                                                                                                                          | m3 | 28  |  |  |   |  |
| <u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u> |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 23                                                                                                                                         | Under footings.                                                                                                                                                                                               | m3 | 13  |  |  |   |  |
| <u>Compaction of surfaces</u>                                                                                                              |                                                                                                                                                                                                               |    |     |  |  |   |  |
| 24                                                                                                                                         | Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density. | m2 | 57  |  |  |   |  |
| <b>Carried to Collection</b>                                                                                                               |                                                                                                                                                                                                               |    |     |  |  | R |  |
| Section 4                                                                                                                                  |                                                                                                                                                                                                               |    |     |  |  |   |  |
| Bill No. 1                                                                                                                                 |                                                                                                                                                                                                               |    |     |  |  |   |  |
| External Works                                                                                                                             |                                                                                                                                                                                                               |    |     |  |  |   |  |

TMT-DBE-23/24-SAFEOS-ECCL64-2  
VUYISILE JUNIOR SECONDARY SCHOOL  
THE MVULA TRUST SAFE PROGRAMME - OMMITED SCOPE

|                              |                                                                                                                                                                                                                                                                                   |    |      |   |  |
|------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|---|--|
|                              | <u>25 Mpa/19mm Concrete</u>                                                                                                                                                                                                                                                       |    |      |   |  |
| 25                           | Strip footings.                                                                                                                                                                                                                                                                   | m3 | 17   |   |  |
|                              | <u>Test blocks:</u>                                                                                                                                                                                                                                                               |    |      |   |  |
| 26                           | Making and testing of 150x150x150mm concrete strength test cubes (Provisional).                                                                                                                                                                                                   | No | 4    |   |  |
|                              | <u>Reinforcement (Provisional)</u>                                                                                                                                                                                                                                                |    |      |   |  |
| 27                           | High tensile steel reinforcement bars to structural concrete work.                                                                                                                                                                                                                | t  | 1.68 |   |  |
|                              | <u>BRICKWORK IN FOUNDATIONS.</u>                                                                                                                                                                                                                                                  |    |      |   |  |
|                              | <u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>                                                                                                                                                   |    |      |   |  |
| 28                           | One brick walls.                                                                                                                                                                                                                                                                  | m2 | 51   |   |  |
|                              | <u>BRICKWORK IN SUPERSTRUCTURE</u>                                                                                                                                                                                                                                                |    |      |   |  |
|                              | <u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>                                                                                                                                                  |    |      |   |  |
| 29                           | One brick walls.                                                                                                                                                                                                                                                                  | m2 | 85   |   |  |
|                              | <u>Brickwork reinforcement:</u>                                                                                                                                                                                                                                                   |    |      |   |  |
| 30                           | 230mm Wide reinforcement built in horizontally.                                                                                                                                                                                                                                   | m  | 339  |   |  |
| 31                           | Ditto but in foundations.                                                                                                                                                                                                                                                         | m  | 678  |   |  |
|                              | <u>FACE BRICK</u>                                                                                                                                                                                                                                                                 |    |      |   |  |
|                              | <u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u> |    |      |   |  |
| 32                           | One brickwall faced on both sides.                                                                                                                                                                                                                                                | m2 | 237  |   |  |
| <b>Carried to Collection</b> |                                                                                                                                                                                                                                                                                   |    |      | R |  |
| Section 4                    |                                                                                                                                                                                                                                                                                   |    |      |   |  |
| Bill No. 1                   |                                                                                                                                                                                                                                                                                   |    |      |   |  |
| External Works               |                                                                                                                                                                                                                                                                                   |    |      |   |  |

|    |                                                                                                                                                                                                                                                                                                                                                                                     |   |     |                                       |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|---------------------------------------|
| 33 | <p><u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u></p> <p>230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.</p> | m | 170 |                                       |
|    | <p>Section 4<br/>Bill No. 1<br/>External Works</p>                                                                                                                                                                                                                                                                                                                                  |   |     | <p>Carried to Collection</p> <p>R</p> |

| <b><u>STORMWATER CHANNELS</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|---|--|
| <u>Excavation not exceeding 2m deep</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 34                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Reducing levels and depositing excavated material in prescribed stock piles on site.                                                                                                                                                                                                                  | m3 | 41  |   |  |
| <u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 35                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Off site to a dumping site to be found by the Contractor.                                                                                                                                                                                                                                             | m3 | 41  |   |  |
| <u>Filling supplied by the contractor under channels</u>                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 36                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | G7 Base course material compacted to 98% Mod AASHTO density                                                                                                                                                                                                                                           | m3 | 20  |   |  |
| 37                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.                                                                                                                                              | m3 | 20  |   |  |
| <u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u> |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 38                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.                                                                                              | m  | 113 |   |  |
| 39                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Extra for 700mm angle                                                                                                                                                                                                                                                                                 | No | 18  |   |  |
| 40                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones. | No | 3   |   |  |
| <b><u>THE FOLLOWING IN DISABLED ACCESS</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| <b>Carried to Collection</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                       |    |     | R |  |
| Section 4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| Bill No. 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| External Works                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                       |    |     |   |  |

|                                                                                                                                            |                                                                                                                                                                                                               |    |    |   |  |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|----|---|--|
| <b><u>SCREEN WALL</u></b>                                                                                                                  |                                                                                                                                                                                                               |    |    |   |  |
| <u>Excavation in earth not exceeding 2m deep:</u>                                                                                          |                                                                                                                                                                                                               |    |    |   |  |
| 41                                                                                                                                         | Trenches.                                                                                                                                                                                                     | m3 | 17 |   |  |
| <u>Extra over all excavations for carting away:</u>                                                                                        |                                                                                                                                                                                                               |    |    |   |  |
| 42                                                                                                                                         | Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.                                                                                               | m3 | 8  |   |  |
| <u>Risk of collapse of excavations:</u>                                                                                                    |                                                                                                                                                                                                               |    |    |   |  |
| 43                                                                                                                                         | Sides of trench and hole excavations not exceeding 1,5m deep.                                                                                                                                                 | m2 | 48 |   |  |
| <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>              |                                                                                                                                                                                                               |    |    |   |  |
| 44                                                                                                                                         | Backfilling to trenches, holes, etc.                                                                                                                                                                          | m3 | 8  |   |  |
| <u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u> |                                                                                                                                                                                                               |    |    |   |  |
| 45                                                                                                                                         | Under footings.                                                                                                                                                                                               | m3 | 6  |   |  |
| <u>Compaction of surfaces</u>                                                                                                              |                                                                                                                                                                                                               |    |    |   |  |
| 46                                                                                                                                         | Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density. | m2 | 17 |   |  |
| <u>25 Mpa/19mm Concrete</u>                                                                                                                |                                                                                                                                                                                                               |    |    |   |  |
| 47                                                                                                                                         | Strip footings.                                                                                                                                                                                               | m3 | 4  |   |  |
| <u>Test blocks:</u>                                                                                                                        |                                                                                                                                                                                                               |    |    |   |  |
| 48                                                                                                                                         | Making and testing of 150x150x150mm concrete strength test cubes (Provisional).                                                                                                                               | No | 4  |   |  |
| <b>Carried to Collection</b>                                                                                                               |                                                                                                                                                                                                               |    |    | R |  |
| Section 4                                                                                                                                  |                                                                                                                                                                                                               |    |    |   |  |
| Bill No. 1                                                                                                                                 |                                                                                                                                                                                                               |    |    |   |  |
| External Works                                                                                                                             |                                                                                                                                                                                                               |    |    |   |  |

Section 4  
Bill No. 1  
External Works

|                              |                                                                                                                                                                                                              |    |    |  |   |
|------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|----|--|---|
|                              | <u>Excavation not exceeding 2m deep</u>                                                                                                                                                                      |    |    |  |   |
| 56                           | Reducing levels and depositing excavated material in prescribed stock piles on site.                                                                                                                         | m3 | 7  |  |   |
|                              | <u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>                                                                      |    |    |  |   |
| 57                           | Off site to a dumping site to be found by the Contractor.                                                                                                                                                    | m3 | 7  |  |   |
|                              | <u>Filling supplied by the contractor under floors, aprons, etc</u>                                                                                                                                          |    |    |  |   |
| 58                           | G7 Base course material compacted to 98% Mod AASHTO density                                                                                                                                                  | m3 | 7  |  |   |
| 59                           | Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.                                                     | m3 | 7  |  |   |
|                              | <u>Coarse river sand filling supplied by the contractor:</u>                                                                                                                                                 |    |    |  |   |
| 60                           | Under floors etc.                                                                                                                                                                                            | m3 | 1  |  |   |
|                              | <u>Compaction of surfaces:</u>                                                                                                                                                                               |    |    |  |   |
| 61                           | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density. | m2 | 14 |  |   |
|                              | <u>Prescribed density tests on filling:</u>                                                                                                                                                                  |    |    |  |   |
| 62                           | In-situ dry density test.                                                                                                                                                                                    | No | 4  |  |   |
|                              | <u>Reinforced 25Mpa/19mm Concrete:</u>                                                                                                                                                                       |    |    |  |   |
| 63                           | Ramps, Landings, etc.                                                                                                                                                                                        | m3 | 7  |  |   |
|                              | <u>Finishing top surfaces of concrete smooth with a wood float:</u>                                                                                                                                          |    |    |  |   |
| 64                           | Surface beds, slabs, etc to falls and currents.                                                                                                                                                              | m2 | 14 |  |   |
| <b>Carried to Collection</b> |                                                                                                                                                                                                              |    |    |  | R |
| Section 4                    |                                                                                                                                                                                                              |    |    |  |   |
| Bill No. 1                   |                                                                                                                                                                                                              |    |    |  |   |
| External Works               |                                                                                                                                                                                                              |    |    |  |   |

TMT-DBE-23/24-SAFEOS-ECCL64-2  
VUYISILE JUNIOR SECONDARY SCHOOL  
THE MVULA TRUST SAFE PROGRAMME - OMMITED SCOPE

|                              |                                                                                                                                 |    |    |  |   |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------|----|----|--|---|
|                              | <u>Test blocks:</u>                                                                                                             |    |    |  |   |
| 65                           | Making and testing of 150x150x150mm concrete strength test cubes (Provisional).                                                 | No | 4  |  |   |
|                              | <u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>                         |    |    |  |   |
| 66                           | 12mm Joints not exceeding 300mm high.                                                                                           | m  | 6  |  |   |
|                              | <u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>                            |    |    |  |   |
| 67                           | 10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.                       | m  | 6  |  |   |
|                              | <u>Fabric reinforcement:</u>                                                                                                    |    |    |  |   |
| 68                           | REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.                                                             | m2 | 14 |  |   |
|                              | <u>Waterproofing under Surface beds</u>                                                                                         |    |    |  |   |
| 69                           | 350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured). | m2 | 14 |  |   |
| <b>Carried to Collection</b> |                                                                                                                                 |    |    |  | R |
| Section 4                    |                                                                                                                                 |    |    |  |   |
| Bill No. 1                   |                                                                                                                                 |    |    |  |   |
| External Works               |                                                                                                                                 |    |    |  |   |

|                                                                                                                                         |                                                                                                                                                                                                              |    |     |  |  |   |  |
|-----------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|--|--|---|--|
| <b><u>THE FOLLOWING IN STORMWATER DRAINAGE, APRONS ETC.</u></b>                                                                         |                                                                                                                                                                                                              |    |     |  |  |   |  |
| <b><u>STORMWATER APRONS</u></b>                                                                                                         |                                                                                                                                                                                                              |    |     |  |  |   |  |
| <u>Excavation not exceeding 2m deep</u>                                                                                                 |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 70                                                                                                                                      | Reducing levels and depositing excavated material in prescribed stock piles on site.                                                                                                                         | m3 | 44  |  |  |   |  |
| <u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u> |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 71                                                                                                                                      | Off site to a dumping site to be found by the Contractor.                                                                                                                                                    | m3 | 44  |  |  |   |  |
| <u>Filling supplied by the contractor under floors, aprons, etc</u>                                                                     |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 72                                                                                                                                      | G7 Base course material compacted to 98% Mod AASHTO density                                                                                                                                                  | m3 | 22  |  |  |   |  |
| 73                                                                                                                                      | Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.                                                     | m3 | 22  |  |  |   |  |
| <u>Coarse river sand filling supplied by the contractor:</u>                                                                            |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 74                                                                                                                                      | Under floors etc.                                                                                                                                                                                            | m3 | 7   |  |  |   |  |
| <u>Compaction of surfaces:</u>                                                                                                          |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 75                                                                                                                                      | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density. | m2 | 145 |  |  |   |  |
| <u>Prescribed density tests on filling:</u>                                                                                             |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 76                                                                                                                                      | In-situ dry density test.                                                                                                                                                                                    | No | 4   |  |  |   |  |
| <u>Reinforced 25Mpa/19mm Concrete:</u>                                                                                                  |                                                                                                                                                                                                              |    |     |  |  |   |  |
| 77                                                                                                                                      | Surface beds cast in panels on waterproofing.                                                                                                                                                                | m3 | 15  |  |  |   |  |
| <b>Carried to Collection</b>                                                                                                            |                                                                                                                                                                                                              |    |     |  |  | R |  |
| Section 4                                                                                                                               |                                                                                                                                                                                                              |    |     |  |  |   |  |
| Bill No. 1                                                                                                                              |                                                                                                                                                                                                              |    |     |  |  |   |  |
| External Works                                                                                                                          |                                                                                                                                                                                                              |    |     |  |  |   |  |

TMT-DBE-23/24-SAFEOS-ECCL64-2  
VUYISILE JUNIOR SECONDARY SCHOOL  
THE MVULA TRUST SAFE PROGRAMME - OMMITED SCOPE

|    |                                                                                                                                 |    |     |
|----|---------------------------------------------------------------------------------------------------------------------------------|----|-----|
| 78 | Edge thickening                                                                                                                 | m3 | 26  |
|    | <u>Finishing top surfaces of concrete smooth with a wood float:</u>                                                             |    |     |
| 79 | Surface beds, slabs, etc to falls and currents.                                                                                 | m2 | 145 |
|    | <u>Test blocks:</u>                                                                                                             |    |     |
| 80 | Making and testing of 150x150x150mm concrete strength test cubes (Provisional).                                                 | No | 4   |
|    | <u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>                         |    |     |
| 81 | 12mm Joints not exceeding 300mm high.                                                                                           | m  | 145 |
|    | <u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>                            |    |     |
| 82 | 10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.                       | m  | 145 |
|    | <u>Fabric reinforcement:</u>                                                                                                    |    |     |
| 83 | REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.                                                             | m2 | 145 |
|    | <u>Waterproofing under Surface beds</u>                                                                                         |    |     |
| 84 | 350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured). | m2 | 145 |

**Carried to Collection**

R

Section 4  
Bill No. 1  
External Works

| <b><u>STORMWATER CHANNELS</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|---|--|
| <u>Excavation not exceeding 2m deep</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 85                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Reducing levels and depositing excavated material in prescribed stock piles on site.                                                                                                                                                                                                                  | m3 | 60  |   |  |
| <u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 86                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Off site to a dumping site to be found by the Contractor.                                                                                                                                                                                                                                             | m3 | 60  |   |  |
| <u>Filling supplied by the contractor under channels</u>                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 87                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | G7 Base course material compacted to 98% Mod AASHTO density                                                                                                                                                                                                                                           | m3 | 30  |   |  |
| 88                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.                                                                                                                                              | m3 | 26  |   |  |
| <u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u> |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| 89                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 700 x 80mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.                                                                                   | m  | 243 |   |  |
| 90                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Extra for 700mm angle                                                                                                                                                                                                                                                                                 | No | 12  |   |  |
| 91                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones. | No | 1   |   |  |
| <b>Carried to Collection</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                       |    |     | R |  |
| Section 4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| Bill No. 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                       |    |     |   |  |
| External Works                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                       |    |     |   |  |

|                                                                                                                                                                    |                                                                                                                    |    |     |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|----|-----|
| <b><u>THE FOLLOWING IN SUB-SOIL DRAINAGE, ETC.</u></b>                                                                                                             |                                                                                                                    |    |     |
| <u>Site Clearance, ETC</u>                                                                                                                                         |                                                                                                                    |    |     |
| 92                                                                                                                                                                 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 190 |
| <u>Excavation in earth not exceeding 2m deep:</u>                                                                                                                  |                                                                                                                    |    |     |
| 93                                                                                                                                                                 | Trenches.                                                                                                          | m3 | 678 |
| <b><u>Extra over trench and hole excavations in earth for excavation in:</u></b>                                                                                   |                                                                                                                    |    |     |
| 94                                                                                                                                                                 | Soft rock.                                                                                                         | m3 | 114 |
| 95                                                                                                                                                                 | Hard rock.                                                                                                         | m3 | 76  |
| <u>Extra over all excavations for carting away:</u>                                                                                                                |                                                                                                                    |    |     |
| 96                                                                                                                                                                 | Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.    | m3 | 63  |
| <u>Risk of collapse of excavations:</u>                                                                                                                            |                                                                                                                    |    |     |
| 97                                                                                                                                                                 | Sides of trench and hole excavations not exceeding 1,5m deep.                                                      | m2 | 814 |
| 98                                                                                                                                                                 | Ditto, but from ground level to exceeding 1,5m.                                                                    | m2 | 542 |
| <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>                                      |                                                                                                                    |    |     |
| 99                                                                                                                                                                 | Backfilling to trenches, holes, etc.                                                                               | m3 | 545 |
| <u>Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:</u> |                                                                                                                    |    |     |
| 100                                                                                                                                                                | 19mm Stone.                                                                                                        | m3 | 33  |
| <b>Carried to Collection</b>                                                                                                                                       |                                                                                                                    |    |     |
| Section 4                                                                                                                                                          |                                                                                                                    |    |     |
| Bill No. 1                                                                                                                                                         |                                                                                                                    |    |     |
| External Works                                                                                                                                                     |                                                                                                                    |    |     |

R

TMT-DBE-23/24-SAFEOS-ECCL64-2  
VUYISILE JUNIOR SECONDARY SCHOOL  
THE MVULA TRUST SAFE PROGRAMME - OMMITED SCOPE

|                              |                                                                                                                                                                                                               |    |      |  |  |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|--|--|
|                              | <u>Membrane</u>                                                                                                                                                                                               |    |      |  |  |
| 101                          | ""Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching.                                                                                                      | m2 | 407  |  |  |
|                              | <u>Keeping excavations free of water:</u>                                                                                                                                                                     |    |      |  |  |
| 102                          | Keeping excavations free from mud and all water including subterranean sources.                                                                                                                               |    | Item |  |  |
|                              | <u>Compaction of surfaces</u>                                                                                                                                                                                 |    |      |  |  |
| 103                          | Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density. | m2 | 190  |  |  |
| <b>Carried to Collection</b> |                                                                                                                                                                                                               |    |      |  |  |
| Section 4                    |                                                                                                                                                                                                               |    |      |  |  |
| Bill No. 1                   |                                                                                                                                                                                                               |    |      |  |  |
| External Works               |                                                                                                                                                                                                               |    |      |  |  |

|     |                                                                                                                                                  |    |     |   |  |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|---|--|
|     | <b><u>SOIL DRAINAGE</u></b>                                                                                                                      |    |     |   |  |
|     | <u>160mm Diameter perforated uPVC pipe surrounded with 300 x 300mm section of 20mm stone wrapped in A3 geotextile material.</u>                  |    |     |   |  |
| 104 | 160mm uPVC pipe.                                                                                                                                 | m  | 271 |   |  |
|     | <u>Extra for:</u>                                                                                                                                |    |     |   |  |
| 105 | 160mm Tee.                                                                                                                                       | No | 4   |   |  |
| 106 | 160mm Bend.                                                                                                                                      | No | 2   |   |  |
| 107 | 160mm Y junction.                                                                                                                                | No | 3   |   |  |
|     | <b><u>THE FOLLOWING IN SOAKAWAY</u></b>                                                                                                          |    |     |   |  |
|     | <u>Site Clearance, Etc</u>                                                                                                                       |    |     |   |  |
| 108 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc                               | m2 | 8   |   |  |
|     | <u>Excavation in earth not exceeding 2m deep:</u>                                                                                                |    |     |   |  |
| 109 | Holes                                                                                                                                            | m3 | 18  |   |  |
|     | <b><u>Extra over trench and hole excavations in earth for excavation in:</u></b>                                                                 |    |     |   |  |
| 110 | Soft rock.                                                                                                                                       | m3 | 5   |   |  |
| 111 | Hard rock.                                                                                                                                       | m3 | 4   |   |  |
|     | <u>Extra over all excavations for carting away</u>                                                                                               |    |     |   |  |
| 112 | Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor within 5km from the building site | m3 | 36  |   |  |
|     | <u>Risk of collapse of excavations</u>                                                                                                           |    |     |   |  |
| 113 | Sides of trench and hole excavations exceeding 1,5m deep but not exceeding 3,0m deep                                                             | m2 | 72  |   |  |
|     | <b>Carried to Collection</b>                                                                                                                     |    |     | R |  |
|     | Section 4                                                                                                                                        |    |     |   |  |
|     | Bill No. 1                                                                                                                                       |    |     |   |  |
|     | External Works                                                                                                                                   |    |     |   |  |

Section 4  
Bill No. 1  
External Works

[illegible]

**THE FOLLOWING IN SECURITY FENCING, ETC**Site clearance

|     |                                                                                                                                                                                             |    |     |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|
| 131 | Allow for clearing site for the width of 1 000 mm where fencing is to be erected including removing trees, shrubs etc. not exceeding 200 mm girth, grubbing up roots and roughly levelling. | m2 | 268 |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|

Straining wires, fencing and razor wire:

|     |                                                                                                                                                                                                                                                                                                                                              |   |       |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-------|
| 132 | Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured). | m | 1 072 |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-------|

|     |                                                                            |   |     |
|-----|----------------------------------------------------------------------------|---|-----|
| 133 | 3 Strands of galvanised barbed wire tied to standards, posts and eye bolts | m | 804 |
|-----|----------------------------------------------------------------------------|---|-----|

|     |                                                                                                                                                                                                                                            |   |     |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|
| 134 | Fencing formed of 50 x 50 x 2.0mm diameter galvanised fencing 1 800mm high and fixed to each straining wire with 8 guage binding wire at 500mm centres including Y12 pegs at 900mm c/c between posts (straining wires elsewhere measured). | m | 268 |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|

Posts for 1 800mm high security fence:

|     |                                                                                                                                                                                                                                              |    |     |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|
| 135 | 60mm Diameter galvanised steel intermediate fencing post 2400mm long fitted with a pressed steel mushroom cap one end and 150 x 150 x 5 mm baseplate at bottom and embedded in and including 350 x 350 x 600 mm mass concrete (15 MPa) base. | No | 107 |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|

|     |                                                                                                                                                                                                                          |    |   |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|
| 136 | 100mm Ditto as corner post, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last. | No | 4 |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|

|     |                                                                                                                                                                                                                                     |    |   |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|
| 137 | 150mm Ditto as gate post 2 400mm long, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last. | No | 8 |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|

**Carried to Collection**

R

Section 4  
Bill No. 1  
External Works

|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |    |   |  |
|------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|----|---|--|
| 138                          | 12mm Diameter galvanised mild steel straining eye bolt with hook, threaded portion and two nuts and washers.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | No | 24 |   |  |
| 139                          | Form 12mm diameter hole through fence post.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | No | 24 |   |  |
|                              | <u>Gates:</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |    |    |   |  |
| 140                          | Security fence single gate, size 1 000 mm wide x 1 800 mm high, formed of 50 mm diameter nominal bore x 3,25 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and cross braces mullion and transome, scribed and welded into angles and at cross intersections, with two 50 mm diameter nominal bore x 3,25 mm wall thickness security posts each 600 mm long with one end welded to top rail of gate and closure plate to other end, the gate covered with 100 x 50 x 2,5 mm weld mesh with four straining wires as before described and with four 2,37 mm four point core diameter single "kampeon" wires with crimped droppers to security posts as before described; including three strands flat wrap razor barbed tape wire fixed as before described, leaf fitted with three 24 mm diameter x 300 mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost with and including 500 mm long approved chain spot welded to gate | No | 1  |   |  |
| 141                          | Two leafed vehicular swing gate. Size 5500mm x 1800mm high.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | No | 1  |   |  |
|                              | <u>PADLOCKS</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |    |   |  |
| 142                          | Supply 50 mm "Viro" Padlocks and Keys (or equal approved )                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | No | 2  |   |  |
| <b>Carried to Collection</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |    | R |  |
| Section 4                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |    |   |  |
| Bill No. 1                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |    |   |  |
| External Works               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |    |   |  |

[illegible]

[illegible]

| Item No                                                                                                                                                                                                                                                                                                                                    | Quantity                                                                                                                                                                                        | Rate | Amount     |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|
| <b><u>SECTION No. 5</u></b>                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                 |      |            |
| <b><u>BILL No. 1</u></b>                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                 |      |            |
| <b><u>PROVISIONAL SUMS</u></b>                                                                                                                                                                                                                                                                                                             |                                                                                                                                                                                                 |      |            |
| <b><u>SUPPLEMENTARY PREAMBLES</u></b>                                                                                                                                                                                                                                                                                                      |                                                                                                                                                                                                 |      |            |
| Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.                                                                              |                                                                                                                                                                                                 |      |            |
| Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto. |                                                                                                                                                                                                 |      |            |
| <b><u>BUDGETARY ALLOWANCES</u></b>                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                 |      |            |
| <b><u>The following budgetary allowances are for work to be executed at rates in the bills of quantities or to be agreed by the Principal agent:</u></b>                                                                                                                                                                                   |                                                                                                                                                                                                 |      |            |
| 1                                                                                                                                                                                                                                                                                                                                          | Provide the sum of R22 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R7 500.00 a month for the duration (3 months) | Item | 22 500.00  |
| 2                                                                                                                                                                                                                                                                                                                                          | Add: Mark-up                                                                                                                                                                                    | %    |            |
| 3                                                                                                                                                                                                                                                                                                                                          | Provide the sum of R105 000. 00 for the hire, maintenance and servicing of temporary toilets for educators and learners during the entire constructions period                                  | Item | 105 000.00 |
| 4                                                                                                                                                                                                                                                                                                                                          | Add: Mark-up                                                                                                                                                                                    | %    |            |
| <b>Carried to Final Summary</b>                                                                                                                                                                                                                                                                                                            |                                                                                                                                                                                                 |      | R          |
| Section 5<br>Bill No. 1<br>Provisional Sums                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                 |      |            |

| Section No                                                                                                                                 | Page No | Amount |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------|--------|
| <b><u>FINAL SUMMARY</u></b>                                                                                                                |         |        |
| 1                                                                                                                                          | 165     |        |
| 2                                                                                                                                          | 169     |        |
| 3                                                                                                                                          | 174     |        |
| 4                                                                                                                                          | 197     |        |
| 5                                                                                                                                          | 198     |        |
| SUB-TOTAL                                                                                                                                  |         | R      |
| <b><u>CONTINGENCIES</u></b>                                                                                                                |         |        |
| Allow five per cent (5%) of the above sub-total for contingencies to be used as directed and deducted in whole or in part if not required. |         |        |
| SUB-TOTAL                                                                                                                                  |         | R      |
| Add Value Added Tax at the rate of 15%                                                                                                     |         | R      |
| Carried to Form of Offer and Acceptance                                                                                                    |         | R      |