

TELA DUNDEE ACCESS ROAD MAINTENANCE
CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS
SECTION 1300

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
13	SECTION 1300				
	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS				
13,01	Contractor's general obligations				
	(a) Fixed time obligations	L/sum	1		
	(b) Value-related obligations	L/sum	1		
	(c) Time-related obligations	Month	8		
	(d) Community Liason Officer for six(8) months	Prov. Sum	1	40 000,00	40 000,00
	(e) Rembursment for Project Steering committee	Prov. Sum	1	18 500,00	18 500,00
	(f)Handling costs and charges for Contractor on items 13 01 d				
	(g) rehabilitation of borrow pit and quarry	sum	1		
13,02	Health and Safety Compliance	Sum	1		
	- Preparation of Contractor's site specific Health and Safety Plan				
	- Principal Contractor's initial obligations in respect of the OHS and Construction Regulations				
	- Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations				
	- Provision for Personal Protective Equipment & Protective				
	Refective vests				
	Work Suits				
	Hard hats				
	Protective foot wear				
	Earplugs and Goggles				
	Dust masks				
	- Provision of full time Construction Health and Safety Officer				
	- Induction Training				
	- Provision of First Aid Boxes				
	- Submission of the Health and Safety File				
TOTAL CARRIED FORWARD TO SUMMARY					

**TELA DUNDEE ACCESS ROAD MAINTENANCE
CLEARING AND GRUBBING
SECTION 1700**

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
17	SECTION 1700 CLEARING AND GRUBBING				
17,01	Clearing and grubbing	ha	1,02		-
17,05	Cleaning out of hydraulic structures (a) Pipes with internal diameter up to and including 750 mm	m ³			-
TOTAL CARRIED FORWARD TO SUMMARY					-

TELA DUNDEE ACCESS ROAD MAINTENANCE
DRAINS
SECTION 2100

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
2100	SECTION 2100 DRAINS				
21,14	Repairing or replacing of existing drainage systems	Prov Sum	1	30 000	
21,18	Class 25MPA/19mm concrete 150mm thick with ref.245 mesh for concrete ditch drain to engineer's drawing specification (1:30) inclusive of formwork, wood float finish, corner rounder and joints.		8		
TOTAL CARRIED FORWARD TO SUMMARY					-

TELA DUNDEE ACCESS ROAD MAINTENANCE
BORROW MATERIALS
SECTION 3100

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
31	SECTION 3100 BORROW MATERIALS				
31,03	Finishing-off borrow areas in: (b) Intermediate material	ha	1,10		-
TOTAL CARRIED FORWARD TO SUMMARY					-

TELA DUNDEE ACCESS ROAD MAINTENANCE
MASS EARTHWORKS
SECTION 3300

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
33	SECTION 3300 MASS EARTHWORKS				
33,12	Insitu treatment of roadbed: a) Insitu treatment by ripping & recompacting	km	1,7		
TOTAL CARRIED FORWARD TO SUMMARY					

**TELA DUNDEE ACCESS ROAD MAINTENANCE
PAVEMENT LAYERS OF GRAVEL MATERIALS
SECTION 3400**

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
34	SECTION 3400				
34,01	PAVEMENT LAYERS OF GRAVEL MATERIAL cut or borrow, including free haul up to 1,0 km b) 150mm G7 gravel wearing course compacted to 95% Mod. AASHTO	m ³	1275		
TOTAL CARRIED FORWARD TO SUMMARY					-

TELA DUNDEE ACCESS ROAD MAINTENANCE
FINISHING THE ROAD AND ROAD RESERVE AND TREATING OLD ROADS
SECTION 5900

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	SECTION 5900				
59	FINISHING THE ROAD AND ROAD RESERVE AND TREATING OLD ROADS				
59,01	Finishing the road and road reserve				
	(b) Single carriageway road	Km	1,7		
TOTAL CARRIED FORWARD TO SUMMARY					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6300	STEEL REINFORCING FOR STRUCTURES				
63,01	Steel reinforcement for:				
	(a) Concrete-lined causeways				
	(3) Welded steel fabric (mesh 395)	Kg	2 963		
CARRIED FORWARD TO SUMMARY :					R -

TELA DUNDEE ACCESS ROAD MAINTENANCE

ITEM NO	DESCRIPTION
6400	CONCRETE FOR STRUCTURES
64,01	Cast in situ concrete
LIC	(a) Class 25 /19

CARRIED FORWARD TO SUMMARY :

R -

UNIT	QUANTITY	RATE	AMOUNT
m ³	180,00		

			R	-

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	SECTION 8100				
81	TESTING MATERIALS AND WORKMANSHIP				
81,03	Other special tests requested by the Engineer	Prov. Sum	1		
TOTAL CARRIED FORWARD TO SUMMARY					-

CONTRACTOR :		
CLIENT:UMZIMVUBU LOCAL MUNICIPALITY		
TELA-DUNDEE ACCESS ROAD MAINTENANCE		
SECTION	DESCRIPTION	TENDER AMOUNT (R)
1300	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS	
1700	CLEARING AND GRUBBING	
2100	DRAINS	
3100	BORROW MATERIALS	
3300	MASS EARTHWORKS	
3400	PAVEMENT LAYERS OF GRAVEL MATERIALS	
5900	FINISHING THE ROAD AND ROAD RESERVE	
6300	STEEL	
6400	CONCRETE	
8100	TESTING MATERIALS AND WORKMANSHIP	
	SUB - TOTAL A	
	Plus 0% Contingencies	
	SUB - TOTAL B	
	Add VAT @ 15%	
	TOTAL TENDER SUM	