

Good hope concourse

Item	Description	UNIT	QTY	RATE	AMOUNT
	BILL NO. 1 PRELIMINARIES AND GENERAL COSTS GENERAL NOTES Contractor is required to visit the site and inspect items before bidding for the tender. Note :All rates should include supply and install SUPPLEMENTARY PREAMBLES View site : Before submitting, the Contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings. Old material to become property of the contractor Old materials from alterations, except where described to be re-used or handed over, become the property of the contractor who must allow credit for same in the Final Summary				
	BILL NO.1 CLEAR SITE SITE CLEARANCE Clear the site and remove all debris,rubble and deep the area including curt away from the site to a dumping site allocated by the contractor BUILDING UP OPENINGS <i>Brickwork in NFP bricks in class 2 mortar in building up openings, including bonding new to existing and make good cement plaster on outside</i> Opening 1500 x 1600 mm high overall 220mm brick work	M³	50.00		
		NO	37		

Opening 1600 x 1600 mm high overall 220mm brick work	NO	29		
Opening between the concrete columns including "HOOP IRONS" every second course 80 m x 3.0 high overall 220mm brick work	NO	1		
EXTRA OVER				
Extra over for galvanised brick force every fourth course	Item	1		
FENCE				
Manufacture, Supply and Install Galvanised and powder coated Clear view fence and poles or Similar				
1,2 m high fixed in the concrete with 10mm thick base plate	M	10		
SLIDING GATE				
Manufacture, supply and fit a sliding gate(s) made of, Locking Portal, Guide wheel Portal with 75x 75 x 3mm. The bottom rail 100 x 100 x 3mm. Vertical gate frame, Horizontal gate frame 60 x 60 x 3mm. Wheels to be 150mm diameter and 4 wheels per gate. Mesh infill Clear view. Guide wheel assembly and a stop and lock assembly with a disc lock with 4 keys. The gate frame to be galvanized in-and outside (minimum 275g/M²) Afterwards an adhesion coating (primer) is applied and finally the gates are PVC coated (min120micron) and the colour to be charcoal.				
Size 10.0 X 2.1m high	No	2		
EXTERNAL WORK				
Pick up remove and set aside for later re use, including relaying existing slabs on 50 mm sandbed.				
450 X 450 X 50 mm	M²	400		
			SUB-TOTAL	
			VAT(15%)	
			TOTAL	

