

ANNEXURE C3.2: SCOPE OF WORK

A) DO THE FOLLOWING WORK AT RAND WATER ZWARTKOPJES CRICKET FIELD AND A-REC CLUB.

- 1.Remove existing 8m x 8m Grass Thatch.
- 2.Supply and Install 2 x A-Frame carports (76 degrees) 8.4m x 7.45m -coloured brown chromo deck sheets.
- 3.Remove all rubble of site
- 4.Safety file.

PREMANUFACTURED PRODUCTS:

1. Poles 3.0m x 76mm x 12
2. A-Frame side beam 7.35m x 150mm x 50mm x 4
3. A-Frame main truss 8.4 x 1.6m x 150mm x 50mm x 20mm x 4.
4. A-Frame sub truss 8.4m x 100mm x 50 x 20 x 2.
5. Purlin 7.5m x100mm x50mm x12
6. Gutters 7.5m x 75mm round x 4
7. Gutter down pipes 2.7m x 75mm x 4
8. Gutter off sets 900mm x 75mm x 4