

SECTION 4: PRICING AND DELIVERY SCHEDULE

NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT R
A.	PRELIMINARY AND GENERAL				
A.1	Site Establishment and De-establishment	sum	1	R	R
A.2	Safety, PPE, Work Permit, Licences, Safety File, Transport, Supervision, Quality, Training, Storage etc	sum	1	R	R
SUB-TOTAL:					R
B.	Earthwork				
B.1	Rip and Compact base layer (compacted to 95% MOD AASTHO)	m ²	6500	R	R
B.2	Supply first layers of C4 material in layers of 100mm compacted to 95% MOD AASTHO	m ²	6500	R	R
B.3	Supply second layers of C4 material in layers of 100mm compacted to 95% MOD AASTHO	m ²	6500	R	R
B.4	Supply of the 80mm paver blocks	m ²	6500	R	R
B.5	Labour cost for the installation of the paving blocks	Sum	1	R	R
B.6	Supply and install Barrier Kerb 1000 X 300 X 150	m	1800	R	R
SUB-TOTAL:					R
TOTAL:					R

Respondent's Signature

Date and Company Stamp

4