

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO: 0				
	C2 .2 PRELIMINARIES AND GENERAL				
	<u>Allow for Preliminaries and General</u>				
1	Time (T) related Preliminaries will only be adjusted for omissions or additions, issued by the Employer.	SUM	1		
Carried to Final Summary					R -

<u>BILL NO. 1</u> <u>CARPENTRY AND JOINERY</u> <u>(CPAP WORK GROUP NO. 126 UNLESS OTHERWISE STATED)</u> <u>PREAMBLES</u> The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "Standard Preambles To All Trades (Rev. 3) DOH 2009", "Supplementary Preambles" and "Supplementary Specifications" to this contract for the full requirements of each scheduled item <u>TIMBER DOORS</u> <u>Single leaf solid core timber door for painting with 2mm thick aluminum plate clading and 250 x 500mm safety glazing viewing panel.</u> <u>Internal doors</u>					
1	Overall size 813 x 2032mm high	No	6		
<u>Double leaf solid core timber door for painting with 2mm thick aluminum plate clading and 250 x 500mm safety glazing viewing panel.</u>					
2	Overall size 1600 x 2032 mm high	No	1		
Carried to Final Summary					R -

<u>BILL NO. 2</u> <u>CEILINGS, PARTITIONS & ACCESS FLOORING</u> <u>(CPAP WORK GROUP NO. 129 UNLESS OTHERWISE STATED)</u> <u>PREAMBLES</u> The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "Standard Preambles To All Trades (Rev. 3) DOH 2009", "Supplementary Preambles" and "Supplementary Specifications" to this contract for the full requirements of each scheduled item <u>SUPPLEMENTARY PREAMBLES</u> Openings in ceilings for light fittings, etc. are to include for additional suspension as required <u>Fixings</u> Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pinned to blockwork or concrete. Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given elsewhere <u>Ceilings</u> Unless otherwise described ceilings shall be deemed to be horizontal <u>NAILED UP CEILINGS</u> <u>9.7mm Gypsum plasterboard with H-type pressed steel jointing strips</u>				
1	"1195 x 595mm Suspended Ceiling board , including 38 x 38mm sawn softwood branderling"	m2	153.5	
<u>Cornices, etc. to ceilings. Gypsum plasterboard cornices</u>				
2	75mm coved cornices	m	52	
Carried to Final Summary				R -

<u>BILL NO. 3</u> <u>ROOF COVERINGS, ETC.</u> <u>(CPAP WORK GROUP NO. 124 UNLESS OTHERWISE STATED)</u> <u>PREAMBLES</u> The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "Standard Preambles To All Trades (Rev. 3) DOH 2009", "Supplementary Preambles" and "Supplementary Specifications" to this contract for the full requirements of each scheduled item <u>PROFILE METAL SHEETING</u> <u>0.5mm Kliplock metal roof sheeting or equal approved by PRS, colour to architects specification over alucusion on galvanised purlins and trusses to structural engineers details.</u> <u>Supply, deliver and fix timber barge boards to gable ends of roof structures, including all necessary labour, materials, cutting, mitring, jointing, drilling, fixing to trusses/purlins, and securing with galvanised nails/screws and proprietary fasteners.</u>				
1	Fascia and Badge boards	m2	12	
Carried to Final Summary				R -

<u>BILL NO. 4</u> <u>IRONMONGERY</u> <u>(CPAP WORK GROUP NO. 132 UNLESS OTHERWISE STATED)</u> <u>SUPPLEMENTARY PREAMBLES</u> <u>Proprietary items</u> Where applicable the manufacturers' names or product catalogue titles are given in sub-headings preceding the items. Prices are to be based on the specific products/articles specified. If tenderers wish to offer alternative products/articles for certain items, these items are to be clearly marked and the alternative specification given with supporting brochures, etc. clarifying the features of the products/articles offered. On request returnable samples are to be provided to the principal agent for consideration. The following locks are to be suitable for master key operation. <u>Finishes to ironmongery</u> Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered: CH Chromium plated: SC Satin chromium plated: SE Silver enamelled: GE Grey enamelled: AS Anodised silver: AB Anodised bronze: AG Anodised gold: ABL Anodised black: PB Polished brass: PL Polished and lacquered: PT Epoxy coated <u>HINGES, BOLTS, ETC.</u> <u>LOCKSETS, ETC.</u> <u>Manufactured by "Union" or other equally approved</u>							
1	L-2241-78 oval cylinder mortice lock	No	6				
2	2 x 20sc MKD euro profile single cylinder master keyed	No	6				
3	8352-100ss stainless steel 100 x 75mm ball bearing	No	12				
4	CZ8731SC rubber buffered door stop	No	6				
Carried to Final Summary						R	-

<u>BILL NO. 5</u> <u>METALWORK</u> <u>(CPAP WORK GROUP NO. 136 UNLESS OTHERWISE STATED)</u> <u>PREAMBLES</u> The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "Standard Preambles To All Trades (Rev. 3) DOH 2009", "Supplementary Preambles" and "Supplementary Specifications" to this contract for the full requirements of each scheduled item <u>SUPPLEMENTARY PREAMBLES</u> <u>Descriptions of bolts, anchors, etc.</u> Descriptions of bolts shall be deemed to include nuts and washers. Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete. Items described as "holed for bolt(s)" shall be deemed to exclude the bolts unless otherwise described. Items described as "plugged" shall be deemed to include screwing to fibre STEEL WINDOWS ,DOORS, ETC <u>GALVANISED PRESSED STEEL DOOR</u> <u>Supply and install external double-rebated galvanised mild steel pressed door, frame to suit double-wall thickness, complete with fixing lugs, tie bars and two pairs of 100 mm steel butt hinges supplied by the manufacturer.</u>					
1	Size approximately 1232 x 2032mm high (As per PRASA blueprint Level G2 bullet resistant anti-badit)	No	1		
<u>ROLLER SHUTTER DOOR</u> <u>Supply, deliver and install mild galvanised heavy-duty steel roller shutter door, and all necessary ironmongery, including manual chain operation, Door to be fixed to structural openings, including all brackets, bolts, and accessories</u>					
2	Roller Shutter door 2000mm x 2600mm high	No	2		
<u>Standard industrial bullet resistance glass transaction windows with mesh buralar screens</u>					
3	W01 size (1000mm x 1500mm)	No	5		
4	W02 (1000mm x 800mm)	No	2		
5	W03 (1000mm x 1200mm)	No	1		
Carried to Final Summary					R -

<u>BILL NO. 6</u>					
<u>PAINTWORK</u>					
<u>(CPAP WORK GROUP NO. 152 UNLESS OTHERWISE STATED)</u>					
<u>PREAMBLES</u>					
The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "Standard Preambles To All Trades (Rev. 3) DOH 2009", "Supplementary Preambles" and "Supplementary Specifications" to this contract for the full requirements of each scheduled item					
<u>PAINT TO TIMBER DOORS</u>					
<u>Prepare and apply one coat Midas Masonry Primer and two coats Midas Midalux 240 paint ,Single leaf solid core timber door .</u>					
<u>Internal doors</u>					
1	Overall size 1000mm x 2600mm high	No		6	
<u>External doors</u>					
<u>Double leaf solid core timber door for painting with 2mm thick aluminum plate cladding and 250 x 500mm safety glazing viewing panel.</u>					
2	Overall size 1000m x 2600mm high	No		1	
<u>ON METAL SURFACES</u>					
<u>Spot priming defects in pre-primed surfaces with zinc phosphate " metal primer ,one coat universal undercoat and two coats ' super universal enamel paint on steel</u>					
3	On steel door frames	No		2	
<u>ON GYPSUM PLASTER BOARD SURFACES</u>					
<u>Prepared and apply one coat Midas Masonry Primer and two coats Midas Midalux 240 paint , as supplied to approved colour for external use</u>					
	On Badge and Fascia Board	m		24	
<u>ROAD MARKINGS</u>					
<u>Non-reflectorized paint applied at nominal rate of 0.42 l/m2 or proprietary brand road marking material applied at normal rate of 0.50 l/m2</u>					
<u>Yellow and white Lines (broken or unbroken)</u>					
4	100mm wide Yellow line	m		360	
5	White Line	m		360	
<u>PAINTING TO BENCHES</u>					
<u>Prepare existing benches by removing rust, dirt, grease, loose paint and all deleterious matter, and apply one coat approved metal primer and two coats enamel paint to all exposed surfaces, complete</u>					
6	Size 7000mm x 500mm	No		4	

7	<u>PAINT TO PLASTERED WALL (SHELTER)</u>	m2	52.64		
	Prepare and paint plastered wall surfaces to shelter, including cleaning down, removal of dust, dirt and loose material, making good minor surface defects, application of primer, undercoat and two coats of approved paint to match the station				
Carried to Final Summary					R -

<u>BILL NO.7</u>				
<u>EXTERNAL WORK</u>				
<u>TREATMENT OF AN EXISTING SURFACE EXHIBITING CERTAIN DEFECTS</u>				
1	Treatment with diluted bituminous (Fogspray), 30% bitumen emulsion (0,4l/m2) and cold Asphalt for patching	m2	30.5	
<u>FENCE REPAIR AND PATCH WORKS</u>				
2	supply and install Clea view mesh wire fence to match existing fence around station	m	20	
Carried to Final Summary				R -

<u>BILL NO. 8</u> <u>PLUMBING AND DRAINAGE</u> <u>(CPAP WORK GROUP NO. 148 UNLESS OTHERWISE STATED)</u> <u>PREAMBLES</u> The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "Standard Preambles To All Trades (Rev. 3) DOH 2009", "Supplementary Preambles" and "Supplementary Specifications" to this contract for the full requirements of each scheduled item <u>PROVISIONAL SUM FOR PLUMBING AND DRAINAGE WORK</u> Allow the sum of R100 000.00 (One Hundred Thousand Rand) for PLUMBING AND DRAINAGE SANITARY FITTINGS. Provision to install sanitary ware, including plumbing, and connection to an existing septic tank.				
1	Item	1	100000	100,000.00
Carried to Final Summary				

<u>BILL NO. 9</u>				
<u>PROVISIONAL SUM FOR ELECTRICAL WORK</u>				
1	Allow the Sum of R 231 818.18(Two Hundred and Thirty-One Thousand Eight Hundred and Eighteen Rand and Eighteen Cents) for Electrical installation, alterations, and associated work to be executed in accordance with the employer's requirements	Sum	1	231,818.18
	Allo Profit and Attendance		10%	23,181.82
Carried to Final Summary				

<u>FINAL SUMMARY</u>				
0	Preliminaries and Generals	Page	0	
1	Carpentry and Joinery	Page	1	
2	Ceilings, Partitions & Access Flooring	Page	2	
2	Roof Covering	Page	3	
3	Ironmongery	Page	4	
4	Metalwork	Page	5	
5	Paintwork	Page	6	
6	External Works	Page	7	
7	Plumbing and Drainage	Page	8	
8	Electical Work	Page	9	
Sub Total (A)		ST		R
Allow a sum of R2500 for a JBCC minor agreement hard copy document		Item	1	2,500.00
Contigencies		SUM	1	100,000.00
Provide for an amount of R 30 000 for Community Liaison Officer (CLO)		Item	1	30,000.00
Allow for Profit and Attandance under CLO budgetary		10%	1	3,000.00
Sub-Total (B)		ST		R -
Sub Total (A+B) Brought Forward				#VALUE!
Value Added Tax (15%)		TAX	15%	R
Total Carried to Form of Tender				R