

Item No.	Description	Unit	Qty	Rate/unit (Excl. VAT)	Total Price (Excl. VAT)
<u>Preliminary and General</u>					
1.	Removal of all the decommissioned equipment and transportation to Rebecca stores.	sum	1		
2.	Preliminary and General (eg Toilets, security, testing and commissioning, etc)	Sum	1		
<u>Work execution</u>					
3.	Supply and Installation of phase wires (x3 plus the earth wire) and all the associated works. (That is total 4 wires)	m	2700		
4.	Supply and Installation of earth wire brackets and all the associated works.	Each	70		
5.	Supply and Install 70mm ² ABC bundled conductor across 3 locations between Mamelodi Gardens and Green View station and all the associated works.	M	500		
6.	Supply and install termination kits (x 2 per bridge), supporting brackets and all the associated works, during installation of the ABC conductor.	Each	4		
7.	Supply and install 11KV Metal-Oxide surge arrestors on every H frame and bundled conductor connection.	Each	33		
8.	Supply and Install pin type Anti vandal insulators for 11kv transmission line (every location where they are missing).	EACH	65		
9.	Supply and Install link-switches complete with operating rode and handle and all the associated works.	Each	9		
10.	Supply and install bonding in all the H-frames along the line. This includes (per H-frame) 2 x spark gaps, 2 x PVC cables, and 2 x earth spikes	Each	4		
11	Stenciling with Black and white number painting for Mast numbering between Koedoespoort and Pienaarsport station, including all the associate works. ## The service provider to provide the paints.	Each	750		
Sub Total Excl. Vat					
VAT (15%)					
Total					