

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	TENDER AMOUNT
1200	GENERAL REQUIREMENTS AND PROVISIONS				
12.01	Community Liaison:				
	(a) Community Liaison Officer cost	Prov. Sum	1,00	27000,00	27000,00
12.02	Remedial Work				
	(a) Rehabilitation of borrow pits and quarry	Lump Sum	1		
	(b) Removal of site establishment	Lump Sum	1,00		
CARRIED FORWARD TO SUMMARY :					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1300	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS				
13,01	The contractor's general obligations:				
	(a) <u>Fixed obligations</u>	Lump sum	1		
	(b) <u>Value-related obligations</u>	Lump sum	1		
	(c) <u>Time-related obligations</u>	Month	6		
13,02	Occupational Health & Safety:	lump sum	1		
	(a) - Preparation of Contractor's site specific Health and Safety Plan				
	(b) - Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations				
	(c) - Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations				
	(d) - Provision for Personal Protective Equipment & Protective Clothing including the following items				
	(i) Reflective vests				
	(ii) Work Suits				
	(iii) Hard hats				
	(iv) Protective foot wear				
	(v) Earplugs and Goggles				
	(vi) Dust masks				
	(e) - Induction Training				
	(f) - Provision of First Aid Boxes				
	(g) - Submission of the Health and Safety File				
	(h) Contractors Obligations for OHS COVID 19 & Construction Regulations				

CARRIED FORWARD TO SUMMARY :

-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1500	ACCOMODATION OF TRAFFIC				
15,01	Accomodation of traffic	km	5,00		
CARRIED FORWARD TO SUMMARY :					0

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1600	OVEHAUL Overhaul on material hauled in excess of 1.0km (ordinary overhaul)	m³-km	21458,12		
CARRIED FORWARD TO SUMMARY :					0

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1700	CLEARING AND GRUBBING				
17,01	Clear and grubbing	ha	2,50		
17,02	Removal and grubbing of large trees and tree stumps:				
	(a) Girth exceeding 1m up to and including 2m	No			
17,04	Clearing and grubbing at inlets and outlets of hydraulic structures	m²			
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3100	BORROW MATERIALS				
31,01	Excess overburden (provisional)	m³	85,00		
31,03	Finishing-off borrow areas				
	(a) Hard material	ha	0,80		
	(b) Intermediate material	ha	0,60		
	(c) Soft material	ha	0,90		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3300	MASS EARTHWORKS				
33,01	Cut and borrow to fill, including freehaul up to 0.5km :				
	(a) Material in compacted layer thickness of 150mm and less:				
	(ii) Compacted to 93% of mod AASHTO	m³	750		
33	Cut to spoil, including free-haul up to 0.5km				
	Material obtained from:				
	(a) Soft excavation	m³	120		
	(b) Intermediate excavation	m³	24		
	(c) Hard excavation	m³	24		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3400	PAVEMENT LAYERS OF GRAVEL MATERIAL				
34,01	Pavement layers constructed from gravel taken from cut or borrow including free haul up to 1,0km				
	(h) Gravel wearing course compacted to				
	(ii) 95% Mod AASHTO density: 150mm layer thickness	m³	3750,00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5100	PITCHING, STONework AND PROTECTION AGAINST EROSION				
51,01	Stone pitching				
LIC	(b) Grouted stone pitching	m²	65,00		
51,03	Stone masonry walls:				
	(b) Cement-mortared stone walls	m²	Rate only		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5900	FINISHING THE ROAD AND ROAD RESERVE AND TREATING OLD ROADS				
59,01	Finishing road and road reserve				
	b) Single carriageway road	km	5,00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6200	FALSEWORK, FORMWORK AND CONCRETE FINISH				
62,01	Formwork to provide class F2 surface finish to concrete	m²			
62,02	Vertical formwork to provide class F2 surface finish to concrete	m²	175,00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6300	STEEL REINFORCING FOR STRUCTURES				
63,01	Steel reinforcement for:				
	(a) Concrete				
	(3) Welded steel fabric mesh (ref 395)	kg	135		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6400	CONCRETE FOR STRUCTURES				
64,01	Cast in situ concrete				
LIC	(a) Class 25 /19	m³	65,00		
CARRIED FORWARD TO SUMMARY :					-

SUMMARY OF SCHEDULE OF QUANTITIES

SECTION	DESCRIPTION	AMOUNT
1200	General Requirements and Provisions	
1300	Contractors Establishment and General Obligations	
1500	Accommodation of Traffic	
1600	Overhaul	
1700	Clearing and Grabbing	
2100	Drains	
3100	Borrow Materials	
3300	Mass Earthworks	
3400	Pavement Layers of Gravel Material	
5100	Pitching, Stonework and Protection Against Erosion	
5900	Finishing the Road Reserve and Treating of Old Roads	
6200	Falsework, Formwork and Concrete Finish	
6300	Steel reinforcing of Structures	
6400	Concrete for Structures	
Subtotal A		
Subtotal B		
Add 15% VAT		
Total Tender Amount		

Signed :

Date:

Name of Tenderer :