

QUESTIONS ASKED AND ANSWERS

TENDER NUMBER: ERACMM-KDS-45103

DESCRIPTION: TO RE-INSTATE TURFGROND 25KV AC TRACTION SUBSTATION UNDER THE CONTROL OF THE DEPOT ENGINEER, KOEDOESPOORT

1. Item 6, What is the diameter of the steel pipes? **50mm²**
2. Item 14, What is the quantity/area in m2 of the stones and stones to be rehabilitated?
Area is 100 square metre
how deep do we need to remove the soil? **500mm**
Does the oil contain PCB? **No**
3. The addendum states that the specification for batteries was issued, but it's not attached
Set of 110V 29AH KPZ10 batteries
4. The dimensions for item 16 & 28 are not attached as well, unless you're referring to the Operator Manual, which does not really assist in quoting for these items
Item 16 Top cubicle 1m x 500mm, Bottom cubicle is 500mmx500mm
Telecontrol room door 2.1m x 800mm
5. Item 29, please assist with the number of lighting and the type of lights (how many watt) required in the telecontrol room and PCB room
Telecontrol 1 x 1.5m fluorescent light, 100W
PCB Room 2 x 1.5m fluorescent light, 100W
6. Annexure C, We are required to insert the price for the VCB control cables, however they are not on the BOQ/price list, only the multichoice control cables, Please clarify ? **The Multicore control cables include the VCB control cables.**
7. The contractor shall re wire control panels containing all the protection relays, control circuitry and associated equipment required for operation of the substation, in accordance with clauses 26.0 and 28.3 of specification CEE.0111.99. **Refer to the attached specification.**