

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F","V","T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

SECTION A: PRINCIPAL BUILDING AGREEMENT

DEFINITIONS

Definitions and interpretation (Clause 1).

1 F: V: T:

Item

OBJECTIVE AND PREPARATION

Offer, acceptance and performance (Clause 2).

2 F: V: T:

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: V: T:

Item

Design responsibility (Clause 4).

4 F: V: T:

Item

Employer's agents (Clause 5).

5 F: V: T:

Item

Site representative (Clause 6).

6 F: V: T:

Item

Compliance with regulations (Clause 7).

7 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Works risk (Clause 8)			
8	F: V: T: Indemnities (Clause 9). Clause 9.1.1 is deleted and substituted with: Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.	Item		
9	F: V: T: Works insurances (Clause 10).	Item		
10	F: V: T: Liability insurances (Clause 11).	Item		
11	F: V: T: Effecting insurances (Clause 12).	Item		
12	F: V: T: State Provisions (Clause 13).	Item		
13	F: V: T: Security (Clause 14).	Item		
14	F: V: T: <u>EXECUTION</u> Preparation for and execution of the works (Clause 15).	Item		
15	F: V: T: Access to the works (Clause 16).	Item		
16	F: V: T: Contract instructions (Clause 17).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

17	F: V: T: Setting out of the works (Clause 18.3). The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item		
18	F: V: T: Assignment (Clause 19).	Item		
19	F: V: T: Nominated subcontractors (Clause 20).	Item		
20	F: V: T: Selected subcontractors (Clause 21).	Item		
21	F: V: T: Employer's Direct contractors (Clause 22).	Item		
22	F: V: T: Contractor's Domestic subcontractors (Clause 23).	Item		
23	F: V: T: <u>COMPLETION</u> Practical completion (Clause 24).	Item		
24	F: V: T: Works completion (Clause 25).	Item		
25	F: V: T: Final completion (Clause 26).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

Latent defects liability period (Clause 27).

Clause 27.0 is amended by the addition of the following clauses:

"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".

"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"

26 F: V: T:

Item

Sectional completion (Clause 28).

27 F: V: T:

Item

Revision of date for practical completion (Clause 29).

28 F: V: T:

Item

Penalty for non-completion (Clause 30).

29 F: V: T:

Item

PAYMENT

Interim payment to the contractor (Clause 31).

The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30 F: V: T:

Item

Recovery of expense and loss (Clause 33).

31 F: V: T:

Item

Final account and final payment (Clause 34).

32 F: V: T:

Item

Payment to other parties (Clause 35).

33 F: V: T:

Item

CANCELLATION

Cancellation by Employer - Contractor's default (Clause 36).

34 F: V: T:

Item

Cancellation by Employer - Loss and damage (Clause 37).

35 F: V: T:

Item

Cancellation by Contractor - Employer's default (Clause 38).

36 F: V: T:

Item

Cancellation - Cessation of the works (Clause 39).

37 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

DISPUTE

Dispute Settlement (Clause 40)

38 F: V: T:

Item

SUBSTITUTE PROVISIONS

State Clauses (Clause 41)

39 F: V: T:

Item

CONTRACT VARIABLES

The Schedule: Pre-Tender information (Clause 42).

40 F: V: T:

Item

CONTRACTING AND OTHER PARTIES (Clause 42.1)

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

<u>CONTRACT DETAILS (Clause 42.2)</u> Clause 42.2.1 Works Description: Construction of new ablution facilities. Clause 42.2.2 Site Description: The site is the existing school. Clause 42.2.3 Work or Installations by Others: NIL Clause 42.2.4 This Agreement is for a State Contract :- Yes Payment will be made for materials and goods:- Yes Dispute resolution :- Mediation (in terms of clause 40) followed by litigation. Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A Clause 42.2.5 Date on which possession of the site is intended to be given on :- To be advised. Clause 42.2.6 Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days. Completion in Sections are required : NO Clause 42.2.7 Intended date of practical completion and the penalty per calendar day for the works as a whole :- To be advised. Carried to Collection Section 1 Bill No. 1 Preliminaries			
---	--	--	--

Penalty amount will be R 2000 per calendar day to a maximum of 10 % of Contract Value.

Clause 42.2.8

Intended dates of practical completion and the penalties per calendar day for the works in sections :

N/A

Clause 42.2.9

The law applicable to this agreement shall be that of - Republic of South Africa.

INSURANCES (Clause 42.3)

Clause 42.3.1

Contract works insurance to be effected by Contractor for the sum of: Contract Sum

With a deductible of : Not exceeding 5% of each and every claim.

Clause 42.3.2

Supplementary insurance is required : Yes

SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).

Clause 42.3.3

Public liability insurance to be effected by Contractor

For the amount of: R 5million

With a deductible of: Not exceeding 5% of each and every claim.

DOCUMENTS (Clause 42.4)

Clause 42.4.1

Waiver of the contractor's lien is required :- YES

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

	Clause 42.4.2 Number of construction document copies to be supplied to the Contractor free of charge :- 1 Clause 42.4.3 Bills of Quantities drawn up in accordance with :- Standard System of Measuring Building Work - Seventh Edition including all amendments Clause 42.4.4 Number of days for submission of priced documents : 5 working days from the Letter of Appointment. Clause 42.4.5 JBCC Engineering General Conditions are to be included in the documents :- No Clause 42.4.6 The contract value is to be adjusted using CPAP:- NO <u>SECTION B: PRELIMINARIES</u> <u>DEFINITIONS AND INTERPRETATION (B1)</u> Definitions and Interpretation (B1) 41 F: V: T: <u>DOCUMENTS (B2)</u> Checking of documents (B2.1) Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc. 42 F: V: T: Provisional Bills of Quantities (B2.2) YES Carried to Collection Section 1 Bill No. 1 Preliminaries			

	Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.		
43	F: V: T: Availability of construction documentation (B2.3)	Item	
44	F: V: T: Interests of Agents (B2.4)	Item	
45	F: V: T: Priced documents (B2.5)	Item	
46	F: V: T: Tender submission (B2.6) Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.	Item	
47	F: V: T: <u>THE SITE (B3)</u> Defined works area (B3.1) The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site. Workmen employed on the site are to be restricted to the immediate area of the site and access thereto. The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.	Item	
48	F: V: T:	Item	
	Carried to Collection		R
	Section 1		
	Bill No. 1		
	Preliminaries		

	Geotechnical investigation (B3.2)		
	A desktop geotechnical report is available upon request.		
49	F: V: T:	Item	
	Inspection of the Site (B3.3)		
50	F: V: T:	Item	
	Existing premises occupied (B3.4)		
51	F: V: T:	Item	
	Previous work - dimensional accuracy (B3.5)		
52	F: V: T:	Item	
	Previous work - defects (B3.6)		
53	F: V: T:	Item	
	Services - known (B3.7)		
54	F: V: T:	Item	
	Services - unknown (B3.8)		
55	F: V: T:	Item	
	Protection of trees (B3.9)		
56	F: V: T:	Item	
	Articles of value (B3.10)		
57	F: V: T:	Item	
	Inspection of adjoining properties (B3.11)		
58	F: V: T:	Item	
	<u>MANAGEMENT OF CONTRACT (B4)</u>		
	Management of the Works (B4.1)		
59	F: V: T:	Item	
	Carried to Collection		R
	Section 1		
	Bill No. 1		
	Preliminaries		

	Programme for the Works (B4.2)			
60	F: V: T:	Item		
	Progress meetings (B4.3)			
61	F: V: T:	Item		
	Technical meetings (B4.4)			
62	F: V: T:	Item		
	<u>SAMPLES AND SHOP DRAWINGS (B5)</u>			
	Samples of materials (B5.1)			
63	F: V: T:	Item		
	Workmanship samples (B5.2)			
64	F: V: T:	Item		
	Shop drawings (B5.3)			
65	F: V: T:	Item		
	<u>TEMPORARY WORKS AND PLANT (B6)</u>			
	Deposits and fees (B6.1)			
66	F: V: T:	Item		
	Enclosure of the works (B6.2)			
	The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.			
67	F: V: T:	Item		
	Advertising (B6.3)			
68	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Plant and equipment (B6.4)		
69	F: V: T: Main notice board (B6.5) One notice board shall be provided by the Contractor	Item	
70	F: V: T: Subcontractors notice board (B6.6) (N/A)	Item	
71	F: V: T: <u>TEMPORARY SERVICES (B7)</u> Location (B7.1)		
72	F: V: T: Water (B7.2) The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item	
73	F: V: T: Electricity (B7.3) The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item	
74	F: V: T: Telecommunication equipment (B7.4) The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item	
75	F: V: T:	Item	
Carried to Collection			
Section 1 Bill No. 1 Preliminaries			R

	Ablution facilities (B7.5)			
	The contractor shall provide toilet facilities on site for the works in accordance with:			
	Alternative A (i.e. to be provided for by the Contractor).			
76	F: V: T:	Item		
	<u>PRIME COST AMOUNTS (B8)</u>			
	Responsibility for prime cost amounts (B8.1)			
77	F: V: T:	Item		
	<u>ATTENDANCE ON N/S SUBCONTRACTORS (B9)</u>			
	General Attendance (B9.1)			
78	F: V: T:	Item		
	Special Attendance (B9.2)			
79	F: V: T:	Item		
	Commissioning - fuel, water and power (B9.3)			
80	F: V: T:	Item		
	<u>FINANCIAL ASPECTS (B10)</u>			
	Statutory taxes, duties and levies (B10.1)			
	Provision is made in the Final Summary of these Bills of Quantities for the inclusion of Value Added Tax (VAT).			
81	F: V: T:	Item		
	Payment of Preliminaries (B10.2)			
82	F: V: T:	Item		
	Adjustment of Preliminaries (B10.3)			
83	F: V: T:	Item		
	Payment certificate cash flow (B10.4)			
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

84	F: V: T: Contractor information supply (B10.5)	Item		
85	F: V: T: <u>GENERAL (B11)</u> Protection of the Works (B11.1)	Item		
86	F: V: T: Protection/isolation of existing/sectionally occupied works (B11.2)	Item		
87	F: V: T: Site security (B11.3)	Item		
88	F: V: T: Notice before covering work (B11.4)	Item		
89	F: V: T: Disturbance (B11.5)	Item		
90	F: V: T: Works cleaning and clearing (B11.6)	Item		
91	F: V: T: Vermin (B11.7)	Item		
92	F: V: T: Overhand work (B11.8)	Item		
93	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

SECTION C: SPECIFIC PRELIMINARIES

Section C: Specific Preliminaries:

C1. Proprietary branded products

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: V: T:

Item

C2. Trade Names, etc.

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: V: T:

Item

C3. Contractors responsibility

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: V: T:

Item

C4. Overtime

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.			
97	F: V: T: C5. As built drawings The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records. Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.	Item		
98	F: V: T: C6. Construction Instructions Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books: a) Construction Instruction Book: Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book. Only instructions issued in such book shall be recognised. b) Daily Record Book:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

	The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.				
99	F: V: T: C7. Labour record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.	Item			
100	F: V: T: C8. Plant record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.	Item			
101	F: V: T: C9. Encroachment During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.	Item			
102	F: V: T: C10. Method Statement	Item			
				Carried to Collection	
					R
				Section 1	
				Bill No. 1	
				Preliminaries	

	The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.			
103	F: V: T: C11. Unauthorised Persons/Workmen on Premises The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect. No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.	Item		
104	F: V: T: C12. Mode of Procedure Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited. Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.	Item		
105	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

	C13. Location of Temporary Buildings and Temporary Services The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period. There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.				
106	F: V: T: <u>C14. Office accommodation</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item			
107	F: V: T: <u>C15. Storage Facilities</u>	Item			
108	The Contractor shall provide a Container for storage of materials.	Item			
109	F: V: T: C16. Removal and Making Good of Temporary Works, etc, on Completion The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item			
110	F: V: T:	Item			
Carried to Collection				R	
Section 1 Bill No. 1 Preliminaries					

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

[illegible]

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Section 1

Bill No. 1

Preliminaries

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

Carried Forward

R

Section 1

Bill No. 1

Preliminaries

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

[illegible]

Item No	Quantity	Rate	Amount
<u>SECTION 1</u>			
<u>BILL No. 2</u>			
<u>HEALTH AND SAFETY</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>SUPPLEMENTARY PREAMBLES</u>			
Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles.			
The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.			
Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications.			
The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety Specifications.			
The costs included herein must incorporate Community Liaison Officer (CLO).			
Carried to Collection			
Section 1 Bill No. 2 Health and Safety			R

<u>OCCUPATIONAL HEALTH AND SAFETY</u>				
<u>General:</u>				
1	Preparation of Contractor's site specific Health and Safety Plan.	Item		
2	Submission of the Health and Safety File.	Item		
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.	Item		
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.	Item		
5	Provision of full time Health and Safety Officer for the entire construction period.	Item		
6	Induction training of personnel.	No		
7	Provision of first aid boxes.	No		
8	SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m		
9	Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high.	No		
<u>Provision for Personal Protective Equipment and Protective Clothing:</u>				
10	Reflective vests.	No		
11	Hard hats.	No		
12	Protective foot wear.	No		
13	Ear Plugs.	No		
14	Dust Masks.	No		
<u>Costs of Medical Certificates and Medical Surveillance:</u>				
15	Initial (baseline) medical examinations.	No		
Carried to Collection			R	
Section 1 Bill No. 2 Health and Safety				

[illegible]

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Section 1

Bill No. 2

Health and Safety

COLLECTION

Total Brought Forward from Page No.

**Page
No**

26

27

28

Amount

Carried Forward to Summary of Section No. 1

R

Section 1

Bill No. 2

Health and Safety

Section 1

SECTION SUMMARY - PRELIMINARIES

**Bill
No**

Preliminaries

Health and Safety

**Page
No**

25

29

Amount

Carried to Final Summary

R

Section 1

Removal of asbestos material

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The following shall apply in respect of asbestos removal

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

Carried to Collection

Section 2
Bill No. 1
Demolitions

R

DEMOLISHING AND REMOVING

- | | |
|---|--|
| 1 | Demolish and cart away ablution structure comprised of brick/block work with corrugated asbestos roof sheeting, approximate size 7000 x 6500mm wide and 3500mm high. |
| 2 | Cart away rubble from demolitions and dispose off site. |

No

2

Item

Carried to Collection

R

Section 2
Bill No. 1
Demolitions

Section 2

Bill No. 1

Demolitions

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

31

32

33

Carried to Final Summary

R

Section 2
Bill No. 1
Demolitions

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 1</u> <u>EARTHWORKS (PROVISIONAL)</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent. <u>Nature of material to be excavated:</u> The material to be excavated is assumed to be predominantly of a composition that will allow excavation in "earth" as specified, but including a percentage of excavation in "soft rock" and "hard rock". <u>Carting away of excavated material:</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations, or alternatively, from stock piles situated on the building site.			
	Carried to Collection		R	
	Section 3 Bill No. 1 Earthworks (Provisional)			

Dewatering of excavations:

The Contractor shall allow for removing seepage and other water from subterranean sources from the excavations by pumping, baling or otherwise. Accurate records of all such dewatering shall be kept to determine the total volume of water so removed and a clear distinction shall be made between water from subterranean sources and other water

Density testing on filling:

Rates for filling, etc. shall include for all density and soil type testing to prove that the specified compaction is achieved. When additional testing is done on instruction of the Principal Agent and these tests are successful, they will be paid for additionally.

Imported fill:

"Filling and bedding to trenches etc. to be in compliance with SABS 1200 DB and LB respectively"

Classification of excavated material

"Hard rock" shall mean granite, quartzitic sandstone or other rock of similar hardness, the removal of which requires drilling, wedging and splitting or the use of explosives.

"Soft rock" shall mean hard material, the removal of which warrants the use of pneumatic tools and includes hard shale, ferricite, compact outcrop and material of similar hardness.

"Earth" shall mean all ground other than that classified as "hard rock" or "soft rock" and shall include made-up ground and any loose stones or pieces of concrete not exceeding 0,03m³ in volume.

Carried to Collection

Section 3
Bill No. 1
Earthworks (Provisional)

R

EXCAVATION OTHER THAN BULK

Excavation in earth not exceeding 2m deep:

1	Trenches.	m3	25		
	A0 : 6 A1 : 7 A6 : 6 AD : 6				
2	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	50		
	A0 : 12 A1 : 15 A6 : 11 AD : 12				

Extra over trench and hole excavations in earth for excavation in:

3	Soft rock.	m3	38		
	A0 : 9 A1 : 11 A6 : 9 AD : 9				
4	Hard rock.	m3	23		
	A0 : 5 A1 : 7 A6 : 5 AD : 5				

Extra over all excavations for carting away:

5	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor.	m3	75		
	A0 : 18 A1 : 22 A6 : 17 AD : 19				

Risk of collapse of excavations:

6	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	120		
	A0 : 29 A1 : 33 A6 : 28 AD : 30				

Keeping excavations free of water:

7	Keeping excavations free from mud and all water including subterranean sources.	Item			
---	---	------	--	--	--

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

EARTH FILLING, ETC.

Earth filling obtained from the excavations and / or prescribed stock piles on site (minimum G7 tested material) compacted to 93% Mod. AASHTO density:

8	Under floors, etc.	m3	19	
	A0 : 4 A1 : 6 A6 : 4 AD : 5			

Imported G5 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to trenches, holes, etc.

9	Under floors, etc.	m3	19	
	A0 : 4 A1 : 6 A6 : 4 AD : 5			

Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to holes, trenches etc.

10	Under floors, etc.	m3	56	
	A0 : 13 A1 : 17 A6 : 13 AD : 14			

Coarse river sand filling supplied by the contractor:

11	Under floors etc.	m3	7	
	A0 : 1 A1 : 2 A6 : 2 AD : 2			

Compaction of surfaces:

12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density.	m2	125	
	A0 : 29 A1 : 37 A6 : 28 AD : 31			

Prescribed density tests on filling:

13	Allow for compaction tests by an approved laboratory to determine density of filling material.	No	35	
	A0 : 8 A1 : 8 A6 : 8 AD : 11			

Carried to Collection

Section 3
Bill No. 1
Earthworks (Provisional)

R

SOIL POISONING

**Approved brand of anti-termite soil poison applied
by a Registered Pest Control company and
guaranteed against termite infestation for ten years:**

14	Under floors, etc., including forming and poisoning shallow furrows against foundation walls, etc., filling in furrows and ramming. A0 : 29 A1 : 37 A6 : 28 AD : 31	m2	125		
----	---	----	-----	--	--

Carried to Collection

Section 3
Bill No. 1
Earthworks (Provisional)

R

Section 3

Bill No. 1

Earthworks (Provisional)

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

35

36

37

38

39

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 1

Earthworks (Provisional)

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 2</u> <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent. <u>Cost of tests:</u> The costs of making, storing and testing of concrete test cubes as required under clause 7 'Tests' of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the Architect. The testing shall be undertaken by an independent firm or institution nominated by the Contractor to the approval of the Architect. (Test cubes are measured separately).			
	Carried to Collection		R	
	Section 3 Bill No. 2 Concrete, Formwork and Reinforcement			

Formwork:

Descriptions of formwork shall be deemed to include use and waste only (except where described as left in or permanent), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use.

The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself.

Formwork to soffits of solid slabs etc., shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described.

Formwork to sides of bases, pile caps, ground beams, etc., will only be measured where it is prescribed by the Engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in Earthworks.

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

**UNREINFORCED CONCRETE CAST AGAINST
EXCAVATED SURFACES**

15Mpa/19mm Concrete

- | | | | | |
|---|--|----|---|--|
| 1 | Surface blinding under footings and bases. | m3 | 6 | |
| | A0 : 1 A1 : 2 A6 : 1 AD : 2 | | | |

**REINFORCED CONCRETE CAST AGAINST
EXCAVATED SURFACES**

30MPa/20mm concrete:

- | | | | | |
|---|---|----|----|--|
| 2 | Concrete raft slab on waterproofing. | m3 | 33 | |
| | A0 : 8 A1 : 10 A6 : 8 AD : 8 | | | |

TEST BLOCKS

Test blocks:

- | | | | | |
|---|---|----|----|--|
| 3 | Making and testing of 150x150x150mm concrete strength test cubes (Provisional). | No | 24 | |
| | A0 : 6 A1 : 6 A6 : 6 AD : 6 | | | |

FINISHING TOP SURFACE OF CONCRETE

Finishing top surfaces of concrete smooth with a wood float:

- | | | | | |
|---|---|----|-----|--|
| 4 | Surface beds, suspended slabs, ground slabs, etc. | m2 | 125 | |
| | A0 : 29 A1 : 37 A6 : 28 AD : 31 | | | |

ROUGH FORMWORK (DEGREE OF ACCURACY III)

Rough Formwork to Sides:

- | | | | | |
|---|---|---|-----|--|
| 5 | Edges, risers, ends and reveals not exceeding 300mm high or wide. | m | 100 | |
| | A0 : 28 A1 : 24 A6 : 23 AD : 25 | | | |

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Smooth Formwork to Sides:

6	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m2	50		
	A0 : 14 A1 : 12 A6 : 12 AD : 12				

MOVEMENT JOINTS ETC

Two layers of 375 micron damp proof course in slip joints between horizontal concrete and brick surfaces including cement mortar bed (Provisional)

7	Not exceeding 300mm wide.	m	155		
	A0 : 34 A1 : 44 A6 : 35 AD : 42				

Saw cut joints:

8	6 x 40mm Saw cut joints in top of concrete (Provisional).	m	81		
	A0 : 20 A1 : 20 A6 : 20 AD : 20				

REINFORCEMENT (PROVISIONAL)

9	High tensile steel reinforcement bars to structural concrete work.	t	5.27		
	A0 : 0.78 A1 : 0.93 A6 : 0.76 AD : 2.81				

Fabric reinforcement:

10	REF. 617 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	125		
	A0 : 29 A1 : 37 A6 : 28 AD : 31				

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

41

42

43

44

Carried Forward to Summary of Section No. 3

R

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 3</u> <u>MASONRY</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. All references to SABS shall be deemed to be the relevant SANS specification <u>SUPPLEMENTARY PREAMBLES</u> <u>BRICKWORK</u> <u>Sizes in descriptions</u> Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick <u>Hollow walls etc</u> Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole. Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixal" bitumen emulsion waterproofing coating.			
	Carried to Collection		R	
	Section 3 Bill No. 3 Masonry			

Face bricks

Bricks shall be ordered timeously to obtain uniformity in size and colour

Pointing

Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc

Samples

Samples of all masonry building units, except those of walls described as "loadbearing", shall consist of a minimum of 6 units. Samples of building units to be used in walls described as "loadbearing" shall consist of 30 units from every 30 000 units delivered to site

Trade names

Where trade names are specified it will read "or equal approved"

Carried to Collection

R

Section 3
Bill No. 3
Masonry

BRICKWORK AND BLOCKWORK SUNDRIES

Galvanized brickwork reinforcement

1	115mm Wide reinforcement built in horizontally A0 : 53 A1 : 124 A6 : 71 AD : 53	m	301		
2	230mm Wide reinforcement built in horizontally. A0 : 304 A1 : 328 A6 : 283 AD : 368	m	1 283		

Cramps, ties, etc:

3	30 x 2mm Galvanized roof tie 1500mm long with one end fixed to timber and other built into brickwork or concrete. A0 : 26 A1 : 26 A6 : 26 AD : 26	No	104		
---	---	----	-----	--	--

Air bricks etc:

4	229 x 152mm terracotta clay vermin proof air brick A0 : 12 A1 : 12 A6 : 12 AD : 12	No	48		
---	--	----	----	--	--

Bagging and sealing the outer face of the inner skin of walls with 1:3 cement and sand mixture and seal with two coats "Brixeal" bitumen emulsion waterproofing coating:

5	To walls (Provisional). A0 : 78 A1 : 93 A6 : 74 AD : 77	m2	322		
---	---	----	-----	--	--

Samples

6	Prepare and construct for approval L-Shaped one brickwall faced and pointed both sides as per given specification, size: 1000x1000x1000mm high. same area (1000x1000mm) to be paved as per given specifications.			Item	
---	--	--	--	------	--

Turning pieces to lintels etc

7	230mm Wide turning pieces A0 : 12 A1 : 18 A6 : 12 AD : 13	m	55		
---	---	---	----	--	--

Carried to Collection

Section 3
Bill No. 3
Masonry

R

FACE BRICK

"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):

8	Half brick wall in beam filling pointed one side including cutting and fitting around roof timbers and bedding roofing solid on top in cement mortar.	m2	53
	A0 : 12 A1 : 16 A6 : 12 AD : 13		
9	One brickwall pointed on both sides.	m2	394
	A0 : 94 A1 : 101 A6 : 87 AD : 113		
10	Half brickwall pointed on both sides.	m2	92
	A0 : 16 A1 : 38 A6 : 22 AD : 16		
11	Fair raking cutting.	m	36
	A0 : 9 A1 : 9 A6 : 9 AD : 9		

Face brick copings, lintels, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces:

12	220mm Brick on edge sill bedded sloping and jointed in cement mortar and pointed on top, edge and projecting soffit including cutting and fitting between reveals and splay cutting brickwork under.	m	28
	A0 : 6 A1 : 9 A6 : 6 AD : 7		
13	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on both sides.	m	32
	A0 : 7 A1 : 10 A6 : 7 AD : 8		

Quarry tiles, cement tiles, fibre-cement, etc.

Natural grey fibre-cement cills

14	15mm x 150mm Wide cill set flat and slightly projecting.	m	28
	A0 : 6 A1 : 9 A6 : 6 AD : 7		

Carried to Collection

Section 3
Bill No. 3
Masonry

R

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Section 3

Bill No. 3

Masonry

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

46

47

48

49

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 3

Masonry

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 4</u> <u>WATERPROOFING</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent. <u>Waterproofing</u> The product and its methodology for application must be approved by Principal Agent before it is used. It is a mandatory requirement for the Contractor to attend training to be provided by Supplier. Proof of attendance will be required prior to application of the approved waterproofing product. Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent or Engineer. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the waterproofing product is intended to be done.			
	Carried to Collection		R	
	Section 3			
	Bill No. 4			
	Waterproofing			

Contractor to provide a Letter of Compliance confirming that waterproofing has been applied as per Manufacturer's instructions and data sheet.

Carried to Collection

Section 3
Bill No. 4
Waterproofing

R

DAMPPROOFING OF WALLS AND FLOORS

One layer of 250 micron 'USB GREEN' waterproof sheeting sealed at laps with 'Gunplas Pressure Sensitive Tape':

1	Under surface beds, bases, etc.	m2	125	
	A0 : 29 A1 : 37 A6 : 28 AD : 31			

One layer of 350 micron embossed dampcourse waterproof sheeting below walls, sills, etc:

2	Below walls, sills, etc.	m2	13	
	A0 : 3 A1 : 4 A6 : 3 AD : 3			

JOINT SEALANTS ETC

Clear Neutral silicone sealant:

3	In joint sealing and pointing all round external window and door frames.	m	212	
	A0 : 47 A1 : 77 A6 : 34 AD : 55			

Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc

4	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary (Provisional).	m	81	
	A0 : 20 A1 : 20 A6 : 20 AD : 20			

Carried to Collection

R

Section 3
Bill No. 4
Waterproofing

Section 3

Bill No. 4

Waterproofing

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

51

52

53

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 4

Waterproofing

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 5</u> <u>ROOF COVERINGS</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Flashings</u> Flashings shall be approved by roof sheeting manufacturer and fixed to the sheeting with S10 clips to obviate any direct fixing perforations. Prior to flashings being fixed, all troughs at the apex shall be stop-ended to the full depth of the sheet in order to prevent any penetration of wind driven water. The trough shall be lipped at the eaves end to form a drip. Flashing flanges shall be notched to the sheet profile where necessary. All these operations must be performed with special tools available from the manufacturer. Care shall be taken to ensure that no sheeting or flashing will be cut with abrasive disc on roof surface in order to prevent steel splatter from penetrating colour coated areas. The flashings shall be supplied with a paint finish consisting of a full top coat silicon modified polyester Colour : White to one side <u>Quality Assurance</u> The manufacturer shall be assessed and certified as complying with ISO 9001: 2008 Quality Management System			
	Carried to Collection		R	
	Section 3 Bill No. 5 Roof Coverings Etc.			

Guarantee

Z200 Galvanized Metal or equal approved sheeting shall be laid in strict accordance with manufacturer's specifications by an approved contractor. The employer shall be provided with a ten year written guarantee on materials by the manufacturer.

Safety

The contractor shall exercise special care when handling long length sheeting, particularly in windy conditions. Should work be interrupted for any reason, all loose sheeting and incomplete sections must be adequately secured against possible movement by wind and gravity

Handling and Storage

The contractor shall ensure that all materials used on site for cladding, etc are transported, handled and stored in accordance with the manufacturer's recommendations. Material damaged shall be rejected and replaced with undamaged material at the contractor's expense. Repair of damaged material will not generally be permitted. Rates are to include for preventing damage and protecting sheets through all stages of construction

Inspection Prior to Installation or Erection

Before commencing with installation, the contractor shall verify that the following items have been checked and accepted:

- a. The entire structure or the portion thereof to be sheeted has been correctly aligned, levelled and grouted
- b. Purlins and sheeting rails are at the correct spacing and are within the specified tolerances
- c. The corners of the roof are square and the wall framework is perpendicular or as specified
- d. No protrusions such as bolt heads, splice plates, cleats, etc. appear on the face of the framework
- e. All members to which roofing and cladding are to be fixed in aesthetically sensitive areas are true and square
- f. Paint and any other materials that may be incompatible with the sheeting, have been painted over or so dealt with that direct contact with the sheeting is avoided
- g. The contact faces between the purlins or the girts and the cladding are in the same plane. Should the alignment be inadequate, the contractor shall request instructions from the engineer before proceeding with the fixing of the cladding

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

Protrusion through Sheeted Surfaces

Protrusions such as pipes, ducts and the like, shall be adequately flashed where they pass through the sheeting surface. Where ribs have to be cut away to permit penetration, additional framing is to be installed as required to support the sheeting. Depending on the position of the penetration through the roof, special attention shall be given to back flashing the sheeting to the ridge or point of water entry. In all cases, all cutting and flashings shall be so arranged that adequate provision is made for the drainage of all troughs and corrugation

Cleaning of Roofs, etc

All debris, etc arising from the fixing of the cladding shall be removed from the sheetin as the fixing progresses. In addition, off-cuts of insulation, surplus fastners and sealants, mandrels from pop rivets, off-cuts of flashings and sheeting, surplus flashing, food packaging, cartons, bottles, cans, etc shall not be left on the roof or in the gutters. Care shall be taken to ensure that no such material enters, blocks or partially impedes the flow of water into the outlets, downpipes, etc

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

ROOF COVERINGS

PROFILED METAL SHEETING AND ACCESSORIES

0.58mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face :

1	Roof sheeting laid to a mono-pitch.	m2	172	
	A0 : 40 A1 : 51 A6 : 39 AD : 42			

0.58mm Flashings pre-painted to match roof sheeting and fixed in strict accordance with manufacturer's instructions:

2	Mono pitched ridge capping with 225mm lapping secured onto the roof.	m	77	
	A0 : 18 A1 : 23 A6 : 17 AD : 19			

ROOF AND WALL INSULATION

"Sisalation Grade FR430" or equal approved heavy industrial insulation

3	Insulation laid taut over roof trusses (at approximately 1 100mm centres) and fixed concurrent with SA Pine purlins at 900mm centres, etc including galvanised steel straining wires	m2	172	
	A0 : 40 A1 : 51 A6 : 39 AD : 42			

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

Section 3

Bill No. 5

Roof Coverings Etc.

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

55

56

57

58

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 5

Roof Coverings Etc.

CARPENTRY

Sawn softwood:

1	38 x 114mm Wall plate. A0 : 36 A1 : 46 A6 : 35 AD : 38	m	155		
2	50 x 76mm Purlins. A0 : 72 A1 : 91 A6 : 70 AD : 76	m	309		
3	50 x 76mm Bracing. A0 : 12 A1 : 12 A6 : 12 AD : 12	m	48		
4	38 x 152mm Rafters. A0 : 44 A1 : 44 A6 : 44 AD : 44	m	178		

Sundries:

5	TRI FIX or equal approved hurricane clip fixed using 10 x 32mm galvanised clout nails (Provisional). A0 : 45 A1 : 45 A6 : 40 AD : 55	No	185		
---	--	----	-----	--	--

EAVES, VERGES, ETC

"Everite Nutec" or equal approved fibre cement

6	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc. A0 : 36 A1 : 46 A6 : 35 AD : 38	m	155		
7	85 x 275 x 6mm Barge board drilled and brass screwed to purlin ends including galvanised steel H-profile jointing strips, screws, holes, etc. A0 : 9 A1 : 9 A6 : 9 AD : 9	m	36		

Carried to Collection

Section 3
Bill No. 6
Carpentry and Joinery

R

DOORS ETC

SANS Approved meranti:

8	44mm Framed, ledged, and battened single door with flush ply panel internally size 813 x 2032mm high comprising 44 x 110mm top rail and stiles, 44 x 220mm bottom rail, 44 x 150mm lock rail and 22 x 70mm vertical "v" jointed boards (D1).	No	5
	A0 : 1 A1 : 1 A6 : 1 AD : 2		
9	44mm Framed, ledged, and battened single door with flush ply panel internally size 950 x 2032mm high comprising 44 x 110mm top rail and stiles, 44 x 220mm bottom rail, 44 x 150mm lock rail and 22 x 70mm vertical "v" jointed boards (D2).	No	2
	A0 : 0 A1 : 0 A6 : 1 AD : 1		
10	44mm Framed, ledged, and battened purpose made single door with flush ply panel internally size 813 x 1832mm high comprising 44 x 110mm stiles, 44 x 220mm bottom rail, 44 x 150mm lock rail and 22 x 70mm vertical "v" jointed boards (D4).	No	15
	A0 : 4 A1 : 8 A6 : 0 AD : 3		
11	44mm Braced and ledged door size 862 x 1000mm Type (D3).	No	4
	A0 : 0 A1 : 0 A6 : 4 AD : 0		

FRAMED FRAMES, ETC

Meranti Frames bolted to wall with expanding masonry bolts - four per style including quadrant beads on both sides:

12	70 x 108mm rebated meranti frame .	m	110
	A0 : 23 A1 : 41 A6 : 23 AD : 23		

Meranti Frames fixed against brickwall using galvanised steel lugs bolted with expanding masonry bolts - four per style including quadrant beads on both sides:

13	70 x 108mm rebated meranti frame .	m	10
	A0 : 0 A1 : 0 A6 : 5 AD : 5		

Carried to Collection

Section 3
Bill No. 6
Carpentry and Joinery

R

Section 3

Bill No. 6

Carpentry and Joinery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

60

61

62

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 6

Carpentry and Joinery

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 7</u> <u>IRONMONGERY</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Keys/Locks</u> Each lock is to be distinctly numbered with consecutive numbers and each key is to be stamped with the corresponding number to the lock that it controls. All locks are to have two keys <u>Trade Names</u> Where trade names are specified other ironmongery approved by the Principal Agent may be used <u>Fixing</u> Fixing of ironmongery is deemed to be fixed to timber unless otherwise described			
	Carried to Collection		R	
	Section 3 Bill No. 7 Ironmongery			

HINGES:

1	75 x 100mm Brass Medium duty ball bearing HMP butt hinges.	Pairs	22.0
	A0 : 5.0 A1 : 9.0 A6 : 2.0 AD : 6.0		

LOCKS

2	"UNION 2277-78SS" or equal approved three lever sash mortice lockset.	No	7
	A0 : 1 A1 : 1 A6 : 2 AD : 3		
3	"UNION w/c indicator bolt satin chrome - Code CZ80941SC	No	19
	A0 : 4 A1 : 8 A6 : 4 AD : 3		

HANDLES

4	"Dorma DPH301B" or equal approved Stainless Steel Straight Tubular Pull handle flange fixing.	No	26
	A0 : 5 A1 : 9 A6 : 6 AD : 6		
5	"Union Radius CZ682-24 SC" Or other equal approved lever handles. (Pair)	No	7
	A0 : 1 A1 : 1 A6 : 2 AD : 3		

Sundries:

6	Stainless Steel Hat and coat hook, code DHC - SS-030-A or equal approved.	No	19
	A0 : 4 A1 : 8 A6 : 4 AD : 3		
7	38mm Diameter black rubber door stop plugged and screwed to wall.	No	26
	A0 : 5 A1 : 9 A6 : 6 AD : 6		

SIGN PLATES:

All sign plates are to be with engraved blue perspex all in accordance with the standard sign plates for Schools.

8	Sign plate plugged and screwed to walls with chromium plated dome headed screws.	No	7
	A0 : 1 A1 : 1 A6 : 2 AD : 3		

Carried to Collection

Section 3
Bill No. 7
Ironmongery

R

SUNDRIES

Halcast or equal approved"

9	Thiefproof toilet roll holder plugged.	No	21	
	A0 : 4 A1 : 8 A6 : 5 AD : 4			

Grade 304 stainless steel ware:

10	32mm outside diameter x 1,6mm thick tubular wall mounted side stainless steel grab rail 1,06m girth with two 45 degree and two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews.	No	2	
	A0 : 0 A1 : 0 A6 : 1 AD : 1			

11	32mm outside diameter x 1,6mm thick tubular wall mounted around cistern back stainless steel grab rail 1,23m girth with two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews.	No	2	
	A0 : 0 A1 : 0 A6 : 1 AD : 1			

Satin Grey Plastics or equal approved

12	"Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose.	No	8	
	A0 : 2 A1 : 2 A6 : 2 AD : 2			

Carried to Collection

Section 3
Bill No. 7
Ironmongery

R

Section 3

Bill No. 7

Ironmongery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

64

65

66

Amount

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 7

Ironmongery

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 8</u> <u>METALWORK</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 10 - Male Ablutions A1 - DWG 17 - Female Ablutions A6 - DWG 07 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> The Contractor is to check and verify on site that the item specified in the BoQ matches existing prior to placing orders. Additional costs will not be borne by the client for items that do not match existing and are not approved by the Principal Agent <u>ALUMINIUM WINDOWS</u> All aluminium windows are to be manufactured by manufacturers who are members of AAAMSA. All aluminium systems to be approved by AAAMSA. All aluminium work is to be protected by covering with plastic sheeting fixed with low tack adhesive prior to leaving the factory. Plastic sheeting is to remain in place during construction. All glazing shall be in accordance with SABS 0400 - 1990, SABS 1263 - 1. All safety glazing materials (individual panes) shall be permanently marked. Such marking shall be visible after glazing process. If it is not marked, it is not safety glass.			
	Carried to Collection		R	
	Section 3 Bill No. 8 Metalwork			

Natural anodised aluminium windows glazed with 6.38mm opaque safety laminated glass and plugged to brickwork:

- | | | | | |
|---|---|----|----|--|
| 1 | Window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01. | No | 46 | |
| | A0 : 10 A1 : 15 A6 : 10 AD : 11 | | | |

HOT DIP GALVANIZED STEEL GATES

Note: The contractor is to check on site measurements before placing of order.

Security Gate consisting of 25 x 25 x 2mm galvanised mild steel frame with 12mm galvanised mild steel square bars infill placed at 109mm centres, hung with one pair of galvanised mild steel hinges including locks, handles, ironmongery complete and fixed to brickwork:

- | | | | | |
|---|---|----|---|--|
| 2 | Security gate size 900 x 2050mm high (G1). | No | 4 | |
| | A0 : 1 A1 : 1 A6 : 1 AD : 1 | | | |
| 3 | Security double gate size 1800 x 2050mm high. | No | 1 | |
| | A0 : 0 A1 : 0 A6 : 0 AD : 1 | | | |

Carried to Collection

Section 3
Bill No. 8
Metalwork

R

Section 3

Bill No. 8

Metalwork

COLLECTION

Total Brought Forward from Page No.

**Page
No**

68

69

Amount

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 8

Metalwork

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u>			
	<u>BILL No. 10</u>			
	<u>PLUMBING AND DRAINAGE (PROVISIONAL)</u>			
	<u>Quantity Split:</u>			
	Note that the total quantity per each item is split into the various buildings and appears below each description as follows:			
	A0 - DWG 10 - Male Ablutions			
	A1 - DWG 17 - Female Ablutions			
	A6 - DWG 07 - Grade R Ablutions			
	AD - DWG 04 - Staff Ablutions			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
	<u>RAINWATER DISPOSAL:</u>			
	<u>Watertite or equal approved Aluminium Gutters and Downpipes:</u>			
1	125 x 85 x 0.6mm Ogee domestic gutters including gutter brackets at 600mm centres. A0 : 18 A1 : 23 A6 : 17 AD : 19	m	77	
2	Extra over eaves gutter for stopped end. A0 : 2 A1 : 2 A6 : 2 AD : 2	No	8	
3	Extra over eaves gutter for outlet for 100 x 75mm aluminium downpipe. A0 : 2 A1 : 2 A6 : 2 AD : 2	No	8	
4	100 x 75 x 0.6mm rectangular fluted downpipes fixed to wall with and including proprietary holderbats to 5000L rainwater tanks (elsewhere measured). A0 : 9 A1 : 9 A6 : 9 AD : 9	m	36	
5	Extra over rainwater downpipe for bends. A0 : 3 A1 : 3 A6 : 3 AD : 3	No	12	
	Carried to Collection			R
	Section 3			
	Bill No. 10			
	Plumbing and Drainage (Provisional)			

TAPS, VALVES, ETC

Solid Cast brass taps, valves, etc:

6	"Cobra KM2-200" or other approved 15mm chrome plated metered bib tap with non-hold open feature and flow controller.	No	16		
	A0 : 2 A1 : 6 A6 : 4 AD : 4				
7	15mm Ball-o-stop valve.	No	17		
	A0 : 2 A1 : 6 A6 : 4 AD : 5				
8	22mm Non Return valve.	No	21		
	A0 : 5 A1 : 5 A6 : 5 AD : 6				

WASTE UNIONS ETC

Outlets, traps, etc:

9	40mm 342/50 CP bottle trap.	No	1		
	A0 : 0 A1 : 0 A6 : 0 AD : 1				
10	40mm Code 316 chrome plated unslotted waste outlet.	No	16		
	A0 : 2 A1 : 6 A6 : 4 AD : 4				
11	40mm Rubber "P" or "S" trap	No	16		
	A0 : 2 A1 : 6 A6 : 4 AD : 4				

Carried to Collection

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

R

SANITARY FITTINGS

Vaal or equal approved:

12	Lavatera White Vitreous china wall mounted bowl urinal with top inlet [code: 704001] 610x385mm, supplied with 38mm chromium plated domical grating [code: 8787], chromium plated spreader [code: 8543], and two hanger brackets [code: 8127] A0 : 0 A1 : 0 A6 : 0 AD : 1	No	1
13	Hibiscus White Vitreous china 510 x 405mm rounded basin [code: 7050] with one tap hole on left hand side, including integrated overflow, bolted to wall with two 8mm bolts [code 8448Z0], to manufacturer's specification. A0 : 2 A1 : 6 A6 : 4 AD : 4	No	16
14	Orchid back inlet white vitreous china wall hung pan [code 439016] with floor bracket [code 8082Z0] fitted as per manufacturer's specifications and combined with: GEBERIT Kombifix UP172 for wall hung WC, [G110.150.00.1], front actuated with Delta21 dual flush actuator [G115.125.46.1] in matt finish, including flushpipe and Pan connector, water supply connection with angle stop valve, Netting for direct plastering, protection cover for service opening and protection cover for flushpipe, fixed with included fastening materials inside a single solid wall [80mm] A0 : 4 A1 : 8 A6 : 1 AD : 4	No	17
15	Junior vitreous china low level suite colour White (Code: 751358), comprising 104° outlet washdown pan (Code: 751301) with matching 6 litre front single flush cistern (Code: 712034) including lid, fitments and flushpipe and Junior double flap wooden seat (Code: 8518Z0). A0 : 0 A1 : 0 A6 : 4 AD : 0	No	4

Carried to Collection

R

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

	<u>Franke Model TU101 or equal approved flush valve/cistern flat back wall mounted urinal:</u>				
16	SS-TU101-1830R Flat back stainless steel school trough urinal wall and floor mounted. manufactured from Grade 304 (18/10) Stainless Steel, 0,9 mm gauge. Urinal to be supplied with a concealed sparge pipe and a 22 mm inlet with chrome plated conex fitting for connecting to water inlet (Connection fitting not supplied). Urinal to include a tiling key to sides and rear walls. The back to be fully sound deadened with vermin proof bitumastic material. Outlet to be situated on the left or right of the urinal with a recess for 40 mm chrome plated waste outlet. A0 : 2 A1 : 0 A6 : 0 AD : 0	No	2		
	<u>SANITARY PLUMBING</u>				
	<u>PVC waste or vent pipes and fittings:</u>				
17	50mm Waste pipe. A0 : 28 A1 : 28 A6 : 30 AD : 27	m	113		
18	110mm Pipe. A0 : 4 A1 : 8 A6 : 1 AD : 4	m	17		
19	110mm Pipe and laying in ground or filling not exceeding 2m deep including excavation, filling in and ramming. A0 : 20 A1 : 19 A6 : 22 AD : 20	m	81		
	<u>uPVC gulleys</u>				
20	200mm Precast concrete gully dish and uPVC lowback assembly complete with 110mm P trap gully (code UGB 40) including 190mm diameter head (code UGA 40) and grate (code UGG 40), not exceeding 750mm deep, jointed to 110mm drain pipe, including excavations for and encasing in concrete (15MPa crushing strength after 28 days) worked up to form kerb, finished smooth on top in 1:3 cement mortar. A0 : 1 A1 : 1 A6 : 1 AD : 1	No	4		
	<u>Extra for:</u>				
21	50mm Bend. A0 : 10 A1 : 12 A6 : 10 AD : 12	No	44		
22	50mm Access bend. A0 : 4 A1 : 3 A6 : 3 AD : 7	No	17		
	Carried to Collection			R	
	Section 3 Bill No. 10 Plumbing and Drainage (Provisional)				

23	100mm Access bend. A0 : 4 A1 : 8 A6 : 1 AD : 4	No	17
<u>WATER SUPPLIES</u>			
<u>Polycop pipes:</u>			
Pipes shall be class 10.			
<u>Fixing of pipes</u>			
Unless specifically otherwise stated, descriptions of pipes shall be deemed to include for fixing to walls etc. casting in, building in or suspending not exceeding 1m below suspension level			
<u>Polycop pipes chased in walls:</u>			
Where pipes have been chased in walls, the price for making good of plaster and paint etc shall be deemed to be included in the description of pipe chased in walls.			
<u>Reducing fittings:</u>			
Where fittings have reducing ends or branches they are described as 'reducing'. In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained.			
<u>Class 10 Polycop pipes:</u>			
24	15mm Pipe chased into brick walls. A0 : 32 A1 : 31 A6 : 32 AD : 33	m	128
25	22mm Pipe chased into brick walls. A0 : 19 A1 : 20 A6 : 20 AD : 17	m	76
<u>Extra over polycop pipes for compression fittings:</u>			
26	15mm Fittings. A0 : 28 A1 : 29 A6 : 29 AD : 24	No	110
27	22mm Fittings. A0 : 25 A1 : 23 A6 : 29 AD : 20	No	97
<u>Connection to existing water supply</u>			
28	Allow for connection to existing water supply.	Item	
Carried to Collection			R
Section 3 Bill No. 10 Plumbing and Drainage (Provisional)			

**Connection of water supply from Waste Water
Treatment System (WWTS)**

29 Allow for connecting water supply from waste water
treatment system.

Testing

30 Testing water pipe system

Item

Item

Carried to Collection

R

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

Section 3

Bill No. 10

Plumbing and Drainage (Provisional)

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

72

73

74

75

76

77

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 10

Plumbing and Drainage (Provisional)

PAINTWORK ETC TO NEW WORK

ON WOOD

Stop, sand down and prepare wood surfaces and apply one coat wood primer, one undercoat and two coats eggshell enamel paint as per Plascon or equal approved:

1	On doors	m2	86	
	A0 : 16 A1 : 29 A6 : 21 AD : 21			

2	On door frames	m2	27	
	A0 : 5 A1 : 9 A6 : 6 AD : 6			

Prepare and apply two coats carbolenium on:

3	On exposed timbers.	m2	56	
	A0 : 13 A1 : 16 A6 : 13 AD : 14			

ON FIBRE-CEMENT

Prepare and apply two coats pure acrylic roof paint on:

4	On fascias and barge boards.	m2	67	
	A0 : 16 A1 : 19 A6 : 15 AD : 16			

5	Internal fibre cement cills not exceeding 300mm girth.	m	28	
	A0 : 6 A1 : 9 A6 : 6 AD : 7			

Carried to Collection

Section 3
Bill No. 11
Paintwork

R

Section 3

Bill No. 11

Paintwork

COLLECTION

Total Brought Forward from Page No.

**Page
No**

79

80

Amount

Carried Forward to Summary of Section No. 3

R

Section 3
Bill No. 11
Paintwork

Section 3

SECTION SUMMARY - BUILDING WORKS

**Bill
No**

**Page
No**

Amount

Earthworks (Provisional)

40

Concrete, Formwork and Reinforcement

45

Masonry

50

Waterproofing

54

Roof Coverings Etc.

59

Carpentry and Joinery

63

Ironmongery

67

Metalwork

70

Plastering

71

Plumbing and Drainage (Provisional)

78

Paintwork

81

Carried to Final Summary

R

Section 3

Item No	Quantity	Rate	Amount
<u>SECTION No. 4</u>			
<u>BILL No. 1</u>			
<u>EXTERNAL WORKS (PROVISIONAL)</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
<u>THE FOLLOWING IN PLATFORMS, ETC.</u>			
<u>Site Clearance, ETC</u>			
1	Allow for clearing the area of the site to be built upon of all grass, weeds, shrubs, trees with trunks not exceeding 200mm girth, debris, etc., including grubbing up all roots, scoffling up as required and cart away all vegetation and debris.	m2	570
2	Stripping average 200mm thick layer of topsoil and stockpiling on site.	m2	570
<u>Open face excavation not exceeding 2m deep:</u>			
3	Excavate to cut in open face, not exceeding 2m deep to reduce levels and grade to fill and compact to 93% mod AASHTO density at optimum moisture content.	m3	68
<u>Extra over all excavations for carting away:</u>			
4	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor.	m3	41
<u>Earth filling from excavated material</u>			
5	Dig, load and remove filling selected from spoil heaps on site and deposit as filling in platforms including spreading and compacting to cambers and falls in layers not exceeding 150 mm thick to a minimum of 95% Modified AASHTO dry density.	m3	27
Carried to Collection			R
Section 4			
Bill No. 1			
External Works			

	<u>Subbase and base courses</u>				
6	G7 Sub-base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 95% modified AASHTO density in platforms including all necessary density and/or control tests.	m3	285		
7	G5 Sub-base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density in platforms including all necessary density and/or control tests.	m3	285		
	<u>Surface Preparation:</u>				
8	Trim and level off surface of ground (excavated or filled under this Contract) including excavating or filling, ripping and scarifying as necessary and compacting the whole area for a depth of 300mm to a density of at least 90% Mod. AASHTO maximum density, part to falls.	m2	570		
	<u>Prescribed density tests on filling:</u>				
9	Modified AASHTO Density test.	No	7		
	<u>LANDSCAPING</u>				
10	Take from topsoil stockpile on site, cart to designated areas, spread and level to contours to achieve an average 200mm thickness including lightly compacting.	m3	12		
11	Kikuyu turf (sods or rolls) instant lawn 25 to 40mm thick, imported from commercial sources, laid firmly with staggered joints, within three days of being lifted including watering.	m2	60		
	<u>THE FOLLOWING IN WALKWAYS</u>				
	<u>Excavation not exceeding 2m deep</u>				
12	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	49		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
13	Off site to a dumping site to be found by the Contractor.	m3	49		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Filling supplied by the contractor under walkways</u>				
14	G7 Sub-base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings including all necessary density and/or control tests.	m3	25		
15	G5 Sub-base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings including all necessary density and/or control tests.	m3	25		
	<u>Rip and recompact insitu material on site compacted to 93% Mod. AASHTO density:</u>				
16	Under floors,etc.	m2	164		
	<u>Prescribed density tests on filling:</u>				
17	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed. (Tests to be executed at the sole discretion of the Engineer)	No	2		
	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>				
18	Treat filling under paving with "Chlordane Heptachlor Aldrin" or other equal approved soil poisoning.	m2	164		
	<u>Concrete Paving Blocks</u>				
	<u>Paving of 50mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:</u>				
19	Paving to walkway areas, etc laid to falls.	m2	164		
20	Extra over ordinary paving for 200mm wide block-on-flat header course edging on 100mm thick mortar bed including unreinforced concrete haunching along outside edge.	m	154		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

<u>Kerbing</u>					
<u>Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.</u>					
21	Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	210		
22	Ditto but circular on plan exceeding 4m radius.	m	12		
23	Ditto but circular on plan not exceeding 4m radius.	m	6		
24	Fig. 12 kerb size 75 x 150mm high overall, laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	18		
25	Ditto but circular on plan exceeding 4m radius.	m	8		
26	Ditto but circular on plan not exceeding 4m radius.	m	4		
<u>Metalwork</u>					
<u>"Mentis Inter-Link" Or other equal approved galvanised mild steel handrailing and accessories</u>					
27	34mm Diameter tubular handrail.	m	42		
28	"MST 90" Ball type vertical stanchion twice bolted to concrete (elsewhere).	No	12		
<u>Extra over handrailing for the following fittings:</u>					
29	"Item 2M" Closure piece.	No	8		
<u>Bolts</u>					
30	Grade 4.8 bolts with head, nut and two washers.	t	0.050		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

WATER RETICULATION

WATER SUPPLY IN GROUND

HDPE 100PN 12.5 pressure pipes:

31	32mm pipes laid in depths not exceeding 1m including excavation, bedding, backfilling, compaction and disposal of surplus material.	m	50
----	---	---	----

32	40mm Pipes laid in depths not exceeding 1m including excavation, bedding, backfilling, compaction and disposal of surplus material.	m	50
----	---	---	----

Extra over (PN12.5) HDPE piping for fittings:

33	32mm Bend.	No	5
----	------------	----	---

34	32mm Adaptor.	No	5
----	---------------	----	---

35	40mm Bend.	No	5
----	------------	----	---

36	32mm Tee.	No	5
----	-----------	----	---

37	40mm Tee.	No	5
----	-----------	----	---

**WATER SUPPLY FROM WASTE WATER
TREATMENT SYSTEM**

HDPE 100PN 12.5 pressure pipes:

38	32mm pipes laid in depths not exceeding 1m including excavation, bedding, backfilling, compaction and disposal of surplus material.	m	50
----	---	---	----

Extra over (PN12.5) HDPE piping for fittings:

39	32mm Bend.	No	5
----	------------	----	---

40	32mm Adaptor.	No	5
----	---------------	----	---

41	32mm Tee.	No	5
----	-----------	----	---

TAPS, VALVES, ETC

42	32mm "Cobra" Ball Valve complete with adaptors for HDPE pipe.	No	5
----	---	----	---

Carried to Collection

Section 4
Bill No. 1
External Works

R

43	32mm Non-return valve.	No	5		
	<u>Municipal connection</u>				
	<u>Sundries:</u>				
44	Allow for amount of R20 000.00 (Twenty Thousand Rand) for municipal water connection to be used at the discretion of the Principal Agent and deducted in whole or in part if not required.		Item		20 000.00
45	Allow for profit if required.			%	
	<u>Testing:</u>				
46	Testing water pipe system.		Item		
	<u>THE FOLLOWING IN STORMWATER DRAINAGE, APRONS ETC.</u>				
	<u>STORMWATER APRONS</u>				
	<u>Excavation not exceeding 2m deep</u>				
47	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	17		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
48	Off site to a dumping site to be found by the Contractor.	m3	17		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
49	G7 Base course material compacted to 98% Mod AASHTO density	m3	9		
50	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	9		
	<u>Coarse river sand filling supplied by the contractor:</u>				
51	Under floors etc.	m3	3		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Compaction of surfaces:</u>				
52	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	57		
	<u>Prescribed density tests on filling:</u>				
53	In-situ dry density test.	No	1		
	<u>Reinforced 25Mpa/19mm Concrete:</u>				
54	Surface beds cast in panels on waterproofing.	m3	5		
55	Edge thickening	m3	1		
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
56	Surface beds, slabs, etc to falls and currents.	m2	57		
	<u>Test blocks:</u>				
57	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	1		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
58	12mm Joints not exceeding 300mm high.	m	14		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
59	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	14		
	<u>Fabric reinforcement:</u>				
60	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	57		
	<u>Waterproofing under Surface beds</u>				
61	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	57		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

**THE FOLLOWING IN SUB-SOIL DRAINAGE,
ETC.**

Site Clearance, ETC

62	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	50
----	--	----	----

Excavation in earth not exceeding 2m deep:

63	Trenches.	m3	50
----	-----------	----	----

Extra over all excavations for carting away:

64	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	5
----	---	----	---

Risk of collapse of excavations:

65	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	200
----	---	----	-----

Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:

66	Backfilling to trenches, holes, etc.	m3	46
----	--------------------------------------	----	----

Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:

67	19mm Stone.	m3	5
----	-------------	----	---

Membrane

68	""Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching.	m2	75
----	--	----	----

Keeping excavations free of water:

69	Keeping excavations free from mud and all water including subterranean sources.		Item
----	---	--	------

Carried to Collection

Section 4
Bill No. 1
External Works

R

	<u>Compaction of surfaces</u>				
70	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	1		
	<u>SOIL DRAINAGE</u>				
	<u>110mm Diameter perforated uPVC pipe surrounded with 300 x 300mm section of 20mm stone wrapped in A3 geotextile material.</u>				
71	110mm uPVC pipe.	m	50		
	<u>Extra for:</u>				
72	110mm Tee.	No	4		
73	110mm Y junction.	No	4		
	<u>THE FOLLOWING IN SOAKAWAY</u>				
	<u>Site Clearance, Etc</u>				
74	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	10		
	<u>Excavation in earth not exceeding 2m deep:</u>				
75	Holes	m3	1		
	<u>Extra over all excavations for carting away</u>				
76	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor within 5km from the building site	m3	1		
	<u>Risk of collapse of excavations</u>				
77	Sides of trench and hole excavations exceeding 1,5m deep but not exceeding 3,0m deep	m2	5		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 90% Mod AASHTO density</u>				
78	Backfilling to holes	m3	1		
	<u>Earth filling with stone material supplied by the contractor:</u>				
79	Stone (>63mm).	m3	1		
	<u>Membranes</u>				
80	"BidimGeotextile or equal approved, lined on all sides including the top and bottom faces.	m2	4		
	<u>Keeping excavations free of water</u>				
81	Keeping excavations free of all water other than subterranean water		Item		
	<u>THE FOLLOWING IN CULVERTS</u>				
	<u>Class 50D concrete pipes:</u>				
82	450mm Diameter Concrete pipe laid in trenches not exceeding 1m deep including excavation, backfill, bedding, cart away and compaction.	m	1		
	<u>Manholes:</u>				
83	Manhole size 600 x 600mm not exceeding 1m deep internally to invert level formed of hard burnt half brick sides in 1:3 cement mortar on and including 100mm thick mass concrete (25 MPa at 28 days in 19 mm stone) bottom reinforced with Y10 bars at 200c/c both directions and projecting 150mm beyond sides, cast on 50mm thick concrete Blinding (15Mpa) and mass concrete (15 MPa at 28 days in 12 mm stone) benching, rendered internally in 1:3 cement plaster with with C.I step irons staggered at 300c/c with 150mm thick grade 25 reinforced precast concrete manhole cover rebated for and fitted with and including cast iron double seal cover and frame type 14B in accordance with SABS 558, bedded in 1:3 cement mortar and sealed in to allow including all necessary vitrified clay channels and fittings, excavations, formwork, holes through sides for pipes, etc	No	1		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

THE FOLLOWING IN HEADWALLS

84	Excavation not exceeding 2m deep.	m3	2
85	Keeping excavations free from water		Item
86	Carting away surplus excavated material	m3	2
87	150mm layer of G7 material compacted to 95% MOD AASHTO under concrete slab.	m3	1
88	150mm layer of G5 material compacted to 95% MOD AASHTO under concrete slab.	m3	1
89	25Mpa/19mm Reinforced concrete in bottom slabs and footings.	m3	2
90	Formwork to edges, risers, ends and reveals not exceeding 300mm wide or high.	m	3
91	Mesh reinforcement Ref 193 in concrete bottom slab.	m2	2
92	One brick wall of 14 MPa NFX bricks.	m2	2
93	230mm Wide reinforcement built in horizontally.	m	24
94	Extra over brickwork for "Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints face brickwork externally.	m2	2
95	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on both sides.	m	5
96	Gabion mattress comprising of 20 to 30mm stones wrapped in A3 geotextile with voids filled with 1:3 cement/sand mortar.	m2	4

Carried to Collection

R

Section 4
Bill No. 1
External Works

SEWER RETICULATION

MODEL PREAMBLES

The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates

SUPPLEMENTARY PREAMBLES

uPVC pipes and fittings

Soil, waste and vent pipes and fittings shall be solvent weld jointed.

Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings.

Excavations:

No claim for rock excavation will be entertained unless the Contractor has timeously notified the quantity surveyor thereof prior to backfilling.

Soft rock and hard rock shall be as defined in Earthworks.

Laying, backfilling, bedding, etc of pipes:

Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions.

Where no manufacturers' instructions exist pipes shall be laid in accordance with clauses 5.1 and 5.2 of each of the following:

SABS 1200

- L :** Medium pressure pipelines
- LD :** Sewers
- LE :** Stormwater drainage Pipe trenches etc shall be backfilled in accordance with clause 3, 5.5, 5.6, 5.7 and 7 of SABS 1200
- DB:** Earthworks (Pipe trenches) Clause 5.7.2 will only be applicable if authorised by the Engineer in writing.

Carried to Collection

Section 4
Bill No. 1
External Works

R

Descriptions of pipes laid in trenches:

Descriptions of pipes laid in and including trenches and of inspection chambers, catch pits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 95% Mod AASHTO density and disposal of surplus material on site

Descriptions of catchpits, junction boxes, manholes, etc:

Descriptions of catchpits, junction boxes, manholes, etc, shall be deemed to include for compaction, disposal of surplus excavated material to a dumping site located by the contractor, risk of collapse and keeping excavations free from water.

Density testing on filling:

Rates for filling, etc. shall include for all density and soil type testing to prove that the specified compaction is achieved. When additional testing is done on instruction of the Principal Agent and these tests are successful, they will be paid for additionally.

BULK SEWER RETICULATION

Heavy duty (Class 34) PVC-U sewer and drain pipes

97	110mm Pipes laid in and including trenches not exceeding 1m deep	m	25
98	110mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep	m	25

Extra over heavy duty (Class 34) PVC-U sewer and drain pipes for fittings

99	110mm Bend	No	5
100	160mm Bend	No	5
101	110mm Rodding eye	No	5
102	160 x 110mm Reducing junction	No	5

Carried to Collection

Section 4
Bill No. 1
External Works

R

PRE-CAST CONCRETE MANHOLES

Pre-cast concrete circular inspection chambers including pre-cast concrete cover slabs, covers and channels in benching

103	Manhole 1000mm diameter not exceeding 1m deep.	No	2
104	Manhole 1000mm diameter exceeding 1m and not exceeding 2m deep.	No	2

SUNDRIES

Earthworks

105	Selected granular filling Class 'B' supplied by the Contractor in bedding under pipes.	m3	4
106	Selected 19mm stone supplied by the Contractor in bedding under pipes.	m3	4
107	300 x 300 x 75mm Pre-cast concrete inspection eye marker slab set in ground.	No	5

Manhole covers

108	620mm dia Type 2A Heavy duty cast iron manhole to SABS 558	No	4
-----	--	----	---

Connection

109	Allow for connecting to Waste Water Treatment System (WWTS).	Item	
-----	--	------	--

Testing:

110	Testing drainage system.	Item	
-----	--------------------------	------	--

THE FOLLOWING IN ONE BRICK WALL (GARDEN WALL)

Excavation in earth not exceeding 2m deep:

111	Trenches.	m3	21
-----	-----------	----	----

Carried to Collection

R

Section 4
Bill No. 1
External Works

	<u>Extra over all excavations for carting away:</u>				
112	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	10		
	<u>Risk of collapse of excavations:</u>				
113	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	60		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>				
114	Backfilling to trenches, holes, etc.	m3	11		
	<u>Filling supplied by the contractor under strip footing</u>				
115	G7 Base course material compacted to 98% Mod AASHTO density	m3	5		
116	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	5		
	<u>Compaction of surfaces</u>				
117	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	60		
	<u>25 Mpa/19mm Concrete</u>				
118	Strip footings.	m3	5		
	<u>Test blocks:</u>				
119	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	2		
	<u>Reinforcement (Provisional)</u>				
120	High tensile steel reinforcement bars to structural concrete work.	t	0.25		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
121	One brick walls.	m2	23		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar :</u>				
122	One brick walls.	m2	15		
	<u>Brickwork reinforcement:</u>				
123	230mm Wide reinforcement built in horizontally.	m	44		
124	Ditto but in foundations.	m	265		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
125	One brickwall faced on both sides.	m2	28		
	<u>Brick-on-edge header course copings, sills, etc. of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
126	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	30		
	<u>STORMWATER CHANNELS</u>				
	<u>Excavation not exceeding 2m deep</u>				
127	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	52		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
128	Off site to a dumping site to be found by the Contractor.	m3	52		
	<u>Filling supplied by the contractor under channels</u>				
129	G7 Base course material compacted to 98% Mod AASHTO density	m3	26		
130	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	26		
	<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>				
131	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	372		
132	Extra for 700mm angle	No	35		
133	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	2		
	<u>Sundries:</u>				
134	Take material from the stockpiles on site and form earth berm, for stormwater control, size 1500m wide at base x 500mm high including compacting material in layers not exceeding 150mm thick.	m	90		
135	Excavate for and construct V-shaped earth drain 2000mm wide x average 300mm deep including setting aside excavated material in stock piles.	m	90		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

ACCESS RAMPS					
	<u>Excavation not exceeding 2m deep</u>				
136	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	5		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
137	Off site to a dumping site to be found by the Contractor.	m3	5		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
138	G7 Base course material compacted to 98% Mod AASHTO density	m3	2		
139	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	2		
	<u>Coarse river sand filling supplied by the contractor:</u>				
140	Under floors etc.	m3	1		
	<u>Compaction of surfaces:</u>				
141	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	15		
	<u>Prescribed density tests on filling:</u>				
142	In-situ dry density test.	No	1		
	<u>Reinforced 25Mpa/19mm Concrete:</u>				
143	Ramps, Landings, etc.	m3	1		
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
144	Surface beds, slabs, etc to falls and currents.	m2	15		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Test blocks:</u>				
145	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	1		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
146	12mm Joints not exceeding 300mm high.	m	4		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
147	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	4		
	<u>Fabric reinforcement:</u>				
148	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	15		
	<u>Waterproofing under Surface beds</u>				
149	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	15		
	<u>THE FOLLOWING IN RETAINING WALLS, ETC.</u>				
	<u>Excavation in earth not exceeding 2m deep</u>				
150	Trenches.	m3	41		
	<u>Risk of collapse of excavations:</u>				
151	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	116		
	<u>Keeping excavations free of water:</u>				
152	Keeping excavations free of all water other than subterranean water.		Item		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
153	Off site to a dumping site to be found by the Contractor.	m3	26		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Filling with approved clean, hard, dry decomposed dolerite filling supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod. AASHTO maximum density:</u>				
154	Behind walls with selected backfilling supplied by the Contractor compacted to 98% Mod ASSHTO density	m3	32		
	<u>Compaction of surfaces</u>				
155	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	116		
	<u>15Mpa/19mm unreinforced concrete</u>				
156	Surface blinding under footings and bases.	m3	2		
	<u>30Mpa/19mm reinforced concrete</u>				
157	Strip footings.	m3	16		
	<u>Test blocks:</u>				
158	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	2		
	<u>Fabric reinforcement:</u>				
159	REF. 395 fabric reinforcement in concrete infill, strip footings.	m2	58		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
160	330mm Thick cavity brick walls in two half brick skins.	m2	58		
	<u>Brickwork reinforcement:</u>				
161	230mm Wide reinforcement built in horizontally.	m	1 364		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>		
162	Extra over brickwork for face brickwork externally.	m2	27
	<u>Brick-on-edge header course copings, sills, etc. of "Rustgold FBS/Qunu Travertine" or equal Architect approved clay face brick size 222 x 106 x 73mm, pointed with recessed joints on all exposed faces:</u>		
163	330mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	58
	<u>Openings in Walls etc.</u>		
164	Leave or form 32mm weephole through one brick wall	No	116
	<u>Membranes</u>		
165	"Geofabric filter blanket wrapped around stone with 300mm side and 300mm end laps, including stitching.	m2	87
166	"Kaytech Wickdrain GPA 250" or other equal approved vertical drain set against back of retaining wall at approximately 2000mm centres.	m	29
	<u>Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:</u>		
167	19mm Stone.	m3	5
	<u>PVC Pipes</u>		
168	110mm Perforated drainage pipe laid as core in stone filling (elsewhere measured).	m	58
	<u>THE FOLLOWING IN RAINWATER TANKS AND STANDS</u>		
	<u>Excavation in earth not exceeding 2m deep:</u>		
169	Trenches.	m3	22

Carried to Collection

Section 4
Bill No. 1
External Works

R

	<u>Extra over all excavations for carting away:</u>				
170	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	12		
	<u>Risk of collapse of excavations:</u>				
171	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	64		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>				
172	Backfilling to trenches, holes, etc.	m3	11		
	<u>Filling supplied by the contractor under strip footing, floors etc.</u>				
173	G7 Base course material compacted to 98% Mod AASHTO density	m3	5		
174	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	5		
	<u>Compaction of surfaces</u>				
175	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	18		
	<u>25 MPa/19mm Concrete:</u>				
176	Concrete raft slab on waterproofing.	m3	9		
	<u>Test blocks:</u>				
177	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
	<u>Finishing top surfaces of concrete smooth with a steel trowel including adding additional cement while concrete is still green to attain a smooth, hard surface:</u>				
178	Surface beds, slabs, etc.	m2	18		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Rough Formwork to Sides:</u>				
179	Edges, risers, ends and reveals not exceeding 300mm high.	m	26		
	<u>Allens Meshco Square Mesh Fabric reinforcement:</u>				
180	Type 617 fabric reinforcement in concrete slabs.	m2	51		
	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
181	One brick walls.	m2	20		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>				
182	One brick walls.	m2	13		
	<u>Brickwork reinforcement:</u>				
183	230mm Wide reinforcement built in horizontally.	m	52		
184	Ditto but in foundations.	m	209		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2(Cement to be 42.5N all-purpose cement):</u>				
185	Extra over brickwork for face brickwork externally.	m2	18		
	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
186	230mm wide header course coping to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	26		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Plastic water tanks etc:</u>				
187	5000 Litre roto molded or equal approved plastic tank complete with lid, 15mm brass bibtap with handle suitable for locking and 4 No. galvanised stay wires 2.5m each long connected to tank, with and including 4 No. eye bolts cast into concrete.	No	6		
188	Hole top of tank for 100mm pipe.	No	6		
	<u>Fittings</u>				
189	PR 100 Hydraulic jump rainwater filter complete with non-return valve and chamber cover.	No	6		
190	Adaptor from 75mm diameter aluminium rainwater pipe to 100mm diameter inlet of PR 100 rainwater filter.	No	6		
191	Hole through side of tank for and including "Purain Seal-110" or other equal approved 110mm rubber seal.	No	6		
	<u>THE FOLLOWING IN SECURITY FENCING, ETC</u>				
	<u>Site clearance</u>				
192	Allow for clearing site for the width of 1 000 mm where fencing is to be erected including removing trees, shrubs etc. not exceeding 200 mm girth, grubbing up roots and roughly levelling.	m2	92		
	<u>Straining wires, fencing and razor wire:</u>				
193	Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured).	m	92		
194	3 Strands of galvanised barbed wire tied to standards, posts and eye bolts	m	92		
195	Fencing formed of 50 x 50 x 2.0mm diameter galvanised fencing 1 800mm high and fixed to each straining wire with 8 guage binding wire at 500mm centres including Y12 pegs at 900mm c/c between posts (straining wires elsewhere measured).	m	92		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Posts for 1 800mm high security fence:</u>				
196	60mm Diameter galvanised steel intermediate fencing post 1800mm long fitted with a pressed steel mushroom cap one end and 150 x 150 x 5 mm baseplate at bottom and embedded in and including 350 x 350 x 600 mm mass concrete (15 MPa) base.	No	31		
197	100mm Ditto as corner post, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last.	No	13		
198	150mm Ditto as gate post 1 800mm long, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last.	No	4		
199	12mm Diameter galvanised mild steel straining eye bolt with hook, threaded portion and two nuts and washers.	No	33		
200	Form 12mm diameter hole through fence post.	No	66		
	<u>Gates:</u>				
201	Security fence single gate, size 1 000 mm wide x 1 800 mm high, formed of 50 mm diameter nominal bore x 3,25 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and cross braces mullion and transome, scribed and welded into angles and at cross intersections, with two 50 mm diameter nominal bore x 3,25 mm wall thickness security posts each 600 mm long with one end welded to top rail of gate and closure plate to other end, the gate covered with 100 x 50 x 2,5 mm weld mesh with four straining wires as before described and with four 2,37 mm four point core diameter single "kampeon" wires with crimped droppers to security posts as before described; including three strands flat wrap razor barbed tape wire fixed as before described, leaf fitted with three 24 mm diameter x 300 mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost with and including 500 mm long approved chain spot welded to gate	No	2		
	<u>PADLOCKS</u>				
202	Supply 50 mm "Viro" Padlocks and Keys (or equal approved)	No	2		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Section 4

Bill No. 1

External Works

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

Carried Forward

R

Section 4

Bill No. 1

External Works

Section 4

Bill No. 1

External Works

COLLECTION

Brought Forward

Total Brought Forward from Page No.

**Page
No**

Amount

R

104

105

106

107

Carried to Final Summary

R

Section 4

Bill No. 1

External Works

Item No	Quantity	Rate	Amount
<u>SECTION 5</u>			
<u>BILL No. 1</u>			
<u>PROVISIONAL SUMS</u>			
<u>SUPPLEMENTARY PREAMBLES</u>			
Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.			
Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.			
<u>BUDGETARY ALLOWANCES</u>			
<u>The following budgetary allowances are for work to be executed at rates in the bills of quantities or to be agreed by the Principal agent:</u>			
<u>COMMUNITY LIAISON OFFICER</u>			
1			
Provide the sum of R58 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R6 500.00 a month for the duration (9 months)	Item		58 500.00
2			
Add: Mark-up		%	
<u>WASTE WATER TREATMENT SYSTEM</u>			
3			
Provide the sum of R 2 500 000.00 (Two Million Five Hundred Thousand Rand) for design and construction of on-site waste water treatment system as per specification provided.	Item		2 500 000.00
4			
Add: Profit		%	
Carried to Collection			R
Section 5			
Bill No. 1			
Provisional Sums			

[illegible]

Section 5

Bill No. 1

Provisional Sums

COLLECTION

Total Brought Forward from Page No.

**Page
No**

110

111

Amount

Carried to Final Summary

R

Section 5

Bill No. 1

Provisional Sums

**SIKHULULE PUBLIC SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Section No	FINAL SUMMARY	Page No		Amount
1	PRELIMINARIES	30		
2	DEMOLITIONS (PROVISIONAL)	34		
3	BUILDING WORKS	82		
4	EXTERNAL WORKS (PROVISIONAL)	109		
5	PROVISIONAL SUMS	112		
	SUB-TOTAL		R	
	<u>CONTINGENCY PROVISIONS</u>			
	Allow the Budgetary Provision of R 400 000.00 (Four Hundred Thousand Rand) for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the Contract Sum.	Item		400 000.00
	Sub Total		R	
	Add Value Added Tax at the rate of 15%		R	
	Carried to Form of Offer and Acceptance		R	