

Enquiries

Masekhu Makgopa

Tel: 013 752 9322

Email: Masekhu.makgopa@transnet.net

Dear Sir / Madam

TENDER NO: HOACMN-NPG-52428: TEST, REPAIR AND COMMISSION 132KV/3KV TRANSFORMERS AT VARIOUS 3KV DC SUBSTATIONS UNDER THE CONTROL OF NELSPRUIT DEPOT.

Further to the tender advertisement issued on 26 June 2025, please be advised of the following updates to the tender documentation and timelines:

1. Issuance of Addendum No. 1

- The enclosed Addendum No. 1 provides clarifications and amendments to the Works Information and Pricing Data.
- All tenderers are required to incorporate these changes in their submissions.

2. Extension of Tender Closing Date

- To allow sufficient time for consideration of this addendum, the closing date for submission of tenders is hereby extended as follows:
- **New Closing Date: 15 July 2025 at 10:00 AM**

3. Acknowledgment of Addendum

- Tenderers must submit the signed acknowledgment form provided below with their tender submission to confirm receipt and acceptance of this Addendum.

Please ensure that this notification and the attached Addendum No. 1 are included with your tender documentation.

Kindly acknowledge receipt of this letter and enclosures on the Form provided below.

Kind regards,



Ramokgethi Sigidane

Designation: Commodity Manager, SCM, Northeast Corridor

Transnet SOC Ltd trading as Transnet Rail Infrastructure Manager

Date: 07/07/2025

**TENDER NO: HOACMN-NPG-52428 TEST, REPAIR AND COMMISSION 132KV/3KV TRANSFORMERS AT
VARIOUS 3KV DC SUBSTATIONS UNDER THE CONTROL OF NELSPRUIT DEPOT**

ADDENDUM NO: 1 Date: 07 July 2025

1. Extension of Tender Closing Date

- To allow sufficient time for consideration of this addendum, the closing date for submission of tenders is hereby extended as follows:
- **New Closing Date: 15 July 2025 at 10:00 AM**

2. PART 2: PRICING DATA AND DELIVERY SCHEDULE (Pricing Schedule Changes)

PART 2: PRICING DATA (Refer to the attached Price Data)

Reason for the amendments

Bidders are hereby advised of the following amendment:

- The original pricing schedule had wrong wording and also the Locations changed due to no access to the service roads.
- These inconsistencies have been corrected to eliminate ambiguity and ensure that pricing submissions align with the correct scope of work.
- **The revised pricing schedule replaces the previous version and must be used when submitting pricing.**

Action Required:

- Please discard the previous pricing schedule and use the attached revised version when preparing your response.
- Ensure your submission reflects the updated pricing structure. Please complete and return the acknowledgment below **together with your bid submission**:

All other aspects of the bid document remain unchanged.

Acknowledgment of Receipt of Addendum No. 1 – Amendment to Pricing Schedule

Receipt of Addendum No. 1 dated 07 July 2025 is hereby acknowledged.

We, the undersigned, hereby acknowledge receipt of Addendum No 1. Dated 07 July 2025, and confirm that we have used the revised pricing schedule as issued in this addendum for the purposes of our bid submission HOACMN-NPG-52428 **TEST, REPAIR AND COMMISSION 132KV/3KV TRANSFORMERS AT VARIOUS 3KV DC SUBSTATIONS UNDER THE CONTROL OF NELSPRUIT DEPOT.**

Company Name: _____

Authorised Representative: _____

Signature: _____

Date: _____

NOTE: This acknowledgment must be signed and submitted along with your tender submission before the closing date and time.

PART 2: PRICING DATA

Test, Repair and commission 132kV/3kV Transformers at various 3kV DC Substations					
Item no.	Description	Unit	Qty	Unit Price	Total Price
A	Sycamore 3kV DC Substation				
1.1	Traction Transformer Repairs				
1.1.1	Drain the transformer oil for temporary storage (supply storage)	Litres	12 400		
1.1.2	Dismantle the transformer and perform a complete re-gasketing on the transformer	Sum	1		
1.1.3	Refill the transformer with the same old oil	Litres	12 400		
1.1.4	Oil purification	Sum	1		
1.1.5	Top up with transformer virgin oil 420L.	Litres	420		
1.1.6	Oil sampling and DGA pre and post purification	Sum	1		
1.1.7	Supply and install Buchholz Relay	Each	1		
1.1.8	Supply and install winding and oil temperature gauges	Each	2		
1.1.9	Supply and install breather with silica gel	Sum	1		
1.1.10	Clean and repaint the transformer grey and the conservator tank white	Sum	1		
1.1.11	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.1.12	Clean and repaint the transformer plinth red (signal red)	M2	7.5		
1.2	Auxiliary Transformer Repairs				
1.2.1	Drain the transformer oil for temporary storage (supply storage)	Litres	154		
1.2.2	Complete re-gasketing of the Auxiliary transformer	Sum	1		

1.2.3	Refill the transformer with the same old oil	Litres	154		
1.2.4	Oil purification	Sum	1		
1.2.5	Oil sampling and DGA pre and post purification	Sum	1		
1.2.6	Repaint the auxiliary transformer grey and the conservator tank white	Sum	1		
1.2.7	Supply and install Buchholz relay	Each	1		
1.2.8	Supply and install breather with silica gel	Sum	1		
1.2.9	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.2.10	Bioenvironmental soil & stones oil treatment on and around both the Traction and Auxiliary transformer slaps	M2	10		
1.2.11	Testing and commissioning	Sum	1		
	Total Price for A Sycamore (Excl. VAT) =				
B	Mayfern 3kV DC Substation				
1.1	Traction Transformer Repairs				
1.1.1	Drain the transformer oil for temporary storage (supply storage)	Litres	11 850		
1.1.2	Dismantle the transformer and perform a complete re-gasketing on the transformer	Sum	1		
1.1.3	Refill the transformer with the same old oil	Litres	11 850		
1.1.4	Oil purification	Sum	1		
1.1.5	Top up with transformer virgin oil 420L.	Litres	420		
1.1.6	Oil sampling and DGA pre and post purification	Sum	1		
1.1.7	Supply and install Buchholz Relay	Each	1		
1.1.8	Supply and install winding and oil temperature gauges	Each	2		
1.1.9	Supply and install breather with silica gel	Sum	1		

1.1.10	Clean and repaint the transformer grey and the conservator tank white	Sum	1		
1.1.11	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.1.12	Clean and repaint the transformer plinth red (signal red)	M2	7.5		
1.2	Auxiliary Transformer Repairs				
1.2.1	Drain the transformer oil for temporary storage (supply storage)	Litres	324		
1.2.2	Complete re-gasketing of the Auxiliary transformer	Sum	1		
1.2.3	Refill the transformer with the same old oil	litres	324		
1.2.4	Oil purification	Sum	1		
1.2.5	Oil sampling and DGA pre and post purification	Sum	1		
1.2.6	Repaint the auxiliary transformer grey and the conservator tank white	Each	1		
1.2.7	Supply and install Buchholz relay	Sum	1		
1.2.8	Supply and install breather with silica gel	Sum	1		
1.2.9	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.2.10	Bioenvironmental soil & stones oil treatment on and around both the Traction and Auxiliary transformer slaps	M2	10		
1.2.11	Testing and commissioning	Sum	1		
	Total Price for B Mayfern (Excl. VAT) =				
C	Rivulets 3kV DC Substation				
1.1	Traction Transformer Repairs				
1.1.1	Drain the transformer oil for temporary storage (supply storage)	Litres	11 850		
1.1.2	Dismantle the transformer and perform a complete re-gasketing on the transformer	Sum	1		
1.1.3	Refill the transformer with the same old oil	Litres	11 850		

1.1.4	Oil purification	Sum	1		
1.1.5	Top up with transformer virgin oil 420L.	Litres	420		
1.1.6	Oil sampling and DGA pre and post purification	Sum	1		
1.1.7	Supply and install Buchholz Relay	Each	1		
1.1.8	Supply and install winding and oil temperature gauges	Each	2		
1.1.9	Supply and install breather with silica gel	Sum	1		
1.1.10	Clean and repaint the transformer grey and the conservator tank white	Sum	1		
1.1.11	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.1.12	Clean and repaint the transformer plinth red (signal red)	M2	7.5		
1.2	Auxiliary Transformer Repairs				
1.2.1	Drain the transformer oil for temporary storage (supply storage)	Litres	324		
1.2.2	Complete re-gasketing of the Auxiliary transformer	Sum	1		
1.2.3	Refill the transformer with the same old oil	litres	324		
1.2.4	Oil purification	Sum	1		
1.2.5	Oil sampling and DGA pre and post purification	Sum	1		
1.2.6	Repaint the auxiliary transformer grey and the conservator tank white	Sum	1		
1.2.7	Supply and install Buchholz relay	Sum	1		
1.2.8	Supply and install breather with silica gel	Sum	1		
1.2.9	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.2.10	Bioenvironmental soil & stones oil treatment on and around both the Traction and Auxiliary transformer slaps	M2	10		

1.2.11	Testing and commissioning	Sum	1		
	Total Price for C Rivulets (Excl. VAT) =				
D	Droogland 3kV DC Substation				
1.1	Traction Transformer Repairs				
1.1.1	Drain the transformer oil for temporary storage (supply storage)	Litres	16 183		
1.1.2	Dismantle the transformer and perform a complete re-gasketing on the transformer	Sum	1		
1.1.3	Refill the transformer with the same old oil	Litres	16 183		
1.1.4	Oil purification	Sum	1		
1.1.5	Top up with transformer virgin oil 420L.	Litres	420		
1.1.6	Oil sampling and DGA pre and post purification	Sum	1		
1.1.7	Supply and install Buchholz Relay	Each	1		
1.1.8	Supply and install winding and oil temperature gauges	Each	2		
1.1.9	Supply and install breather with silica gel	sum	1		
1.1.10	Clean and repaint the transformer grey and the conservator tank white	Sum	1		
1.1.11	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.1.12	Clean and repaint the transformer plinth red (signal red)	M2	7.5		
1.2	Auxiliary Transformer Repairs				
1.2.1	Drain the transformer oil for temporary storage (supply storage)	Litres	333		
1.2.2	Complete re-gasketing of the Auxiliary transformer	Sum	1		
1.2.3	Refill the transformer with the same old oil	Litres	333		
1.2.4	Oil purification	Sum	1		
1.2.5	Oil sampling and DGA pre and post purification	Sum	1		

1.2.6	Repaint the auxiliary transformer grey and the conservator tank white	Each	1		
1.2.7	Supply and install Buchholz relay	Sum	1		
1.2.8	Supply and install breather with silica gel	Sum	1		
1.2.9	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.2.10	Bioenvironmental soil & stones oil treatment on and around both the Traction and Auxiliary transformer slaps	M2	10		
1.2.11	Testing and commissioning	Sum	1		
D	Total Price for D Droogland (Excl. VAT) =				
E	Tenbosch 3kV DC Substation				
1.1	Traction Transformer Repairs				
1.1.1	Drain the transformer oil for temporary storage (supply storage)	Litres	11 850		
1.1.2	Dismantle the transformer and perform a complete re-gasketing on the transformer	Sum	1		
1.1.3	Refill the transformer with the same old oil	Litres	11 850		
1.1.4	Oil purification	Sum	1		
1.1.5	Top up with transformer virgin oil 420L.	Litres	420		
1.1.6	Oil sampling and DGA pre and post purification	Sum	1		
1.1.7	Supply and install Buchholz Relay	Each	1		
1.1.8	Supply and install winding and oil temperature gauges	Each	2		
1.1.9	Supply and install breather with silica gel	Sum	1		
1.1.10	Clean and repaint the transformer grey and the conservator tank white	Sum	1		
1.1.11	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.1.12	Clean and repaint the transformer plinth red (signal red)	M2	7.5		

1.2	Auxiliary Transformer Repairs				
1.2.1	Drain the transformer oil for temporary storage (supply storage)	Litres	324		
1.2.2	Complete re-gasketing of the Auxiliary transformer	Sum	1		
1.2.3	Refill the transformer with the same old oil	Litres	324		
1.2.4	Oil purification	Sum	1		
1.2.5	Oil sampling and DGA pre and post purification	Sum	1		
1.2.6	Repaint the auxiliary transformer grey and the conservator tank white	Each	1		
1.2.7	Supply and install Buchholz relay	Sum	1		
1.2.8	Supply and install breather with silica gel	Sum	1		
1.2.9	Replace oil gauge (side glass) on the conservator tank	Each	1		
1.2.10	Bioenvironmental soil & stones oil treatment on and around both the Traction and Auxiliary transformer slaps	M2	10		
1.2.11	Testing and commissioning	Sum	1		
	Total Price for E Tenbosch (Excl. VAT) =				
F	Boulders 3kV DC Substation				
1.1	Supply and install Traction transformer bushings	Each	3		
1.2	Supply and install Buchholz relay	Each	1		
1.3	Testing and commissioning	Sum	1		
	Total Price for F Boulders (Excl. VAT) =				
G	Malelane 3kV DC Substation				
1.1	Supply and install Traction transformer bushings	Each	3		
1.2	Supply and install Buchholz relay	Each	1		

1.3	Testing and commissioning	Sum	1		
	Total Price for G Malelane (Excl. VAT) =				
	General				
H	Preliminaries & General	Sum	1		
	Total Price for H Preliminaries & general (Excl. VAT) =				
	Total Price (A+B+C+D+E +F+G+H) Excl. VAT				
	VAT @ 15%				
	Total Price Incl. VAT				

Company Name: _____

Authorised Representative: _____

Signature: _____

Date: _____

Company Stamp (if available)