

Scope of Work

Fibre Repairs between STP and Sentech Tower (Randburg, Hill Street)

1. Installation of 96 Core Blown fibre (UG) cable SM. Fibre to be collected at STP. Cable length will be determined during the site survey.
2. Removal of the damaged fibre.
3. Supply of two dome joints
4. Minor trenching services to expose the 4-way duct on both sides of the road.
5. Fibre splicing services.
6. OTDR tests.

A site survey will be required to define the full scope of work to the suppliers.

We propose scheduling the site briefing on **15 October 2024** at 10h00.

Location: -26.091934, 27.987670

Hill Street and Long Ave, Ferndale Randburg