CONTRACT 48Q/2026/27

REHABILITATION OF SWARTKLIP ROAD BETWEEN SPINE ROAD AND JAPHTA K MASEMOLA ROAD
SCHEDULE B: ROADWORKS

SECTION 5.5

Item	Description	Unit			Amount
C5.5	**RECONSTRUCTION OF PAVEMENT LAYERS**				
C5.5.1	**Compiling and implementing M&U plans for the reconstruction of an existing road pavement**	number (No.)	1.00		-
C5.5.5	**Construction of a trial section using a recycler**	cubic metre (m³)	200.00		-
C5.5.15	**In-situ reconstruction of a pavement layer using a recycler to construct a stabilised subbase layer**				
C5.5.15.1	Chemically stabilised subbase layer compacted to 100% of MDD:				
	(b) Using cemented material compacted to 200mm thick	cubic metre (m³)	10,884.00		-
C5.5.20	**Material shortfall or make-up material**				
C5.5.20.2	For subbase layer	cubic metre (m³)	10,718.00		-
Total Carried Forward To Summary					-