

INDEX TO BILL OF QUANTITIES**SECTION 1 PRELIMINARY AND GENERAL ITEMS**

PART 0102	C1.2 GENERAL REQUIREMENTS AND PROVISIONS
PART 0103	C1.3 CONTRACTOR'S SITE ESTABLISHMENT AND
PART 0104	C1.4 FACILITIES FOR THE ENGINEER
PART 0105	C1.5 ACCOMMODATION OF TRAFFIC

SECTION 2 SITE CLEARANCE

PART 0106	C1.6 CLEARING AND GRUBBING
PART 0107	C1.7 LOADING AND HAULING

SECTION 3 SERVICES

PART 0201	C2.1 GEN REQMENTS AND TRENCHING SERVICE
PART 0204	C2.4 ENERGY AND OTHER SERVICES
PART 023B	C2.3B WET SERVICES - WATER MAINS

SECTION 4 DRAINAGE

PART 0302	C3.2 CULVERTS
PART 0303	C3.3 CONCRETE KERBING AND CHANNELING
PART 1206	C12.6 MECH STABILISED FILL AND GABIONS

SECTION 5 EARTHWORKS

PART 0402	C4.2 CUT MATERIALS
PART 0403	C4.3 EXISTING ROAD MATERIALS
PART 0404	C4.4 COMMERCIAL MATERIALS
PART 0502	C5.2 FILL

SECTION 6 LAYERWORKS

PART 0404	C4.4 COMMERCIAL MATERIALS
PART 0501	C5.1 ROADBED
PART 0503	C5.3 ROAD PAVEMENT LAYERS
PART 0901	C9.1 ASPHALT LAYERS
PART 1203	C12.3 GROUND IMPROVEMENT

SECTION 7 ANCILLARY ROAD WORKS

PART	1104	C11.4 ROAD RESTRAINT SYSTEMS
PART	1105	C11.5 FENCING
PART	1106	C11.6 ROAD SIGNS
PART	1107	C11.7 ROAD MARKINGS AND ROAD STUDS
PART	1108	C11.8 LANDSCAPING AND PLANTING PLANTS
PART	1109	C11.9 FINISHING ROAD AND ROAD RESERVE

SECTION 8 RETAINING WALLS

PART	1206	C12.6 MECH STABILISED FILL AND GABIONS
-------------	-------------	---

BILL OF QUANTITIES**SECTION 1 PRELIMINARY AND GENERAL ITEMS****PART 0102 C1.2 GENERAL REQUIREMENTS AND PROVISIONS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Environmental Management</u>				
1	C1.2.1.1 PS.C1.2.1.1	Monitoring of compliance with and reporting on the EMP	months	4		
2	C1.2.1.2 PS.C1.2.1.2	Dedicated environmental officer	months	4		
		<u>Programming and Reporting</u>				
3	C1.2.2.3 PS.1.1 PS.C1.2.2.3	Submission of a Scheme 2 Initial Programme	Lump sum	1		
4	C1.2.2.4 PS.C1.2.2.3	Submission of a Scheme 2 Full Programme	Lump sum	1		
5	C1.2.2.5 PS.C1.2.2.5	Reviewing and updating a Scheme 2 programme every month	months	4		
		<u>Other Documentation</u>				
6	C1.2.2.6	Preparation and submission of all information and reports specified in the Contract Documentation, including reporting on local labour	months	4		
		<u>Routine road maintenance of existing public roads within the Site of the Works or other public roads outside the Site of the Works which are used as detours</u>				
7	C1.2.3.1	Grass cutting	ha	0.4		
8	C1.2.3.4	Collection of rubbish / litter	km	0.5		
		<u>Stakeholder Management & Liaison</u>				
9	C1.2.4 PS.24	Stakeholder Management and Liaison	months	4		
		<u>Health and Safety</u>				
10	C1.2.5.1 PS.10	Health and safety plan	Lump sum	1		
11	C1.2.5.2 PS.10	Implementation of health and safety plan	months	4		
12	C1.2.6.1	Work adjacent to properties: Survey of adjacent properties	no	15		
13	C1.2.6.2	Preventive and/or mitigation measures	PC Sum	25000	1.00	25 000.00
14	C1.2.6.3	Handling cost, profit and all other charges in respect of item C1.2.6.2	%	25000		
		<u>Community Liaison Officer</u>				
15	PS.25	Allow for CLO to be appointed	PC Sum	100000	1.00	100 000.00

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07 OUTER WEST

Part Continued **PART 0102 C1.2 GENERAL REQUIREMENTS AND PROVISIONS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
16	PS.25	Handling costs and profit in respect of PS.25	%	100000		
		<u>Additional Security</u>				
17	PS.11	Provision of security on site to guard against any disruption of the works throughout the duration of the contract	months	4		

TOTAL CARRIED TO SECTION 1 SUMMARY: PRELIMINARY AND GENERAL ITEMS

R

PART 0103 C1.3 CONTRACTOR'S SITE ESTABLISHMENT AND

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>The Contractor's General Obligations</u>				
1	C1.3.1.1 PS.C1.3.1	Fixed obligations	Lump sum	1		
2	C1.3.1.2 PS.C1.3.1	Value-related obligations	Lump sum	1		
3	C1.3.1.3 PS.C1.3.1	Time-related obligations	months	4		
4	C1.3.2 PS.C1.3.2	Contract sign boards (as per drawing)	no.	1		
5	PS.17	Submission of As-Built Data	sum	1		

TOTAL CARRIED TO SECTION 1 SUMMARY: PRELIMINARY AND GENERAL ITEMS

R

PART 0104 C1.4 FACILITIES FOR THE ENGINEER

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Services at Site Offices, Laboratories and Site Accommodation</u>				
1	PS.19	Allowance for Progress Photographs every month, digital and aerial	PC Sum	40000	1.00	40 000.00
2	PS.19	Handling costs and profit in respect of item above	%	40000		
3	PS.21	Allowance for the additional survey required by the Engineer	PC Sum	40000	1.00	40 000.00
4	PS.21	Handling costs in respect of item above	%	40000		
5	PS.23	Allowance for Laboratory Acceptance testing as required by the Engineer	PC Sum	40000	1.00	40 000.00
6	PS.23	Handling costs in respect of item above	%	40000		

TOTAL CARRIED TO SECTION 1 SUMMARY: PRELIMINARY AND GENERAL ITEMS

R

PART 0105 C1.5 ACCOMMODATION OF TRAFFIC

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C1.5.1.1 PS.1.3	Accommodation of pedestrian and non-motorised traffic	months	4		

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

Part Continued **PART** 0105 C1.5 ACCOMMODATION OF TRAFFIC

Item	Clause	Description	Unit	Quantity	Rate	Amount
2	C1.5.2	Accommodation of vehicular traffic	months	4		
		<u>Temporary Traffic Control Facilities</u>				
3	C1.5.7.1(a)	Delineators including mounting bases and ballast: Single sided, reversible left or right (1200mm x 250mm)	no	15		
4	C1.5.7.1(b)	Delineators including mounting bases and ballast: Double sided, reversible left or right (1200mm x 250mm)	no	15		
5	C1.5.7.3	Flagmen	man-day	176		
6	C1.5.7.4	Traffic controllers	man-day	88		
7	C1.5.7.5 (c)	(c)Illuminated road sign – R & TR series (900mm)	no	16		
8	C1.5.8 PS.1.3.4	Traffic safety officer	months	4		
9	C1.5.7.2	Traffic cones, minimum height 750 mm	no	15		
		<u>Provision of Safety Equipment for Visitors</u>				
10	C1.5.11.1	Provision of reflective safety vests for visitors	no	7		
11	C1.5.11.2	Provision of hard hats for visitors	no	7		
12	C1.5.7.9	Cleaning of traffic control facilities	months	4		

TOTAL CARRIED TO SECTION 1 SUMMARY: PRELIMINARY AND GENERAL ITEMS

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 1 PRELIMINARY AND GENERAL ITEMS**

PART 0102	C1.2 GENERAL REQUIREMENTS AND PROVISIONS	
PART 0103	C1.3 CONTRACTOR'S SITE ESTABLISHMENT AND	
PART 0104	C1.4 FACILITIES FOR THE ENGINEER	
PART 0105	C1.5 ACCOMMODATION OF TRAFFIC	
TOTAL CARRIED TO FINAL SUMMARY		

SECTION 2 SITE CLEARANCE**PART 0106 C1.6 CLEARING AND GRUBBING**

Item	Clause	Description	Unit	Quantity	Rate	Amount
		Clearing				
1	C1.6.1.1	Clearing with machines and some hand labour where necessary	ha	0.3		
2	C1.6.1.2	Clearing with hand labour only when labour enhanced work is specified	ha	0.1		
		Grubbing				
3	C1.6.2.1	Grubbing with machines and some hand labour where necessary	ha	0.35		
4	C1.6.2.2	Grubbing with hand labour when labour enhancement work is specified or it is not practical to use a machine	ha	0.1		
5	C1.6.2.4	Grubbing by hand for service trenches (over the agreed width required)	m2	200		

TOTAL CARRIED TO SECTION 2 SUMMARY: SITE CLEARANCE

R

PART 0107 C1.7 LOADING AND HAULING

Item	Clause	Description	Unit	Quantity	Rate	Amount
		Loading				
1	C1.7.1.1	Loading from stockpile using machines and some hand labour where necessary	m3	1225		
		Hauling material for use in the Works				
2	C1.7.2.1(a)	Hauling material for use in the Works and off-loading it on the site of the Works: (a) Soil, gravel, crushed stone and pavement layer material	m3 * km	50		
		Hauling material to spoil				
3	C1.7.2.2(a) PS.C1.7.2.2	Hauling material to spoil in sites designated by the Contractor: (a) Cleared and grubbed material (organic matter and all other unsuitable or waste material)	m3	100		
4	C1.7.2.2(b) PS.C1.7.2.2	Hauling material to spoil in sites designated by the Contractor: (b) Soil and gravel material	m3	1000		
5	C1.7.2.2(c) PS.C1.7.2.2	Hauling material to spoil in sites designated by the Contractor: (c) Boulders and hard material	m3	25		

TOTAL CARRIED TO SECTION 2 SUMMARY: SITE CLEARANCE

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 2 SITE CLEARANCE**

PART	0106	C1.6 CLEARING AND GRUBBING	
PART	0107	C1.7 LOADING AND HAULING	
TOTAL CARRIED TO FINAL SUMMARY			

SECTION 3 SERVICES**PART 0201 C2.1 GEN REQMENTS AND TRENCHING SERVICE**

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Location, Identification, Protection and Relocation of Existing Services</u>				
1	C2.1.1.1	Contractor's obligation	Lump sum	1		
		<u>Relocation of Services by Others:</u>				
		<u>Water</u>				
2	C2.1.1.2 PS.3	Permanent services relocation or protection work by others: Water	PC Sum	50000	1.00	50 000.00
3	C2.1.1.3 PS.3	Handling costs and profit in respect of item C2.1.1.2 above	%	50000		
		<u>Electricity</u>				
4	C2.1.1.2 PS.6	Permanent services relocation or protection work by others: Electricity	PC Sum	50000	1.00	50 000.00
5	C2.1.1.3 PS.6	Handling costs and profit in respect of item C2.1.1.2 above	%	50000		
		<u>Proving By Hand</u>				
6	C2.1.2.5 PS.2.2	Using hand excavation to locate, expose and verify services, Depth of 0.0m to 1.5m. (Prov)	m3	20		
7	C2.1.2.5 PS.2.2	Using hand excavation to locate, expose and verify services, Depth of 1.5m to 2.0m (Prov)	m3	10		
		<u>Cable Ducts</u>				
8	C2.1.6.1(a) PS.C2.1.6	Trench excavation (in soft material): Trenches up to 1,0 m wide (a) Up to 1,0 m deep	m3	20		
9	C2.1.7.1	Extra over item for excavating in hard material irrespective of depth	m3	5		
10	C2.1.11.1(a) PS.C2.1.6	Backfilling of trenches: Backfill compacted to 93 % (100 % for sand) of MDD (areas subject to traffic loads) using material: (a) From the excavated trench material	m3	20		
11	C2.1.11.1(b) PS.C2.1.6	Backfilling of trenches: Backfill compacted to 93 % (100 % for sand) of MDD (areas subject to traffic loads) using material: (b) From other excavations on Site	m3	10		

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07 OUTER WEST

Part Continued **PART** 0201 C2.1 GEN REQMENTS AND TRENCHING SERVICE

Item	Clause	Description	Unit	Quantity	Rate	Amount
12	C2.1.11.1(d) PS.C2.1.6	Backfilling of trenches: Backfill compacted to 93 % (100 % for sand) of MDD (areas subject to traffic loads) using material: (d) From sources provided by the Contractor	m3	30		
13	C2.1.14.2	Extra over items C2.1.11, C2.1.12 and C2.1.13 for additional compaction of backfill: Compaction increased from 93 % of MDD to 95 % of MDD	m3	10		
14	C2.1.17.2	Removal and disposal of spoil material from trench excavations: To spoil sites or dumping areas provided by the Contractor	m3	10		
15	C2.1.19.1	Dealing with surface water	Lump sum	1		
16	C2.1.19.2	Dealing with subsurface water	Lump sum	1		

TOTAL CARRIED TO SECTION 3 SUMMARY: SERVICES

R

PART 0204 C2.4 ENERGY AND OTHER SERVICES

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	PS.6.2	Street lighting	PC Sum	50000	1.00	50 000.00
2	PS.20	Handling costs and profit in respect of Street lighting	%	50000		

TOTAL CARRIED TO SECTION 3 SUMMARY: SERVICES

R

PART 023B C2.3B WET SERVICES - WATER MAINS

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Supply and lay water main ducts</u>				
1	C2.3.21.1(a)	U-PVC, type N450, with push fit couplings: (a) 160 mm diameter	m	200		
		<u>Bedding for Ducts</u>				
2	C2.3.29.1(a)	Bedding for ducts compacted to 93 % of MDD (100 % for sand) using material: Selected from the excavated trench material	m3	10		
3	C2.3.29.1(e)	Bedding for ducts compacted to 93 % of MDD (100 % for sand) (e) From commercial sources	m3	5		
		<u>Concrete for bedding and encasement for ducts</u>				
4	C2.3.30.1	Concrete for bedding (Class 20/26)	m3	5		

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

Part Continued **PART** 023B C2.3B WET SERVICES - WATER MAINS

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Duct accessories :</u>				
5	C2.3.33.6(a)	(a) Duct Markers (230 x 250 x 50)	no	7		
6		(b) Draw Wires	m	250		
7		© End cap or plugs (U-PVC for 160mm Dia)	no	5		

TOTAL CARRIED TO SECTION 3 SUMMARY: SERVICES

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 3 SERVICES**

PART	0201	C2.1 GEN REQMENTS AND TRENCHING SERVICE	
PART	0204	C2.4 ENERGY AND OTHER SERVICES	
PART	023B	C2.3B WET SERVICES - WATER MAINS	
TOTAL CARRIED TO FINAL SUMMARY			

SECTION 4 DRAINAGE**PART 0302 C3.2 CULVERTS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Excavation:</u> <u>Pipes</u>				
1	C3.2.1.1(a) PS.C2.1.6 PS.C3.2.1.1	Excavation for culvert structures for pipes: in all material situated within the following depth ranges below the surface level: (a) 0 m to 1,5 m	m3	40		
2	C3.2.1.1(b) PS.C2.1.6 PS.C3.2.1.1	Excavation for culvert structures for pipes: in all material situated within the following depth ranges below the surface level: (b) Exceeding 1,5 m and up to 3,0 m	m3	30		
3	C3.2.1.4 PS.C2.1.6	Extra over sub-item C3.2.1.1 for excavation in hard or boulder material,irrespective of depth	m3	5		
		<u>Backfilling:</u> <u>Pipes</u>				
4	C3.2.2.1	Backfilling: Using the excavated material	m3	30		
5	C3.2.2.2(a)	Backfilling: Using imported selected material: (a) From commercial sources (Using granular material)	m3	30		
6	C3.2.3.3 PS.C3.2.3.2	Concrete pipe culverts, Spigot and Socket: On Class C bedding (450mm diameter concrete Class 100D)	m	40		
		<u>Excavation:</u> <u>Manholes, Inlets and Headwalls</u>				
7	C3.2.1.1(a) PS.C2.1.6	Excavation for culvert structures for Manholes Inlets and Headwalls: in all material situated within the following depth ranges below the surface level: (a) 0 m to 1,5 m	m3	25		
8	C3.2.1.1(b) PS.C2.1.6	Excavation for culvert structures for Manholes Inlets and Headwalls: in all material situated within the following depth ranges below the surface level: (b) Exceeding 1,5 m and up to 3,0 m	m3	10		
9	C3.2.1.4 PS.C2.1.6	Extra over sub-item C3.2.1.1(b) for excavation in hard or boulder material,irrespective of depth	m3	5		
		<u>Backfilling:</u> <u>Manholes, Inlets and Headwalls</u>				
10	C3.2.2.1	Backfilling: Using the excavated material	m3	5		

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

Part Continued **PART** 0302 C3.2 CULVERTS

Item	Clause	Description	Unit	Quantity	Rate	Amount
11	C3.2.2.2(a)	Backfilling: Using imported selected material: (a) From commercial sources <u>Headwalls</u>	m3	5		
12	PS.C3.2.9	Inlets and outlets to culverts: Headwalls, Type A, for 450mm pipes <u>Manholes and Inlets</u>	no	1		
13	PS.C3.2.15.2	Manhole: Type A with a heavy duty concrete cover; Depth: Exceeding 0,0m and up to 1,5m	no	2		
14	PS.C3.2.15.2 PS.C3.2.15.2	Manhole: Type A with a heavy duty concrete cover; Depth: Exceeding 1,5m and up to 2,0m	no	1		
15	PS.C3.2.15.2	Inlet: Type D3, heavy duty concrete cover; Depth: Exceeding 0,0m and up to 1,5m <u>Compaction</u>	no	1		
16	C3.2.24.1	Compaction of bedding for inlets, outlets, manholes and catchpits: Preparation and compaction of in situ bedding material to 90 % of MDD (depth 150mm)	m3	5		
17	C1.7.2.2(a) PS.C1.7.2.2	Hauling material to spoil and off-loading it at a designated spoil area: (a) Soil and gravel material <u>Driveways</u>	m3	5		
18	PS..26	Construction of affected driveways to original or better conditions. (Rate is to include excavation, preparation of subbase, provision and compaction of granular base material, supply of all materials, shiuttering, formwork, expansion joints, reinforcing Mesh REF 193 and weedkiller) The driveway is to be constructed with a 100mm thick x 3.0m wide concrete pavement with a 150mm - 250mm concrete lip above the final road level ege to cater for stormwate drainage.	no	10		

TOTAL CARRIED TO SECTION 4 SUMMARY: DRAINAGE

R

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07 OUTER WEST

PART 0303 C3.3 CONCRETE KERBING AND CHANNELING

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C3.3.2.1, PS.C3.3.2.1	Prefabricated kerbing, cast in-situ channeling: Type F Mountable Kerb, Fig. 6, with 150mm channel, Drawing 38577	m	390		
2	C3.3.3.1, PS.C3.3.2.1	Extra over item 1 for concrete kerbing and channeling on curves of radii more than or equal to 2,0 m but less than 25 m	m	20		
3	C3.3.3.1	Extra over items 1 for concrete kerbing or concrete kerbing and channeling on curves of radii more than or equal to 40,0 m but less than 200 m	m	25		
4	C3.3.4	Extra over item C3.3.2 for drop kerbs and channel / Fillet at pedestrian crossings and driveways (Drawing 38579)	m	15		
		<u>Sidewalk Edge Restraint</u>				
5	C3.3.2.1, PS.C3.3.2.1	Prefabricated kerbing (edge restraint, Figure 12 kerb including 100mm x 100mm haunching)	m	430		
		<u>Scoops</u>				
6	C13.4.11	Cast in situ concrete for Pedestrian / Vehicular Scoop (Grade 20/13)	m ³	10		
7	C3.3.6.2	Cast in situ concrete chutes (v drains - 1.5m wide x 200mm deep as per drawing). Item to include formation, backfill and compaction. Concrete reinforced and formwork.	m	10		

TOTAL CARRIED TO SECTION 4 SUMMARY: DRAINAGE

R

PART 1206 C12.6 MECH STABILISED FILL AND GABIONS

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Reno Mattress and Gabions for Headwalls</u>				
1	C12.6.14.1(a)	Foundation trench excavation: Excavating all material for gabions and reno mattress situated within the following depth ranges (a) 0 m to 1,5 m	m ³	40		
2	C12.6.14.1(b)	Foundation trench excavation: Excavating all material for gabions and reno mattress situated within the following depth ranges (b) Exceeding 1,5 m and up to 3,0 m	m ³	5		
3	C12.6.15	Surface preparation for bedding the reno mattress	m ²	90		
4	C12.6.16.2	Reno mattress: PVC coated gabion boxes (2.0m x 1.0m x 0.3m)	m ³	25		

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

Part Continued **PART** 1206 C12.6 MECH STABILISED FILL AND GABIONS

Item	Clause	Description	Unit	Quantity	Rate	Amount
5	C12.6.17, PS.C12.6.17	Geotextile (Filtertation and separation for use with reno mattress, min Grade 7)	m2	110		

TOTAL CARRIED TO SECTION 4 SUMMARY: DRAINAGE

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 4 DRAINAGE**

PART 0302	C3.2 CULVERTS	
PART 0303	C3.3 CONCRETE KERBING AND CHANNELING	
PART 1206	C12.6 MECH STABILISED FILL AND GABIONS	
TOTAL CARRIED TO FINAL SUMMARY		

SECTION 5 EARTHWORKS**PART 0402 C4.2 CUT MATERIALS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
Excavation to Stockpile or Fill						
1	C4.2.3.1 PS.C4.2	Excavating of materials in cuttings for use in the works, material obtained from: Soft excavation	m3	250		
2	C4.2.3.4 PS.C4.2	Excavating of materials in cuttings for use in the works, material obtained from: Hard excavation (other than by blasting)	m3	50		
3	C4.2.4.1 PS.C4.2	Excavating of materials in box cuts for use in the works, material obtained from: Soft excavation	m3	200		
4	C4.2.4.4 PS.C4.2	Excavating of materials in box cuts for use in the works, material obtained from: Hard excavation (other than by blasting)	m3	40		
5	C1.7.2.2(b) PS.C1.7.2.2	Hauling material to spoil in sites designated by the Contractor: (b) Soil and gravel material	m3	700		
6	C1.7.2.2(c) PS.C1.7.2.2	Hauling material to spoil in sites designated by the Contractor: (c) Boulders and hard material	m3	200		
7	C1.7.2.1(a)	Hauling material for use in the Works and off-loading it on the site of the Works: (a) Soil, gravel, crushed stone and pavement layer material	m3 * km	100		
8	C1.7.1.1	Loading from stockpile using machines and some hand labour where necessary	m3	240		
Excavation to Spoil						
9	C4.2.9.1 PS.C4.2	Excavate material to spoil in sites designated by the Contractor, material obtained from: Soft excavation, overburden and unsuitable material	m3	50		
Finishing of Banks						
10	C4.2.12.1(a)	Finishing the side slopes of Cuttings: (a) In soft material	m2	575		
TOTAL CARRIED TO SECTION 5 SUMMARY: EARTHWORKS					R	

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

PART 0403 C4.3 EXISTING ROAD MATERIALS

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C4.3.4.1(a)	<u>Saw-cut</u> Saw-cutting existing materials within the following average depth ranges: Asphalt: (a) Up to 50 mm	m	20		
2	C4.3.9.2 PS.C4.2	Excavating material by using conventional road construction equipment to stockpile: Crushed stone and macadam materials	m3	5		

TOTAL CARRIED TO SECTION 5 SUMMARY: EARTHWORKS

R

PART 0404 C4.4 COMMERCIAL MATERIALS

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C4.4.2.1(g)	<u>Import Fill Material</u> Commercial materials identified by the Contractor from commercial, private or other non-commercial suppliers: Pavement layer material: Type G7	m3	60		

TOTAL CARRIED TO SECTION 5 SUMMARY: EARTHWORKS

R

PART 0502 C5.2 FILL

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C5.2.2.1(a)	<u>Processing and Compaction</u> Fill construction: Normal fill material (G7) in compacted layer thicknesses of 200 mm and less: (a) Compacted to 95 % of MDD	m3	60		
2	C5.2.3	Side-cut to fill compacted to 93 % of MDD in compacted layer thicknesses of 200 mm and less	m3	25		
3	C5.2.11.1	Finishing-off fill slopes	m2	480		

TOTAL CARRIED TO SECTION 5 SUMMARY: EARTHWORKS

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 5 EARTHWORKS**

PART	0402	C4.2 CUT MATERIALS	
PART	0403	C4.3 EXISTING ROAD MATERIALS	
PART	0404	C4.4 COMMERCIAL MATERIALS	
PART	0502	C5.2 FILL	
TOTAL CARRIED TO FINAL SUMMARY			

SECTION 6 LAYERWORKS**PART 0404 C4.4 COMMERCIAL MATERIALS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Import Layerworks</u>				
1	C4.4.2.1(b)	Commercial materials identified by the Contractor from commercial, private or other non-commercial suppliers: Pavement layer material: Type G2	m3	315		
2	C4.4.2.1(f)	Commercial materials identified by the Contractor from commercial, private or other non-commercial suppliers: Pavement layer material: Type G5	m3	330		
3	C4.4.2.1(g)	Commercial materials identified by the Contractor from commercial, private or other non-commercial suppliers: Pavement layer material: Type G7	m3	40		

TOTAL CARRIED TO SECTION 6 SUMMARY: LAYERWORKS

R

PART 0501 C5.1 ROADBED

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C5.1.1.2	Roadbed construction and compaction to 95 % of MDD	m3	320		
		<u>Removal of Unsuitable (Undercut)</u>				
2	C5.1.4.1(a)	Removal of unsuitable material to spoil: In layer thicknesses of 200 mm and less (a) Stable material	m3	30		
3	C5.1.4.2(a)	Removal of unsuitable material to spoil: In layer thicknesses exceeding 200 mm (a) Stable material	m3	25		

TOTAL CARRIED TO SECTION 6 SUMMARY: LAYERWORKS

R

PART 0503 C5.3 ROAD PAVEMENT LAYERS

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C5.3.1	Compiling and implementing M&U plans for the construction of all the pavement layers.	no	1		
		<u>Processing and Compaction</u>				
2	C5.3.2.1(k)	Construction of layers: Upper subbase (G2) layer compacted to 98 % of MDD	m3	315		
3	C5.3.2.1(j)	Construction of layers: Lower subbase (G5) layer compacted to 95 % of MDD	m3	330		

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

Part Continued **PART 0503 C5.3 ROAD PAVEMENT LAYERS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
4	C5.3.2.1(b)	Construction of layers: Upper selected subgrade layer (G7) compacted to 95 % of MDD	m3	40		

TOTAL CARRIED TO SECTION 6 SUMMARY: LAYERWORKS

R

PART 0901 C9.1 ASPHALT LAYERS

Item	Clause	Description	Unit	Quantity	Rate	Amount
		Bond Coat (Tack)				
1	C9.1.3.1 PS.C9.1	Application of bond coat: Stable –grade 30 % net bitumen emulsion as specified. Applied with a calibrated distributor	l	3000		
		Asphalt Surface				
2	C9.1.5.1(e) PS.C9.1	New construction (paver laid) (a) Stone skeletal mix – continuously graded (SA-S14) (40mm layer)	m2	2000		
3	C8.1.1.2	Prime coat: MC -30 cut-back bitumen. 0.8l/m2	l	1600		

TOTAL CARRIED TO SECTION 6 SUMMARY: LAYERWORKS

R

PART 1203 C12.3 GROUND IMPROVEMENT

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C12.3.20 PS.C12.3.20	Importing dump rock for subgrade improvement, 300mm thick	m3	30		
2	PS.C12.3.20	Supply and place minimum grade 5 geofabric to dumprock layer.	m2	265		
3	PS.27	Povision of clean coarse sand as a filter over dumprock layer. Sand layer thickness to be 200mm thick	m3	20		

TOTAL CARRIED TO SECTION 6 SUMMARY: LAYERWORKS

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 6 LAYERWORKS**

PART	0404	C4.4 COMMERCIAL MATERIALS	
PART	0501	C5.1 ROADBED	
PART	0503	C5.3 ROAD PAVEMENT LAYERS	
PART	0901	C9.1 ASPHALT LAYERS	
PART	1203	C12.3 GROUND IMPROVEMENT	
TOTAL CARRIED TO FINAL SUMMARY			

SECTION 7 ANCILLARY ROAD WORKS**PART 1104 C11.4 ROAD RESTRAINT SYSTEMS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C11.4.1.1(c)	Erecting of guardrails at 3,81 m spacing: Complete galvanized system compliant to SANS 1350: (c) on CONCRETE post (Drawing 38580)	m	35		
2	C11.4.1.2(b)	Terminal sections for 3,81 guardrails comprising of: (b) Bullnoses to SANS 1350	no	2		
3	C11.4.5.1	"Additional guardrail posts for 3,81 m systems: Concrete"	no	4		
4	C11.4.6.2	Reflective Plastic plates	no	6		
5	C11.4.4.1	Extra over C11.4.1 for horizontally curved guard rails factory bent to a radius of less than 45m	m	10		

TOTAL CARRIED TO SECTION 7 SUMMARY: ANCILLARY ROAD WORKS

R

PART 1105 C11.5 FENCING

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Wire Mesh Fence - Drawing 38583</u>				
1	C11.5.1.3	Diamond mesh	m2	75		
2	C11.5.1.9(a)(i)	Straining posts, stays and anchors:(a) Vertical (Concrete straining post)	no	4		
		<u>New Gate</u>				
3	C11.5.2 PS.C11.5.4.1	(a) Vehicular	no	2		
4	C11.5.2 PS.C11.5.4.1	(b) Pedestrian	no	2		
5	C11.5.10.1	Disposal of existing fencing materials: Security Fences	m	20		
6	C11.5.3.1(d)	"Moving existing fences:(d) Security fences"	km	0.03		
7	C11.5.4.1(d)	"Dismantling existing fences:(d) Security fences"	km	0.05		
8	C11.5.9	Repairing existing fences : To match existing fencing on site as and when required	km	0.05		

TOTAL CARRIED TO SECTION 7 SUMMARY: ANCILLARY ROAD WORKS

R

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

PART 1106 C11.6 ROAD SIGNS

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C11.6.1.3(a)	Road signboards with painted or coloured semi-matt background. Symbols, lettering and borders in semi-matt black or in Class I retro-reflective material, where the sign board is constructed from: Prepainted galvanized steel plate: (a) Area 0 to 0,5 m2	m2	8		
2	C11.6.3.1	Road sign supports: Steel tubing (75mm diameter), Galvanised	m	20		
3	C11.6.5.1	Excavation and backfilling for road sign supports: Excavating soft material and backfilling	m3	2		
4	C11.6.5.4	Extra over item C11.6.5.1 for hard material excavation	m3	2		
5	C13.4.11	Cast in situ concrete for road sign footings as directed by the Engineer (Grade 20/19)	m3	5		

TOTAL CARRIED TO SECTION 7 SUMMARY: ANCILLARY ROAD WORKS

R

PART 1107 C11.7 ROAD MARKINGS AND ROAD STUDS

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C11.7.1.4 PS.C.11.7.1	White lettering and symbols (Thermoplastic) <u>Broken and Unbroken Lines</u>	m2	6		
2	C11.7.1.1 PS.C11.7.1	Thermoplastic Road marking, broken or unbroken (White, 100mm wide)	km	0.04		
3	C11.7.1.1 PS.C11.7.1	Thermoplastic Road marking, broken or unbroken (White, 200mm wide)	km	0.01		

TOTAL CARRIED TO SECTION 7 SUMMARY: ANCILLARY ROAD WORKS

R

PART 1108 C11.8 LANDSCAPING AND PLANTING PLANTS

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C11.8.3.3(a)	Preparing the areas for grassing: (a) Topsoil obtained from within the road reserve or borrow areas	m3	200		
2	C11.8.3.3(b)	Preparing the areas for grassing: (b) Topsoil obtained from commercial sources by the Contractor	m3	50		

TOTAL CARRIED TO SECTION 7 SUMMARY: ANCILLARY ROAD WORKS

R

PART 1109 C11.9 FINISHING ROAD AND ROAD RESERVE

Item	Clause	Description	Unit	Quantity	Rate	Amount
1	C11.9.1.2	Single carriageway road	km	0.4		

TOTAL CARRIED TO SECTION 7 SUMMARY: ANCILLARY ROAD WORKS

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 7 ANCILLARY ROAD WORKS**

PART	1104	C11.4 ROAD RESTRAINT SYSTEMS	
PART	1105	C11.5 FENCING	
PART	1106	C11.6 ROAD SIGNS	
PART	1107	C11.7 ROAD MARKINGS AND ROAD STUDS	
PART	1108	C11.8 LANDSCAPING AND PLANTING PLANTS	
PART	1109	C11.9 FINISHING ROAD AND ROAD RESERVE	
TOTAL CARRIED TO FINAL SUMMARY			

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

SECTION 8 RETAINING WALLS**PART 1206 C12.6 MECH STABILISED FILL AND GABIONS**

Item	Clause	Description	Unit	Quantity	Rate	Amount
		<u>Gabions</u>				
1	C12.6.14.1(a)	Foundation trench excavation: Excavating all material for gabions situated within the following depth ranges (a) 0 m to 1,5 m	m3	20		
2	C12.6.14.1(b)	Foundation trench excavation: Excavating all material for gabions situated within the following depth ranges (b) Exceeding 1,5 m and up to 3,0 m	m3	40		
3	C12.6.15	Surface preparation for bedding the gabions	m2	75		
4	C.12.6.16.2	Gabions and mattresses: PVC coated gabion boxes (1.0m x 1.0m x1.0m)	m3	40		
5	C12.6.16.2	Gabions and mattresses: PVC coated gabion boxes (1.0m x 1.0m x 2.0m)	m3	30		
6	C12.6.17, PS.C12.6.17	Geotextile (Filtertation and separation for use with gabions, min Grade 7)	m2	150		
7	C12.6.11	Backfill (compacted to 95%MDD)	m3	30		

TOTAL CARRIED TO SECTION 8 SUMMARY: RETAINING WALLS

R

BILL OF QUANTITIES SECTION SUMMARY**SECTION 8 RETAINING WALLS**

PART	1206	C12.6 MECH STABILISED FILL AND GABIONS	
TOTAL CARRIED TO FINAL SUMMARY			

SUMMARY OF BILL OF QUANTITIES**Section**

1	PRELIMINARY AND GENERAL ITEMS		R	_____
0102	C1.2 GENERAL REQUIREMENTS AND PROVISIONS	R	_____	
0103	C1.3 CONTRACTOR'S SITE ESTABLISHMENT AND	R	_____	
0104	C1.4 FACILITIES FOR THE ENGINEER	R	_____	
0105	C1.5 ACCOMMODATION OF TRAFFIC	R	_____	
2	SITE CLEARANCE		R	_____
0106	C1.6 CLEARING AND GRUBBING	R	_____	
0107	C1.7 LOADING AND HAULING	R	_____	
3	SERVICES		R	_____
0201	C2.1 GEN REQMENTS AND TRENCHING SERVICE	R	_____	
0204	C2.4 ENERGY AND OTHER SERVICES	R	_____	
023B	C2.3B WET SERVICES - WATER MAINS	R	_____	
4	DRAINAGE		R	_____
0302	C3.2 CULVERTS	R	_____	
0303	C3.3 CONCRETE KERBING AND CHANNELING	R	_____	
1206	C12.6 MECH STABILISED FILL AND GABIONS	R	_____	
5	EARTHWORKS		R	_____
0402	C4.2 CUT MATERIALS	R	_____	
0403	C4.3 EXISTING ROAD MATERIALS	R	_____	
0404	C4.4 COMMERCIAL MATERIALS	R	_____	
0502	C5.2 FILL	R	_____	
6	LAYERWORKS		R	_____
0404	C4.4 COMMERCIAL MATERIALS	R	_____	
0501	C5.1 ROADBED	R	_____	
0503	C5.3 ROAD PAVEMENT LAYERS	R	_____	
0901	C9.1 ASPHALT LAYERS	R	_____	
1203	C12.3 GROUND IMPROVEMENT	R	_____	
7	ANCILLARY ROAD WORKS		R	_____
1104	C11.4 ROAD RESTRAINT SYSTEMS	R	_____	
1105	C11.5 FENCING	R	_____	
1106	C11.6 ROAD SIGNS	R	_____	
1107	C11.7 ROAD MARKINGS AND ROAD STUDS	R	_____	
1108	C11.8 LANDSCAPING AND PLANTING PLANTS	R	_____	
1109	C11.9 FINISHING ROAD AND ROAD RESERVE	R	_____	
8	RETAINING WALLS		R	_____
1206	C12.6 MECH STABILISED FILL AND GABIONS	R	_____	

UPGRADING OF TRK's 74200 (Phase 01) and 74201 IN ILANGA, WARD 07_OUTER WEST

Section

SUB TOTAL	R	
ADD VAT (15%) - (only if a registered VAT Vendor)	R	
TOTAL CARRIED TO FORM OF TENDER	R	