

Item No.	Payment Refers	Item Description	UNIT	QUANTITY	RATE	AMOUNT RANDS/CENTS
SCHEDULE 2 AREA (HIGH MAST LIGHTING)						
1		30M MASTS				
	a)	Supply Masts	ea	9		
	b)	Supply H.D. Bolts & Template Set Includes Bolts, Nuts, Washers and Delivery	ea	9		
	c)	Assembly and Erection of Mast Crane Truk & Site Establishments	ea	9		
	d)	Hi-Up Truck Mounted Crane for Erection Operating time, Site Establishment Crane Mobilisation	ea	1		
	e)	Soil bearing pressure test certificates signed by a Professional Engineer.	ea	9		
	f)	5 Pin Electrical Material in Mast Trailing Cables, Distribution Box and Splitter Box	ea	9		
	g)	Concrete Foundation				
		DCP Test and Test Cube Results Including Design, Certificate signed by a Professional Engineer.	ea	9		
	h)	Earthing Comprising of Earth Spike, BCEW	ea	9		
	i)	Complete technical information including SANS certification for masts, lights and all other relevant equipment, for every 30m high mast light.	ea	9		
	j)	Certificate of compliance for galvanising specifications.	ea	9		
	k)	Testing and commissioning complete with certificate of compliance, for every 30m high mast light.	ea	9		
	l)	Floodlights 9 (Per Mast) LED flood 279W ma 12827945121AIG	ea	9		
		Portable Double Drum Winch	ea	1		
		Electric Power tool	ea	1		
		3 Metre Test Lead	ea	1		
		4 PIN VANDAL PROOF KEY	ea	1		
2		OTHER				
		ANY OTHER ITEM DEEMED NECESSARY FOR THE SUCCESSFUL COMPLETION OF WORKS.	EA	1		
		ESKOM CONNECTIONS				
		ALLOW FOR MAIN SUPPLY FROM ESKOM	SUM	1		
TOTAL CARRIED FORWARD						
						R -
BOQ PAGE NUMBER 3						