

#### UMTHATHA PERIMETER FENCING SCOPE OF WORK ADDENDUM

##### **Perimeter Fencing Scope of works addendum (Please note that this is an addendum/ additional information to the original scope)**

- **The total Perimeter: 151m**
- This total perimeter is made of the following measurements:
  - $42\text{m} + 38\text{m} + 43\text{m} + 15\text{m} + 13\text{m} = \mathbf{151\text{m}}$

##### **Gate:**

- Double swinging gates that is lockable, the gate is to be **4m** in length and to be in similar height and specification as the fence. The gate is to be fitted with an anti-vandal locker

##### **Post:**

- The posts are to be spaced as per the original scope (3m panels)
- However, the sides of 38m and 15m are to be spaced at 1.5m apart, as these sides have a steep terrain.

##### **FOUNDATION**

- Concrete footing to be casted on the 38m and 15m sides.
- The footing size is to be 150mm x150mm. (Factor in 75mm excavation for footing when pricing) ( Please note that the footings do not replace the foundations for the posts but will be an additional task).
- Removal of existing fence and transporting it to our offices. (Please factor in these when pricing, distance to our offices and the removal costs)

