

Add the following payment item:

"Item	Description	Unit
PSC1.6.14	Remove existing palisade fences and stack for reinstatement	m ²
The removal and stacking of existing palisade fences shall be measured to the nearest square metre. Where existing 2.4 m high precast concrete palisade fences in the work area are to be removed by the Contractor these shall be removed carefully to minimise damage, and shall be stacked for use in reinstatement when work in the area is complete. The rate tendered and paid is for the recovery of existing palisade fences and shall include for disposal of surplus spoil and concrete bedding and shall cover all labour, plant and other incidental costs necessary to execute the work described. Palisades which in the opinion of the Project Manager are damaged by the Contractor during recovery or transportation, to the extent that they cannot be reused will not be measured for payment." Add the following payment item:		
"Item	Description	Unit
PSC1.6.15	Remove existing vibracrete fences and stack for reinstatement	m ²

The removal and stacking of existing pre-cast concrete panel fences shall be measured to the nearest square metre.

Where existing pre-cast concrete panel fences, of up to 2.0 m high, in the work area are to be removed by the Contractor these shall be removed carefully to minimise damage, and shall be stacked for use in reinstatement when work in the area is complete.

The rate tendered and paid is for the recovery of existing pre-cast concrete panel fences and shall include for disposal of surplus spoil and concrete bedding and shall cover all labour, plant and other incidental costs necessary to execute the work described. Pre-cast concrete panels which in the opinion of the Engineer are damaged by the Contractor during recovery or transportation, to the extent that they cannot be reused will not be measured for payment."