

BILL OF QUANTITIES

SCHEDULE: C BULK ROADS AND SERVICES
SECTION: C5 STORMWATER DRAINAGE

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
C5.11		POND AND FOREBAY TO DETAIL				
C5.11.1		i) Construct detention ponds as per drawings SD101 and SD201	No	4		
C5.11.2	SANS 1200 DK	ii) Gabions complete, 1.0 x 1.0 x 1.0m	m ³	148		
C5.11.3	SANS 1200 DK	iii) Gabions complete, 1.0 x 1.0 x 0.5m	m ³	44		
C5.11.4	SANS 1200 DK	iv) Reno Mattress complete, 2.0 x 1.0 x 0.3m	m ³	72		
C5.11.5		v) Amorflex - Type 140 or equivalent complete and to manufacturers specifications	m ²	180		
C5.11.6		vi) Channel lining - Geotextile Grade A4	m ²	650		
C5.11.7		vii) Pond outlet structures to detail as per drawings SD101 and SD201	No	4		
C5.11.8		viii) Pond inlet headwall structure to detail complete	No	8		
C5.11.9	SANS 1200 DK	ix) Pond overflows to detail complete as per drawing SD102	No	4		
TOTAL FOR SECTION C5 CARRIED FORWARD TO SUMMARY						