

RFP160/2023: THE SUPPLY AND DELIVERY OF FILTER SAND, FLY ASH FOR CONCRETE, WATERSTOPS CEMENT AND READY MIX MATERIALS TO DWS CONSTRUCTION NORTH TZANEEN DAM RAISING PROJECT IN THE LIMPOPO PROVINCE					
Item	Description	Unit	Quantity	Rate	Total
1	Supply and delivery of Bulk Fly Ash for Concrete	Tonnes	4,000		R0.00
2	Supply and Delivery of cement in bags Cement in bags CEM III/A-L 42.5 N)	no	45,000		R0.00
3	Supply and Delivery of Bulk Cement Cement in bulk CEM II/A-L 52.5 N	tons	11000		R0.00
4	Supply and delivery of Ready- Mix Concrete Concrete grade of 30/19	m3	3000		R0.00
5	Supply and Delivery of Bentonite (25kg)	no	15000		R0.00
6	Drilling and Grouting Material sika grout 212	tons	75		R0.00
7	Drilling and Grouting Material Service	Sum	1		R0.00
8	PVC WATERSTOPS (As per Specifications)				
8.1	250 mm PVC Centre- Bulb Water stops	m	2,500		R0.00
8.2	250mm wide PVC Rearguard "S" Water stop	m	500		R0.00
8.3	250 mm PVC Centre- bulb Intersections (T – Piece)	Number	50		R0.00
8.4	250 mm PVC Centre- bulb Intersections (4 way on flat)	Number	50		R0.00
8.5	250 mm PVC Centre- bulb Intersections (3 way on flat)	Number	30		R0.00
8.6	250mm wide PVC Rearguard "S" Water stop Intersections (4 way on flat)	Number	50		R0.00
8.7	250mm wide PVC Rearguard "S" Water stop Intersections (3 way on flat)	Number	40		R0.00
9	EXPANDABLE JOINT SEALING WATERSTOP (As per Specification)				
9.1	10 mm x 20 mm Expandable Preformed Joint Sealing waterstops	m	1,500		R0.00
10	JOINTING PACKAGE TO JOIN 250MM WIDE PVC WATER STOPS (As per Specification)				
10.1	PVC Water stops Heater Blade complete	Number	15		R0.00
10.2	PVC 250 mm Centre bulb Water stops Jointing rig	Number	10		R0.00
10.3	PVC 250 mm Rearguard "S" Water stop Jointing rig	Number	10		R0.00
TOTAL					R0.00
CONTEGENCIES		%	5%		R0.00
SUB TOTAL					R0.00
VAT @ 15%		%	15%		R0.00
GRAND TOTAL					R0.00