Tender No: **22Q/2025/26**

Description: **REHABILITATION OF CONCRETE ROADS IN MANENBERG**

NOTICE TO TENDERERS NO: 01

Responses to Relevant Queries Received via Email

……

Question 1:
Item C3.2.15.1 & C3.2.15.2 - Is this for the removal & re-laying of existing culverts or the supplying of new culverts? In either case, what is the size of these culverts?

Answer 1:
Please note the following items refer to manholes and catchpits constructed using prefabricated element and roofs, not culverts.
C3.2.15.1 *– Manholes and catchpits constructed using prefabricated elements.*
C3.2.15.2 *– Prefabricated roofs.*

These items are for 41 manholes to be reconstructed and the 28 new, additional manholes.

The supply of new culverts is measured under ***Item C3.2.3****, with all sizes and lengths specified in the Bill of Quantities (BOQ).*

Relaying existing culverts:

- *Must be replaced with new pipes of the same size.*
- *Measurement still falls under* ***C3.2.3.***
- *Site assessment required for all existing pipes.*

……

Question 2:
Item C11.9.1 – Please elaborate – Is this for existing gravel roads & verges?

Answer 2:
C11.9.1 Finishing the road and road reserve.

The tendered rates shall include full compensation for cleaning, trimming, disposing of material, tidying and all other work to be done for finishing off the road and road reserve as specified.

……

Question 3:
Can you perhaps forward the engineers details

Answer 3:
Unfortunately, details cannot be shared at this stage.

……

Question 4:
Please forward the drawings in PDF, we require the road section drawings

Answer 4:
Drawings can be downloaded on the link provided on pg. 144
……

Question 5:
Item C5.4 – Chemical Stabilization
Please forward the specification

Answer 5:
C4 Subbase Design to be executed on Sit (G5A + CEM II 32.5):
- *Beneath kerbs and road widenings, as indicated on the Typical Pavement Design Drawing*
- *Rehabilitation section of Vygekraal*
- *Embayment areas*

*G2 Material, stabilised with 2% cement, to be applied in widening sections (**Type 2B : 50mm – 300mm**)*
……